MILITARY SPECIFICATION

VOLTAGE REGULATOR SUBASSEMBLY: 10525755

This amendment forms a part of Military Specification MIL-V-60217(MU), dated 2 March 1965.

Table 1: Add the following note below Table 1:

"NOTE: Resistor R8 plus R9 shall equal 30.0 ohms or 30.1 ohms ± 0.5 percent.
Resistor R60 plus R61 shall equal 70 ohms ± 0.5 percent.
Resistor R43 plus R44 shall equal 110 ohms ± 0.5 percent.
Resistor R67 plus R68 shall equal 110 ohms ± 0.5 percent.
Resistor R71 plus R72 shall equal 110 ohms ± 0.5 percent."

Table II, under Voltage Inputs: Delete the columns and substitute the following columns:

"NAME	LOW LINE (volts)	NOMINAL LINE (volts)	HIGH LINE (volts)
+150v main	+193.0 ± 6.0	+232.0 ± 6.0	+274.0 ± 6.0
+150v bias	+193.0 ± 6.0	+232.0 ± 6.0	+274.0 ± 6.0
+20v	+16.0 ± 1.0	+19.5 ± 1.0	+23.0 ± 1.0
+15v main	+21.0 ± 1.2	+26.0 ± 1.5	+30.8 ± 1.2
+6v	+5.5 ± 0.05	+6.0 ± 0.05	+6.5 ± 0.05
-12v	-12.0 ± 1.2	-12.0 ± 1.2	-12.0 ± 1.2
-27v	-21.0 ± 1.0	-25.5 ± 1.0	-29.6 ± 1.6
-32v	-26.0	-31.0	-37.0 "

Table II, under Trip Load (amperes), lines 1 and 2: Delete "0.19 ± 0.02" and "1.7 ± o.1" and substitute "$0.19^{+0.04}_{-0.0}$" and "$1.7^{+0.2}_{-0.0}$"; add new column under "Loads".

"EXTREME TEMPERATURES TRIP LOAD (amperes)
$0.19^{+0.06}_{-0.00}$
$1.7^{+0.3}_{-0.0}$ "

Paragraph 4.5.1.3.2: Delete in its entirety and substitute:

"4.5.1.3.2 Operating.- This test shall be conducted in accordance

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T00:20Z
Check the source to verify that this is the current version before use.

with the humidity test defined in Procedure III of MIL-F-13926, except that the humidity shall be maintained at 92 to 97 percent for the 24-hour period, and the test shall cease at the end of that period (Method 106 of MIL-STD-202 shall be excluded). Throughout the test period, the board shall be capable of performing the tests of 4.5.8. In order to demonstrate this capability, the tests of 4.5.8 shall be performed a minimum of once each 6 hours of the 24-hour period. The final test shall be conducted during the final portion of the 24-hour period. Between tests, the board shall be electrically energized as described in 4.5.8.1."

Paragraph 4.5.1.4: Delete in its entirety and substitute:

"4.5.1.4 Salt spray.- This test shall be conducted in accordance with the salt spray test defined in Method 101, Condition B of MIL-STD-202 using a 5 percent salt solution. At the end of the exposure period, salt deposits shall be removed from the board by a gentle wash, not exceeding 30 minutes, in running water not warmer than 100°F, using a soft-hair brush or plastic-bristle brush. The board shall then be air dried in a controlled environment at 72°F + 5°F and a relative humidity of 30 to 50 percent for a period of 24 hours. The board shall then be inspected visually for any physical damage, then tested in accordance with 4.5.4 to 4.5.8.6 inclusive.

Paragraph 4.5.3.5: Add to last sentence: "except that the trip current resistors shall be values that give the next higher bias ratio (R68 to R67 for +150V and R43 to R44 for +15V) than the potentiometer settings".

Paragraph 4.5.8.1(b): After "150V main" add "plus 150V bias".

Paragraph 4.5.8.3: Delete "0.19 amperes" and substitue "0.23 amperes".

After paragraph "4.5.8.6" add new paragraph:

" 4.5.9 Extreme environmental conditions.- All tests of 4.5.8 shall be made using the extreme temperature columns of Table II where applicable. A minimum of 100 feet per minute of air at ambient temperature shall flow across the components mounted on the board."

Table VI, Three Phase Full Wave Bridge Types*: Delete second column and substitute new second column.

"VARIABLE RANGE OF OUTPUT (volts)
+187 to +280
+187 to +280
+19 to +32
+15 to +24
-20 to -31.2"

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T00:20Z
Check the source to verify that this is the current version before use.

under "T1".

Figure 6, below "-32V P.S.": Add phrase "see Figure 5".

Custodian

Army - MU

Preparing activity

Army - MU

Project No. 1220-A057

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T00:20Z
Check the source to verify that this is the current version before use.