MILITARY SPECIFICATION

MINE, ANTIPERSONNEL, BLU-54/B

LOADING, ASSEMBLING AND PACKING

1. SCOPE

1.1 This specification covers the loading, assembling and packin for one type of mine designated as Mine Antipersonnel, BLU-54/B.

2. APPLICABLE DOCUMENTS

2.1 The following documents of the issue in effect on date of invitation for bids or request for proposal, form a part of this specification to the extent specified herein.

SPECIFICATIONS

FEDERAL

MILITARY

MIL-A-2550	-	Ammunit ion and Special Weapons, General Specification for
MIL- I-45607	-	Inspection Equipment, Supply and Maintenance of

STANDARDS

MILITARY

FSC:1345

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T20:18Z
Check the source to verify that this is the current version before use.

MIL-STD-105	-	Sapling Procedures and Tables for Inspection by Attributes (ABC-STD-105)
MIL-STD-109	-	Quality Assurance Terms and Definitions
MIL-STD-1168	-	Lot Numbering of Ammunition
MIL-STD-1235	-	Single and Multilevel Continuous Sampling Procedures and Tables for Inspection by Attributes

DRAWINGS

U.S. AIR FORCE

68F10448	-	Mine, Antipersonnel: BLU-54/B (Loading)

PUBLICATIONS

ARMY

ET-68F10448	-	Equipment Tabulation

(Copies of specifications. standards, drawings and publications required by suppliers in connection with specific procurement functions should be obtained from the procuring activity or as directed by the Contracting Officer.)

2.2 Other publications. -The following documents form a part of this specification to the extent specified herein. Unless otherwise indicated, the issue in effect on the date of invitation for bids *or* request for proposal shall apply.

CODE OF FEDERAL REGULATIONS

Title 49	Transportation, Parts 171-179

(The Code of Federal Regulations is available from the Superintendent of Documents, U.S. Government Printing Office, Washington, D.C. 20402. Orders should specify 49 CFR 171-179 (latest revision).)

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T20:18Z
Check the source to verify that this is the current version before use.

3. REQUIREMENTS

3.1 Material.-Materials shall be in accordance with the applicable drawings and specifications.

3.2 Mines.-The mines shall comply with all requirements specified on Drawing (Dwg.) 68F10448, all associated drawings, and with all requirements specified in applicable specifications.

3.3 Workmanship. -All parts and assemblies shall be fabricated, loaded and assembled in a thorough, workmanlike manner. They shall be free of burrs, sharp edges, cracks, dirt, grease, rust, and other foreign matter. The cleaning method used shall not be injurious to any part, nor shall the parts be contaminated by the cleaning agents. Exterior surface coatings shall be continuous except for a few light scratches not exposing base material, All required marking and stamping shall be neat and sharply defined.

3.4 Submission of results of contractor-conducted examinations and tests. -The contractor shall forward copies of the results of any of his examinations or tests to the designated address as required by the contract. (see 6.4)

3.5 First article testing.-This specification makes provisions for first article testing. Submission of first article quantity by the contractor shall be as specified in the contract.

4. QUALITY ASSURANCE PROVISIONS

4.1 Responsibility for Inspection.-Unless otherwise specified in the contract or purchase order, the supplier is responsible for the performance of all inspection requirements as specified herein. Except as otherwise specified in the contract or order, the supplier may use his own or any other facilities suitable for the performance of the inspect ion requirements specified herein, unless disapproved by the Government. The Government reserves the right to perform any of the inspections set forth in the specification where such inspections are deemed necessary to assure supplies and services conform to prescribed requirements. Reference shall be made to MIL-STD-109 to define terms used

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T20:18Z
Check the source to verify that this is the current version before use.

herein. The provisions of MIL-A-2550 shall apply.

4.1.1 Submission of product.-At the time the completed lot of items deliverable under the contract is submitted to the Government for acceptance, the contractor shall supply the following information accompanied by a certificate which attests that the information provided is correct and applicable to the product being submitted:

a. A statement that the lot complies with all the quality assurance provisions specified in this specification.
b. Drawing and specification number and date, together with identification and date of changes thereto.
c. A statement that all material purchased by the contractor meets requirements, when such material is controlled by Government or commercial specifications referenced in any of the contractual documents, and that certificates of conformance are on file and available for review.
d. Number of items in the lot.
e. Date submitted.

The certificate shall be signed by a responsible agent of the certifying organization. The initial certificate submitted shall be substantiated by evidence of the agent's authority to bind his principal. Substantiation of the agent's authority will not be required with subsequent certificates unless, during the course of the contract, this authority is vested in another agent of the certifying organization.

4.2 First article inspection

4.2.1 Submission.-The contractor shall submit a first article quantity as designated by the Contracting Officer for evaluation in accordance with the provisions of 4.2.2. (See 6.1) The first article sample shall consist of the following:

a. Twenty-five (25) hemisphere assemblies, left hand, loaded
b. Twenty-five (25) hemisphere assemblies, right hand, loaded.
c. Twenty-five (25) Mine, Antipersonnel, BLU-54/B.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T20:18Z
Check the source to verify that this is the current version before use.

All sub assemblies and completed assemblies submitted shall have been produced by the contractor (or furnished by a supplier) using the same production processes, procedures and equipment as will be used in fulfilling the contract. All parts and materials, including packa ing and packing, shall be obtained from the same sources of supply as will be used in regular production. The sample shall be accompanied by certificates of conformance. A first article quantity, or portion thereof, as directed by the Contracting Officer, shall also be submitted whenever there is a lapse in production for a period in excess of 90 days, or whenever a change occurs in manufacturing process, material used, drawing, specification or source of supply as to significantly affect product uniformity as determined by the Government. Prior to submission, the contractor shall inspect the sample to the degree necessary to assure that it conforms to the requirements of the contract and submit a record of this inspection with the sample. A sample containing known defects will not be submitted unless specifically authorized by the Contracting Officer.

4.2.2 Inspections to be performed. -Assemblies and sub-assembl ies will be subjected by the Government to any or all the examinations or tests specified in this specification and any or all requirements of the applicable drawings.

4.2.3 Rejection.- If any assembly or sub-assem blies fail to comply with any of the applicable requirements, the first article quantity shall be rejected. The Government reserves the right to terminate its inspection upon any failure of an assembly or sub-assembly in the sample to comply with any of the stated requirements. In the event of rejection, the Government reserves the right to require the contractor to take corrective action and submit a new first article quantity or portion thereof. Until a first article quantity is accepted, the contractor is in no way authorized by the Government to resume regular production unless otherwise directed by the Contracting Officer.

4.3 Inspection provisions

4.3.1 Lot formation.-The term “inspection lot” as used in this specification is defined as an essentially homogeneous

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T20:18Z
Check the source to verify that this is the current version before use.

collection of units of product from which a representative sample. is drawn and inspected to determine conformance with applicable requirements. The sample selected shall represent only that quantity of units from which the sample was drawn and shall not be construed to represent any prior or subsequent quantities presented for inspection. Homogeneity shall be considered to exist provided the inspection lot has been produced by one manufacturer, in one unchanged process, in accordance with the same drawing, same drawing revision, same specification and same specification revision and complies with the provisions for submission of product as specified in MI L-S TD-105. Changes to process, specification, or drawing not affecting safety, performance, interchangeability> or storage, as determined by the Government, shall not be deemed to alter the homogeneity of an inspection lot. All material submitted for inspection in accordance with this specification shall comply with the homogeneity criteria specified herein regardless of the type of sampling procedure which is being applied to determine conformance with requi rements . Lot numbering as required, shall be in accordance with MIL-STD-1168. Each inspec tion lot of mines shall contain:

a. Booster assemblies of one lot interfix number from one manufacturer.
b. Loaded fuzes of one lot interfix number from one manufacturer.
c. Composition E of one lot interfix number from one manufacturer.
d. MPTS of one let interfix number from one manufacturer.

4.3.2 Examination. -The examinations listed in the following subparagraph shall be performed on inspection lots (see 4.3.1) of the components or assemblies designated in the applicable paragraph hea dings. Inspection for critical defects (and major defects, when so specified) shall be 100 percent. Sampling plans for major and minor defects shall be in accordance with MIL-S TD-105 except that continuous sampling plans in accordance with MIL-STD-1235 may be us ed if approved by the Government . Instead of applying the AQL's designated herein to the groups of major and minor defects listed, the Contractor may elect to apply AQL'S to individual defects using an AQL of 0.40 percent for each major defect and an AQL of 0.65 percent for each minor

Source: https://assist.dla.mil -- Downloaded: 202610-22T20:18Z
Check the source to verify that this is the current version before use.

defect. When this method is elected, it shall be applied to all of the major and minor defects listed in the applicable subparagraph of this section, except where 100 percent inspection is specified, and be documented as part of the contractor's inspection system. Equipment necessary for the performance of the inspections listed shall be in accordance with 4.3.4.

4.3.2.1 Hemisphere assembly, left hand (See Dwg. 67D10434 covering a detail of Dwg. 68F10448).-

Categories	Defects	Method of Inspection	Code No (See 6.2)
Critical:	None defined		
Major:	AQL 0.65 Percent		
101.	Explosive flush to below flush	Gage	(01001)
102.	Concentricity of the cavity diameters with the hole including erpendicularily	Gage	(01002)
103.	Voids in explosive (See 6.5)	Visual	(01003)
Minor	AQL 1.50 Percent		
201.	Depth to bottom of second largest cavity	Gage	(01004)
202.	Depth to bottom of fourth largest cavity	Gage	(01005)
203.	Evidence of poor workmanship (See 3.3)	Visual	(01006)

4.3.2.2 Hemisphere assembly, right hand (See Dwg 67D10436 covering a detail of Dwg. 68F10488).-

Categories	Defects	Method of Inspection	Code No.
Critical:	None defined		
Major	AQL 1.00 Percent		
101.	Explosive flush to below flush	Gage	(02001)
102.	Depth to booster cavity	Gage	(02002)
103.	Width of booster cavity	Gage	(02003)

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T20:18Z
Check the source to verify that this is the current version before use.

104.	Largest cavity diamether, max	Gage	(02004)
105.	Concentricity of cavity diameters with hole including perpendicularity	Gage	(02005)
106.	Voids in explosive (See 6.5)	Visual	(02006)
Minor	AQL 1.50 Percent		
201.	Depth of first cavity	Gage	(02007)
202.	Depth of second cavity	Gage	(02008)
203.	Depth of fourth cavity	Gage	(02009)
204.	Evidence of poor workmanship (See 3.3)	Visual	(02010)

4.3.2.3 Mine, Antipersonnel prior to joining right and left hemisphere assemblies (See Dwg. 68F10448).-

Categories	Defects	Method of Inspection	Code No.
Critical:	None defined		
Major	AQL 0.65 Percent		
101.	Booster pad	Visual	03001
102.	Booster assembly missing	Visual	03002
103.	Explosive on mating surface	Visual	03003
Minor	AQL 0.65 Percent		
201.	Evidence of poor workmanship (See 3.3)	Visual	03004

4.3.2.4 Mine, Antipersonnel (See Dwg. 68F10448)

Categories	Defects	Method of Inspection	Code No.
Critical:	None defined		
Major	AQL 1.00 Percent		
101.	Strap torn, broken or cracked	Visual	04001
102.	Max gap between strap and body	Gage	04002
103.	Alignment of ribs improper	Gage	04003

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T20:18Z
Check the source to verify that this is the current version before use.

104.	Retaining ring and spring missing or assembled improperly	Visual	04004
105.	Tabs not removed or bent back from sensor cups (8 places)	Visual	04005
106.	Mine cracked or deformed	Visual	04006
Minor	AQI 0.65 Percent		
201.	Evidence of poor workmanship (See 3.3)	Visual	04007

4.3.3 Testing

4.3.3.1 Density of explosive in parts, (See dwg 67D10434 and 67D10436) Major Defect, Code No, 05001.-The following requirement shal 1 be appl ied separately to hemisphere assembl ies, 67D10434 and 67D10436. Density of explosive shall be determined for a minimum of two (2) parts, (two for each hemisphere)) randomly selected, from each four (4) hour's production. If any defective part is found, that portion of production since the last control check shall be rejected.

4.3.4 Inspection equi pment.-Equipment Tabulation (ET) number 68F10448 and Equipment Lists (EL'S) referenced thereon identify the inspection 'equipment required to perform the examinations and tests prescribed in this section. The contractor shall design inspection equipment in accordance with the instructions in 6.3. Supply and maintenance of the equipment listed on the EL's shall be in accordance with MIL-I-45607.

4.3.4.1 Government rights to documentation.-Inspection equipment drawings and lists provided and revised in accordance with the requirements of this specification may be used by DOD activities for design, procurement, manufacture, testing, evaluation, production and receiving inspection, overhaul, shipping, storage, identification of stock, ordering and storage of replacement parts, inspection of items at overhaul, general maintenance of equipment, construction, survey, and whenever inspection equipment drawings are needed.

5. PREPARATION FOR DELIVERY

5.1 Packing and Marking.-Marking shall be packed and marked in

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T20:18Z
Check the source to verify that this is the current version before use.

accordance with code of federal Regulations, Title 49, Parts 171-179.

6. NOTES

6.1 Intended use

6.1 Ordering data.-Procurement documents shall specify the following:

a. Title, number and date of this specification.
b. Data cards shall be prepared for each lot in accordance with the information specified in Standard MIL-STD-1167.
c, Provisions for submission of first article samples.

6.2 Inspection code numbers.-The five-digit code numbers assigned to the inspections herein are to facilitate future data collection and analysis by the Government. These code numbers are also used to correlate the characteristics cited on Equipment Lists with the inspections listed in this specification. These code numbers shall be listed on drawin s of equipment designs submitted by the contractor (see 6.3.5).

6.3 Inspection equipment.-The contractor shall design inspection equipment as required by the referenced Equipment Lists (EL) in accordance with the instructions of paragraphs 6.3.1 through 6.3.5.

6.3.1 Equipment lists.-Equipment lists indicate the availability of inspection equipment desgins by showing in the “Part Number” column of the list of inspection equipment (Form SMUPA 1010) the numbers of drawings of Federal Stock numbers of existing equipment designs, or codes as indicated in paragraph 6.3.2. Design action required of the contractor is described in paragraphs 6.3,3 and 6.3.4. The contractor will be required to prepare detailed drawings in accordance with 6.3.4 for all the equipment coded as “Contractor Design” in the “Part Number” column. These contractor designs must be approved by the Government prior to fabrication or procuring of the equipment. Designs shall be submitted for approval as specified in 6.3.5,

6.3.2 Equipment list codes.-The inspection equipment as

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T20:18Z
Check the source to verify that this is the current version before use.

defined in 6.3.3 and 6.3.4 will be designated in the EL by the following codes:

CD - Contractor design on controlled contractor format and/or commercial equipment.
MU - Army design, mandatory for use.

6.3.3 Arm desi ns.-Army desi ns are reflected on detailed drawings which completely depict all the information necessary for the fabrication of the item of inspection equipment. The contractor need provide no design when an Army design is listed for an item of inspection equipment. Army design fall into two basic classifications: Mandatory (designated "MU") and non-mandatory (indicated by drawing or Federal Stock Number). When an equipment list references mandatory Army Designs, the contractor shall comply with, and use these designs accordingly. The contractor may, however, in connection with non-mandatory designs, with the approval of the Government, design alternate inspection equipment to facilitate his operations. Such contractor-prepared designs (see 6.3.4) or commercial equipment selections must be approved by the Government prior to fabrication or procuring of the equipment. Designs shall be submitted for approval as specified in 6.3.5.

6.3.4 Contractor designs.-Contractor designs are designs of inspection equipment for which the Government has assigned design responsibility to the contractor. Contractor designs shall be supported by detailed drawings which depict all information necessary to completely fabricate, calibrate and operate an item of inspection equipment. This requires that the necessary views, dimensions, materials, finishes, notes and operatin and calibration instructions be properly depicted in accordance with approved practices to the extent that further calculation or clarification will not be required. Unless otherwise specified, contractor designs may be developed on the format the contractor normally employs in his equipmet design procedure provided such format reflects the detail and information specified above, subject to the following controls: All submitted contractor designs shall conform to Specification MIL-D-1000, Category A, Form 2. Le ibility and re reducibility shall permit conventional making of cleanly understandable, high-contrast reproductions. Contractors shall submit three copies of final designs

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T20:18Z
Check the source to verify that this is the current version before use.

as a flat set. Designs shall be submitted for approval as specified in 6.3.5.

6.3.5 Submission of contractor design.-All submitted designs shall contain a reference to the applicable 5-digit code number contained in Section 4 of this specification and-the appropriate component or assembly drawing number and revision letter to which the specific design applies. Unless otherwise specified on the EL, all designs of equipment for inspection of defects classified as critical and major shall be submitted for approval to the Commanding Officer, Picatinny Arsenal, ATTN: SMUPA-ND13. All other designs of inspection equipment shall be proved by the inspection element of the agency administering the contract. Submission shall be as directed to the contracting officer. Partial submission of inspection equipment designs is permissible and encouraged. However, the Arsenal completion date for design review will be based on the date of the final submission of designs. Picatinny Arsenal design review will be accomplished, normally, within one month after receipt.

6.4 Submission of results of contractor-conducted examinations and tests.-Unless otherwise specified by the Contracting Officer, the contractor shall forward requested records of examinations or tests to Commanding Officer, Picatinny Arsenal, ATTN: SMUPA-ND3

6.5 Voids.-Voids as used in this specification are defined as cavities having any dimension greater than 3/16 of an inch.

Custodian:
Army-MU

Preparing activity:
Army-MU

Project Number: 1345-A-287

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T20:18Z
Check the source to verify that this is the current version before use.

FOLD

DEPARTMENT OF THE ARMY
PICATINNY ARSENAL
DOVER, NEW JERSEY 07801

OFFICIAL BUSINESS

POSTAGE AND FEES PAID
DEPARTMENT OF THE ARMY

COMMANDING OFFICER
United States Army
Picatinny Arsenal
ATTN: SMUPA-ND
Dover, New Jersey 07801

FOLD

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T20:18Z
Check the source to verify that this is the current version before use.

SPECIFICATION ANALYSIS SHEET

Form Approved
Budget Bureau No 119-R004

INSTRUCTIONS

This sheet is to be filled out by personnel either Government or contractor, involved in the use of the specification in procurement of products for ultimate use by the Department of Defense. This sheet is provided for obtaining information on the use of this specification which will insure that suitable products can be procured with a minimum amount of delay and at the least cost. Comments and the return of this form will be appreciated. Fold on lines on reverse side, staple in corner, and send to preparing activity

SPECIFICATION

ORGANIZATION	CITY AND STATE

CONTRACT NO	QUANTITY OF ITEMS PROCURED	DOLLAR AMOUNT
		$

MATERIAL PROCURED UNDER A

☐ DIRECT GOVERNMENT CONTRACT ☐ SUBCONTRACT

1 HAS ANY PART OF THE SPECIFICATION CREATED PROBLEMS OR REQUIRED INTERPRETATION IN PROCUREMENT USE?

A GIVE PARAGRAPH NUMBER AND WORDING

B RECOMMENDATIONS FOR CORRECTING THE DEFICIENCIES

2 COMMENTS ON ANY SPECIFICATION REQUIREMENT CONSIDERED TOO RIGID

3 IS THE SPECIFICATION RESTRICTIVE?

☐ YES ☐ NO IF "YES", IN WHAT WAY?

4 REMARKS *(Attach any pertinent data which may be of use in improving this specification. If there are additional papers, attach to form and place both in an envelope addressed to preparing activity)*

SUBMITTED BY *(Printed or typed name and activity)*	DATE

DD FORM 1 OCT 64 1426

Source: https://assist.dla.mil -- Downloaded: 202640-22T20:18Z
Check the source to verify that this is the current version before use.