MILITARY SPECIFICATION

CABINETRY SYSTEM, MEDICAL AND PHARMACEUTICAL, DEPLOYABLE

This specification is approved for use by the Defense Personnel Support Center, Department of Defense, and is available for use by all Departments and Agencies of the Department of Defense.

1. SCOPE

1.1 Scope. This specification covers a deployable, medical and pharmaceutical cabinetry system, and level 3 production drawings and associated lists. It is intended for use only during the first requisition of the items herein covered. The drawings procured with this specification are to be incorporated in the specifications which are intended for use during subsequent requisitions of cabinetry units specified herein.

Beneficial comments (recommendations, additions, deletions) and any pertinent data which may be of use in improving this document should be addressed to: Defense Personnel Support Center, Directorate of Medical Materiel, Technical Operation Division, DPSC-RST, 2800 South 20th Street, Philadelphia, PA 19101, by using the self-addressed Standardization Document Improvement Proposal (DD Form 1426) appearing at the end of this document or by letter.

AMSC N/A FSC 6530
DISTRIBUTION STATEMENT A. Approved for public release; distribution is unlimited

Source: https://assist.dla.mil -- Downloaded: 2026-10-21T11:47Z
Check the source to verify that this is the current version before use.

1.2 Classification.

1.2.1 Classification of units.

1.2.1.1 Identification of units. The cabinetry system covers the following units:

Unit No.	NSN	Description
945	6530-01-163-3761	Cabinet, Medical, Base Section (18 inch, 4 drawers).
931	6530-01-209-1197	Cabinet, Medical, Base Section (18 inch, 5 drawers).
916	6530-01-163-3760	Cabinet, Pharmaceutical, Base Section (18 inch, 4 Drawers).
932	6525-01-168-0574	Cabinet, Cassette Storage, Darkroom Equipment Set (Base Section, 18 inch).
903	6530-01-162-8237	Cabinet, Pharmaceutical, Upper Section (36 inches wide).
930	6530-01-164-9635	Cabinet, Pharmaceutical Storage (Upper Section, 18 inches wide).
914	6530-01-190-4378	Box, Plastic (Bin for upper units).
913	6530-01-162-6764	Bar, Retainer, Base Cabinet, Steel.
929	6530-01-222-3914	Hanger, Work Counter, Box of 4.
928	6530-01-169-3150	Counter, Work, Medical Cabinet, 36 inch wide.
927	6530-01-162-6758	Counter, Work, Medical Cabinet, 42 inch wide.
936	6545-01-163-1899	Sink Unit, Scrub, Field Hospital (30 inches wide).
937	6530-01-162-4443	Table, Folding leg.

1.2.1.2 Classification number (CN) of units. The unit number is the suffix of a CN. Unit numbers may also be found on DPSC Sketch Number 25511. A complete CN is formed by adding the prefix "25511-" to a unit number. The CN for the first unit listed in 1.2.1.1 is "25511-945". Herein, a unit may be referred to by using only the unit number.

Source: https://assist.dla.mil -- Downloaded: 2026-10-21T11:47Z
Check the source to verify that this is the current version before use.

1.2.1.3 Configuration of units. The units shall collectively constitute a cabinetry system, and shall be modular, permitting a variety of system configurations. Interchangeability of the units within any possible configuration shall be as follows:

Vertical columns list units which shall dimensionally interchange

Fixed width configurations		Variable width configurations		
Base unit	Upper unit	Base unit	Upper unit	Counters
945	903	945	903	928
931	930 1	931		
916		916	930 1	927
932		932		
		936		

Notation applicable to 1.2.1.3:

1 Two of these 18 inch upper units (930) are required to replace one 36 inch upper unit (903).

1.2.1.4 Interfunctionability between units. Interfunctionability between units within any possible configuration shall be as follows:

First unit in vertical columns (CHU) shall function with below listed.

945	931	916	932	903	930	914	913	928	927	929	936
903 1	903 1	903 1	903 1	945	945	903	945	945	945	945	929 4
930 2	930 2	930 2	930 2	931	921	930	931	931	931	931	928 1
913 3	913 3	913 3	913 3	916	916		916	916	916	916	927 1
929 4	929 4	929 4	929 4	932	932		932	932	932	932	
928 1	928 1	928 1	928 1	914 5	914 7		903	929	929	928 9	
927 1	927 1	927 1	927 1	913 6	913 8		930	936	936	927 9	
										936	

Notations applicable to Column Head Units (CHU) in 1.2.1.4:

1 This unit is supported by CHU plus any 1 unit of 945, 931, 916, or 932 (when this unit is 928 or 927 it can also be supported by 936)

2 This unit is supported by CHU.

3 Two of these units secure the CHU plus any one of 945, 931, 916, or 932 to unit 903; or two of these units secure CHU unit to 930.

4 A set of these units are used to support 928 or 927 by CHU plus any one of 945, 931, 916, 932, and/or 936.

5 A maximum of 25 of these units will fit in the CHU.

6 Two of these units secure any two of 945, 931, 916, or 932 to CHU.

Source: https://assist.dla.mil -- Downloaded: 2026-10-21T11:47Z
Check the source to verify that this is the current version before use.

2 A maximum of nine of these units will fit in the CHU.

8 Two of these units secure any one of 945, 931, 916, or 932 to CHU.

9 These units are held at a selected height on any combination of two units 945, 931, 916, 932, and/or 936 by a set of the CHUs.

1.2.1.5 Compatibility with previously procured cabinetry. In order to maintain capability of base section cabinetry units specified herein (units 945, 931, 916, 932, and 936) and counter units (units 928 and 927) specified herein to be compatible with certain previously procured base section cabinetry, the carrying handles and hanger supports (to receive counter units) for base section units shall be mounted such that the counter support area of free hanging hand grips shall be 21 3/8 inches (± 1/8 inch) from the bottom of the cabinet skid-rail and the counter support area of the hanger supports shall be 27 1/4 inches (± 1/8 inch) from the floor (carrying handles mounted on a completed cabinet with skid-rails); and both hanger supports and carrying handles shall be horizontally located with respect to the casework front surface such that a simulator (simulating a counter unit, see DPSC Sketch 25511-S), as described here, shall be capable of having its front surface flush with the casework front surface when the drop flanges of the simulator are supported by the hand grips and when the drop flanges are supported by the hanger supports. The simulator shall be a flat bar, approximately 23 inches long by 3 inches wide by, at least, 1/8 inch thick. One end of the simulator shall be designated to be the front surface and the other end shall be designated to be the back end. One 3 inch wide surface shall be designated to be top. Two drop flanges (2 right angles, each 1/8 inch thick by 1 inch by 1 inch by 4 1/4 inches (± 1/32 inch) long) shall be butt welded to a common long edge of the simulator such that one 1 inch flat surface of each drop flange is flush with the top of the simulator. One drop flange shall be located with respect to the simulator front surface such that the forward end of the drop flange shall be 4 7/16 inches (± 1/32 inch) from the front surface of the simulator (toward the back end of the simulator). The forward end of the other drop flange shall be 15 15/16 inches (± 1/32 inch) from the front surface of the simulator. Additionally, in order to maintain compatibility, counter units 928 and 927 shall be capable of being supported by base section units which are capable of receiving the described simulator.

1.2.2 Classification of drawings and associated lists.

1.2.2.1 Identification of drawings. The drawings shall consist of two (2) drawing sets. Each set shall collectively be classified as DPSC Drawing Number 25511.

1.2.2.2 Configuration of drawings and associated lists. The drawings and associated lists configuration shall be in accordance with DOD-D-1000 and DOD-STD-100.

1.3 Application. This solicitation and contract may be for any combination of, and any quantity of, individual units which are listed in 1.2.1.1. The draw-

Source: https://assist.dla.mil -- Downloaded: 2026-10-21T11:47Z
Check the source to verify that this is the current version before use.

ings and associated lists shall describe all units listed in 1.2.1.1. The drawing description of units not being procured shall comply with all requirements.

1.4 Contractor support responsibility. The contractor shall maintain copies of the final accepted drawings and associated list for a period of, at least, three (3) years for the purpose of correcting any possible deficiencies (see 3.7.2.4).

1.5 Definition of terms. As used in this specification, the term "herein" shall apply to this entire specification. As used herein, the terms "cabinet"(s), "sink", "counter"(s), "bar"(s), "hanger"(s), "table", and "box"(es) shall apply to units specified herein as they are respectively identified in 1.2.1.1. Other terms are defined as follows:

a. nominal: With respect to dimensions, this term shall apply to concept design dimensions and does not indicate allowable tolerances within specified drawings.

b. permanent attachment/permanently attached: An attachment which requires the use of a cutting tool, other than a razor type scraper, in order to perform a detachment.

c. casework: An indivisible welded assembly forming a shell of a cabinet.

d. unit(s): Any complete item listed in 1.2.1.1.

e. item(s): Any component of a unit, unit(s), drawings, and/or data specified herein.

f. part/subassembly/assembly/interchangeable item/interchangeable /exploratory development/advanced development/engineering development/prototype production: As specified in MIL-STD-280.

g. drawing(s)/associated lists: The engineering drawings and associated lists specified herein.

h. small hand tools: Shall be tools consisting of standard screwdrivers for slotted and phillips screw heads, wrenches up to 5/8 inch, pliers up to 11 inch, a manual riveter, a 1/4 HP hand drill with high speed drill bits up to 3/8 inch, and any tools which are components of a subject units/parts/ subassembly/assembly.

i. proof/proofed/proofing: Shall apply to drawings and associated lists which have been interpreted for use in creating shop drawings, sketches, data and instructions applicable to live production/manufacturing by the contractor.

Source: https://assist.dla.mil -- Downloaded: 2026-10-21T11:47Z
Check the source to verify that this is the current version before use.

2. APPLICABLE DOCUMENTS

2.1 Government documents.

2.1.1 Specifications and Standards. Unless otherwise specified, the following specifications and standards of the issue listed in that issue of the Department of Defense Index of Specifications and Standards (DODISS) in effect on the date of this solicitation, form a part of this specification to the extent specified herein.

SPECIFICATIONS

MILITARY

DOD-D-1000	Drawings, Engineering And Associated Lists.
MIL-C-20709	Casework, Metal And Wood (Medical and Dental)

STANDARDS

MILITARY

DOD-STD-100	Engineering Drawing Practices.
MIL-STD-105	Sampling Procedures and Tables for Inspection by Attributes.
MIL-STD-129	Marking for Shipment and Storage.
MIL-STD-130	Identification Marking of US Military Property.
MIL-STD-280	Definitions of Item Levels, Item Exchangeability, Models, and Related Terms.

(Copies of specifications and standards required by manufacturers in connection with specific acquisition functions should be obtained from the contracting activity or as directed by the contracting officer.)

2.1.2 Other Government documents, drawings, and specifications. The following other Government documents form a part of this specification to the extent specified herein.

DPSC Sketch

25511-S	Sketch, Medical Cabinetry System.

Source: https://assist.dla.mil -- Downloaded: 2026-10-21T11:47Z
Check the source to verify that this is the current version before use.

DPSC Specifications

DPSC-DEPMEDS-AT(DM)	Deployable Medical Systems, General Requirements For. (see Notation a and b)

a. Delete all references to section 6 in DPSC-DEPMEDS-AT(DM), Reuseable Container. Reuseable container is not required.

b. All references in DPSC-DEPMEDS-AT(DM) to "Specification Sheet" shall be interpreted as referring to this specification.

(Copies of DPSC sketches and specifications required by manufacturers in connection with specific acquisition functions should be obtained from the contracting activity or as directed by the contracting officer.)

2.2 Other publications. The following documents form a part of this specification to the extent specified herein. The issue of the documents which are indicated as DoD adopted shall be the issue listed in the current DODISS and the supplement thereto, if applicable.

AMERICAN SOCIETY FOR TESTING AND MATERIALS (ASTM)

A-370	Mechanical Testing of Steel Products.
A-568	Steel Carbon Sheet and High Strength Low-Alloy Hot Rolled Sheet and Cold Rolled Sheet, General Requirements, Specifications for.

(Application for copies should be addressed to the American Society for Testing and Materials, 1916 Race Street, Philadelphia, PA 19103).

NATION SANITATION FOUNDATION

NSF-30	Cabinetry And Laboratory Furniture For Hospitals.

(Application for copies should be addressed to the National Sanitation Foundation, 3475 Plymouth Road, Ann Arbor, MI 48106.)

2.3 Order of precedence. In the event of a conflict between the text of this specification and the applicable documents cited herein, the text of this specification shall take precedence. Except for requirements covering the scrub sink unit 936, and drawings and associated lists, the rank of applicable docu-

Source: https://assist.dla.mil -- Downloaded: 2026-10-21T11:47Z
Check the source to verify that this is the current version before use.

ments shall descend from DPSC Sketch 25511-S, MIL-C-20709 to the remaining documents in accordance with the subject being addressed. With regard to the scrub sink, the rank of applicable documents shall descend from DPSC Sketch 25511-S, DPSC-DEPMEDS-AT(DM) with attached DD Forms 1423 and DD Forms 1664, MIL-C-20709 to the remaining documents as applicable. With regard to drawings and associated lists, the rank of applicable documents shall descend from DPSC Sketch 25511-S, DOD-D-1000 and DOD-STD-100, MIL-C-20709 to the remaining documents in accordance with the subject being addressed.

3. REQUIREMENTS

3.1 Description, general. Except as specified herein, and in addition to this specification, all cabinetry units shall be in accordance with MIL-C-20709 as applicable (see 2.3). All material shall be in conformance with the general description in MIL-C-20709, "Material".

3.2 Operating environmental conditions. The cabinetry system is intended for use and operation in a wide range of environmental conditions. All units shall be capable of being used and operated in environmental conditions ranging from 5 to 95 percent humidity and temperatures ranging from 35 degrees to 120 degrees Fahrenheit. Usage and operation in these environmental conditions shall not damage or adversely affect the units. Except for metal and wood, all material used in the production of the cabinetry system shall be rated by the manufacturer of the material/component for use as employed and for use in the specified environmental conditions (see 4.1.4).

3.3 Material, construction, and finish.

3.3.1 Prototype units. Units that generally meet the requirements of this specification, but not in particular with regard to every detail, have been manufactured and served as acceptable prototype units for general design and manufacturing techniques. For purposes other than demonstrating acceptable material selection, techniques of manufacturing, sizes, and finishes, these prototype units do not form a part of this specification. They are an example of generally acceptable design using acceptable manufacturing techniques. An appointment for inspection by interested manufacturers in connection with specific acquisition functions may be obtained from the contracting activity or as directed by the contracting officer.

3.3.2 Casework, all cabinet units. All casework shall be fabricated of cold-rolled steel. The steel shall be, at least, commercial quality, Class 1, matte (dull) finish, and oiled. Shall be in accordance with ASTM A-568. When ordering steel, the contractor shall be responsible to specify appropriate i.d. and o.d. of coil sizes and/or any special requirements such as "stretcher leveled"; specify gage required to be in accordance with MIL-C-20709, and enable parts/subassemblies/assemblies to conform to the requirements of this specification; and specify steel that shall be capable of successful compliance with test procedures in ASTM A-370. The steel shall be tested in accordance with

Source: https://assist.dla.mil -- Downloaded: 2026-10-21T11:47Z
Check the source to verify that this is the current version before use.

Information Handling Services DODSTD Issue 95-03

ASTM A-370. Steel gages used shall be the minimum required to enable a completed part/subassembly/assembly to be appropriately rigid and strong, and in conformance with this specification. Completed parts/subassemblies/assemblies shall be free of sharp edges, sharp corners, and protruding points that are accessible and hazardous to installation/user personnel. All structural components shall be securely welded into a single unitized structure requiring no additional panels to complete a shell. All exposed, interior and exterior, edges shall be smooth and rounded. The construction shall not employ exposed single thickness metal termination when gage of metal is less than number 16. All exposed metal terminations shall be smooth and rounded. The smaller dimension for support surfaces, sliding support areas, and/or non-buttwelded attachment surfaces shall be, at least, 1/2 inch. Exposed adjoining flange returns shall be either mitered, or depressed square lapped, providing a single exposed surface level. Exposed flange joints shall not be visible as normally viewed on a closed completed cabinet/unit. Before attaching any replaceable parts/subassemblies, the entire casework shall be finished with either two (2) coats of chemical resistant, baked mist-green enamel or mist-green powder coat epoxy finish. The color shall approximate the color of the prototype units (see 3.3.1). The finish shall have a maximum light reflectance of 50 percent and a cleanability of not more than 70 micrograms of residual soil per square inch after cleaning (National Sanitation Foundation Standard NSF 30, paragraph 3.2.1). The finish shall have a heat resistance to 400 degrees Fahrenheit. Additionally, the finish shall be in accordance with MIL-C-20709, "Surface finish of carbon steel casework surface".

3.3.2.1 Casework, base and sink units 945, 931, 916, 932, & 936. The casework for the base section cabinets and sink unit shall complete the interior bottom, interior and exterior sides, and interior and exterior back of the respective units. Shall include an integral extension to the exterior bottom incorporating a full-width toe space approximately 3 inches deep by 4 inches high at the bottom front. Shall include recessed areas in the two ends (sides) for carrying handles, and hanger support members for supporting counter units 928 and 927, and supporting hanger units 929. Casework for units 945, 931, and 916 shall be interchangeable (casework for drawered units). The cassette storage casework may be interchangeable with drawered units' casework. The sink unit's casework shall be of the same design except its width shall be in accordance with the sink unit's width. The cavity of each drawered casework shall accommodate 30 inches of accumulated drawer height. The cavity of the cassette storage casework shall accommodate compartments for darkroom equipment set. The construction of the casework shall provide for all attachments as specified herein. Other requirements for these casework shall be as specified herein.

3.3.2.2 Casework, upper section units 903 and 930. The casework for the upper section cabinets shall complete the exterior and interior sides, top, and interior bottom. Shall have an extension to the casework base. The base shall have a supporting surface which is a minimum of 3/4 inch wide and is folded inward from all sides of the casework. The interior right and left sides shall be smooth and flat (except for possible attachment of shelf slides), and shall be flush with the doorway. The interior bottom shall be smooth and flat. The casework shall include recessed areas in the two ends (sides) for carrying

Source: https://assist.dla.mil -- Downloaded: 2026-10-21T11:47Z
Check the source to verify that this is the current version before use.

handles. The bottom shall provide for application of strip padding material (see 3.3.9). As these two units are of different widths, their casework shall not be interchangeable except within like unit numbers. The casework may include shelf slides. The casework for unit 930 shall accommodate a narcotics locker. Other requirements for these casework shall be as specified herein.

3.3.3 Counters, units 926 and 927. The counter units shall be fabricated of cold-rolled steel. The material, construction, and finish shall be as specified for "Casework, all cabinet units" (see 3.3.2). The counters shall be unitized with vertical walls, a bottom flange extending inward a minimum of 3/4 inch from all sides, and reinforcement member(s) as appropriate. As these two units are of different widths, they shall not be interchangeable except within like unit numbers. Other requirements for these casework shall be as specified herein.

3.3.4 Box, unit 914. The box shall be fabricated of high density, molded plastic. Shall have a smooth finish with rounded corners and edges. Other requirements for the box shall be as specified herein.

3.3.5 Bar and hanger, units 913 and 929. As appropriate with the alternatives (see 3.6.4 and 3.6.5 respectively), the bar and hanger units shall be fabricated of cold rolled steel. The material, construction, and finish shall be as specified for "Casework, all cabinet units" (see 3.3.2) except the finish may be color black. Other requirements for these units shall be as specified herein.

3.3.6 Sink top and bowl, unit 936. The top and bowl for the sink unit shall be fabricated of 16 gage, 304 stainless steel. Shall be welded together as a unitized unit. All exposed welds shall be ground smooth. All exposed surfaces shall be finished with, at least, a number 4 grind for easy cleaning. Except as specified herein, the top shall be in accordance with MIL-C-20709, "Material", "Corrosion resisting steel", and "sink". Other requirements for the sink top and bowl shall be as specified herein.

3.3.7 Table top, unit 937. The table top for the folding leg table shall be fabricated of 304 stainless steel. The top shall be flat. All exposed surfaces shall be finished with, at least, a number 4 grind for easy cleaning. Except as specified herein, the table top shall be in accordance with MIL-C-20709, "Material", "Corrosion resisting steel". Other requirements for the table top shall be as specified herein.

3.3.8 Table underside, unit 937. The underside of the folding leg table shall be fabricated of cold rolled steel. The material, construction, and finish shall be as specified for "Casework, all cabinet units" (see 3.3.2). Shall include a folding mechanism to fold the legs under the top. Other requirements for the underside of the table shall be as specified herein.

3.3.9 Attachment fasteners and welds. Attachments shall be noncustomized and shall enable compliance with interchangeability requirements. In addition to those requirements (3.3.9 thru 3.3.9.3), fasteners and welds shall be in accordance with MIL-C-20709, "Workmanship".

Source: https://assist.dla.mil -- Downloaded: 2026-10-21T11:47Z
Check the source to verify that this is the current version before use.

3.3.9.1 Threaded fasteners. Except for threaded fasteners intended to match material and finish of hardware and self-tapping and/or self-drilling type screws, all threaded fasteners, including sheet-metal screws, shall be series 300 stainless steel. Self-tapping and self-drilling type screws shall be stainless steel series 400. Threaded fasteners shall not be employed to secure permanent attachments.

3.3.9.2 Rivet fasteners. All rivet fasteners shall be corrosion resistant steel or metal treated for corrosion resistance. Treatment for corrosion resistance shall be in accordance with nationally recognized standards, Federal Specification/Standard, or Military Specification/Standard. Rivets used for replaceable parts/subassemblies shall be capable of, and accessible for, removal and installation using only small hand tools. Rivets used for permanent or structural attachments shall be steel rivets.

3.3.9.3 Hardware fasteners. Hardware fasteners (fasteners matching material and finish of hardware) shall be in accordance with MIL-C-20709, "Hardware", "Fasteners".

3.4 Dimensions and weights of units. The system is intended to be deployable and therefore weight is critical. The weights specified are absolute maximum. It is desirable to reduce these weights while meeting all requirements of this specification (see 3.7.2.3, Design, generic requirements). Dimensional tolerances specified herein are concept functional tolerances and are not intended to be the tolerances specified in the drawings and associated lists. All dimensions in the following chart are nominal unless noted otherwise. Listed dimensions are for the purpose of establishing functional performance characteristics for modular units. Nominal dimensions are permitted to vary ± 1 inch. The nominal overall dimensions shall be as follows with listing of maximum allowable weights:

CHART OF WEIGHT IN POUNDS AND DIMENSIONS IN INCHES

Unit No.	Max. Wt.	Nom. Width	Nom. Ht.	Nom. Depth
945	160 8	18	37	23
931	160 8	18	37	23
916	160 8	18	37	23
932	130 8	18	37	23
903	130	36	31	12
930	115	18	31	12
914	1	5.75 1	5.00 1	9.25 1
913 2	-- 3	2-1/2	31	0-1/2
929 2	16 4			
928	20	36 5	1.25 1	22-5/8
927	25	48 5	1.25 1	22-5/8
936	265 8	30	40 6	24
937	85	45	36 7	30

Source: https://assist.dla.mil -- Downloaded: 2026-10-21T11:47Z
Check the source to verify that this is the current version before use.

Notations applicable to 3.4:

1 Dimension tolerance ± 0.125

2 Alternatives may be acceptable (see 3.6.4 or 3.6.5).

3 Unit weight is not specified, but is included in the weight of 945, 931, 916, 932, and 930 as a component.

4 Weight is for a complete set of four (4) hangers.

5 Width does not include attached hardware for securing counter to either the cabinet handle or hanger unit 929.

6 Less caster height, 44-1/2 inches with casters.

7 Folded height of 4-1/2 (± 1/2 inch).

8 Including 1/2 set hanger unit 929 (or alternate thereof).

3.5 Replaceable parts/subassemblies/assemblies. Except as individually noted, at least the items specified here, 3.5 through 3.5.37, shall be replaceable parts/sub-assemblies/assemblies. They shall be components of the respective subject units. Shall be interchangeable with like parts/subassemblies/assemblies. Shall be free of sharp edges, sharp corners, and protruding points that are accessible and hazardous to installation personnel. The specified finish shall be applied to the entire part/subassembly before it is attached to another part/subassembly/assembly.

3.5.1 Casework assembly, unit 945, 931, and 916. The casework assembly for drawered cabinets shall include, at least, a casework (see 3.3.2 and 3.3.2.1); an exterior bottom (see 3.5.6); and two (2) skid rails (see 3.5.8). The skid-rails shall be mounted via stainless steel, countersunk fasteners. The assembly may include permanently attached elements for drawer suspension and/or permanently attached brackets for receiving retaining bars, unit 913. Any permanently attached drawer element shall be universal to all possible drawer size configurations (see 3.5.11). As appropriate with specified alternatives, the assembly shall provide for attachment of the quick disconnect pin located on the lower end of the retaining bar unit 913 as specified in 3.6.4. Elements of unit 945, 931, and 916 which are required to be available as a replaceable part/subassembly shall not be permanently attached. Any element permanently attached to the casework need not be available as a replaceable part/subassembly. This casework assembly may be available in common with the case-work assembly for unit 932 (see 3.5.2). Elements which are not permanently attached but are required to adapt the casework to intended usage shall be available as replaceable parts/subassemblies/assemblies. Other requirements for this casework assembly shall be as specified herein.

Source: https://assist.dla.mil -- Downloaded: 2026-10-21T11:47Z
Check the source to verify that this is the current version before use.

3.5.2 Casework assembly, unit 932. The casework assembly for the cassette storage cabinet shall include, at least, a casework (see 3.3.2and 3.3.2.1); an exterior bottom (see 3.5.6); and two(2) skid-rails (see 3.5.8). The skid-rails shall be mounted via stainless steel, countersunk fasteners. The assembly may include permanently attached elements for cassette storage compartments. As appropriate with specified alternatives, the assembly shall provide for attachment of the quick disconnect pin located on the lower end of the retaining bar unit 913 as specified in 3.6.4. Elements of unit 932 which are required to be available as a replaceable part/subassembly shall not be permanently attached. Any element permanently attached to the casework need not be available as a replaceable part/subassembly. This case-work assembly may be available in common with the casework assembly for unit 945, 931, and 916 (see 3.5.1). Elements which are not permanently attached but are required to adapt the casework to intended usage shall be available as replaceable parts/subassemblies/assemblies. Other requirements for this casework assembly shall be as specified herein.

3.5.3 Casework assembly, unit 903. The casework assembly for the 36 inch wide upper section pharmaceutical cabinet shall include, at least, a casework (see 3.3.2 and 3.3.2.2), and strip padding material applied to the casework bottom (see 3.5.9). The casework may include permanently attached shelf slides which allow for all shelf height configurations (see 3.6.2.1.1). Elements of unit 903 which are required to be available as a replaceable part/subassembly shall not be permanently attached. Any element permanently attached to the casework need not be available as a replaceable part/subassembly. Elements which are not permanently attached but are required to adapt the casework to intended usage shall be available as replaceable parts/sub-assemblies/assemblies. Other requirements for this casework assembly shall be as specified herein.

3.5.4 Casework assembly, unit 930. The casework assembly for the 18 inch wide upper section pharmaceutical cabinet shall include, at least, a casework (see 3.3.2 and 3.3.2.2), and strip padding material applied to the casework bottom (see 3.5.9). The casework may include permanently attached shelf slides which allow for all shelf required heights (see 3.6.2.1.2). Elements of unit 930 which are required to be available as a replaceable part/subassembly shall not be permanently attached. Any element permanently attached to the casework need not be available as a replaceable part/subassembly. Elements which are not permanently attached but are required to adapt the casework to intended usage shall be available as replaceable parts/sub-assemblies/assemblies. Other requirements for this casework assembly shall be as specified herein.

3.5.5 Casework assembly, unit 936. The casework assembly for the scrub sink unit shall include, at least, a casework (see 3.3.2 and 3.3.2.1); insulated mounting platform(s) for the water pump and motor to dampen vibration; three recessed areas in casework back side; an exterior bottom (see 3.5.7); and two (2) skid-rails (see 3.5.8). Shall include provisions for attachment of casters. The recessed areas shall accommodate a power supply inlet (see 3.5.33), a female section of a quick disconnect water supply coupling (see 3.5.29.2), and a waste water connector (see 3.5.29.1). The two plumbing recesses may be combined. Elements of unit 936 which are required to be available as a replaceable

Source: https://assist.dla.mil -- Downloaded: 2026-10-21T11:47Z
Check the source to verify that this is the current version before use.

part/subassembly shall not be permanently attached. Any element permanently attached to the casework need not be available as a replaceable part/subassembly. Elements which are not permanently attached but are required to adapt the casework to intended usage shall be available as replaceable parts/subassemblies/assemblies. Other requirements for this casework assembly shall be as specified herein.

3.5.6 Exterior bottom, units 945, 931, 916, and 932. The exterior bottom for the base section units shall be fitted and drilled for installation. Shall be fabricated of cold rolled steel. The material, construction, and finish shall be as specified for "Casework, all cabinet units" (see 3.3.2). Only small hand tools (excluding drill and drill bits) shall be required for installation. Other requirements for the exterior bottom shall be as specified herein.

3.5.7 Exterior bottom, unit 936. The exterior bottom for the scrub sink unit shall be fitted and drilled for installation. Shall be fabricated of cold rolled steel. The material, construction, and finish shall be as specified for "Casework, all cabinet units" (see 3.3.2). Only small hand tools (excluding drill and drill bits) shall be required for installation. Other requirements for the exterior bottom shall be as specified herein.

3.5.8 Skid-rail, units 945, 931, 916, 932, and 936. Skid-rails for base section units and sink unit shall be fabricated of anti-frictional nylon or polyethelene UHMW. Shall be approximately 5/16 inch high by 3/4 inch wide by a length equal to the respective unit's width (or depth in event side mounting is required to allow caster mounting on sink unit). Shall have rounded edges which are intended to contact the floor. The finish shall be smooth. The bottom long edges shall have a radius of 1/8 inch (± 1/32 inch). Skid-rails shall be available for each required length and be predrilled for installation and shall include fasteners. Other requirements for the skid-rails shall be as specified herein.

3.5.9 Strip padding material, units 903 and 930. Strip padding for upper section cabinets shall have a minimum width of 3/4 inch. Shall be available in individually cut lengths, or in standard commercial lengths not to exceed 25 feet. The adhesive material may be pre-applied or separately available. If adhesive material is separately available, an adequate supply shall be included with the strip padding material or the instruction manual shall advise the user of the requirement to order adhesive material separately. Other requirements for the strip padding shall be as specified herein.

3.5.10 Carrying handle, unit 945, 931, 916, 932, 903, 930, & 936. The carrying handles for the cabinets and sink units shall be Sessions Model 5300-WD SPRING.

3.5.11 Drawer, units 945, 931, and 916. The drawers for the drawered base section cabinets shall be fabricated of cold rolled steel. The material, construction, and finish shall be as specified for "Casework, all cabinet units" (see 3.3.2). The drawer front shall be a replaceable double wall (hollow) subas-

Source: https://assist.dla.mil -- Downloaded: 2026-10-21T11:47Z
Check the source to verify that this is the current version before use.

Information Handling Services DODSTD Issue 95-03

sembly with a minimum thickness of 5/8 inch. Each drawer shall include, at least, a flush mounted aluminum handle located on the vertical centerline near the top of the drawer front, and a label holder located on the drawer front in accordance with a pattern used to locate the card holder on all drawers of all drawered cabinets. The label holder shall have a card opening 2-1/4 inches by 1-1/8 inches (both ± 1/8 inch). The label holder shall be capable of receiving a card 2-1/8 inch wide by 1 inch high, and provide a viewable area of, at least, 1-3/4 inch by 3/4 inch. The drawer may include permanently attached elements of the drawer suspension system. Drawers shall be available with modular face heights of 3 (± 1/4), 6 (± 3/8), 9 (± 3/8), and 12 (± 3/8) inches. The 12 inch drawer shall include a removable bottom insert which shall include a sliding file support (slides from back of drawer to front to hold files upright). In conjunction with the design of the drawer suspension, any set of drawers, having a combined face height of 30 inches, shall be capable of being installed in casework for units 945, 931, and 916. Drawers shall have a minimum inside width of 14 inches and a minimum inside front to back dimension of 18-1/4 inches. The drawer dimensions shall be a minimum as follows:

Drawer Size	Inside Height (back & sides)	Outside Face Height (actual), minimum)
3	1-5/8 inches	2-3/4 inches
6	4-3/8	5-5/8
9	7-1/4	8-5/8
12	10-1/4	11-1/2

The internal horizontal edges shall have a radius of 3/16 inch (± 1/16 inch) for easy cleaning. Internal vertical edges may be butted without a radius. Drawers shall be available in each of the specified sizes (face heights). Other requirements for drawers shall be as specified herein.

3.5.11.1 Test feature, deflection, drawer, units 945, 931, & 916. The drawer bottom shall be capable of supporting at least 50 pounds, distributed over a centered 1 square foot area. During this loading, the drawer bottom shall not deflect in excess of 0.100 inch. The drawer shall be capable of successful compliance with test procedure in 4.4.17.

3.5.12 Drawer suspension, units 945, 931, and 916. The drawer suspension for drawered cabinets shall be fabricated of corrosion resistant steel or metal treated for corrosion resistance (except seals, bumpers, o.d. of drawer roller, etc.). Shall consist of all elements which are required to allow drawers to operate as specified. The overall design shall allow field reordering of drawer configuration to any possible combination specified in 3.5.11. Field reordering of drawer configuration may require use of small hand tools. The design of the suspension shall be such that when the casework is level, drawers shall either close by gravity or have a spring catch to hold them in the closed position. If the design incorporates gravity for drawer closure, then there shall be a feature to hold a draw in the open position when so set by a user. The suspension system shall incorporate a stop to prevent a drawer from being in-

Source: https://assist.dla.mil -- Downloaded: 2026-10-21T11:47Z
Check the source to verify that this is the current version before use.

advertently pulled out and off the drawer runs, but shall allow for intentional removal without use of tools. There shall be a bumper arrangement to prevent metal to metal contact upon drawer closure. Elements of the suspension may be permanently attached to the cabinet casework and/or the drawer provided such attachments are universal to all required drawer configurations. The suspension shall be as specified herein.

3.5.12.1 Test features, drawer suspension, units 945, 931, & 916.

3.5.12.1.1 Accidental drawer opening, tilt and jolt. A fully closed drawer shall not open if the upright cabinet is tilted forward at an angle of 3 degrees from vertical and jolted with a force equal to a 1 pound natural rubber weight dropped 6 inches onto the cabinet's rear edge. For a drawer suspension with gravity closure, "open" is considered as opening beyond the front edge of the cabinet's top. For drawer suspension with a drawer catch, "open" is considered as a drawer being dislodged from the drawer catch. Shall be capable of successful compliance with test procedure 4.4.28

3.5.12.1.2 Opening & closing force, drawer, units 945, 931 & 916. An intalled, empty new drawer, less drawer catch (if provided), shall be capable of being opened without applying more than 2.2 pounds of pulling force. An installed drawer, loaded with 100 pounds evenly distributed on its bottom, after 10,000 cycles of being opened and closed, shall be capable of being opened and closed without applying forces in excess of 20 percent increase above the forces required to open and close the loaded drawer prior to cycling. If the drawer is not intended to close by gravity, then a new drawer shall be capable of being closed without applying more than 2.2 pounds of pushing force. If a drawer is intended to close by gravity, then an open drawer (empty or loaded with 100 pounds, before and after cycling) shall close upon release provided it is not set to (or beyond) a position intended to keep the drawer open. Shall be capable of successful compliance with test procedure 4.4.10.

3.5.12.1.3 Cycling requirement, drawer, units 945, 931, and 916. Drawers shall be capable of continually operating smoothly for, at least, 10,000 cycles when loaded with 100 pounds evenly distributed within the drawer. After the cycling operations, the used drawer shall be capable of normal operation, except a 20 percent additional pulling/pushing operating force above new drawer requirement is acceptable, except gravity closure shall remain operational (see 3.5.12.1.2). A test cycled drawer shall be capable of being reconditioned to as-new requirements. For purposes of determining ease of opening, closing and durability (cycling drawer), full open shall be interpreted as just before engagement of a feature to hold drawer in open position (if present and less than 13 inches from full closed), or 13 inches from full closed position. Shall be capable of successful compliance with test procedure in 4.4.21.

3.5.12.1.4 Bumper and catch, drawer, units 945, 931, and 916. The drawer bumper and the drawer catch shall remain operational and effective following the specified cycling performance (see 3.5.12.1.3). Shall be capable of successful compliance with test procedure in 4.4.10 and 4.4.21.

Source: https://assist.dla.mil -- Downloaded: 2026-10-21T11:47Z
Check the source to verify that this is the current version before use.

3.5.13 reserved.

3.5.14 Drawer partitionment set, drawer, unit 931. The drawer partitionment set for the 6 inch drawers in unit 931 shall be fabricated of metal which is corrosion resistant or is treated for corrosion resistance. The partitionment set shall be capable of providing multiple compartment size configurations. Compartment dividers shall be adjustable on 1 inch centers in both directions. There shall be 3 dividers intended to be placed parallel with the drawer front and 3 dividers intended to be placed perpendicular to the drawer front (neither include perimeter walls). The approximate overall size of the partitionment set shall be 18 inches front-to-back by 14 inches wide by 4-1/4 inches high.

3.5.15 Pullboard, units 945, 931, 916, and 932. Pullboard for base section cabinets shall be fabricated of cold rolled steel. The material, construction, and finish shall be as specified for "Casework, all cabinet units" (see 3.3.2). The pullboard top shall be smooth and flat. Shall be approximately 9/16 inch thick by 16 inches wide and be extendible by approximately 14 inches. When fully closed, shall have available an easy means for opening which does not protrude forward of the top. Shall have a stop to prevent the pullboard from being inadvertently pulled out. This stop shall not utilize metal to metal contact. Shall have a bumper, or other design feature to prevent metal to metal contact upon closing. Any element of the pullboard which is not permanently attached to either the pullboard or the casework, shall be available as a replaceable part/subassembly. Other requirements for the pullboard shall be as specified herein.

3.5.16 Top, units 945, 931, 916, and 932. The top for base section cabinets shall be fabricated of cold rolled steel. The material, construction, and finish shall be as specified for "Casework, all cabinet units" (see 3.3.2). The top surface shall be smooth and flat. The top shall be approximately 1 inch thick. A mounted top shall overhang the casework (front edge only) by approximately 1 inch. The underside, front center shall provide for engagement of the retaining bar, unit 913, as specified in 3.6.4. The top may incorporate elements for attachment of counter units 928 and 927 at elevation flush-with-top provided such elements are water spray tight. These elements may consist of four (2 per side) built-in recessed counter support bars exposed to view from side edges and top view. Employment of these elements (in conjunction with 8 additional bars recessed into casework side panels) shall eliminate requirement for separate and loose parts (Hanger unit 929) for attachment of counters (units 928 and 927) at required elevations. Other requirements for the top shall be as specified herein.

3.5.17 Door, right and left, unit 903. The doors for the 36 inch wide pharmaceutical upper section cabinet shall be fabricated of cold rolled steel. The material, construction, and finish shall be as specified for "Casework, all cabinet units" (see 3.3.2). The back pan need not be permanently attached or a replaceable part. Each door shall be double wall (hollow) constructed and have a minimum thickness of 5/8 inch. Except for the padlock recessed area, the exposed

Source: https://assist.dla.mil -- Downloaded: 2026-10-21T11:47Z
Check the source to verify that this is the current version before use.

inside and outside panel surfaces shall be smooth and flat for easy cleaning. The interior shall be fitted with sound deadening cellular material. Each door shall accommodate two (2) hinges, one top and one bottom, for mounting the door on the cabinet front side (right and left side respectively). When closed, a set of doors shall meet at the cabinet's front vertical centerline. The doorway width and height shall expose the entire interior of the cabinet. Each door shall include a bumper arrangement to prevent metal to metal contact upon closing. A mounted door shall be capable of swinging 180 degrees. Each door shall be removable. When either door is open approximately 90 degrees, it shall be capable of being lifted off and disengaged from the hinges without use of tools. When in the closed position, neither door nor hinge shall be capable of being removed. When reinstalling a removed door, one hinge shall engage ahead of the other allowing for easy installation. Hinge pins shall be welded to the male side of the hinge. The door shall accommodate catches to hold the door closed (see 3.5.21). Doors shall have a recessed reinforced panel located on the cabinet front vertical centerline for padlock security. The recess shall be designed to accommodate an installed military padlock (approximately 5/8 inch thick and having a shackle diameter of approximately 1/4 inch) being flush with the door front. The door shall be capable of withstanding the test features specified in 3.6.2.3.7 through 3.6.2.3.11. Right and left door are not required to be interchangeable. Each door, right and left, shall be available as a replaceable item. Other requirements for the door shall be as specified herein.

3.5.18 Door, right and left, unit 930. The doors for the 18 inch wide pharmaceutical upper section cabinet shall be fabricated of cold rolled steel. The material, construction, and finish shall be as specified for "Casework, all cabinet units" (see 3.3.2). The back pan need not be permanently attached or a replaceable part. Each door shall be double wall (hollow) constructed and have a minimum thickness of 5/8 inch. Except for the padlock recessed area, the exposed inside and outside panel surfaces shall be smooth and flat for easy cleaning. The interior shall be fitted with sound deadening cellular material. Each door shall accommodate two (2) hinges, one top and one bottom, for mounting the door on the cabinet front side (right and left side respectively). When closed, a set of doors shall meet at the cabinet's front vertical centerline. The doorway width and height shall expose the entire interior of the cabinet. Each door shall include a bumper arrangement to prevent metal to metal contact upon closing. A mounted door shall be capable of swinging 180 degrees. Each door shall be removable. When either door is open approximately 90 degrees, it shall be capable of being lifted off and disengaged from the hinges without use of tools. When in the closed position, neither door nor hinge shall be capable of being removed. When reinstalling a removed door, one hinge shall engage ahead of the other allowing for easy installation. Hinge pins shall be welded to the male side of the hinge. The door shall accommodate catches to hold the door closed (see 3.5.21). Doors shall have a recessed reinforced panel located on the cabinet front vertical centerline for padlock security. The recess shall be designed to accommodate an installed military padlock (approximately 5/8 inch thick and having a shackle diameter of approximately 1/4 inch) being flush with the door front. The door shall be capable of withstanding the test features specified in 3.6.2.3.7 through 3.6.2.3.11. Right and left door are not required

Source: https://assist.dla.mil -- Downloaded: 2026-10-21T11:47Z
Check the source to verify that this is the current version before use.

to be interchangeable. Each door, right and left, shall be available as a replaceable item. Other requirements for the door shall be as specified herein.

3.5.19 Hinge, bottom of door, units 903 and 930. The hinge shall be a replaceable standard commercial, stainless steel (series 300) hinge manufactured by a nationally recognized manufacturer. Shall be in accordance with the general provision in MIL-C-20709, "Material". The hinge pivot length shall be approximately 2-1/2 inches long. The hinge plate material shall be approximately 0.08 inch thick. Each complete hinge, installed, shall be capable of withstanding the forces induced by testing the requirements of the door (see 3.6.2.3.7 thru 3.6.2.3.11). The hinge pin shall be the commercial length and shall be 3/8 inch (± 1/8 inch) longer than the top hinge pin (see 3.5.20). The top of the pin shall be welded to the male hinge section and the bottom shall be rounded or beveled for easy engagement. Alterations to the commercial hinge are allowed. As an alternative, the length of this pin and the pin specified in 3.5.20 may be exchanged. As a replaceable part/subassembly, any alterations shall be included. Other requirements for the hinge shall be as specified herein.

3.5.20 Hinge, top of door, units 903 and 930. The hinge shall be a replaceable standard commercial, stainless steel (series 300) hinge manufactured by a nationally recognized manufacturer. Shall be the same hinge as specified in 3.5.19 except the pin shall be cut short by approximately 3/8 inch. As an alternative, the length of this pin and the pin specified in 3.5.19 may be exchanged. Other requirements for the hinge shall be as specified herein.

3.5.21 Catch, door, units 903 and 930. Shall be a door catch for holding the door closed. Shall be in accordance with MIL-C-20709, "Hardware", "Catches". Other requirements for the catch shall be as specified herein.

3.5.22 Hanger, one piece, unit 929. As applicable with the specified alternatives (see 3.6.5), individual hangers shall be available. Other requirements for the hanger shall be as specified herein.

3.5.23 Door, right and left, unit 936. The doors for the sink unit shall be fabricated of cold rolled steel. The material, construction, and finish shall be as specified for "Casework, all cabinet units" (see 3.3.2). The back pan need not be permanently attached or a replaceable part. Each door shall be double wall (hollow) constructed and have a minimum thickness of 5/8 inch. Except for compartment(s) for manuals, the exposed inside and outside panel surfaces shall be smooth and flat for easy cleaning. The interior shall be fitted with sound deadening cellular material. Each door shall accommodate two (2) hinges, one top and one bottom, for mounting the door on the cabinet front side (right and left side respectively). When closed, a set of doors shall meet at the cabinet's front vertical centerline. The doorway width and height shall expose the entire interior from a height, at least, 1 inch above the bottom of the sink bowl to the cabinet interior bottom. Each door shall include a bumper arrangement to prevent metal to metal contact upon closing. A mounted door shall be capable of swinging approximately 180 degrees. The door shall be fitted with flush mounted handle(s) and latch(es). The door shall be capable of withstanding the test features

Source: https://assist.dla.mil -- Downloaded: 2026-10-21T11:47Z
Check the source to verify that this is the current version before use.

specified in 3.6.7.2.6 and 3.6.7.2.7. Right and left door are not required to be interchangeable. Other requirements for the door shall be as specified herein.

3.5.24 Hinge, door, unit 936. The hinge shall be a replaceable standard commercial, stainless steel (series 300) hinge manufactured by a nationally recognized manufacturer. Shall be in accordance with the general provisions in MIL-C-80709, "Material". Each complete hinge, installed, shall be capable of withstanding the forces induced by testing the requirements of the door (see 3.6.7.2.6 and 3.6.7.2.7). Other requirements for the hinge shall be as specified herein.

3.5.25 Latch, door, unit 936. The door latch shall be fabricated of corrosion resistant steel or metal treated for corrosion resistance. Shall be flush mounted type and incorporate the handle. Shall be of such design and so installed that a latched door may not be opened without operating the latch. Other requirements for the latch shall be as specified herein.

3.5.26 Shelf, unit 903. The shelf for the 36 inch wide upper section cabinet shall have a length which approximately equals the full interior width of the cabinet. The shelf shall be fabricated of cold rolled steel. The material, construction, and finish shall be as specified for "Casework, all cabinet units" (see 3.3.2). The shelf shall be supported by slides and be removable except one shelf may be secured in place with removable fasteners. The shelf thickness shall be 3/4 inch (± 1/8 inch). Other requirements for the shelf shall be as specified herein.

3.5.27 Shelf, unit 930. The shelf for the 18 inch wide upper section cabinet shall have a length which approximately equals the full interior width of the cabinet. The shelf shall be fabricated of cold rolled steel. The material, construction, and finish shall be as specified for "Casework, all cabinet units" (see 3.3.2). The shelf shall be supported by slides and be removable except one shelf may be secured in place with removable fasteners. The shelf thickness shall be 3/4 inch (± 1/8 inch). Other requirements for the shelf shall be as specified herein.

3.5.28 Front cover, unit 932. Shall be a detachable cover for the cassette storage cabinet. Shall be fabricated of cold rolled steel. The material, construction, and finish shall be as specified for "Casework, all cabinet units" (see 3.3.2). Shall be reinforced as appropriate to allow normal handling and storage. Shall be capable of being secured in place by a retaining bar unit 913. When in place, it shall cover the entire cabinet cavity. Other requirements for the cover shall be as specified herein.

3.5.29 Sink plumbing parts/subassemblies/assemblies, unit 936. All plumbing parts/subassemblies/assemblies shall be standard items. Except as noted for individual items, they shall be available from nationally recognized manufacturers.

3.5.29.1 Waste piping. Internal waste piping shall be 1-1/2 inch PVC, polybutline, or polypropolene with compression fittings capable of being leak proof

Source: https://assist.dla.mil -- Downloaded: 2026-10-21T11:47Z
Check the source to verify that this is the current version before use.

tightened by hand. Shall include a connector which is compatible with the tail piece, a dismountable U trap, and an exterior mounted connector located in a rear recess for connection of a drain hose. Shall also include the strainer bowl and tail piece which shall be corrosion resistant steel or steel treated for corrosion resistance. The tail piece may be modified commercial. Shall be available as replaceable parts in accordance with 3.5.29.16. Shall be as specified herein.

3.5.29.2 Supply plumbing. Internal supply piping shall be a combination of 1/2 inch and 1/4 inch i.d. plastic type material. Flexible piping shall be polybutylene with minimum 1/4 inch i.d. Cold water, non-flexible, piping shall be either PVC or CPVC. Hot water, non-flexible, piping shall be CPVC. No individual water branch shall utilize more than one flexible pipe/tube. Shall include an exterior mounted female section of a quick disconnect coupling (see 3.5.29.8), a backflow check valve to prevent system water from entering exterior supply water system (see 3.5.29.11), and appropriately located unions for disassembly/assembly purposes. Shall be available as replaceable parts in accordance with 3.5.29.16. Shall be as specified herein.

3.5.29.3 Faucet, 23 inch. The faucet shall be single, removable, swivel, gooseneck type with chrome finish and have an overall height of 23 inches (± 1 inch) from the top of the sink. The finish shall be in accordance with MIL-C-20709, "Plumbing fixtures". The faucet shall include a standard type nonsplash nozzle which shall be attached via standard faucet end threads. As an alternative, the nonsplash nozzle may be available as a separate part.

3.5.29.4 Faucet, 11 inch (non-component item). In addition to the 23 inch faucet specified in 3.5.29.3, an 11 inch high faucet shall be available as a replaceable item. This faucet shall not be included as a component of the sink unit. Other than height, it shall be as specified for the 23 inch high faucet.

3.5.29.5 Handles, faucet water valves. The handles for the faucet water valves shall be chrome finished, standard 6 inch elbow wing type (paddle shaped). The finish shall be in accordance with MIL-C-20709, "Plumbing fixtures". Each valve shall be permanently identified as a "H"/"hot", and "C"/"cold". May be available only as a set of hot and cold handles or as individual handles.

3.5.29.6 Valve, faucet hot water. The hot water valve shall be dedicated to hot water and rotate counter-clockwise for the ON position. Shall be a part of a matched set with the valve specified in 3.5.29.7. The finish of exposed elements shall be in accordance with MIL-C-20709, "Plumbing fixtures". It may be available only as a set of valves (hot and cold) or as an individual hot water valve.

3.5.29.7 Valve, faucet cold water. The cold water valve shall be dedicated to cold water and rotate clockwise for the ON position. The valve shall be a part of a matched set with the valve specified in 3.5.29.6. The finish of exposed elements shall be in accordance with MIL-C-20709, "Plumbing fixtures". It may be available only as a set of valves (hot and cold) or as an individual cold water valve.

Source: https://assist.dla.mil -- Downloaded: 2026-10-21T11:47Z
Check the source to verify that this is the current version before use.

3.5.29.8 Supply water quick disconnect coupling assembly. The quick disconnect coupling shall be 1/2 inch, automatic shut off McMaster-Carr or equal. Shall be rated by the manufacturer for working water pressure of, at least, 70 psi. Both the male and female section shall have an automatic shut off valve which blocks water flow upon disconnect. The female section shall have a secured cap to cap its opening when not connected to the male section. Other requirements for the coupling shall be as specified herein.

3.5.29.9 Line strainer. Shall be a line strainer with a 40 mesh stainless steel (300 series) screen. The inlet shall be compatible with the water supply hose connector (see 3.5.29.10). The outlet shall be compatible with the male section of the quick disconnect coupling (non-coupling side).

3.5.29.10 Water supply hose assembly. The water supply hose assembly shall be nominal 3/8 inch by approximately 10 feet long. Shall include a male section of the quick disconnect coupling (see 3.5.29.8), a line strainer (see 3.5.29.9), and a hose with one free end having no connector. The hose shall be rated by the manufacturer for, at least, 70 psi working pressure.

3.5.29.11 Backflow check valve. The backflow check valve shall prevent backflow of water into the exterior water system. Shall be capable of withstanding water pressure of 70 psi from either direction without being damaged. Shall be operational with supply water and/or system water pressure through a range of negative pressure of 20 feet of water to positive pressure of 50 psi.

3.5.29.12 Drain petcock, supply plumbing and pumping system. The petcock shall be appropriately located in the supply plumbing system to enable drainage of the supply plumbing and pumping system. Shall include a connector which is compatible with the drain tubing (see 3.5.29.13).

3.5.29.13 Drain tubing, supply plumbing and pumping system. Shall be a flexible drain tubing at least 18 inches long. Shall be compatible with the connector on the petcock (see 3.5.29.12).

3.5.29.14 Drain hose, waste water. The waste water drain hose shall be 1-1/2 inch flexible, at least 7 feet long. Shall have a connector or slip-joint which forms a leak-proof connection and which is compatible with the drain connector/slip-joint on the waste piping (see 3.5.29.1).

3.5.29.15 Strainer and stopper assembly, sink bowl. The strainer and stopper assembly shall be stainless steel (300 series). Shall be capable of retaining debris greater than 1/4 inch. Shall have two positions, one to stop drainage and one to drain the sink.

3.5.29.16 Individual pipes and plumbing parts. Individual pipes and plumbing parts shall be standardized within the plumbing system. Each item shall be available as a separate part.

Source: https://assist.dla.mil -- Downloaded: 2026-10-21T11:47Z
Check the source to verify that this is the current version before use.

3.5.29.17 Seals and normally replaceable wear items. All seals and normally replaceable wear items shall be available as replaceable items. They may be individually available or available as components of seal kits.

3.5.30 Water heater, unit 936. The water heater for the sink unit shall be a tankless type. Shall be rated 4000 watts at 240 volts. Shall be capable of operating on power supplies of 2 wire, 240 volts, 50 Hz; 3 wire, 230 volts, 50/60 Hz; and 4 wire, 208 volts (3 phase), 50/60 Hz. In conjunction with water system controls, it shall be capable of operating over a supply pressure range of negative 20 feet of water pressure to positive pressure of 70 psi. Shall have a thermostat which shall be capable of controlling the faucet water temperature from 80 degrees F to 120 degrees F (user selectable), provided the difference between the supply water temperature and the setting (in conjunction with flow rate setting) is equal or less than the heater's achievable temperature rise. The heater system shall provide for maximum flow control (user selectable/adjustable) over a range of, at least, 1/2 gallon per minute to 2 gallons per minute. This control shall be located inside the sink cabinet and, in conjunction with the adjustable thermostat, shall allow a user to obtain optimal temperature rise and flow rate of hot water. Once the flow rate is adjusted (inside the cabinet) to any setting within the specified range, the maximum flow rate (obtainable via hot water faucet valves) shall be constant (± 15 percent of mean flow rate) over an extended period of time, and after unit is turned off and reactivated without changing the maximum flow control setting (inside the cabinet). The water heater shall be UL approved/listed. The water heater and controls shall be compatible with the pump and captive air tank with its controls specified in 3.5.31. All controls shall be manufactured by nationally recognized manufacturers. The system shall consist of only commercially available items. Other requirements for the heating system shall be as specified herein.

3.5.31 Motor, pump and captive air tank, unit 936. The motor, pump and captive air tank shall maintain working pressure at the faucet. Shall be provisioned with a switch, conveniently located inside the cabinet, for turning the pump on and off. The switch shall be marked or covered to prevent accidental turn-off while the heater is on, or there shall be other adequate protection against unloaded heater burnout. Shall be capable of handling all required pumping for the system. As a durability requirement, the motor shall be rated by the manufacturer for continuous duty at, at least, 1/3 HP. Shall include all necessary controls to operate as specified herein. Shall be compatible with other controls within the water system. May be available as separate items. All items shall be manufactured by nationally recognized manufacturers. Other requirements for the motor, pump and captive air tank shall be as specified herein.

3.5.32 Power supply cord, unit 936. The power supply cord shall be a 4 wire number 10 AWG, grounding, flange twist-lock type. Shall be at least 9 feet long. Shall be compatible with the inlet located in the dedicated recessed area in the casework rear panel (see 3.5.33). Shall include a standard detachable male wall plug rated at 30 amps which shall be of type consistent with requirements under Electrical Characteristics in DEPMEDS General Requirements. Available types of wall plugs shall include world-wide standards of 30 amp for 2 wire 240 volt 50

Source: https://assist.dla.mil -- Downloaded: 2026-10-21T11:47Z
Check the source to verify that this is the current version before use.

Hz, 3 wire 220-230 volt 50/60 Hz, and 4-wire 208 volts (3 phase) 50/60 Hz. Shall be a commercially available item except the commercially available length may be 9 to 16 feet, or alternatively, the cord and plug may be available separately. Other requirements for the power cord shall be as specified herein. In addition to these requirements, the cord shall be consistent with requirements in DPSC-DEPMED8 General Requirements.

3.5.33 Inlet, electrical power supply, unit 936. The inlet shall be a recessed male inlet, twist-lock type, UL rated for at least 30 amps. Shall be compatible with the power supply cord (see 3.5.32). Shall be located in the dedicated recessed area in the casework's rear panel. Shall include a secured cap to cover the inlet when not in use. Shall be a commercially available item. In addition, it shall be in accordance with the electrical requirements of DPSC-DEPMED8-AT(DM). Other requirements for the inlet shall be as specified herein.

3.5.34 Top and bowl, sink unit, 936. The top and bowl for the sink unit shall be unitized (see 3.3.6). The top shall have a marine edge along the front and two sides with a rise of 3/16 inch (± 1/16 inch), and a 3-1/2 inch high (± 1/4 inch) high back-splash across the back. The underside shall be sound deadened. The bowl shall be approximately 24 inches wide by 14 inches front to back by 12 inches deep. All internal returns (vertical and bottom horizontal edges) shall be radiused by at least 3/8 inch and at most 2 inches. Radius tolerance shall be ± 1/16 inch. The top marine edge may incorporate elements for attachment of counter units 928 and 927 at elevation flush-with-top of Base Section Units provided such elements are water spray tight, are fabricated of 300 series stainless steel, and the 3/16 inch rise is maintained. These elements may consist of four (2 per side) built-in recessed counter support bars exposed to view from side edges and top view. Employment of these elements (in conjunction with 8 additional bars recessed into casework side panels) shall eliminate requirement for separate and loose parts (Hanger unit 929) for attachment of counters (units 928 and 927) at required elevations. Other requirements for the top and bowl shall be as specified herein.

3.5.35 Installation tools, unit 936. Any tools, other than small hand tools (see 1.5, h), required for installation of a part/subassembly/assembly, performing adjustments normally performed by user, and/or readying an operational unit for storage, shall be furnished as replaceable parts. Shall be fabricated of corrosion resistant material or steel that has been treated for corrosion resistance.

3.5.36 Soap dispenser assembly, unit 936. The soap dispenser assembly shall consist of a counter top mounted polished stainless steel or chrome finished spout base and spout, a soap reservoir, an exterior foot actuated pump, and interconnecting tubing. Other requirements for the soap dispenser shall be as specified herein.

3.5.37 Casters for sink unit 936. Four casters are required per sink unit. Casters shall be detachable, swivel type with 4 inch wheels being 3/4 inch wide. At least 2 for each sink shall have toe actuated brakes. If all casters do not

Source: https://assist.dla.mil -- Downloaded: 2026-10-21T11:47Z
Check the source to verify that this is the current version before use.

have brakes, then they shall be available as replaceable items separately (one with brakes, and one without brakes). Shall be a standard commercial caster manufactured by a nationally recognized manufacturer. Each caster shall be rated by the manufacturer for continuous operating load of, at least, 100 pounds.

3.6 Unit requirements. Each unit, except sink units 936, shall be provided with one (1) dedicated parts manual which shall list all replaceable parts with commercial source of supply (including name, address and phone number) and corresponding commercial Part Number. As appropriate with the complexity of the unit being addressed, the manual shall include illustrations indicating location of the parts on the unit and method by which the part is attached. The parts manual may be a single page of appropriate size. This requirement does not apply to sink unit 936 as its manuals are specified in 3.6.7.1.12.

3.6.1 Base section units 945, 931, 916, and 932. The base section cabinet units shall include four carrying handles (see 3.5.10) each with a hanger support; a pullboard (see 3.5.15); a top (see 3.5.16); a retaining bar staple centered above the toe space; four rear mounted retainer attachments; a retaining bar unit 913 (see 3.6.4 and 3.6.4.1); and 1/2 set hangers, unit 929 (see 3.6.5). Base section units shall maintain compatibility with previously procured counter units (see 1.2.1.5). Shall be as specified herein.

3.6.1.1 Individual requirements, units 945, 931, 916, and 932.

3.6.1.1.1 Cabinet, medicine, base section, 4 drawer, unit 945. Shall be a four-drawer, floor mounted, free-standing cabinet for storage of medical supplies. Drawer face height sizes shall consist of two 6 inch and two 9 inch drawers (see 3.5.11 and 3.5.12). In addition to components specified in 3.6.1, this unit shall include a casework assembly with an exterior bottom and two skid-rails (see 3.5.1).

3.6.1.1.2 Cabinet, medicine, base section, 5 drawer, unit 931. Shall be a five-drawer, floor mounted, free-standing cabinet for storage of medical supplies. Drawer face height sizes shall consist of five 6 inch drawers (see 3.5.11 and 3.5.12). In addition to components specified in 3.6.1, this unit shall include a casework assembly with an exterior bottom and two skid-rails (see 3.5.1) and a drawer partitionment set for each drawer (see 3.5.14).

3.6.1.1.3 Cabinet, Pharmaceutical, base section, unit 916. Shall be a four-drawer, floor mounted, free-standing cabinet for storage of pharmaceutical supplies. Drawer face height sizes shall consist of one 3 inch, one 6 inch, one 9 inch, and one 12 inch drawer (see 3.5.11 and 3.5.12). In addition to components specified in 3.6.1, this unit shall include a casework assembly with an exterior bottom and two skid rails (see 3.5.1).

3.6.1.1.4 Cabinet, cassette storage, unit 932. Shall be a floor mounted, free-standing cassette storage cabinet for storage of darkroom equipment set. The compartment configuration and sizes shall be in accordance with DPSC Sketch 25511-S. If the upper compartments are a replaceable sub-cabinet, then it shall

Source: https://assist.dla.mil -- Downloaded: 2026-10-21T11:47Z
Check the source to verify that this is the current version before use.

be fabricated of cold rolled steel. The material, construction, and finish of the sub-cabinet shall be as specified for "Casework, all cabinet units" (see 3.3.8). The interior sides, top, and bottom walls of the three upper compartments shall be smooth and flat. In addition to components specified in 3.6.1, the cassette cabinet unit shall include a casework assembly with an exterior bottom and two skid-rails (see 3.5.2), and a detachable front cover (see 3.5.28).

3.6.1.2 Common examination features, units 945, 931, 916, and 932.

3.6.1.2.1 Retainer attachments. As appropriate with alternative (see 3.6.4), the cabinet unit shall have four (4) retainer attachments affixed to the rear of the casework. Two (2) retainers shall be located toward each side of the rear, positioned one above the other, and mate with the locations of the retainer attachments on the upper section cabinets. The function of the retainer attachments is to provide a means of securing upper section cabinets to base section cabinets via retaining bars (unit 913). The retainer attachments also provide a place to stow a component retaining bar when the bar is not in use. The retainer attachments shall not protrude from the casework rear in excess of 3/4 inch. The requirements for retainer attachments shall be consistent with the specified alternatives in 3.6.4 covering the retaining bar.

3.6.1.2.2 Exterior bottom. The exterior bottom shall fully close the casework bottom and be attached via stainless steel (series 300) fasteners.

3.6.1.2.3 Skid-rails. There shall be two (2) skid-rails attached to the bottom of each unit. They shall be mounted on the front and rear bottom, flush with the casework edges, extending the full width of the casework. The skid-rails shall be secured via counter sunk fasteners.

3.6.1.2.4 Carrying handles and hanger support mounting. There shall be four (4) carrying handles and supports for hangers (unit 929) per base section cabinet. The carrying handles and hanger supports shall be paired in sets of one each. Each set shall be mounted in a common recess (as appropriate with alternatives in 3.6.3). The four carrying handles shall be mounted, two on the right side and two on the left side of the casework. The handles shall be positioned, all at the same height, and widely separated on each side of casework. The handle grip, when raised to the lifting position, shall be approximately 24 inches from the casework bottom. There shall be a hanger support mounted above and in line with each carrying handle. The hanger supports shall be approximately 27 inches from the casework bottom. The carrying handles shall be compatible with counter units 928 and 927. The hanger supports shall be compatible with hanger unit 929.

3.6.1.2.5 Staple, for retaining bar. As consistent with the specified alternatives in 3.6.4 covering the retaining bar, there shall be a staple attached to the casework. The staple shall be positioned on the cabinet's front vertical centerline, below the casework cavity and above the toe space. It shall mate with the slot in the bottom of the retaining bar and enable an installed bar to be secured to the casework bottom.

Source: https://assist.dla.mil -- Downloaded: 2026-10-21T11:47Z
Check the source to verify that this is the current version before use.

3.6.1.3 Common test features, unit 945, 931, 916, and 932.

3.6.1.3.1 Casework with top, load support. With the casework floor mounted in upright position, a casework with its top attached shall be capable of supporting 600 pounds distributed inside a 1 inch margin of the top's outside edges. Shall be capable of successful compliance with test procedure in 4.4.1.

3.6.1.3.2 Top, attachment of. The top shall be securely fastened to the casework. With the casework upright and held to a level floor, each corner of the top shall be capable of withstanding a lifting force of 75 pounds without causing damage to any part of the unit. Shall be capable of successful compliance with test procedure in 4.4.14.

3.6.1.3.3 Top flatness, support area of upper section units. The area on top of a base cabinet which supports an upper section cabinet shall be flat within 1/32 inch. Shall be capable of successful compliance with test procedure in 4.4.22.

3.6.1.3.4 Top, deflection under load. The top shall be capable of being loaded with 40 pounds per square foot without a deflection in excess of 1/200 of the span/space while loaded. Shall be capable of successful compliance with test procedure in 4.4.18.

3.6.1.3.5 Pullboard, load support. A pullboard, when fully extended, shall be capable of supporting 75 pounds evenly distributed on its work surface without being damaged or causing damage to the cabinet. Shall be capable of successful compliance with test procedure in 4.4.3.

3.6.1.3.6 Carrying handle and hanger support, attachment of. Each attachment of handle and hanger support to the casework, shall be capable of withstanding a pulling force of 150 pounds. Shall be capable of successful compliance with test procedure in 4.4.9.

3.6.1.3.7 Casework support area for hangers & counters, trueness. The area on the hanger support members which support hanger units 929 (and alternatively support counters directly) shall be true to a common plane. This trueness shall allow proper attachment of counter unit 928 or 927. The trueness of two hanger supporting surfaces on one side of a casework shall be within 1/32 inch of a straight line which passes over their support areas. The termination points of this straight line shall be the span of both support surfaces on one side of the cabinet unit. The two termination points shall be an equal distance from the floor within 1/8 inch. The position of these supporting surfaces shall be capable of successful compliance with test procedure in 4.4.25.

3.6.1.3.8 Stability. The cabinet, when mounted upright on a flat table, shall be stable and shall not have a rock in excess of 1/8 inch. Shall be capable of successful compliance with test procedure in 4.4.16.

Source: https://assist.dla.mil -- Downloaded: 2026-10-21T11:47Z
Check the source to verify that this is the current version before use.

3.6.1.3.9 Alternate hanger support for counters. Any alternate system for supporting counter units 928 and 927 shall include a feature which allows easy installation of counters. The system employed shall allow initial placement of base section cabinets/sink unit (from which counter units are to be supported) 3 inches further apart than the closest position possible after counters have been installed (i.e. flanges on counters could be mounted to counter via a captured 1-1/2 inch slip-joint). Shall be capable of successful compliance with test procedure in 4.4.32.

3.6.2 Upper section units 903 and 930. The upper section cabinet units shall include four carrying handles (see 3.5.10); door hinges (see 3.5.19 and 3.5.20); door catches (see 3.5.21); a staple for a military padlock; and two rear mounted retainer attachments. The retainer attachments shall be mounted on the rear of the casework. They shall be widely separated and mate with retainer attachments on the base section cabinets. The retainer attachments shall receive two retaining bar unit 913 and secure upper cabinet units to base cabinet units (unit 903 requires 2 base section cabinets). The installed bars and the retainer attachments shall not protrude from the rear of the casework in excess of 3/4 inch. Other requirements for the upper cabinets shall be as specified herein.

3.6.2.1 Individual unit requirements, units 903 and 930.

3.6.2.1.1 Cabinet, Pharmaceutical, upper section, unit 903. Shall be a 36 inch wide, 4 shelved (see 3.5.26), double door (see 3.5.17), upper section cabinet intended to rest on two base section cabinet units. At least three shelves shall be removable without use of tools. The remaining shelf shall also be removable, but its removal may require the use of small hand tools. The shelves shall be capable of being positioned an equal distance apart, one above the other. They shall collectively provide storage space for 20 boxes (unit 914) on the shelves plus 5 boxes below the bottom shelf. In addition, there shall be available, at least, three alternate shelf height positions which shall be midway between the positions described above. In addition to components specified in 3.6.2, this unit shall include a casework with bottom mounted strip padding material (see 3.5.3).

3.6.2.1.2 Cabinet, Pharmaceutical, upper section, unit 930. Shall be an 18 inch wide, 3 shelved (see 3.5.27), double door (see 3.5.18), upper section cabinet intended to rest on one base section cabinet. At least two shelves shall be removable without use of tools. The remaining shelf shall also be removable, but its removal may require the use of small hand tools. The shelves shall be capable of being positioned an equal distance apart, one above the other. They shall collectively provide storage space for 9 boxes (unit 914) on the shelves. In addition to components specified in 3.6.2, this unit shall include a casework with bottom mounted strip padding material (see 3.5.4); a retaining bar unit 913 (see 3.6.4 and 3.6.4.1); and a narcotics chest located in the bottom section. The narcotics chest shall be in accordance with MIL-C-20709, "Narcotic chests". The narcotics chest shall be fabricated of cold rolled steel. The material, construction, and finish of the chest shall be as specified for "Casework, all cabinet units" (see 3.3.2).

Source: https://assist.dla.mil -- Downloaded: 2026-10-21T11:47Z
Check the source to verify that this is the current version before use.

3.6.2.2 Common examination features, units 903 and 930.

3.6.2.2.1 Strip padding material. The padding shall be applied to the full width (side to side) and/or full depth (front to back) of the cabinet. There shall be at least two (2) strips positioned flush with opposing outside bottom edges of the cabinet. The exposed surface shall resist adhesion to a base section cabinet.

3.6.2.2.2 Carrying handles. Each unit shall have four (4) carrying handles. Two shall be mounted near the vertical centerline of each side (end panels) of the casework. The handles on each side shall be positioned one above (and aligned with) the other. The free hanging grip of the lower handle shall be approximately 4-1/2 inches above the bottom of the casework. The other free hanging grip shall be approximately 18-1/2 inches above the first.

3.6.2.2.3 Staple for military padlock. The staple anchorage shall be traceable by at least one straight line to the casework. It shall be positioned so that an installed military padlock shall engage the staple and each of the doors.

3.6.2.3 Common test features, units 903 and 930.

3.6.2.3.1 Casework, load support. The casework shall be capable of supporting 500 pounds without being damaged. Shall be capable of successful compliance with test procedure in 4.4.2.

3.6.2.3.2 Strip padding material, peel and breaking strength. The removal of applied strip padding shall require at least 6 pounds per inch of width (width of strip padding material to nearest 1/8 inch), of a peel force applied at 90 degrees from the cabinet bottom. The breaking strength of the strip material shall be at least 15 pounds. Shall be capable of successful compliance with test procedure in 4.4.26.

3.6.2.3.3 Strip padding material, scratching and rubbing. The strip padding material shall be applied to the bottom of upper units in order to protect the tops of base units from being scratched or otherwise permanently marked. An upper unit, loaded with 100 pounds, and put in motion across the surface of a base unit, shall not permanently mark the top of the base cabinet. Installed strip padding material, subjected to these forces, shall not become dislocated. Shall be capable of successful compliance with test procedure in 4.4.27.

3.6.2.3.4 Carrying handle, attachment of, pulling. Attachment of each handle to the casework shall be capable of withstanding a pulling force of 150 pounds. Shall be capable of successful compliance with test procedure in 4.4.9.

3.6.2.3.5 Shelf, warpage. A shelf shall not have a noticeable warp. No one corner shall be out of a plane, established by the remaining 3 corners, by more than 3/32 inch. Shall be capable of successful compliance with test procedure in 4.4.4.

Source: https://assist.dla.mil -- Downloaded: 2026-10-21T11:47Z
Check the source to verify that this is the current version before use.

3.6.2.3.6 Shelf, concentrated center load. A shelf, supported by its normal support surfaces, shall be capable of supporting 30 pounds of center concentrated load applied across the centerline between the two supporting surfaces. The shelf shall not deflect more than 1/16 inch while supporting this load. This loading shall not cause permanent deflection or otherwise damage the shelf. Shall be capable of successful compliance with test procedure in 4.4.5.

3.6.2.3.7 Door, torsion. A dismounted door shall be capable of withstanding a torsion load of 50 pounds placed at its upper left and lower right corners (25 pounds each corner). When so loaded, the door shall be supported on a 1 inch wide support beam running between the adjacent corners. The door shall support this same loading when the load corners and support corners are switched. Shall be capable of successful compliance with test procedure in 4.4.19.

3.6.2.3.8 Door, contort pull. A mounted door on an anchored cabinet, partially opened and having the lower corner (opposite lower hinge) anchored, shall be capable of withstanding a 50 pound pulling force applied at the top outside corner attempting to open the door further. This loading shall not cause permanent deflection or damage to any part of the cabinet. Shall be capable of successful compliance with test procedure in 4.4.11.

3.6.2.3.9 Door staple, pulling. The installed staple for the military padlock, with the doors removed, shall be capable of withstanding a pulling force of 85 pounds without causing damage to any part of the cabinet. Shall be capable of successful compliance with test procedure in 4.4.12.

3.6.2.3.10 Locked door, pulling. A cabinet, with doors mounted and locked with a military padlock, shall be capable of withstanding a 200 pound pulling force applied to the padlock (horizontal pull away from cabinet front). This force shall not cause damage to any part of the cabinet other than possibly the staple and staple support members. It shall not cause damage to the casework or permanently attached components. The allowed damage shall not exceed that which a layman is capable of repairing to a usable condition using a hammer, block and small hand tools only. The cabinet shall be capable of being repaired to as new condition by replacing/repairing only the staple and staple support members. Shall be capable of successful compliance with test procedure in 4.4.13.

3.6.2.3.11 Door catch, tilt and jolt cabinet. The catch shall hold the cabinet door closed against an opening force created by tilting the top surface of the cabinet forward at a 10 degree angle away from horizontal. The catch shall remain effective when the force is increased by jolting the cabinet. The jolting force shall equal a 1 pound natural rubber weight free-falling 12 inches onto the cabinet's rear top edge. Shall be capable of successful compliance with test procedure in 4.4.29.

3.6.2.3.12 Stability. The cabinet, when mounted upright on a flat table, shall be stable and shall not have a rock in excess of 1/8 inch. Shall be capable of successful compliance with test procedure in 4.4.16.

Source: https://assist.dla.mil -- Downloaded: 2026-10-21T11:47Z
Check the source to verify that this is the current version before use.

3.6.3 Box, plastic, unit 914. Shall be a plastic box for use as a storage bin in upper section cabinet units 903 and 930 (see 3.3.4). Shall include a sliding lid and have a molded slot on the front which shall capture a content identification card. Other requirements shall be as specified herein.

3.6.3.1 Test feature, tension, unit 914. The box shall be resilient. When lidless, it shall be capable of withstanding a tension force of 20 pounds, pulling the two top side edges together. Shall be capable of successful compliance with test procedure in 4.4.15.

3.6.4 Bar, retaining, base cabinet, steel, unit 913. The bar shall be a retaining bar serving 3 functions as follows:

a. Secure one upper section unit 903 to two base section units, or one upper section unit 930 to one base section unit during usage (see 1.2.1.4).

b. Secure drawers of drawered units 945, 931, and 916 closed during storage.

c. Secure front cover of cassette storage unit 932 in place during storage.

This bar unit may be eliminated from the cabinetry system and/or its elements may be reordered as permanent and/or replaceable parts/subassemblies of base section cabinet units 945, 931, 916, 932, and upper section cabinets units 903 and 930 provided the bar's functions, durability, and relative simplicity are maintained. In any event, the specified maximum weight for units 945, 931, 916, 932, 903 and 930 shall not be altered, nor shall these units have unsecured components. The bar, as a separate unit, shall be an assembly having no unsecured parts. The top end of the bar shall be capable of being captured by the underside of a base cabinet's top (see 3.5.16). The bottom of the bar shall be capable of being captured by base cabinet's staple located above the toe space (see 3.5.1 and 3.5.2). The bar shall be furnished with a 3/16 inch diameter self-locking, quick disconnect pin and pull ring. This pin and pull ring shall be attached to the bar via a 4 inch long flexible stainless steel wire rope. The quick disconnect pin and wire rope associated parts shall be fabricated of corrosion resistant steel or metal treated for corrosion resistance. Other requirements for the bar shall be as specified herein.

3.6.4.1 Test feature, load tests, bar unit 913. The bar shall be capable of supporting 30 pounds of concentrated load without deflecting more than 1/16 inch or being permanently deformed. The wire rope and its attachment shall be capable of supporting 100 pounds stretched 90 degrees over a 3/4 inch diameter rod without being kinked or otherwise damaged. Shall be capable of successful compliance with test procedure in 4.4.6.

Source: https://assist.dla.mil -- Downloaded: 2026-10-21T11:47Z
Check the source to verify that this is the current version before use.

3.6.5 Hanger, work counter, box of 4, unit 929. Shall be a set of 4 hangers serving one function. The function shall be to provide three elevations by which two counter units, either 928 or 927, may be simultaneously suspended from a combination of two base section cabinets and/or sink unit. One elevation shall have the counter work surface even with the top of base section units. A second elevation shall have the counter work surface at desk height of approximately 27-1/2 inches above the bottom of the supporting cabinets and the third elevation shall have the counter work surface approximately 11 inches above the bottom of the supporting cabinets. This unit, a set of 4 hangers, may be eliminated from the cabinetry system and/or its elements may be reordered as permanent and/or replaceable parts/subassemblies of base section units 945, 931, 916, 932, and sink unit 936, and counter units 928 and 927 provided the hanger's function, durability, and relative simplicity are maintained. In any event, the specified maximum weight for units 945, 931, 916, 932, 936, 927, or 928 shall not be altered, nor shall units 928 or 927 have unsecured components. One acceptable alternative would be to have 4 hanger supports per casework side (in lieu of 2) plus 2 hanger supports per top side edge so located that the hanger supports become counter supports (eliminating the hanger supports), providing the specified elevations for the attachment of the counters. This could be accomplished utilizing either one elongated recess per set of carrying handle and hangers (2 recesses per cabinet side) or multiple recesses per set of carrying handle and hangers. Individual hangers shall not have unsecured components. Other requirements for the the set of hangers shall be as specified herein.

3.6.5.1 Test features, load support, hanger unit 929. One set of four hangers shall be capable of supporting one counter unit evenly loaded with 600 pounds. Shall be capable of supporting this loading from any support elevation. This loading shall not cause damage to the the hangers. Shall be capable of successful compliance with test procedure in 4.4.7.

3.6.5.2 Alternate hanger support for counters. Any alternate system for supporting counter units 928 and 927 shall include a feature which allows easy installation of counters. The system employed shall allow initial placement of base section cabinets/sink unit (from which counter units are to be supported) 3 inches further apart than the closest position possible after counters have been installed (i.e. flanges on counters could be mounted to counter via a captured 1-1/2 inch slip-joint). Shall be capable of successful compliance with test procedure in 4.4.32.

3.6.6 Counter units 928 and 927. The work counters shall be a counter for use as work or storage space when attached to two base section cabinets and/or sink unit. Shall be compatible with the handles and hanger support members of units 945, 931, 916, 932 and 936. Shall also be compatible with hanger unit 929.

3.6.6.1 Individual requirements, units 928 and 927.

3.6.6.1.1 Counter, work, medical cabinet, 36 inch, unit 926. Shall be as specified herein.

Source: https://assist.dla.mil - Downloaded: 2026-10-21T11:47Z
Check the source to verify that this is the current version before use.

3.6.6.1.2 Counter, work, medical cabinet, 48 inch, unit 927. Shall be as specified herein.

3.6.6.2 Common examination features, units 928 and 927. Shall be provided with two 3/4 inch drop flanges at each side (total of 4) which shall be capable of capturing the carrying handles and/or hanger support members of base section cabinets and sink unit. The drop flanges shall also be capable of capturing the support surfaces of hanger units. The material, construction, and finish of the drop flanges shall be as specified for bar and hanger (see 3.3.5). The counter shall have no unsecured components.

3.6.6.3 Common test features, units 928 and 927.

3.6.6.3.1 Load support, top. The counter shall be capable of supporting 600 pounds evenly distributed within a 1 inch margin on its work surface. This loading shall not cause damage to the counter. Shall be capable of successful compliance with test procedure in 4.4.7.

3.6.6.3.2 Warpage. A counter shall not have a noticeable warp. No corner shall be out of a plane which is established by the remaining three corners, by more than 1/16 inch. Shall be capable of successful compliance with test procedure in 4.4.23.

3.6.6.3.3 Support surface trueness. The support surfaces on the four drop flanges by which the counter hangs shall have an overall trueness (with respect to a common plane) within 1/16 inch. That is, no area of any support surface shall be more than 1/16 inch away from a plane established by either the three high points or the three low points (one point per flange on any set of three flanges). Also, no one flange shall be more than 1/32 inch out of parallel with a common plane. That is, a support surface of a flange which contacts any common plane as described above, shall not have any portion of its support surface further than 1/32 inch away from that plane. The individual support surfaces of the flanges shall be flat and free of bumps. The counter shall be capable of successful compliance with test procedure in 4.4.24.

3.6.7 Sink unit, scrub, field hospital, unit 936. Shall be a field hospital scrub sink unit. The unit shall include a casework assembly with insulated platform(s), recessed areas in rear panel, an exterior bottom and two skid-rails (see 3.5.5); a pair of access doors to compartment under sink (see 3.5.23); door hinges (see 3.5.24); door latch (see 3.5.25); four recessed carrying handles with hanger support members (see 3.5.10); water heater (see 3.5.30); Motor and pump with captive air tank (see 3.5.31); power supply cord (see 3.5.32); power supply inlet (see 3.5.33); top with sink bowl (see 3.5.34); installation tools (see 3.5.35); soap dispenser (see 3.5.36); four casters (see 3.5.37); replaceable plumbing parts (see 3.5.29 thru 3.5.29.17); 1/2 set (2 pieces) hangers, unit 929 (see 3.6.5); and manuals/instructions. The unit shall be mobile and self contained. Elements of the sink unit which are required to be available as replaceable parts/subassemblies shall not be permanently attached.

Source: https://assist.dla.mil -- Downloaded: 2026-10-21T11:47Z
Check the source to verify that this is the current version before use.

Any element permanently attached need not be available as a replaceable item. Elements which are not permanently attached but are required to adapt the unit to its intended usage shall be available as replaceable parts/subassemblies. Other requirements for the sink unit shall be as specified herein.

3.6.7.1 Examination features, unit 936.

3.6.7.1.1 Casework. The casework for the sink unit shall include dedicated brackets/receptacles for stowing each loose part/subassembly which is not normally attached or connected to the sink unit when it is installed and operational. An exception to requirement of dedicated bracket/receptacle is the 1/2 set (2 pieces) of hangers, unit 929, which shall be separately stowed. These brackets/receptacles shall be either permanently attached or available as replaceable parts/subassemblies.

3.6.7.1.2 Exterior bottom. The exterior bottom shall fully close the casework bottom and be attached via stainless steel (series 300) fasteners.

3.6.7.1.3 Skid-rails. There shall be two (2) skid-rails attached to the bottom of each unit. They shall be mounted on the front and rear bottom (or alternately, mounted on bottom side edges), flush with the casework edges, extending the full width (or alternately, full depth) of the casework. The skid-rails shall be secured via counter sunk stainless steel (series 300) fasteners.

3.6.7.1.4 Carrying handles and hanger support mounting. There shall be four (4) carrying handles and supports for hangers (unit 929) per base section cabinet. The carrying handles and hanger supports shall be paired in sets of one each. Each set shall be mounted in a common recess (as appropriate with alternatives in 3.6.5). The four carrying handles shall be mounted, two on the right side and two on the left side of the casework. All handles shall be positioned at the same height and widely separated on each side of casework. The handle grip, when raised to the lifting position, shall be approximately 24 inches from the casework bottom. There shall be a hanger support mounted above and in line with each carrying handle. The hanger supports shall be approximately 27 inches from the casework bottom. The carrying handles shall be compatible with counter units 928 and 927. The hanger supports shall be compatible with hanger unit 929.

3.6.7.1.5 Metal pipes and fittings. All metal pipes and metal pipe/hose/tubing fittings shall be corrosion resistant steel or metal treated for corrosion resistance.

3.6.7.1.6 Grommets. Rubber grommets or equal shall be used wherever dissimilar metals are connected within the plumbing system.

3.6.7.1.7 Sound deadening, top and sink bowl underside. The underside of the top and sink bowl shall be coated with a sound deadening material which shall withstand normal usage and storage.

Source: https://assist.dla.mil -- Downloaded: 2026-10-21T11:47Z
Check the source to verify that this is the current version before use.

3.6.7.1.8 Reservoir, soap dispenser. There shall be convenient access to replenish soap in the reservoir.

3.6.7.1.9 Cabinet exterior surface. All exterior components, intended to be connected during usage, or normally attached, shall be recessed mounted or flush mounted. There shall be no protrusions from a disconnected cabinet's front, sides, or rear.

3.6.7.1.10 Electrical requirements. In addition to requirements of this specification, electrical requirements shall be in accordance with DPSC-DEPMEDS-AT(DM).

3.6.7.1.11 Provisioning. In addition to the requirements of this specification, the sink unit shall be provisioned in accordance with DPSC-DEPMEDS-AT(DM). The contract data requirements list contained in the appendix of DPSC-DEPMEDS-AT(DM) shall be limited to the following sequence numbers:

A001 - Short form provisioning parts list.
A004 - Tools and test equipment list.
A005 - Commercial maintenance manual (see 3.6.7.1.13).
A006 - Commercial operating instruction manual (see 3.6.7.1.13).
A009 - Supplementary provisioning technical documentation.
A011 - Design change notice.
A014 - Consumable/durable item list.

3.6.7.1.12 Manuals. Operating, instruction, service and maintenance manuals shall be provided in accordance with DPSC-DEPMEDS-AT(DM) and as specified herein. Manuals which are provided with the sink unit shall be stowed in dedicated compartment(s) inside the casework.

3.6.7.1.13 Labels, for installer/warning labels and controls. Information provided by labels intended for use by installer and/or user shall be appropriately accessible. In the event that a label on a contractor procured component is not positioned for easy reading by installer/user (as directed to) and provides required information, it shall be repositioned for easy reading or its information shall be reprinted at an appropriate location either within the cabinet or within the specified manual(s). All warning labels which are applicable to safety shall be within easy view for reading or a duplicate shall be provided at an appropriate location. Controls which are intended for use by installer shall be positioned for easy access by installer.

3.6.7.2 Test features, unit 936.

3.6.7.2.1 Casework with top, load support. With the casework floor mounted in upright position, a casework with its top attached shall be capable of supporting 600 pounds distributed inside the marine edging and back-splash of the top. Shall be capable of successful compliance with test procedure in 4.4.1.

Source: https://assist.dla.mil -- Downloaded: 2026-10-21T11:47Z
Check the source to verify that this is the current version before use.

3.6.7.2.2 Top, attachment of. The top shall be securely fastened to the casework. With the casework upright and held to a level floor, each corner of the top shall be capable of withstanding a lifting force of 75 pounds without causing damage to any part of the unit. Shall be capable of successful compliance with test procedure in 4.4.14.

3.6.7.2.3 Top, resistance to reagents. The sink top and bowl shall be capable of successful compliance with test procedures for "Resistance of sink to reagents", MIL-C-20709.

3.6.7.2.4 Carrying handle and hanger support, attachment of. Each attachment of handle and hanger support to the casework, shall be capable of withstanding a pulling force of 150 pounds. Shall be capable of successful compliance with test procedure in 4.4.9.

3.6.7.2.5 Casework support area for hangers & counters, trueness. The area on the hanger support members which support hanger units 929 (and alternatively support counters directly) shall be true to a common plane. This trueness shall allow proper attachment of counter unit 928 or 927. The trueness of two hanger supporting surfaces on one side of a casework shall be within 1/32 inch of a straight line which passes over their support areas. The termination points of this straight line shall be the span of both support surfaces on one side of the cabinet unit. The two termination points shall be an equal distance from the floor within 1/8 inch. The position of these supporting surfaces shall be capable of successful compliance with test procedure in 4.4.25.

3.6.7.2.6 Door, torsion. A dismounted door shall be capable of withstanding a torsion load of 50 pounds placed at its upper left and lower right corners (25 pounds each corner). When so loaded, the door shall be supported on a 1 inch wide support beam running between the adjacent corners. The door shall support this same loading when the load corners and support corners are switched. Shall be capable of successful compliance with test procedure in 4.4.19.

3.6.7.2.7 Door, contort pull. A mounted door on an anchored cabinet, partially opened and having the lower corner (opposite lower hinge) anchored, shall be capable of withstanding a 50 pound pulling force applied at the top outside corner attempting to open the door further. This loading shall not cause permanent deflection or damage to any part of the cabinet. Shall be capable of successful compliance with test procedure in 4.4.11.

3.6.7.2.8 Stability. The cabinet, when mounted upright on a flat table (castors removed), shall be stable and shall not have a rock in excess of 1/8 inch. This rock shall not exceed 3/16 inch with casters mounted. Shall be capable of successful compliance with test procedure in 4.4.16.

3.6.7.2.9 Water burst, leakage. All plumbing parts/subassemblies in the path of supply water shall be capable of withstanding the maximum water pressure that the system is capable of inducing, and/or the pressure induced into the system by connecting the water to a supply pressure of 70 psi. These pressures shall not

Source: https://assist.dla.mil -- Downloaded: 2026-10-21T11:47Z
Check the source to verify that this is the current version before use.

cause any item to burst or otherwise to become damaged. The water system shall be capable of continuous operation when connected to a water supply of 50 psi without leaking or otherwise being damaged. The plastic pipe connections shall be capable of being leak proof tightened by hand without use of tools. Shall be capable of successful compliance with test procedure in 4.4.30.

3.6.7.2.10 Supply hose assembly, leakage. The supply hose assembly shall be capable of withstanding a pressure of 70 psi without bursting or otherwise being damaged. It shall also be capable of continuous operation with supply pressure of 50 psi without leaking or otherwise being damaged. Shall be capable of successful compliance with test procedure in 4.4.30.

3.6.7.2.11 System flow control, for temperature control. A single control within the unit's cabinet shall enable an installer to set the system maximum flow rate of hot water at a desired setting within the range from 1/2 to 2 gallons per minute in order to obtain optimum flow rate with respect to available water temperature rise. After any maximum flow rate (within the specified range) has been set, it shall remain constant (± 15 percent of obtained maximum flow rate) so long as the exterior water supply pressure remains constant within 5 percent (i.e. The maximum available flow rate at the faucet shall remain constant over an indefinite time period and after unit is disconnected and reconnected to same water and power source). Other controls, including pressure and temperature, shall be compatible with this requirement. Shall be capable of successful compliance with test procedure in 4.4.31.

3.6.7.2.12 Heater output. The water heater shall be rated 4000 watts at 240 volts. The heater shall be operational with water flow rates over the range from 1/2 to 2 gallons/minute. The heater shall be prevented from outputting heat if the water temperature is in excess of 150° F. When the sink unit is operated in an ambient temperature which is equal to the external water supply temperature, the sink unit shall be capable of providing Actual Water Temperature Rise (AWTR) as follows:

Expected Water Temperature Rise	= EWTR	in Fahrenheit degrees.
Actual Water Temperature Rise	= AWTR	derived from measurement.
Actual Water Flow Rate	= AWFR	as measured in GPM.
Actual Voltage	= AV	as measured.
Constant factor	= K	= 0.000460.
EWTR	= (K * AV * AV / AWFR) - 1	(see 6.5)
AWTR	=> EWTR	

The sink unit shall be capable of successful compliance with test procedure in 4.4.31.

3.6.7.2.13 Thermostat range and accuracy. The hot water thermostat shall be capable of being set between 80 degrees and 120 degrees F. It shall maintain water temperature within 2 degrees of setting. It shall prevent water from being heated beyond 150 degrees F. The thermostat shall be capable of successful compliance with test procedure in 4.4.33.

Source: https://assist.dla.mil -- Downloaded: 2026-10-21T11:47Z
Check the source to verify that this is the current version before use.

3.6.7.2.14 Pump, flow rate. The pump and motor shall be capable of providing a flow rate of 2 gallons per minute. The unit shall be capable of pumping 2 gallons per minute from a negative external supply pressure of 20 ft. water. Shall be capable of successful compliance with test procedure in 4.4.34.

3.6.7.2.15 Alternate hanger support for counters. Any alternate system for supporting counter units 928 and 927 shall include a feature which allows easy installation of counters. The system employed shall allow initial placement of base section cabinets/sink unit (from which counter units are to be supported) 3 inches further apart than the closest position possible after counters have been installed (i.e. flanges on counters could be mounted to counter via a captured 1-1/2 inch slip-joint). Shall be capable of successful compliance with test procedure in 4.4.32.

3.6.8 Table, folding legs, unit 937. Shall be a folding leg table for use as a utility table with the deployable cabinetry system. The table shall include a stainless steel top (see 3.3.7) and an under carriage (see 3.3.8). The table top and edges thereof shall be reinforced with a solid maple wood framework wrapped on three sides by the stainless steel top. The top shall wrap the wood frame's top, outside edge, and a portion of the bottom. The underside of the top, including the wood frame, shall be coated with a sound deadening material. The top shall have a reinforcing skirt attached to its bottom. The table shall be provisioned with quick leg folding mechanism(s) which shall lock the legs and folding components in either position. The folding mechanism(s) shall be capable of being operated by a single motion applied to a tubular handle. When folded, there shall be no element protruding below the skirt. Threaded fasteners shall not be employed at pivot locations. Pivot locations shall employ thrust washers which shall oppose all thrust bearing surfaces. Crimping of rods/pins shall not be employed as a method of positioning thrust washers. Other requirements for the table shall be as specified herein.

3.6.8.1 Test features, table, unit 937.

3.6.8.1.1 Load support and stability. The erected table shall be sturdy. When the table is erected, the table top shall be capable of supporting 400 pounds evenly distributed. When so loaded, a horizontal force of 50 pounds applied to any one top edge shall not move the top horizontally in excess of 1 inch (with feet of legs anchored). Shall be capable of successful compliance with test procedure in 4.4.8.

3.6.8.1.2 Top, deflection under load. The top shall be capable of supporting 90 pounds, distributed over a centered one square foot area without deflecting the center of the top in excess of 3/32 inch. Shall be capable of successful compliance with test procedure in 4.4.20.

3.6.8.1.3 Top, resistance to reagents. The table top shall be capable of successful compliance with test procedures for "Resistance of sink to reagents", MIL-C-20709.

Source: https://assist.dla.mil -- Downloaded: 2026-10-21T11:47Z
Check the source to verify that this is the current version before use.

3.7 Engineering drawings and associated lists.

3.7.1 Scope. Engineering drawings shall be complete and associated lists shall be provided. The drawings and associated lists shall completely describe the units herein, as delivered and accepted. Shall be level three production drawings and associated lists. Shall enable a future third party manufacturer of these type of units to fabricate interchangeable units (interchangeable with the units fabricated and accepted under this contract) without resource of knowledge concerning the units other than the engineering drawings and associated lists. The completeness of the drawings and associated lists shall be such that units fabricated in accordance with the drawings and associated lists shall be capable of being in strict compliance with requirements of this specification (see 3.7.2.4). Level one and level two drawings are not required.

3.7.2 Design.

3.7.2.1 Design of units. The design of each unit shall be in accordance with DPSC Sketch 25511-S and the functional requirements of this specification. All deviations from specifications herein shall be delineated in a cover letter accompanying the offeror's offer. (This requirement is in addition to requirements in paragraph 3.7.3.6.) Each delineation shall cite the paragraph number for which it applies. To the extent practical, the drawings and associated lists shall maximize alternative methods of fabricating individual parts. The drawings, excluding references to alternate methods of fabrication, shall describe the elements as fabricated and delivered under this contract. That is, if the contractor is extruding a part that could be interchangeable with a cast part as an acceptable alternative method of fabrication, then the drawings should illustrate the part as an extrusion and, at least, cite casting as an acceptable alternative with complete description of material and method of fabrication, including Industrial/Federal/Military designations. To the extent practical, the drawings and/or associated lists shall not restrict a unit, assembly, subassembly and/or part to a single source of availability. The drawings and associated lists, excluding references to alternative material, shall describe the materials used as applicable to units fabricated under this contract.

3.7.2.2 Design of sheet metal parts. Sheet metal parts which are intended to be fabricated from two or more joined sheets (of which one or more are intended to be pre-bent) shall be treated as assemblies (of pre-joined sheet metal parts) with a notation that the method of assembly is for guidance, and not intended to be restrictive. The notation shall state that other methods of fabricating the elements into a single part are acceptable (see 1.5, definition of "part"). This notation shall not apply to units manufactured under this contract. The drawings and associated lists, excluding references to alternative methods, shall describe the method of fabricating sheet metal parts as they are fabricated under this contract.

3.7.2.3 Design, generic requirement. The specified design of the cabinetry system is generic. The drawings shall render the design generic with no rights

Source: https://assist.dla.mil -- Downloaded: 2026-10-21T11:47Z
Check the source to verify that this is the current version before use.

owned and/or assignable to any party other than the Government. There shall be no financial allowance by the Government for offeror's/contractor's expenditure(s) involving exploratory development, advanced development, engineering development, and/or prototype production. The drawings and associated lists shall not be proprietary.

3.7.2.4 Integrity of drawings and associated list. Should it be found within three (3) years after final acceptance of drawings and associated list that units produced/manufactured in strict accordance with the drawings and associated list do not comply with functional and/or test requirements as specified herein, then the contractor shall further update the drawings and associated list as a requirement of this contract (see 1.4). Such update/correction shall be accomplished within 45 days after notification by the Government to the contractor delineating the deficiency. This requirement is in addition to any warranty provision which may exist with respect to this contract. This requirement does not restrict the warranty provision that exists.

3.7.3 Preparation of drawings and associated lists.

3.7.3.1 Number and type of drawings. The number and type of individual drawings and associated lists shall be left to the ingenuity of the contractor within the bounds of this specification. Two proofed sets of level 3 engineering drawings is an end item and the drawings being purchased by this contract (see DOD-STD-100).

3.7.3.2 Drawing and associated list format. In addition to the requirements of this specification, the drawings and associated lists format shall be in accordance with DOD-STD-100 and DOD-D-1000, except metric system is not required. The English system of measurements is acceptable.

3.7.3.3 Drawing and associated list changes. Drawing and associated list shall be updated, reflecting all changes through the last unit of production and inspection. Final drawings and associated lists shall be fully proofed. The only exception to the requirement that the drawings be fully proofed are as follows:

a. Drawings of, and references to, units not requisitioned in this contract.

b. Alternative methods of fabrication and alternative materials delineated in the drawings and associated lists as per 3.7.2.1 and 3.7.2.2.

3.7.3.4 Drawing and associated list submittal. The drawings and associated lists shall be prepared in accordance with DOD-D-1000 (metric system not required) and submitted for approval in accordance with the attached DD Form 1423, covering Data Item Description (DID) DI-E-7031. Drawings and associated lists shall be delivered in accordance with the attached DD Form 1423.

Source: https://assist.dla.mil -- Downloaded: 2026-10-21T11:47Z
Check the source to verify that this is the current version before use.

Information Handling Services DODSTD Issue 95-03

3.7.3.5 Drawings and associated lists, review and acceptance. The drawings and associated lists submitted as preliminary and submitted for review of current changes shall be returned to the contractor, with comment(s), within 30 days after receipt. The contractor shall not submit drawings and/or associated lists for review while the Government is in the process of reviewing a prior submittal. Drawings and associated lists submitted for review shall incorporate previous comments. Upon contractor receipt of comments from the Government, the contractor shall revise the drawings and associated lists as appropriate with comments, and any new data/changes found to be applicable. The contractor shall resubmit the newly revised drawings and associated lists (with clear notations of all changes since the previous submittal) within 30 days after receipt. Final submittal of drawings and associated lists for review purpose shall be timely to allow application of final comments to be incorporated with the drawings and associated lists which are submitted for acceptance. Drawings and associated lists submitted for acceptance shall be capable of successful compliance with the procedure in 4.5. All submittals of drawings and associated lists shall include a certificate of compliance (see 4.1.1.2.2).

3.7.3.6 Compliance with offered sketches and data. The drawings and associated lists shall be in compliance with the final offered sketches and data as required by the specification section of the procurement document. At award, the sketches and data shall combine with, and form a part of, the contract. Subsequent to award, any part of the sketches and/or data which is found to be deficient in selection of material, shape, and/or method (as delineated in the procurement document), and/or renders the end item(s) incapable of being in conformance with this specification, shall be revised in accordance with the procurement document. In any event, the end items shall be in strict compliance with this specification.

3.8 Identification marking. Each unit shall be permanently and legibly marked with the contract or purchase order number, the contractor's name, the National Stock Number (NSN), and the unit's name. The unit's name shall be the first two words (including the comma and space) listed under "Description" for the respective units listed in 1.2.1.1, "Identification of units". These markings shall be applied in accordance with MIL-STD-130 as appropriate for permanency being the expected life of the unit. Units 945, 931, 916, 932, 903, 930, and 936 shall be marked on the right hand side (facing cabinet) of the casework, upper forward area. Units 928 and 927 shall be marked on the underside, on a flat surface of a reinforcement member. Other units shall be marked on a flat surface at a location easily found.

3.9 First article inspection. A first article sample for each unit procured by this contract shall be inspected at source by the contractor in accordance with clause I 15. Government representatives shall be present during these inspections. The contractor shall give at least 21 days notice of inspection date(s) to the contracting officer before date(s) of first article inspections. The samples shall be in strict conformance with specifications. Accepted first article samples shall be held at source until the last item is accepted. First

Source: https://assist.dla.mil -- Downloaded: 2026-10-21T11:47Z
Check the source to verify that this is the current version before use.

article inspections shall be in accordance with the quality assurance provisions in section 4 and as specified herein. The contractor shall provide all necessary equipment required for the performance of first article inspection.

4. QUALITY ASSURANCE PROVISIONS

4.1 Responsibility for inspection. Unless otherwise specified in the contract or purchase order, the contractor is responsible for the performance of all inspection requirements (examination and tests) as specified herein. Except as otherwise specified in the contract or purchase order, the contractor may use his own or any other facilities suitable for the performance of the inspection requirements specified herein, unless disapproved by the Government. The Government reserves the right to perform any of the inspections set forth in the specification where such inspections are deemed necessary to assure supplies and services conform to prescribed requirements.

4.1.1 Responsibility for compliance. All items shall meet all requirements of sections 3 and 5. The inspection set forth in this specification shall become a part of the contractor's overall inspection system or quality program. The absence of any inspection requirements in the specification shall not relieve the contractor of the responsibility of ensuring that all products or supplies submitted to the Government for acceptance comply with all requirements of the contract. Sampling in quality conformance does not authorize submission of known defective material, either indicated or actual, nor does it commit the Government to acceptance of defective material.

4.1.1.1 Records. Records of examinations and tests performed by or for the contractor shall be maintained by the contractor and made available to the Government, upon the Government's request, at any time, or from time to time, during the performance of the contract and for a period of 3 years after delivery of the supplies to which such records relate.

4.1.1.2 Noncompliance. If a sample fails to pass inspection, the manufacturer shall notify the qualifying activity and the cognizant inspection activity of such failure and take corrective action on the material or processes, or both, as warranted, and on all units of product which can be corrected and which were manufactured with essentially the same materials and processes, and which are considered subject to the same failure. Acceptance and shipment of the product shall be discontinued until corrective action, acceptable to the qualifying activity has been taken. After the corrective action has been taken, inspection shall be repeated on additional sample units (all tests and examinations, or the test which the original sample failed, at the option of the qualifying activity). Final acceptance and shipment shall be withheld until inspection has shown that the corrective action was successful. In the event of failure after reinspection, information concerning the failure shall be furnished to the cognizant inspection activity and the qualifying activity.

Source: https://assist.dla.mil -- Downloaded: 2026-10-21T11:47Z
Check the source to verify that this is the current version before use.

Information Handling Services DODSTD Issue 95-03

4.1.1.3 Certificate of compliance.

4.1.1.3.1 Certificate of compliance, units. The contractor shall have available for inspection, a certificate of compliance that the required examinations and tests have been performed and that the units are in compliance with specifications.

4.1.1.3.2 Certificate of compliance, drawings and associated list. The contractor shall have available, for inspection, a certificate of compliance that the drawings and associated lists, at completed stages (submitted for review), were prepared in accordance with specifications. The contractor shall certify that drawings and associated lists, submitted for final acceptance were prepared in accordance with specifications. Further, the contractor shall certify that final drawings submitted for acceptance fully and accurately describe units as delivered and accepted.

4.1.2 Inspection. Inspection, as used in this specification, is defined as both examination (such as visual, or auditory, investigation without the use of special laboratory appliances or procedures) and testing (determination by technical means of physical and chemical properties) of the item.

4.1.3 Destructive and/or degradative tests. Units offered for tests which involve planned destruction and/or degradation of replaceable parts/subassemblies shall be provided with appropriate replacement parts/subassemblies to allow the test unit to be reconditioned as a new unit.

4.1.3.1 Destruction of strip padding material. Peel and breaking strength, strip padding material is a destructive test (see 4.4.26). Units offered for this test shall be provided with adequate replacement materials, and shall be reconditioned to as new after completion of the test.

4.1.3.2 Degradation of drawer bearings, cycling test. Cycling test, opening and closing drawer (see 4.4.21), is a degradation test. Units offered for this test shall be provided with at least replacement roller bearings and drawer catch. After performance of the second testing as specified in 4.4.10 (which follows test 4.4.21) at least the roller bearings and drawer catch (if a component) shall be replaced without inspection. After bearing replacement, the drawer shall be retested a third time in accordance with 4.4.10 to determine if the unit is in new condition. If the third test does not meet the requirements of a new unit, the appropriate replaceable parts/subassemblies shall be replaced. Then the drawer shall be retested a fourth and final time to determine if the unit is reconditioned as new. In any event, a unit found to be defective during the fourth test in accordance with 4.4.10 shall not be reconditioned. A reconditioned unit which does not meet the requirements of 4.4.10 as a new unit shall be rejected. This rejection is a defect ("A test cycled drawer shall be capable of being reconditioned to as-new requirements.", 3.5.12.1.3).

4.1.3.3 Allowed degradation of padlock staple and support member. Pulling test, locked door (see 4.4.13) permits damage to the padlock staple and replace-

Source: https://assist.dla.mil -- Downloaded: 2026-10-21T11:47Z
Check the source to verify that this is the current version before use.

able components supporting the staple. All damaged components which are permitted to be damaged shall be replaced with new components. The test unit shall be examined as new. Failure to successfully comply with the examination is a defect.

4.1.4 Operating environmental requirements. All materials (except metal and wood) and contractor procured components shall be in conformance with requirements specified in 3.2. The contractor's records (see 4.1.1) shall reflect that all materials/components (except metal and wood) used in the production of the cabinetry units are rated by the manufacturer of the material/component for use as employed in the specified environments.

4.2 Sampling.

4.2.1 For examination. Sampling for examination shall be conducted in accordance with MIL-STD-105 and Table I.

Table I. For examination

	Inspection level	AQL (percent defects)
For visual examination		
Major defects	II	1.0
Minor defects	II	2.5
For dimensional examination	II	1.0
For weight examination	II	1.0

4.2.2 For tests. Sampling for tests shall be conducted in accordances with MIL-STD-105 and Table II. Acceptance number shall be zero. The Inspection Level (IL) shall be as listed in Table II (see 4.2.2.1).

Table II. For tests

Characteristic	Unit Number	Requirement	Procedure	IL
Cold-rolled steel	All units	3.3.2	ASTM A-370	*
Finish of casework	All cabinets	3.3.2	MIL-C-20709	**
Cleanable, casework	All cabinets	3.3.2	NSF-30	**

CONTINUED on next page

Information Handling Services, DODSTD Issue 95-03

Source: https://assist.dla.mil -- Downloaded: 2026-10-21T11:47Z
Check the source to verify that this is the current version before use.

Continuation of Table II. For tests

Characteristic	Unit Number	Requirement	Procedure	IL
Drawer, bottom deflection	945, 931, 916	3.5.11.1	4.4.17	S-2
Drawer, accidental opening	945, 931, 916	3.5.12.1.1	4.4.28	S-2
Drawer, open-close	945, 931, 916	3.5.12.1.2	4.5.10	S-2
Bumper and catch	" " "	3.5.12.1.4	"	"
Drawer, cycling test	945, 931, 916	3.5.12.1.3	4.4.21	S-2
Bumper & catch test	" " "	3.5.12.1.4	"	"
Casework, load top	945,931,916,932	3.6.1.3.1	4.4.1	S-2
" " "	936	3.6.7.2.1	"	S-2
Top, attachment of	945,931,916,932	3.6.1.3.2	4.4.14	S-2
" " "	936	3.6.7.2.2	"	S-2
Top, flatness	945,931,916,932	3.6.1.3.3	4.4.22	S-2
Top, deflection load	945,931,916,932	3.6.1.3.4	4.4.18	S-2
Pullboard, loading	945,931,916,932	3.6.1.3.5	4.4.3	S-2
Carrying handle,	945,931,916,932	3.6.1.3.6	4.4.9	S-2
hanger support, &	903, 930	3.6.2.3.4	"	S-2
hanger unit loads	936	3.6.7.2.4	"	S-2
Trueness, for hanger	945,931,916,932	3.6.1.3.7	4.4.25	S-2
" " "	936	3.6.7.2.5	"	S-2
Unit stability	945,931,916,932	3.6.1.3.8	4.4.16	S-2
" "	903, 930	3.6.2.3.12	"	S-2
" "	936	3.6.7.2.8	"	S-2
Alternate Support,	945,931,916,932	3.6.1.3.9	4.4.32	S-2
Hanger	936	3.6.7.2.15	"	S-2
Casework, load, top	903, 930	3.6.2.3.1	4.4.2	S-2
Strip padding,	903, 930	3.6.2.3.2	4.4.26	S-2
peel & break				

CONTINUED on next page

Source: https://assist.dla.mil -- Downloaded: 2026-10-21T11:47Z
Check the source to verify that this is the current version before use.

Continuation of Table II. For tests

Characteristic	Unit Number	Requirement	Procedure	IL
Strip padding, scratch and rub	903, 930	3.6.2.3.3	4.4.27	S-2
Shelf, warp test	903, 930	3.6.2.3.5	4.4.4	S-2
Shelf, center load	903, 930	3.6.2.3.6	4.4.5	S-2
Door, torsion	903, 930	3.6.2.3.7	4.4.19	S-2
" "	936	3.6.7.2.6	"	S-2
Door, contort pull	903, 930	3.6.2.3.8	4.4.11	S-2
" " "	936	3.6.7.2.7	"	S-2
Door staple, pulling	903, 930	3.6.2.3.9	4.4.12	S-2
Door lock, pulling	903, 930	3.6.2.3.10	4.4.13	S-2
Door catch, tilt and jolt cabinet	903, 930	3.6.2.3.11	4.4.29	S-2
Plastic box, side tension	914	3.6.3.1	4.4.15	S-2
Retaining bar, loads	913	3.6.4.1	4.4.6	S-2
Referred fr. 3.6.1	945,931,916,932	"	"	S-2
" fr. 3.6.2.1.2	930	"	"	S-2
Hanger, load support	929	3.6.5.1	4.4.7	S-2
Counter, " "	928, 927	3.6.6.3.1	"	S-2
Counter, warp test	928, 927	3.6.6.3.2	4.4.23	S-2
Counter, support surface trueness	928, 927	3.6.6.3.3	4.4.24	S-2
Stainless steel tops reagent test	936	3.6.7.2.3	MIL-C-20709	**
	937	3.6.8.1.3		**
Plumbing leaks	936	3.6.7.2.9	4.4.30	S-2
Supply hose leaks	"	3.6.7.2.10	"	"
Water flow rate, for temperature control	936	3.6.7.2.11	4.4.31	S-2
Water heater output	936	3.6.7.2.12	4.4.31	S-2

CONTINUED on next page

Source: https://assist.dla.mil -- Downloaded: 2026-10-21T11:47Z
Check the source to verify that this is the current version before use.

Continuation of Table II. For tests

Characteristic	Unit Number	Requirement	Procedure	IL
Thermostat accuracy	936	3.6.7.2.13	4.4.33	S-2
Water pump, required maximum flow rate	936	3.6.7.2.14	4.4.34	S-2
Table, load support	937	3.6.8.1.1	4.4.8	S-2
Table, deflection	937	3.6.8.1.2	4.4.20	S-2

* The contractor's records (see 4.1.1) shall reflect successful compliance. A manufacturer's certificate that each production run of cold-rolled steel has been successfully tested in accordance with ASTM A-370.

** Inspection level (IL) shall be as specified by procedure document.

4.2.2.1 Inspection level (IL). The listed IL refers to each contract quantity for each correspondingly listed unit number.

4.3 Examination. Each unit shall be examined to determine compliance with all requirements contained in this specification.

4.3.1 Classification of defects. Examination shall be conducted in accordance with table III. Examination shall not be restricted to the classified possible defects.

Table III. Classification of defects

Categories	Unit No.: Defects
Major	
101	All units: A specified part not present.
102	All units: Not free of sharp edges/points hazardous to user's hand.
103	All units: Unit not assembled & ready for installation.
104	All units: Unit not permanently marked (identification).
105	All units: Unit not prepared for shipment (loose parts).

CONTINUED on next page

Source: https://assist.dla.mil -- Downloaded: 2026-10-21T11:47Z
Check the source to verify that this is the current version before use.

Continuation of Table III. Classification of defects

Categories	Unit No.: Defects
106	945, 931, 916, 932, 936: Any exterior panel, interior bottom, and/or pullboard top does not appear flat, has ripples, bumps and/or curves that are distinctly noticeable during a cursory examination.
107	945, 931, 916, 932, 936: Exterior bottom does not cover entire bottom.
108	945, 931, 916, 932, 936: Skid-rail bottom edges that are intended to contact the floor are not rounded.
109	945, 931, 916, 932, 936: Missing support member above carrying handle for attachment of hanger unit 929.
110	945, 931, 916, 932, 903, 930, 936: Carrying handles not recessed.
111	945, 931, 916, 932, 903, 930, 936: Carrying handles lifting position not in approximate horizontal plane.
112	945, 931, 916, 932: Pullboard, when closed, not easily grasped to open, has no stop to prevent unintentional removal when fully extended, and/or bumper is not present (prevents metal to metal contact when opened and closed).
113	945, 931, 916: Drawer has no stop to prevent unintentional removal when fully opened, and/or no bumper (prevents metal to metal contact when opened and closed).
114	931: Partitionment set missing from any drawer.
115	903, 930: An exterior panel, interior bottom, any shelf top, shelf support surface, and/or door panel (inside or outside) is uneven or has ripples, bumps and/or curves that are distinctly noticeable during a cursory examination.
116	903, 930: Strip padding material not fully attached to bottom of casework.
117	903, 930: Doors not removable and mountable (no tools).
118	903, 930: Doorway does not expose full cabinet interior.

CONTINUED on next page

Source: https://assist.dla.mil -- Downloaded: 2026-10-21T11:47Z
Check the source to verify that this is the current version before use.

Continuation of Table III. Classification of defects

Categories	Unit No.: Defects
119	903, 930: Shelf not removable (one shelf may require tools) and/or required quantity of boxes do not fit.
120	903: Shelves do not have alternate spacing available.
121	914: Box lid does not slide open and closed easily.
122	928, 927: Top surface and/or a supporting surface does not appear flat, has ripples, bumps and/or curves that are distinctly noticeable during a cursory examination.
123	936: Casters missing, or at least 2 do not have brakes.
124	936: Waste piping, supply plumbing, faucet, soap dispenser, water heater, pump and captive air tank, quick disconnect coupling, water supply hose, line strainer, backflow valve, 18 inch tubing, power supply cord, power receptacle, strainer/stopper not present.
125	936: Soap reservoir not easily accessible to replenish soap for the soap dispenser.
126	936: Door latch does not engage the casework and/or either door may be opened without using the latch handle.
127	936: Motor for pump not rated at least 1/3 HP for continuous duty.
128	936: Missing bracket/receptacle for stowing a part/ assembly/manuals which is not normally connected to the sink when the sink is installed and operational.
129	936: Missing sound deadening material, underside of sink
130	937: Missing sound deadening material, underside of top.
131	937: Table legs do not unfold as specified.
Minor	
201	There are no minor defects on this first order which establishes the design, and to some extent, the manufacturing techniques of this cabinetry system.

Source: https://assist.dla.mil -- Downloaded: 2026-10-21T11:47Z
Check the source to verify that this is the current version before use.

4.3.2 Dimensional and weight examination. Each unit shall be examined for defects in dimensions and weight limitation. Any dimension and/or weight not within the limits specified herein shall be classified as a defect.

4.4 Tests. Tests shall be conducted to determine compliance with specification requirements in accordance with Table II and the following:

a. Except for Scratch-rub test 4.4.27, protective material, such as cardboard, may be placed between elements being tested and elements of test equipment which exert physical force.

b. Alternate methods of testing may be employed, provided it is demonstrated to the Government's satisfaction that the alternate methods present the same, or better, degree of protection that the tested units meet the requirements of the specifications. If the contractor intends to employ alternate test procedure(s), the contractor shall submit such procedure(s) to the contracting officer within 45 days after award. The Government shall respond within 45 days, after receipt, with notification of acceptance/rejection and/or comments. No additional scheduling time shall be granted for this purpose.

c. These test procedures allow for practical test measurement tolerances. The contractor shall deliver units which are intended to be in conformance with requirements in section 3 of this specification without regard to allowable measurement tolerances in testing procedures.

d. Each test procedure shall be preceded by an examination of the item being tested. Examine the test item(s) for pretest damage. Reject any items (and complete unit if a rejected item is a component of a unit) if pretest damage or a defect is found. The rejection of an item by pretest examination is a defect.

4.4.1 Load support; casework & top, 945, 931, 916, 938, & 936. This test shall be performed on a complete unit. It shall test load carrying capability of casework in accordance with requirement 3.6.1.3.1, or requirement 3.6.7.2.1 as appropriate. Place the test unit on a level floor. By examination, sense the ease of performing the following operations:

a. Remove and install all drawers (if components of test unit).

b. Open and close all doors (if components of test unit).

c. Extend and push in the pullboard (except unit 936).

Source: https://assist.dla.mil -- Downloaded: 2026-10-21T11:47Z
Check the source to verify that this is the current version before use.

To continue, if test unit is 932, remove the front cover panel. If test unit is 936, place 1 inch thick boards (or a single sheet of any material capable of supporting the test load) across its top. These boards shall cover the area inside the marine edging and the back-splash. The weight of the boards used for testing unit 936 shall be subtracted from the 600 pounds of test weights. Open all drawers and/or doors. Using 50 pound scale testing weights (and a weight as needed with boards), distribute 600 pounds on the top of the test unit. These weights shall be inside a 1 inch margin (or marine edging and back-splash for unit 936) of the test unit's top edges. If weights overhang this margin (but not the cabinet's top edges), then place an appropriately sized wood board under individual weights to maintain load transfer within the specified margin. Weights shall not overhang the top outside edges. Maintain this loading for a period of 5 minutes. Remove the weights. Examine test item for any damage. Examine fit and function of all parts. Detection of damage, misfit, a distinct increased effort to operate, and/or a nonfunctioning part is a defect.

4.4.2 Load support, casework, units 903 and 930. This test shall be performed on a complete unit. It shall test the load carrying capability of a casework in accordance with requirement 3.6.2.3.1. Place the test unit on a level floor. Examine fit and function of all parts including ease of opening and closing doors. Open all doors. Using 50 pound scale testing weights, distribute 500 pounds on the top of the test unit. These weights shall be inside a 1 inch margin of the test unit's top edges. If weights overhang this margin (but not the cabinet edge), then place an appropriately sized wood board under individual weights to maintain load transfer within the specified margin. Weights shall not overhang the top outside edges. Maintain this loading for a period of 5 minutes. Remove the weights. Examine test item for any damage. Examine fit and function of all parts. Detection of damage, misfit, a distinct increased effort to operate, and/or a nonfunctioning part is a defect.

4.4.3 Load support, pullboard, units 945, 931, 916, and 932. This test shall be performed on a complete unit. It shall test for possible distortion of casework and/or pullboard caused by loading a weight on the pullboard in accordance with requirement 3.6.1.3.5. Operate the pullboard, sensing the ease of its operation. Operate the drawer directly under the pullboard (if test unit has a drawer) sensing the ease it operates. With the test unit resting on a level floor and the pullboard in the full extended position, evenly distribute 75 pounds on the pullboard. Maintain this loading for a 5 minute period. Remove the 75 pounds. Examine the unit for damage. Operate the pullboard and drawer directly thereunder. Detection of damage by examination and/or a distinct increase of effort to operate the pullboard and/or drawer is a defect.

4.4.4 Warp test, shelf, unit 903 and 930. This test shall be performed on a shelf. It shall test if the test shelf is warped in accordance with requirement 3.6.2.3.5. Randomly select one shelf per IL as a test shelf. Prepare a height gage, 1/2 inch square by 0.125 inch high. Place the test shelf on a true flat table (flat within 0.005 inch), right side up. If any corner is raised from the flat table, then attempt to slide the height gage under the high corner to a depth which positions two outside edges of the height gage even with the outside

Source: https://assist.dla.mil -- Downloaded: 2026-10-21T11:47Z
Check the source to verify that this is the current version before use.

edges of the high corner. If the height gage will fit under the high corner (as described) then a defect exists. Reposition the test unit on the table with the shelf top facing downward. Repeat this test as above except with the top facing down.

4.4.5 Center load support, shelf, units 903 and 930. This test shall be performed on a shelf. Randomly select one shelf per IL as a test shelf. It shall test the shelf's ability to withstand a concentrated center load in accordance with requirement 3.6.2.3.6. This test shall be performed on a flat table (flat within 0.005 inch). Support the test shelf, right side up, on two pieces of equal height bar stock (approximately 12 inches long). Position the supporting bar stock under the normal supporting surfaces of the test shelf. Establish 2 center points; 1 on each shelf long edge (underside edge of shelf). The center points are the center between the 2 supporting bar stock pieces. Measure and record the distance between both center points and the flat table (Nearest 0.002 inch). Obtain a 1 inch wide by approximately 12 inches long beam weighing 29.5 pounds (± 1/2 pound). Place the 29.5 pound weight on top of the shelf, passing over the 2 center points. Maintain this loading for a period of 5 minutes. Measure the distance between both established center points and the flat table. Compare the first set of measurements to the second set. A difference between a first and second corresponding measurement greater than 0.094 inch is a defect. Remove the weight. Measure the distance between both established center points and the flat table. Compare the first set of measurements to this third set. A difference between a first and third corresponding measurement greater than 0.010 inch is a defect. Examine the test shelf for damage. Determination of damage by examination is a defect.

4.4.6 Load test, unit 913. This test is predicated on not using alternative specifications. If offeror is employing an alternate construction, then offeror shall offer adequate testing procedures as appropriate (see 4.4 b). This test shall be performed on a complete retaining bar. It shall test the ability of the bar to resist deflection under load, and the tensile strength and flexibility of the wire rope in accordance with requirements in 3.6.4.1 (and as referred from 3.6.1 and 3.6.2.1.2 to 3.6.4.1). This test shall be performed on a flat table (flat within 0.002 inch). If the bar is channel shaped, face the open side up. Support the test unit on two pieces of bar stock having the same height. Place the supporting bar stock pieces directly under the extreme ends of the test unit's channeling (termination location of side walls). The 2 pieces of supporting bar stock shall be parallel with each other and perpendicular to the long dimension of the test unit. Establish 2 center points, 1 on each of the test unit's long edges (underside of test unit as setup). The center points are the center between the 2 supporting bar stock pieces. Measure the distance between both center points and the flat table (nearest 0.001 inch). Obtain a 29.5 pound weight (± 0.5 pounds) with a 1 inch wide support surface which is capable of resting on the top of the test unit, positioned above the two established center points. Position the weight over the 2 center points and parallel with the supporting bar stock pieces. Measure the distance between both center points and the flat table. Compare the first set of measurements with the second. A difference between a first and second corresponding measurements greater than 0.068

Source: https://assist.dla.mil -- Downloaded: 2026-10-21T11:47Z
Check the source to verify that this is the current version before use.

inch is a defect. Examine the wall of the bar for deformation. A noticeable deformation of the bar walls is a defect. Remove the test load and examine the bar for damage. With the bar in a secured position, pull the wire rope approximately 90 degrees, around a 3/4 inch diameter steel rod. Apply a force to the wire rope of 100 pounds. This force shall be transmitted through the pull ring of the pin. Examine the wire rope for broken strands, and pull ring for damage. Remove the test load and resecure the bar so that the wire rope faces downward. Hang a 10 pound (± 1/4 pound) weight by the pin or pin ring. Examine the wire rope for being straight without a kink, and for broken strands. Determination of a kink, broken strand, bent channel wall, or other damage by examination is a defect.

4.4.7 Load support, units 928 and 927, and unit 929. This test shall be performed using any combination of two base section or sink units 945, 931, 916, 932, or 936 as counter support units, 1 box of 4 hangers unit 929 as test unit, and one counter unit 928 or 927 as a test unit. It shall test the loading capability of counter units 928 or 927 in accordance with requirement 3.6.6.3.1, and a box of 4 hangers in accordance with requirement 3.6.5.1. The support units (945, 931, 916, 932, or 936) may be simulated by using a simulating means to support a set of test hangers. If either test unit is not called for by the IL and the test is being conducted for the other test unit, then the unit not required to be tested may be simulated in an appropriate manner. The test hangers shall support the test counter. Assemble two base section units (or simulated supports), a set of hangers, and a counter in accordance with any possible configuration (see 1.2.1.4). Using a contour gage, establish the contour of the test counter unit's top forward and rear edges, and the contour along the centerline between these 2 edges. Contour readings shall be ± 1/64 inch. The contour gage shall provide a reading every 6 inches (± 1/4 inch). Using 50 pound scale testing weights, evenly distribute 600 pounds on the test counter. These weights shall be inside a 1 inch margin of outside edges. Maintain this loading for a period of 5 minutes. Remove the weights. Measure the contour of the forward and rear top edges, and the centerline between these edges. Compare the first set of contour reading with the second corresponding set. A difference between any 2 corresponding contour readings greater than 1/16 inch is a defect. Examine all test units for any damage. Determination of damage by examination is a defect. If the hanger is a required test unit during this test, then repeat this test two times, except use the alternate hanger elevations. The contour gage need not be used on the second or third test but if the counter is a test unit, it shall be re-examined for damage.

4.4.8 Load support and stability, unit 937. This test shall be performed on a complete table. It shall test the sturdiness of a test table under load in accordance with requirement 3.6.8.1.1. Erect a test table ready for use on a level floor. Secure the bottom of the legs to the floor (Block the feet of the legs from movement in the direction of applied horizontal forces). Hang a plumb bob from table top to within 1/16 inch of the floor and mark the floor under the plumb bob. Distribute rigidly 400 pounds on the table top. Examine the table for damage. Make a second mark under the plumb bob. Measure the change in position of the plumb bob from the first mark on the floor. A change of plumb bob

Source: https://assist.dla.mil -- Downloaded: 2026-10-21T11:47Z
Check the source to verify that this is the current version before use.

position from the first mark in excess of 1/4 inch shall be a defect. Apply a horizontal force of 50 pounds perpendicular to, and at center of a table top edge. Make a third mark on the floor under the plumb bob. Measure the difference between the second and third mark on the floor. Repeat this procedure three more times except applying the force to a different edge and marking the floor under the plumb bob, numbers 4, 5, and 6. Measure the distance from the second mark to marks 3, 4, 5, and 6. A measurement in excess of 1 inch shall be a defect. Determination of damage by examination shall be a defect. It shall be acceptable to set the table next to a wall, or other upright structure, apply the above loadings, and substitute measurements of the table top travel with respect to the upright structure, in lieu of using a plumb bob. The table, or upright structure, shall be repositioned for each of the last 4 measurements. The upright structure shall not be permitted to interfere with the horizontal travel of the table top.

4.4.9 Handle & support attachment, 945, 931, 916, 932, 903, 930 & 936. These tests shall be performed on a complete unit. They shall test the attachment of carrying handle and the casework hanger's support member in accordance with requirement 3.6.1.3.6, requirement 3.6.2.3.4, or requirement 3.6.7.2.4 as appropriate. Perform the tests as follows:

a. Test the horizontal pulling capability of two opposing handles simultaneously. Position the test unit so that one side is facing a wall, or upright anchor structure. Anchor a test handle to the wall with the handle grip at horizontal. Apply a 150 pound horizontal pulling force to the opposing handle, attempting to pull the test unit away from the wall. That is, if forward right (top) handle is anchored, then apply the force to the forward left side (top) handle. Examine both handles and handle mounting for damage. Remove the test load. Examine both handles and handle mounting for damage. Determination of damage by examination is a defect.

b. If the test unit is unit 945, 931, 916, 932, or 936, then repeat procedure a except substitute "casework hanger's support member" for references to handle.

4.4.10 Opening and closing force, drawer, units 945, 931 and 916. This test shall be performed on a complete unit. It shall test the ease of opening and closing a new test drawer before the cycling test, and second time after the cycling test (see 4.4.21), and then a third and possibly a fourth time for reconditioning purposes (see 4.1.3.2). It is in accordance with requirement 3.5.18.1.2. It shall also test the durability of the drawer catch and bumper in accordance with requirement 3.5.18.4. Randomly select one drawer and suspension per test unit as a test drawer and suspension. Remove the drawer catch which is intended to hold the drawer closed (if present). For purpose of this test, full open shall be interpreted as just before engagement of feature intended to hold the drawer in the opened position (if present and less than 13 inches from full

Source: https://assist.dla.mil -- Downloaded: 2026-10-21T11:47Z
Check the source to verify that this is the current version before use.

closed). Otherwise, full open shall be interpreted as 13 inches from full closed. With the test unit resting on a level floor and with the test drawer fully closed, apply a smoothly increasing force, from 0 to maximum of 2.2 pounds, to the drawer handle, attempting to open the drawer. If the drawer does not fully open then a defect exists. If the drawer is designed for gravity closure, release the opened drawer and allow it to close. If the drawer does not fully close then a defect exists. If the drawer is not designed for gravity closure, then apply a smoothly increasing load, from 0 to 2.2 pounds, to the drawer handle attempting to close the drawer. If the drawer does not fully close then a defect exists. Otherwise, load the drawer with 100 pounds evenly distributed. Close the drawer. Using a pull gage, open the drawer. Record the peak pulling force required to open the drawer during the mid 3 inches of travel. Designate this measurement as Opening Force Before Cycling (OFBC). Using a push gage, close the drawer. Record the peak force required to close the drawer during the mid 3 inches of travel. Designate this force as Closing Force Before Cycling (CFBC). Replace the drawer catch (if provided) and cycle test the drawer in accordance with procedure in 4.4.21. This test is to be repeated a second time after the cycling test has been performed. During the second test of an empty drawer, the maximum pulling and pushing force shall be increased from 2.2 to 2.64 pounds (applies to second test only). If the force required to open and close the loaded drawer during the second test exceeds 1.21 times the OFBC and/or CFBC respectively, then a defect exists. Examine the operation of the drawer catch (if provided) and bumper. If the drawer catch and/or bumper are not performing in a normal manner, then a defect exists. After the second test is completed, and if no defect is found, recondition the test unit as new (see 4.1.3.2). This test shall be repeated a third time to verify that the drawer and suspension are reconditioned as new. The force required to open and close the loaded drawer during the third test (and fourth test if performed) shall not exceed 1.05 times the OFBC and CFBC respectively. This test may be repeated a fourth time for final verification of drawer renewal. If the drawer passes the third or fourth test, then it is reconditioned as new. If the test drawer is not reconditioned as new then a defect exists.

4.4.11 Contort pull test, door, units 903, 930, and 936. This test shall be performed on a complete unit. This procedure shall test the door, door hinge, and door hinge mounting capability to withstand a contorted pull force in accordance with requirement 3.6.2.3.8 or requirement 3.6.7.2.7 as appropriate. Randomly select one door per test unit as a test door. Open and close the test door noticing the ease of the operation. Examine the door fit in the closed position. Anchor the test unit to the floor. Open the test door about 45 degrees and secure the door in this position by its lower, extended corner only (corner away from hinge). Apply a 50 pound pulling force at the upper corner above the secured corner (perpendicular to the door surface), attempting to open the door further. Examine the door, hinge, and hinge mounting for damage. Remove the test load and anchors. Close the door and examine that it closes flush to the casework. Examine the operation of the door opening and closing. Examine the hinges and hinge mounting. Determination of damage by examination is a defect.

Source: https://assist.dla.mil -- Downloaded: 2026-10-21T11:47Z
Check the source to verify that this is the current version before use.

4.4.12 Pulling test, door staple, unit 903 and 930. This test shall be performed on a complete unit with the doors and non-secured shelves removed. It shall test the padlock staple and staple mounting in accordance with requirement 3.6.2.3.9. Remove the doors and non-secured shelves. Support the test unit on two sawhorses, face down. The two sawhorses shall support the unit by its front-side edges. Install a padlock on the padlock staple. A metal ring may simulate the padlock. Apply an 85 pound downward pulling force to the padlock, attempting to pull the padlock away from the front of the unit. Examine the staple mounting area and all elements in the line of force for damage. Remove the test load and padlock. Set the unit upright. Examine the complete cabinet unit for damage. Determination of damage by examination is a defect.

4.4.13 Pulling test, locked door, unit 903 and 930. This test shall be performed on a complete unit. It shall test the ability of a locked door to resist a pulling force in accordance with requirement in 3.6.2.3.10. Damaging replaceable parts is permitted. Allowable damage may require new parts for repair (see 4.1.3). Secure the test unit to a wall with the front facing away from the wall, in a manner that will not interfere with the test. The casework shall be held by its upper and lower forward edges using grips that fit between the closed doors and the casework. The bottom of the casework shall be held off the floor to free the doors from interference. Close and padlock the doors in a normal manner. A metal ring may simulate the padlock. Apply a 200 pound horizontal pulling force to the padlock, attempting to pull the padlock forward and away from the front of the unit. Maintain this loading for a period of 5 minutes. If a door pulls away from the casework 2 inches or more, then a defect exists. Remove the load and securing arrangement. Remove the doors, the staple, and replaceable staple support members (supporting the staple to the casework). Install the non-secured shelves and the doors. Examine the unit, as assembled, including the door operation and fit. Determination of damage by examination is a defect. Using a hammer, block and small hand tools only, straighten/repair the staple and staple replaceable support members (from staple to casework, not including casework). These repairs shall be performed as by unskilled personnel. Completely assemble the units using the repaired parts. Examine that the unit is usable. Center load the attached shelf with 80 pounds. Examine that a box (unit 914) will fit under and on the center loaded shelf. Examine that the padlock will fit in place and secure the door in a normal manner (manual force allowed to align components). Determination that the unit is not functionally usable by examination is a defect. Replace the staple and staple replaceable support parts with new parts as needed to renew the cabinet. Assemble the complete unit as new. Examine the unit for defects and/or damage. Determination of damage by examination is a defect.

4.4.14 Pull test, attachment of top, 945, 931, 916, 932, & 934. This test shall be performed on a complete unit. It shall test the mounting of the top to the casework in accordance with requirement 3.6.1.3.2 or requirement 3.6.7.2.2 as appropriate. Anchor the test unit to the floor. Anchor a vertical lifting mechanism to the top only, within 1 inch of a corner. Apply a 75 pound lifting force to the table top. Examine the unit for damage. Remove the test load and lifting mechanism. Examine the unit for damage. Examine the operation of all

Source: https://assist.dla.mil -- Downloaded: 2026-10-21T11:47Z
Check the source to verify that this is the current version before use.

doors and drawers (that may be present). If all corners are fastened by the same means, then this test need not be repeated at other corners. Repeat this test and these examinations at each remaining corner that is fastened in a different manner. (It may be necessary to dismount the top, install spacer washers, and reassemble to obtain a grip. If so, remove spacers after test.) Determination of damage by examination is a defect.

4.4.15 Tension test, plastic box, unit 914. This test shall be performed on a plastic box with its lid removed. It shall test the resilience and strength of the box in accordance with requirement 3.6.8.1. Open and close the lid sensing its operation. Remove the lid. Apply a 20 pound tension force between two opposite sides (sides with longest lengths). The locations of force contact shall be on the outside of the box, within 1/4 inch of the top, on the centerline between the front and back of the box. Maintain the application of this force for 5 minutes. Examine the box for cracks and/or other damage excluding deformation. Remove the test load. Install and close the lid. Open and close the lid sensing its operation. Examine the box for damage including deformation (lid closed). Determination of damage by examination and/or a distinct difference in lid operation is a defect.

4.4.16 Stability, units 945, 931, 916, 932, 903, 930, and 936. This test shall be performed on a complete unit. It shall test the stableness of a unit in accordance with requirement 3.6.1.3.8, requirement 3.6.2.3.12, or requirement 3.6.7.2.8 as appropriate. Place the test unit on a true flat table (flat within 0.002 inch) in an upright position. Stabilize the unit by shimming one corner support area. A corner support area is the area within 1 inch of the end of the skid-rails/strip padding material. No one corner shall receive a shim thickness greater than 0.127 inch. After placement of shims, examine cabinet stability by manually pressing down on each top corner. If rocking is observed, then a defect exists. This test shall be performed on the sink unit 936 twice, once with casters mounted, in which case caster shall be considered as the corner, and once without casters mounted. With casters mounted, the total acceptable shim thickness shall be increased to 0.190 inch.

4.4.17 Deflection test, drawer bottom, unit 945, 931, and 916. This test shall be performed on a drawer. It shall test for permanent deflection of a drawer bottom caused by loading the drawer in accordance with requirement 3.5.11.1. Randomly select one drawer per IL as a test drawer. Suspend the drawer in a normal manner for operation in a cabinet, or by a simulated cabinet suspension. If the test drawer is suspended within a cabinet, it shall be located in a middle position, and no drawer shall be mounted below or above the test drawer. In any event, the test drawer shall be suspended over a level surface by the same means that a closed drawer is normally suspended. With the test drawer closed, measure the distance from the drawer bottom center point to the level surface below. Prepare a 50 pound weight having a bearing area of 12 inches by 12 inches. Center the weight in the closed drawer so that the edges are parallel with the drawer sides. Measure the distance between the center point of the drawer bottom and the level surface below. A difference between the first and second measurement greater than 0.102 inch is a defect.

Source: https://assist.dla.mil -- Downloaded: 2026-10-21T11:47Z
Check the source to verify that this is the current version before use.

4.4.18 Deflection test, top, units 945, 931, 916, and 932. This test shall be performed on a complete unit. It shall test the capability of a top to resist deflection while under load in accordance with requirement 3.6.1.2.4. Perform stability test (see 4.4.16) and if unit is not rejected then continue. While the test unit is on the flat table, in a stable condition, establish, to the nearest 0.001 inch, the height of the center point of the cabinet top and designate this measurement as "W" inches. Prepare test weights as follows:

a. Measure the top surface of the test unit to the nearest 1/16 inch.

b. Designate "A" to equal the distance from the front edge to the rear edge (should be between 82 and 84 inches).

c. Designate "B" to equal A less 12 inches. Redesignate B to equal B divided by 2 (should be between 5 and 6 inches).

d. Designate "C" to equal the distance from the right side edge to the left side edge (should be between 17 and 19 inches).

e. Designate "D" to equal C less 12 inches. Redesignate D to equal D divided by 2 (should be between 2-1/2 and 3-1/3 in).

Allowing 1/16 inch for error, reject the test unit as being out of dimensional tolerance if measurements are not within stated ranges. Otherwise, continue preparing weights. All edges of the bearing surfaces shall be parallel and/or perpendicular with each other. Weights shall not overhang the bearing surface dimensions. The center of gravity of the weights shall be at their approximate center points of bearing surface. Weights with smaller surface bearing dimensions than calculated above may be used by the contractor for his convenience (not applicable to Government inspectors):

f. Prepare one weight to weigh 40 pounds (+ 0, -1/4 pound) having a bearing surface of 12 inches by 12 inches, and designate it as weight "F".

g. Establish the distance between the center points on the top and bottom surfaces of weight F within 0.001 inch and designate it as "E" inches.

h. Redesignate W to equal W + E inches.

i. Prepare two weights, each having a bearing surface of B inches by C inches, and each weighing 0.277 pounds multiplied by B times C (should be between 23.5 and 31.6 pounds), and designate each of them as weight "G".

Source: https://assist.dla.mil -- Downloaded: 2026-10-21T11:47Z
Check the source to verify that this is the current version before use.

j. Prepare two additional weights, each having a bearing surface of 12 inches by D inches, and each weighing 0.277 pounds multiplied by 12 times D (should be between 8.3 and 11.7 pounds), and designate each of them as weight "H".

Position weight F on the test unit's top, centered, with the edges of the weight parallel to the edges of the test unit. Fit both weights G on the test unit's top, one in front of and the other to the rear of weight F. Fit both weights H on the remaining spaces of the test unit's top. Establish the distance from the top center point of weight F to the flat table within 0.001 inch, and designate it as "X" inches. Designate "Y" to equal W less X inch. Designate "Z" to equal A inches divided by 200 and carry the result to the fourth decimal point and round it to the third decimal point. If Y is greater than Z in excess of 0.004 then a defect exists.

4.4.19 Torsion test, door, units 903, 930, and 936. This test shall be performed on a complete unit. It shall test the door's ability of withstanding a torsion load without being damaged in accordance with requirement 3.6.2.3.7 or requirement 3.6.7.2.6 as appropriate. Randomly select one door of the test unit as a test door. Operate the test door and note the ease of operation. Examine the door fit in closed position. Remove the test door from the unit. Face the inside of the door downward and support the door on a horizontal 1 inch wide beam extending diagonally beyond the door boundary, within one inch of diagonal corners. Stabilize the door in this position throughout the test period by balance only. Apply a 25 pound load at each unsupported corner (total 50 pounds). Examine the test unit for damage. Remove the loading. Examine the door for damage. Install and operate the door. Examine the door fit in the closed position. Detection of damage by examination and/or a noticeable difference in door operation is a defect. Repeat this test, switching load and support corners.

4.4.20 Deflection test, table unit 937. This test shall be performed on a complete unit. It shall test the capability of a table top to resist deflection while under load in accordance with requirement 3.6.8.1.2. Place the test table on a level floor. Establish to the nearest 0.001 inch, the height of the center point of the table's top and designate this height as "A". Prepare a test weight with a base surface area of 12 inches by 12 inches, and weighing 50 pounds. Measure the height of the weight from the center point on its top surface to its base, to the nearest 0.001 inch, and designate this measurement "B". Add the A to B and designate the result as "C". Place the test weight on the table top, centered with its edges parallel to the table top's edges. Establish the measurement between the floor and the test weight's top center point, and designate it as "D". Subtract D from C and carry the result to the nearest 0.001 inch. If the last result is greater than 0.095 inch, then a defect exists.

4.4.21 Cycling test, drawer, units 945, 931, and 916. This test shall be performed on a complete unit. It shall test drawer suspension, drawer bumper, and drawer catch (if provided) in accordance with requirement 3.5.12.1.3 and 3.5.12.1.4. The test unit, drawer and suspension shall have been tested in accordance with 4.4.10, opening and closing (of drawer) as a new unit. Arrange an

Source: https://assist.dla.mil -- Downloaded: 2026-10-21T11:47Z
Check the source to verify that this is the current version before use.

automatic apparatus to open and close a test drawer. This apparatus shall have a counter to count the number of open-close cycles. The cycling apparatus shall operate smoothly and require approximately 6 seconds per cycle. A new drawer, loaded with 99 pounds (± 1 pound) evenly distributed therein, shall be cycled 10,000 times. After completion of cycling, remove the apparatus. Operate the drawer in a normal manner. Examine drawer, suspension, and bumper operation. Detection of damage by examination and/or a noticeable difference in drawer operation is a defect. If no defect exists, then continue with the second test in 4.4.10.

4.4.22 Top, flatness test, units 945, 931, 916, and 932. This test shall be performed on a complete unit. It shall test the flatness of a base cabinet's top in the area which it supports an upper section cabinet in accordance with requirement 3.6.1.3.3. Place the test unit upright on a level floor. Prepare a true flat plate which is flat on one side within 0.002 inch. The length of this plate shall equal the test cabinet's width (+ 1/8 inch, - 0.0 inch); its width shall equal an upper cabinet's depth (front to back, + 1/8 inch, - 0.0 inch); and it shall have a weight of 65 pounds (± 10 pounds). An underweight plate may be weighted during test. Place the flat plate on the test unit's top, positioned to simulate a properly placed upper cabinet unit 930. If a 0.035 inch thick gauge, having a surface area of 1 inch by 1 inch, will fit under any location of the plate's edge to a depth of 1 inch, then a defect exists.

4.4.23 Warpage, counter unit 928 and 927. This test shall be performed on a complete unit. It shall test if a counter is warped in accordance with requirement 3.6.6.3.2. Prepare a height gage, 1 inch square by 0.070 inch high. Place the test counter on a true flat table (flat within 0.002 inch), with the work surface down. If any corner corner is raised from the flat table, then attempt to slide the height gage under the high corner to a depth which positions two outside edges of the height gage even with the outside edges of the high corner. If the height gage will fit under the high corner (as described) then a defect exists. Reposition the unit on the table with the work surface up. Repeat this test on each corner. If permanently attached hardware interferes with the test, then place bar stock of appropriate height by approximately 1 inch wide, under each edge facing downward, running the full length of all edges.

4.4.24 Support surface trueness, units 928 and 927. This test shall be performed on a complete counter. It shall test the trueness of the support area of a counter's drop flanges in accordance with requirement 3.6.6.3.3. Prepare 2 rectangular bars with dimensions of 1.500 inches (± 0.002 inch) high by 0.250 inch (± 0.002 inch) wide. The length shall equal the distance which spans the supporting surfaces of two drop flanges on one side of the test counter. Place the test counter upside down on a flat table (flat within 0.002 inch). Place 1 bar along the centerlines of the 2 drop flanges on one side of the counter. The referenced centerline of the drop flanges is that line intended to rest on the hanger support of the cabinet. Place the other bar along the centerlines of the other 2 drop flanges (located at opposite end of the counter). Position the bars so that their widths (1/4 inch) are centered inside the drop flange channels. If the bars do not cover all points of drop flange centerlines, then a defect ex-

Source: https://assist.dla.mil -- Downloaded: 2026-10-21T11:47Z
Check the source to verify that this is the current version before use.

ists. If the side edges of the 2 bars are not parallel (with each other) within 0.070 inch (from bar end to bar end) then a defect exists. If the top edges of the 2 bars are not parallel within 0.070 inch (from bar end to bar end) then a defect exists. If the bottom of the bars are not within 0.035 inch of the drop flange surfaces intended to rest on the hanger supports, then a defect exists. This bottom measurement shall apply to all 1/4 inch long by 1/4 wide segments within the channels of the drop flanges (i.e. a depression less than 1/4 inch long by 1/4 wide is ignored, but any rise is counted).

4.4.25 Trueness, hanger support members, 945, 931, 916, 932, 936. This test shall be performed on a complete unit. It shall test the trueness of supports for counters and hangers to assure that their mounting render them compatible with counters in accordance with requirement 3.6.1.3.7 or requirement 3.6.7.2.5 as appropriate. It shall be performed on a unit which has been tested in accordance with the stability test (see 4.4.16) and was not found defective. Place the unit on a flat table and stabilize it. Prepare a true flat plate (flat within 0.002 inch), approximately 1/4 inch thick (for rigidness). This plate shall be a gage to test the trueness of 2 support members on one side of a test unit. The width shall be a minimum width which shall be patterned to fit into recesses and lay on the two hanger supports covering their entire support surface. The length of this gage shall be approximately 11 inches. Lay the true surface of the flat plate on the support surfaces of the hanger supports. Establish a third position on the gage to support the gage. This third position shall be on the gage's centerline which is perpendicular to the insert edges (edges resting on hanger support). The third support location shall be approximately 9 inches away from the cabinet. Support the plate on two hanger supports and by the third position, positioned with the above mentioned centerline parallel with the flat table. Examine the contact area between the gage and support surface. If space exists, then attempt to insert a 0.035 inch feeler gauge (1/2 inch wide) into the space. If the feeler gauge fits, then a defect exists. If the flat plate width is not parallel with the floor within 0.130 inch (from end to end of gage width) then a defect exists. Repeat this test, except apply it to the opposite side of the casework.

4.4.26 Peel and breaking strength, strip padding, 903 and 930. This test shall be performed on a complete unit or on a simulated unit. It shall test the peeling and breaking strength of strip padding material in accordance with requirement 3.6.2.3.2. A simulated unit shall consist of a strip of cold-rolled steel, at least 12 inches long by 3 inches wide, having an identical finish as the casework. If the test unit is being simulated then, at least 7-1/2 inches of a 12 inch long strip of padding material shall have been applied to it, and shall have been pressed thereon with a force of 6 psi (± 1/4 psi) for a period of at least one week. The remaining free end of strip material need not have been applied to a simulated test unit. Otherwise, a test cabinet shall be loaded with 100 pounds, evenly distributed, and set on a level floor for a period of, at least, one week. In any event, a test unit shall be conditioned to have 3 inches (± 1/2 inch) of freed strip padding material. The test unit shall be appropriately positioned and secured for a peel test. The last 1 inch of freed strip material shall be grasped evenly and pulled with a force of 1 pound at a 90

Source: https://assist.dla.mil -- Downloaded: 2026-10-21T11:47Z
Check the source to verify that this is the current version before use.

degree angle to the adhesion surface. A line shall be marked at the line of adhesion where the free end meets the metal. The force shall be increased to 6 pounds per inch of width calculated using the nearest 1/8 inch of width and rounded to the nearest 1/10 pound. The application of this force shall be maintained for 3 minutes (± 3 seconds). A second line shall be marked at the line of adhesion. A separation of more than 1/8 inch between the two marked lines shall be a defect. Obtain a 6 inch length of new strip padding material, subject it to a stretching force of 15 pounds (± 0.5 pounds). If the strip padding material breaks, then a defect exists. In addition to this test, the material shall be tested in accordance with test 4.4.28.

4.4.27 Scratching-rubbing, strip padding material, 930 and 903. This test shall be performed using a complete unit and a combination of two base cabinets (units 945, 931, 916, and 932) for testing unit 903, or any one of these base cabinets for testing unit 930, or a simulated surface to represent base cabinets. A simulated surface shall consist of a sheet of cold-rolled steel having the same finish as cabinetry casework. This test shall test the protection provided by strip padding material against scratching, or otherwise permanently marking a supporting base cabinet in accordance with requirement 3.6.2.3.3. If a simulated surface is being used as supporting cabinetry, then it shall be appropriately sized according to the cabinetry it is simulating, and secured to a level surface in a manner which will not interfere with the test. Position and stabilize appropriate supporting cabinets (or simulated supporting surface) to receive the test unit. Only supporting surface(s) with no scratches or other marks shall be used. Place the test unit on the support surface with the test unit's front right corner on top of the supporting surface's rear right corner, and the test unit's left rear corner pointing toward the left front corner of the support surface. Load 100 pounds into the test unit, distributing the load on shelves. Using a horizontal motion applied near the bottom of both sides of the test unit, rotate the test unit to be properly positioned on the supporting surface for installation of retaining bars. Rotate the test unit back to the setup position. Again, rotate the test unit to the proper position for installation of retainer bars. Remove the 100 pounds from the test unit, and the test unit from the supporting surface. Examine the supporting surface for scratches or permanent marks. Examine the strip padding material on the test unit for dislocation. Scratch marks or permanent marks on the supporting surface is a defect. Dislocation of strip padding material on the test unit is a defect.

4.4.28 Accidental drawer opening, tilt and jolt, 945, 931, & 916. This test shall be performed on a complete unit. It shall test the ability of all drawers on a test unit to resist opening accidentally in accordance with requirement 3.5.12.1.1. Place the test cabinet on a level floor. Open, then close the drawers in a normal manner. Gently tilt the cabinet forward at an angle of 3 degrees ($+0.0^{\circ}$, -0.25°). Suspend a 1 pound (± 2 ounces) natural rubber weight 6 inches (± 1/2 inch) above the top rear edge and allow it to free fall onto the edge. For drawer suspension with gravity closure, if a drawer opens by a distance from full closed which is greater than the distance which the top overhangs the casework, then a defect exists. For drawers with a catch to hold them closed, if a drawer dislodges from its catch, then a defect exists.

Source: https://assist.dla.mil -- Downloaded: 2026-10-21T11:47Z
Check the source to verify that this is the current version before use.

4.4.29 Door catch, tilt and jolt test, units 903 and 930. This test shall be performed on a complete unit. It shall test the ability of the door catch to hold the door closed in accordance with requirement 3.6.2.3.11. Set the test unit on a level pedestal such that the pedestal will not interfere with the doors opening when unit is tilted forward. Be sure that both doors are closed in a normal manner. Tilt the test unit forward (top ahead of bottom) 9 degrees from vertical (± 1 degree). Position a 1 pound rubber weight 11-3/4 inches (± 1/4 inch) above the top rear edge of the test cabinet. Allow the rubber weight to free fall onto the cabinet's edge, jolting the test cabinet. If either door opens then a defect exists.

4.4.30 Water bursting and leakage, pressure tests, unit 936. This test shall be performed on a complete sink unit. It shall test for water leakage and system bursts in accordance with requirement 3.6.7.2.9 and requirement 3.6.7.2.10. Obtain one water supply source which will maintain 48 psi (± 2 psi), and another source which will maintain 68 psi (± 2 psi). Install the test sink in accordance with the instruction manual, connect it to an appropriate power supply, and connect the 68 psi water supply. Test the unit as follows:

a. Pressure test for burst. Adjust the controls to obtain the maximum pressure and temperature that the unit is capable of producing. Turn on both the hot and cold water. Maintain this condition for a period of 5 minutes. Examine the plumbing system, including the supply hose assembly, for any damage (seepage at connections is not damage during this test). Turn off the hot and cold water. Maintain this condition for a period of 5 minutes. Examine the plumbing system, including the supply hose assembly, for any damage. Detection of damage by examination is a defect.

b. Test for static leaks with no water running. Disconnect the 68 psi water supply and connect the 48 psi water supply. Adjust appropriate controls to produce the maximum pressure and temperature that the unit is capable of providing. With the faucet turned off, thoroughly wipe all plumbing pipes and fittings. Examine the unit, including the supply hose assembly, for water leakage. The presence of any leakage is a defect.

c. Test for leakage with hot and cold water running. Fully turn on both the hot and cold water. Examine the system for leakage. This examination shall include the hot and cold water lines, and drainage systems. Turn off the hot and cold water. Detection by examination of any leakage is a defect.

d. This test shall test the capability of the plastic pipe connectors to be tightened by hand without leaking. Loosen any one cold water pipe fitting at a union connection. Use of

Source: https://assist.dla.mil -- Downloaded: 2026-10-21T11:47Z
Check the source to verify that this is the current version before use.

a tool is allowed to loosen this fitting. Loosen this fitting until it starts to leak. Hand tighten this fitting without the use of tools. Thoroughly wipe the area and examine for leakage. Detection by examination of leakage at this connection is a defect.

4.4.81 System flow rate, for temperature control, 936. This test shall be performed on a complete unit. It shall test the ability of the control system to provide a controlled maximum flow rate in order to maintain water temperature rise during use. It is in accordance with requirement 3.6.7.2.11 and 3.6.7.2.12 to test the heater output. Obtain a clean water supply in a container such as a 55 gallon drum. Install the test sink unit and water supply in a temperature controlled room (do not connect the sink unit to a power supply or the water supply). Obtain test equipment capable of providing measurements of water temperature at the faucet outlet and water supply ± 0.10° F over a range of 60° F to 160° F, water flow rate at faucet outlet ± 0.0032 gallons per minute (1/2 Oz. per minute) over a range of 1/4 to 2.5 gallons per minute, and voltage at power source (wall outlet or dedicated posts in fuse box within the test room) ± 0.10 volts over a range of 200 volts to 250 volts. These accuracies shall be employed throughout this test procedure. All calculations shall be carried to the 6th decimal. Allow the water temperature to stabilize to room temperature (± 1° F) before continuing. After water temperature stabilizes, remove the nonsplash nozzle from the faucet. Perform test steps as follows:

a. Connect the sink unit water system to the water supply (insert the supply hose into the 55 gallon drum).

b. With the cold water faucet OFF, adjust the hot water faucet to full ON. Adjust the hot water flow control (inside the cabinet) to lowest flow rate/OFF. Adjust the thermostat to its highest temperature setting. Connect the unit to a specified power supply which is readily available. Turn ON the unit.

c. If no water is flowing and heater is producing heat, then a defect exists. If water is flowing at a rate greater than 1/2 GPM (+ 15% or 0.5750 GPM) then a defect exists.

d. If no defect exists, follow the manufacturer's instructions to set the hot water for minimum flow rate with heater producing heat. Allow the unit to run in this condition for a period of time of, at least, 10 minutes measuring the water temperature at the faucet outlet once per minute.

e. If the water temperature is measured to be greater than 150° F (+ 3% or 154.5° F), then a defect exists. Measure the flow rate once per minute during this same time period. If the flow rate is greater than 1/2 gallon per minute (+ 15%, or 0.575 GPM) for any one valid measurement, then a defect exists.

Source: https://assist.dla.mil -- Downloaded: 2026-10-21T11:47Z
Check the source to verify that this is the current version before use.

f. Following the manufacturer's instructions and (if necessary in accordance with manufacturer's instructions, use trial and error measuring the flow rate) adjust the flow to 0.575 GPM (± 15%). Allow the unit to run in this condition for a time period of 30 minutes, taking measurements of water temperature and flow rate (both at the faucet outlet), and the voltage draw at the source of power, all measurements once per minute.

g. If the water temperature is measured to be greater than 150° F (+3% or 154.5° F), then a defect exists. At the end of the 30 minute time period, calculate the mean flow rate of the measured flow rates. If any one measured flow rate varies more than 15% from the mean flow rate, then a defect exists. Otherwise, assign the mean flow rate to Actual Water Flow Rate (AWFR, see 3.6.7.2.12).

h. Calculate the mean voltage measured at the power source and assign the result to Actual Voltage (AV, see 3,.6.7.2.12). Calculate the Expected Water Temperature Rise (EWTR, see 3.6.7.2.12). Calculate the mean water temperature. Measure the water supply temperature and subtract it from the mean water temperature and assign the result to Actual Water Temperature Rise (AWTR, see 3.6.7.2.12). If AWTR is a decimal/fractional result then round the result to the next higher integer. Using the equations specified in 3.6.7.2.12, if the Actual Water Temperature Rise is not equal to or not greater than Expected Water Temperature Rise, then a defect exists.

Except for the adjustment of flow rate in f, repeat f through h setting the initial water flow rate at 1 GPM (± 15%); Then repeat again except using an initial flow rate setting of 1.70 (± 15%) in f. This test procedure as described above shall be completed once per specified power supply, testing the unit's performance under each power supply.

4.4.32 Ease of installing counters. This test shall be performed only if an alternate system is employed to support counter units 928 and 927. It shall test the ease by which counter units may be attached to base section units and sink unit in accordance with requirement 3.6.1.3.9 or requirement 3.6.7.2.15. It requires that a combination of 2 support units and 3 counter units (all 3 counters of same unit number) be tested simultaneously. Any combination (2 base units, 2 sink units, or 1 each) of support units may be employed. Remove casters from any sink units which are being tested. Install the 3 counter units and then move the supporting unit as close to each other as possible. Mark the floor with a line along the apposing bottom sides (right side of left supporting unit and left side of right supporting unit - as facing unit front). The marks on the floor shall be vertically under the specified (supporting) panels and each line shall terminate at the back and front (inside the toe space) of the supporting units. Remove the counters and place them on the floor, stacked, parallel with their installed position and 3 feet in front of supporting units. Separate the supporting units by a sufficient distance to allow marking the floor with a third

Source: https://assist.dla.mil -- Downloaded: 2026-10-21T11:47Z
Check the source to verify that this is the current version before use.

line. The left line shall be identified as line 1 and the right line shall be identified as line 2. The third line shall be positioned parallel to the right line and 2-3/4 inches (± 1/8 inch) to the right of the right line (line 2) and shall be identified as line 3. Reposition the supporting units, one with its right panel directly above line 1 and the other with its left panel directly above line 3. One person without assistance (mechanical or any other assistance) shall install the 3 counters within a time period not to exceed 5 minutes. The supporting units may not be moved during this installation procedure. Failure to accomplish installation of the 3 counter units within specified time shall be a defect for each unit being tested.

4.4.33 Thermostat operation, unit 936. This test shall be performed on a complete unit. It shall test the performance of the hot water thermostat as installed in a unit in accordance with 3.6.7.2.13. Obtain three (3) water supplies; one each with a known constant temperature of 75 degrees F (± 3° F), 110 degrees F (± 3° F), and one at 153 degrees F (± 3° F). Connect the sink unit to the 75 degree F water supply. Install the sink unit in accordance with the manufacturer's instructions and set the controls to obtain 1/2 GPM. Reset the thermostat to 85. Turn the hot water faucet full on. Measure the water temperature at the faucet. If the measured temperature is not within a range of 83° F and 87° F, then a defect exists. Otherwise, shutdown the sink unit and connect it to the 110° F water supply. Repeat the above procedure except, reset the thermostat (after setting the controls to obtain 1/2 GPM) to 115° F, substitute the acceptable measured range of temperature at the faucet with 113° F to 117° F. If the measured temperature at the faucet is not within the range of 113° F and 117° F, then a defect exists. Otherwise, shutdown the sink unit and connect it to the 153° F water supply. Install the sink unit in accordance with the manufacturer's instructions except, assign one individual (inspector) to monitor the heater light (indicator which indicates that the heater element is heating water) If the heater unit activates and remains heating for a period of time greater than 2 seconds then a defect exists.

4.4.34 Flow test, water pump, unit 936. This test shall be performed on a complete unit. It shall test the ability of the unit to provide the maximum required water flow rate in accordance with requirement 3.6.7.2.14. Obtain a water source with a negative pressure of 20 ft. water. Install the unit in accordance with the instruction manual. Connect it to an appropriate electrical supply and the negative pressure water supply. If the heater is turned on, turn it off. Set the controls for maximum flow rate (no heat). Turn on the cold water. Using a measuring system such as a stop watch and a 2 gallon bucket, measure the rate of water flow at the faucet outlet. If the water flow is less than 2 gallons per minute, then a defect exists.

4.5 Drawings and associated lists, acceptance submittal. The contractor shall maintain current updated drawings and associated lists. The drawings and associated lists submitted for acceptance (see 3.7.8.5, and DD Form 1423 covering Data Item Description (DID)
DI-E-7031) shall be examined for compliance with paragraphs 3.7 through 3.7.3.6. The contractor shall include a certificate of compliance with submittals (see

Source: https://assist.dla.mil -- Downloaded: 2026-10-21T11:47Z
Check the source to verify that this is the current version before use.

4.1.1.2.2). Drawings and associated lists that do not meet the requirements as specified shall be rejected.

4.6 Packaging inspection. The sampling and inspection of the packing and marking for shipment and storage shall be in accordance with the quality assurance provisions of the applicable container specification and marking requirements of MIL-STD-129.

5. PACKAGING

5.1 Packaging requirements. The requirements for packaging shall be in accordance with MIL-C-20709.

6. NOTES

6.1 Intended use.

6.1.1 Use of end items. The units are intended to be used in The DoD Deployable Medical System (DMS/DEPMEDS). The drawings and associated lists are intended to be incorporated into the specifications for use in future procurements.

6.1.2 Use of this specification. The solicitation is a request for proposals. Offerors are solicited to offer items which meet the requirements of this specification. It is intended that a contract will be awarded after at least one round of discussions/negotiations. These discussions/negotiations may include changing some requirements specified herein. All items shall be in strict conformance with specifications as of date of award. Awards shall not be split between contractors (all or nothing type of award only).

6.2 Ordering data. Acquisition documents should specify the following:

a. Title, number and date of this specification.

b. National Stock Number (NSN) and unit number of units required (see 1.2.1.1).

6.3 First article. Inspection of first article is required by contractor at source with Government representative present. Contractor is required to provide at least 21 days notice of inspection date. All first article samples are to have been inspected within 120 calendar days after award.

Source: https://assist.dla.mil -- Downloaded: 2026-10-21T11:47Z
Check the source to verify that this is the current version before use.

6.4 Required data.

6.4.1 Offeror: required data. The offerors are required to submit sketches and data (see specification section of procurement document). The sketches and data of the successful offeror are incorporated into the specifications (see 3.7.3.6).

6.4.2 Contractor required data. The contractor is required to provide level 3 drawings and associated lists (see 3.7 thru 3.7.3.6). If this procurement includes sink unit 936, then the contractor is required to provide provisioning data in accordance with DPSC-DEPMED9-AT(DM).

6.5 Heater output equation. The heater output equation is based on:

Rated Watts at 240 V: RW; Actual Voltage: AV; Actual Watts: AW

AW = RW * AV * AV / 240

Custodians:
Army-MD
Navy-MS
Air Force - 03

Review activities:
Army-MD
Navy-MS
Air Force - 03

Preparing activity:
DLA-DM

Project No. 6530-1973

Source: https://assist.dla.mil -- Downloaded: 2026-10-21T11:47Z
Check the source to verify that this is the current version before use.