MIL-T-38002B(USAF)
23 July 1964
Superseding
MIL-T-38002A(USAF)
31 August 1962

MILITARY SPECIFICATION

TRAILER, VAN A/M32M-16 CREW CHIEF STATION

1. SCOPE

1.1 This specification covers one type of van trailer, designated A/M32M-16.

2. APPLICABLE DOCUMENTS

2.1 The following documents, of the issue in effect on date of invitation for bids or request for proposal, form a part of this specification to the extent specified herein:

SPECIFICATIONS

Federal

W-C-596	Connector, Plug, Electrical, Connector, Receptacle, Electrical, Plate, Wall, Electrical

Military

MIL-P-116	Preservation, Methods of
MIL-C-3432	Cable and Wire, Electrical (Power and Control, Flexible and Extra Flexible, 300 and 600 Volts)
MIL-C-3767/3	Connector, Plug, Electrical (Power, Nonpolarized, Parallel-Bladed) Type UP120M
MIL-M-8090	Mobility Requirements, Ground Support Equipment, General Specification For
MIL-D-70327	Drawings, Engineering and Associated Lists

STANDARDS

Military

MIL-STD-129	Marking for Shipment and Storage
MIL-STD-130	Identification Marking of U. S. Military Property

FSC 1730

Source: https://assist.dla.mil -- Downloaded: 2026-10-21T11:47Z
Check the source to verify that this is the current version before use.

MIL-STD-143	Specifications and Standards, Order of Precedence for the Selection of
MIL-STD-281	Automobile, Trucks, Truck-Tractors, Trailer and Trailer Dollies, Preservation and Packaging of
MIL-STD-808	Finishes, Protective, and Codes, for Finishing Schemes for Ground and Ground Support Equipment
MIL-STD-810	Environmental Test Methods for Aerospace and Ground Equipment
MIL-STD-831	Test Reports, Preparation of
MS33586	Metals, Definition of Dissimilar

(Copies of specifications, standards, drawings, and publications required by suppliers in connection with specific procurement functions should be obtained from the procuring activity or as directed by the contracting officer.)

3. REQUIREMENTS

3.1 Preproduction. This specification makes provisions for preproduction testing.

3.2 Components. The trailer shall consist of the following major components:

Item Name	See Requirement
Chassis	3.7.1
Van body	3.7.2
Electrical hardware	3.7.3
Interior furnishings	3.7.4.

3.3 Selection of specifications and standards. Specifications and standards for necessary commodities and services not specified herein shall be selected in accordance with MIL-STD-143.

3.4 Materials

3.4.1 Protective treatment. When materials are used in the construction of the trailer that are subject to deterioration when exposed to climatic and environmental conditions likely to occur during service usage, they shall be protected against such deterioration in a manner that will in no way prevent compliance with the performance requirements of this specification. The use of a protective coating that will crack, chip, or scale with age or extremes of climatic and environmental conditions shall be avoided.

Source: https://assist.dla.mil -- Downloaded: 2026-10-21T11:47Z
Check the source to verify that this is the current version before use.

3.4.2 High strength-weight ratio materials. When feasible, high strength-weight ratio materials shall be used to reduce the gross weight of the trailer.

3.4.3 Metals. Metals shall be of the corrosion-resistant type or treated to resist corrosion due to salt spray or atmospheric conditions likely to be met in storage or normal service.

3.4.3.1 Dissimilar metals. Unless protected against electrolytic corrosion, dissimilar metals shall not be used in intimate contact with each other. Dissimilar metals are defined in MS33586.

3.5 Design and construction. The trailer configuration shall be that of a 4-wheel, 2-wheel, steerable, wagon-type vehicle and shall be designed to conform to type II, group C mobility as specified in MIL-M-8090. The trailer shall be designed and constructed to withstand the strains, shocks, vibrations, and other detrimental conditions incident to service, shipping, and storage.

3.5.1 Reliability. The trailer shall have a minimum mean-time-between-failure (MTBF) of 5.2 hours with a minimum reliability of 0.91 for a 0.5-hour mission at a confidence factor of 0.90 (see 6.3.1 and 6.3.2).

3.5.2 Maintainability. The trailer shall be designed and constructed as specified herein and to provide the following:

a. Minimum number of parts consistent with reliability and performance specified herein

b. Minimum amount of training and time necessary for assembly, disassembly, location of trouble sources, and maintenance including servicing. Where practical, parts and components shall be located or positioned for rapid and simple inspection and recognition of excessive wear or potential failure

c. Permit adjustments, servicing, replacement of parts and components, and other maintenance with minimum disturbance to other equipment parts or components. Parts and components shall be located for ample and rapid access unless performance or reliability will be appreciably degraded by the accessible location. In performing maintenance, if engineering reasoning or data determines that physical or visual interference between items cannot be avoided, the item predicted to require the most maintenance shall be located for best accessibility

d. Permit maintenance with general-purpose tools and equipment normally available commercially. Use of special-purpose tools and equipment shall be subject to approval by the procuring activity

Source: https://assist.dla.mil -- Downloaded: 2026-10-21T11:47Z
Check the source to verify that this is the current version before use.

e. Minimum number of tools required for maintenance by design practices such as reducing the variety of bolt head sizes to the practicable minimum.

3.5.3 Foolproofness. Where improper installation of an item could cause malfunctioning of that item or system in which it is installed, it shall be so designed that the item can only be installed in its proper operating position.

3.5.4. Transportability. The trailer, loaded or unloaded, shall be designed for transportation by rail, air, and water. Four 10,000-pound capacity tiedown rings shall be provided and installed, two on the front and two on the rear of the trailer.

3.5.5. Lubrication. Where practicable, lubricated-for life components or components not requiring lubrication shall be used in the construction of the trailer. Grease and oil seals shall be designed and located to provide maximum accessibility for inspection, servicing, and replacement.

3.6 Performance. The trailer shall operate satisfactorily in rainfall as encountered in any locale.

3.6.1 Capacity. The trailer shall be capable of handling and transporting a load of 1,500 pounds under the conditions specified herein.

3.7 Details of components

3.7.1 Chassis. The applicable parts of the trailer chassis shall conform to MIL-M-8090 for type II, group C mobility, except as modified below:

3.7.1.1 Parking brakes. Two wheel, adjustable, parking brakes shall be provided in accordance with MIL-M-8090. The foot- or hand-operated parking brake actuating mechanism shall be located in an easily accessible, protected location near the towbar.

3.7.2 Van body. The van body shall have essentially a L-shaped longitudinal cross section with the lower right corner of the letter L hereafter referred to as the front of the van. The van body shall be designed and constructed to provide a personnel compartment having insulated walls, floor, and ceiling, tool chest storage facilities, and a cowling storage platform. The van body shall be an integral body-frame-type structure designed to meet the requirements of this specification. The exterior and interior surfaces shall be sealed and trimmed to provide a continuous surface. Unless otherwise specified, exterior surfaces shall be constructed of aluminum not less than 0.030 inch thick.

Source: https://assist.dla.mil -- Downloaded: 2026-10-21T11:47Z
Check the source to verify that this is the current version before use.

3.7.2.1 Insulation. The van insulation shall be properly vented to prevent the formation of ice on the interior of the body during low temperature operations. The insulation shall be fire resistant and shall be of a type that will not pack or settle. Any condensate formed between the walls shall be drained by gravity flow. The average heat loss per square foot per degree Fahrenheit of the body shall not exceed 0.5 BTU per hour in a 25-knot wind.

3.7.2.2 Roof. The roof shall be watertight and shall withstand a static snow load of 45 psf. The roof shall be slightly crowned to permit drainage.

3.7.2.3 Walls. The walls shall be vertical and shall withstand a windload of 10 psf. The interior walls and ceiling shall be finished with 1/4-inch AC exterior grade plywood (A grade side exposed). All joints and seams shall be appropriately sealed and trimmed to provide a continuous surface.

3.7.2.4 Floor. The floor shall be not less than 5/8 inch thick and shall be flat and free of obstructions such as wheel wells, framing, and ducts. The floor shall support 70 psf.

3.7.2.4.1 Floor covering. The floor shall be covered with a heavy-duty-type skid-resistant rubber covering not less than 1/8 inch thick. If rib-type covering is used, the ribbing shall run in the direction which best facilitates cleaning. The covering shall be permanently bonded to the flooring and shall be oil and fuel resistant.

3.7.2.5 Door and windows

3.7.2.5.1 Personnel door. An insulated door shall be located in the sidewall of the van body. The door shall open outward to form a clear minimum opening 28 inches wide by 72 inches high. A means shall be provided for latching the door against the sidewall in the fully open position. In the maximum-open position, the door shall be flat against the wall of the van body. The door threshold shall be flush with the floor to facilitate cleaning. The door clearance shall not exceed 3/8 inch and shall be filled with a weathertight resilient gasket. A hand-grip shall be provided beside the door for ease of entry. If the distance from the ground to the top of the door sill exceeds 21 inches, a retractable, commercial, house-trailer-type step shall be provided.

3.7.2.5.1.1 Door window. A window, a minimum of 18 by 18 inches, shall be located in the upper portion of the door. The bottom of the window shall be approximately 48 inches from the bottom of the door.

Source: https://assist.dla.mil -- Downloaded: 2026-10-21T11:47Z
Check the source to verify that this is the current version before use.

3.7.2.5.2 Van body windows. A window shall be located in the sidewall opposite the door and in the rear wall. The windows shall be a minimum of 25 inches high by 30 inches long. The windows shall be of the horizontal sliding type for ventilating purposes. The open window area shall be not less than 75 percent of the closed window area. The windows shall incorporate easily removable screens. Provisions shall be made for opening and closing a 3- by 14-inch section at the rear window screen from inside or outside the van. The bottom of the window shall be approximately 40 inches above the floor.

3.7.2.5.3 Weather seals. Sufficient weather stripping shall be provided to keep dust, snow, and rain from entering the closed door and windows.

3.7.2.5.4 Drip shields. Rain drip shields shall be provided over the door and all windows which open.

3.7.2.5.5 Door and window hardware. All door and window hardware shall be heavy-duty, commercial type equivalent to that furnished on refrigeration trucks and trailers. A push-type emergency release shall be provided on the interior side of the door. The following hardware shall be provided on the door:

a. Exterior refrigeration-door-type handle for opening

b. Interior refrigeration-door-type handle for opening

c. Refrigeration-type door hinges

d. Refrigeration-type door latches.

3.7.2.6 Exterior shelf. A shelf 12 by 48 inches shall be located below the rear window of the van. The shelf shall be located approximately 4 feet from the ground and 75° from the vertical and shall support an evenly distributed 150-pound load. A retaining lip shall be provided along the lower edge of the shelf.

3.7.2.7 Outside cowling platform. A platform 48 inches long by the full van width shall be provided on the front wall of the van body over the tool box compartments. The front of the platform shall be approximately 1/4 inch lower than the rear. The platform shall support 200 pounds on any one square foot plus an additional 500 pounds evenly distributed over the entire surface. The surface of the platform shall be not more than 52 inches from the ground and shall incorporate rust-resistant metal sockets located on approximately 12-inch centers over the entire surface beginning with a row around the perimeter. The sockets shall be provided with drainage provisions. Galvanized pipes, 3/4 inch inside diameter by 24 inches long, shall be provided for two-thirds

Source: https://assist.dla.mil -- Downloaded: 2026-10-21T11:47Z
Check the source to verify that this is the current version before use.

the number of sockets. The pipes shall be coated with fuel- and oil-resistant material not less than 1/8 inch thick. The pipes shall slip fit into the sockets for ease of installation and removal. The slip fit shall be such that the pipes will not vibrate out of the sockets during the testing specified in 4.5.2 and 4.5.3. The covering shall be stripped from that portion of the pipe which slips into the socket. A fuel, oil, and skid-resistant rubber-type matting not less than 1/8 inch thick shall be permanently bonded to the platform. The top surface of the matting shall be flush with the tops of the sockets. The matting and sockets shall be sealed in such a manner which prevents penetration of water, fuel, or oil beneath the mat or around the outside of the socket. The sockets shall be so installed that a 100-pound horizontal force at the end of the pipes will not cause any permanent deformation of the sockets, or their support structure, or destroy the water-tight seal.

3.7.2.8 Toolbox compartments. Five toolbox compartments shall be provided at the front end of the van beneath the cowling storage area and shall incorporate a minimum 0.03-inch metal separator to provide individual storage spaces for each toolbox. The inside dimensions of the individual storage spaces shall be not less than 14 inches wide by 24 inches high by 21 inches deep and shall incorporate individual doors. The doors shall be external to the van body, hinged, and provided with hasps for padlocks. The decks of the compartments shall be inclined 5 percent toward the rear to preclude toolbox shifting during trailer braking operations. Door openings shall be not less than 12 inches wide by 22 inches high. The edge of the door openings shall be reinforced with a 1 by 1 by 1/8-inch metal angle, or equivalent. Door thresholds shall be flush with the floor to facilitate cleaning. Drainage provisions shall be provided.

3.7.2.9 Dimensions. The dimensions of the van shall be as follows:

a. Overall length (excluding towbar) not to exceed 130 inches

b. Overall width not more than 84 inches

c. Personnel compartment

(1) Inside height not less than 78 inches

(2) Inside width not less than 67 inches

(3) Inside length not less than 60 inches.

Source: https://assist.dla.mil -- Downloaded: 2026-10-21T11:47Z
Check the source to verify that this is the current version before use.

3.7.3 Electrical hardware

3.7.3.1 Wiring. The van shall be wired for a power input of 120V, single-phase, 60- and 400-cycle, 15-amp capacity. A 15-amp circuit breaker box shall be installed within the van.

3.7.3.2 Power input receptacle. A waterproof, recessed, male receptacle with spring-loaded cover shall be provided on the outside of the van on the wall opposite the door. The receptacle shall conform to W-C-596, style A. The location shall be determined on a basis of optimum accessibility and protection from damage. The receptacle shall be directly connected to the circuit breaker box inside the van.

3.7.3.3 Power supply cable. A 50-foot electric cable conforming to MIL-C-3432, class HO, flexibility F shall be provided with the van. The cable shall be a minimum size of two No. 12 conductor. One end of the cord shall be equipped with a female receptacle conforming to W-C-596, style A. The other end shall be equipped with a UP120M male plug conforming to MIL-C-3767/3.

3.7.3.4 Heater. A wall-mounted, 1,500W, 115V heater with thermostat and protective grille shall be furnished as part of the trailer. The heater shall satisfactorily operate from either 60- or 400-cycle current.

3.7.3.5 Lighting

3.7.3.5.1 Outside light. A 75 PAR 38/FL bulb and weatherproof fixture shall be so located over the center of the rear exterior shelf to provide optimum illumination of the entire shelf. A toggle-type wall switch shall be mounted inside the van near the door.

3.7.3.5.2 Inside light. A 75 PAR 38/FL bulb and fixture shall be so located over the center of the desk to provide optimum illumination. A toggle-type wall switch shall be mounted inside the van near the door.

3.7.4 Interior furnishings

3.7.4.1 Desk. A formica topped, or equal, writing surface approximately 24 inches by the full van width shall be permanently installed inside the van beneath the rear window approximately 30 inches from the floor. The writing surface shall be constructed and installed to support a centrally located 250-pound load without deflecting more than 0.1 inch. A good quality, commercial, two-drawer wood or metal filing cabinet shall be securely installed under each end of the writing surface. Drawers shall incorporate positive catches to hold them closed during vehicle transit. The cabinets shall be approximately 15 inches wide by 30 inches high by 24 inches deep. The front edge of the cabinets shall be flush with the front edge of the writing surface.

Source: https://assist.dla.mil -- Downloaded: 2026-10-21T11:47Z
Check the source to verify that this is the current version before use.

3.7.4.2 Floor storage area. A storage area approximately 18 inches deep by 24 inches high by the full van width shall be provided at the rear of the toolbox storage area. A shelf the full width of the van shall be provided approximately 15 inches from the floor. At least four sliding doors shall be provided at the base of the front inside van wall in the personnel compartment.

3.7.4.3 Overhead storage. Technical order storage cases shall be mounted in the upper wall corners above the desk on each side of the rear window. The storage cases shall face the front of the van and shall be approximately 30 inches high by 12 inches deep by as near the remaining width between the window and the sidewalls as possible but not less than 33 inches total. Each case shall be provided with three shelves that can be adjusted on approximately 3 inch centers. Provisions shall be made to prevent spillage from the shelves during 1g decelerations. Each shelf shall be of sufficient thickness to support 35 psf without deflecting more than 0.1 inch at the center. Each storage case shall be constructed and installed to support a total minimum load of 100 pounds.

3.8 Part numbering of interchangeable parts. All parts having the same manufacturer's part number shall be functionally and dimensionally interchangeable. The item identification and part number requirements of MIL-D-70327 shall govern the manufacturer's part numbers and changes thereto.

3.9 Weight. The net weight of the trailer shall not exceed 2,000 pounds.

3.10 Finishes and protective coatings. Cleaning, painting, and plating shall be in accordance with MIL-STD-808. The procedures specified herein shall be utilized. Additional procedures required for the finishing of the trailer shall be selected by the contractor from those specified in MIL-STD-808. Commercial equipment already painted shall not be repainted.

3.10.1 Exterior surfaces. Exterior surfaces of the trailer shall be finished in yellow, color code DG.

3.10.2 Interior surfaces. Interior surfaces shall be varnished in accordance with good commercial practice or painted in accordance with MIL-STD-808.

3.10.2.1 The rubber floor covering specified in 3.7.2.4.1 shall be black.

3.11 Markings

3.11.1 Operational markings. The operational markings shall be applied in accordance with the marking requirements of MIL-STD-808, except that the operational markings required by MIL-M-8090 shall be stenciled in accordance with MIL-STD-808 at both ends of the trailer. The letters shall be at least 1 inch high.

Source: https://assist.dla.mil -- Downloaded: 2026-10-21T11:47Z
Check the source to verify that this is the current version before use.

3.11.2 Towing speed. The trailer shall be marked as follows:

MAX TOWING SPEED 20 MPH.

3.11.3 Lubrication markings. Lubrication fittings shall be clearly indicated by a 2-inch diameter circle painted red, color BG, in accordance with MIL-STD-808.

3.12 Identification of product. Equipment, assemblies, and parts shall be marked for identification in accordance with MIL-STD-130. The date of delivery and the date of manufacture shall be permanently stamped on each nameplate.

3.13 Workmanship. The trailer, including all parts and accessories, shall be fabricated and finished in a thoroughly workmanlike manner. Particular attention shall be given to freedom from blemishes, defects, burrs, and sharp edges; accuracy of dimensions, radii of fillets, and marking of parts and assemblies; thoroughness of soldering, welding, brazing, painting, wiring, and riveting; alignment of parts and tightness of assembly screws and bolts, cleaning, et cetera.

4. QUALITY ASSURANCE PROVISIONS

4.1 Responsibility for inspection. Unless otherwise specified in the contract or purchase order, the supplier is responsible for the performance of all inspection requirements as specified herein. Except as otherwise specified, the supplier may utilize his own facilities or any commercial laboratory acceptable to the Government. The Government reserves the right to perform any of the inspections set forth in the specification where such inspections are deemed necessary to assure supplies and services conform to prescribed requirements.

4.2 Classification of tests. The inspection and testing of the trailer shall be classified as follows:

a. Preproduction testing.....see 4.3

b. Acceptance tests.....see 4.4.

4.3 Preproduction testing (see 6.2)

4.3.1 Test sample. One trailer shall be subjected to the tests specified in 4.3.3.

4.3.2 Test report. Upon completion of the preproduction tests, a test report shall be prepared in accordance with MIL-STD-831 and three copies of the report furnished to the procuring activity. The information required in 4.5.4 shall also be included.

Source: https://assist.dla.mil -- Downloaded: 2026-10-21T11:47Z
Check the source to verify that this is the current version before use.

4.3.2.1 Reliability and maintainability information. The following information shall be included as an appendix to the test report:

a. All failures, servicing, adjustments, maintenance, and irregular functioning shall be identified by accumulated operating time, cycles, miles, or position in the test procedure, as appropriate. Test conditions at the time of the events identified shall be recorded

b. A summary of the engineering analysis leading to any corrections made to design, construction, quality control, or other procedures, or leading to any corrections to be made to production items or proposed to be made. The summary shall also include an analysis of the predicted effectiveness of such corrections.

c. Clock time and man-hours required for each maintenance and servicing action taken during the tests. A brief description of the experience and qualifications of the personnel taking such actions shall be included

d. Test activity or contractor comments on item features or requirements that, if modified, should improve the item

e. Test activity or contractor comments on use or maintenance conditions to be avoided or cultivated to increase the reliability or useful life of the item

f. Any of the above information that is already included in the test report body need not be repeated in the information required by this paragraph, but clear reference to the location of the data shall be included.

4.3.3 Preproduction tests. The preproduction tests shall consist of all tests described under 4.5.

4.4 Acceptance tests. The acceptance tests shall consist of the individual tests.

4.4.1 Individual tests. Each trailer shall be subjected to the following tests as described under 4.5:

a. Examination of product

b. Road test.

4.5 Test methods

4.5.1 Examination of product. The trailer shall be inspected to determine compliance with the requirements specified herein with respect to weight,

Source: https://assist.dla.mil -- Downloaded: 2026-10-21T11:47Z
Check the source to verify that this is the current version before use.

dimensions, workmanship, finish, and marking. The trailer shall be subjected to a thorough inspection to determine quality, ease of adjustment, alignment, and functioning of all parts of the running gear and van body housed components.

4.5.2 Road test. The trailer shall be loaded to 3,500 pounds GVW and towed at 20 mph for a distance of 5 miles to determine general functioning of all components. Any malfunctioning or excessive deformation of the trailer shall be cause for rejection.

4.5.3 Mobility. The trailer shall be loaded to 3,500 pounds GVW and tested for compliance with MIL-M-8090 for type II, group C mobility. Fifty left and 50 right turns at maximum cramping angle and at 8 mph shall also be conducted.

4.5.4 Loading. Calculations may be submitted in lieu of conducting the following tests.

4.5.4.1 Snow load. The roof shall be subjected to a load of 45 psf to determine structural integrity. The van body may be placed on jacks or other substantial platform for this test. There shall be no failure or impending failure of the roof as a result of this test.

4.5.4.2 Floor load. The floor of the van shall be subjected to a load of 70 psf to determine structural integrity. There shall be no failure or impending failure as a result of this test. For this test, the frame ends of the trailer may be placed on jacks or blocks.

4.5.4.3 Cowling platform. The cowling platform shall be subjected to an evenly distributed load of 500 pounds and a 200-pound load on any one square foot to determine structural integrity. There shall be no failure or signs of impending failure as a result of this test.

4.5.4.4 Windload. One sidewall of the trailer shall be subjected to a load of 10 psf to determine structural integrity. There shall be no failure or signs of impending failure as a result of this test.

4.5.4.5 Shelf load. The outside rear shelf shall be subjected to an evenly distributed load of 150 pounds. There shall be no failure or signs of impending failure as a result of this test.

4.5.4.6 Overhead storage load. The overhead storage area shall be loaded as required to indicate compliance with 3.7.4.3. There shall be no failure or signs of impending failure as a result of this test.

Source: https://assist.dla.mil -- Downloaded: 2026-10-21T11:47Z
Check the source to verify that this is the current version before use.

4.5.4.7 Desk load. The desk shall be centrally loaded with 250 pounds. There shall be no failure or signs of impending failure as a result of this test. The deflection shall not exceed 0.1 inch.

4.5.5 Rain. The trailer shall be subjected to rain in accordance with MIL-STD-810, method 506, procedure I. An improvised spray device may be used in lieu of the specified spray chamber.

4.5.6 Insulation test. The van shall be tested to determine compliance with the overall heat loss coefficient specified in 3.7.2.1.

4.5.7 Reliability demonstration and test. Satisfactory completion of all tests specified herein without failure demonstrates compliance with the quantitative reliability requirements of this specification.

4.5.8 Maintainability evaluation. The trailer shall be inspected and evaluated from the standpoint of ease of maintenance, servicing, and operation. Particular attention shall be given maintenance with a minimum number of common tools, servicing and operation by personnel wearing heavy gloves, and provisions made to prevent accumulation of dirt, snow, ice, et cetera, that may hinder servicing and operation.

4.6 Inspection of preparation for delivery. Preservation, packaging, packing, and marking shall be inspected to verify conformance to section 5 herein.

5. PREPARATION FOR DELIVERY

5.1 Preservation and packaging. Preservation and packaging shall be level A or C as specified (see 6.2).

5.1.1 Level A. Unless otherwise specified in the contract or order, the trailer shall be preserved and packaged in accordance with MIL-STD-281, level A. Methods of preservation shall be in accordance with MIL-P-116.

5.1.2 Level C. The trailer, component parts, repair parts, tools, and publications shall be preserved and packaged in accordance with the supplier's standard practice.

5.2 Packing. Packing shall be level A, B, or C, as specified (see 6.2).

5.2.1 Level A. Unless otherwise specified, each trailer preserved and packaged as specified in 5.1.1 shall be packed in accordance with MIL-STD-281, level A. Packing shall be type I (skidded) or type II (boxed), or type III (mobile), as specified in the contract or order.

Source: https://assist.dla.mil -- Downloaded: 2026-10-21T11:47Z
Check the source to verify that this is the current version before use.

5.2.2 Level B. Unless otherwise specified, each trailer preserved and packaged as specified in 5.1.1 shall be packed in accordance with MIL-STD-281, level B. Packing shall be type I (skidded) or type III (mobile), as specified in the contract or order.

5.2.3 Level C. The trailer preserved and packaged as specified in 5.1.2 shall be packed in accordance with MIL-STD-281, level C.

5.3 Marking. In addition to any special markings required by the contract or order, interior packages and exterior shipping containers shall be marked in accordance with MIL-STD-129. The nomenclature shall be as follows:

Trailer, Van A/M32M-16, Crew Chief Station.

6. NOTES

6.1 Intended use. The A/M32M-16 trailer is intended for use as a mobile station from which the aircraft servicing crew chief can satisfactorily and efficiently operate.

6.2 Ordering data. Procurement documents should specify the following:

a. Title, number, and date of this specification

b. That MIL-M-008090D(USAF), dated 21 February 1961, or later issue be used in connection with this specification

c. Location and conditions for preproduction testing (see 4.3)

d. Applicable level of preservation and packaging, and packing (see 5.1 and 5.2).

6.3 Definitions. For the purpose of this specification, the following definitions apply:

6.3.1 Reliability. Reliability is defined as the probability of performing a specified function under given conditions without failure for a specified period of time. Recognizing that, in general, the rate of failure of equipment is fairly constant throughout the life of the equipment, the probability of nonfailure over an operating time interval decreases exponentially as a function of the length of the interval, during which time there is a constant failure rate, and can be expressed as follows:

Confidence level: 90 percent

$$\text{MTBF} = \frac{\text{Total test time}}{2.3}$$

Source: https://assist.dla.mil -- Downloaded: 2026-10-21T11:47Z
Check the source to verify that this is the current version before use.

Reliability $= e^{-x}$ where $x = \frac{\text{Mission time}}{\text{MTBF}}$

The $2.3 = \frac{4.61}{2}$ is based on the constant for the Poisson/Chi squared distribution, assuming an exponential (2 degrees of freedom) distribution even though the failure rate for the test time is zero.

6.3.2 Mean-time-between-failures. The mean life or mean-time-between-failures is the arithmetical mean (average) of the operating time between failures.

Custodian:
Air Force - 11

Preparing Activity:
Air Force - 11

Reviewers:

Air Force - 11, 82

Reviewer/user information is current as of the date of this document. For future coordination of changes to this document, draft circulation should be based on the information in the current Federal Supply Classification Listing of DOD Standardization Documents.

Source: https://assist.dla.mil -- Downloaded: 2026-10-21T11:47Z
Check the source to verify that this is the current version before use.

FOLD

SEG (SEPS)
WRIGHT-PATTERSON AFB, OHIO

POSTAGE AND FEES PAID

UNITED STATES AIR FORCE
OFFICIAL BUSINESS

Commander
Systems Engineering Group
ATTN: SEPS
Wright-Patterson AFB, Ohio

FOLD

GPO 812-304-1

Source: https://assist.dla.mil -- Downloaded: 2026-10-21T11:47Z
Check the source to verify that this is the current version before use.

SPECIFICATION ANALYSIS SHEET	Form Approved Budget Bureau No. 119-R004

INSTRUCTIONS

This sheet is to be filled out by personnel either Government or contractor, involved in the use of the specification in procurement of products for ultimate use of the Department of Defense. This sheet is provided for obtaining information on the use of this specification which will insure that suitable products can be procured with a minimum amount of delay and at the least cost. Comments and the return of this form will be appreciated. Fold on lines on reverse side, staple in corner, and send to preparing activity.

SPECIFICATION

ORGANIZATION	CITY AND STATE

CONTRACT NO.	QUANTITY OF ITEMS PROCURED	DOLLAR AMOUNT $

MATERIAL PROCURED UNDER A
☐ Direct Government Contract ☐ Subcontract

1. HAS ANY PART OF THE SPECIFICATION CREATED PROBLEMS OR REQUIRED INTERPRETATION IN PROCUREMENT USE?
   A. GIVE PARAGRAPH NUMBER AND WORDING

   B. RECOMMENDATIONS FOR CORRECTING THE DEFICIENCIES

2. COMMENTS ON ANY SPECIFICATION REQUIREMENT CONSIDERED TOO RIGID

3. IS THE SPECIFICATION RESTRICTIVE?
   ☐ YES ☐ NO IF "YES" IN WHAT WAY?

4. REMARKS (Attach any pertinent data which may be of use in improving this specification. If there are additional papers, attach to form and place both in an envelope addressed to preparing activity)

SUBMITTED BY (Printed or typed name and activity)	DATE

DD Form 1426

Source: https://assist.dla.mil -- Downloaded: 2026-10-21T11:47Z
Check the source to verify that this is the current version before use.