NOT MEASUREMENT SENSITIVE

MIL-STD-2525E
31 December 2022

SUPERSEDING
MIL-STD-2525D
w/CHANGE 1
2 August 2018

DEPARTMENT OF DEFENSE INTERFACE STANDARD

JOINT MILITARY SYMBOLOGY



Distribution A: Approved for public release, distribution is unlimited.

AMSC N/A AREA INST

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

FOREWORD

1. This standard is approved for use by all departments and agencies of the Department of Defense (DOD) and available for use by non-DOD entities (e.g., first responders, United Nations, and multinational partners).

2. This standard provides a standardized, structured set of graphical symbols for the display of information in command and control (C2) systems and applications. A standard method for symbol construction is provided, using common building block concepts to create current symbol sets as well as for creating sets that may be needed in the future. This includes frame, icon, modifier, and amplifier using color, graphical, and alphanumeric representations. It provides requirements for symbol construction and composition with flexibility for special user's needs.

3. In joint military operations, it is imperative to have a common language clearly understood among all users. Graphical representation of objects of interest (e.g., units, installations, equipment, control measures, activities, and meteorological occurrences) are observed and readily understood faster than merely text alone. This is valid even more for a user population with a widely different background of language, component, knowledge, and experience. A common standard of joint military symbols is therefore an important element to enhance efficiency and to contribute to success in joint operations.

4. This revision has resulted in many changes (SCP incorporation list) to the standard, but the most significant ones are as follows"

a. Changed the symbol identification code from 3, 32-bit long integer values to a single 30-postion value that uses the hexadecimal range of values to provide more available symbols.

b. Created Sector 1 and Sector 2 Common Modifiers that can be used across all dimensions.

c. Added ability to change the operational dimension of a symbol with the use of the frame shape identifier.

d. Converted many land symbols from a full octagon to a main icon for better flexibility.

e. Updated the cyberspace appendix to better represent current needs.

5. Comments, suggestions, or questions on this document should be addressed to Defense Information Systems Agency (DISA) Military Message Standards Branch (EM7), P.O. Box 549, Ft. Meade, MD 20755-0549, or emailed to disa.meade.EE.mbx.symbology@mail.mil. Since contact information can change, you may want to verify the currency of this address information using the ASSIST [Acquisition Streamlining and Standardization Information System] online database at https://assist.dla.mil/.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

CONTENTS

PARAGRAPH PAGE
1 SCOPE 1
1.1 Scope 1
2 APPLICABLE DOCUMENTS 1
2.1 General 1
2.2 Government documents. 1
2.2.1 Specifications, standards, and handbooks. 1
2.2.2 Other Government documents, drawings, databases and publications 2
2.3 Order of precedence 3
3 DEFINITIONS 3
3.1 Acronyms and abbreviations used in this standard 3
3.2 Definitions used in this standard 4
3.2.1 Amplifier 4
3.2.2 Area 4
3.2.3 Assumed friend 4
3.2.4 Atmospheric environment phenomena 4
3.2.5 Attribute. 4
3.2.6 Boundary 4
3.2.7 C2 (Command and Control) 5
3.2.8 Combat effectiveness 5
3.2.9 Commission Internationale de l'Eclairage (CIE) 5
3.2.10 Contact 5
3.2.11 Control measure symbol. 5
3.2.12 Cyberspace 5
3.2.13 Defended area 5
3.2.14 Defense support of civil authorities 5
3.2.15 Faker 5
3.2.16 Field 5
3.2.17 Frame 5
3.2.18 Friend 5
3.2.19 Frontogenesis. 6
3.2.20 Frontolysis 6
3.2.21 Graphic 6
3.2.22 Hostile 6
3.2.23 Icon 6
3.2.24 Icon-based symbol 6
3.2.25 Installation 6

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

3.2.26 Interoperability 6
3.2.27 Joint military symbology. 6
3.2.28 Joker 6
3.2.29 Lollipopping 6
3.2.30 Meteorological symbology 6
3.2.31 Modifier 6
3.2.32 Neutral 6
3.2.33 Operational environment 7
3.2.34 Own ship 7
3.2.35 Pending 7
3.2.36 Point. 7
3.2.37 Signals intelligence (SIGINT) 7
3.2.38 Suspect 7
3.2.39 Symbol 7
3.2.40 Symbol identification code (SIDC) 7
3.2.41 Text 7
3.2.42 Track 7
3.2.43 Unknown 7
4 GENERAL REQUIREMENTS 7
4.1 Joint military symbology 7
4.2 Command and control symbols 8
4.3 Other symbols 8
4.4 Monochromatic and hand-drawn symbols 8
4.5 Symbol recognition and legibility 8
4.6 Availability of scalable vector graphics (SVG) format symbol components 8
4.7 Application and implementation of approved symbology change proposals (SCP) 9
4.7.1 Requirements and advantages of implementing approved SCPs 9
4.7.2 Obtaining approved SCPs 9
4.7.3 Receipt of unrecognized symbol identification codes 9
5 DETAILED REQUIREMENTS 9
5.1 Objective 9
5.2 Organization 10
5.3 Icon-based symbols 10
5.3.1 Bounding octagon. 10
5.3.1.1 Bounding octagon and frames 10
5.3.1.2 The bounding octagon and icons/modifiers 13
5.3.2 Frame 13
5.3.2.1 Standard identity 17

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

5.3.2.2 Domain 18
5.3.2.3 Status 18
5.3.3 Fill 19
5.3.3.1 Fill color 19
5.3.4 Icons 19
5.3.4.1 Main icons 20
5.3.4.2 Full octagon icons. 20
5.3.4.3 Full frame icons 20
5.3.5 Invalid symbols 21
5.3.6 Modifiers 21
5.3.7 Amplifiers 21
5.3.7.1 Headquarters staff amplifier 32
5.3.7.2 Echelon indicator 32
5.3.7.3 Task force indicator. 33
5.3.7.4 Feint/decoy/dummy indicator 33
5.3.7.4.1 Construction 33
5.3.7.4.2 Line style 34
5.3.7.4.3 Position 34
5.3.7.4.4 Position for icon-based symbols 34
5.3.7.4.4.1 Unframed icon-based symbol position. 34
5.3.7.5 Offset/precise location amplifier 36
5.3.7.6 Altitude/depth modifier 36
5.3.7.6.1 Altitude base reference point. 36
5.3.7.6.2 Relative altitude 36
5.3.7.6.3 Flight level 37
5.3.7.6.4 Multiple instances of altitude/depth modifiers 37
5.3.7.7 Speed amplifier 37
5.3.7.8 Date-time group 38
5.3.7.9 Direction of movement amplifier 38
5.3.7.10 Mobility indicator 38
5.3.7.11 Auxiliary equipment indicator 40
5.3.7.12 Text modifiers 40
5.3.7.13 Dynamic graphic amplifiers 40
5.3.7.13.1 Area of uncertainty amplifier 42
5.3.7.13.1.1 Ellipse AOU amplifier. 42
5.3.7.13.1.2 Bearing box AOU amplifier 42
5.3.7.13.1.3 Line of bearing AOU amplifier 42
5.3.7.13.2 Dead reckoning trailer amplifier 42

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

5.3.7.13.2.1 Line DR trailer amplifier 42
5.3.7.13.2.2 Farthest-on circle DR trailer amplifier 42
5.3.7.13.3 Speed leader amplifier 42
5.3.7.13.4 Pairing line amplifier 43
5.3.7.13.5 Dynamic towed sensor array amplifier 43
5.3.7.14 Operational condition amplifier 43
5.3.7.15 Engagement amplifier bar 44
5.3.7.15.1 Engagement designation using the engagement amplifier bar 44
5.3.7.15.2 Target designation using the engagement amplifier bar 45
5.3.7.15.2.1 For hostile targets 45
5.3.7.15.3 Engagement amplifier bar structure 46
5.3.7.15.3.1 Remote and local engagements 46
5.3.7.15.3.2 Engagement stage 46
5.3.7.15.3.3 Weapons assignment or deployment 47
5.3.8 Manually-generated tracks 48
5.3.9 Dismounted Individual Leadership 48
5.3.10 Composition of icon-based symbols 48
5.3.10.1 Symbol display hierarchy 49
5.3.11 Symbol size 51
5.3.12 Line width 51
5.3.13 Plotting 51
5.3.14 Orientation 51
5.4 Compliance criteria 51
5.4.1 Appearance of tactical symbols 51
5.4.2 Assembling and parsing of SIDC 52
5.5 Color 52
6 NOTES 54
6.1 Intended use 54
6.2 Subject term (key word) listing 54
6.3 International standardization agreement implementation 54
6.4 Changes from previous issue 55
6.5 Symbology change proposal incorporation 55
6.5.1 Symbology change proposals (SCPs) incorporated into MIL-STD-2525E 55
SYMBOL IDENTIFICATION CODES 61
A.1 SCOPE. 61
A.1.1 Scope 61
A.2 APPLICABLE DOCUMENTS 61
Specific documents in 2.2 of this standard apply to this appendix. 61

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

A.3 DEFINITIONS 61
The definitions in section 3 of this standard apply to this appendix. 61
A.4 GENERAL REQUIREMENTS 61
A.4.1 Organization. This appendix contains SIDC and their elements. 61
A.5 DETAILED REQUIREMENTS 61
A.5.1 Symbol identification code 61
A.5.2 Elements of the symbol identification code 61
A.5.2.1 Set A - First ten values. 61
A.5.2.2 Set B - Second ten values. 62
A.5.2.3 Set C - Third ten values. 62
A.5.3 Set A 63
A.5.3.1 Version. 63
A.5.3.2 Standard identity 63
A.5.3.2.1 Context implementation guidance 64
A.5.3.2.2 Standard identity implementation guidance 64
A.5.3.3 Symbol set 64
A.5.3.3.1 Symbol set implementation guidance 65
A.5.3.4 Status 66
A.5.3.4.1 Status implementation guidance 66
A.5.3.5 Headquarters/task force/dummy 66
A.5.3.5.1 Headquarters/task force/dummy implementation guidance 66
A.5.3.6 Echelon/mobility/towed array amplifier 67
A.5.3.6.1 Echelon/mobility/towed array amplifier implementation guidance 68
A.5.4 Set B 68
A.5.4.1 Common Modifiers 71
A.5.4.2 Air (01) 73
A.5.4.3 Air missile (02). 76
A.5.4.4 Space (05). 77
A.5.4.5 Space missile (06). 78
A.5.4.6 Land unit (10) 79
A.5.4.7 Land civilian unit/organization (11). 89
A.5.4.8 Land Equipment (15). 90
A.5.4.9 Land installations (20). 97
A.5.4.10 Control measure (25). 101
A.5.4.11 Dismounted individual (27). 119
A.5.4.12 Sea surface (30) 121
A.5.4.13 Sea subsurface (35). 125
A.5.4.14 Mine warfare (36). 127

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

A.5.4.15 Activities (40). 129
A.5.4.16 Atmospheric (45). 134
A.5.4.17 Oceanographic (46). 140
A.5.4.18 Meteorological space (47). 145
A.5.4.19 Signals intelligence equipment (50). 146
A.5.4.20 Cyberspace (60). 147
A.5.5 Set C 149
A.5.5.1 Sector 1 modifier identifier 149
A.5.5.1.1 Sector 1 common modifier. 149
A.5.5.2 Sector 2 modifier identifier 149
A.5.5.2.1 Sector 2 common modifier 150
A.5.5.3 Frame shape identifier 150
A.5.5.4 Nationality/country/geopolitical/geographic name or entity 150
COMMON MODIFIERS 151
B.1 SCOPE 151
B.1.1 Scope 151
B.2 APPLICABLE DOCUMENTS 151
B.3 DEFINITIONS 151
B.4 GENERAL REQUIREMENTS 151
B.4.1 Organization. 151
B.5 DETAILED REQUIREMENTS 151
B.5.1 Technical specifications 151
B.5.2 Symbol identification coding scheme 151
B.5.3 Composition of common modifiers 151
B.5.3.1 Symbol building process 151
B.5.3.2 Common modifiers 152
SPACE SYMBOLS 165
C.1 SCOPE 165
C.1.1 Scope 165
C.2 APPLICABLE DOCUMENTS 165
C.3 DEFINITIONS 165
C.4 GENERAL REQUIREMENTS 165
C.4.1 Organization 165
C.5 DETAILED REQUIREMENTS 165
C.5.1 Technical specifications 165
C.5.2 Symbol identification coding scheme 165
C.5.3 Composition of space symbols 165
C.5.3.1 Symbol building process 166

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

C.5.3.2 Icons and modifiers 167
C.5.3.3 Amplifiers 167
C.5.3.3.1 Text amplifiers 167
C.5.3.3.2 Graphic amplifiers 167
C.6 SPACE EQUIPMENT AND PLATFORM SYMBOLS 168
C.6.1 Space equipment and platform symbols 168
C.6.2 Space equipment and platform icons 168
C.6.3 Space equipment and platform sector 1 modifiers 174
C.6.4 Space equipment and platform sector 2 modifiers 175
C.7 SPACE MISSILE SYMBOLS 176
C.7.1 Space missile symbols 176
C.7.2 Space missile icons 176
C.7.3 Space missile sector 1 modifiers 177
C.7.4 Space missile sector 2 modifiers 177
AIR SYMBOLS 181
D.1 SCOPE 181
D.1.1 Scope 181
D.2 APPLICABLE DOCUMENTS 181
D.3 DEFINITIONS 181
D.4 GENERAL REQUIREMENTS 181
D.4.1 Organization 181
D.5 DETAILED REQUIREMENTS 181
D.5.1 Technical specifications 181
D.5.2 Symbol identification coding scheme 181
D.5.3 Composition of air symbols 182
D.5.3.1 Symbol building process 182
D.5.3.2 Icons and modifiers 183
D.5.3.3 Amplifiers 183
D.5.3.3.1 Text amplifiers 183
D.5.3.3.2 Graphic amplifiers 183
D.6 AIR EQUIPMENT AND PLATFORM SYMBOLS 185
D.6.1 Air equipment and platform symbols 185
D.6.2 Air equipment and platform icons 185
D.6.3 Air equipment and platform sector 1 modifiers 192
D.6.4 Air equipment and platform sector 2 modifiers 195
D.7 AIR MISSILE SYMBOLS 196
D.7.1 Air missile symbols 196
D.7.2 Air missile icons 196

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

D.7.3 Air missile sector 1 modifiers.. 196
D.7.4 Air missile sector 2 modifiers. 198
LAND SYMBOLS 201
E.1 SCOPE 201
E.1.1 Scope. 201
E.2 APPLICABLE DOCUMENTS 201
E.3 DEFINITIONS 201
E.4 GENERAL REQUIREMENTS 201
E.4.1 Organization.. 201
E.5 DETAILED REQUIREMENTS 201
E.5.1 Technical specifications. 201
E.5.2 Symbol identification coding scheme. 201
E.5.3 Composition of land symbols. 201
E.5.3.1 Symbol building process. 202
E.5.3.2 Icons and modifiers. 203
E.5.3.3 Amplifiers. 203
E.5.3.3.1 Text amplifiers. 203
E.5.3.3.2 Graphic amplifiers. 203
E.6 LAND UNIT SYMBOLS 203
E.6.1 Land unit symbols. 203
E.6.2 Land unit amplifiers. 203
E.6.3 Land unit icons. 207
E.6.4 Land unit sector 1 modifiers. 236
E.6.5 Land unit sector 2 modifiers. 244
E.7 LAND CIVILIAN INDIVIDUALS/ORGANIZATION SYMBOLS 252
E.7.1 Land civilian individuals/organization symbols. 252
E.7.2 Land civilian individuals/organization icons. 252
E.7.3 Land civilian unit/organization sector 1 modifiers. 253
E.7.4 Land civilian unit sector 2 modifiers. 255
E.8 LAND EQUIPMENT SYMBOLS 256
E.8.1 Land equipment symbols. 256
E.8.2 Land equipment icons. 259
E.8.3 Land equipment sector 1 modifiers. 289
E.8.4 Land equipment sector 2 modifiers. 290
E.9 LAND INSTALLATION SYMBOLS 291
E.9.1 Land installation symbols. 291
E.9.2 Land installation icons. 294
E.9.3 Land installation sector 1 modifiers. 314

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

E.9.4 Land installation sector 2 modifiers.. 315
DISMOUNTED INDIVIDUAL SYMBOLS 317
F.1 SCOPE 317
F.1.1 Scope 317
F.2 APPLICABLE DOCUMENTS 317
F.3 DEFINITIONS 317
F.4 GENERAL REQUIREMENTS 317
F.4.1 Organization.. 317
F.5 DETAILED REQUIREMENTS 317
F.5.1 Technical specifications 317
F.5.2 Symbol identification coding scheme 317
F.5.3 Composition of land symbols. 317
F.5.3.1 Symbol building process 318
F.5.3.2 Icons and modifiers 319
F.5.3.3 Amplifiers. 319
F.6 DISMOUNTED INDIVIDUAL SYMBOLS 322
F.6.1 Dismounted individual symbols. 322
F.6.2 Dismounted individual icons.. 322
F.6.3 Dismounted individual sector 1 modifiers. 329
F.6.4 Dismounted individual sector 2 modifiers. 330
SEA SURFACE SYMBOLS 337
G.1 SCOPE 337
G.1.1 Scope. 337
G.2 APPLICABLE DOCUMENTS 337
G.3 DEFINITIONS 337
G.4 GENERAL REQUIREMENTS 337
G.4.1 Organization 337
G.5 DETAILED REQUIREMENTS 337
G.5.1 Technical specifications.. 337
G.5.2 Symbol identification coding scheme.. 337
G.5.3 Composition of sea surface symbols. 337
G.5.3.1 Symbol building process. 338
G.5.3.2 Icons and modifiers. 338
G.5.3.3 Amplifiers. 338
G.5.3.3.1 Text amplifiers 338
G.5.3.3.2 Graphic amplifiers 340
G.6 SEA SURFACE UNIT, EQUIPMENT AND INSTALLATION SYMBOLS 340
G.6.1 Sea surface unit, equipment and installation symbols. 340

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

G.6.2 Sea surface unit, equipment and installation icons. 340
G.6.3 Sea surface unit, equipment and installation sector 1 modifiers. 355
G.6.4 Sea surface unit, equipment, and installation sector 2 modifiers. 356
G.6.5 Sea surface local tracks. 357
G.6.5.1 Fused tracks 358
SEA SUBSURFACE SYMBOLS 359
H.1 SCOPE 359
H.1.1 Scope. 359
H.2 APPLICABLE DOCUMENTS 359
H.3 DEFINITIONS 359
H.4 GENERAL REQUIREMENTS 359
H.4.1 Organization. 359
H.5 DETAILED REQUIREMENTS 359
H.5.1 Technical specifications. 359
H.5.2 Symbol identification coding scheme 359
H.5.3 Composition of sea subsurface symbols. 359
H.5.3.1 Symbol building process. 360
H.5.3.2 Icons and modifiers. 360
H.5.3.3 Amplifiers. 361
H.5.3.3.1 Text amplifiers. 361
H.5.3.3.2 Graphic amplifiers 362
H.6 SEA SUBSURFACE UNIT, EQUIPMENT and INSTALLATION SYMBOLS 363
H.6.1 Sea subsurface unit, equipment and installation symbols. 363
H.6.2 Sea subsurface unit, equipment and installation icons. 363
H.6.3 Sea subsurface unit, equipment and installation sector 1 modifiers. 366
H.6.4 Sea subsurface unit, equipment, and installation sector 2 modifiers. 367
H.6.5 Sea subsurface local tracks. 368
H.6.5.1 Fused tracks 369
H.7 MINE WARFARE SYMBOLS 369
H.7.1 Mine warfare symbols. 369
H.7.2 Mine warfare icons 369
ACTIVITIES SYMBOLS 383
I.1 SCOPE 383
I.1.1 Scope. 383
I.2 APPLICABLE DOCUMENTS 383
I.3 DEFINITIONS 383
I.4 GENERAL REQUIREMENTS 383
I.4.1 Organization. 383

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

I.5 DETAILED REQUIREMENTS 383
I.5.1 Technical specifications. 383
I.5.2 Symbol identification coding scheme 383
I.5.3 Composition of activities symbols. 383
I.5.3.1 Symbol building process.. 384
I.5.3.2 Icons and modifiers. 384
I.5.3.3 Amplifiers. 385
I.5.3.3.1 Text amplifiers 385
I.5.3.3.2 Graphic amplifiers.. 387
I.6 ACTIVITIES SYMBOLS 387
I.6.1 Activities symbols.. 387
I.6.2 Activities icons. 387
I.6.3 Activities sector 1 modifiers. 410
I.6.4 Activities sector 2 modifiers. 411
SIGNALS INTELLIGENCE SYMBOLS 413
J.1 SCOPE 413
J.1.1 Scope.. 413
J.2 APPLICABLE DOCUMENTS 413
J.3 DEFINITIONS 413
J.4 GENERAL REQUIREMENTS 413
J.4.1 Organization. 413
J.5 DETAILED REQUIREMENTS 413
J.5.1 Technical specifications 413
J.5.2 Symbol identification coding scheme 413
J.5.3 Composition of SIGINT symbols 413
J.5.3.1 Symbol building process. 414
J.5.4 Icons and modifiers. 414
J.5.5 Amplifiers 414
J.6 SIGINT SYMBOLS 415
J.6.1 SIGINT symbols 415
J.6.2 SIGINT icons. 415
J.6.3 SIGINT sector 1 modifiers. 415
J.6.4 SIGINT sector 2 modifiers. 423
CYBERSPACE SYMBOLS 425
K.1 SCOPE 425
K.1.1 Scope. 425
K.2 APPLICABLE DOCUMENTS 425
K.3 DEFINITIONS 425

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

K.4 GENERAL REQUIREMENTS 425
K.4.1 Organization. 425
K.5 DETAILED REQUIREMENTS 425
K.5.1 Technical specifications. 425
K.5.2 Symbol identification coding scheme. 425
K.5.3 Composition of cyberspace symbols. 425
K.5.3.1 Symbol building process. 426
K.5.3.2 Icons and modifiers. 426
K.5.4 Amplifiers. 426
K.5.4.1 Text amplifiers. 426
K.5.4.2 Graphic amplifiers. 428
K.6 CYBERSPACE SYMBOLS 429
K.6.1 Cyberspace symbols. 429
K.6.2 Cyberspace icons. 429
K.6.3 Cyberspace sector 1 modifiers. 436
K.6.4 Cyberspace sector 2 modifiers. 437
CONTROL MEASURE SYMBOLS 439
L.1 SCOPE 439
L.1.1 Scope. 439
L.2 APPLICABLE DOCUMENTS 439
L.3 DEFINITIONS 439
L.4 GENERAL REQUIREMENTS 439
L.4.1 Organization. 439
L.5 DETAILED REQUIREMENTS 439
L.5.1 Control measure symbols. 439
L.5.1.1 Composition of control measure symbols. 440
L.5.1.1.1 Standard identity (color rules) for control measure symbols. 440
L.5.1.1.2 Point control measure height. 440
L.5.1.1.3 Status. 440
L.5.1.1.4 Amplifiers. 441
L.5.1.1.5 Direction of movement indicator. 443
L.5.1.1.6 Echelon indicator. 443
L.5.1.1.7 Offset location indicator. 444
L.5.1.1.8 Text amplifier. 444
L.5.1.1.9 Altitude/depth amplifier. 444
L.5.1.1.10 Altitude base reference point. 444
L.5.1.1.10.1 Relative altitude. 444
L.5.1.1.10.2 Flight level. 444

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

L.5.1.1.10.3 Multiple instances of altitude/depth amplifiers. 444
L.5.1.1.11 Date-time group. 445
L.5.1.1.12 Location of control measure symbols sector 1 and 2 modifiers.. 445
L.5.1.1.12.1 Control measure sector 1 modifier. 445
L.5.1.1.12.2 Mine types. 445
L.5.1.1.12.3 Default mine type. 445
L.5.1.1.12.4 Mine type(s) as a fill pattern. 446
L.5.1.1.13 Feint/decoy/dummy indicator. 446
L.5.2 Construction of control measure symbols. 449
L.5.2.1 Point control measure symbols. 449
L.5.2.2 Line and area control measure symbols. 449
L.5.3 Coloring. 450
L.5.4 Labeling. 450
L.5.4.1 Fonts. 450
L.5.5 Command and control. 450
L.5.5.1 Boundaries. 450
L.5.5.2 Boundary line segment orientation determination. 450
L.5.5.2.4 Control measure draw rules. 452
L.5.6 Points. 462
L.5.7 Lines. 463
L.5.8 Areas. 463
L.5.9 Area of operations. 464
L.5.10 Command and control measure symbols. 466
L.5.11 Maneuver control measure symbols. 474
L.5.12 Defensive maneuver.. 484
L.5.12.1 Areas. 484
L.5.12.2 Observation post. 485
L.5.13 Offensive maneuver. 488
L.5.14 Axis of advance. 488
L.5.14.1 Direction of attack. 491
L.5.15 Airspace coordinating measures. 495
L.5.15.1 Airspace coordinating measures. 495
L.5.16 Maritime control measures. 509
L.5.16.1 Maritime control measures.. 509
L.5.17 Fire support coordination measures. 545
L.5.17.1 Fire support coordination measures. 545
L.5.18 Targets. 553
L.5.18.1 Targets. 553

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

L.5.19 Target acquisition. 561
L.5.19.1 Target acquisition. 562
L.5.20 Obstacles 571
L.5.20.1 Obstacles 571
L.5.21 Field fortification control measures 589
L.5.21.1 Field fortification. 589
L.5.22 CBRN defense control measure symbols. 591
L.5.22.1 CBRN defense. 591
L.5.23 Sustainment control measures. 598
L.5.23.1 Sustainment control measures. 598
L.5.24 Supply points. 604
L.5.24.1 Supply point 604
L.5.25 Mission and operational tasks. 615
L.5.25.1 Mission and operational task symbols 615
L.5.26 Intelligence control measures. 624
L.5.26.1 Intelligence control measure symbols. 624
L.5.27 Control measure sector 1 modifiers 624
L.5.28 Abbreviations and acronyms for use with control measure symbols. 630
L.5.28.1 Boundary abbreviations and acronyms. 630
L.5.28.2 Unit functions abbreviation and acronyms. 631
METEOROLOGICAL AND OCEANOGRAPHIC SYMBOLOGY 633
M.1 SCOPE 633
M.1.1 Scope. 633
M.2 APPLICABLE DOCUMENTS 633
M.3 DEFINITIONS 633
M.4 GENERAL REQUIREMENTS 633
M.4.1 Organization. 633
M.5 DETAILED REQUIREMENTS 633
M.5.1 Technical specifications. 633
M.5.2 Symbology identification coding scheme. 633
M.5.3 Symbology set. 633
USE OF WARFIGHTING SYMBOLS IN PSEUDO-THREE-DIMENSIONAL DISPLAYS 733
N.1 SCOPE 733
N.1.1. Scope. 733
N.2 REFERENCES 733
N.3 DEFINITIONS 733
N.3.1. Billboarding 733
N.3.2. Cubing 733

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

N.3.3. Curve (line) 733
N.3.4. Geospatial..... 733
N.3.5. Glyph..... 733
N.3.6. Icon..... 733
N.3.7. Image..... 734
N.3.8. Marker post (lollipop). 734
N.3.9. Model. 734
N.3.10. Pictograph. 734
N.3.11. Point 734
N.3.12. Solid (volume)..... 734
N.3.13. Surface (area) 734
N.3.14. Symbicon. 734
N.3.15. Symbol. 734
N.3.16. Terrain draping..... 734
N.3.17. Three-dimensional. 734
N.3.18. Two-dimensional 734
N.4 PSEUDO-THREE-DIMENSIONAL (2.5D) SYMBOLIZATION 734
N.4.1. Introduction.. 734
N.4.2. When to use 2.5D displays..... 735
N.4.3. Taxonomy of symbols and displays..... 736
N.4.3.1. Subject area. 736
N.4.3.2. Delineation type. 736
N.4.3.3. Degree of Abstraction. 736
N.4.3.4. Dimensionality. 736
N.4.3.5. Relative to terrain. 737
N.4.4. Geospatial (map) symbols..... 737
N.4.4.1. Raster data. 737
N.4.4.2. Vector data.. 737
N.4.5. Imagery. 737
N.4.6. Optimum display method.. 737
N.5 GUIDANCE AND PORTRAYAL CONSIDERATIONS IN PSEUDO-THREE-DIMENSIONAL (2.5D) DISPLAYS 738
N.5.1. Use of 2D symbols in 2.5D display. 738
N.5.1.1. Visualization of icons..... 738
N.5.1.1.1. Terrain draping..... 738
N.5.1.1.2. Billboarding. 739
N.5.1.1.3. Cubing.. 739
N.5.1.1.4. Marker post. 740

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

N.5.1.2. Visualization of control measure symbols.. 740
N.5.1.3. Symbicon.. 742
N.5.2. Pseudo-three-dimensional models. 742
N.5.2.1. Modeling and simulation (M&S) standards.. 742
N.5.2.2. Model libraries. 743
N.5.3. Design considerations for symbology in a 2.5D display. 743
N.5.3.1. Symbol location. 743
N.5.3.1.1. Submergence of symbols.. 743
N.5.3.1.2. Height above/below terrain surface. 743
N.5.3.1.3. Estimating track position. 743
N.5.3.2. Perspective. 743
N.5.3.3. Direction indicators.. 744
N.5.4. Text amplifiers for symbols. 745
N.5.5. Speed vectors and trailing lines. 745
N.5.6. Incomplete data. 745
N.5.7. Vertical exaggeration of terrain and tactical symbols. 745
N.5.8. Implications for training and doctrine. 746
N.6 NOTES 746
CONCLUDING MATERIAL 747

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

1 SCOPE

1.1 Scope. This military standard (MIL-STD) establishes the rules and requirements to develop and display joint military symbology within the Department of Defense (DOD) and non-DOD entities.

2 APPLICABLE DOCUMENTS

2.1 General. The documents listed in this section are specified in sections 3, 4, or 5 of this standard. This section does not include documents cited in other sections of this standard or recommended for additional information or as examples. While every effort has been made to ensure the completeness of this list, document users are cautioned that they must meet all specified requirements of documents cited in this standard, whether or not they are listed.

2.2 Government documents.

2.2.1 Specifications, standards, and handbooks. The following specifications, standards and handbooks form a part of this document to the extent specified herein. Unless otherwise specified, the issues of these documents are those cited in the solicitation or contract.

INTERNATIONAL (NATO) STANDARDIZATION AGREEMENTS (STANAG)

STANAG 1166/APP-20	-	Standard Ship Designator System
STANAG 1241	-	Standard Identity Description Structure for Tactical Use
STANAG 2019/APP-06	-	Joint Military Symbology
STANAG 2147		Target Numbering System (Nonnuclear)
STANAG 2511	-	Uncertainty Representation and Reasoning Evaluation Framework (URREP) Reliability Versus Credibility in Information Fusion
STANAG 2961	-	Classes of Supply of NATO Forces
STANAG 3680/AAP-6	-	Glossary of Terms and Definitions

DEPARTMENT OF DEFENSE (DOD) STANDARDS

MIL-STD-1472	-	Design Criteria Standard: Human Engineering
MIL-STD-6016	-	Interoperability Standard: Tactical Data Link (TDL) Link-16 Message Standard
MIL-STD-6017	-	Interoperability Standard: Variable Message Format (VMF) Message Standard
NGA.STND.0033	-	Geopolitical Entities, Names and Codes (GENC) Standard

(Copies of these documents are available online at https://assist.dla.mil/, https://quicksearch.dla.mil/, https://nsgreg.nga.mil/genc/registers.jsp)

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

2.2.2 Other Government documents, drawings, databases and publications. The following other Government documents, drawings and publications form a part of this document to the extent specified herein. Unless otherwise specified, the issues of these documents are those cited in the solicitation or contract.

DEPARTMENT OF DEFENSE PUBLICATIONS

Department of Defense Dictionary of Military and Associated Terms

MULTISERVICE PUBLICATIONS

ATP 2-01.3/ MCRP 2-10B.1	-	Intelligence Preparation of the Battlefield/Battlespace
ATP 3-17.2 (MCRP 3-20B.1[3-21-1B], NTTP 3-02.18, AFTTP 3-2.68)	-	Multiservice Tactics, Techniques and Procedures for Airfield Opening
ATP 3-37.10/MCRP 3-17.7N		Base Camps

JOINT PUBLICATIONS (JP)

AartyP-1	-	NATO – Land-Based Fire Support Procedures
AARTYP-5/ STANAG 2484	-	NATO Fire Support Doctrine
AJP-3.3.5	-	Allied Joint Doctrine for Airspace Control
JP 2-01.3	-	Joint Intelligence Preparation of the Operation Environment
JP 3-09	-	Joint Fire Support
JP 3-09.3	-	Close Air Support
JP 3.13	-	Information Operations
JP 3-52	-	Joint Airspace Control

(Copies of these documents are available at https://jdeis.js.mil/jdeis/.)

ONLINE DATABASES

NATOTERM	-	NATO Terminology Database

(Link to NATOTerm database: https://nso.nato.int/natoterm/)

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

ARMY PUBLICATIONS

FM 1-02.1	-	Operational Terms
FM 1-02.2	-	Military Symbols
FM 3-34	-	Engineer Operations
FM 3-90	-	Tactics
ADP 3-90	-	Offense and Defense
ATP 2-33.4	-	Intelligence Analysis
ATP 3-05.1	-	Unconventional Warfare at the Combined Joint Special Operations Task Force Level
ATP 3-09.30	-	Observed Fires
ATP 4-02.2	-	Medical Evacuation

(Copies of these documents are available at https://armypubs.army.mil/.)

UNITED STATE MARINE CORPS PUBLICATIONS

MCWP-16	-	Fire Support Coordination in the Ground Combat Element

(A copy of this document is available at https://www.marines.mil/News/Publications/MCPEL/Tag/95321/doctrine/)

INTERNATIONAL ORGANIZATION FOR STANDARDIZATION

STANAG 1059	-	Letters Codes for Geographical Entities

(A copy of this document is available at https://nso.nato.int/nso/home#)

2.3 Order of precedence. Unless otherwise noted herein or in the contract, in the event of a conflict between the text of this document and the references cited herein, the text of this document takes precedence. Nothing in this document, however, supersedes applicable laws and regulations unless a specific exemption has been obtained.

3 DEFINITIONS

3.1 Acronyms and abbreviations used in this standard. The acronyms used in this standard are defined as follows:

AAP	allied administrative publication
ADP	Army doctrine publication
ADRP	Army doctrine reference publication
AFH	Air Force handbook
AIS	automated information system
AJP	allied joint publication
AOU	area of uncertainty
APP	allied procedural publication
ASSIST	Acquisition Streamlining and Standardization Information System
ATP	Army Training Publication

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

C2	command and control
CBRN	chemical, biological, radiological, and nuclear
CIE	Commission Internationale de l'Eclairage
DISA	Defense Information Systems Agency
DOD	Department of Defense
DR	dead reckoning
FM	field manual
HSL	hue, saturation and luminance
IFF	identification friend or foe
ISO	International Organization for Standardization
JP	joint publication
MCRP	Marine Corps reference publication
METOC	meteorological and oceanographic
MGRS	military grid reference system
MIL-STD	military standard
NATO	North Atlantic Treaty Organization
RGB	red, green, blue
SIF	selective identification feature
SIGINT	signals intelligence
STANAG	standardization agreement NATO
USMTF	United States message text format
VMF	variable message format
WGS 84	World Geodetic System 1984

3.2 Definitions used in this standard. Terms used in this document are defined as follows. When applicable, the source of the definition is cited in parentheses. Unless otherwise annotated, this publication is the proponent for all terms and definitions found in the index.

3.2.1 Amplifier. Optional text or graphics that provide additional information about a symbol and are always located outside the frame area.

3.2.2 Area. 1. A flat piece of ground or open space. 2. A distinct space or surface, or one having a special function. (Refer to FM 1-02.1 for the definition of specific types of areas.)

3.2.3 Assumed friend. "In identification, the designation given to a track, object or entity whose characteristics, behavior or origin indicate that it is a probable friend." (NATOTerm)

3.2.4 Atmospheric environment phenomena. A term used to describe natural phenomena occurring in the envelope of air surrounding the Earth, including its interfaces and interactions with the Earth's solid or liquid surface.

3.2.5 Attribute. A distinctive feature or characteristic such as line, shape, color, texture (fill), edge, mass and value.

3.2.6 Boundary. A line that delineates surface areas for the purpose of facilitating coordination and deconfliction of operations between adjacent units, formations, or areas. (DOD Dictionary)

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

3.2.7 C2 (Command and Control). The exercise of authority and direction by a properly designated commander over assigned and attached forces in the accomplishment of the mission. Command and control functions are performed through an arrangement of personnel, equipment, communications, facilities, and procedures employed by a commander in planning, directing, coordinating, and controlling forces and operations in the accomplishment of the mission.

3.2.8 Combat effectiveness. The ability of a unit to perform its mission. Factors such as ammunition, personnel, fuel status, and weapon systems are evaluated and rated. (FM 1-02.1)

3.2.9 Commission Internationale de l'Eclairage (CIE). A color space chart widely used to describe the range of color seen by the human eye.

3.2.10 Contact. In air intercept, a term meaning, "Unit has an unevaluated target."

3.2.11 Control measure symbol. A category of joint military symbology that provides information about objects necessary for battlefield planning and management.

3.2.12 Cyberspace. Cyberspace is a global domain within the information environment consisting of interdependent networks of information technology infrastructures and resident data, including the internet, telecommunications networks, computer systems, and embedded processors and controllers (JP 3-12).

3.2.13 Defended area. An area the Source Track Number (STN) is capable of defending against ballistic missiles, etc., (i.e., the Source TN is operational with ready weapons and has designated the area for defense). (MIL-STD-6016)

3.2.14 Defense support of civil authorities. Support provided by US Federal military forces, Department of Defense civilians, Department of Defense contract personnel, Department of Defense component assets, and National Guard forces (when the Secretary of Defense, in coordination with the governors of the affected states, elects and requests to use those forces in Title 32, United States Code, status) in response to requests for assistance from civil authorities for domestic emergencies, law enforcement support, and other domestic activities or from qualifying entities for special events. (DOD Dictionary)

3.2.15 Faker. A friendly track acting as a hostile for exercise purposes. (STANAG 1241)

3.2.16 Field. A defined area in which a limited combination of alphanumeric and other characters, amplifiers and/or abbreviations are grouped/situated in an established way around a symbol/icon, line, area, point, or boundary and used for the purpose of providing additional information about the associated object or operational environment geometry.

3.2.17 Frame. The geometric border of a symbol that provides an indication of the standard identity, dimension and status of a joint military object.

3.2.18 Friend. In identification, the designation given to a track, object or entity belonging to a declared, presumed or recognized friendly nation, faction or group (NATOTerm)

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

3.2.19 Frontogenesis. The process where a frontal boundary is developing.

3.2.20 Frontolysis. The process where a frontal system is dissipating/weakening.

3.2.21 Graphic. Any and all products of the cartographic and photogrammetric art. A graphic may be either a map, chart, or mosaic or even a film strip that was produced using cartographic techniques. (AAP-6)

3.2.22 Hostile. In identification, the designation given to a track, object or entity whose characteristics, behavior or origin indicate that it is a threat to friendly forces. Designation as hostile does not necessarily imply clearance to engage. (NATOTerm)

3.2.23 Icon. The innermost part of a symbol that provides a graphic representation of an object.

3.2.24 Icon-based symbol. A category of joint symbology that provides information about the standard identity, dimension, status and mission of an object.

3.2.25 Installation. A grouping of facilities which support particular functions. Installations may be elements of a base.

3.2.26 Interoperability. The condition achieved among communications-electronics systems or items of communications-electronics equipment when information or services can be exchanged directly and satisfactorily between them and/or their users. The degree of interoperability should be defined when referring to specific cases. (DOD Dictionary)

3.2.27 Joint military symbology. Symbology used to plan and execute joint military operations in support of C2 functions. These symbols fall into two basic categories: icon-based symbols and control measure symbols.

3.2.28 Joker. A friendly track acting as a suspect for exercise purposes. (STANAG 1241)

3.2.29 Lollipopping. The placing of a symbol above the ground surface on a map using a marker post. The user can set an arbitrary height above the ground surface and drop down lines connecting the symbol to its ground location without having the symbol actually cover the location on the map.

3.2.30 Meteorological symbology. Symbology used in weather/climatic forecasting.

3.2.31 Modifier. A pictorial or alphanumeric component that provides additional information about the icon and is always located inside the frame area.

3.2.32 Neutral. 1. In combat and combat – support operations, an identity applied to a track whose characteristics, behavior, origin, or nationality indicate that it is neither supporting nor opposing friendly forces. (DOD Dictionary). 2. In identification, the designation given to a track, object or entity whose characteristics, behavior, origin or nationality indicate that it is neither supporting nor opposing friendly forces (NATOTerm).

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

3.2.33 Operational environment. A composite of the conditions, circumstances, and influences that affect the employment of capabilities and bear on the decisions of the commander. (DOD Dictionary)

3.2.34 Own ship. The visual representation of the ship that the operator is currently occupying.

3.2.35 Pending. Tracks which have not been subject to the identification process but which are available for reporting may be reported with a status of pending. (STANAG 1241)

3.2.36 Point. A position, place, spot, or locality. (Refer to FM 1-02 for the definition of specific types of points.) A symbol that has only one set of coordinates.

3.2.37 Signals intelligence (SIGINT). 1. A category of intelligence comprising either individually or in combination all communications intelligence, electronic intelligence, and foreign instrumentation signals intelligence, however transmitted. 2. Intelligence derived from communications, electronics, and foreign instrumentation signals. (DOD Dictionary)

3.2.38 Suspect. In identification, the designation given to a track, object or entity whose characteristics, behaviour or origin indicate that it is a potential threat to friendly forces. (STANAG 1241)

3.2.39 Symbol. A graphic object that presents information.

3.2.40 Symbol identification code (SIDC). A numeric code based on a hierarchical structure that provides the elements required to construct the basic symbol.

3.2.41 Text. Words, alphanumeric information and other American Standard Code for Information Interchange (ASCII) characters used to define or further designate the meaning of a symbol.

3.2.42 Track. 1. A series of related contacts displayed on a data display console or other display device. 2. To display or record the successive positions of a moving object. 3. The actual path of an aircraft above or a ship on the surface of the earth. (DOD Dictionary) The course is the path that is planned; the track is the path that is actually taken.

3.2.43 Unknown. In identification, the designation given to an evaluated track, object or entity that has not been identified. (NATOTerm) An identity applied to an evaluated track that has not been identified. (DOD Dictionary)

4 GENERAL REQUIREMENTS

4.1 Joint military symbology. Figure 1 shows the appendices that contain the joint military symbology sets available for planning and conducting joint operations.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.




FIGURE 1. Joint military symbology appendices.

4.2 Command and control symbols. The symbol sets encompass the graphic representation of units, equipment, installations and other elements and activities relevant to joint military operations. They contain the building blocks for joint symbols from the air, land, maritime (sea surface and sea subsurface), space and cyberspace domains.

4.3 Other symbols. This standard also contains standardized symbols and figures for control measures, meteorological and oceanographic (METOC), signals intelligence (SIGINT), activities and dismounted individuals.

4.4 Monochromatic and hand-drawn symbols. While the focus of this publication is the display of symbols in modern multi-chromatic electronic systems, all symbols should be usable in monochromatic systems and as hand-drawn symbols.

4.5 Symbol recognition and legibility. When engineering and designing symbols and composing their building blocks, consider human factors; such as, symbol recognition and legibility across a variety of illumination conditions, map backgrounds, symbol sizes, display types and resolutions, and mental and physical fatigue.

4.6 Availability of scalable vector graphics (SVG) format symbol components. The Symbology Standard Management Committee (SSMC) has created symbol building blocks in scalable vector graphics (SVG) format. These symbol components are Scalable Vector Graphics (SVG) 1.1 (Second Edition), 16 August 2011 compliant and can be used as examples of control measure symbols, can be used to assemble and/or parse symbols in all other appendices, and can be used as input in creating MIL-STD-2525 compliant symbols in other formats by implementers of the standard. Requests for these files (please specify MIL-STD-2525 version) should be addressed to Defense Information Systems Agency (DISA) Military Message Standards Branch (EM7), P.O. Box 549, Ft. Meade, MD 20755-0549, or emailed to disa.meade.EE.mbx.symbology@mail.mil. Since contact information can change, you may want to verify the currency of this address information using the ASSIST [Acquisition Streamlining and Standardization Information System] online database at https://assist.dla.mil/.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

4.7 Application and implementation of approved symbology change proposals (SCP). symbology change proposals (SCPs) written against the current version of MIL-STD-2525 and approved by the SSMC, unless specifically stated otherwise in the approved SCP document, can be immediately implemented and fielded upon approval of the SCP by the SSMC on any system or platform prior to that SCP being incorporated into the next formal release of MIL-STD-2525.

4.7.1 Requirements and advantages of implementing approved SCPs. There are many reasons why a Service, system, system of systems or application would immediately implement SSMC SCPs that were approved for implementation vice waiting for an updated version of the standard to be published. Many new symbol requirements have originated with deployed warfighters engaged in combat operations for new symbol to depict things not supported in the (at that time) current version of the standard – things such as improvised explosive devises (IED), IED suicide bombers, IED explosions, emergency distress call points, terrorist organizations, raids on houses, etc. Other new symbol requirements originate from a Service when their doctrine changes and new symbols are identified in those documents. As these documents are used in training, it is often imperative to get these new symbols approved and into fielded systems so the warfighter will have all the tools available to them that they were trained to use. Waiting for an updated version of the standard to be published can take years and is often an unacceptable delay to the warfighters we support.

4.7.2 Obtaining approved SCPs. Copies of SCPs are available for download from the SSMC website: (https://intelshare.intelink.gov/sites/datalinks/Symbology/SitePages/Community%20Home.aspx). Requests should be addressed to Defense Information Systems Agency (DISA) Military Message Standards Branch (EM7), P.O. Box 549, Ft. Meade, MD 20755-0549, or emailed to disa.meade.EE.mbx.symbology@mail.mil. Since contact information can change, you may want to verify the currency of this address information using the ASSIST [Acquisition Streamlining and Standardization Information System] online database at https://assist.dla.mil/.

4.7.3 Receipt of unrecognized symbol identification codes. The ability to implement SSMC approved SCPs immediately upon approval could cause fielded systems to receive a symbol identification code (SIDC) that the system does not recognize. If a system receives an unrecognized SIDC, the system should handle exception to the best of its ability and based upon its specific system/user requirements. This could include, for example, discarding the unrecognized SIDC, displaying an Unknown symbol (see table I) at the unrecognized SIDC location, or displaying the portions of the unrecognized SIDC that can be understood; such as, an empty frame (affiliation based/shaped) when SIDC Set A is recognized and understood but Set B is not recognized or understood.

5 DETAILED REQUIREMENTS

5.1 Objective. To promote interoperability at the information level within the area of joint military symbology, it is necessary to define a standard set of rules for symbol construction and generation to be implemented in C2 systems. The rules in this standard are considered to be the minimum necessary to ensure that information about joint military symbology is exchanged successfully across service and organizational boundaries. These rules are not intended to constrain the manner in which the symbology is used.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

5.2 Organization. This section provides the detailed requirements concerning the composition, construction, display and transmission of tactical symbols and control measure symbols considered essential to achieve interoperability. Display rules are provided which allow the degree of complexity of the resulting symbology to be tailored to operational requirements and system capabilities. Additional implementation guidance is provided in each appendix as it applies to the particular symbology set.

5.3 Icon-based symbols. Icon-based symbols represent units, individuals, equipment, installations, activities, cyberspace and meteorological occurrences. An icon-based symbol can be composed of a frame, fill, icon, modifiers and amplifiers (see figure 2) and optionally may be rotated on its anchor point. These elements are located within and around a virtual bounding octagon. The symbol anchor point shall be the center point of the virtual bounding octagon. The components of an icon-based symbol provide information about the standard identity, dimension, status and mission of an operational object. The placement and display options of the various elements are explained in the following paragraphs. When representing unorthodox platforms, select the most appropriate icon from the standard.




FIGURE 2. Icon-based symbol components.

5.3.1 Bounding octagon. The bounding octagon serves as the spatial reference for the relative sizing and placement of frames, icons and modifiers. The default length and height of the bounding octagon is L (see figure 3). L is measured from point to opposite point in the octagon. The bounding octagon shall not be displayed in a symbol. The bounding octagon appears in example symbols throughout this document for clarification purposes only.




FIGURE 3. The bounding octagon.

5.3.1.1 Bounding octagon and frames. The size and placement of frames shall be determined by the size of the bounding octagon. Frame length and height shall vary from 1L to

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

1.5L depending on the particular frame. See figure 4 for extracted examples of sizing requirements of the basic frames relative to the bounding octagon. See 5.3.2 for more information on frames.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.




FIGURE 4. The bounding octagon and frame sizes (illustrative examples).

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

5.3.1.2 The bounding octagon and icons/modifiers. The bounding octagon is divided into three horizontal sectors (main, 1 and 2) to specify positioning and sizing of icons and modifiers. Main icons shall be placed in the main sector, unless expressly noted within a specific symbol draw rule, while modifiers are placed in sectors 1 and 2. To optimize legibility, icons may be enlarged within the constraints of the bounding octagon when one or no modifiers are displayed. Specific icons/symbols, as identified in the standard, require the sectored bounding octagon to be rotated 90 degrees counterclockwise to create vertical sectors. Figure 5 shows the horizontal and vertical sectored bounding octagons. The dimensions of unframed icons shall be the same as framed icons. See 5.3.4 for more information on icons. Modifiers shall not exceed the dimensions of sectors 1 and 2, unless expressly noted within a specific symbol. See 5.3.6 for more information on modifiers.






FIGURE 5. The bounding octagon with horizontal and vertical sectors.

5.3.2 Frame. The frame is the border of a symbol. A frame shall be optionally depicted in only two cases: land equipment and sea surface civilian vessels. Natural event symbols are unframed. When a frame is included in a symbol, its shape indicates the standard identity, dimension and status of the object. A frame can be black or white depending on display background. Table I provides the frame shapes that shall be used during real-world, non-exercise situations. Table II provides the frame shapes that shall be used during exercises. Table III provides the frame shapes that shall be used during simulations. If training tracks are displayed, they shall be identified by adding "-T" to the "X" in the exercise frame (see figure 6).

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.















TABLE I. Frames depicting standard identities and dimensions.

DIMENSION / STANDARD IDENTITY	UNKNOWN	SPACE	AIR	LAND UNIT	LAND EQUIPMENT AND SEA SURFACE	LAND INSTALLATION	SEA SUBSURFACE	ACTIVITY/ EVENT	CYBERSPACE (VIRTUAL)	DISMOUNTED INDIVIDUAL
PENDING (YELLOW)										
UNKNOWN (YELLOW)										
FRIEND (CYAN)										
NEUTRAL (GREEN)										
HOSTILE (RED)										
ASSUMED FRIEND (CYAN)										
SUSPECT (ORANGE)										

Note: Frames displayed with solid lines or alternating black and white dotted lines, as shown above, indicate status as present, i.e., the object exists at the location identified. See table IV for examples of frames depicting planned or anticipated status.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.
























TABLE II. Exercise frames.

DIMENSION / STANDARD IDENTITY	UNKNOWN	SPACE	AIR	LAND UNIT	LAND EQUIPMENT AND SEA SURFACE	LAND INSTALLATION	SEA SUBSURFACE	ACTIVITY/ EVENT	CYBERSPACE (VIRTUAL)	DISMOUNTED INDIVIDUAL
EXERCISE PENDING (YELLOW)										
EXERCISE UNKNOWN (YELLOW)										
EXERCISE FRIEND (CYAN)	N/A									
EXERCISE NEUTRAL (GREEN)	N/A									
FAKER (RED)	N/A									
EXERCISE ASSUMED FRIEND (CYAN)	N/A									
JOKER (ORANGE)	N/A									

Note: Frames displayed with solid lines or alternating black and white dotted lines, as shown above, indicate status as present, i.e., the object exists at the location identified. See table IV for examples of frames depicting planned or anticipated status.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE III. Simulation frames.

DIMENSION / STANDARD IDENTITY	UNKNOWN	SPACE	AIR	LAND UNIT	LAND EQUIPMENT AND SEA SURFACE	LAND INSTALLATION	SEA SUBSURFACE	ACTIVITY/ EVENT	CYBERSPACE (VIRTUAL)	DISMOUNTED INDIVIDUAL
SIMULATED PENDING (YELLOW)										
SIMULATED UNKNOWN (YELLOW)										
SIMULATED FRIEND (CYAN)										
SIMULATED NEUTRAL (GREEN)										
SIMULATED HOSTILE (RED)										
SIMULATED ASSUMED FRIEND (CYAN)										
SIMULATED SUSPECT (ORANGE)										

Note: Frames displayed with solid lines or alternating black and white dotted lines, as shown above, indicate status as present, i.e., the object exists at the location identified. See table IV for examples of frames depicting planned or anticipated status.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.




FIGURE 6. Friend and neutral exercise training tracks.

5.3.2.1 Standard identity. In imagery interpretation, identity is the discrimination between objects within a particular type or class. Standard identity reflects the relationship between the viewer and the operational object being monitored.

a. The Standard Identity categories are Unknown, Assumed Friend, Friend, Neutral, Suspect, and Hostile (see tables I, II, and III). In addition, Pending is a valid condition but not considered a standard identity. Figure 7 shows assumed friend and suspect frames on various backgrounds.

b. A closed frame is used to denote the Land and Sea Surface Dimensions, a frame open at the bottom to denote the Air and Space Dimensions, and a frame open at the top to denote the Sea Subsurface Dimension.

c. A solid line is used when the identity of an entity is certain. A solid line can be used with the standard identifiers of Friend, Hostile, Neutral and Unknown.

d. A dotted line of alternating black and white dots is used when the identity of an entity is uncertain. A dotted line can be used with the standard identifiers of Assumed Friend, Suspect, or the category of Pending. Figure 7 shows assumed friend and suspected frames on various backgrounds.

e. Standard Identity is not applicable to Meteorological Oceanographic (METOC) symbols.




FIGURE 7. Assumed friend and suspect frames on various backgrounds.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

5.3.2.2 Domain. A domain commonly reflects the physical environment where either the entity's primary function is conducted or where the entity is located on, above or below the Earth's surface (space, air, land, or maritime). Additionally, within the information environment, cyberspace is a global domain that permeates all physical domains and includes a virtual dimension. A dimension is a subset or aspect of a particular domain.

- The land domain includes only those graphical representations that are physically located on the land surface or close to the surface. Units, equipment, and installations are dimensions of the land domain.
- The maritime domain includes only those objects that are physically located on or below the sea surface. Sea surface and sea subsurface are dimensions of the maritime domain.
- The air domain is unidimensional and includes those objects that are physically located beginning at the Earth's surface and extending to the altitude where atmospheric effects upon operations become negligible. Aircraft, regardless of Service ownership, shall be depicted in the air domain, while air facilities shall be depicted as land installations. Air-related ground equipment and installations shall be depicted in the land equipment or installation dimensions.
- The space domain is unidimensional and includes the environment above the exosphere. Space-related ground equipment and installations shall be depicted in the land equipment or installation dimensions.
- The virtual cyberspace domain is a part of the information environment consisting of computer networks characterized by the use of electronics and the electromagnetic spectrum. Within the physical domains and the associated dimensions (i.e., units, equipment, installations, sea surface, and sea subsurface), cyberspace entities and their physical presence are depicted using the existing physical domains and dimensions symbology.
- Activity/event, dismounted individuals and unknown are categorized as dimensions. They do not have a direct relationship to a specific domain.

5.3.2.3 Status. Status depicts whether an object exists at the location identified (status is "present" or "confirmed"), will in the future reside at that location (status is "planned" or "anticipated"), or is thought to reside at that location ("suspected"). See table IV.

- The symbol frame shall be a solid or black and white dotted line when indicating a present or confirmed status and a dashed line when indicating anticipated, planned, or suspected status.
- When the frame is assumed friend, suspect, or pending, the status shall not be displayed. In these cases, the frame is depicted as a dotted line.
- For icons that can be framed or unframed, and icons where framing is optional, icons shall be framed when showing status. Status other than "present" or "confirmed" shall not be shown when the symbol icon is unframed or is displayed as a dot.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE IV. Friend frames shown in present and planned status.

DIMENSION / STANDARD IDENTITY	UNKNOWN	SPACE	AIR	LAND UNIT	LAND EQUIPMENT AND SEA SURFACE	LAND INSTALLATION	SEA SUBSURFACE	ACTIVITY/ EVENT	CYBERSPACE	DISMOUNTED INDIVIDUAL
FRIEND (CYAN)										
ASSUMED FRIEND (CYAN)										

5.3.3 Fill. The fill is the interior area within a frame. In framed symbols, color shall provide a redundant indicator with regard to standard identity. If color is not used, the fill is transparent (see figure 8 below).




FIGURE 8. Examples of filled and unfilled symbols.


5.3.3.1 Fill color. In unframed symbols, color shall be the sole indicator of standard identity, excluding text amplifiers. Table I depicts the default colors that shall be used to designate standard identity when colored symbols are either hand-drawn or displayed electronically. See 5.5 for additional information on how color is to be displayed in a symbol.

5.3.4 Icons. The icon is the innermost part of a symbol which provides an abstract pictorial or alphanumeric representation of units, equipment, installations, activities, or operations. This standard distinguishes between icons that must be framed or unframed and icons

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

where framing is optional. See table V for examples of framed and unframed icons. Text icons shall be no more than four characters.

TABLE V. Framed and unframed icons shown in present and planned status.

SYMBOL	FRAMED ICON (PRESENT)	UNFRAMED ICON (PRESENT)	FRAMED ICON (PLANNED)
FRIEND MORTAR			
HOSTILE TANK			

5.3.4.1 Main icons. Main icons are icons that are placed in the main sector of the bounding octagon and normally do not exceed the dimensions of the main sector (see figure 9). For better readability, main icons may be “enlarged” to extend into any unused modifier sector.




FIGURE 9. Examples of main icons.

5.3.4.2 Full octagon icons. Full octagon icons are icons that fill the main and both modifiers do not adhere to the sectors of the bounding octagon and thus do not allow modifiers. They shall not exceed the dimensions of the bounding octagon (see figure 10).




FIGURE 10. Example of full octagon icon.

5.3.4.3 Full frame icons. Full frame icons are main icons that exceed the dimensions of the bounding octagon and touch the interior border of the frame (see figure 11). Modifiers may be used as long as the full frame icon does not require the use of that sector.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.




FIGURE 11. Examples of full frame icons (medical unit).

5.3.5 Invalid symbols. When migrating between standards, if a system's software encounters a SIDC and is unable to translate that into a 2525E symbol code because of a disconnect between the two codes, an inverted question mark within a yellow clover frame shape shall be used (see figure 12).




FIGURE 12. Example of invalid symbol.

5.3.6 Modifiers. A modifier provides an abstract pictorial or alphanumeric representation that is displayed in conjunction with an icon inside the symbol frame or frame area when the frame is not shown. The modifier provides additional information about the object, such as unit, equipment, installation, or activity being displayed. Text modifiers shall be no more than four characters. Any modifier in a symbol that would overlap a main icon, the modifier shall be offset, within its sector, to the main icon.

5.3.7 Amplifiers. An amplifier provides additional information about the symbol and is displayed outside the frame (see table VI). Not all amplifiers are applicable to all symbols. The amplifier field descriptions vary by dimension and are detailed within the respective appendices. The default placement of amplifiers around symbols is shown in each of the dimensions. When an amplifier is displayed, it shall be defined in accordance with the appropriate standard identity or control measure symbol. For the purposes of de-cluttering the display, only essential amplifiers should be used. When multiple text amplifiers are displayed in a single field, only the most critical amplifier should be used. Amplifiers on the left shall be right aligned, amplifiers on the right shall be left aligned and top and bottom amplifiers shall be centered. All text shall be presented in upper case sans serif font. Font size and color should be tested to determine display legibility. Amplifier fields should be used, even if all amplifiers on a particular side of the symbol are not displayed; the order of the amplifier fields shall remain unchanged.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE VI. Amplifier field definitions and maximum display lengths -.

FIELD	FIELD TITLE	DESCRIPTION	Format - Min/Max Data Length and Display Values **# - Numeric, X - Alphanumeric**	Symbol Set	Remarks
A	Symbol Icon	The innermost part of a symbol, comprised of an icon and optional modifiers, that represents a joint military object (see 5.3.4).	Graphic	All	Determined by SIDC positions 11-20.
B	Echelon	An amplifier in a unit symbol that identifies command level (see 5.3.7.1 and table VII).	Graphic	All	
C	Quantity	An amplifier in an equipment symbol that identifies the number of items present. Examples include: 350 Beds 50 Gallons	Alphanumeric - {1,19} [#########] [XXXXXXXXXX]	10, 11, 15, 25, 27, 60	Two-part composite field. Where # is the numeric value [1-999999999], and X is the unit of measure. **Note**: There should be a space between the numeric and the unit of measure values.
D	Task Force Indicator	An amplifier that identifies a unit or activities symbol as a task force (see 5.3.7.2 and figure 14).	Graphic	10	Determined by SIDC position 8.
F	Reinforced or Reduced	An amplifier in a unit symbol that displays (+) for reinforced, (-) for reduced, (±) reinforced and reduced.	Alphanumeric - {1,1}	10	
G	Staff Comments	An amplifier for units, equipment and installations; content is implementation specific.	Alphanumeric - {1,20}	01, 05, 10, 15, 20, 27, 30, 35, 40	
H	Additional Information	An amplifier for units, equipment and installations; content is implementation specific.	Alphanumeric - {1,20}	All	
H1	Unlisted Point Information	An alphanumeric text amplifier used to provide an up to a three-character letter field acronym to describe a point that is not already listed.	Alphanumeric - {1,3}	25	Only used with Action Points (General) control measure. SIDC 130100.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE VI. Amplifier field definitions and maximum display lengths - Continued.

FIELD	FIELD TITLE	DESCRIPTION	Format - Min/Max Data Length and Display Values **# - Numeric, X - Alphanumeric**	Symbol Set	Remarks
J	Evaluation Rating	An amplifier that consists of a one-letter reliability rating and a one-number credibility rating. (See ATP 2-33.4)	Alphanumeric - {2,2} [X][#]	10, 15, 20, 27, 40	**Reliability Ratings:** A-completely reliable B-usually reliable C-fairly reliable D-not usually reliable E-unreliable F-reliability cannot be judged --- **Credibility Ratings:** 1-confirmed by other sources 2-probably true 3-possibly true 4-doubtfully true 5-improbable 6-truth cannot be judged
K	Combat Effectiveness	An amplifier for units and installations that indicates unit effectiveness or installation capability.	Alphanumeric - {2,3}	10, 15, 27	**List of Values**: FO - Fully Operational SO - Substantially operational MO - Marginally operational NO - Not operational UNK - Unknown
L	Signature Equipment	An amplifier for hostile equipment; “!” indicates detectable electronic signatures.	Alphanumeric - {1,1}	15	The amplifier displayed is the exclamation mark "!".
M	Higher Formation	An amplifier for units that indicates number or title of higher echelon command (corps are designated by Roman numerals).	Alphanumeric - {1,21}	10	
N	Hostile (Enemy)	An amplifier for equipment; letters "ENY" denote hostile symbols.	Graphic	15, 25	Determined by SIDC position 4. **Note**: This amplifier must be used when displaying enemy/hostile control measures on monochromatic displays

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE VI. Amplifier field definitions and maximum display lengths - Continued.

FIELD	FIELD TITLE	DESCRIPTION	Format - Min/Max Data Length and Display Values **# - Numeric, X - Alphanumeric**	Symbol Set	Remarks
P	IFF/SIF/AIS	An amplifier displaying IFF/SIF/AIS Identification modes and codes.	Alphanumeric - {4,4} MODE 1:##, where ## is a two-digit octal number (0-7). **The rightmost digit is limited to 0-3.** [1:##]	01, 10, 15, 27, 30, 35	Note: 'MODE' is not required when displaying.
			Alphanumeric - {6,6} MODE 2:####, where #### is a four-digit octal number (0-7). [2:####]		
			Alphanumeric - {6,6} MODE 3:####, where #### is a four-digit octal number (0-7). [3:####]		
			Alphanumeric - {6,6} MODE 5:####, where #### is a 4-digit hexadecimal number (0-F). **The leftmost digit is limited from 0 to 3.** [5:####]		
			Alphanumeric - {8,8} MODE S:XXXXXX [S:XXXXXX]		
			Alphanumeric - {x,x} AIS IMO:XXXXXX [S:XXXXXX]		

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE VI. Amplifier field definitions and maximum display lengths - Continued.

FIELD	FIELD TITLE	DESCRIPTION	Format - Min/Max Data Length and Display Values **# - Numeric, X - Alphanumeric**	Symbol Set	Remarks
Q	Direction of Movement Indicator	An amplifier consisting of a line with arrow that identifies the direction of movement or intended movement of an object (see 5.3.7.9 and figure 14).	Graphic (Alphanumeric for exchange only)	10, 15, 20, 25, 27	If the exchanged value has a length of 7 characters, the value will be parsed as degrees. The allowed range is 000-360. The “DDD” DGT (True North) DGM (Magnetic north) and DGG (Grid North). The degrees must be prefixed with 0 to form a 3-digit number. e.g. “026 DGT”. 2. If the exchanged value has a length of 8 characters, the value will be parsed as mils. The “MMM” is the north reference: MGT (True North) MGM (Magnetic north) and MGG (Grid North). The mils must be prefixed with 0 to form a 4-digit number. e.g.: “0150 MGT”
R	Mobility Indicator	An amplifier that depicts the mobility of an object not intrinsic to the entity itself (see 5.3.7.9, figure 14 and table IX).	Graphic	10	Determined by SIDC positions 9-10
R2	SIGINT Mobility Indicator	An amplifier that indicates the mobility of a SIGINT unit.	Alphanumeric - {1,1}	50, 51, 52, 53, 54	**List of Values**: M = Mobile, S = Static U = Uncertain.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE VI. Amplifier field definitions and maximum display lengths - Continued.

FIELD	FIELD TITLE	DESCRIPTION	Format - Min/Max Data Length and Display Values **# - Numeric, X - Alphanumeric**	Symbol Set	Remarks
S	Headquarters Staff Indicator	An amplifier for units, installations and activities that identifies them as a headquarters (see figure 14 and figure 13).	Graphic	10, 20, 40	Determined by SIDC position 8.
S2	Offset Location Indicator	An amplifier used to indicate the offset or precise location of a single point symbol (see 5.3.7.5, 5.3.12, and figure 14).	Graphic	10, 20, 25, 27, 40	Determined by individual system implementations.
T	Unique Designation	An amplifier that uniquely identifies a particular symbol or track number. Identifies acquisitions number when used with SIGINT symbology.	Alphanumeric - {1,30}	All	
T1	Lines - Unique Identifier or Primary Purpose	Lines - Second unique identifier for boundaries.	Alphanumeric - {1,30}	25	Only for use with Boundary Control measure symbols.
		Lines - Other than phase lines that have a specific purpose, (for example, restrictive fire line RFL), should have the primary purpose labelled on top of the line at both ends of the line inside the lateral boundaries or as often as necessary for clarity.			
	Points - Purpose or Servicing Unit	Points - Provides the unit servicing the point	Alphanumeric - {1,7}		For use with point symbols.
T2	Controlling Headquarters	An amplifier used to provide the designation of the Establishing Headquarters.	Alphanumeric - {1,7}	25	Used with Fire Support Control Measures only.
V	Type	An amplifier for equipment that indicates types of equipment.	Alphanumeric - {1,24}		**Example**: AH-64 for Attack Helicopter

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE VI. Amplifier field definitions and maximum display lengths - Continued.

FIELD	FIELD TITLE	DESCRIPTION	Format - Min/Max Data Length and Display Values **# - Numeric, X - Alphanumeric**	Symbol Set	Remarks
W	Date/Time Group (DTG)	An amplifier for displaying a date-time group (DDHHMMSSZMONYYYY) or (DDHHMMZMMMYYYY) or “O/O” for On Order. Field "W" is used to provide DTG or if used with field "W1" the start of a period of time. Field "W1" is used to provide the end of a period of time.	Alphanumeric - {3,16}	10, 15, 20, 25, 27, 40, 45	The date-time group is composed of a group of six numeric digits with a time zone suffix and the standardized three-letter abbreviation for the month followed by four digits representing the year. The first pair of digits represents the day; the second pair, the hour; the third pair, the minutes. For automated systems, two digits may be added before the time zone suffix and after the minutes to designate seconds (see 5.3.7.8).
W1				25	
X	Altitude/Depth	An amplifier that displays either altitude, flight level, depth for submerged objects or height of equipment or structures on the ground, the minimum, maximum and/or specific altitude (in feet or meters in relation to a reference datum) or depth (for submerged objects in feet below sea level). See 5.3.7.6 for content.	Alphanumeric - {3,16} Three formats are allowed: (e.g. MSL, 9000FTAMSL, FL280.) 1. Base reference point - [XXX]: “MSL” (Mean Sea Level) or “GL” (Ground Level). 2. Flight level - [FL###]. FL is fixed text, "###" is the flight level (range 0-999).	14	SM = Statute Miles DM = Data Miles

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE VI. Amplifier field definitions and maximum display lengths - Continued.

FIELD	FIELD TITLE	DESCRIPTION	Format - Min/Max Data Length and Display Values **# - Numeric, X - Alphanumeric**	Symbol Set	Remarks
			3. Height from a reference point. [###### UU RRRR] "######" is the value, (Range 0-999999) "UU" is the unit of measurement, (FT, M, KM, SM,DM). "BBBB" is the reference point, (AGL, AMSL, BMSL and HAE).		
Y	Location	An amplifier that displays a symbol's location in degrees, minutes and decimal minutes (or in MGRS, GARS, or other applicable display formats).	Alphanumeric - {3,16}	10, 15, 20, 25, 27, 30, 40	Exchange format is implementation specific.
Z	Speed	An amplifier that displays velocity (see 5.3.7.7).	Alphanumeric - {5,9} [#####] [XXX]	8	Two-part composite field. Where # is the numeric value [1-999999999], and XXX is the unit of measure (KPH, KPS, MPH, NMH, KTS). **Note**: There should be a space between the numeric and the unit of measure values.
AA	Special C2 Headquarters	A amplifier that is contained inside the frame in place of the main icon and contains the name of the special C2 Headquarters.	Alphanumeric - {1,9}	10	Examples: Named command such as SHAPE, PACOM, and joint, multinational, or coalition commands such as CJTF, JTF, or MJTF.
AB	Feint/Dummy indicator	An amplifier that identifies an offensive or defensive unit, intended to draw the enemy's attention away from the area of the main attack.	Graphic	10, 15, 20, 27	Determined by SIDC position 8.
AD	Platform Type	An amplifier that identifies the electronic identification for a pulsed or non-pulsed electromagnetic emission.	Alphanumeric - {5,5}	10, 15	**List of Values**: ELNOT = Electronic intelligence notation CENOT = Communications intelligence notation
AE	Equipment Teardown Time	An amplifier that identifies equipment teardown time in minutes.	Numeric – {1,3}	15,52	

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE VI. Amplifier field definitions and maximum display lengths - Continued.

FIELD	FIELD TITLE	DESCRIPTION	Format - Min/Max Data Length and Display Values **# - Numeric, X - Alphanumeric**	Symbol Set	Remarks
AF	Common Identifier	An amplifier to provide a common name used to identify an entity.	Alphanumeric - {1,12}	10, 15, 27	Example: “Hawk” for Hawk SAM system.
AG	Auxiliary Equipment Indicator	An amplifier for equipment that indicates the presence of a towed sonar array (see 5.3.7.11, figure 14 and table IX).	Graphic	35	Determined by SIDC positions 9-10.
AH	Area of Uncertainty	An amplifier that indicates the area where an object is most likely to be, based on the object’s last report and the reporting accuracy of the sensor that detected the object (see 5.3.7.13.1 and figure 18.	Graphic (Alphanumeric for exchange only)	01, 05 10, 15, 20, 25, 27, 30, 35, 40	The amplifier can be displayed as an ellipse, a bearing box, or a line of bearing, depending on the report received for the object.
AI	Dead Reckoning Trailer	An amplifier that identifies where an object should be located at present, given its last reported course and speed (see 5.3.7.13.2).	Graphic	01, 05, 10, 15, 20, 25, 27, 30, 35, 40	Locally derived information. This datum is not exchanged.
AJ	Speed Leader	An amplifier that depicts the speed and direction of movement of an object (see 5.3.7.13.3 and figure 18).	Graphic	01, 02, 30, 35	Land units and equipment use the Direction of Movement and Speed amplifiers for this information.
AK	Pairing Line	An amplifier that connects two objects and is updated dynamically as the positions of the two objects change (see 5.3.7.13.4 and figure 18).	Graphic	N/A	
AL	Operational Condition	An amplifier that indicates operational condition or capacity.	Graphic	01, 05,10, 15, 20, 30, 35	Determined by SIDC position 7.
AM	Distance	An amplifier that displays a minimum, maximum, or a specific distance (range, radius, width, length, etc.), in meters.	Alphanumeric - {3,9} [#] [X]	25	"#" is the value (range 0-99999) XXX is the distance unit. Note: there should be a space between the integer and the unit of measure values. Where more than one distance is specified the AM amplifier will be suffixed with a numeric entry, e.g. AM1, AM2.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE VI. Amplifier field definitions and maximum display lengths - Continued.

FIELD	FIELD TITLE	DESCRIPTION	Format - Min/Max Data Length and Display Values **# - Numeric, X - Alphanumeric**	Symbol Set	Remarks
AN	Azimuth	An amplifier that displays an angle measured from true north to any other line in degrees.	Alphanumeric - {7,8} [#####] [XXX]	25	For Degrees entries. XXX DGT, where XXX is degrees from 000-359 and DGT is referenced to TRUE North. For Mils entries. XXXX MGT, where XXXX is MILS from 0000-6399 and MGT is referenced to TRUE North. Where more than one angle is specified the AN amplifier will be suffixed with a numeric entry, e.g. AN1, AN2.
AO	Engagement Bar	An amplifier placed immediately atop the symbol. May denote: 1) local/remote status 2) engagement status 3) weapon type.	Composite list of values Alphanumeric - {6,10} A:BBB-CC	01, 05, 10, 30, 35	See 5.3.7.15.3 for explanation of engagement bar structure and codes. A - Type of Engagement BBB - Engagement Stage CC - Type of Weapon Assignment
AP	Target Number	An amplifier used in Fire Support operations to uniquely designate targets in accordance with STANAG 2934.	Alphanumeric - {6,6} [XX][####]	25	Two-part composite field. Where positions 1-2 are text, and positions 3-6 are numeric.
AP1	Target Number Extension	An amplifier used to identify a target number extension which is a sequentially assigned number identifying the individual elements in a target (MIL-STD-6017),	Numeric – {2,3} [-##]	25	Position 1 is a dash (-) and positions 2-3 are numbers, from 1 through 15. It is applicable only to the “Point or Single Target” symbol. It is conditional upon the presence of the Target Number amplifier and is visually displayed appended to the Target Number amplifier.
AQ	Guarded Unit	An amplifier used during ballistic missile defense. Some tracks are designated as guarded by a particular unit.	Alphanumeric - {6,6} [XX]	30	**Single value:** BG - Guarded Unit
AR	Special Designator	An amplifier that identifies special track designators.	Alphanumeric - {3,3}	10, 30, 35	**List of values:** NRT - Non-Real Time. SIG - Tactically Significant Tracks.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE VI. Amplifier field definitions and maximum display lengths - Continued.

FIELD	FIELD TITLE	DESCRIPTION	Format - Min/Max Data Length and Display Values **# - Numeric, X - Alphanumeric**	Symbol Set	Remarks
AS	Country	A three-letter code that indicates the country of origin of the organization (US systems shall use GENC).	Alphanumeric - {3,3}	All	Determined by SIDC positions 28-30.
AT	Capacity of Installation	Capacity of installation displayed.	Alphanumeric - {1,19} [#########] [XXXXXXXXXX]		Two-part composite field. Comprised of: Quantity 0-99999999 followed by the unit of measure. e.g. 400 Beds
AV	Leadership	Identifies Leadership (ONLY IN DISMOUNTED INDIVIDUAL)	Graphic		Determined by SIDC positions 9-10.
AW	Headquarters Element	An amplifier that indicates what type of element of a headquarters is being represented, such as TOC, MAIN2.	Alphanumeric {0,8}	10	
AX	Installation Composition	Indicates the component type of the installation	Alphanumeric {3,7}	20	**List of Values:** DEVELOP - Development. RSRCH - Research. PROD - Production. SVC - Service. STORE - Storage. UTIL - Utility.
AY	Network Identifier	Indicates the network the entity has privileges within.	Alphanumeric		The colour of the graphic shall be assignable by the operator.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

5.3.7.1 Headquarters staff amplifier. The headquarters staff amplifier is a line extending downward from the left side of the frame that identifies units, equipment and installations as headquarters. The headquarters staff amplifier shall extend a distance of one octagon height below the bottom of the frame. See figure 13.




FIGURE 13. Headquarters staff amplifier.

Note: 1. Command is a unit or units, an organization, or an area under the command of one individual. It does not correspond to any of the other echelons.

5.3.7.2 Echelon indicator. The echelon indicator provides a graphic representation of command level and is used to show the element echelon on installations, boundary lines, lines and areas. Echelon indicator codes are listed in table VII. The indicator is represented in field B as defined in table VI.

TABLE VII. Echelon amplifiers.

AMPLIFIER	DESCRIPTION
Ø	TEAM/CREW
•	SQUAD
••	SECTION
•••	PLATOON/DETACHMENT
I	COMPANY/BATTERY/TROOP
I I	BATTALION/SQUADRON
I I I	REGIMENT/GROUP
X	BRIGADE
X X	DIVISION
X X X	CORPS
X X X X	ARMY
X X X X X	ARMY GROUP
X X X X X X	THEATER
+ +	COMMAND

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.




FIGURE 14. Graphic amplifiers for military symbols.

5.3.7.3 Task force indicator. The task force indicator is a bracket that identifies a unit or activities symbol as a task force. The indicator is represented in field D as defined in table VI and is positioned as shown in figure 14.

5.3.7.4 Feint/decoy/dummy indicator. The feint, decoy or dummy indicator is a dashed inverted “V” that identifies offensive or defensive units, equipment and installations, signal intelligence, activities, and control measures. It is intended to draw the enemy's attention away from the area of the main attack, and/or an imitation of a person, object or phenomenon, which is intended to deceive hostile surveillance or detection systems or mislead the adversary. The indicator is represented in SIDC set A, position 8 "HQ / Task Force / Dummy when populated with “1” to specify the symbol is a “Feint/Decoy/Dummy”. This can apply to the SIDC for any symbol in MIL-STD-2525E as shown in figure 14, and is constructed and positioned as follows.

5.3.7.4.1 Construction. The feint, decoy, or dummy indicator shall be rendered as an isosceles triangle (two equal length sides and two equal angles), where angles “A” and “C” (the two base angles) = 45°, angle “B” (the top angle) = 90°, and the length of line AB is equal to the length of line BC (see figure 15). Line AC (gray) in figure 15 shall not be rendered.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.




FIGURE 15. Feint, decoy, or dummy indicator construction.

5.3.7.4.2 Line style. The line style of the feint, decoy, or dummy indicator when used with control measure symbols shall always be rendered as dashed lines, even when the status of the symbols is present and the symbol line style is solid.

5.3.7.4.3 Position. On a geographically referenced system display, the feint, decoy, or dummy indicator shall always be rendered on top of the symbol when the display is oriented north up. If the system display has the capability to rotate (i.e., a moving map display inside a vehicle in motion), the feint, decoy, or dummy indicator shall rotate with the base symbol.

5.3.7.4.4 Position for icon-based symbols. See 5.3.2 that describes which types of icon-based symbols can be rendered unframed.

5.3.7.4.4.1 Unframed icon-based symbol position. The feint, decoy, or dummy indicator when used with unframed icon-based symbols shall be positioned as shown below in figure 16. Point “A” shall be rendered 0.4L above the top edge of the bounding octagon and aligned with the left edge of the bounding octagon. Point “C” shall be rendered 0.4L above the top edge of the bounding octagon and aligned with the right edge of the bounding octagon. The spacing above the top of the bounding octagon will support any authorized amplifier(s) to be applied to the unframed icon-based symbol without overlapping the indicator.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.




FIGURE 16. Position of the feint, decoy, or dummy indicator for unframed icon-based symbols.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.




FIGURE 17. Position of the feint, decoy, or dummy indicator for framed icon-based symbols.

5.3.7.5 Offset/precise location amplifier. The offset/precise location indicator is used when placing an object away from its actual location. The offset/precise location indicator is a system display de-cluttering technique (see 5.3.13); it is not exchanged between or shared among systems. The offset/precise location indicator is a three point line extending from the anchor point of the symbol. Point 1 is the anchor point of the offset symbol. Point 3 is the actual geographic location. Point 2 is an elbow between the symbol anchor point and the actual geographic location. See figure 14.

5.3.7.6 Altitude/depth modifier. This field may contain alternate value formats. Enter a description of the altitude/depth (X) using one of the following.

5.3.7.6.1 Altitude base reference point. Legal values are “GL” ground level and “MSL” mean sea level.

5.3.7.6.2 Relative altitude. The relative altitude is a composite field consisting of multiple parts: the numeric altitude, the altitude unit of measurement and the altitude vertical dimension. Legal values for the numeric altitude are (minus) -99999 through 99999 in increments of 1. Legal values for altitude units of measure are feet “FT,” meters “M,” kilometers “KM,” and statute miles “SM.” The legal value for the depth unit of measure is feet “FT and meters “M.” Legal values for the vertical dimension are “AGL” above ground level, “AMSL” above mean sea level, “HAE” height above ellipsoid and “BMSL” below mean sea level. BMSL is used only for depth of submerged objects, reported in feet. A space may be added between the values in the field to make it easier to read.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

Examples: 1250 FT AGL, 1000 FT AMSL, 1524 M HAE, 35760 FT BMSL.

5.3.7.6.3 Flight level. By definition, flight level (FL) is, “Surfaces of constant atmospheric pressure which are related to a specific pressure datum, 1013.2 mb (29.92 in) and are separated by specific pressure intervals. (Flight levels are expressed in three digits that represent hundreds of feet; e.g., flight level 250 represents a barometric altimeter indication of 25,000 feet and flight level 255 is an indication of 25,500 feet.)” The legal value for flight level indicator is “FL.” A space may be added between the values in the field to make it easier to read. The legal value for context quantity is 000-999, in increments of one.

Example: FL 290.

5.3.7.6.4 Multiple instances of altitude/depth modifiers. When multiple instances of the “X” modifier are present in a single instance of a symbol or graphic (ex., Minimum Altitude “X,” Maximum Altitude “X1”), for display purposes, the fields may be separated by a hyphen “-,” or a space, hyphen and space “ - .”

Examples:
500 FT AGL – 1250 FT AGL

25 FT AMSL –
150 FT AMSL

FL 250 – FL 290

MSL –
35760 FT BMSL

5.3.7.7 Speed amplifier. The speed amplifier is used to display a unit or equipment velocity. The amplifier has a specific format as follows.

The first part of this eight-character (maximum length) amplifier shall be a numeric value (quantity) in the range 0 through 99999 or any combination of four or fewer digits and a significant decimal point. There is a 5-character maximum for the numeric portion of this amplifier. The allowable entries for the numeric portion of this amplifier are as follows. The legal entries are a decimal point and numbers. The legal range of values for the numeric portion are zero (0) through 99999. The minimum length of this portion of the amplifier is 1; the maximum is 5. The minimum decimal place is zero (0); the maximum decimal place is four (4).

The second part of this eight-character (maximum length) amplifier shall be the speed/velocity unit of measure. Legal entries for this portion of the amplifier shall be “KPH” (kilometers per hour), “MPS” (meters per second), “KTS” (knots per hour), or “MPH” (miles per hour).

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.





Examples: 220KPH = 220 kilometers per hour
974.5MPS = 974.5 meters per second
18.75KTS = 18.75 knots per hour
5MPH = 5 miles per hour

5.3.7.8 Date-time group. Date-time group (DTG) is defined as the date and time expressed in an alphanumeric combination. The alphanumeric combination used is day-time-time zone-month-year. The alphanumeric combination can be displayed in a number of ways. In its longest form, sixteen characters, it is composed of eight digits (first pair of digits denotes the date, second pair denotes the hours, third pair denotes the minutes and fourth pair denotes the seconds) followed by the time zone suffix, followed by a three-letter month abbreviation and four digits for the year: DDHHMMSSZMONYYYY. It can also be expressed in shorter forms by removing characters, such as DDHHMMZMONYY. On order (O/O) is a valid substitute for DTG.

5.3.7.9 Direction of movement amplifier. The direction of movement amplifier is an arrow or staff identifying the direction of movement or intended movement of an object. For land symbols, the amplifier is an angled arrow extending downward from the bottom center of the frame or icon and pointing in the direction of movement. For all other symbols, the amplifier is an arrow extending from the center of the frame or icon and pointing in the direction of movement (see figure 14).






5.3.7.10 Mobility indicator. The mobility indicator, which is only used for equipment, depicts the mobility feature of an object, as shown in table VIII. This indicator identifies mobility other than that intrinsic to the equipment itself. For example, the symbol for a self-propelled howitzer moving by train would include a railway mobility indicator, while the symbol for a self-propelled howitzer, a tank or other tracked vehicle would not have a mobility indicator. The indicator is represented in field R as defined in table VI and is positioned as shown in figure 14.

TABLE VIII. Equipment mobility indicators.

DESCRIPTION	MOBILITY SYMBOL	UNFRAMED	UNKNOWN	FRIEND	NEUTRAL	HOSTILE
WHEELED (LIMITED CROSS-COUNTRY)						
WHEELED (CROSS-COUNTRY)						
TRACKED						

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE VIII. Equipment mobility indicators - Continued.

DESCRIPTION	MOBILITY SYMBOL	UNFRAMED	UNKNOWN	FRIEND	NEUTRAL	HOSTILE
WHEELED AND TRACKED COMBINATION						
TOWED						
RAILWAY						
OVER-SNOW (PRIME MOVER)						
SLED						
PACK ANIMALS						
BARGE						
AMPHIBIOUS						

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

5.3.7.11 Auxiliary equipment indicator. The auxiliary equipment indicator, which is only used for towed equipment, depicts the mobility feature of an array, as shown in table IX. The indicator is represented in field AG as defined in table VI and is positioned as shown in figure 14.

TABLE IX. Auxiliary equipment indicators.

DESCRIPTION	MOBILITY SYMBOL	UNFRAMED	UNKNOWN	FRIEND	NEUTRAL	HOSTILE
TOWED SONAR ARRAY (SHORT)						
TOWED SONAR ARRAY (LONG)						

5.3.7.12 Text modifiers. Table VI defines the specific content, length and type of each text modifier. Not all text modifiers are applicable to all symbols. However, when any such modifier is displayed, it shall be defined in accordance with the contents of table VI and positioned in accordance with individual appendices. Air/space and sea track numbers are included in field T. Staff comments and additional information are contained in fields G and H, with the content of these fields being implementation specific so long as the maximum number of characters in each field is not exceeded. Although text modifiers are normally displayed around the symbol, the special C2 headquarters indicator (field AA as defined in table VI) is contained inside the frame, as seen in figure 13.

5.3.7.13 Dynamic graphic amplifiers. A dynamic amplifier is a line or area graphic whose size and placement are based on the attributes of the object represented by the symbol and can change as these attributes and the scale of the background change. An example of each dynamic graphic amplifier is shown in figure 18. These examples are notional; the size and placement of each amplifier will vary based on the attributes of the object.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.




FIGURE 18. Dynamic graphic amplifiers for icon-based symbols.

Dynamic graphic amplifiers may be color-coded based on the attributes of the symbol. In cases such as ballistic missile target status as indicated in the Engagement/Target Bar (field AO), the symbol's track history, projected trajectory (similar to dead reckoning), threat fan and its projected impact ellipse should reflect target status of the ballistic missile. Likewise, if threat is denoted by color via the operational condition/status bar (field AL), associated symbols amplifier graphics should reflect the color status indicated in the operational condition/status field. Figure 19 illustrates an example of dynamic amplifiers being color coded.




FIGURE 19. Color coded dynamic amplifiers.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

5.3.7.13.1 Area of uncertainty amplifier. The area of uncertainty (AOU) amplifier displays the area where an object is most likely to be located, based on the object's last report and the reporting accuracy of the sensor that detected the object. The AOU amplifier can be displayed as an ellipse, a bearing box, or a line of bearing, depending on the report received for the object.

5.3.7.13.1.1 Ellipse AOU amplifier. The ellipse AOU amplifier is a rotated ellipse whose center is the last reported position for the object. The ellipse is shown as a solid line whose draw parameters are based on the attributes of the sensor that detected the object. The symbol for the object is displayed at the center of the ellipse.

5.3.7.13.1.2 Bearing box AOU amplifier. The bearing box AOU amplifier is a rotated rectangle whose center is the last reported position for the object. The rectangle is shown as a solid line whose draw parameters are based on the attributes of the sensor that detected the object. The symbol for the object is displayed at the center of the box.

5.3.7.13.1.3 Line of bearing AOU amplifier. The line of bearing AOU amplifier is a solid line whose rotation represents the bearing of the object and whose length is determined by its range estimate. The amplifier has a single bearing "center" line and may include bearing error "V" lines. The bearing error determines the placement of the "V" lines and is the angle from the bearing line to one of the bearing error lines. The bearing error lines are dotted and symmetric on either side of the bearing line. The length of the bearing error lines is equal to the bearing length.

5.3.7.13.2 Dead reckoning trailer amplifier. An object can be displayed at its last reported position, or it can be displayed at its dead reckoned position. Dead reckoning (DR) uses the course and speed of an object from the last report and calculates where the object should be at present. The object is then plotted where it should be at the present time, assuming the course and speed are unchanged. The DR trailer amplifier can be displayed as a line or circle, depending on the report received for the object. Because DR calculates where the object should be at present, the status of the symbol for the object is shown as "present," rather than "planned."

5.3.7.13.2.1 Line DR trailer amplifier. The line DR trailer amplifier is a dotted line that extends from the last reported position for the object to its dead reckoned position. The dotted line is a series of uniformly sized and shaped dots, with the symbol for the object displayed at its dead reckoned position.

5.3.7.13.2.2 Farthest-on circle DR trailer amplifier. The farthest-on circle DR trailer amplifier is a dotted circle indicating the furthest an object could be after a given time traveling at its top speed in any direction. The center of the circle is the last reported position for the object, and the radius is the maximum distance the object could travel based on its last reported position and speed; the symbol for the object is displayed at the center of the circle.

5.3.7.13.3 Speed leader amplifier. The speed leader amplifier is a line extending from the center of the frame or icon and pointing in the direction of movement; the length of the line is based on a combination of actual speed and object type. For example, the length of the speed leader for a submarine might be 1/4 inch if its speed is less than 15 knots, 1/2 inch if its speed is between 15 and 30 knots and 3/4 inch if its speed is more than 30 knots, while the length of the

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.


speed leader for an aircraft might be 1/4 inch if its speed is less than 300 knots, 1/2 inch if its speed is between 300 and 600 knots and 3/4 inch if its speed is more than 600 knots. The speed leader represents both speed and direction of movement information in a single amplifier; by contrast, the static direction of movement amplifier is a fixed length and identifies only the direction of movement of the object.

5.3.7.13.4 Pairing line amplifier. The pairing line amplifier is a line that connects two objects and is updated dynamically as the positions of the two objects change. For example, a pairing line might connect an active missile to the associated hostile aircraft. A pairing line is drawn from the center of the frame or icon for the first object to the center of the frame or icon for the second object. The color and style (e.g., solid, dotted) of the line can vary based on the specific context in which the amplifier is used.

5.3.7.13.5 Dynamic towed sensor array amplifier. The dynamic towed sensor array amplifier is a line extending from the center of a symbol to the center of towed acoustic array. The length of the line is based upon the distance between the stern of the towing ship and the center of the towed acoustic array. The orientation of the towed sensor array amplifier shall be 180 degrees from the speed leader of the object. A solid circle, representing the center of the acoustic array, shall be at the terminus of the towed sensor array amplifier.

5.3.7.14 Operational condition amplifier. The operational condition amplifier provides a graphic representation of an entity's (equipment or installation) operational condition. Operational condition amplifiers are shown in table X and defined in the appendix for each symbology set. An alternative color representation is shown in table XI.






TABLE X. Operational condition amplifiers for icon-based symbols.

DIMENSION / OPER. CONDITION	AIR/SPACE	SURFACE					SEA SUBSURFACE	CYBERSPACE (Virtual)
		LAND			DISMOUNTED INDIVIDUAL	SEA SURFACE		
		UNITS	EQUIPMENT	INSTALL ATIONS				
FULLY CAPABLE								
DAMAGED/ RENDERED INEFFECTIVE[1]								
DESTROYED								

Notes: 1. The "Rendered Ineffective" operational condition amplifier shall be used when equipment capable of inflicting injury and/or death (IEDs or mines) is known to have been defused or rendered inoperable while under the control of friendly forces. The "Damaged" operational condition amplifier shall be used where "Rendered Ineffective" does not apply.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE XI. Alternate operational condition amplifiers for icon-based symbols.

DIMENSION / OPER. CONDITION	AIR/SPACE	SURFACE						
		LAND			DIMOUNTED INDIVIDUAL	SEA SURFACE	SEA SUBSURFACE	CYBERSPACE (Virtual)
		UNITS	EQUIPMENT	INSTALL ATIONS				
FULLY CAPABLE								
DAMAGED/ RENDERED INEFFECTIVE[1]								
DESTROYED								
FULL TO CAPACITY[2]								

Notes: 1. The "Rendered Ineffective" operational condition amplifier shall be used when equipment capable of inflicting injury and/or death (IEDs or mines) is known to have been defused or rendered inoperable while under the control of friendly forces. The "Damaged" operational condition amplifier shall be used where "Rendered Ineffective" does not apply.

2. Associated with a symbolized object where its capacity can be measured and the status of that capacity is relevant.

5.3.7.15 Engagement amplifier bar. The engagement amplifier bar may be used to designate engagements and/or to indicate targets. Both may be done in conjunction where depicted targets contain engagement information.

5.3.7.15.1 Engagement designation using the engagement amplifier bar. Engagement bars are positioned immediately atop the hostile target and its assigned friendly track. Example depictions of engagement bars are illustrated in figure 20 and figure 21.




FIGURE 20. Example local engagement scenarios: engage (left), missile in flight (right).

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.




FIGURE 21. Example engagement scenario: participating units.

The engagement bar may contain information on 1) remote/local engagement; 2) stage of the engagement (i.e., assign/cover, engage, hold fire, cease fire, cease engage, break engagement, missile in flight); and 3) type of weapon assignment (i.e., missile, gun, torpedo). The color of the engagement bar should be identical to its symbol's standard identity. Therefore, engagement bars for a hostile target and a friendly participating unit would have red and blue engagement bars, respectively (see figure 22 and figure 23). The colors of the engagement bars should have the same RGB value as its respective symbol. All engagement bars should have a black or white frame based on providing optimal contrast between the colored amplifier bar and the map background.

5.3.7.15.2 Target designation using the engagement amplifier bar. If the engagement amplifier bar is used to designate targets, non-targets or expired targets, a different coloring schema shall be used. Hostile tracks which are deemed targets shall have a red bar (RGB: 255, 0, 0) to indicate target. For hostile tracks deemed to be non-targets, white (RGB: 255, 255, 255) should be used to indicate non-target. Finally hostile tracks which have expired shall be colored orange (RGB: 255, 120, 0). Figure 22 depicts the three target designations.




FIGURE 22. Engagement amplifier bar colors for target designation.

5.3.7.15.2.1 For hostile targets. If engagement text is incorporated, either white (RGB: 255, 255, 255) or black (RGB: 0, 0, 0) may be used to denote engagement status. Otherwise, for non-targets and expired tracks, engagement status within the engagement amplifier bars shall remain black (see figure 23).

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.




FIGURE 23. Engagement amplifier bar text colors for target designation.

5.3.7.15.3 Engagement amplifier bar structure. The engagement amplifier shall be arranged as follows: A:BBB-CC, where A (1 character) denotes a local versus remote engagement, BBB (up to 3 characters) denotes engagement state and CC (up to 2 characters) denotes weapon deployment/asset control.

5.3.7.15.3.1 Remote and local engagements. Remote and local engagements may be identified in the engagement amplifier (part A of A:BBB-CC). A remote engagement is defined as an engagement assigned outside of own ship control. A local engagement is defined as an engagement assigned to own ship. Local engagements shall have no letter assignment in the A:BBB-CC engagement bar; whereas, remote engagements shall be denoted as “R” in the engagement bar. In the case of multiple engagements, there may be a mixture of both local and remote engagements. In such cases, “B” shall be denoted to indicate both local and remote engagements and shall be used in conjunction with the multiple engagements amplifier (MLT).

5.3.7.15.3.2 Engagement stage. Engagement stage may be identified by up to a three-character code (part BBB of A:BBB-CC). Typical engagement stages to depict include assign/cover, engage and missile(s) in flight. Other engagement events such as hold fire, cease fire, cease engage, break engagement, terminate engagement, management by exception, management by exception less than threshold and others may be depicted in the engagement amplifier. In the case of multiple engagements where no one specific engagement is highlighted, “MLT” may be used to indicate multiple engagements. In conjunction with the MLT designation, the number of engagements shall be listed in the subsequent CC field (see 5.3.7.15.3.3). Table XII depicts engagement stage codes.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE XII. Engagement[1] stage codes.

ENGAGEMENT STAGE	CODE
ASSIGN/COVER	ASN
ENGAGE	ENG
MISSILE IN FLIGHT	MIF
CEASE FIRE	CF
CEASE ENGAGE	CE
HOLD FIRE	HF
TERMINATE ENGAGEMENT	TE
BREAK ENGAGEMENT	BE
MANAGEMENT BY EXCEPTION (MBE)	MBE
MBE LESS THAN THRESHOLD	M<T
MULTIPLE ENGAGEMENTS[2]	MLT

Notes: 1. The term "Engagement" as used in 5.3.7.15.3.2 denotes both air-to-air and air-to-ground/air-to-surface activities.
2. Number of engagements shall be represented in CC field (see 5.3.7.15.3.3).

5.3.7.15.3.3 Weapons assignment or deployment. Weapons assignment or deployment may also be presented in the engagement amplifier (part CC of A:BBB-CC). Either deployed weapons such as missiles, guns and torpedoes or controlled assets such as unmanned systems, interceptor aircraft and attack aircraft may have representation in the engagement bar. In the case where multiple engagements are represented within a single engagement amplifier bar, the number of engagements starting from "02" shall be used in the CC field. Table XIII depicts weapon and asset codes.

TABLE XIII. Weapon and asset codes.

WEAPON/ASSET	CODE
MISSILE	M
BALLISTIC MISSILE	BM
CRUISE MISSILE	CM
GUN	GN
TORPEDO	T
ATTACK AIRCRAFT	A
COMBAT AIR PATROL (DEFENSIVE COUNTER AIR)	C
DEFENSIVE COUNTER AIR (COMBAT AIR PATROL)	D
UNDERSEA WARFARE (USW)/ANTISUBMARINE WARFARE (ASW) ENGAGEMENT	UW
MINE WARFARE (MIW) ENGAGEMENT	MW
SURFACE WARFARE (SUW) ENGAGEMENT	SW
ELECTROMAGNETIC ATTACK	EA
ELECTRONIC DEFENSE	ED

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE XIII. Weapon and asset codes - Continued.

WEAPON/ASSET	CODE
UNMANNED VEHICLE	UV
CLOSE-IN WEAPON SYSTEM	CW
LAMPS	L3
VERTICAL LAUNCH ASROC[1]	VA
NUMBER OF ENGAGEMENTS[2]	## (02-99)

Notes: 1. Some non-US ships still use non-vertical launch ASROC
2. Shall only be used in conjunction with multiple engagements. Valid numbers are 02-99.

5.3.8 Manually-generated tracks. Manually-generated tracks are those symbols which have not been received through messaging systems, such as Link 16, but rather have been created locally for display. Manually-generated (or manual) tracks are denoted by the "MAN" icon placed within the symbol. Manual tracks can be created across all standard identities and dimensions by adding the "MAN" icon to the center of the frame. In addition, manual tracks can be created for tracks with a known standard identity but unknown dimension by adding the "MAN" icon under the "?" icon. See figure 24 for examples of manual tracks. Manual tracks are only local symbols and not transmitted.




FIGURE 24. Manually-generated tracks.

5.3.9 Dismounted Individual Leadership. This leadership indicator amplifier is used with dismounted individual symbols only. The leadership indicator amplifier is an inverted "V" placed over the symbol and extending the width of the frame. See figure 25.




FIGURE 25. Dismounted individual leadership amplifier examples.

5.3.10 Composition of icon-based symbols. The purpose of icon, modifier and amplifier placement is to standardize the location of information that graphically describes a unit, equipment, or installation and provides additional information on capability, status and location. Figure 26 shows the composition and placement of a frame, fill, icon, modifiers and amplifiers to

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

form a hostile land unit symbol. The placement of icons, modifiers and amplifiers is the same regardless of frame shape or standard identity.





FIGURE 26. Composition of an icon-based symbol.

5.3.10.1 Symbol display hierarchy. C2 systems differ in their operational requirements concerning the amount of information about an object to be displayed. As a result, this document standardizes those symbology elements required to achieve interoperability in information presentation and allows flexibility in the symbol components that are displayed to the warfighter. Display options range from complex, such as a symbol displaying a frame, fill, icon and modifiers, to primitive, such as a symbol rendered as a dot that denotes the presence of an object at a specific location. Table XIV provides examples of display options that can be used in color and monochrome displays and can be either hand-drawn or computer generated. The examples in the table depict some of the display options for the two symbols. Based on operational requirements, systems may be implemented with a fixed set of display options or with the ability to allow warfighters to select one or more display options. If the amplifying information provided by internal icons and modifiers is not required by the warfighter, the symbols may be displayed with frame or frame and fill only, omitting the icons and modifiers. Any display options in table XIV are compliant with this standard. If a system is implemented with multiple display options, the warfighter may be allowed to select a single option for rendering all symbols or to select different options based on the standard identity or dimension of the object and the amount of information required. For example, the warfighter may choose to display minimal information about friendly objects (displaying these symbols as dots) and maximal information about potential threats (displaying these symbols with frame, fill, icon and modifiers).

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE XIV. Symbol display options.

EXAMPLES		DISPLAY OPTION DESCRIPTIONS
CARRIER	FERRY	
		Frame: ON (black or white depending on background) Fill: ON (use default color indicating standard identity) Icon: ON (black or white) Modifiers: ON (civilian sea surface symbols do not permit modifiers) Note: The first column example is a MILITARY COMBATANT, CARRIER with modifiers for HELICOPTER EQUIPPED and NUCLEAR POWERED. The second column example is a CIVILIAN, MERCHANT SHIP and FERRY.
		Frame: ON (black or white depending on background) Fill: OFF Icon: ON (black or white) Modifiers: ON
		Frame: ON (use default color indicating standard identity) Fill: OFF Icon: ON (use default color indicating standard identity) Modifiers: ON
N/A		Frame: OFF Fill: ON Icon: ON (use default color indicating standard identity) Modifiers: N/A (civilian sea surface symbols do not permit modifiers) Note: Normally only land equipment and civilian sea surface symbols can be displayed without a frame. For civilian white-filled icons, the white-fill should be changed to the color indicating its standard identity.
		Frame: ON (black or white depending on background) Fill: ON (use default color indicating standard identity) Icon: OFF Modifiers: OFF Note: The examples show the dimension level display of CARRIER and FERRY. The CARRIER and FERRY icons, including their parent icons, are not displayed.
		Frame: ON Fill: ON Icon: ON Modifiers: OFF Note: The examples show the entity level display of CARRIER (MILITARY COMBATANT) and FERRY (CIVILIAN).
		Frame: ON Fill: ON Icon: ON Modifiers: OFF Note: The examples show the entity type level display of CARRIER and FERRY (MERCHANT SHIP).
		Frame: OFF Fill: ON (use default color indicating standard identity) Icon: OFF Modifiers: OFF
		Frame: OFF Fill: OFF Icon: OFF Modifiers: OFF Note: Use only to indicate the location of a symbol.

Note: This table shows frame and fill color when displayed on a color monitor.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

5.3.11 Symbol size. The relative size of each symbol and symbol component shall be consistent within a given implementation (see "Alphanumeric character and symbol sizes of MIL-STD-1472 for guidance"). Each of these sizes shall be related to length L as described in 5.3.1. The minimum diameter of a symbol displayed as a dot should be 0.15L.

5.3.12 Line width. Because the symbol frame indicates both the standard identity and dimension of an object, it is critical that line width is sufficient to ensure frame legibility and discriminability at normal viewing distance (see "Symbol line width of MIL-STD-1472 for guidance"). The optimum line width may differ depending on frame size and be affected by whether the frame is filled or unfilled and displayed in color or black/white. Usability testing should be performed to identify the optimum rendering for a given implementation.

5.3.13 Plotting. The plotting of most single point symbols shall be based on the geometric center of the symbol. The geometric center indicates the general vicinity of the center of mass of an object. Single point symbols that do not use their geometric center for plotting shall be positioned based on their anchor point. If an offset/precise location indicator is displayed with a symbol, the endpoint of the indicator shall show the object's location. If a group of symbols are displayed at one location, the group may be enclosed with a bracket and the location of that group identified with an offset/precise location indicator. An offset/precise location indicator is one option for reducing clutter when symbols overlap or are collocated. Other options for reducing visual clutter include (1) repositioning or turning off labels so that they are not obscured by other objects, with a line connecting each label to its object and/or (2) supporting variable coding of objects (e.g., high-interest objects are rendered as symbols and low-interest objects as dots). The choice of display options for addressing clutter is considered to be user specific. The positional accuracy of symbology plotting is also considered user specific.

5.3.14 Orientation. The frame and icon in framed tactical symbols shall be displayed in the orientation shown in the appendices. Equipment in the land dimension can be rotated to face the direction of movement only when the symbol is unframed. Control measure symbols shall be displayed in the orientation shown in appendix H. Point graphics that are positioned based on their anchor point can be rotated 90 degrees when necessary to minimize interference with other symbology or terrain features.

5.4 Compliance criteria. If common joint military symbology is implemented to visually display or present symbology, the implementation shall comply with the provisions of this standard. To be considered MIL-STD-2525 compliant, implementations must satisfy criteria related to the appearance of tactical symbols and graphics, the assembling and parsing of SIDC and the interpretation and generation of symbol representations. Each category of compliance criteria is described below:

5.4.1 Appearance of tactical symbols. The following compliance criteria apply to the appearance of tactical symbols:

a. The frame shape in a tactical symbol indicates the standard identity, dimension and status as defined in this MIL-STD.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

b. If color is used in a tactical symbol, it indicates the standard identity as defined in this MIL-STD.

c. The icon in a tactical symbol is displayed as framed or unframed in accordance with framing requirements defined in this MIL-STD.

d. The icons in this MIL-STD are used to provide role or mission information whenever the objects for which icons are provided are displayed in a tactical symbol.

e. If text and/or graphic amplifiers are included in a tactical symbol, they conform to the field definitions and display lengths defined in this MIL-STD.

f. Tactical symbol components and modifiers are sized and positioned as defined in this MIL-STD.

g. The rendering of tactical symbols and modifiers conform to the display options defined in table XIV.

h. Any temporary features added to a tactical symbol conform to the display rules in this MIL-STD.

5.4.2 Assembling and parsing of SIDC. The following compliance criteria apply to the assembling and parsing of SIDC:

a. An implementation can assemble the correct tactical symbol or graphic and its modifier(s) from a SIDC.

b. An implementation can generate the SIDC that will produce the correct tactical symbol or graphic when transmitted to another MIL-STD-2525 compliant system.

5.5 Color. It is important that implementations maximize the contrast between symbology and the display background in order to provide optimum discriminability.

a. Implementers should include sufficient usability testing to ensure effective operator performance when selecting colors to render the symbology. Color luminance (or brightness) may need to vary depending on the display option(s) selected for symbols. For example, different shades of red may be needed for both filled and unfilled symbols to heighten its contrast upon its map background or display.

b. For filled symbols, this contrast can be provided by using black (RGB: 0, 0, 0) for the frame, icon, modifiers and amplifiers when filled symbols are displayed on a light background and using white (RGB: 255, 255, 255) for these elements when filled symbols are displayed on a dark background. Implementers should select specific values (e.g., in CIE, RGB, or UV terms) for the default symbol colors based on considerations such as operational requirements, hardware configuration, display background and viewing conditions (e.g., ambient lighting). Table XV lists a range of acceptable symbol colors that have been empirically validated across a variety of viewing backgrounds. Table XV lists the symbol colors in terms of RGB and their corresponding hue, saturation and luminance (HSL) values.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

Three sample color sets are displayed in table XV. The colors for each standard identity shall vary only in terms of their luminance values (luminance values are **in bold** in table XV). Implementers may use any of the example color sets or may choose an alternative set whose luminance values fall within the range of the light and dark color sets. Filled symbols may be depicted as translucent. In such cases, opacity should be set at 35% (65% transparency).

c. For unfilled symbols, implementers should use the default symbol colors in table XVI unless considerations such as operational requirements, hardware configuration, display background and viewing conditions (e.g., ambient lighting) necessitate an alternate symbol color set. In the case of an alternative symbol color set, implementers should select specific values (e.g., in Commission Internationale de I'Elcairage (CIE), Red, Green, Blue (RGB), or Ultraviolet (UV) terms) for unfilled symbols based on sufficient usability testing.

d. For control measures, this contrast can be provided by using black (RGB: 0, 0, 0) for the graphic when it is displayed on a light background and using white (RGB: 255, 255, 255) when it is displayed on a dark background. If color is used in a graphic, implementers should select specific values for the default colors in table XVI based on the same considerations as for icon-based symbols.

TABLE XV. Color range values for filled symbols.

IDENTITY	COLOR	COMPUTER GENERATED		
		DARK	MEDIUM	LIGHT
UNKNOWN, PENDING	YELLOW			
		RGB (225, 220, 0)	RGB (255, 255, 0)	RGB (255, 255, 128)
		HSL (42, 255, **110**)	HSL (42, 255, **128**)	HSL (42, 255, **192**)
FRIEND, ASSUMED FRIEND	BLUE			
		RGB (0, 107, 140)	RGB (0, 168, 220)	RGB (128, 225, 255)
		HSL (138, 255, **70**)	HSL (138, 255, **110**)	HSL (138, 255, **192**)
NEUTRAL	GREEN			
		RGB (0, 160, 0)	RGB (0, 226, 0)	RGB (170, 255, 170)
		HSL (85, 355, **80**)	HSL (85, 255, **113**)	HSL (85, 255, **213**)
SUSPECT	ORANGE			
		RGB (255, 188, 1)	RGB (255, 217, 107)	RGB (255, 229, 153)
		HSL (31, 255, **128**)	HSL (31,255, **181**)	HSL (31, 255, **204**)
HOSTILE	RED			
		RGB (200, 0, 0)	RGB (255, 48, 49)	RGB (255, 128, 128)
		HSL (0, 255, **100**)	HSL (0, 255, **152**)	HSL (0, 255, **192**)

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE XVI. Default colors for unfilled symbols.

DESCRIPTION	HAND DRAWN	COMPUTER GENERATED	
		ICON (RGB VALUE)	ICON COLOR
UNKNOWN, PENDING	YELLOW	YELLOW (255, 255, 0)	
FRIEND, ASSUMED FRIEND	BLUE	CYAN (0, 255, 255)	
NEUTRAL	GREEN	NEON GREEN (0, 255, 0)	
SUSPECT	ORANGE	ORANGE (255, 188, 1)	
HOSTILE	RED	RED (255, 0, 0)	

6 NOTES

(This section contains information of a general or explanatory nature that may be helpful, but is not mandatory.)

6.1 Intended use. MIL-STD-2525 is designed to enhance DOD's joint interoperability by providing sets of C2 symbols, a coding scheme for symbol automation and information transfer, and technical details to support symbology for C2 systems.

6.2 Subject term (key word) listing.

Activities
Amplifier
Civil support
Command and control
Control measures
Emergency management
Graphic
Icon
Interoperability
Meteorological
Modifier
Oceanographic
Operations
Signals intelligence
Symbol
Symbol identification code
Warfighter

6.3 International standardization agreement implementation. This standard implements NATO STANAG 2019/APP-06, NATO Joint Military Symbology. When changes to, revision, or cancellation of this standard are proposed, the preparing activity must coordinate the action

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

with the US National Point of Contact for the international standardization agreement as identified in the ASSIST database at https://assist.dla.mil/.

6.4 Changes from previous issue. Marginal notations are not used in this revision to identify changes with respect to the previous issue due to the extent of the changes.

6.5 Symbology change proposal incorporation.

6.5.1 Table XVII contains the symbology change proposals (SCPs) that have been incorporated into this update of MIL-STD-2525E.

TABLE XVII. Incorporated symbology change proposals.

SCP Number	SCP Title
18-007-AR	Isolated Personnel Initial Location Control Measure
18-008-AR	Isolated Personnel Main Icon
18-009-AR	Change Name of Downed Aircrew Pick-Up Point
18-010-MC	Addition of Handover Line (HOL) control measure
18-011-MC	Addition of Battle Handover Line (BHL) line control measure
18-012-MC	Addition of Forward Passage of Lines as a Mission Task
18-013-MC	Addition of Rearward Passage of Lines as a Mission Task
18-014-MC	Addition of Control Point to C2 Points Table
18-015-AR	Add Human Resources Main Icon
18-016-AR	Delete Unit Main Railhead
18-017-AR	Delete Unit Main Armored/Mechanized/Tracked
18-018-AR	Delete Unit Main Towed
18-019-AR	Delete Unit Main Special Boat
18-020-AR	Delete Unit Main Special SSNR
18-021-AR	Rename/Correct Unit Sector2 Wheeled
18-022-AR	Add Unit Sector2 Wheeled LTD
18-023-AR	Delete Unit Main Security Police air
18-024-AR	Add Unit Sector2 Fixed Wing
18-026-AR	Delete Equipment Main Vehicle
18-027-AR	Delete Equipment Main Armored
18-028-AR	Delete Equipment Main Armored Pro Recovery Veh
18-029-AR	Delete Equipment Main Armored Pro MEDEVAC Veh
18-030-AR	Delete Equipment Main Mech
18-031-AR	Delete Unit Main SelfPropelled
18-032-AR	Delete Unit Main Target Acquisition
18-033-AR	Rename/Correct Unit Main Armor/Armored/Mech/SelfProp Track
18-035-AR	Delete Unit Main Mech CBRN
18-039-AR	Remove TACSAT Main

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE XVII. Incorporated symbology change proposals – Continued.

SCP Number	SCP Title
18-040-AR	Modify Underwater Demolition Team Main Icon
18-041-AR	Add Equip Sector1 Light/Medium/Large
18-042-AR	Modify Arrest Main Icon Name
18-043-AR	Delete Control Measure Guerrilla Base
18-044-AR	Delete Control Measure Base Camp
18-045-AR	Delete Equip Main Compact/Midsize/Sedan
18-046-AR	Delete Equip Main Pickup Small/Large
18-047-AR	Delete Van Main Icons Small/Large
18-048-AR	Delete SUV Main Icons Small/Large
18-049-AR	Delete Equip Main Small Light/Medium/Large
18-050-AR	Delete Boxtrailer Main Icons Small Light/Medium/Large
18-051-AR	Delete Ambulance Main Icon
18-052-AR	Delete Medical Evacuation Helicopter Main Icon
18-053-AR	Delete Flatbed Trailer Main Icon Small Light/Medium/Large
18-054-AR	Delete Equip Main Icon Medical Evacuation
18-055-AR	Delete Equip Main Mine Clearing Equipment Trailer Mounted
18-056-AR	Delete Unit Main Seaport Debark/Embark
18-057-AR	Delete Unit Main Airport Debark/Embark
18-058-AR	Delete Unit Main Floating Craft
18-059-AR	Delete Equip Main Railcar
18-060-DS	Change Hijacking/Hijacked modifier from H to HJK
18-061-AR	Modify Weapons Modifier
18-062-AR	Delete SigInt Main Icon Unknown
18-067-AR	Add New Control Measure_C2 Area
18-068-AR	Add New Control Measure_C2 Line
18-069-AF	Add New Airport-Air Base Symbols
18-070-AR	Add Sector 2 Heavy Modifier for Equipment
18-071-DS	Add Operational Condition for Units
19-001-DS	Update Version Identification Coding
19-002-DS	Correct Nuclear Event Fallout Producing Symbol
19-003-DS	Add main icon for house
19-004-AR	Add Surgical Sector 2 Modifier
19-008-AR	Change Religious Main Icon Usage
19-010-C01-AR	House Main Icon
19-011-AR	Delete Sensor Zone Control Measure Symbols
19-012-AR	Corrections to Status visualization for frames in Table VI
19-015-AR	Correct On Order Examples in MIL-STD-2525D Ch1 Appendix H

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE XVII. Incorporated symbology change proposals – Continued.

SCP Number	SCP Title
19-018-AR	Delete Obsolete Note from MIL-STD-2525D Ch1 Appendix H (test)
19-019-DS	Define Domain and Dimension within MIL-STD-2525
19-022-AF	Add Space Civilian Planetary Lander Main Icon
19-024-AF	Add Space Civilian Space Vehicle Main Icon
19-027-AF	Add Space Electronic Warfare (ASAT) Sector 2 Modifier
19-029-AF	Add Space High Power Microwave (ASAT) Sector 2 Modifier
19-032-AF	Add Space Laser (ASAT) Sector 2 Modifier
19-033-AF	Add Space Mine (ASAT) Sector 2 Modifier
19-041-AF	Add Space Maintenance Sector 2 Modifier
19-042-AF	Add Space Refuel Sector 2 Modifier
19-043-AF	Add Space Tug Sector 2 Modifier
20-001-MC	Battlefield Coordination Line Modification
20-004-MC	Dismounted Individual Symbology
20-005-AF	Adjust METOC Area 2 Draw Rules
20-006-DS	Clarify Dynamic and Static definitions in standard
20-007-DS	Correct Attack and Support by Fire Description
20-008-AR	Modify the Dental Services sector 2 modifier symbol for units
20-009-AR	Add Blood Support sector 2 modifier for units
20-010-AR	Add Combat and Operational Stress Control Sector 2 Modifier for units
20-011-AR	Add Company Echelon of Support sector 1 modifier for units
20-012-AR	Add Battalion Echelon of Support sector 1 modifier for units and equipment
20-013-AR	Modify Detainee holding area control measure
20-014-AR	Add Grenade Main Icon for Installations
20-015-AR	Add Jamming sector 2 modifier for units
20-016-AR	Modify Key Terrain control measure
20-017-AR	Add Medical Bed sector 2 modifier for units
20-018-AR	Add optometry support sector 2 modifier for units
20-019-AR	Add Preventive Med sector 2 modifier for units
20-020-AR	Add Mobile Gun Main Icon for units
20-021-AR	Modify the mountain sector 2 modifier for units
20-022-AR	Add Multifunctional sector 2 modifier for units and installations
20-023-AR	Modify the Toxic Release Inventory main icon for installations and activities
20-024-AR	Add mortuary affairs collection point control measure
20-025-AR	Add one-way traffic route control measure
20-027-AR	Add alternating traffic route control measure
20-028-AR	Add traffic route control measure
20-029-AR	Add Corps Support Area control measure

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE XVII. Incorporated symbology change proposals – Continued.

SCP Number	SCP Title
20-031-DS	Modification to symbol identification code (SIDC) Format
20-032-DS	Correct language within the Scope of each appendix
20-033-DS	Redefine the term Battle Dimension within the standard
20-034-DS	Modify all Armored Vehicle icons from a Full octagon to a Main icon
20-035-DS	Remove Light Wheeled Armor Vehicle full octagon equipment symbol
20-036-DS	Remove Bridge Mounted On Utility Vehicle full octagon equipment symbol
20-037-DS	Remove Fire Station full octagon equipment symbol
20-038-DS	Remove Petroleum Facility full octagon equipment symbol
20-039-DS	Remove Tank Recovery Vehicle full octagon equipment symbols
20-040-DS	Remove Tent full octagon equipment symbol
20-041-DS	Correct Attack and Support by fire description
20-042-DS	Add clarifying language for single point symbols
20-043-AR	Add Cyber main icon for units
21-001-DS	Add Cyberspace Physical Entity Symbol Set Codes
21-002-DS	Add Dismounted Individual To Domain Paragraph
21-003-DS	Address SIDC Reserved Values Within the Standard
21-004-DS	Admin change to remove duplicate infrastructure wording
21-005-DS	Change Codes and Digits Header Names to Values
21-006-DS	Correct Breach Mission Task Draw Rules
21-007-DS	Remove Occupied Assembly Area Control Measure
21-009-DS	Remove Confusing Draw Rules for Mission Tasks
21-010-DS	Change All References to 2525D and Replace with 2525E
21-012-C01-MC	Add AM Amplifier to Ship Area of Interest Rectangle (AEGIS ONLY) Symbol
21-013-DS	Add Clarifying Text for Offsetting Modifiers
21-014-AR	Modify Weapon Systems to Main Icon
21-016-DS	Hypersonic Air and Space Missile Modifier
21-017-DS	Change Appendices Order Within Standard
21-018-AR	Add Multi-Domain Operations main icon for units
21-019-AR	Add Robotic sector 1 modifier for units
21-020-DS	Add Restricted Targets and No-Strike Entities
21-021-DS	Add Common Modifier Identifiers to the Symbol Identification Code
21-022-DS	Clarification of Proper Use of Main Icons
21-023-DS	Administrative Hexadecimal SIDC Paragraph Update
21-024-JS	Add C2 Modifier to Cyberspace Appendix
21-025-JS	Add Cyberspace Server Main Icon
21-026-JS	Add Cyber Continuity of Operations COOP Modifier
21-027-JS	Add Operations Main and Modifier to Cyberspace Appendix

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE XVII. Incorporated symbology change proposals – Continued.

SCP Number	SCP Title
21-028-JS	Add Security Main Icon and Modifier to Cyberspace Appendix
21-029-JS	Add Data Main Icon to Cyberspace
21-030-JS	Add Internet Service Provider Modifier to Cyberspace
21-031-JS	Add Cyberspace Financial Modifier
21-032-JS	Add Cyberspace Medical Modifier
21-033-JS	Add Cyberspace Out-of-Band Modifier
21-034-JS	Add Cyberspace Power Utility Modifier
21-035-JS	Add Water Modifier to Cyberspace Appendix
21-036-JS	Add Cyberspace Wired Modifier
21-037-JS	Add Cyberspace Wireless Modifier
21-038-JS	Add Cyberspace Network Main Icon
21-039-JS	Add Cyberspace Honey Net/Pot Modifier
21-041-MC	Modify Draw Rules of Line Symbols
21-042-MC	Add Amplifiers to Isolated Personnel Recovery Point
21-043-AR	Add Air Defense Sector 2 modifier for units
21-044-AR	Add Multi-Domain Operations Sector 1 modifier icon for units
21-045-AR	Add Directed Energy main icon for units
21-046-DS	Modify Tetrahedron/Dragons Teeth primitives
21-047-DS	Remove NATO Supply Class - ALL
21-048-DS	Modify Air Sector 1 Modifier for Cargo
21-049-DS	Modify Sector 2 Modifier Mountain Icon
21-050-DS	Modify Weapons Modifier Icon
21-051-DS	Removal of Version Extension Flag (VEF)
21-052-DS	Add Common Modifier Tables to MIL-STD-2525
21-053-AR	Remove Retired Mode 4 Code Examples
22-001-DS	Change Nation and Non-Nation main icons to modifiers
22-002-DS	Modify Laser (Directed Energy) Equipment Icon
22-003-AF	ID and Color Corrections
22-004-DS	Move HQ and Echelon Amplifier Examples to Main Document
22-006-DS	Move Data Modifier in Cyberspace Appendix to Modifier 1
22-007-JS	Add New Cyberspace Main and Modifier Primitives
22-009-DS	Clarification/Modification of Amplifier Field Tables
22-011-AR	Remove Mobile Gun System Symbols from MIL-STD-2525
22-012-MC	Change Medic Symbol for Dismounted Individual
22-013-MC	Change New Offset Amplifier Guidance
22-014-DS	Change Dismounted Ranks to US ranks
22-015-DS	Admin Changes based on 22-2 CRM

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE XVII. Incorporated symbology change proposals – Continued.

SCP Number	SCP Title
22-016-DS	Create an SIDC Frame Shape Identifier
22-017-DS	Add Hijacking/Hijacked/Hijacker to Common Modifier Table
22-018-DS	Remove Hierarchical Graphics From MIL-STD-2525
22-019-AR	Corrections to Vertical Obstruction Symbols
22-020-DS	Update Control Measures Sector Modifier Language
22-023-JS	Delete Cyberspace EDM Modifier

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

SYMBOL IDENTIFICATION CODES

A.1 SCOPE.

A.1.1 Scope. This appendix outlines the procedures for developing symbol identification codes (SIDC) for symbols in MIL–STD–2525E. The use of these codes is optional but highly recommended.

A.2 APPLICABLE DOCUMENTS

Specific documents in 2.2 of this standard apply to this appendix.

A.3 DEFINITIONS

The definitions in section 3 of this standard apply to this appendix.

A.4 GENERAL REQUIREMENTS

A.4.1 Organization. This appendix contains SIDC and their elements.

A.5 DETAILED REQUIREMENTS

A.5.1 Symbol identification code. A symbol identification code (SIDC) is a 30-position code that uniquely identifies the core elements needed to build a joint military compliant symbol. The SIDC shall only use the hexadecimal range of values (0-9 and A-F). This range provides the capability to exchange symbol information in a bandwidth-efficient manner, when converting to other format such as binary, by treating the SIDC as a hexadecimal number. When processing and storing the SIDC within implementations, it may be treated as a string with no loss of information. Values within the SIDC are given to an established symbol by the SSMC only.

A.5.2 Elements of the symbol identification code**.** The SIDC is composed of fourteen elements of information which are presented in three sets of ten values. See figure A–1.

Note: SIDC values shall only be assigned by the SSMC and only values listed in this MIL-STD or approved SCPs shall be used. Other SIDC values may be assigned to other organizations such as values used in STANAG 2019 (APP-06).

For more information contact Defense Information Systems Agency (DISA) Military Message Standards Branch (EM7), P.O. Box 549, Ft. Meade, MD 20755-0549, or emailed to disa.meade.EE.mbx.symbology@mail.mil.

A.5.2.1 Set A - First ten values.

Version
Standard identity
Symbol set
Status
HQ/Task Force/Dummy
Amplifier/Descriptor

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

A.5.2.2 Set B - Second ten values.

Entity
Entity type
Entity subtype
Sector 1 modifier
Sector 2 modifier

A.5.2.3 Set C - Third ten values.

Sector 1 Common Modifier Identifier
Sector 2 Common Modifier Identifier
Nationality/country/geopolitical/geographic name or Entity numeric code




FIGURE A-1. Elements of the symbol identification code.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

A.5.3 Set A. The first set of ten values:

Values 1 and 2 is the Version.
Values 3 and 4 is the Standard Identity.
Values 5 and 6 is the Symbol Set.
Value 7 is the Status.
Value 8 is the Headquarters/Task Force/Dummy.
Values 9 and 10 is the Amplifier/Descriptor.

A.5.3.1 Version. The version is comprised of two values and identifies an edition or version change within the harmonized symbology standards APP-06 and MIL-STD-2525. The version number will increment by one each time either of the standards is promulgated. This provides accounting for further updates to the standards.

TABLE A-I. Version.

Value	Description	Promulgated
10	MIL-STD-2525D	June 2014
10	APP-06(D)(1)	October 2017
11	MIL-STD-2525D(1)	August 2, 2018
12	APP-06(D)(2)	Withdrawn
13	MIL-STD-2525E	December 31, 2022
14-3F	Reserved for future Editions/Versions	N/A
40-FF	N/A	N/A

Note: MIL-STD-2525D and APP-06(D)(1) are the extant standards and should have the same versioning due to the omission of any changes between the two standards.

A.5.3.2 Standard identity. Standard identity is comprised of two values. The first value represents the context of the symbol and the second value reflects the standard identity. The following are the entries for standard identity:

TABLE A-II. Standard identity.

Description	1st Position Value	2d Position Value
Context		
Reality	0	
Exercise	1	
Simulation	2	
Restricted Target – Reality	3	
No-Strike Entity – Reality	4	
Restricted Target – Exercise	5	
No-Strike Entity – Exercise	6	
Restricted Target – Simulation	7	
No-Strike Entity – Simulation	8	
Standard Identity		
Pending		0
Unknown		1
Assumed Friend		2
Friend		3
Neutral		4
Suspect/Joker		5

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE A-II. Standard identity - Continued.

Description	1st Position Value	2d Position Value
Hostile/Faker		6

A.5.3.2.1 Context implementation guidance. The three contexts listed here are reality, exercise, and simulation, and these are directly related to frames depicted in each of tables I, II, and III, respectively. The graphic (svg) files provided for frames include complete sets of those that need "X" for exercise or "S" for simulation text amplifiers, however graphic (svg) files for training are not currently available. These amplifiers are built into the exercise and simulation frame graphic (svg) files themselves, rather than supplied as separate text amplifier graphic (svg) files.

A.5.3.2.2 Standard identity implementation guidance. The standard identities are documented, and examples of the various frames used for each of the standard identities illustrated, in tables I, II, and III. The standard identities themselves are also listed in 5.3.2.1. The seven standard identities are grouped into four standard identity groups each of which has an associated frame shape for each dimension. The standard identity groups are Unknown, Friend, Neutral and Hostile and the mapping between them and the standard identities are as shown in table A-III.

TABLE A-III. Standard Identity Mapping.

Standard Identity Group	Standard Identities
Unknown	Pending and Unknown
Friend	Friend and Assumed Friend
Neutral	Neutral
Hostile	Hostile/Faker and Suspect/Joker

When a symbol component is variable according to frame shape, the standard identity group can be used to determine which of the available graphic (svg) files should be used for symbol construction.

A.5.3.3 Symbol set. The symbol set is comprised of two positions.

TABLE A-IV. Symbol sets.

Description	Value
Unknown	00
Air	01
Air Missile	02
Space	05
Space Missile	06
Land Unit	10
Land Civilian Unit/Organization	11
Land Equipment	15
Land Installation	20
Control Measure	25
Dismounted Individuals	27
Sea Surface	30
Sea Subsurface	35

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE A-IV. Symbol sets - Continued.

Description	Value
Mine Warfare	36
Activities	40
Atmospheric	45
Oceanographic	46
Meteorological Space	47
Signals Intelligence	50
Cyberspace - Virtual	60

A.5.3.3.1 Symbol set implementation guidance. A symbol set represents a collection of symbol entities, sector one modifiers, and sector two modifiers. One or more symbol sets are grouped into a given dimension. A dimension is a collection of symbols that all share the same basic frame shape and amplifier placement specifications. The various dimensions are further illustrated as columns in tables I, II, and III. Multiple dimensions may combine to form domains (see 5.3.2.2). For any given symbol's SIDC, its context, standard identity, dimension, and status codes assist in determining which frame and associated fill (see 5.3.2, 5.3.3, and tables I, II, and III) is used to depict that symbol. Typically, given a collection of available filled frame graphic (svg) files, a given "affiliation" or "relationship" between a single context, single standard identity, single dimension, together with status, will permit the identification and selection of a single best choice for a frame graphic (svg) file. The optional choice of drawing a frame using the magenta fill for "civilian" provides a further opportunity to choose a particularly appropriate graphic (svg) file for frame depiction.

See table A-V for a mapping of the relationships between dimensions and symbol sets. Domains (5.3.2.2) cut across dimensions. MIL-STD-2525C also referred to the concept of a Battle Dimension (Air, Space, Ground, Sea Surface, Sea Subsurface, SOF, Other, and Unknown), and so, for clarity, table A-V also shows the relationships between the older concept of Battle Dimension and the newer concepts of Dimension, Domain, and Symbol Set.

TABLE A-V. Domain/dimension/symbol set mappings.

Battle Dimension (MIL-STD-2525C)	Dimension (MIL-STD-2525E)	Domain	Symbol Sets	Symbol Set Value
Unknown	Unknown	Unknown	Unknown	00
Air	Air	Air	Air Air Missile	01 02
Space	Space	Space	Space Space Missile	05 06
Ground	Land Unit	Land	Land Unit Land Civilian Unit/Organization	10 11
	Land Equipment		Land Equipment	15
	Land Installation		Land Installation	20
Sea Surface	Sea Surface	Maritime	Sea Surface	30

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

Sea Subsurface	Sea Subsurface		Sea Subsurface Mine Warfare	35 36
--	Dismounted Individual	By Location	Dismounted Individual	27
--	Cyberspace	Cyberspace	Cyberspace (Virtual)	60
--	Activities	By Location	Activities	40
--	Control Measure	By Location	Control Measure	25
--	METOC	Air	Atmospheric	45
		Sea	Oceanographic	46
		Space	Meteorological Space	47

A.5.3.4 Status. The status is comprised of one value.

TABLE A-VI. Status.

Description	Value
Present	0
Planned/Anticipated/Suspect	1
Present/Fully capable	2
Present/Damaged	3
Present/Destroyed	4
Present/Full to capacity	5

A.5.3.4.1 Status implementation guidance. Status is defined under 5.3.2.3. The status code in an SIDC can, alternatively, represent a given symbol's operational condition (5.3.7.14), since the operational condition and status (5.3.2.3) are mutually exclusive. Graphic (svg) files are available for each frame shape to enable a location Status of Present (solid frame) or Anticipated/Planned/Suspected (dashed frame) to be indicated for the relevant standard identities. Similarly, graphic (svg) files (differentiated by context, standard identity, dimension, and status) are available to ensure that when the operational condition of an entity is expressed using the colored bar approach shown in table XI, the bars are properly aligned when drawn beneath various frame shapes.

A.5.3.5 Headquarters/task force/dummy. The headquarters/task force/dummy is comprised of one value.

TABLE A-VII. Headquarters/task force/dummy.

Description	Value
Unknown	0
Feint/Decoy/Dummy	1
Headquarters	2
Feint/Dummy Headquarters	3
Task Force	4
Feint/Dummy Task Force	5
Task Force Headquarters	6
Feint/Dummy Task Force Headquarters	7

A.5.3.5.1 Headquarters/task force/dummy implementation guidance. Task force and feint/dummy indicators are described in 5.3.7.3 and 5.3.7.4, respectively. The headquarters staff

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

indicator is mentioned in 5.3.7.1 and figure 13. Code values exist for each of the eight possible combinations of these three graphic amplifiers including the case where none of the amplifiers are used. Graphic (svg) files exist for each combination of standard identity group, dimension, and the aforementioned Headquarters/Task Force/Dummy codes.

A.5.3.6 Echelon/mobility/towed array amplifier. The amplifier is comprised of two values.

TABLE A-VIII. Descriptor: Echelon/mobility/towed array amplifier.

Description	1st Position Value	2nd Position Value
Unknown	0	0
Echelon at brigade and below	1	
Team/Crew		1
Squad		2
Section		3
Platoon/detachment		4
Company/battery/troop		5
Battalion/squadron		6
Regiment/group		7
Brigade		8
Echelon at division and above	2	
Division		1
Corps/MEF		2
Army		3
Army Group/front		4
Region/Theater		5
Command		6
Equipment mobility on land	3	
Wheeled limited cross country		1
Wheeled cross country		2
Tracked		3
Wheeled and tracked combination		4
Towed		5
Rail		6
Pack animals		7
Equipment mobility on snow	4	
Over snow (prime mover)		1
Sled		2
Equipment mobility on water	5	
Barge		1
Amphibious		2
Naval towed array	6	
Short towed array		1
Long towed Array		2

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE A-VIII. Descriptor: Echelon/mobility/towed array amplifier - Continued.

Description	1st Position Value	2nd Position Value
Leadership Indicator	7	
Leader Individual		1

A.5.3.6.1 Echelon/mobility/towed array amplifier implementation guidance. An amplifier can either be textual or graphical. Documented in 5.3.7, with further echelon indicator details in 5.3.7.1, mobility indicator details in 5.3.7.10, and towed array amplifier details in 5.3.7.13.5, these codes allow, within the contents of an SIDC, for the inclusion of three of the most commonly used graphic amplifiers. An individual graphic (svg) file can be identified for use for a given amplifier based on an SIDC's standard identity group and its two amplifier values.

A.5.4 Set B. The second set of ten values:

a. These values define the icon and modifier contents of each symbol set

Positions 11 and 12 is the entity.
Positions 13 and 14 is the entity type.
Positions 15 and 16 is the entity subtype.
Positions 17 and 18 is the first modifier.
Positions 19 and 20 is the second modifier.

If an entity is "Unspecified", then the remainder of the second set of ten values shall be set to 0.

The tables in this section are organized by symbol sets.

b. Icons are the innermost part of a symbol. A symbol is, at most, composed of one and only one icon or compound icon. Icons are fully defined in 5.3.4. The SIDC structure is organized using a logical three-tier hierarchy based on first, second and third order military functions; each tier (military function level) is expressed using a pair of values. A first order military function is expressed as an Entity. Where there are second order military functions associated with a first order military function, these are expressed as Entity Types. Similarly, if a second order military function has related third order military functions; these are expressed as Entity Subtypes. The placement of the values representing Entity, Entity Type and Entity Subtype can be seen in figure A-1. Some entities and entity types are used purely for hierarchical purposes; these are never associated with an actual physical icon (an individual svg graphic file) and thus are never intended to be displayed. Most entities and entity types, however, and all entity subtypes, are associated with a single physical icon (an individual svg file). The icon used to represent a concept should be that associated with the highest level of detail available i.e. the one that reflects a non-zero-zero value at the most discriminating (i.e., lowest order) of the Entity, Entity Type and Entity Subtype values. When the icon to be used is a full frame icon (see 5.3.4.3), so by definition it touches the edge of the frame it is drawn within, one of four graphic (svg) files needs to be used, based on the standard identity group of the given SIDC.

c. A symbol set is also comprised of up to two sets of sector modifiers (sector 1 and sector 2). Sector modifiers are defined in 5.3.6, and their placement in 5.3.1.2. The graphic (svg)

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

file for a given sector 1 modifier can be determined through an SIDC's symbol set and sector 1 modifier value or by the use of the sector 1 modifier indicator and sector 1 modifier values. The graphic (svg) file for a given sector 2 modifier can be determined through an SIDC's symbol set and sector 2 modifier values or using the sector 1 modifier indicator and sector 2 modifier values.

d. For example, SIDC of 10031002161204010006013000840 would be interpreted as:

- 10 = Original version of this symbol (no effect on how this symbol is built/drawn)
- 03 = Reality context, friend standard identity, friend standard identity group
- 10 = Land unit symbol set, which belongs to the land unit dimension
- 0 = Status of present
- 2 = Headquarters/task force/dummy amplifier of headquarters
- 16 = Echelon at brigade and below, specifically a battalion/squadron echelon



- 12 = within the land unit symbol set, the movement and maneuver entity
- 04 = within the movement and maneuver entity, an antitank/antiarmor entity type
- 01 = within the antitank/antiarmor entity type, an armored unit
- 00 = within the land unit symbol set, no sector one modifier
- 06 = within the land unit symbol set, the wheeled sector two modifier

- 0 = no sector 1 common modifier used
- 1 = Sector 2 common modifier used
- 3 = Land unit frame shape
- 0000 = not used
- 840 = United States GENC code

e. The above example would be drawn as:

Values Used	Graphic (svg)
03 = Reality friend **10** = Land unit symbol set (and dimension) **0** = status of present **3** = Land unit frame shape All of the above values must be noted, in order to select the single best graphic for the frame and fill.	
3 = Friend **10** = Land unit **2** = Headquarters All of the above values must be noted, in order to select the single best graphic for the headquarters/task force/dummy amplifier.	

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

3 = Friend **16** = Echelon at brigade or below, battalion/squadron The friend standard identity belongs to the friend standard identity group, which in turn helps determine which graphic (svg) to use.	
10 = Land unit symbol set **12** = Entity is movement/maneuver	No icon is associated with this entity (hierarchical purposes only)
3 = Friend **04** = Entity type within land unit movement/maneuver entity is antitank/antiarmor. Since this is a full frame icon, the standard identity of friend determines the specific graphic (svg) needed. This icon would be used if this were the highest order non-zero-zero military function code in this SIDC. But it is not, in this example, the icon we desire.	
3 = Friend **01** = Entity subtype within land unit movement/maneuver entity and antitank/antiarmor entity type is armored. Since this is a full frame icon, the standard identity of friend determines the specific graphic (svg) needed. Since this is the highest (3rd) order non-zero-zero military function code in this particular SIDC, this icon IS used, NOT the previous icon for antitank/antiarmor.	
00 = Sector one modifier code is zero.	Nothing is drawn in sector one.
06 = Sector two modifier code is the second and third values of the sector two common modifier, wheeled	
0 = Sector one common modifier indicator is zero.	Nothing is drawn.
1 = Sector two common modifier indicator is first value of sector two common modifier. In this example, the common modifier value is **105**.	Nothing is drawn. It identifies the use of a common modifier
3 = Land unit frame shape	
0000 = not used	Nothing is drawn. Values are not used
840 = United States	USA
When composed and drawn, the final result is… 1003100216, 1204010006, 0130000840	

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

A.5.4.1 Common Modifiers

TABLE A-IX. Sector 1 common modifier.

Sector 1 Modifier	Category	Value	Remarks
Unmanned Aircraft (UA)/ Unmanned Aerial Vehicle (UAV)/ Unmanned Aircraft System (UAS)/ Remote Piloted Vehicle (RPV)	Mobility	100	
Robotic	Mobility	101	
Fixed Wing	Mobility	102	Not used by USAF
Rotary Wing	Mobility	103	
Tilt-Rotor	Mobility	104	
VSTOL/VTOL or Helicopter Equipped	Mobility	105	
Attack or Attack/Strike	Capability	106	
Armored	Capability	107	
Ballistic Missile/Ballistic Missile Defense Shooter	Capability	108	
Bridge/Bridging	Capability	109	
Cargo	Capability	110	
Utility	Capability	111	
Light	Capability	112	
Medium	Capability	113	
Heavy	Capability	114	
Cyberspace	Capability	115	
Command Post Node	Capability	116	
Joint Network Node	Capability	117	
Retransmission Site	Capability	118	
Brigade	Support Level	119	
Close Protection	Capability	120	
Combat	Capability	121	
Command and Control	Capability	122	
Crowd and Riot Control	Capability	123	
Explosive Ordnance Disposal	Capability	124	
Intelligence Surveillance Reconnaissance	Capability	125	
Maintenance	Capability	126	
Medevac/Medic/Medical	Capability	127	
Search and Rescue	Capability	128	
Security	Capability	129	
Sniper	Capability	130	
Special Operations Forces	Capability	131	
Special Weapons and Tactics (SWAT)	Capability	132	
Guided Missile	Capability	133	
Other Guided Missile	Capability	134	
Petroleum/Petroleum Oil and Lubricants	Capability	135	
Water	Capability	136	
Weapon or Weapons	Capability	137	
Chemical	CBRN	138	
Radiological	CBRN	140	
Nuclear	CBRN	141	
Decontamination	CBRN	142	
Civilian	Organization	143	
Government Organization/ Government Organization Member	Organization	144	

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE A-IX. Sector 1 common modifier - Continued.

Sector 1 Modifier	Category	Value	Remarks
Accident	Composite Loss or Incident Qualifier	145	
Assassination	Crime	146	
Execution	Crime	147	
Kidnapping	Crime	148	
Piracy	Crime	149	
Rape	Crime	150	
Antisubmarine Warfare	Mission Area	151	
Escort	Mission Area	152	
Mine Countermeasures	Mission Area	153	
Mine Warfare	Mission Area	154	
Surface Warfare	Mission area	155	
Command	Support Level	156	
Company	Support Level	157	
Platoon/Detachment	Support Level	158	
Regiment Group	Support Level	159	
Section	Support Level	160	
Squad	Support Level	161	
Team/Crew	Support Level	162	
Battalion	Support Level	163	
Directed Energy	Capability	164	
Hijacker	Crime	165	

TABLE A-X. Sector 2 common modifier.

Sector 2 Modifier	Category	Value	Remarks
Airborne	Mobility	100	
Bicycle Equipped	Mobility	101	
Railroad/Railway	Capability	102	
Ski	Mobility	103	
Tracked	Mobility	104	
Wheeled (Limited Cross Country)	Mobility	105	
Wheeled X (Cross Country)	Mobility	106	
Fixed Wing	Mobility	107	
Rotary Wing	Mobility	108	
Robotic	Mobility	109	
Autonomous Control	Capability	110	
Remotely Piloted	Capability	111	
Expendable	Capability	112	
Mountain	Capability	113	
Long Range	Capability	114	
Medium Range	Capability	115	
Short Range	Capability	116	
Close Range	Capability	117	
Heavy	Capability	118	
Medium	Capability	119	
Light and Medium	Capability	120	
Light	Capability	121	
Cyberspace	Capability	122	
Security Force Assistance	Capability	123	

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE A-X. Sector 2 common modifier - Continued.

Sector 2 Modifier	Category	Value	Remarks
Medical Bed	Capability	124	
Multifunctional	Capability	125	

A.5.4.2 Air (01)

TABLE A-XI. Air entity/entity type/entity subtype.

Entity (Positions 11 and 12)	Entity Type (Positions 13 and 14)	Entity Subtype (Positions 15 and 16)	Value
Note: The actual value is shown in **bold numbers**. The remaining values are used to show placement within the six positions.			
Unspecified			000000
Military			**11**0000
	Fixed Wing		11**01**00
		Medical Evacuation (MEDEVAC)	1101**01**
		Attack/Strike	1101**02**
		Bomber	1101**03**
		Fighter	1101**04**
		Fighter/Bomber	1101**05**
		{Disused}	1101**06**
		Cargo	1101**07**
		Electronic Combat (EC)/Jammer	1101**08**
		Tanker	1101**09**
		Patrol	1101**10**
		Reconnaissance	1101**11**
		Trainer	1101**12**
		Utility	1101**13**
		Vertical or Short Take-off and Landing (VSTOL)	1101**14**
		Airborne Command Post (ACP)	1101**15**
		Airborne Early Warning (AEW)	1101**16**
		Antisurface Warfare	1101**17**
		Antisubmarine Warfare	1101**18**
		Communications	1101**19**
		Combat Search and Rescue (CSAR)	1101**20**
		Electronic Support (ES)	1101**21**
		Government	1101**22**
		Mine Countermeasures (MCM)	1101**23**
		Personnel Recovery	1101**24**
		Search and Rescue	1101**25**
		Special Operations Forces	1101**26**
		Ultra Light	1101**27**
		Photographic Reconnaissance	1101**28**
		Very Important Person (VIP)	1101**29**
		Suppression of Enemy Air Defense	1101**30**
		Passenger	1101**31**

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE A-XI. Air entity/entity type/entity subtype - Continued.

Entity (Positions 11 and 12)	Entity Type (Positions 13 and 14)	Entity Subtype (Positions 15 and 16)	Value
Note: The actual value is shown in **bold numbers**. The remaining values are used to show placement within the six positions.			
		Escort	110132
		Electromagnetic Attack (EA)	110133
	Rotary Wing		110200
	Unmanned Aircraft (UA) / Unmanned Aerial Vehicle (UAV) / Unmanned Aircraft System (UAS) / Remotely Piloted Vehicle (RPV)		110300
	Vertical–Takeoff UAV (VT–UAV)		110400
	Lighter Than Air		110500
	Airship		110600
	Tethered Lighter than Air		110700
Civilian			120000
	Fixed Wing		120100
	Rotary Wing		120200
	Unmanned Aircraft (UA) / Unmanned Aerial Vehicle (UAV) / Unmanned Aircraft System (UAS) / Remotely Piloted Vehicle (RPV)		120300
	Lighter Than Air		120400
	Airship		120500
	Tethered Lighter than Air		120600
Weapon			130000
	Bomb		130100
	Decoy		130200
Manual Track			140000

TABLE A-XII. Air sector 1 modifier.

Sector 1 Modifier	Category	Value	Remarks
Not Applicable		00	
{Disused}		01	
Bomber	Military Aircraft Type	02	
{Disused}		03	
Fighter	Military Aircraft Type	04	
Interceptor	Military Aircraft Type	05	
Tanker	Aircraft Type	06	
{Disused}		07	
{Disused}		08	
Passenger	Aircraft Type	09	
Ultra Light	Aircraft Type	10	
Airborne Command Post (ACP)	Military Aircraft Type	11	
Airborne Early Warning (AEW)	Military Aircraft Type	12	
{Disused}		13	
{Disused}		14	
{Disused}		15	
Electronic Combat (EC)/Jammer	Military Mission Area	16	

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE A-XII. Air sector 1 modifier - Continued.

Sector 1 Modifier	Category	Value	Remarks
Patrol	Mission Area	17	
Reconnaissance	Mission Area	18	
Trainer	Mission Area	19	
Photographic (Reconnaissance)	Mission Area	20	
Personnel Recovery	Mission Area	21	
{Disused}		22	
Communications	Mission Area	23	
Electronic Support (ES)	Military Mission Area	24	
{Disused}		25	
{Disused}		26	
{Disused}		27	
{Disused}		28	
Very Important Person (VIP) Transport	Mission Area	29	
Combat Search and Rescue (CSAR)	Military Mission Area	30	
Antisurface Warfare	Military Mission Area	32	
Fighter/Bomber	Military Aircraft Type	33	
Intensive Care	Mission Area	34	
Electromagnetic Attack (EA)	Military Mission Area	35	
Multi-Mission	Mission Area	36	
{Disused}		37	
ASW Helo - LAMPS	Mission Area	38	
ASW Helo - SH-60R	Mission Area	39	
{Disused}		40	
{Disused}		41	

TABLE A-XIII. Air sector 2 modifier.

Sector 2 Modifier	Category	Value	Remarks
Not Applicable		00	
{Disused}		01	
{Disused}		02	
{Disused}		03	
Boom–Only	Re-Fueling Capability	04	
Drogue–Only	Re-Fueling Capability	05	
Boom and Drogue	Re-Fueling Capability	06	
{Disused}		07	
{Disused}		08	
{Disused}		09	
{Disused}		10	
Downlinked	Track Link Availability	11	
{Disused}		12	

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

A.5.4.3 Air missile (02).

TABLE A-XIV. Air missile entity/entity type/entity subtype.

Entity (Positions 11 and 12)	Entity Type (Positions 13 and 14)	Entity Subtype (Positions 15 and 16)	Value
Note: The actual value is shown in **bold numbers**. The remaining values are used to show placement within the six positions.			
Unspecified			000000
Missile			**11**0000

TABLE A-XV. Air missile sector 1 modifier.

Sector 1 Modifier	Category	Value	Remarks
Unspecified		00	
Air	Launch Origin	01	
Surface	Launch Origin	02	
Subsurface	Launch Origin	03	
Space	Launch Origin	04	
Anti–Ballistic	Missile Class	05	
Ballistic	Missile Class	06	
Cruise	Missile Class	07	
Interceptor	Missile Class	08	
Hypersonic	Missile Class	09	

TABLE A-XVI. Air missile sector 2 modifier.

Sector 2 Modifier	Category	Value	Remarks
Unspecified		00	
Air	Missile Destination	01	
Surface	Missile Destination	02	
Subsurface	Missile Destination	03	
Space	Missile Destination	04	
Launched	Missile Status	05	
{Disused}		06	
Patriot	Missile Type-BMD	07	
Standard Missile-2 (SM-2)	Missile Type-AAW	08	
Standard Missile-6 (SM-6)	Missile Type-AAW	09	
Evolved Sea Sparrow Missile (ESSM)	Missile Type-AAW	10	
Rolling Airframe Missile (RAM)	Missile Type-AAW	11	
Short Range	Missile Range	12	
Medium Range	Missile Range	13	
Intermediate Range	Missile Range	14	
Long Range	Missile Range	15	
Intercontinental	Missile Range	16	

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

A.5.4.4 Space (05).

TABLE A-XVII. Space entity/entity type/entity subtype.

Entity (Positions 11 and 12)	Entity Type (Positions 13 and 14)	Entity Subtype (Positions 15 and 16)	Value
Note: The actual value is shown in **bold numbers**. The remaining values are used to show placement within the six positions.			
Unspecified			000000
Military			**11**0000
	Space Vehicle		11**01**00
	Re–Entry Vehicle		11**02**00
	Planet Lander		11**03**00
	Orbiter Shuttle		11**04**00
	Capsule		11**05**00
	Satellite		11**07**00
	Antisatellite Weapon		11**08**00
	Astronomical Satellite		11**09**00
	Biosatellite		11**10**00
	Communications Satellite		11**11**00
	Earth Observation Satellite		11**12**00
	Miniaturized Satellite		11**13**00
	Navigational Satellite		11**14**00
	Reconnaissance Satellite		11**15**00
	Space Station		11**16**00
	Tethered Satellite		11**17**00
	Weather Satellite		11**18**00
	Space Launched Vehicle (SLV)		11**19**00
Civilian			**12**0000
	Orbiter Shuttle		12**01**00
	Capsule		12**02**00
	Satellite		12**03**00
	Astronomical Satellite		12**04**00
	Biosatellite		12**05**00
	Communications Satellite		12**06**00
	Earth Observation Satellite		12**07**00
	Miniaturized Satellite		12**08**00
	Navigational Satellite		12**09**00
	Space Station		12**10**00
	Tethered Satellite		12**11**00
	Weather Satellite		12**12**00
	Planetary Lander		12**13**00
	Space Vehicle		12**14**00
Manual Track			**13**0000

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE A-XVIII. Space sector 1 modifier.

Sector 1 Modifier	Category	Value	Remarks
Unspecified		00	
Low Earth Orbit (LEO)	Orbit	01	
Medium Earth Orbit (MEO)	Orbit	02	
High Earth Orbit (HEO)	Orbit	03	
Geosynchronous Orbit (GSO)	Orbit	04	
Geostationary Orbit (GO)	Orbit	05	
Molniya Orbit (MO)	Orbit	06	
{Disused}		07	

TABLE A-XIX. Space sector 2 modifier.

Sector 2 Modifier	Category	Value	Remarks
Unspecified		00	
Optical	Sensor	01	
Infrared	Sensor	02	
Radar	Sensor	03	
Signals Intelligence (SIGINT)	Sensor	04	
{Disused}		05	
Electromagnetic Warfare (ASAT)	Capability	06	
High Power Microwave (ASAT)	Capability	07	
Laser (ASAT)	Capability	08	
Mine (ASAT)	Capability	09	
Maintenance	Capability	10	
Refuel	Capability	11	
Tug	Capability	12	

A.5.4.5 Space missile (06).

TABLE A-XX. Space missile entity/entity type/entity subtype.

Entity (Positions 11 and 12)	Entity Type (Positions 13 and 14)	Entity Subtype (Positions 15 and 16)	Value
Note: The actual value is shown in **bold numbers**. The remaining values are used to show placement within the six positions.			
Unspecified			000000
Missile			**11**0000

TABLE A-XXI. Space missile sector 1 modifier.

Sector 1 Modifier	Category	Value	Remarks
Unspecified		00	
Ballistic	Missile Class	01	
Space	Launch Origin	02	
Interceptor	Missile Class	03	
Hypersonic	Missile Class	04	

TABLE A-XXII. Space missile sector 2 modifier.

Sector 2 Modifier	Category	Value	Remarks
Unspecified		00	
Short Range	Missile Range	01	

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE A-XXII. Space missile sector 2 modifier - Continued.

Sector 2 Modifier	Category	Value	Remarks
Medium Range	Missile Range	02	
Intermediate Range	Missile Range	03	
Long Range	Missile Range	04	
Intercontinental	Missile Range	05	
Arrow	Missile Type-BMD	06	
Ground-Based Interceptor (GBI)	Missile Type-BMD	07	
Patriot	Missile Type-BMD	08	
Standard Missile Terminal Phase (SM-T)	Missile Type-BMD	09	
Standard Missile – 3 (SM-3)	Missile Type-BMD	10	
Terminal High Altitude Area Defense (THAAD)	Missile Type-BMD	11	
Space	Launch Origin	12	
Close Range (CRBM)	Missile Range	13	
Debris	Missile Type-BMD	14	
Unknown	Missile Type-BMD	15	

A.5.4.6 Land unit (10).

TABLE A-XXIII. Land unit entity/entity type/entity subtype.

Entity (Positions 11 and 12)	Entity Type (Positions 13 and 14)	Entity Subtype (Positions 15 and 16)	Value
Note: The actual value is shown in **bold numbers**. The remaining values are used to show placement within the six positions.			
Unspecified			000000
Command and Control			**11**0000
	Broadcast Transmitter Antennae		11**01**00
	Civil Affairs		11**02**00
	Civil–Military Cooperation		11**03**00
	Information Operations		11**04**00
	Liaison		11**05**00
	Military Information Support Operations (MISO)		11**06**00
		Broadcast Transmitter Antennae	1106**01**
	Radio		11**07**00
	Radio Relay		11**08**00
	Radio Teletype Center		11**09**00
	Signal		11**10**00
		Radio	1110**01**
		Radio Relay	1110**02**
		Teletype	1110**03**
		{Disused}	1110**04**
		Video Imagery (Combat Camera)	1110**05**
	{Disused}		11**11**00
	Video Imagery (Combat Camera)		11**12**00
	Space		11**13**00

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE A-XXIII. Land unit entity/entity type/entity subtype - Continued.

Entity (Positions 11 and 12)	Entity Type (Positions 13 and 14)	Entity Subtype (Positions 15 and 16)	Value
Note: The actual value is shown in **bold numbers**. The remaining values are used to show placement within the six positions.			
	Special Troops		11**14**00
	Multi-Domain Operations		11**15**00
Movement and Maneuver			**12**0000
	Air Assault with Organic Lift		12**01**00
	Air Traffic Services/Airfield Operations		12**02**00
	{Disused}		12**03**00
	Antitank/Antiarmor		12**04**00
		Armored	1204**01**
		Motorized	1204**02**
	Armor /Mechanized		12**05**00
		Reconnaissance/Cavalry/Scout	1205**01**
		Amphibious	1205**02**
	Army Aviation/Aviation Rotary Wing		12**06**00
		Reconnaissance	1206**01**
	Aviation Composite		12**07**00
	Aviation Fixed Wing		12**08**00
		Reconnaissance	1208**01**
	Combat		12**09**00
	Combined Arms		12**10**00
	Infantry		12**11**00
		Amphibious	1211**01**
		Armored/Mechanized/Tracked	1211**02**
		Main Gun System, Infantry	1211**03**
		Motorized	1211**04**
		Infantry Fighting Vehicle	1211**05**
		Main Gun System	1211**06**
	Observer		12**12**00
	Reconnaissance/Cavalry/Scout		12**13**00
		Reconnaissance and Surveillance	1213**01**
		Marine	1213**02**
		Motorized	1213**03**
	Sea Air Land (SEAL)		12**14**00
	Sniper		12**15**00
	Surveillance		12**16**00
	Special Forces		12**17**00
	Special Operations Forces (SOF)		12**18**00
		Fixed Wing MISO	1218**01**

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE A-XXIII. Land unit entity/entity type/entity subtype - Continued.

Entity (Positions 11 and 12)	Entity Type (Positions 13 and 14)	Entity Subtype (Positions 15 and 16)	Value
Note: The actual value is shown in **bold numbers**. The remaining values are used to show placement within the six positions.			
		Ground	1218**02**
		{Disused}	1218**03**
		Special SSNR	1218**04**
		Underwater Demolition	1218**05**
	Unmanned Aerial Systems		12**19**00
	Ranger		12**20**00
Fires			**13**0000
	Air Defense		13**01**00
		Main Gun System	1301**01**
		Missile	1301**02**
		Air and Missile Defense	1301**03**
	Air/Land Naval Gunfire Liaison		13**02**00
	Field Artillery		13**03**00
	Field Artillery Observer		13**04**00
	Joint Fire Support		13**05**00
	Meteorological		13**06**00
	Missile		13**07**00
	Mortar		13**08**00
		{Disused}	1308**01**
		Self-Propelled Wheeled	1308**02**
	Survey		13**09**00
Protection			**14**0000
	Chemical Biological Radiological Nuclear Defense		14**01**00
		{Disused}	1401**01**
		Motorized	1401**02**
		Reconnaissance	1401**03**
		{Disused}	1401**04**
		Reconnaissance Equipped	1401**05**
		Chemical, Biological, Radiological, Nuclear, and High-Yield Explosives	1401**06**
	Combat Support (Maneuver Enhancement)		14**02**00
	Criminal Investigation Division		14**03**00
	Diving		14**04**00
	Dog		14**05**00
	Drilling		14**06**00
	Engineer		14**07**00
		Mechanized	1407**01**
		Motorized	1407**02**
		Reconnaissance	1407**03**

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE A-XXIII. Land unit entity/entity type/entity subtype - Continued.

Entity (Positions 11 and 12)	Entity Type (Positions 13 and 14)	Entity Subtype (Positions 15 and 16)	Value
Note: The actual value is shown in **bold numbers**. The remaining values are used to show placement within the six positions.			
	Explosive Ordnance Disposal (EOD)		14**08**00
	Field Camp Construction		14**09**00
	Fire Fighting/Fire Protection		14**10**00
	Geospatial Support/Geospatial Information Support		14**11**00
	Military Police		14**12**00
	Mine		14**13**00
	Mine Clearing		14**14**00
	Mine Launching		14**15**00
	Mine Laying		14**16**00
	Security		14**17**00
		{Disused}	1417**01**
		Motorized	1417**02**
	Search and Rescue		14**18**00
		Isolated Personnel	1418**01**
	{Disused}		14**19**00
	Shore Patrol/Security Police		14**20**00
	Topographic/Geospatial		14**21**00
	Missile Defense		14**22**00
Intelligence			**15**0000
	Analysis		15**01**00
	Counterintelligence		15**02**00
	Direction Finding		15**03**00
	Electronic Ranging		15**04**00
	Electromagnetic Warfare		15**05**00
		Analysis	1505**01**
		Direction Finding	1505**02**
		Intercept	1505**03**
		Jamming	1505**04**
		Search	1505**05**
	Intercept (Search and Recording)		15**06**00
	Interrogation		15**07**00
	Jamming		15**08**00
	Joint Intelligence Center		15**09**00
	Military Intelligence		15**10**00
	Search		15**11**00
	Sensor		15**12**00
	Military History		15**13**00
Sustainment			**16**0000
	Administrative		16**01**00

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE A-XXIII. Land unit entity/entity type/entity subtype - Continued.

Entity (Positions 11 and 12)	Entity Type (Positions 13 and 14)	Entity Subtype (Positions 15 and 16)	Value
Note: The actual value is shown in **bold numbers**. The remaining values are used to show placement within the six positions.			
	All Classes of Supply		160200
	{Disused}		160300
	Ammunition		160400
	Band		160500
		Army Music	160501
	Combat Service Support		160600
	Finance		160700
	Judge Advocate General		160800
	Labor		160900
	Laundry/Bath		161000
	Maintenance		161100
	Material		161200
	Medical		161300
	Medical Treatment Facility		161400
	Morale, Welfare and Recreation		161500
	Mortuary Affairs		161600
	Multiple Classes of Supply		161700
	NATO Supply Class I		161800
	{Disused}		161900
	NATO Supply Class III		162000
	NATO Supply Class IV		162100
	{Disused}		162200
	Ordnance		162300
	Personnel Services		162400
	Petroleum, Oil and Lubricants		162500
	{Disused}		162600
	{Disused}		162700
	Public Affairs/Public Information		162800
	Quartermaster		162900
	{Disused}		163000
	Religious Support		163100
	Replacement Holding Unit		163200
	{Disused}		163300
	{Disused}		163400
	Joint Information Bureau (JIB)		163500
	Transportation		163600
	US Supply Class I		163700
	{Disused}		163800
	{Disused}		163900

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE A-XXIII. Land unit entity/entity type/entity subtype - Continued.

Entity (Positions 11 and 12)	Entity Type (Positions 13 and 14)	Entity Subtype (Positions 15 and 16)	Value
Note: The actual value is shown in **bold numbers**. The remaining values are used to show placement within the six positions.			
	US Supply Class IV		164**0**00
	{Disused}		164**1**00
	US Supply Class VI		164**2**00
	US Supply Class VII		164**3**00
	US Supply Class VIII		164**4**00
	US Supply Class IX		164**5**00
	US Supply Class X		164**6**00
	{Disused}		164**7**00
	Water Purification		164**8**00
	Broadcast		164**9**00
	{Disused}		165**0**00
	Interpreter/Translator		165**1**00
	Support		165**2**00
	Army Field Support		165**3**00
	Contracting Services		165**4**00
	Parachute Rigger		165**5**00
	Human Resources		165**6**00
Naval			**17**0000
	Naval		17**01**00
Named Headquarters			**18**0000
	Allied Command Europe Rapid Reaction Corps (ARRC)		18**01**00
	Allied Command Operations		18**02**00
	International Security Assistance Force (ISAF)		18**03**00
	Multinational (MN)		18**04**00
Emergency Operation			**19**0000
Law Enforcement			**20**0000
	Bureau of Alcohol, Tobacco, Firearms and Explosives (ATF) (Department of Justice)		20**01**00
	Border Patrol		20**02**00
	Customs Service		20**03**00
	Drug Enforcement Administration (DEA)		20**04**00
	Department of Justice (DOJ)		20**05**00
	Federal Bureau of Investigation (FBI)		20**06**00
	Police		20**07**00

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE A-XXIII. Land unit entity/entity type/entity subtype - Continued.

Entity (Positions 11 and 12)	Entity Type (Positions 13 and 14)	Entity Subtype (Positions 15 and 16)	Value
Note: The actual value is shown in **bold numbers**. The remaining values are used to show placement within the six positions.			
	Prison		20**08**00
	United States Secret Service (USSS)		20**09**00
	Transportation Security Administration (TSA)		20**10**00
	US Coast Guard		20**11**00
	US Marshals Service		20**12**00
	Internal Security Force		20**13**00
Cyber			**21**0000

TABLE A-XXIV. Land unit sector 1 modifier.

Sector 1 Modifier	Category	Value	Remarks
Unspecified		00	
Tactical Satellite Communications	Capability	01	
Area	Capability	02	
{Disused}		03	
Biological	Capability	04	
Border	Capability	05	
{Disused}		06	
{Disused}		07	
{Disused}		08	
{Disused}		09	
{Disused}		10	
Communications Contingency Package	Capability	11	
Construction	Capability	12	
Cross Cultural Communication	Capability	13	
{Disused}		14	
{Disused}		15	
Detention	Capability	16	
Direct Communications	Capability	17	
Diving	Capability	18	
Division	Capability	19	
Dog	Capability	20	
Drilling	Capability	21	
Electro–Optical	Capability	22	
Enhanced	Capability	23	
{Disused}		24	
Fire Direction Center	Capability	25	
Force	Capability	26	
Forward	Capability	27	
Ground Station Module	Capability	28	
Landing Support	Capability	29	
{Disused}		30	
{Disused}		31	
Meteorological	Capability	32	
{Disused}		33	
Missile	Capability	34	

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE A-XXIV. Land unit sector 1 modifier - Continued.

Sector 1 Modifier	Category	Value	Remarks
Mobile Advisor and Support	Capability	35	
Mobile Subscriber Equipment	Capability	36	
Mobility Support	Capability	37	
{Disused}		38	
Multinational	Capability	39	
Multinational Specialized Unit	Capability	40	
Multiple Rocket Launcher	Capability	41	
NATO Medical Role 1	Capability	42	
NATO Medical Role 2	Capability	43	
NATO Medical Role 3	Capability	44	
NATO Medical Role 4	Capability	45	
Naval	Capability	46	
Unmanned Aerial Systems (UAS)	Capability	47	
{Disused}		48	
Operations	Capability	49	
Radar	Capability	50	
Radio Frequency Identification (RFID) Interrogator/Sensor	Capability	51	
{Disused}		52	
{Disused}		53	
{Disused}		54	
Sensor	Capability	55	
{Disused}		56	
Signal Intelligence	Capability	57	
{Disused}		58	
Single Rocket Launcher	Capability	59	
Smoke	Capability	60	
{Disused}		61	
Sound Ranging	Capability	62	
{Disused}		63	
{Disused}		64	
Survey	Capability	65	
Tactical Exploitation	Capability	66	
Target Acquisition	Capability	67	
Topographic/Geospatial	Capability	68	
{Disused}		69	
Video Imagery (Combat Camera)	Capability	70	
Mobility Assault	Capability	71	
Amphibious Warfare Ship	Capability	72	
Load Handling System	Capability	73	
Palletized Load System	Capability	74	
{Disused}		75	
{Disused}		76	
Support	Capability	77	
{Disused}		78	
Route, Reconnaissance, and Clearance	Capability	79	
{Disused}		80	
{Disused}		81	
{Disused}		82	
{Disused}		83	
Assault	Capability	84	

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE A-XXIV. Land unit sector 1 modifier - Continued.

Sector 1 Modifier	Category	Value	Remarks
{Disused}		85	
Criminal Investigation Division	Capability	86	
Digital	Capability	87	
Network or Network Operations	Capability	88	
Airfield, Aerial Port of Debarkation, or Aerial Port of Embarkation	Capability	89	
Pipeline	Capability	90	
Postal	Capability	91	
{Disused}		92	
{Disused}		93	
Theater	Capability	94	
Army or Theater Army	Capability	95	
Corps	Capability	96	
{Disused}		97	
Headquarters or headquarters staff element	Capability	98	
Multi-Domain Operations	Capability	99	

TABLE A-XXV. Land unit sector 2 modifier.

Sector 2 Modifier	Category	Value	Remarks
Unspecified		00	
{Disused}		01	
Arctic	Mobility	02	
Battle Damage Repair	Capability	03	
{Disused}		04	
Casualty Staging	Capability	05	
Clearing	Capability	06	
{Disused}		07	
Control	Capability	08	
Decontamination	Capability	09	
Demolition	Capability	10	
Dental	Capability	11	
Digital	Capability	12	
Enhanced Position Location Reporting System (EPLRS)	Capability	13	
{Disused}		15	
High Altitude	Capability	16	
Intermodal	Capability	17	
Intensive Care	Capability	18	
{Disused}		19	
Laboratory	Capability	20	
Launcher	Capability	21	
{Disused}		22	
Low Altitude	Capability	23	
{Disused}		24	
Medium Altitude	Capability	25	
{Disused}		26	
{Disused}		27	
High to Medium Altitude	Capability	28	
Multi–Channel	Capability	29	
Optical (Flash)	Capability	30	

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE A-XXV. Land unit sector 2 modifier - Continued.

Sector 2 Modifier	Category	Value	Remarks
Pack Animal	Capability	31	
Patient Evacuation Coordination	Capability	32	
Preventive Maintenance	Capability	33	
Psychological	Capability	34	
Radio Relay Line of Sight	Capability	35	
{Disused}		36	
Recovery (Unmanned Systems)	Capability	37	
Recovery (Maintenance)	Capability	38	
Rescue Coordination Center	Capability	39	
Riverine	Mobility	40	
Single Channel	Capability	41	
{Disused}		42	
{Disused}		43	
Strategic	Capability	44	
Support	Capability	45	
Tactical	Capability	46	
Towed	Mobility	47	
Troop	Capability	48	
Vertical or Short Take–Off and Landing (VTOL/VSTOL)	Mobility	49	
Veterinary	Capability	50	
{Disused}		51	
High to Low Altitude	Capability	52	
Medium to Low Altitude	Capability	53	
Attack	Capability	54	
Refuel	Capability	55	
Utility	Capability	56	
Combat Search and Rescue	Capability	57	
Guerrilla	Capability	58	
Air Assault	Mobility	59	
Amphibious	Mobility	60	
Very Heavy	Capability	61	
Supply	Capability	62	
{Disused}		63	
Navy Barge, Self-Propelled	Mobility	64	
Navy Barge, Not Self-Propelled	Mobility	65	
Launch	Mobility	66	
Landing Craft	Mobility	67	
Landing Ship	Mobility	68	
Service Craft/Yard	Mobility	69	
Tug Harbor	Mobility	70	
Ocean Going Tug Boat	Mobility	71	
Surface Deployment and Distribution Command	Capability	72	
Noncombatant Generic Vessel	Mobility	73	
Composite	Capability	74	
Shelter	Capability	75	
{Disused}		76	
{Disused}		77	
{Disused}		78	
{Disused}		79	
{Disused}		80	

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE A-XXV. Land unit sector 2 modifier - Continued.

Sector 2 Modifier	Category	Value	Remarks
Surgical	Capability	81	
Blood	Capability	82	
Combat and Operational Stress Control	Capability	83	
Jamming	Capability	84	
{Disused}		85	
Optometry	Capability	86	
Preventive Medicine	Capability	87	
{Disused}		88	
Air Defense	Capability	89	

A.5.4.7 Land civilian unit/organization (11).

TABLE A-XXVI. Land civilian unit/organization entity/entity type/entity subtype.

Entity (Positions 11 and 12)	Entity Type (Positions 13 and 14)	Entity Subtype (Positions 15 and 16)	Value
Note: The actual value is shown in **bold numbers**. The remaining values are used to show placement within the six positions.			
Unspecified			000000
Civilian			**11**0000
	Environmental Protection		11**01**00
	Government Organization		11**02**00
	Individual		11**03**00
	Organization or Group		11**04**00
	Killing Victim		11**05**00
	Killing Victims		11**06**00
	Victim of an Attempted Crime		11**07**00
	Spy		11**08**00
	Composite Loss		11**09**00
	Emergency Medical Operation		11**10**00

TABLE A-XXVII. Land civilian unit/organization sector 1 modifier.

Sector 1 Modifier	Category	Value	Remarks
Unspecified		00	
{Disused}		01	
{Disused}		02	
Murder Victims	Crime	03	
{Disused}		04	
{Disused}		05	
{Disused}		06	
{Disused}		07	
{Disused}		08	
Displaced Person(s), Refugee(s) and Evacuee(s)	Organization	09	
Foreign Fighter(s)	Organization	10	
Gang Member or Gang	Organization	11	
{Disused}		12	
Leader or Leadership	Organization	13	

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE A-XXVII. Land civilian unit/organization sector 1 modifier - Continued.

Sector 1 Modifier	Category	Value	Remarks
Nongovernmental Organization Member or Nongovernmental Organization	Organization	14	
Unwilling/Coerced Recruit	Organization	15	
Willing Recruit	Organization	16	
Religious or Religious Organization	Organization	17	
Targeted Individual or Organization	Organization	18	
Terrorist or Terrorist Organization	Organization	19	
Speaker	Organization	20	
{Disused}		21	
{Disused}		22	
Other	Composite Loss	23	
Loot	Crime	24	
{Disused}		25	
{Disused}		26	

TABLE A-XXVIII. Land civilian unit/organization sector 2 modifier.

Sector 2 Modifier	Category	Value	Remarks
Unspecified		00	
Leader or Leadership	Organization	01	
{Disused}		02	

A.5.4.8 Land Equipment (15).

TABLE A-XXIX. Land equipment entity/entity type/entity subtype.

Entity (Positions 11 and 12)	Entity Type (Positions 13 and 14)	Entity Subtype (Positions 15 and 16)	Value
Note: The actual value is shown in **bold numbers**. The remaining values are used to show placement within the six positions.			
Unspecified			000000
Weapon/Weapon System			**11**0000
	Rifle		11**01**00
		Single Shot Rifle	1101**01**
		Semiautomatic Rifle	1101**02**
		Automatic Rifle	1101**03**
	Machine Gun		11**02**00
		Light	1102**01**
		Medium	1102**02**
		Heavy	1102**03**
	Grenade Launcher		11**03**00
		Light	1103**01**
		Medium	1103**02**
		Heavy	1103**03**
	Flame Thrower		11**04**00
	Air Defense Gun		11**05**00
		Light	1105**01**
		Medium	1105**02**

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE A-XXIX. Land equipment entity/entity type/entity subtype - Continued.

Entity (Positions 11 and 12)	Entity Type (Positions 13 and 14)	Entity Subtype (Positions 15 and 16)	Value
Note: The actual value is shown in **bold numbers**. The remaining values are used to show placement within the six positions.			
		Heavy	1105**03**
	Antitank Gun		11**06**00
		Light	1106**01**
		Medium	1106**02**
		Heavy	1106**03**
	Direct Fire Gun		11**07**00
		Light	1107**01**
		Medium	1107**02**
		Heavy	1107**03**
	Recoilless Gun		11**08**00
		Light	1108**01**
		Medium	1108**02**
		Heavy	1108**03**
	Howitzer		11**09**00
		Light	1109**01**
		Medium	1109**02**
		Heavy	1109**03**
	Missile Launcher		11**10**00
		Light	1110**01**
		Medium	1110**02**
		Heavy	1110**03**
	Air Defense Missile Launcher		11**11**00
		Light	1111**01**
		Light, Light Transporter-Launcher and Radar (TLAR)	1111**02**
		Light, Light Tactical Landing Approach Radar (TELAR)	1111**03**
		Medium	1111**04**
		Medium, TLAR	1111**05**
		Medium, TELAR	1111**06**
		Heavy	1111**07**
		Heavy, TLAR	1111**08**
		Heavy, TELAR	1111**09**
	Antitank Missile Launcher		11**12**00
		Light	1112**01**
		Medium	1112**02**
		Heavy	1112**03**
	Surface-to-Surface Missile Launcher		11**13**00
		Light	1113**01**
		Medium	1113**02**
		Heavy	1113**03**
	Mortar		11**1400**

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE A-XXIX. Land equipment entity/entity type/entity subtype - Continued.

Entity (Positions 11 and 12)	Entity Type (Positions 13 and 14)	Entity Subtype (Positions 15 and 16)	Value
Note: The actual value is shown in **bold numbers**. The remaining values are used to show placement within the six positions.			
		Light	111400
		Medium	111402
		Heavy	111403
	Single Rocket Launcher		111500
		Light	111501
		Medium	111502
		Heavy	111503
	Multiple Rocket Launcher		111600
		Light	111601
		Medium	111602
		Heavy	111603
	Antitank Rocket Launcher		111700
		Light	111701
		Medium	111702
		Heavy	111703
	Nonlethal Weapon		111800
	Taser		111900
	Water Cannon		112000
Vehicle			120000
	Armored		120100
		Armored Fighting Vehicle	120101
		Armored Fighting Vehicle Command and Control	120102
		Armored Personnel Carrier	120103
		Armored Personnel Carrier Ambulance	120104
		Armored Protected Vehicle	120105
		{Disused}	120106
		{Disused}	120107
		Armored Personnel Carrier, Recovery	120108
		Combat Service Support Vehicle	120109
		{Disused}	120110
		Light Armor Reconnaissance	120111
	Tank		120200
		Light	120201
		Medium	120202
		Heavy	120203
	{Disused}		120300
		{Disused}	120301
		{Disused}	120302
		{Disused}	120303
Engineer Vehicle and Equipment			130000
	Bridge		130100

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE A-XXIX. Land equipment entity/entity type/entity subtype - Continued.

Entity (Positions 11 and 12)	Entity Type (Positions 13 and 14)	Entity Subtype (Positions 15 and 16)	Value
Note: The actual value is shown in **bold numbers**. The remaining values are used to show placement within the six positions.			
	{Disused}		13**02**00
	Fixed Bridge		13**03**00
	Floating Bridge		13**04**00
	Folding Girder Bridge		13**05**00
	Hollow Deck Bridge		13**06**00
	Drill		13**07**00
		Drill Mounted on Utility Vehicle	1307**01**
	Earthmover		13**08**00
		Multifunctional Earthmover/Digger	1308**01**
	Mine Clearing Equipment		13**09**00
		{Disused}	1309**01**
		Mine Clearing Equipment on Tank Chassis	1309**02**
		Assault Breacher Vehicle (ABV) with Combat Dozer Blade	1309**03**
		Medium Capability Equipment	1309**04**
		Heavy Capability Equipment	1309**05**
	Mine Laying Equipment		13**10**00
		Mine Laying Equipment on Utility Vehicle	1310**01**
		Armored Carrier with Volcano	1310**02**
		Truck Mounted with Volcano	1310**03**
	Dozer		13**11**00
		Dozer, Armored	1311**01**
	Armored Assault		13**12**00
	Armored Engineer Recon Vehicle (AERV)		13**13**00
	Backhoe		13**14**00
	Construction Vehicle		13**15**00
	Ferry Transporter		13**16**00
Utility Vehicle			**14**0000
	Vehicle (Generic)		14**01**00
	Medical		14**02**00
	{Disused}		14**03**00
	Mobile Emergency Physician		14**04**00
	Bus		14**05**00
	Semi–Trailer and Truck		14**06**00
		Light	1406**01**
		Medium	1406**02**
		Heavy	1406**03**
	Limited Cross Country Truck		14**07**00
	Cross Country Truck		14**08**00
	Petroleum, Oil and Lubricant		14**09**00

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE A-XXIX. Land equipment entity/entity type/entity subtype - Continued.

Entity (Positions 11 and 12)	Entity Type (Positions 13 and 14)	Entity Subtype (Positions 15 and 16)	Value
Note: The actual value is shown in **bold numbers**. The remaining values are used to show placement within the six positions.			
	Water		14**10**00
	Amphibious Utility Wheeled Vehicle		14**11**00
	Tow Truck		14**12**00
		Light	1412**01**
		Heavy	1412**02**
Train			**15**0000
	Locomotive		15**01**00
Civilian Vehicle			**16**0000
	Automobile		16**01**00
	Open-Bed Truck		16**02**00
	Multiple Passenger Vehicle		16**03**00
	Utility Vehicle		16**04**00
	Jeep Type Vehicle		16**05**00
	Tractor Trailer Truck with Box		16**06**00
	Tractor Trailer Truck with Flatbed Trailer		16**07**00
	Known Insurgent Vehicle		16**08**00
	Drug Vehicle		16**09**00
Law Enforcement			**17**0000
	Bureau of Alcohol, Tobacco, Firearms and Explosives (ATF) (Department of Justice)		17**01**00
	Border Patrol		17**02**00
	Customs Service		17**03**00
	Drug Enforcement Administration (DEA)		17**04**00
	Department of Justice (DOJ)		17**05**00
	Federal Bureau of Investigation (FBI)		17**06**00
	Police		17**07**00
	United States Secret Service (USSS)		17**08**00
	Transportation Security Administration (TSA)		17**09**00
	US Coast Guard		17**10**00
	US Marshals Service		17**11**00
Pack Animals			**18**0000
Missile Support			**19**0000
	Transloader		19**01**00
	Transporter		19**02**00
	Crane/Loading Device		19**03**00
	Propellant Transporter		19**04**00
	Warhead Transporter		19**05**00

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE A-XXIX. Land equipment entity/entity type/entity subtype - Continued.

Entity (Positions 11 and 12)	Entity Type (Positions 13 and 14)	Entity Subtype (Positions 15 and 16)	Value
Note: The actual value is shown in **bold numbers**. The remaining values are used to show placement within the six positions.			
Other Equipment			**20**0000
	Antennae		20**01**00
	Bomb		20**02**00
	Booby Trap		20**03**00
	CBRN Equipment		20**04**00
	Computer System		20**05**00
	Command Launch Equipment (CLE)		20**06**00
	Generator Set		20**07**00
	Ground-based Midcourse Defense (GMD) Fire Control (GFC) Center		20**08**00
	In-Flight Interceptor Communications System (IFICS) Data Terminal (IDT)		20**09**00
	Directed Energy		20**10**00
	Military Information Support Operations (MISO)		20**11**00
	Sustainment Shipments		20**12**00
	Tent		20**13**00
		Civilian	2013**01**
		Military	2013**02**
	Unit Deployment Shipments		20**14**00
	Emergency Medical Operation		20**15**00
Land Mines			**21**0000
	Land Mine		21**01**00
	Antipersonnel Land mine (APL)		21**02**00
	Antitank Mine		21**03**00
	Improvised Explosives Device (IED)		21**04**00
	Less Than Lethal		21**05**00
Sensors			**22**0000
	Sensor		22**01**00
	Sensor Emplaced		22**02**00
	Radar		22**03**00
Emergency Operation			**23**0000
	{Disused}		23**01**00
	Fire Fighting/Fire Protection		23**02**00
Manual Track			**24**0000
Rotary Wing			**25**0000

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE A-XXX. Land equipment sector 1 modifier.

Sector 1 Modifier	Category	Value	Remarks
Unspecified		00	
Biological	Sensor Type	01	
{Disused}		02	
Early Warning Radar	Sensor Type	03	
Intrusion	Sensor Type	04	
{Disused}		05	
{Disused}		06	
Upgraded Early Warning Radar	Sensor Type	07	
{Disused}		08	
{Disused}		09	
{Disused}		10	
{Disused}		11	
Multi-purpose Blade	Capability	12	
Tank-width Mine Plow	Capability	13	
{Disused}		14	
{Disused}		15	
{Disused}		16	
{Disused}		17	
{Disused}		18	
{Disused}		19	
{Disused}		20	
{Disused}		21	
{Disused}		22	
{Disused}		23	
{Disused}		24	
{Disused}		25	
{Disused}		26	
{Disused}		27	

TABLE A-XXXI. Land equipment sector 2 modifier.

Sector 2 Modifier	Category	Value	Remarks
Unspecified		00	
{Disused}		01	
{Disused}		02	
{Disused}		03	
{Disused}		04	
{Disused}		05	
Tractor Trailer	Capability	06	
{Disused}		07	
{Disused}		08	
{Disused}		09	
{Disused}		10	

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

A.5.4.9 Land installations (20).

TABLE A-XXXII. Land installation entity/entity type/entity subtype.

Entity (Positions 11 and 12)	Entity Type (Positions 13 and 14)	Entity Subtype (Positions 15 and 16)	Value
Note: The actual value is shown in **bold numbers**. The remaining values are used to show placement within the six positions.			
Unspecified			000000
Military/Civilian			**11**0000
	Aircraft Production/Assembly		11**01**00
	Ammunition and Explosives Production		11**02**00
	Ammunition Cache		11**03**00
	Armament Production		11**04**00
	Black List Location		11**05**00
	Chemical, Biological, Radiological and Nuclear (CBRN)		11**06**00
	Engineering Equipment Production		11**07**00
		Bridge	1107**01**
	Equipment Manufacture		11**08**00
	Government Leadership		11**09**00
	Gray List Location		11**10**00
	Mass Grave Site		11**11**00
	Materiel		11**12**00
	Mine		11**13**00
	Missile and Space System Production		11**14**00
	Nuclear (Non CBRN Defense)		11**15**00
	Printed Media		11**16**00
	Safe House		11**17**00
	White List Location		11**18**00
	Tented Camp		11**19**00
		Displaced Persons/ Refugee/Evacuees Camp	1119**01**
		Training Camp	1119**02**
	Warehouse/Storage Facility		11**20**00
		Grenade	1120**01**
	Law Enforcement		11**21**00
		Bureau of Alcohol, Tobacco, Firearms and Explosives (ATF) (Department of Justice)	1121**01**
		Border Patrol	1121**02**
		Customs Service	1121**03**
		Drug Enforcement Administration (DEA)	1121**04**
		Department of Justice (DOJ)	1121**05**
		Federal Bureau of Investigation (FBI)	1121**06**
		Police	1121**07**
		Prison	1121**08**

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE A-XXXII. Land installation entity/entity type/entity subtype - Continued.

Entity (Positions 11 and 12)	Entity Type (Positions 13 and 14)	Entity Subtype (Positions 15 and 16)	Value
Note: The actual value is shown in **bold numbers**. The remaining values are used to show placement within the six positions.			
		United States Secret Service (USSS)	1121**09**
		Transportation Security Administration (TSA)	1121**10**
		US Coast Guard	1121**11**
		US Marshals Service	1121**12**
	Emergency Operation		11**22**00
		Fire Station	1122**01**
		Emergency Medical Operation	1122**02**
	Home/House		11**23**00
Infrastructure			**12**0000
	Agriculture and Food		12**01**00
		Agriculture Laboratory	1201**01**
		Animal Feedlot	1201**02**
		Commercial Food Distribution Center	1201**03**
		Farm/Ranch	1201**04**
		Food Distribution	1201**05**
		Food Production Center	1201**06**
		Food Retail	1201**07**
		Grain Storage	1201**08**
	Banking Finance and Insurance		12**02**00
		ATM	1202**01**
		Bank	1202**02**
		Bullion Storage	1202**03**
		Economic Infrastructure Asset	1202**04**
		Federal Reserve Bank	1202**05**
		Financial Exchange	1202**06**
		Financial Services, Other	1202**07**
	Commercial		12**03**00
		Chemical Plant	1203**01**
		Firearms Manufacturer	1203**02**
		Firearms Retailer	1203**03**
		Hazardous Material Production	1203**04**
		Hazardous Material Storage	1203**05**
		Industrial Site	1203**06**
		Landfill	1203**07**
		Pharmaceutical Manufacturer	1203**08**
		Contaminated Hazardous Waste Site	1203**09**
		Toxic Release Inventory	1203**10**
	Educational Facilities		12**04**00
		College/University	1204**01**
		School	1204**02**
	Energy Facility		12**05**00

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE A-XXXII. Land installation entity/entity type/entity subtype - Continued.

Entity (Positions 11 and 12)	Entity Type (Positions 13 and 14)	Entity Subtype (Positions 15 and 16)	Value
Note: The actual value is shown in **bold numbers**. The remaining values are used to show placement within the six positions.			
		Electric Power	120**501**
		Generation Station	120**502**
		Natural Gas Facility	120**503**
		{Disused}	120**504**
		Petroleum/Gas/Oil	120**505**
		Propane Facility	120**506**
	Government Site		12**0600**
	Medical		12**0700**
		Medical	120**701**
		Medical Treatment Facility (Hospital)	120**702**
	Military		12**0800**
		Military Armory	120**801**
		Military Base	120**802**
		Airport/Air Base	120**803**
	Postal Services		12**0900**
		Postal Distribution Center	120**901**
		Post Office	120**902**
	Public Venues		12**1000**
		Enclosed Facility (Public Venue)	121**001**
		Open Facility (Public Venue)	121**002**
		Recreational Area	121**003**
		Religious Institution	121**004**
	Special Needs		12**1100**
		Adult Day Care	121**101**
		Child Day Care	121**102**
		Elder Care	121**103**
	Telecommunications		12**1200**
		Broadcast Transmitter Antennae	121**201**
		Telecommunications	121**202**
		Telecommunications Tower	121**203**
	Transportation		12**1300**
		Aerial Port of Debarkation / Aerial Port of Embarkation	121**301**
		Air Traffic Control Facility	121**302**
		Bus Station	121**303**
		Ferry Terminal	121**304**
		Helicopter Landing Site	121**305**
		Maintenance Facility	121**306**
		Railhead/Railroad Station	121**307**
		Rest Stop	121**308**
		Sea Port/Naval Base	121**309**
		Ship Yard	121**310**

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE A-XXXII. Land installation entity/entity type/entity subtype - Continued.

Entity (Positions 11 and 12)	Entity Type (Positions 13 and 14)	Entity Subtype (Positions 15 and 16)	Value
Note: The actual value is shown in **bold numbers**. The remaining values are used to show placement within the six positions.			
		Toll Facility	1213**11**
		Traffic Inspection Facility	1213**12**
		Tunnel	1213**13**
	Water Supply		12**14**00
		Control Valve	1214**01**
		Dam	1214**02**
		Discharge Outfall	1214**03**
		Ground Water Well	1214**04**
		Pumping Station	1214**05**
		Reservoir	1214**06**
		Storage Tower	1214**07**
		Surface Water Intake	1214**08**
		Wastewater Treatment Facility	1214**09**
		Water	1214**10**
		Water Treatment	1214**11**

TABLE A-XXXIII. Land installation sector 1 modifier.

Sector 1 Modifier	Category	Value	Remarks
Unspecified		00	
Biological	CBRN Type	01	
{Disused}		02	
{Disused}		03	
{Disused}		04	
{Disused}		05	
Coal	Electric Power Type	06	
Geothermal	Electric Power Type	07	
Hydroelectric	Electric Power Type	08	
Natural Gas	Electric Power Type	09	
{Disused}		10	
{Disused}		11	
Civilian Telephone	Telecommunication Type	12	
Civilian Television	Telecommunication Type	13	
{Disused}		14	

TABLE A-XXXIV. Land installation sector 2 modifier.

Sector 2 Modifier	Category	Value	Remarks
Unspecified		00	
Biological Warfare Production	Capability	01	
Chemical Warfare Production	Capability	02	
Nuclear Warfare Production	Capability	03	
Radiological Warfare Production	Capability	04	
Atomic Energy Reactor	Capability	05	
Nuclear Material Production	Capability	06	
Nuclear Material Storage	Capability	07	

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE A-XXXIV. Land installation sector 2 modifier – Continued.

Weapons Grade Production	Capability	08	
{Disused}		09	
Transportation	Capability	10	

A.5.4.10 Control measure (25).

TABLE A-XXXV. Control measure entity/entity type/entity subtype.

Entity (Positions 11 and 12)	Entity Type (Positions 13 and 14)	Entity Subtype (Positions 15 and 16)	Geometric Rendering	Value
Note: The actual value is shown in **bold numbers**. The remaining values are used to show placement within the six positions.				
Command and Control Lines				**11**0000
	Boundary		Line	11**01**00
	Light Line		Line	11**02**00
	Engineer Work Line		Line	11**03**00
	Generic		Line	11**04**00
	Decision Line			11**05**00
Command and Control Areas				**12**0000
	Area of Operations		Area	12**01**00
	Named Area of Interest		Area	12**02**00
	Targeted Area of Interest		Area	12**03**00
	Airfield Zone		Area	12**04**00
	Base Camp		Area	12**05**00
	Guerrilla Base		Area	12**06**00
	Generic		Area	12**07**00
Command and Control Points				**13**0000
	Action Point (General)		Point	13**01**00
	Amnesty Point		Point	13**02**00
	Checkpoint		Point	13**03**00
	Center of Main Effort		Point	13**04**00
	Contact Point		Point	13**05**00
	Coordinating Point		Point	13**06**00
	Decision Point		Point	13**07**00
	Distress Call		Point	13**08**00
	Entry Control Point		Point	13**09**00
	Fly-To-Point			13**10**00
		Sonobuoy	Point	1310**01**
		Weapon	Point	1310**02**
		Normal	Point	1310**03**
	Linkup Point		Point	13**11**00
	Passage Point		Point	13**12**00
	Point of Interest		Point	13**13**00
		Launch Event	Point	1313**01**

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE A-XXXV. Control measure entity/entity type/entity subtype - Continued.

Entity (Positions 11 and 12)	Entity Type (Positions 13 and 14)	Entity Subtype (Positions 15 and 16)	Geometric Rendering	Value
Note: The actual value is shown in **bold numbers**. The remaining values are used to show placement within the six positions.				
	Rally Point		Point	131**4**00
	Release Point		Point	131**5**00
	Start Point		Point	131**6**00
	Special Point		Point	131**7**00
	Waypoint		Point	131**8**00
	Airfield		Point	131**9**00
	Target Handover		Point	132**0**00
	Key Terrain		Point	132**1**00
	Control Point		Point	132**2**00
	Vital Ground		Point	132**3**00
Maneuver Lines				**14**0000
	Forward Line of Troops		Line	140**1**00
	{Disused}			140**2**00
	Phase Line		Line	140**3**00
	Forward Edge of the Battle Area		Line	140**4**00
	Principle Direction of Fire		Line	140**5**00
	Direction of Attack		Line	140**6**00
		Friendly Aviation	Line	14060**1**
		Friendly Main Attack /Decisive	Line	14060**2**
		Friendly Supporting Attack	Line	14060**3**
		Feint	Line	14060**5**
	Final Coordination Line		Line	140**7**00
	Infiltration Lane		Line	140**8**00
	Limit of Advance		Line	140**9**00
	Line of Departure		Line	141**0**00
	Line of Departure/Line of Contact		Line	141**1**00
	Probable Line of Deployment		Line	141**2**00
	Airhead Line		Line	141**3**00
	Bridgehead Line		Line	141**4**00
	Holding Line		Line	141**5**00
	Release Line		Line	141**6**00
	Ambush		Line	141**7**00
	Handover Line		Line	141**8**00
	Battle Handover Line		Line	141**9**00
Maneuver Areas				**15**0000
	Area		Area	150**1**00
	Assembly Area		Area	150**2**00
	{Disused}			150**3**00
	{Disused}			150**4**00
	Action Area			150**5**00

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE A-XXXV. Control measure entity/entity type/entity subtype - Continued.

Entity (Positions 11 and 12)	Entity Type (Positions 13 and 14)	Entity Subtype (Positions 15 and 16)	Geometric Rendering	Value
Note: The actual value is shown in **bold numbers**. The remaining values are used to show placement within the six positions.				
		Joint Tactical Action Area (JTAA)	Area	1505**01**
		Submarine Action Area (SAA)	Area	1505**02**
		Submarine-Generated Action Area (SGAA)	Area	1505**03**
	Drop Zone		Area	15**06**00
	Extraction Zone		Area	15**07**00
	Landing Zone		Area	15**08**00
	Pick–Up Zone		Area	15**09**00
	Fortified Area		Area	15**10**00
	Limited Access Area		Area	15**11**00
	Battle Position		Area	15**12**00
		Prepared (P) but not Occupied	Area	1512**02**
		Strong Point	Area	1512**03**
		Contain	Area	1512**04**
		Retain	Area	1512**05**
	Engagement Area (EA)		Area	15**13**00
	Axis of Advance			15**14**00
		Friendly Airborne/Aviation	Line	1514**01**
		Attack Helicopter	Line	1514**02**
		Main Attack	Line	1514**03**
		Supporting Attack	Line	1514**04**
	Assault Position		Area	15**15**00
	Attack Position		Area	15**16**00
	Objective Area		Area	15**17**00
	Encirclement			15**18**00
	Penetration Box		Area	15**19**00
	Attack by Fire		Area	15**20**00
	Support by Fire		Area	15**21**00
	Search Area/Reconnaissance Area		Area	15**22**00
Maneuver Points				**16**0000
	Observation Post/Outpost (unspecified)		Point	16**01**00
	Observation Post/Outpost (specified)		Point	16**02**00
		Reconnaissance Outpost	Point	1602**01**
		Forward Observer/Spotter Outpost/Position	Point	1602**02**
		CBRN Observation Outpost	Point	1602**03**
		Sensor Outpost /Listening Post	Point	1602**04**
		Combat Outpost	Point	1602**05**
	Target Reference Point		Point	16**03**00

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE A-XXXV. Control measure entity/entity type/entity subtype - Continued.

Entity (Positions 11 and 12)	Entity Type (Positions 13 and 14)	Entity Subtype (Positions 15 and 16)	Geometric Rendering	Value
Note: The actual value is shown in **bold numbers**. The remaining values are used to show placement within the six positions.				
	Point of Departure		Point	16**04**00
Airspace Control (Corridors) Areas				**17**0000
	Air Corridor		Area	17**01**00
	Low Level Transit Route		Area	17**02**00
	Minimum–Risk Route		Area	17**03**00
	Safe Lane		Area	17**04**00
	Standard Use Army Aircraft Flight Route		Area	17**05**00
	Transit Corridor		Area	17**06**00
	Special Corridor		Area	17**07**00
	Base Defense Zone		Area	17**08**00
	High–Density Airspace Control Zone		Area	17**09**00
	Restricted Operations Zone (ROZ)		Area	17**10**00
	Air-to-Air Restricted Operating Zone (AARROZ)		Area	17**11**00
	Unmanned Aircraft Restricted Operating Zone (UA-ROZ)		Area	17**12**00
	Weapon Engagement Zone		Area	17**13**00
	Fighter Engagement Zone (FEZ)		Area	17**14**00
	Joint Engagement Zone (JEZ)		Area	17**15**00
	Missile Engagement Zone (MEZ)		Area	17**16**00
	Low Altitude Missile Engagement Zone (LOMEZ)		Area	17**17**00
	High Altitude Missile Engagement Zone (HIMEZ)		Area	17**18**00
	Short Range Air Defense Engagement Zone (SHORADEZ)		Area	17**19**00
	Weapons Free Zone		Area	17**20**00
Airspace Control Points				**18**0000
	Air Control Point		Point	18**01**00
	Communications Checkpoint		Point	18**02**00
	Isolated Personnel Recovery Point		Point	18**03**00
	Pop–up Point		Point	18**04**00
	Air Control Rendezvous		Point	18**05**00
	Tactical Air Navigation (TACAN)		Point	18**06**00
	Combat Air Patrol (CAP)Station		Point	18**07**00
	Airborne Early Warning (AEW) Station		Point	18**08**00
	ASW (Helo and F/W) Station		Point	18**09**00
	Strike Initial Point		Point	18**10**00
	Replenishment Station		Point	18**11**00

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE A-XXXV. Control measure entity/entity type/entity subtype - Continued.

Entity (Positions 11 and 12)	Entity Type (Positions 13 and 14)	Entity Subtype (Positions 15 and 16)	Geometric Rendering	Value
Note: The actual value is shown in **bold numbers**. The remaining values are used to show placement within the six positions.				
	Tanking		Point	181**2**00
	Antisubmarine Warfare, Rotary Wing		Point	181**3**00
	Surface Combat Air Patrol (SUCAP) – Fixed Wing		Point	181**4**00
	SUCAP – Rotary Wing		Point	181**5**00
	MIW – Fixed Wing		Point	181**6**00
	MIW – Rotary Wing		Point	181**7**00
	Tomcat		Point	181**8**00
	Rescue		Point	181**9**00
	Unmanned Aerial System (UAS/UA)		Point	182**0**00
	Vertical Takeoff and Landing (VTOL) Tactical Unmanned Aircraft (VTUA)		Point	182**1**00
	Orbit		Point	182**2**00
	Orbit – Figure Eight		Point	182**3**00
	Orbit – Race Track		Point	182**4**00
	Orbit – Random Closed		Point	182**5**00
	Isolated Personnel Location		Point	182**6**00
Airspace Control Lines				**19**0000
	Identification Friend or Foe (IFF) Off Line		Line	19**01**00
	Identification Friend or Foe (IFF) On Line		Line	19**02**00
Maritime Control Areas				**20**0000
	Launch Area			20**01**00
		Ellipse/Circle	Area	20010**1**
	Defended Area			20**02**00
		Ellipse/Circle	Area	20020**1**
		Rectangle	Area	20020**2**
	No Attack (NOTACK) Zone		Area	20**03**00
	Ship Area of Interest		Point	20**04**00
		Ellipse/Circle	Area	20040**1**
		Rectangle	Area	20040**2**
	Active Maneuver Area		Point	20**05**00
	Cued Acquisition Doctrine		Point	20**06**00
	Radar Search Doctrine		Point	20**07**00
Maritime Control Points				**21**0000
	Plan Ship		Point	21**01**00
	Aim Point		Point	21**02**00
	Defended Asset		Point	21**03**00

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE A-XXXV. Control measure entity/entity type/entity subtype - Continued.

Entity (Positions 11 and 12)	Entity Type (Positions 13 and 14)	Entity Subtype (Positions 15 and 16)	Geometric Rendering	Value
Note: The actual value is shown in **bold numbers**. The remaining values are used to show placement within the six positions.				
	Drop Point		Point	21**04**00
	Entry Point		Point	21**05**00
	Air Detonation		Point	21**06**00
	Ground Zero		Point	21**07**00
	Impact Point		Point	21**08**00
	Predicted Impact Point		Point	21**09**00
	Launched Torpedo		Point	21**10**00
	Missile Detection Point		Point	21**11**00
	Acoustic Countermeasure (Decoy)		Point	21**12**00
	Electronic Countermeasures (ECM) Decoy		Point	21**13**00
	Brief Contact		Point	21**14**00
	Datum Lost Contact		Point	21**15**00
	BT Buoy Drop		Point	21**16**00
	Reported Bottomed Sub		Point	21**17**00
	Moving Haven		Point	21**18**00
	Screen Center		Point	21**19**00
	Lost Contact		Point	21**20**00
	Sinker		Point	21**21**00
	Trial Track		Point	21**22**00
	Acoustic Fix		Point	21**23**00
	Electromagnetic Fix		Point	21**24**00
	Electromagnetic – Magnetic Anomaly Detection (MAD)		Point	21**25**00
	Optical Fix		Point	21**26**00
	Formation		Point	21**27**00
	Harbor		Point	21**28**00
	Harbor Entrance Point		Point	21**29**00
		A	Point	2129**01**
		Q	Point	2129**02**
		X	Point	2129**03**
		Y	Point	2129**04**
	Dip Position		Point	21**30**00
	Search		Point	21**31**00
	Search Area		Point	21**32**00
	Search Center		Point	21**33**00
	Navigational Reference Point		Point	21**34**00
	Sonobuoy		Point	21**35**00
		Ambient Noise	Point	2135**01**
		Air Transportable Communication (ATAC)	Point	2135**02**
		Barra	Point	2135**03**

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE A-XXXV. Control measure entity/entity type/entity subtype - Continued.

Entity (Positions 11 and 12)	Entity Type (Positions 13 and 14)	Entity Subtype (Positions 15 and 16)	Geometric Rendering	Value
Note: The actual value is shown in **bold numbers**. The remaining values are used to show placement within the six positions.				
		Bathythermograph Transmitting	Point	2135**04**
		Command Active Multi-Beam Sonobuoy (CAMBS)	Point	2135**05**
		Command Active Sonobuoy Directional Command Active Sonobuoy System (CASS)	Point	2135**06**
		Directional Frequency Analysis and Recording (DIFAR)	Point	2135**07**
		Directional Command Active Sonobuoy System (DICASS)	Point	2135**08**
		Expendable Reliable Acoustic Path Sonobuoy (ERAPS)	Point	2135**09**
		Expired	Point	2135**10**
		Kingpin	Point	2135**11**
		Low Frequency Analysis and Recording (LOFAR)	Point	2135**12**
		Pattern Center	Point	2135**13**
		Range Only	Point	2135**14**
		Vertical Line Array Directional Frequency Analysis and Recording (DIFAR)	Point	2135**15**
	Reference Point		Point	21**36**00
	Special Point		Point	21**37**00
	Navigational Reference Point		Point	21**38**00
	Data Link Reference Point		Point	21**39**00
	{Disused}			21**40**00
	Vital Area Center		Point	21**41**00
	Corridor Tab Point		Point	21**42**00
	Enemy Point		Point	21**43**00
	Marshall Point		Point	21**44**00
	Position and Intended Movement (PIM)		Point	21**45**00
	Pre-Landfall Waypoint		Point	21**46**00
	Estimated Position (EP)		Point	21**47**00
	Waypoint		Point	21**48**00
	General Sea Subsurface Station		Point	21**49**00
	Submarine Sea Subsurface Station		Point	21**50**00
	Submarine Antisubmarine Warfare Sea Subsurface Station		Point	21**51**00
	Unmanned Underwater Vehicle Sea Subsurface Station		Point	21**52**00

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE A-XXXV. Control measure entity/entity type/entity subtype - Continued.

Entity (Positions 11 and 12)	Entity Type (Positions 13 and 14)	Entity Subtype (Positions 15 and 16)	Geometric Rendering	Value
Note: The actual value is shown in **bold numbers**. The remaining values are used to show placement within the six positions.				
	Antisubmarine Warfare (ASW) Unmanned Underwater Vehicle Sea Subsurface Station		Point	21**53**00
	Mine Warfare Unmanned Underwater Vehicle Sea Subsurface Station		Point	21**54**00
	Sea Surface Warfare Unmanned Underwater Vehicle Subsurface Station		Point	21**55**00
	General Sea Surface Station		Point	21**56**00
	Antisubmarine Warfare (ASW) Sea Surface Station		Point	21**57**00
	Mine Warfare Sea Surface Station		Point	21**58**00
	Non-Combatant Sea Surface Station		Point	21**59**00
	Picket Sea Surface Station		Point	21**60**00
	Rendezvous Sea Surface Station		Point	21**61**00
	Replenishment at Sea Surface Station		Point	21**62**00
	Rescue Sea Surface Station		Point	21**63**00
	Surface Warfare Sea Surface Station		Point	21**64**00
	Unmanned Underwater Vehicle Sea Surface Station		Point	21**65**00
	Antisubmarine Warfare (ASW) Unmanned Underwater Vehicle Sea Surface Station		Point	21**66**00
	Mine Warfare Unmanned Underwater Vehicle Sea Surface Station		Point	21**67**00
	Remote Multi-Mission Vehicle Mine Warfare Unmanned Underwater Sea Surface Station		Point	21**68**00
	Surface Warfare Mine Warfare Unmanned Underwater Vehicle Sea Surface Station		Point	21**69**00
	Shore Control Station		Point	21**70**00
	General Route		Point	21**71**00
	Diversion Route		Point	21**72**00
	Position and Intended Movement (PIM) Route		Point	21**73**00
	Picket Route		Point	21**74**00
	Point R Route		Point	21**75**00
	Rendezvous Route		Point	21**76**00
	Waypoint Route		Point	21**77**00
	Clutter, Stationary or Cease Reporting		Point	21**78**00
	Tentative or Provisional Track		Point	21**79**00
	Distressed Vessel		Point	21**80**00
	Ditched Aircraft/Downed Aircraft		Point	21**81**00
	Person in Water/Bailout		Point	21**82**00

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE A-XXXV. Control measure entity/entity type/entity subtype - Continued.

Entity (Positions 11 and 12)	Entity Type (Positions 13 and 14)	Entity Subtype (Positions 15 and 16)	Geometric Rendering	Value
Note: The actual value is shown in **bold numbers**. The remaining values are used to show placement within the six positions.				
	Iceberg		Point	21**83**00
	Navigational		Line	21**84**00
	Oil Rig		Point	21**85**00
	Sea Mine–Like		Point	21**86**00
	Bottom Return/Non-Mine, Mine-Like Bottom Object (NOMBO)		Point	21**87**00
	Bottom Return/Non-Mine, Mine-Like Bottom Object (NOMBO)/Installation Manmade		Point	21**88**00
	Marine Life		Point	21**89**00
	Sea Anomaly (Wake, Current, Knuckle)		Point	21**90**00
	Bottom Return/Non-MILCO, Wreck, Dangerous		Point	21**91**00
	Bottom Return/Non-MILCO, Wreck, Non Dangerous		Point	21**92**00
Maritime Control Lines				**22**0000
	Bearing Line		Line	22**01**00
		Electronic	Line	220101
		Electromagnetic Warfare (EW)	Line	220102
		Acoustic	Line	220103
		Acoustic (Ambiguous)	Line	220104
		Torpedo	Line	220105
		Electro-Optical Intercept	Line	220106
		Jammer	Line	220107
		Radio Direction Finder (RDF)	Line	220108
{Disused}				**23**0000
Fires Areas				**24**0000
	Airspace Coordination Area			24**01**00
		Irregular	Area	240101
		Rectangular	Area	240102
		Circular	Area	240103
	Free Fire Area			24**02**00
		Irregular	Area	240201
		Rectangular	Area	240202
		Circular	Area	240203
	No Fire Area			24**03**00
		Irregular	Area	240301
		Rectangular	Area	240302
		Circular	Area	240303
	Restricted Fire Area			24**04**00

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE A-XXXV. Control measure entity/entity type/entity subtype - Continued.

Entity (Positions 11 and 12)	Entity Type (Positions 13 and 14)	Entity Subtype (Positions 15 and 16)	Geometric Rendering	Value
Note: The actual value is shown in **bold numbers**. The remaining values are used to show placement within the six positions.				
		Irregular	Area	240**401**
		Rectangular	Area	240**402**
		Circular	Area	240**403**
	Position Area For Artillery (PAA)			24**0500**
		Rectangular	Area	240**501**
		Circular	Area	240**502**
		Irregular	Area	240**503**
	Point Targets			24**0600**
		Point or Single Target	Point	240**601**
		Nuclear Target	Point	240**602**
		Target-Recorded	Point	240**603**
	Linear Targets			24**0700**
		Linear Target	Line	240**701**
		Linear Smoke Target	Line	240**702**
		Final Protective Fire (FPF)	Line	240**703**
	Area Targets			24**0800**
		Area Target	Area	240**801**
		Rectangular Target	Area	240**802**
		Circular Target	Area	240**803**
		Rectangular Target – Single Target	Area	240**804**
		Series or Groups of Targets	Area	240**805**
		Smoke	Area	240**806**
		{Disused}		240**807**
		Bomb Area	Area	240**808**
	Fire Support Station		Point	24**0900**
	Fire Support Area			24**1000**
		Irregular	Area	241**001**
		Rectangular	Area	241**002**
		Circular	Area	241**003**
	Artillery Target Intelligence Zone			24**1100**
		Irregular	Area	241**101**
		Rectangular	Area	241**102**
		Circular	Area	241**103**
	Call for Fire Area			24**1200**
		Irregular	Area	241**201**
		Rectangular	Area	241**202**
		Circular	Area	241**203**
	Censor Zone			24**1300**
		Irregular	Area	241**301**
		Rectangular	Area	241**302**
		Circular	Area	241**303**

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE A-XXXV. Control measure entity/entity type/entity subtype - Continued.

Entity (Positions 11 and 12)	Entity Type (Positions 13 and 14)	Entity Subtype (Positions 15 and 16)	Geometric Rendering	Value
Note: The actual value is shown in **bold numbers**. The remaining values are used to show placement within the six positions.				
	Critical Friendly Zone			24**14**00
		Irregular	Area	2414**01**
		Rectangular	Area	2414**02**
		Circular	Area	2414**03**
	Dead Space Area			24**15**00
		Irregular	Area	2415**01**
		Rectangular	Area	2415**02**
		Circular	Area	2415**03**
	{*Disused*}			24**16**00
	Target Build–up Area			24**17**00
		Irregular	Area	2417**01**
		Rectangular	Area	2417**02**
		Circular	Area	2417**03**
	Target Value Area			24**18**00
		Irregular	Area	2418**01**
		Rectangular	Area	2418**02**
		Circular	Area	2418**03**
	Zone of Responsibility			24**19**00
		Irregular	Area	2419**01**
		Rectangular	Area	2419**02**
		Circular	Area	2419**03**
	Terminally Guided Munition Footprint (TGMF)		Area	24**20**00
	Weapon/Sensor Range fan, Circular		Area	24**21**00
	Weapon/Sensor Range fan, Sector		Area	24**22**00
	Kill Box			24**23**00
		Irregular, Blue	Area	2423**01**
		Rectangular, Blue	Area	2423**02**
		Circular, Blue	Area	2423**03**
		Irregular, Purple	Area	2423**04**
		Rectangular, Purple	Area	2423**05**
		Circular, Purple	Area	2423**06**
Fires Points				**25**0000
	Firing Point		Point	25**01**00
	Hide Point		Point	25**02**00
	Launch Point		Point	25**03**00
	Reload Point		Point	25**04**00
	Survey Control Point		Point	25**05**00
	Known Point		Point	25**06**00
Fire Lines				**26**0000
	Fire Support Coordination Line (FSCL)		Line	26**01**00

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE A-XXXV. Control measure entity/entity type/entity subtype - Continued.

Entity (Positions 11 and 12)	Entity Type (Positions 13 and 14)	Entity Subtype (Positions 15 and 16)	Geometric Rendering	Value
Note: The actual value is shown in **bold numbers**. The remaining values are used to show placement within the six positions.				
	Coordinated Fire Line (CFL)		Line	26**02**00
	No Fire Line		Line	26**03**00
	Battlefield Coordination Line		Line	26**04**00
	Restrictive Fire Line		Line	26**05**00
	Munition Flight Path		Line	26**06**00
Protection Areas				**27**0000
	Obstacle Belt		Area	27**01**00
	Obstacle Zone		Area	27**02**00
	Obstacle Free Zone		Area	27**03**00
	Obstacle Restricted Zone		Area	27**04**00
	Obstacle Effects			27**05**00
		Block	Area	2705**01**
		Disrupt	Area	2705**02**
		Fix	Line	2705**03**
		Turn	Line	2705**04**
	Obstacle Bypass			27**06**00
		Easy	Point	2706**01**
		Difficult	Point	2706**02**
		Impossible	Point	2706**03**
	Minefield			27**07**00
		Static Depiction	Point	2707**01**
		Dynamic Depiction	Area	2707**07**
	Mined Area		Area	27**08**00
		Fenced	Area	27**08**01
	Unexploded Explosive Ordnance (UXO) Area		Area	27**10**00
	Bridge or Gap		Line	27**11**00
	Roadblocks, Craters and Blown Bridges			27**12**00
		Planned	Line	2712**01**
		Explosives, State of Readiness 1 (Safe)	Line	2712**02**
		Explosives, State of Readiness 2 (armed but passable)	Line	2712**03**
		Roadblock Complete (Executed)	Line	2712**04**
	Assault Crossing		Line	27**13**00
	{Disused}			27**14**00
	Ford Easy		Line	27**15**00
	Ford Difficult		Line	27**16**00
	Biological Contaminated Area		Area	27**17**00
	Chemical Contaminated Area		Area	27**18**00
	Nuclear Contaminated Area		Area	27**19**00

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE A-XXXV. Control measure entity/entity type/entity subtype - Continued.

Entity (Positions 11 and 12)	Entity Type (Positions 13 and 14)	Entity Subtype (Positions 15 and 16)	Geometric Rendering	Value
Note: The actual value is shown in **bold numbers**. The remaining values are used to show placement within the six positions.				
	Radiological Contaminated Area		Area	27**20**00
	Minimum Safe Distance Zone		Area	27**21**00
		Multiple Strikes – STRIKWARN	Area	2721**01**
	Radiation Dose Rate Contour Lines		Area	27**22**00
Protection Points				**28**0000
	Abatis		Point	28**01**00
	Antipersonnel Mine		Point	28**02**00
		Antipersonnel Mine with Directional Effects	Point	2802**01**
	Antitank Mine		Point	28**03**00
	Antitank Mine with Anti-handling Device		Point	28**04**00
	Wide Area Antitank Mine		Point	28**05**00
	Unspecified Mine		Point	28**06**00
	Booby Trap		Point	28**07**00
	Engineer Regulating Point		Point	28**08**00
	Shelter		Point	28**09**00
	Above Ground Shelter		Point	28**10**00
	Below Ground Shelter		Point	28**11**00
	Fort		Point	28**12**00
	Chemical Event		Point	28**13**00
	Biological Event		Point	28**14**00
	Nuclear Event		Point	28**15**00
	Nuclear Fallout Producing Event		Point	28**16**00
	Radiological Event		Point	28**17**00
	General Decontamination Point/Site		Point	28**18**00
		Alternate	Point	2818**01**
		Equipment	Point	2818**02**
		Troop	Point	2818**03**
		Equipment/Troop	Point	2818**04**
		Operational	Point	2818**05**
		Thorough	Point	2818**06**
		Main Equipment	Point	2818**07**
		Forward Troop	Point	2818**08**
		Wounded Personnel	Point	2818**09**
	Tetrahedrons, Dragons Teeth, and Other Similar Obstacles			28**19**00
		Fixed and Prefabricated	Point	2819**01**
		Movable	Point	2819**02**
		Movable and Prefabricated	Point	2819**03**
	Vertical Obstructions			28**20**00
		Tower, Low	Point	2820**01**

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE A-XXXV. Control measure entity/entity type/entity subtype - Continued.

Entity (Positions 11 and 12)	Entity Type (Positions 13 and 14)	Entity Subtype (Positions 15 and 16)	Geometric Rendering	Value
Note: The actual value is shown in **bold numbers**. The remaining values are used to show placement within the six positions.				
		Tower, High	Point	282**02**
		Overhead Wire	Line	282**03**
Protection Lines				**29**0000
	Obstacle Line		Line	29**01**00
		Mineline	Line	2901**01**
	Antitank Obstacles			29**02**00
		Ditch Under Construction	Line	2902**01**
		Ditch Completed	Line	2902**02**
		Ditch Reinforced, with Antitank Mines	Line	2902**03**
		Antitank Wall	Line	2902**04**
	Wire Obstacles			29**03**00
		Unspecified	Line	2903**01**
		Single Fence	Line	2903**02**
		Double Fence	Line	2903**03**
		Double Apron Fence	Line	2903**04**
		Low Wire Fence	Line	2903**05**
		High Wire Fence	Line	2903**06**
		Single Concertina	Line	2903**07**
		Double Strand Concertina	Line	2903**08**
		Triple Strand Concertina	Line	2903**09**
	Mine Cluster		Area	29**04**00
	Trip Wire		Line	29**05**00
	Lane		Line	29**06**00
	Ferry		Line	29**07**00
	Raft Site		Line	29**08**00
	Fortified Line		Line	29**09**00
	Fighting Position		Line	29**10**00
Intelligence Lines				**30**0000
	Intelligence Coordination Line		Line	30**01**00
Sustainment Areas				**31**0000
	Detainee Holding Area		Area	31**01**00
	Enemy Prisoner of War (EPW) Holding Area		Area	31**02**00
	Forward Arming and Refueling Point (FARP)		Area	31**03**00
	Refugee Holding Area		Area	31**04**00
	Regimental Support Area		Area	31**05**00
	Brigade Support Area		Area	31**06**00
	Division Support Area		Area	31**07**00
	Corps Support Area		Area	31**08**00

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE A-XXXV. Control measure entity/entity type/entity subtype - Continued.

Entity (Positions 11 and 12)	Entity Type (Positions 13 and 14)	Entity Subtype (Positions 15 and 16)	Geometric Rendering	Value
Note: The actual value is shown in **bold numbers**. The remaining values are used to show placement within the six positions.				
Sustainment Points				**32**0000
	Ambulance Points		Point	32**01**00
		Ambulance Exchange Point	Point	3201**01**
		Ambulance Control Point	Point	3201**02**
		Ambulance Load Point	Point	3201**03**
		Ambulance Relay Point	Point	3201**04**
	Ammunition Supply Point		Point	32**02**00
	Ammunition Transfer and Holding Point		Point	32**03**00
	Cannibalization Point		Point	32**04**00
	Casualty Collection Point		Point	32**05**00
	Civilian Collection Point		Point	32**06**00
	Detainee Collection Point		Point	32**07**00
	Enemy Prisoner of War (EPW) Collection Point		Point	32**08**00
	Logistics Release Point (LRP)		Point	32**09**00
	Maintenance Collection Point (MCP)		Point	32**10**00
	Medical Evacuation Point (MEDEVAC) Pick-Up Point		Point	32**11**00
	Rearm, Refuel and Resupply Point (R3P)		Point	32**12**00
	Refuel on the Move (ROM) Point		Point	32**13**00
	Traffic Control Post (TCP)		Point	32**14**00
	Trailer Transfer Point (TTP)		Point	32**15**00
	Unit Maintenance Collection Point (UNCP)		Point	32**16**00
	General Supply Point		Point	32**17**00
		NATO Class I	Point	3217**01**
		NATO Class II	Point	3217**02**
		NATO Class III	Point	3217**03**
		NATO Class IV	Point	3217**04**
		NATO Class V	Point	3217**05**
		NATO Multiple Class	Point	3217**06**
		US Class I	Point	3217**07**
		US Class II	Point	3217**08**
		US Class III	Point	3217**09**
		US Class IV	Point	3217**10**
		US Class V	Point	3217**11**
		US Class VI	Point	3217**12**
		US Class VII	Point	3217**13**
		US Class VIII	Point	3217**14**
		US Class IX	Point	3217**15**

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE A-XXXV. Control measure entity/entity type/entity subtype - Continued.

Entity (Positions 11 and 12)	Entity Type (Positions 13 and 14)	Entity Subtype (Positions 15 and 16)	Geometric Rendering	Value
Note: The actual value is shown in **bold numbers**. The remaining values are used to show placement within the six positions.				
		US Class X	Point	3217**16**
	Medical Supply Point		Point	32**18**00
	Mortuary Affairs Collection Point		Point	32**19**00
Sustainment Lines				**33**0000
	Moving Convoy		Line	33**01**00
	Halted Convoy		Line	33**02**00
	Main Supply Route (MSR)		Line	33**03**00
		One Way Traffic	Line	330**301**
		Two Way Traffic	Line	330**302**
		Alternating Traffic	Line	330**303**
	Alternate Supply Route (ASR)		Line	33**04**00
		One Way Traffic	Line	330**401**
		Two Way Traffic	Line	330**402**
		Alternating Traffic	Line	330**403**
	Traffic Route		Line	33**05**00
		One Way Traffic	Line	330**501**
		Alternating Traffic	Line	330**502**
Mission Tasks				**34**0000
	Block		Area	34**01**00
	Breach		Line	34**02**00
	Bypass		Point	34**03**00
	Canalize		Point	34**04**00
	Clear		Line	34**05**00
	Counterattack		Line	34**06**00
	Counterattack by Fire		Line	34**07**00
	Delay		Line	34**08**00
	Destroy		Point	34**09**00
	Disrupt		Area	34**10**00
	Fix		Line	34**11**00
	Follow and Assume		Line	34**12**00
	Follow and Support		Line	34**13**00
	Interdict		Point	34**14**00
	Isolate		Area	34**15**00
	Neutralize		Point	34**16**00
	Occupy		Area	34**17**00
	Penetrate		Area	34**18**00
	Relief in Place (RIP)		Area	34**19**00
	Retire/Retirement		Line	34**20**00
	Secure		Area	34**21**00
	Security			34**22**00
		Cover	Line	3422**01**

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE A-XXXV. Control measure entity/entity type/entity subtype - Continued.

Entity (Positions 11 and 12)	Entity Type (Positions 13 and 14)	Entity Subtype (Positions 15 and 16)	Geometric Rendering	Value
Note: The actual value is shown in **bold numbers**. The remaining values are used to show placement within the six positions.				
		Guard	Line	3422**02**
		Screen	Line	3422**03**
	Seize		Line	34**23**00
	Withdraw		Line	34**24**00
	Withdraw Under Pressure		Line	34**25**00
	Cordon and Knock		Area	34**26**00
	Cordon and Search		Area	34**27**00
	Suppress		Point	34**28**00
	Forward Passage of Lines		Line	34**41**00
	Rearward Passage of Lines		Line	34**42**00

TABLE A-XXXVI. Control Measures sector 1 modifier.

Sector 1 Modifier	Capability	Value	Remarks
Unspecified		00	
Wheeled limited cross country	Mobility	01	
Wheeled cross country	Mobility	02	
Tracked	Mobility	03	
Wheeled and tracked combination	Mobility	04	
Towed	Mobility	05	
Rail	Mobility	06	
Pack Animals	Mobility	09	
Sled	Mobility	08	
Pack Animals	Mobility	09	
Barge	Mobility	10	
Amphibious	Mobility	11	
No Vehicles	Mobility	12	
Unspecified Mine	Obstacles	13	
Antipersonnel Mine	Obstacles	14	
Antipersonnel Mine with Directional Effects	Obstacles	15	
Antitank Mine	Obstacles	16	
Antitank Mine with Antihandling Device	Obstacles	17	
Wide Area Antitank Mine	Obstacles	18	
Mine Cluster	Obstacles	19	
Antipersonnel Mine and Antipersonnel Mine with Directional Effects	Obstacles	20	
Antipersonnel Mine and Antitank Mine	Obstacles	21	
Antipersonnel Mine and Antitank Mine with Antihandling Device	Obstacles	22	
Antipersonnel Mine and Wide Area Antitank Mine	Obstacles	23	
Antipersonnel Mine and Mine Cluster	Obstacles	24	
Antipersonnel Mine with Directional Effects and Antitank Mine	Obstacles	25	
Antipersonnel Mine with Directional Effects and Antitank Mine with Antihandling Device	Obstacles	26	

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE A-XXXVI. Control Measures sector 1 modifier - Continued.

Sector 1 Modifier	Capability	Value	Remarks
Antipersonnel Mine with Directional Effects and Wide Area Antitank Mine	Obstacles	27	
Antipersonnel Mine with Directional Effects and Mine Cluster	Obstacles	28	
Antitank Mine and Antitank Mine with Antihandling Device	Obstacles	29	
Antitank Mine and Wide Area Antitank Mine	Obstacles	30	
Antitank Mine and Mine Cluster	Obstacles	31	
Antitank Mine with Antihandling Device and Wide Area Antitank Mine	Obstacles	32	
Antitank Mine with Antihandling Device and Mine Cluster	Obstacles	33	
Wide Area Antitank Mine and Mine Cluster	Obstacles	34	
Antipersonnel Mine, Antipersonnel Mine with Directional Effects, and Antitank Mine	Obstacles	35	
Antipersonnel Mine, Antipersonnel Mine with Directional Effects, and Antitank Mine with Antihandling Device	Obstacles	36	
Antipersonnel Mine, Antipersonnel Mine with Directional Effects, and Wide Area Antitank Mine	Obstacles	37	
Antipersonnel Mine, Antipersonnel Mine with Directional Effects, and Mine Cluster	Obstacles	38	
Antipersonnel Mine, Antitank Mine, and Antitank Mine with Antihandling Device	Obstacles	39	
Antipersonnel Mine, Antitank Mine, and Wide Area Antitank Mine	Obstacles	40	
Antipersonnel Mine, Antitank Mine, and Mine Cluster	Obstacles	41	
Antipersonnel Mine, Antitank Mine with Antihandling Device, and Wide Area Antitank Mine	Obstacles	42	
Antipersonnel Mine, Antitank Mine with Antihandling Device, and Mine Cluster	Obstacles	43	
Antipersonnel Mine, Wide Area Antitank Mine, and Mine Cluster	Obstacles	44	
Antipersonnel Mine with Directional Effects, Antitank Mine, and Antitank Mine with Antihandling Device	Obstacles	45	
Antipersonnel Mine with Directional Effects, Antitank Mine, and Wide Area Antitank Mine	Obstacles	46	
Antipersonnel Mine with Directional Effects, Antitank Mine, and Mine Cluster	Obstacles	47	
Antipersonnel Mine with Directional Effects, Antitank Mine with Antihandling Device, and Wide Area Antitank Mine	Obstacles	48	
Antipersonnel Mine with Directional Effects, Antitank Mine with Antihandling Device, and Mine Cluster	Obstacles	49	
Antipersonnel Mine with Directional Effects, Wide Area Antitank Mine, and Mine Cluster	Obstacles	50	

TABLE A-XXXVII. Control Measures sector 2 modifier.

Sector 2 Modifier	Capability	Value	Remarks
Unspecified		00	

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

A.5.4.11 Dismounted individual (27).

TABLE A-XXXVIII. Dismounted individual.

Entity (Positions 11 and 12)	Entity Type (Positions 13 and 14)	Entity Subtype (Positions 15 and 16)	Value
Note: The actual value is shown in **bold numbers**. The remaining values are used to show placement within the six positions.			
Military			**11**0000
	{Disused}		11**01**00
	Activity/Task		11**02**00
		Explosive Ordnance Disposal	1102**01**
		Field Artillery Observer	1102**02**
		Joint Fire Support	1102**03**
		Liaison	1102**04**
		Messenger	1102**05**
		Military Police	1102**06**
		Observer	1102**07**
		Security	1102**08**
		Sniper	1102**09**
		Special Operation Forces	1102**10**
		Designated Marksman	1102**11**
		Medic	1102**12**
		Signaler	1102**13**
		Reconnaissance	1102**14**
		Infantry	1102**15**
		Close Protection	1102**16**
		Crowd and Riot Control	1102**17**
		SWAT	1102**18**
		Demolition	1102**19**
		Commander (CDR)	1102**20**
		Second in Command (SIC)	1102**21**
	Lethal Weapons		11**03**00
		Rifle	1103**01**
		Single Shot Rifle	1103**02**
		Semiautomatic Rifle	1103**03**
		Automatic Rifle	1103**04**
		Machine Gun	1103**05**
		Machine Gun - Light	1103**06**
		Machine Gun - Medium	1103**07**
		Machine Gun - Heavy	1103**08**
		Grenade Launcher	1103**09**
		Grenade Launcher - Light	1103**10**
		Grenade Launcher - Medium	1103**11**
		Grenade Launcher - Heavy	1103**12**
		Flame Thrower	1103**13**
		Mortar	1103**14**
		Single Rocket Launcher	1103**15**

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE A-XXXVIII. Dismounted individual - Continued.

Entity (Positions 11 and 12)	Entity Type (Positions 13 and 14)	Entity Subtype (Positions 15 and 16)	Value
Note: The actual value is shown in **bold numbers**. The remaining values are used to show placement within the six positions.			
		Antitank Rocket Launcher	1103**16**
	Non-Lethal Weapons		11**04**00
		Non-Lethal Weapon	1104**01**
		Non-Lethal Grenade Launcher	1104**02**
		Taser	1104**03**

TABLE A-XXXIX. Dismounted individual sector 1 modifier.

Sector 1 Modifier	Category	Value	Remarks
Unspecified		00	
{Disused}		01	
{Disused}		02	
{Disused}		03	
{Disused}		04	
{Disused}		05	
{Disused}		06	
Non-Governmental Organization Member		07	
{Disused}		10	
Field Artillery Observer		11	
Joint Fire Support		12	
Liaison		13	
Messenger		14	
Military Police		15	
Observer		16	
Designated Marksman		17	
{Disused}		18	
{Disused}		19	
Signaler		20	
Reconnaissance		21	
Infantry		22	
Commander (CDR)		23	
Second in Command (SIC)		24	
Demolition		25	
Police		26	
Individual		46	
{Disused}		47	
{Disused}		48	
{Disused}		49	
{Disused}		50	
{Disused}		51	
{Disused}		52	
{Disused}		53	
{Disused}		54	

TABLE A-XL. Dismounted individual sector 2 modifier.

Sector 2 Modifier	Category	Value	Remarks
Unspecified		00	

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE A-XL. Dismounted individual sector 2 modifier - Continued.

Sector 2 Modifier	Category	Value	Remarks
{Disused}		01	
{Disused}		02	
Video Imagery (Combat Camera)		03	
Functional Staff Area J1		04	
Functional Staff Area J2		05	
Functional Staff Area J3		06	
Functional Staff Area J4		07	
Functional Staff Area J5		08	
Functional Staff Area J6		09	
Functional Staff Area J7		10	
Functional Staff Area J8		11	
Functional Staff Area J9		12	
{Disused}		13	
Rank OF-1		14	
Rank OF-2		15	
Rank OF-3		16	
Rank OF-4		17	
Rank OF-5		18	
Rank OF-6		19	
Rank OF-7		20	
Rank OF-8		21	
Rank OF-9		22	
Rank OF-10		23	
Rank E-1		25	
Rank E-2		26	
Rank E-3		27	
Rank E-4		28	
Rank E-5		29	
Rank E-6		30	
Rank E-7		31	
Rank E-8		32	
Rank E-9		33	
Rank WO-1		34	
Rank WO-2		35	
Rank WO-3		36	
Rank WO-4		37	
Rank WO-5		38	
{Disused}		39	

A.5.4.12 Sea surface (30).

TABLE A-XLI. Sea surface entity/entity type/entity subtype.

Entity (Positions 11 and 12)	Entity Type (Positions 13 and 14)	Entity Subtype (Positions 15 and 16)	Value
Note: The actual value is shown in **bold numbers**. The remaining values are used to show placement within the six positions.			
Unspecified			000000
Military			**11**0000
Military Combatant			**12**0000

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE A-XLI. Sea surface entity/entity type/entity subtype - Continued.

Entity (Positions 11 and 12)	Entity Type (Positions 13 and 14)	Entity Subtype (Positions 15 and 16)	Value
Note: The actual value is shown in **bold numbers**. The remaining values are used to show placement within the six positions.			
	Carrier		12**01**00
	Surface Combatant, Line		12**02**00
		Battleship	1202**01**
		Cruiser	1202**02**
		Destroyer	1202**03**
		Frigate	1202**04**
		Corvette	1202**05**
		Littoral Combatant Ship	1202**06**
	Amphibious Warfare Ship		12**03**00
		Amphibious Command Ship	1203**01**
		Amphibious Assault, Non-specified	1203**02**
		Amphibious Assault Ship, General	1203**03**
		Amphibious Assault Ship, Multipurpose	1203**04**
		Amphibious Assault Ship, Helicopter	1203**05**
		Amphibious Transport Dock	1203**06**
		Landing Ship	1203**07**
		Landing Craft	1203**08**
	Mine Warfare Ship		12**04**00
		Mine Layer	1204**01**
		Mine Sweeper	1204**02**
		Mine Sweeper, Drone	1204**03**
		Mine Hunter	1204**04**
		Mine Countermeasures	1204**05**
		Mine Countermeasures, Support Ship	1204**06**
	Patrol Boat		12**05**00
		Patrol Craft, Submarine Chaser/Escort, General	1205**01**
		Patrol Ship, General	1205**02**
	Decoy		12**06**00
	Unmanned Surface Water Vehicle (USV)		12**07**00
	Speedboat		12**08**00
		Rigid–Hull Inflatable Boat (RHIB)	1208**01**
	Jet Ski		12**09**00
	Navy Task Organization		12**10**00
		Navy Task Element	1210**01**
		Navy Task Force	1210**02**
		Navy Task Group	1210**03**
		Navy Task Unit	1210**04**
		Convoy	1210**05**
	Sea-Based X-Band Radar		12**11**00
Military Non Combatant			**13**0000

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE A-XLI. Sea surface entity/entity type/entity subtype - Continued.

Entity (Positions 11 and 12)	Entity Type (Positions 13 and 14)	Entity Subtype (Positions 15 and 16)	Value
Note: The actual value is shown in **bold numbers**. The remaining values are used to show placement within the six positions.			
	Auxiliary Ship		13**01**00
		Ammunition Ship	1301**01**
		Naval Stores Ship	1301**02**
		Auxiliary Flag Ship	1301**03**
		Intelligence Collector	1301**04**
		Oceanographic Research Ship	1301**05**
		Survey Ship	1301**06**
		Hospital Ship	1301**07**
		Naval Cargo Ship	1301**08**
		Combat Support Ship, Fast	1301**09**
		Oiler, Replenishment	1301**10**
		Repair Ship	1301**11**
		Submarine Tender	1301**12**
		Tug, Ocean Going	1301**13**
	Service Craft/Yard		13**02**00
		Barge, not Self–Propelled	1302**01**
		Barge, Self–Propelled	1302**02**
		Tug, Harbor	1302**03**
		Launch	1302**04**
Civilian			**14**0000
	Merchant Ship		14**01**00
		Cargo, General	1401**01**
		Container Ship	1401**02**
		Dredge	1401**03**
		Roll On/Roll Off	1401**04**
		Ferry	1401**05**
		Heavy Lift	1401**06**
		Hovercraft	1401**07**
		Lash Carrier (with Barges)	1401**08**
		Oiler/Tanker	1401**09**
		Passenger	1401**10**
		Tug, Ocean Going	1401**11**
		Tow	1401**12**
		Transport Ship, Hazardous Material	1401**13**
		Junk/Dhow	1401**14**
		Barge, not Self–Propelled	1401**15**
		Hospital Ship	1401**16**
	Fishing Vessel		14**02**00
		Drifter	1402**01**
		Trawler	1402**02**
		Dredger	1402**03**
	Law Enforcement Vessel		14**03**00

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE A-XLI. Sea surface entity/entity type/entity subtype - Continued.

Entity (Positions 11 and 12)	Entity Type (Positions 13 and 14)	Entity Subtype (Positions 15 and 16)	Value
Note: The actual value is shown in **bold numbers**. The remaining values are used to show placement within the six positions.			
	Leisure Craft, Sailing		14**04**00
	Leisure Craft, Motorized		14**05**00
		Rigid–Hull Inflatable Boat (RHIB)	1405**01**
		Speedboat	1405**02**
	Jet Ski		14**06**00
	Unmanned Surface Water Vehicle (USV)		14**07**00
Own Ship			**15**0000
Fused Track			**16**0000
Manual Track			**17**0000

TABLE A-XLII. Sea surface sector 1 modifier.

Sector 1 Modifier	Category	Value	Remarks
Unspecified	Mission Area	00	
Own Ship	Mission Area	01	APP6
Antiair Warfare	Mission Area	02	
{Disused}		03	
{Disused}		04	
Electromagnetic Warfare	Mission Area	05	
{Disused}		06	
{Disused}		07	
Missile Defense	Mission Area	08	
Medical	Mission Area	09	
{Disused}		10	
Remote Multi-mission Vehicle (RMV)	Mission Area	11	USV–only
{Disused}		12	
{Disused}		13	
{Disused}		14	
{Disused}		15	
{Disused}		16	
Torpedo	Weapons Capability	17	
Drone–Equipped	Asset Capability	18	
{Disused}		19	
{Disused}		20	
Ballistic Missile Defense, Long-Range Surveillance and Track (LRS&T)	Mission Area	21	
Sea-Base X-Band	Mission Area	22	
{Disused}		23	
{Disused}		24	
{Disused}		25	

TABLE A-XLIII. Sea surface sector 2 modifier.

Sector 2 Modifier	Category	Value	Remarks
Unspecified		00	
Nuclear Powered	Ship Propulsion	01	
{Disused}		02	
{Disused}		03	

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE A-XLIII. Sea surface sector 2 modifier - Continued.

Sector 2 Modifier	Category	Value	Remarks
{Disused}		04	
Dock	Cargo Capacity	05	
Logistics	Cargo Capacity	06	
Tank	Cargo Capacity	07	
Vehicle	Cargo Capacity	08	
Fast	Ship Mobility	09	
Air–Cushioned (US)	Ship Mobility	10	
Air–Cushioned (NATO)	Ship Mobility	11	
Hydrofoil	Ship Mobility	12	
{Disused}		13	
{Disused}		14	
{Disused}		15	
{Disused}		16	

A.5.4.13 Sea subsurface (35).

TABLE A-XLIV. Sea subsurface entity/entity type/entity subtype.

Entity (Positions 11 and 12)	Entity Type (Positions 13 and 14)	Entity Subtype (Positions 15 and 16)	Value
Note: The actual value is shown in **bold numbers**. The remaining values are used to show placement within the six positions.			
Unspecified			000000
Military			**11**0000
	Submarine		11**01**00
		Submarine, Surfaced	1101**01**
		Submarine, Snorkeling	1101**02**
		Submarine, Bottomed	1101**03**
	Other Submersible		11**02**00
	Nonsubmarine		11**03**00
	Autonomous Underwater Vehicle (AUV)/Unmanned Underwater Vehicle (UUV)		11**04**00
	Diver		11**05**00
Civilian			**12**0000
	Submersible		12**01**00
	Autonomous Underwater Vehicle (AUV)/ Unmanned Underwater Vehicle (UUV)		12**02**00
	Diver		12**03**00
Weapon			**13**0000
	Torpedo		13**01**00
	Improvised Explosive Device (IED)		13**02**00
	Decoy		13**03**00
Echo Tracker Classifier (ETC) / Possible Contact (POSCON)			**14**0000
Fused Track			**15**0000

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE A-XLIV. Sea subsurface entity/entity type/entity subtype - Continued.

Entity (Positions 11 and 12)	Entity Type (Positions 13 and 14)	Entity Subtype (Positions 15 and 16)	Value
Note: The actual value is shown in **bold numbers**. The remaining values are used to show placement within the six positions.			
Manual Track			**16**0000

TABLE A-XLV. Sea subsurface sector 1 modifier.

Sector 1 Modifier	Category	Value	Remarks
Unspecified		00	
{Disused}		01	
Auxiliary	Mission Area	02	
{Disused}		03	
{Disused}		04	
{Disused}		05	
{Disused}		06	
{Disused}		07	
{Disused}		08	
{Disused}		09	
{Disused}		10	
{Disused}		11	
{Disused}		12	
Possible Submarine Low 1	Submarine Confidence	13	
Possible Submarine Low 2	Submarine Confidence	14	
Possible Submarine High 3	Submarine Confidence	15	
Possible Submarine High 4	Submarine Confidence	16	
Probable Submarine	Submarine Confidence	17	
Certain Submarine	Submarine Confidence	18	
Anti-torpedo Torpedo	Weapons Capability	19	
{Disused}		20	
{Disused}		21	
{Disused}		22	

TABLE A-XLVI. Sea subsurface sector 2 modifier.

Sector 2 Modifier	Category	Value	Remarks
Unspecified		00	
Air Independent Propulsion	Ship Propulsion	01	
Diesel Electric, General	Ship Propulsion	02	
Diesel – Type 1	Ship Propulsion	03	
Diesel – Type 2	Ship Propulsion	04	
Diesel – Type 3	Ship Propulsion	05	
Nuclear Powered, General	Ship Propulsion	06	
Nuclear – Type 1	Ship Propulsion	07	
Nuclear – Type 2	Ship Propulsion	08	
Nuclear – Type 3	Ship Propulsion	09	
Nuclear – Type 4	Ship Propulsion	10	
Nuclear – Type 5	Ship Propulsion	11	
Nuclear – Type 6	Ship Propulsion	12	
Nuclear – Type 7	Ship Propulsion	13	
{Disused}		14	
{Disused}		15	

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE A-XLVI. Sea subsurface sector 2 modifier - Continued.

{Disused}		16	
{Disused}		17	

A.5.4.14 Mine warfare (36).

TABLE A-XLVII. Mine warfare entity/entity type/entity subtype.

Entity (Positions 11 and 12)	Entity Type (Positions 13 and 14)	Entity Subtype (Positions 15 and 16)	Value
Note: The actual value is shown in **bold numbers**. The remaining values are used to show placement within the six positions.			
Unspecified			000000
Sea Mine, General			**11**0000
	Sea Mine, Bottom		11**01**00
	Sea Mine, Moored		11**02**00
	Sea Mine, Floating		11**03**00
	Sea Mine, Rising		11**04**00
	Sea Mine, Other Position		11**05**00
	Kingfisher		11**06**00
	Small Object, Mine–Like		11**07**00
	Exercise Mine, General		11**08**00
		Exercise Mine, Bottom	1108**01**
		Exercise Mine, Moored	1108**02**
		Exercise Mine, Floating	1108**03**
		Exercise Mine, Rising	1108**04**
	Neutralized Mine, General		11**09**00
		Neutralized Mine, Bottom	1109**01**
		Neutralized Mine, Moored	1109**02**
		Neutralized Mine, Floating	1109**03**
		Neutralized Mine, Rising	1109**04**
		Neutralized Mine, Other Position	1109**05**
Unexploded Ordnance			**12**0000
Sea Mine Decoy			**13**0000
	Sea Mine Decoy, Bottom		13**01**00
	Sea Mine Decoy, Moored		13**02**00
Mine–Like Contact (MILCO)			**14**0000
	MILCO - General		14**01**00
		MILCO - General, Confidence Level 1	1401**01**
		MILCO - General, Confidence Level 2	1401**02**
		MILCO - General, Confidence Level 3	1401**03**
		MILCO - General, Confidence Level 4	1401**04**

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE A-XLVII. Mine warfare entity/entity type/entity subtype - Continued.

Entity (Positions 11 and 12)	Entity Type (Positions 13 and 14)	Entity Subtype (Positions 15 and 16)	Value
Note: The actual value is shown in **bold numbers**. The remaining values are used to show placement within the six positions.			
		MILCO - General, Confidence Level 5	1401**05**
	MILCO - Bottom		14**02**00
		MILCO - Bottom, Confidence Level 1	1402**01**
		MILCO - Bottom, Confidence Level 2	1402**02**
		MILCO - Bottom, Confidence Level 3	1402**03**
		MILCO - Bottom, Confidence Level 4	1402**04**
		MILCO - Bottom, Confidence Level 5	1402**05**
	MILCO - Moored		14**03**00
		MILCO - Moored, Confidence Level 1	1403**01**
		MILCO - Moored, Confidence Level 2	1403**02**
		MILCO - Moored, Confidence Level 3	1403**03**
		MILCO - Moored, Confidence Level 4	1403**04**
		MILCO - Moored, Confidence Level 5	1403**05**
	MILCO - Floating		14**04**00
		MILCO - Floating, Confidence Level 1	1404**01**
		MILCO - Floating, Confidence Level 2	1404**02**
		MILCO - Floating, Confidence Level 3	1404**03**
		MILCO - Floating, Confidence Level 4	1404**04**
		MILCO - Floating, Confidence Level 5	1404**05**
Mine–Like Echo (MILEC), General			**15**0000
	Mine–Like Echo, Bottom		15**01**00
	Mine–Like Echo, Moored		15**02**00
	Mine–Like Echo, Floating		15**03**00
Negative Reacquisition, General			**16**0000
	Negative Reacquisition, Bottom		16**01**00
	Negative Reacquisition, Moored		16**02**00

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE A-XLVII. Mine warfare entity/entity type/entity subtype - Continued.

Entity (Positions 11 and 12)	Entity Type (Positions 13 and 14)	Entity Subtype (Positions 15 and 16)	Value
Note: The actual value is shown in **bold numbers**. The remaining values are used to show placement within the six positions.			
	Negative Reacquisition, Floating		16**03**00
Obstructor			**17**0000
	Neutralized Obstructor		17**01**00
General Mine Anchor			**18**0000
Non-Mine Mine–Like Object (NMLO), General			**19**0000
	Non-Mine Mine–Like Object, Bottom		19**01**00
	Non-Mine Mine–Like Object, Moored		19**02**00
	Non-Mine Mine–Like Object, Floating		19**03**00
Environmental Report Location			**20**0000
Dive Report Location			**21**0000

A.5.4.15 Activities (40).

TABLE A-XLVIII. Activities entity/entity type/entity subtype.

Entity (Positions 11 and 12)	Entity Type (Positions 13 and 14)	Entity Subtype (Positions 15 and 16)	Value
Note: The actual value is shown in **bold numbers**. The remaining values are used to show placement within the six positions.			
Unspecified			000000
Incident			**11**0000
	Criminal Activity Incident		11**01**00
		Arrest/Apprehend/Detain	1101**01**
		Arson	1101**02**
		Drive-by Shooting	1101**04**
		Extortion	1101**06**
		Graffiti	1101**07**
		Killing	1101**08**
		Poisoning	1101**09**
		Civil Rioting	1101**10**
		Booby Trap	1101**11**
		{Disused}	1101**12**
		Black Marketing	1101**13**
		Vandalism/Loot/Ransack/Plunder	1101**14**
		Jail Break	1101**15**
		Robbery	1101**16**
		Theft	1101**17**

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE A-XLVIII. Activities entity/entity type/entity subtype - Continued.

Entity (Positions 11 and 12)	Entity Type (Positions 13 and 14)	Entity Subtype (Positions 15 and 16)	Value
Note: The actual value is shown in **bold numbers**. The remaining values are used to show placement within the six positions.			
		Burglary	1101**18**
		Smuggling	1101**19**
		Rock Throwing	1101**20**
		Dead Body	1101**21**
		Sabotage	1101**22**
		Suspicious Activity	1101**23**
	Bomb/Bombing		11**02**00
		Bomb Threat	1102**01**
	IED Event		11**03**00
		IED Explosion	1103**01**
		Premature IED Explosion	1103**02**
		IED Cache	1103**03**
		IED Suicide Bomber	1103**04**
	Shooting		11**04**00
		Sniping	1104**01**
	Illegal Drug Operation		11**05**00
		Trafficking	1105**01**
		Illegal Drug Lab	1105**02**
	Explosion		11**06**00
		Grenade Explosion	1106**01**
		Incendiary Explosion	1106**02**
		Mine Explosion	1106**03**
		Mortar Fire Explosion	1106**04**
		Rocket Explosion	1106**05**
		Bomb Explosion	1106**06**
	Home/House		11**07**00
Civil Disturbance			**12**0000
	Demonstration		12**01**00
Operation			**13**0000
	Patrolling		13**01**00
	Military Information Support Operation (MISO)		13**02**00
		TV and Radio Propaganda	1302**01**
	Foraging/Searching		13**03**00
	Recruitment		13**04**00
		Willing	1304**01**
		Unwilling/Coerced	1304**02**
	Mine Laying		13**05**00
	Spy		13**06**00
	Warrant Served		13**07**00
	Exfiltration		13**08**00
	Infiltration		13**09**00

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE A-XLVIII. Activities entity/entity type/entity subtype - Continued.

Entity (Positions 11 and 12)	Entity Type (Positions 13 and 14)	Entity Subtype (Positions 15 and 16)	Value
Note: The actual value is shown in **bold numbers**. The remaining values are used to show placement within the six positions.			
	Meeting		13**10**00
		Polling Place/Election	1310**01**
	{Disused}		13**11**00
	Emergency Operation		13**12**00
		Emergency Collection Evacuation Point	1312**01**
		Emergency Food Distribution	1312**02**
		Emergency Incident Command Center	1312**03**
		Emergency Operations Center	1312**04**
		Emergency Public Information Center	1312**05**
		Emergency Shelter	1312**06**
		Emergency Staging Area	1312**07**
		Emergency Water Distribution Center	1312**08**
	Emergency Medical Operation		13**13**00
		EMT Station Location	1313**01**
		Health Department Facility	1313**02**
		Medical Facilities Outpatient	1313**03**
		Morgue	1313**04**
		Pharmacy	1313**05**
		Triage	1313**06**
	Fire Fighting Operation		13**14**00
		Fire Hydrant	1314**01**
		{Disused}	1314**02**
		Other Water Supply Location	1314**03**
	Law Enforcement Operation		13**15**00
		Bureau of Alcohol, Tobacco, Firearms and Explosives (ATF) (Department of Justice)	1315**01**
		Border Patrol	1315**02**
		Customs Service	1315**03**
		Drug Enforcement Administration (DEA)	1315**04**
		Department of Justice (DOJ)	1315**05**
		Federal Bureau of Investigation (FBI)	1315**06**
		Police	1315**07**
		Prison	1315**08**
		United States Secret Service (USSS)	1315**09**
		Transportation Security Administration (TSA)	1315**10**
		US Coast Guard	1315**11**
		US Marshals Service	1315**12**
		Internal Security Force	1315**13**
Fire Event			**14**0000
	Fire Origin		14**01**00
	Smoke		14**02**00
	Hot Spot		14**03**00

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE A-XLVIII. Activities entity/entity type/entity subtype - Continued.

Entity (Positions 11 and 12)	Entity Type (Positions 13 and 14)	Entity Subtype (Positions 15 and 16)	Value
Note: The actual value is shown in **bold numbers**. The remaining values are used to show placement within the six positions.			
	Non-Residential Fire		14**04**00
	Residential Fire		14**05**00
	School Fire		14**06**00
	Special Needs Fire		14**07**00
	WildFire		14**08**00
Hazardous Materials			**15**0000
	Hazardous Materials Incident		15**01**00
		Chemical Agent	1501**01**
		Corrosive Material	1501**02**
		Hazardous when Wet	1501**03**
		Explosive Material	1501**04**
		Flammable Gas	1501**05**
		Flammable Liquid	1501**06**
		Flammable Solid	1501**07**
		Non-Flammable Gas	1501**08**
		Organic Peroxide	1501**09**
		Oxidizer	1501**10**
		Radioactive Material	1501**11**
		Spontaneously Combustible Material	1501**12**
		Toxic Gas	1501**13**
		Toxic Infectious Material	1501**14**
		Unexploded Ordnance	1501**15**
Transportation Incident			**16**0000
	Air		16**01**00
	Marine		16**02**00
	Rail		16**03**00
	Vehicle		16**04**00
	Wheeled Vehicle Explosion		16**05**00
Natural Event			**17**0000
	Geologic		17**01**00
		Aftershock	1701**01**
		Avalanche	1701**02**
		Earthquake Epicenter	1701**03**
		Landslide	1701**04**
		Subsidence	1701**05**
		Volcanic Eruption	1701**06**
		Volcanic Threat	1701**07**
		Cave Entrance	1701**08**
	Hydro-Meteorological		17**02**00
		Drought	1702**01**
		Flood	1702**02**

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE A-XLVIII. Activities entity/entity type/entity subtype - Continued.

Entity (Positions 11 and 12)	Entity Type (Positions 13 and 14)	Entity Subtype (Positions 15 and 16)	Value
Note: The actual value is shown in **bold numbers**. The remaining values are used to show placement within the six positions.			
		Tsunami	1702**03**
	Infestation		17**03**00
		Bird	1703**01**
		Insect	1703**02**
		Microbial	1703**03**
		Reptile	1703**04**
		Rodent	1703**05**
Individual			**18**0000
	Religious Leader		18**01**00
	Speaker		18**02**00

TABLE A-XLIX. Activities sector 1 modifier.

Sector 1 Modifier	Category	Value	Remarks
Unspecified		00	
{Disused}		01	
{Disused}		02	
{Disused}		03	
House–to–House	Military Information Support Operations	04	
{Disused}		05	
Murder	Crime	06	
{Disused}		07	
{Disused}		08	
Written Military Information Support Operations	Military Information Support Operations	09	
Pirate	Crime	10	
False	IED Category	11	
Find	IED Category	12	
Found and Cleared	IED Category	13	
Hoax (Decoy)	IED Category	14	
Attempted	Incident Qualifier	15	
{Disused}		16	
Incident	Incident Qualifier	17	
Theft	Crime	18	
{Disused}		19	
{Disused}		20	
Eviction	Incident Qualifier	21	
Raid	Incident Qualifier	22	

TABLE A-L. Activities sector 2 modifier.

Sector 2 Modifier	Category	Value	Remarks
Unspecified		00	
{Disused}		01	
{Disused}		02	

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

A.5.4.16 Atmospheric (45).

TABLE A-LI. Atmospheric entity/entity type/entity subtype.

Entity (Positions 11 and 12)	Entity Type (Positions 13 and 14)	Entity Subtype (Positions 15 and 16)	Geometric Rendering	Value
Note: The actual value is shown in **bold numbers**. The remaining values are used to show placement within the six positions.				
Pressure Systems				**11**0000
	Low Pressure Center		Point	11**01**00
		Cyclone Center	Point	1101**01**
		Tropopause Low	Point	1101**02**
	High Pressure Center		Point	11**02**00
		Anticyclone Center	Point	1102**01**
		Tropopause High	Point	1102**02**
	Frontal Systems		Point	11**03**00
		Cold Front	Line	1103**01**
		Upper Cold Front	Line	1103**02**
		Cold Frontogenesis	Line	1103**03**
		Cold Frontolysis	Line	1103**04**
		Warm Front	Line	1103**05**
		Upper Warm Front	Line	1103**06**
		Warm Frontogenesis	Line	1103**07**
		Warm Frontolysis	Line	1103**08**
		Occluded Front	Line	1103**09**
		Upper Occluded Front	Line	1103**10**
		Occluded Frontolysis	Line	1103**11**
		Stationary Front	Line	1103**12**
		Upper Stationary Front	Line	1103**13**
		Stationary Frontogenesis	Line	1103**14**
		Stationary Frontolysis	Line	1103**15**
	Lines			11**04**00
		Trough Axis	Line	1104**01**
		Trough	Line	1104**02**
		Ridge Axis	Line	1104**03**
		Severe Squall Line	Line	1104**04**
		Instability Line	Line	1104**05**
		Shear Line	Line	1104**06**
		Inter–Tropical Convergence Zone	Line	1104**07**
		Convergence Line	Line	1104**08**
		Inter–Tropical Discontinuity	Line	1104**09**
	Pressure Tendency			11**05**00
		Rise Then Fall Higher	Point	1105**01**
		Rise Then Steady	Point	1105**02**
		Rise	Point	1105**03**
		Rise Then Rise Higher	Point	1105**04**
		Steady	Point	1105**05**

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE A-LI. Atmospheric entity/entity type/entity subtype - Continued.

Entity (Positions 11 and 12)	Entity Type (Positions 13 and 14)	Entity Subtype (Positions 15 and 16)	Geometric Rendering	Value
Note: The actual value is shown in **bold numbers**. The remaining values are used to show placement within the six positions.				
		Fall Then Rise Lower	Point	110**506**
		Fall Then Steady	Point	110**507**
		Fall	Point	110**508**
		Rise Then Fall Lower	Point	110**509**
Turbulence				**12**0000
	Light		Point	12**01**00
	Moderate		Point	12**02**00
	Severe		Point	12**03**00
	Extreme		Point	12**04**00
	Mountain Waves		Point	12**05**00
Icing				**13**0000
	Clear Icing			13**01**00
		Light	Point	1301**01**
		Moderate	Point	1301**02**
		Severe	Point	1301**03**
	Rime Icing			13**02**00
		Light	Point	1302**01**
		Moderate	Point	1302**02**
		Severe	Point	1302**03**
	Mixed Icing			13**03**00
		Light	Point	1303**01**
		Moderate	Point	1303**02**
		Severe	Point	1303**03**
Winds				**14**0000
	Calm Winds		Point	14**01**00
	Wind Plot		Point	14**02**00
	Jet Stream		Line	14**03**00
	Stream Line		Line	14**04**00
Cloud Cover				**15**0000
	Cloud Coverage Symbols			15**01**00
		Clear Sky	Point	1501**01**
		Few Coverage	Point	1501**02**
		Scattered Coverage	Point	1501**03**
		Broken Coverage	Point	1501**04**
		Overcast Coverage	Point	1501**05**
		Sky Totally or Partially Obscured	Point	1501**06**
Weather Symbols				**16**0000
	Rain			16**01**00
		Intermittent Light	Point	1601**01**
		Continuous Light	Point	1601**02**
		Intermittent Moderate	Point	1601**03**

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE A-LI. Atmospheric entity/entity type/entity subtype - Continued.

Entity (Positions 11 and 12)	Entity Type (Positions 13 and 14)	Entity Subtype (Positions 15 and 16)	Geometric Rendering	Value
Note: The actual value is shown in **bold numbers**. The remaining values are used to show placement within the six positions.				
		Intermittent Moderate/ Continuous Moderate	Point	1601**04**
		Intermittent Heavy	Point	1601**05**
		Intermittent Heavy/ Continuous Heavy	Point	1601**06**
	Freezing Rain			16**02**00
		Light	Point	1602**01**
		Moderate/Heavy	Point	1602**02**
	Rain Showers			16**03**00
		Light	Point	1603**01**
		Moderate/Heavy	Point	1603**02**
		Torrential	Point	1603**03**
	Drizzle			16**04**00
		Intermittent Light	Point	1604**01**
		Intermittent Light/ Continuous Light	Point	1604**02**
		Intermittent Moderate	Point	1604**03**
		Intermittent Moderate/ Continuous Moderate	Point	1604**04**
		Intermittent Heavy	Point	1604**05**
		Intermittent Heavy/ Continuous Heavy	Point	1604**06**
	Freezing Drizzle			16**05**00
		Light	Point	1605**01**
		Moderate/Heavy	Point	1605**02**
	Rain and Snow Mixed			16**06**00
		Rain or Drizzle and Snow – Light	Point	1606**01**
		Rain or Drizzle and Snow – Moderate/Heavy	Point	1606**02**
		Rain and Snow Showers – Light	Point	1606**03**
		Rain and Snow Showers – Moderate/Heavy	Point	1606**04**
	Snow			16**07**00
		Intermittent Light	Point	1607**01**
		Intermittent Light/ Continuous Light	Point	1607**02**
		Intermittent Moderate	Point	1607**03**
		Intermittent Moderate/ Continuous Moderate	Point	1607**04**
		Intermittent Heavy	Point	1607**05**
		Intermittent Heavy/ Continuous Heavy	Point	1607**06**

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE A-LI. Atmospheric entity/entity type/entity subtype - Continued.

Entity (Positions 11 and 12)	Entity Type (Positions 13 and 14)	Entity Subtype (Positions 15 and 16)	Geometric Rendering	Value
Note: The actual value is shown in **bold numbers**. The remaining values are used to show placement within the six positions.				
		Blowing Snow – Light/ Moderate	Point	1607**07**
		Blowing Snow – Heavy	Point	1607**08**
	Snow Grains		Point	16**08**00
	Snow Showers			16**09**00
		Light	Point	1609**01**
		Moderate/Heavy	Point	1609**02**
	Hail			16**10**00
		Light not Associated with Thunder	Point	1610**01**
		Moderate/Heavy not Associated with Thunder	Point	1610**02**
	Ice Crystals (Diamond Dust)		Point	16**11**00
	Ice Pellets (Sleet)			16**12**00
		Light	Point	1612**01**
		Moderate	Point	1612**02**
		Heavy	Point	1612**03**
	Inversion		Point	16**13**00
	Storms			16**14**00
		Thunderstorm – No Precipitation	Point	1614**01**
		Thunderstorm Light to Moderate with Rain/Snow – No Hail	Point	1614**02**
		Thunderstorm Heavy with Rain/Snow – No Hail	Point	1614**03**
		Thunderstorm Light to Moderate – with Hail	Point	1614**04**
		Thunderstorm Heavy – with Hail	Point	1614**05**
		Funnel Cloud (Tornado/Waterspout)	Point	1614**06**
		Squall	Point	1614**07**
		Lightning	Point	1614**08**
	Fog			16**15**00
		Shallow Patches	Point	1615**01**
		Shallow Continuous	Point	1615**02**
		Patchy	Point	1615**03**
		Sky Visible	Point	1615**04**
		Sky Obscured	Point	1615**05**
		Freezing, Sky Visible	Point	1615**06**
		Freezing, Sky Obscured	Point	1615**07**
	Mist		Point	16**16**00
	Smoke		Point	16**17**00
	Haze		Point	16**18**00
	Dust or Sand			16**19**00

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE A-LI. Atmospheric entity/entity type/entity subtype - Continued.

Entity (Positions 11 and 12)	Entity Type (Positions 13 and 14)	Entity Subtype (Positions 15 and 16)	Geometric Rendering	Value
Note: The actual value is shown in **bold numbers**. The remaining values are used to show placement within the six positions.				
		Light to Moderate	Point	1619**01**
		Severe	Point	1619**02**
		Dust Devil	Point	1619**03**
		Blowing Dust or Sand	Point	1619**04**
	Tropical Storm Systems			16**20**00
		Tropical Depression	Point	1620**01**
		Tropical Storm	Point	1620**02**
		Hurricane/Typhoon	Point	1620**03**
		Tropical Storm Wind Areas and Date/Time Labels	Area	1620**04**
	Volcanic Eruption		Point	16**21**00
		Volcanic Ash	Point	1621**01**
	Tropopause Level		Point	16**22**00
	Freezing Level		Point	16**23**00
	Precipitation of Unknown Type and Intensity		Point	16**24**00
Bounded Areas of Weather				**17**0000
	Instrument Flight Rule (IFR)		Area	17**01**00
	Marginal Visual Flight Rule (MVFR)		Area	17**02**00
	Turbulence		Area	17**03**00
	Icing		Area	17**04**00
	Liquid Precipitation – Non-Convective Continuous or Intermittent		Area	17**05**00
		Liquid Precipitation – Convective	Area	1705**01**
	Freezing /Frozen Precipitation		Area	17**06**00
	Thunderstorm		Area	17**07**00
	Fog		Area	17**08**00
	Dust or Sand		Area	17**09**00
	Operator–Defined Freeform		Area	17**10**00
Isopleths				**18**0000
	Isobar – Surface		Line	18**01**00
	Contour – Upper Air		Line	18**02**00
	Isotherm		Line	18**03**00
	Isotach		Line	18**04**00
	Isodrosotherm		Line	18**05**00
	Thickness		Line	18**06**00
	Operator–Defined Freeform		Line	18**07**00
State of the Ground				**19**0000
	Without Snow or Measurable Ice Cover			19**01**00

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE A-LI. Atmospheric entity/entity type/entity subtype - Continued.

Entity (Positions 11 and 12)	Entity Type (Positions 13 and 14)	Entity Subtype (Positions 15 and 16)	Geometric Rendering	Value
Note: The actual value is shown in **bold numbers**. The remaining values are used to show placement within the six positions.				
		Surface Dry Without Cracks or Appreciable Dust or Loose Sand	Point	1901**01**
		Surface Moist	Point	1901**02**
		Surface Wet, Standing Water in Small or Large Pools	Point	1901**03**
		Surface Flooded	Point	1901**04**
		Surface Frozen	Point	1901**05**
		Glaze (Thin Ice) on Ground	Point	1901**06**
		Loose Dry Dust or Sand not Covering Ground Completely	Point	1901**07**
		Thin Loose Dry Dust or Sand Covering Ground Completely	Point	1901**08**
		Moderate/Thick Loose Dry Dust or Sand Covering Ground Completely	Point	1901**09**
		Extremely Dry with Cracks	Point	1901**10**
	With Snow or Measurable Ice Cover			19**02**00
		Predominately Ice Covered	Point	1902**01**
		Compact or Wet Snow (with or without Ice) Covering Less Than One–Half of Ground	Point	1902**02**
		Compact or Wet Snow (with or without Ice) Covering at Least One–Half of Ground, but Ground not Completely Covered	Point	1902**03**
		Even Layer of Compact or Wet Snow Covering Ground Completely	Point	1902**04**
		Uneven Layer of Compact or Wet Snow Covering Ground Completely	Point	1902**05**
		Loose Dry Snow Covering Less Than One–Half of Ground	Point	1902**06**
		Loose Dry Snow Covering at Least One–Half of Ground, but Ground not Completely Covered	Point	1902**07**
		Even Layer of Loose Dry Snow Covering Ground Completely	Point	1902**08**
		Uneven Layer of Loose Dry Snow Covering Ground Completely	Point	1902**09**
		Snow Covering Ground Completely, Deep Drifts	Point	1902**10**

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

A.5.4.17 Oceanographic (46).

TABLE A-LII. Oceanographic entity/entity type/entity subtype.

Entity (Positions 11 and 12)	Entity Type (Positions 13 and 14)	Entity Subtype (Positions 15 and 16)	Geometric Rendering	Value
Note: The actual value is shown in **bold numbers**. The remaining values are used to show placement within the six positions.				
Ice Systems				**11**0000
	Icebergs			11**01**00
		Many Icebergs	Point	1101**01**
		Belts and Strips	Point	1101**02**
		General	Point	1101**03**
		Many Icebergs – General	Point	1101**04**
		Bergy Bit	Point	1101**05**
		Many Bergy Bits	Point	1101**06**
		Growler	Point	1101**07**
		Many Growlers	Point	1101**08**
		Floeberg	Point	1101**09**
		Ice Island	Point	1101**10**
	Ice Concentration			11**02**00
		Bergy Water	Point	1102**01**
		Water with Radar Targets	Point	1102**02**
		Ice Free	Point	1102**03**
	Dynamic Processes			11**03**00
		Convergence	Point	1103**01**
		Divergence	Point	1103**02**
		Shearing or Shear Zone	Point	1103**03**
		Ice Drift (Direction)	Point	1103**04**
	Sea Ice			11**04**00
		Ice Thickness (Observed)	Point	1104**01**
		Ice Thickness (Estimated)	Point	1104**02**
		Melt Puddles or Flooded Ice	Point	1104**03**
	Limits			11**05**00
		Limits of Visual Observation	Line	1105**01**
		Limits of Under Cast	Line	1105**02**
		Limits of Radar Observation	Line	1105**03**
		Observed Ice Edge or Boundary	Line	1105**04**
		Estimated Ice Edge or Boundary	Line	1105**05**
		Ice Edge or Boundary from Radar	Line	1105**06**
	Openings in the Ice			11**06**00
		Cracks	Line	1106**01**
		Cracks at a Specific Location	Line	1106**02**
		Lead	Line	1106**03**
		Frozen Lead	Line	1106**04**

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE A-LII. Oceanographic entity/entity type/entity subtype - Continued.

Entity (Positions 11 and 12)	Entity Type (Positions 13 and 14)	Entity Subtype (Positions 15 and 16)	Geometric Rendering	Value
Note: The actual value is shown in **bold numbers**. The remaining values are used to show placement within the six positions.				
	Snow Cover		Point	11**07**00
		Sastrugi (with Orientation)	Point	1107**01**
	Topographical Features			11**08**00
		Ridges or Hummocks	Point	1108**01**
		Rafting	Point	1108**02**
		Jammed Brash Barrier	Point	1108**03**
Hydrography				**12**0000
	Depth			12**01**00
		Soundings	Point	1201**01**
		Depth Curve	Line	1201**02**
		Depth Contour	Line	1201**03**
		Depth Area	Area	1201**04**
	Coastal Hydrography			12**02**00
		Coastline	Line	1202**01**
		Island	Area	1202**02**
		Beach	Area	1202**03**
		Water	Area	1202**04**
		Foreshore – Line	Line	1202**05**
		Foreshore – Area	Area	1202**06**
	Ports and Harbors			12**03**00
		Ports		1203**01**
		Berths (Onshore)	Point	1203**02**
		Berths (Anchor)	Point	1203**03**
		Anchorage – Point	Point	1203**04**
		Anchorage – Line	Line	1203**05**
		Anchorage – Area	Area	1203**06**
		Call in Point	Point	1203**07**
		Pier/Wharf/Quay	Line	1203**08**
		Fishing Harbor – Point	Point	1203**09**
		Fish Weirs – Point	Point	1203**10**
		Fish Stakes – Point	Point	1203**11**
		Fish Traps – Area	Area	1203**12**
		Facilities		1203**13**
		Drydock	Area	1203**14**
		Landing Place	Point	1203**15**
		Offshore Loading Facility – Point	Point	1203**16**
		Offshore Loading Facility – Line	Line	1203**17**
		Offshore Loading Facility – Area	Area	1203**18**
		Ramp – Above Water	Line	1203**19**
		Ramp – Below Water	Line	1203**20**

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE A-LII. Oceanographic entity/entity type/entity subtype - Continued.

Entity (Positions 11 and 12)	Entity Type (Positions 13 and 14)	Entity Subtype (Positions 15 and 16)	Geometric Rendering	Value
Note: The actual value is shown in **bold numbers**. The remaining values are used to show placement within the six positions.				
		Landing Ring	Point	120321
		Ferry Crossing	Point	120322
		Cable Ferry Crossing	Point	120323
		Dolphin	Point	120324
		Shoreline Protection		120325
		Breakwater/Groin/Jetty – Above Water	Line	120326
		Breakwater/Groin/Jetty – Below Water	Line	120327
		Seawall	Line	120328
	Aids to Navigation			120400
		Beacon	Point	120401
		Buoy Default	Point	120402
		Marker	Point	120403
		Perches/Stakes – Point	Point	120404
		Perches/Stakes – Area	Area	120405
		Light	Point	120406
		Leading Line	Line	120407
		Light Vessel/Light Ship	Point	120408
		Lighthouse	Point	120409
	Dangers/Hazards			120500
		Rock Submerged	Point	120501
		Rock Awashed	Point	120502
		Underwater Danger/Hazard	Area	120503
		Foul Ground – Point	Point	120504
		Foul Ground – Area	Area	120505
		Kelp/Seaweed – Point	Point	120506
		Kelp/Seaweed – Area	Area	120507
		Snags/Stumps	Point	120508
		Wreck (Uncovers)	Point	120509
		Wreck (Submerged)	Point	120510
		Breakers	Line	120511
		Reef	Line	120512
		Eddies/Overfalls/Tide Rips	Point	120513
		Discolored Water	Area	120514
	Bottom Features			120600
		Bottom Characteristics - Sand	Point	120601
		Bottom Characteristics - Mud	Point	120602
		Bottom Characteristics - Clay	Point	120603
		Bottom Characteristics - Silt	Point	120604
		Bottom Characteristics - Stones	Point	120605

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE A-LII. Oceanographic entity/entity type/entity subtype - Continued.

Entity (Positions 11 and 12)	Entity Type (Positions 13 and 14)	Entity Subtype (Positions 15 and 16)	Geometric Rendering	Value
Note: The actual value is shown in **bold numbers**. The remaining values are used to show placement within the six positions.				
		Bottom Characteristics - Gravel	Point	120**06**
		Bottom Characteristics - Pebbles	Point	120**07**
		Bottom Characteristics - Cobbles	Point	120**08**
		Bottom Characteristics - Rock	Point	120**09**
		Bottom Characteristics - Coral	Point	120**10**
		Bottom Characteristics - Shell	Point	120**11**
		Qualifying Terms - Fine	Point	120**12**
		Qualifying Terms - Medium	Point	120**13**
		Qualifying Terms - Coarse	Point	120**14**
	Tide and Current			12**07**00
		Water Turbulence	Point	1207**01**
		Current Flow – Ebb	Line	1207**02**
		Current Flow – Flood	Line	1207**03**
		Tide Data Point	Point	1207**04**
		Tide Gauge	Point	1207**05**
Oceanography				**13**0000
	Bioluminescence			13**01**00
		Visual Detection Ratio (VDR) Level 1–2	Area	1301**01**
		VDR Level 2–3	Area	1301**02**
		VDR Level 3–4	Area	1301**03**
		VDR Level 4–5	Area	1301**04**
		VDR Level 5–6	Area	1301**05**
		VDR Level 6–7	Area	1301**06**
		VDR Level 7–8	Area	1301**07**
		VDR Level 8–9	Area	1301**08**
		VDR Level 9–10	Area	1301**09**
	Beach Slope			13**02**00
		Flat	Area	1302**01**
		Gentle	Area	1302**02**
		Moderate	Area	1302**03**
		Steep	Area	1302**04**
Geophysics/Acoustics				**14**0000
	Mine Warfare (MIW) Bottom Descriptors			14**01**00
		MIW Bottom Sediments - Solid Rock	Area	1401**01**
		MIW Bottom Sediments - Clay	Area	1401**02**

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE A-LII. Oceanographic entity/entity type/entity subtype - Continued.

Entity (Positions 11 and 12)	Entity Type (Positions 13 and 14)	Entity Subtype (Positions 15 and 16)	Geometric Rendering	Value
Note: The actual value is shown in **bold numbers**. The remaining values are used to show placement within the six positions.				
		MIW Bottom Sediments - Very Coarse Sand	Area	140103
		MIW Bottom Sediments - Coarse Sand	Area	140104
		MIW Bottom Sediments - Medium Sand	Area	140105
		MIW Bottom Sediments - Fine Sand	Area	140106
		MIW Bottom Sediments - Very Fine Sand	Area	140107
		MIW Bottom Sediments - Very Fine Silt	Area	140108
		MIW Bottom Sediments - Fine Silt	Area	140109
		MIW Bottom Sediments - Medium Silt	Area	140110
		MIW Bottom Sediments - Coarse Silt	Area	140111
		MIW Bottom Sediments - Boulders	Area	140112
		MIW Bottom Sediments - Cobbles, Oyster Shells	Area	140113
		MIW Bottom Sediments - Pebbles, Shells	Area	140114
		MIW Bottom Sediments - Sand and Shells	Area	140115
		MIW Bottom Sediment - Land	Area	140116
		MIW Bottom Sediment - No Data	Area	140117
		Bottom Roughness - Smooth	Area	140118
		Bottom Roughness - Moderate	Area	140119
		Bottom Roughness - Rough	Area	140120
		Clutter (Bottom) - Low	Area	140121
		Clutter (Bottom) - Medium	Area	140122
		Clutter (Bottom) - High	Area	140123
		Impact Burial - 0%	Area	140124
		Impact Burial - 0–10%	Area	140125
		Impact Burial - 10–20%	Area	140126
		Impact Burial - 20–75%	Area	140127
		Impact Burial - >75%	Area	140128
		MIW Bottom Category A	Area	140129
		MIW Bottom Category B	Area	140130
		MIW Bottom Category C	Area	140131
		MIW Bottom Type - A1	Area	140132

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE A-LII. Oceanographic entity/entity type/entity subtype - Continued.

Entity (Positions 11 and 12)	Entity Type (Positions 13 and 14)	Entity Subtype (Positions 15 and 16)	Geometric Rendering	Value
Note: The actual value is shown in **bold numbers**. The remaining values are used to show placement within the six positions.				
		MIW Bottom Type - A2	Area	140**133**
		MIW Bottom Type - A3	Area	140**134**
		MIW Bottom Type - B1	Area	140**135**
		MIW Bottom Type - B2	Area	140**136**
		MIW Bottom Type - B3	Area	140**137**
		MIW Bottom Type - C1	Area	140**138**
		MIW Bottom Type - C2	Area	140**139**
		MIW Bottom Type - C3	Area	140**140**
Limits				**15**0000
	Maritime Limit Boundary		Line	15**01**00
	Maritime Area		Area	15**02**00
	Restricted Area		Line	15**03**00
	Swept Area		Area	15**04**00
	Training Area		Area	15**05**00
	Operator–Defined		Area	15**06**00
Man–Made Structures				**16**0000
	Submarine Cable		Line	16**01**00
	Submerged Crib		Area	16**02**00
	Canal		Line	16**03**00
	Ford		Point	16**04**00
	Lock		Point	16**05**00
	Oil/Gas Rig		Point	16**06**00
	Oil/Gas Rig Field		Area	16**07**00
	Pipelines/Pipe		Line	16**08**00
	Pile/Piling/Post		Point	16**09**00

A.5.4.18 Meteorological space (47).

TABLE A-LIII. Meteorological space equipment entity/entity type/entity subtype.

Entity (Positions 11 and 12)	Entity Type (Positions 13 and 14)	Entity Subtype (Positions 15 and 16)	Geometric Rendering	Value
Note: The actual value is shown in **bold numbers**. The remaining values are used to show placement within the six positions.				
Space				**11**0000

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

A.5.4.19 Signals intelligence equipment (50).

TABLE A-LIV. Signals intelligence equipment entity/entity type/entity subtype.

Entity (Positions 11 and 12)	Entity Type (Positions 13 and 14)	Entity Subtype (Positions 15 and 16)	Value
Note: The actual value is shown in **bold numbers**. The remaining values are used to show placement within the six positions.			
Unspecified			000000
Signal Intercept			**11**0000
	Communications		11**01**00
	Jammer		11**02**00
	Radar		11**03**00

TABLE A-LV. Signals intelligence equipment sector 1 modifier.

Sector 1 Modifier	Category	Value	Remarks
Unspecified		00	
Anti-Aircraft Fire Control	Radar	01	
Airborne Search and Bombing	Radar	02	
Airborne Intercept	Radar	03	
Altimeter	Radar	04	
Airborne Reconnaissance and Mapping	Radar	05	
Air Traffic Control	Radar	06	
Beacon Transponder (not IFF)	Radar	07	
Battlefield Surveillance	Radar	08	
Controlled Approach	Radar	09	
Controlled Intercept	Radar	10	
Cellular/Mobile	Communications	11	
Coastal Surveillance	Radar	12	
Decoy/Mimic	Radar	13	
Data Transmission	Radar	14	
Earth Surveillance	Radar	15	
Early Warning	Radar	16	
Fire Control	Radar	17	
Ground Mapping	Radar	18	
Height Finding	Radar	19	
Harbor Surveillance	Radar	20	
Identification, Friend or Foe (Interrogator)	Radar	21	
Instrument Landing System	Radar	22	
Ionospheric Sounding	Radar	23	
Identification, Friend or Foe (Transponder)	Radar	24	
Barrage Jammer	Jammer	25	
Click Jammer	Jammer	26	
Deceptive Jammer	Jammer	27	
Frequency Swept Jammer	Jammer	28	
Jammer (general)	Jammer	29	
Noise Jammer	Jammer	30	
Pulsed Jammer	Jammer	31	
Repeater Jammer	Jammer	32	
Spot Noise Jammer	Jammer	33	
Transponder Jammer	Jammer	34	
Missile Acquisition	Radar	35	
Missile Control	Jammer	36	

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE A-LV. Signals intelligence equipment sector 1 modifier - Continued.

Sector 1 Modifier	Category	Value	Remarks
Missile Downlink	Air Radar	37	
Meteorological	Radar	38	
Multi-Function	Jammer	39	
Missile Guidance	Radar	40	
Missile Homing	Radar	41	
Missile Tracking	Jammer	42	
Navigational/General	Jammer	43	
Navigational/Distance Measuring Equipment	Jammer	44	
Navigation/Terrain Following	Jammer	45	
Navigational/Weather Avoidance	Jammer	46	
Omni-Line of Sight (LOS)	Jammer	47	
Proximity Use	Air Radar	48	
Point-to-Point Line of Sight (LOS)	Communications	49	
Instrumentation	Radar	50	
Range Only	Radar	51	
Sonobuoy	Radar	52	
Satellite Downlink	Communications	53	
Space	Radar	54	
Surface Search	Radar	55	
Shell Tracking	Land Radar	56	
Satellite Uplink	Communications	57	
Target Acquisition	Radar	58	
Target Illumination	Radar	59	
Tropospheric Scatter	Communications	60	
Target Tracking	Radar	61	
Unknown	Radar	62	
Video Remoting	Radar	63	
Experimental	Radar	64	
{Disused}		65	

TABLE A-LVI. Signals intelligence equipment sector 2 modifier.

Sector 2 Modifier	Category	Value	Remarks
Unspecified		00	
{Disused}		01	

A.5.4.20 Cyberspace (60).

TABLE A-LVII. Cyberspace entity/entity type/entity subtype.

Entity (Positions 11 and 12)	Entity Type (Positions 13 and 14)	Entity Subtype (Positions 15 and 16)	Value
Note: The actual value is shown in **bold numbers**. The remaining values are used to show placement within the six positions.			
Unspecified			000000
Cyberspace Unit			**11**0000
	Combat Mission Team		11**01**00
	National Mission Team		11**02**00
	Cyber Protection Team		11**03**00
	{Disused}		11**04**00

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE A-LVII. Cyberspace entity/entity type/entity subtype - Continued.

Entity (Positions 11 and 12)	Entity Type (Positions 13 and 14)	Entity Subtype (Positions 15 and 16)	Value
Note: The actual value is shown in **bold numbers**. The remaining values are used to show placement within the six positions.			
	{Disused}		11**05**00
	Defensive Cyberspace		11**06**00
	Offensive Cyberspace		11**07**00
	Internet Service Provider		11**08**00
	Security		11**09**00
	Operations		11**10**00
Threat Actors			**12**0000
	Insider		12**02**00
Agent			**13**0000
	Firewall		13**01**00
	Firmware		13**02**00
Application			14**00**00
	Fileserver		14**02**00
	Search Engine		14**03**00
	Social Media		14**04**00
Threat			**15**0000
	Malware		15**01**00
	Phishing		15**02**00
	Spear Phishing		15**03**00
	Whale Phishing		15**04**00
Data			**16**0000
	Digital Currency		16**01**00
	Persona		16**02**00
Endpoint			**17**0000
	Server		17**01**00
	Workstation		17**02**00
	Portable Electronic Device (PED)		17**03**00
		Smartphone	17030**1**
		Tablet	17030**2**
		Laptop	17030**3**
		Health Monitor	17030**4**
		Smartvest	17030**5**
		Smartwatch	17030**6**
		Wearable	17030**7**
	Internet of Things Device		17**04**00
	Printer		17**05**00
	Router		17**06**00
	Switch		17**07**00
Network			**18**0000

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE A-LVIII. Cyberspace sector 1 modifier.

Sector 1 Modifier	Category	Value	Remarks
Unspecified		00	
Defensive Cyberspace	Capability	01	
Offensive Cyberspace	Capability	02	
Social	Capability	03	
Wired	Capability	04	
Wireless	Capability	05	
Radio Frequency	Capability	06	
Operating System	Capability	07	
Continuity of Operations	Capability	08	
Internet Service Provider (ISP)	Capability	09	
Finance	Capability	10	
Out of Band	Capability	11	
Cloud		12	
Data		13	

TABLE A-LIX. Cyberspace sector 2 modifier.

Sector 2 Modifier	Category	Value	Remarks
Unspecified		00	
Secured	Capability	01	
Open	Capability	02	
Response Actions	Capability	03	
Internal Defense Measures	Capability	05	
Advanced Persistent Threat	Capability	06	
Nation State		07	
Nation State Sponsored		08	

A.5.5 Set C. The third set of ten values:

Positions 21 is the sector 1 modifier identifier.
Positions 22 is the sector 2 modifier identifier.
Positions 23 through 27 are reserved for future use (to be assigned by SSMC).
Positions 28 through 30 are the nationality/country/geopolitical/geographic name or Entity numeric code.

A.5.5.1 Sector 1 modifier identifier. The sector 1 modifier identifier determines if the sector 1 modifier uses a modifier based on the symbol set or a common modifier. A value greater than 0 identifies the modifier is based on the common modifier.

A.5.5.1.1 Sector 1 common modifier. The sector 1 common modifier is comprised of three values identifying the common modifier. The first value is the sector 1 modifier identifier and the remaining two positions are based on the values in the sector 1 modifier.

A.5.5.2 Sector 2 modifier identifier. The sector 2 modifier identifier determines if the sector 2 modifier uses a modifier based on the symbol set or a common modifier.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

A.5.5.2.1 Sector 2 common modifier. The sector 2 common modifier is comprised of three values identifying the common modifier. The first value is the sector 2 modifier identifier and the remaining two positions are based on the values in the sector 2 modifier.

A.5.5.3 Frame shape identifier. The frame shape identifier is comprised of one position and along with the standard identity, determines which frame shape and fill color shall be used.

TABLE A-LX. Frame shape.

Description	Value
Unknown	0
Space	1
Air	2
Land Unit	3
Land Equipment/Sea Surface	4
Land Installation	5
Dismounted Individuals	6
Sea Subsurface	7
Activity/Event	8
Cyberspace	9
Unframed	A

A.5.5.4 Nationality/country/geopolitical/geographic name or entity. The nationality/country/geopolitical/geographic name or entity numeric code is a three position value. Several lists of codes exist, to include GENC and NATO STANAG 1059. US shall use GENC.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

COMMON MODIFIERS

B.1 SCOPE

B.1.1 Scope. This appendix addresses common modifiers that support multiple dimension symbols within the C2 domain. The tables in this appendix present the modifiers for use across multiple dimensions. The information contained herein is intended for compliance.

B.2 APPLICABLE DOCUMENTS

Specific documents in 2.2 of this standard apply to this appendix.

B.3 DEFINITIONS

The definitions in section 3 of this standard apply to this appendix.

B.4 GENERAL REQUIREMENTS

B.4.1 Organization. This appendix contains technical specifications, a symbol coding scheme, a symbology hierarchy and symbology.

B.5 DETAILED REQUIREMENTS

B.5.1 Technical specifications. Composition, construction and display of symbols are explained in the detailed requirements section of the standard.

B.5.2 Symbol identification coding scheme. A symbol identification code (SIDC) is a numeric string that may be used to provide the unique identifier necessary to display or exchange symbol information between MIL-STD-2525 compliant systems. Refer to Appendix A for SIDC positions and descriptions.








B.5.3 Composition of common modifiers. Refer to 5.3.9 for an explanation of symbol composition.

B.5.3.1 Symbol building process. The symbol building process is identical for common modifiers as it is for standard modifiers.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.









B.5.3.2 Common modifiers. All common modifiers shall be placed in sectors 1 or 2 as appropriate (see table B-I and table B-II). Only one modifier may be placed in each sector at a given time. Multiple modifiers in the same position are prohibited due to legibility concerns.

TABLE B-I. Common modifiers sector 1.

DESCRIPTION	CATEGORY	MODIFIER	REMARKS
Unmanned Aircraft (UA)/ Unmanned Aerial Vehicle (UAV)/ Unmanned Aircraft System (UAS)/ Remote Piloted Vehicle (RPV) Value: 100	Mobility		
Robotic Value: 101	Mobility		
Fixed Wing Value: 102	Mobility		Not used by USAF
Rotary Wing Value: 103	Mobility		
Tilt-Rotor Value: 104	Mobility		
VSTOL/VTOL or Helicopter Equipped Value: 105	Capability		
Attack or Attack/Strike Value: 106	Capability		









Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE B-I. Common modifiers sector 1- Continued.

DESCRIPTION	CATEGORY	MODIFIER	REMARKS
Armored Value: 107	Capability		
Ballistic Missile/Ballistic Missile Defense Shooter Value: 108	Capability		
Bridge/Bridging Value: 109	Capability		
Cargo Value: 110	Capability		
Utility Value: 111	Capability		
Light Value: 112	Capability		
Medium Value: 113	Capability		
Heavy Value: 114	Capability		









Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE B-I. Common modifiers sector 1- Continued.

DESCRIPTION	CATEGORY	MODIFIER	REMARKS
Cyberspace Value: 115	Capability		
Command Post Node Value: 116	Capability		
Joint Network Node Value: 117	Capability		
Retransmission Site Value: 118	Capability		
Brigade Value: 119	Support Level		
Close Protection Value: 120	Capability		
Combat Value: 121	Capability		
Command and Control Value: 122	Capability		









Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE B-I. Common modifiers sector 1- Continued.

DESCRIPTION	CATEGORY	MODIFIER	REMARKS
Crowd and Riot Control Value: 123	Capability		
Explosive Ordnance Disposal (EOD) Value: 124	Capability		
Intelligence, Surveillance, Reconnaissance Value: 125	Capability		
Maintenance Value: 126	Capability		
Medevac/Medic/Medical Value: 127	Capability		
Search and Rescue Value: 128	Capability		
Security Value: 129	Capability		
Sniper Value: 130	Capability		









Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE B-I. Common modifiers sector 1- Continued.

DESCRIPTION	CATEGORY	MODIFIER	REMARKS
Special Operations Forces Value: 131	Capability		
Special Weapons and Tactics (SWAT) Value: 132	Capability		
Guided Missile Value: 133	Capability		
Other Guided Missile Value: 134	Capability		
Petroleum/Petroleum Oil and Lubricants Value: 135	Capability		
Water Value: 136	Capability		
Weapon or weapons Value: 137	Capability		
Chemical Value: 138	CBRN		









Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE B-I. Common modifiers sector 1- Continued.

DESCRIPTION	CATEGORY	MODIFIER	REMARKS
Radiological Value: 140	CBRN		
Nuclear Value: 141	CBRN		
Decontamination Value: 142	CBRN		
Civilian Value: 143	Organization		
Government Organization/Government Organization Member Value: 144	Organization		
Accident Value: 145	Composite Loss or Incident Qualifier		
Assassination Value: 146	Crime		
Execution Value: 147	Crime		









Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE B-I. Common modifiers sector 1- Continued.

DESCRIPTION	CATEGORY	MODIFIER	REMARKS
Kidnapping Value: 148	Crime		
Piracy Value: 149	Crime		
Rape Value: 150	Crime		
Antisubmarine Warfare Value: 151	Mission Area		
Escort Value: 152	Mission Area		
Mine Countermeasures Value: 153	Mission Area		
Mine Warfare Value: 154	Mission Area		APP-06 uses ‘MW’
Surface warfare Value:155	Mission Area		

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE B-I. Common modifiers sector 1- Continued.

DESCRIPTION	CATEGORY	MODIFIER	REMARKS
Command Value: 156	Support Level		
Company Value: 157	Support Level		
Platoon/Detachment Value:158	Support Level		
Regiment/Group Value: 159	Support Level		
Section Value:160	Support Level		
Squad Value: 161	Support Level		
Team/Crew Value:162	Support Level		
Battalion Value: 163	Support Level		

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE B-I. Common modifiers sector 1- Continued.
















DESCRIPTION	CATEGORY	MODIFIER	REMARKS
Directed Energy Value: 164	Capability		
Hijacker Value: 165	Crime		

TABLE B-II. Common modifiers sector 2.

DESCRIPTION	CATEGORY	MODIFIER	REMARKS
Airborne Value: 100	Mobility		
Bicycle Equipped Value: 101	Mobility		
Railroad/Railway Value: 102	Capability		
Ski Value: 103	Mobility		
Tracked Value: 104	Mobility		









Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE B-II. Common modifiers sector 2 - Continued.

DESCRIPTION	CATEGORY	MODIFIER	REMARKS
Wheeled **(Limited Cross Country)** Value: 105	Mobility		
Wheeled X **(Cross Country)** Value: 106	Mobility		
Fixed Wing Value: 107	Mobility		
Rotary Wing Value: 108	Mobility		
Robotic Value: 109	Mobility		
Autonomous Control Value: 110	Capability		
Remotely Piloted Value: 111	Capability		
Expendable Value: 112	Capability		






Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE B-II. Common modifiers sector 2 - Continued.

DESCRIPTION	CATEGORY	MODIFIER	REMARKS
Mountain Value: 113	Capability		
Long Range Value: 114	Capability		
Medium Range Value: 115	Capability		
Short Range Value: 116	Capability		
Close Range Value: 117	Capability		
Heavy Value: 118	Capability		
Medium Value: 119	Capability		
Light and Medium Value: 120	Capability		

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE B-II. Common modifiers sector 2 - Continued.

DESCRIPTION	CATEGORY	MODIFIER	REMARKS
Light Value: 121	Capability		
Cyberspace Value: 122	Capability		
Security Force Assistance Value: 123	Capability		
Medical Bed Value: 124	Capability		Modifier is offset so that the modifier is not compromised by the main sector icon.
Multifunctional Value: 125	Capability		

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

PAGE INTENTIONALLY LEFT BLANK

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

SPACE SYMBOLS

C.1 SCOPE

C.1.1 Scope. This appendix addresses symbols that support space equipment and weapons in the C2 domain. The tables in this appendix present the icons and modifiers for the space symbol sets. This appendix is divided into two sections (see figure C-1): 1) equipment and platform symbols (see C.6) and 2) missile symbols (see C.7). The information contained herein is intended for compliance.




FIGURE C-1. Space appendix sections.

C.2 APPLICABLE DOCUMENTS

Specific documents in 2.2 of this standard apply to this appendix.

C.3 DEFINITIONS

The definitions in section 3 of this standard apply to this appendix.

C.4 GENERAL REQUIREMENTS

C.4.1 Organization. This appendix contains technical specifications, a symbol coding scheme, a symbology hierarchy and space symbology.

C.5 DETAILED REQUIREMENTS

C.5.1 Technical specifications. Composition, construction and display of symbols are explained in the detailed requirements section of the standard.

C.5.2 Symbol identification coding scheme. A symbol identification code (SIDC) is a numeric string that may be used to provide the unique identifier necessary to display or exchange symbol information between MIL-STD-2525 compliant systems. Refer to Appendix A for SIDC positions and descriptions.

C.5.3 Composition of space symbols. A standard method for constructing symbols is presented. Refer to 5.3.10 for an explanation of symbol composition. Figure C-2 shows an example of a space equipment symbol.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.









FIGURE C-1. Space symbol components.

C.5.3.1 Symbol building process. Table C-I depicts the symbol building process for space symbols. The process is identical for icons and modifiers requiring the vertical bounding octagon.

TABLE C-I. Space symbol building process.

STEP	DESCRIPTION	EXAMPLE
1.	Choose the frame that matches the dimension of the object from the appropriate column in tables I, II, or III and standard identity (table A-II). In this example, the dimension is space and the standard identity is friend. The example depicts a "friendly space track."	
2.	Choose an icon for the main sector of the bounding octagon. In this example, the icon is "civilian earth observation satellite," a space entity subtype. The example depicts a "friendly civilian earth observation satellite."	
3.	If required, choose a modifier to depict an additional characteristic of the icon. In this example, the modifier is "low earth orbit," a sector 1 modifier. The example depicts a "friendly civilian earth observation satellite on a low earth orbit."	
4.	If required, choose a modifier to depict another characteristic of the icon. In this example, the modifier is "optical," a sector 2 modifier. The example depicts a "friendly civilian earth observation satellite on a low earth orbit with optical sensor."	
5.	The finished symbol will appear as shown in the example.	

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

C.5.3.2 Icons and modifiers. All icons shall be placed within the main sector of the bounding octagon (see table C-I). When depicted, modifiers shall be placed in sectors 1 or 2 as appropriate (see table C-I). Only one modifier may be placed in each sector at a given time. Multiple modifiers in the same position are prohibited due to legibility concerns.

C.5.3.3 Amplifiers.

C.5.3.3.1 Text amplifiers. The purpose of the static text amplifiers described in this appendix is to standardize the display of additional alphanumerical information on identity, movement and location and capabilities. See 5.3.7 for more information on amplifiers. Figure C-2 shows the placement of space symbol amplifiers around the friend symbol frame. Table C-II provides descriptions and formats of each amplifier.

C.5.3.3.2 Graphic amplifiers. Graphic amplifiers can be static, located in a fixed position in relation to a track's symbol, or dynamic and move about the symbol based on the track's characteristics. See 5.3.7 for more information on amplifiers, including examples of dynamic amplifiers.




FIGURE C-2. Placement of space symbol amplifiers.

TABLE C-II. Descriptions and formats of space symbol amplifiers.

FIELD	FIELD TITLE	DESCRIPTION	FORMAT
A	Space Vehicle Icon	The innermost part of a symbol, comprised of an icon and optional modifiers, that represents a joint military object (see 5.3.4).	
G	Staff Comments	A text amplifier for units, equipment and installations; content is implementation specific.	
H	Additional Information	A text amplifier for units, equipment and installations; content is implementation specific.	
Q	Direction of Movement Indicator	A graphic amplifier that identifies the direction of movement or intended movement of an object (see 5.3.7.9 and figure 14).	

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE C-II. Descriptions and formats of space symbol amplifiers – Continued.

FIELD	FIELD TITLE	DESCRIPTION	FORMAT
T	Unique Designation (Track Number)	A text amplifier for units, equipment and installations that uniquely identifies a particular symbol or track number.	Prefix = TN:##### Example: TN:13579
V	Type	A text amplifier for equipment that indicates types of equipment.	
X	Altitude	A text amplifier for units that displays altitude flight level. See 5.3.7.6 for content.	Measurement units shall be displayed within the string Examples: 1500MSL FL150
Z	Speed	A text amplifier for units and equipment that displays velocity (see 5.3.7.7).	
AL	Operational Condition	A graphic amplifier for equipment or installations that indicates operational condition or capacity.	Operational Condition amplifier, if used, shall be comprised of only one color. Ex. Satellite: Red - damaged, Green – fully capable Ex: Missile: Red – imminent threat, Green – no threat
AO	Engagement Bar	A graphic amplifier placed immediately atop the symbol. May denote: 1) local/remote status 2) engagement status 3) weapon type.	A:BBB-CC, where A = remote/local BBB = engagement status CC = weapon asset
AS	Country	A three-letter code that indicates the country of origin of the organization (US systems shall use GENC).	

C.6 SPACE EQUIPMENT AND PLATFORM SYMBOLS

C.6.1 Space equipment and platform symbols. This section includes the lists of icons and modifiers for building space equipment and platform symbols.




C.6.2 Space equipment and platform icons. Table C-III depicts space equipment and platform icons. Military symbols are depicted with black-filled icons, whereas civilian symbols are depicted with white-filled icons.

TABLE C-III. Space equipment and platform icons.

DESCRIPTION	ICON	REMARKS
Military Type: Entity Symbol Set: 05 Value: **11**0000 Icon Type: Main	N/A	Reserved for hierarchical purposes.







Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE C-III. Space equipment and platform icons- Continued.

DESCRIPTION	ICON	REMARKS
Space Vehicle Type: Entity Type Entity: Military Symbol Set: 05 Value: 11**01**00 Icon Type: Main		N/A
Re-Entry Vehicle Type: Entity Type Entity: Military Symbol Set: 05 Value: 11**02**00 Icon Type: Main		N/A
Planet Lander Type: Entity Type Entity: Military Symbol Set: 05 Value: 11**03**00 Icon Type: Main		N/A
Orbiter Shuttle Type: Entity Type Entity: Military Symbol Set: 05 Value: 11**04**00 Icon Type: Main		N/A
Capsule Type: Entity Type Entity: Military Symbol Set: 05 Value: 11**05**00 Icon Type: Main		N/A
Satellite Type: Entity Type Entity: Military Symbol Set: 05 Value: 11**07**00 Icon Type: Main		N/A
Antisatellite Weapon Type: Entity Type Entity: Military Symbol Set: 05 Value: 11**08**00 Icon Type: Main		N/A





Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE C-III. Space equipment and platform icons- Continued.

DESCRIPTION	ICON	REMARKS
Astronomical Satellite Type: Entity Type Entity: Military Symbol Set: 05 Value: 11**09**00 Icon Type: Main		N/A
Biosatellite Type: Entity Type Entity: Military Symbol Set: 05 Value: 11**10**00 Icon Type: Main		N/A
Communications Satellite Type: Entity Type Entity: Military Symbol Set: 05 Value: 11**11**00 Icon Type: Main		N/A
Earth Observation Satellite Type: Entity Type Entity: Military Symbol Set: 05 Value: 11**12**00 Icon Type: Main		N/A
Miniaturized Satellite Type: Entity Type Entity: Military Symbol Set: 05 Value: 11**13**00 Icon Type: Main		N/A
Navigational Satellite Type: Entity Type Entity: Military Symbol Set: 05 Value: 11**14**00 Icon Type: Main		N/A
Reconnaissance Satellite Type: Entity Type Entity: Military Symbol Set: 05 Value: 11**15**00 Icon Type: Main		N/A








Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE C-III. Space equipment and platform icons- Continued.

DESCRIPTION	ICON	REMARKS
Space Station Type: Entity Type Entity: Military Symbol Set: 05 Value: 111**6**00 Icon Type: Main		N/A
Tethered Satellite Type: Entity Type Entity: Military Symbol Set: 05 Value: 111**7**00 Icon Type: Main		N/A
Weather Satellite Type: Entity Type Entity: Military Symbol Set: 05 Value: 111**8**00 Icon Type: Main		N/A
Space Launched Vehicle (SLV) Type: Entity Type Entity: Military Symbol Set: 05 Value: 111**9**00 Icon Type: Main		N/A
Civilian Type: Entity Symbol Set: 05 Value: **12**0000 Icon Type: Main	N/A	Reserved for hierarchical purposes.
Orbiter Shuttle Type: Entity Type Entity: Civilian Symbol Set: 05 Value: 12**01**00 Icon Type: Main		N/A
Capsule Type: Entity Type Entity: Civilian Symbol Set: 05 Value: 12**02**00 Icon Type: Main		N/A




Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE C-III. Space equipment and platform icons- Continued.

DESCRIPTION	ICON	REMARKS
Satellite Type: Entity Type Entity: Civilian Symbol Set: 05 Value: 120300 Icon Type: Main		N/A
Astronomical Satellite Type: Entity Type Entity: Civilian Symbol Set: 05 Value: 120400 Icon Type: Main		N/A
Biosatellite Type: Entity Type Entity: Civilian Symbol Set: 05 Value: 120500 Icon Type: Main		N/A
Communications Satellite Type: Entity Type Entity: Civilian Symbol Set: 05 Value: 120600 Icon Type: Main		N/A
Earth Observation Satellite Type: Entity Type Entity: Civilian Symbol Set: 05 Value: 120700 Icon Type: Main		N/A
Miniaturized Satellite Type: Entity Type Entity: Civilian Symbol Set: 05 Value: 120800 Icon Type: Main		N/A
Navigational Satellite Type: Entity Type Entity: Civilian Symbol Set: 05 Value: 120900 Icon Type: Main		N/A

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.







TABLE C-III. Space equipment and platform icons- Continued.

DESCRIPTION	ICON	REMARKS
Space Station Type: Entity Type Entity: Civilian Symbol Set: 05 Value: 12**10**00 Icon Type: Main		N/A
Tethered Satellite Type: Entity Type Entity: Civilian Symbol Set: 05 Value: 12**11**00 Icon Type: Main		N/A
Weather Satellite Type: Entity Type Entity: Civilian Symbol Set: 05 Value: 12**12**00 Icon Type: Main		N/A
Planetary Lander Type: Entity Type Entity: Civilian Symbol Set: 05 Value: 12**13**00 Icon Type: Main		N/A
Space Vehicle Type: Entity Type Entity: Civilian Symbol Set: 05 Value: 12**14**00 Icon Type: Main		N/A
Manual Track Type: Entity (Local) Symbol Set: 05 Value: **13**0000 Icon Type: Full Octagon		N/A

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

C.6.3 Space equipment and platform sector 1 modifiers. Space equipment and platform sector 1 modifiers denote orbit category. Table C-IV lists space equipment and platform sector 1 modifiers and illustrates their placement within the bounding octagon. Additional sector 1 modifiers, where required, are included in table B-I and are accessed using the modifier extension flag.







TABLE C-IV. Space equipment and platform sector 1 modifiers.

DESCRIPTION	CATEGORY	MODIFIER	REMARKS
Low Earth Orbit (LEO) Symbol Set: 05 Value: 01	Orbit		N/A
Medium Earth Orbit (MEO) Symbol Set: 05 Value: 02	Orbit		N/A
High Earth Orbit (HEO) Symbol Set: 05 Value: 03	Orbit		N/A
Geosynchronous Orbit (GSO) Symbol Set: 05 Value: 04	Orbit		N/A
Geostationary Orbit (GO) Symbol Set: 05 Value: 05	Orbit		N/A
Molniya Orbit (MO) Symbol Set: 05 Value: 06	Orbit		N/A

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.





C.6.4 Space equipment and platform sector 2 modifiers. Space equipment and platform sector 2 modifiers denote sensor category. Table C-V lists space equipment and platform sector 2 modifiers and illustrates their placement within the bounding octagon. Additional sector 2 modifiers, where required, are included in table B-II and are accessed using the modifier extension flag.

TABLE C-V. Space equipment and platform sector 2 modifiers.

DESCRIPTION	CATEGORY	MODIFIER	REMARKS
Optical Symbol Set: 05 Value: 01	Sensor		Only used with satellite icons.
Infrared Symbol Set: 05 Value: 02	Sensor		Only used with satellite icons.
Radar Symbol Set: 05 Value: 03	Sensor		Only used with satellite icons.
Signals Intelligence (SIGINT) Symbol Set: 05 Value: 04	Sensor		Only used with satellite icons.
Electromagnetic Warfare (ASAT) Symbol Set: 05 Value: 06	Capability		Only used with Anti-Satellite Weapon Main Icon.
High Power Microwave (ASAT) Symbol Set: 05 Value: 07	Capability		Only used with Anti-Satellite Weapon Main Icon.
Laser (ASAT) Symbol Set: 05 Value: 08	Capability		Only used with Anti-Satellite Weapon Main Icon.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE C-V. Space equipment and platform sector 2 modifiers - Continued.


DESCRIPTION	CATEGORY	MODIFIER	REMARKS
Maintenance Symbol Set: 05 Value: 09	Capability		N/A
Mine (ASAT) Symbol Set: 05 Value: 10	Capability		Only used with Anti-Satellite Weapon Main Icon.
Refuel Symbol Set: 05 Value: 11	Capability		N/A
Tug Symbol Set: 05 Value: 12	Capability		N/A

C.7 SPACE MISSILE SYMBOLS

C.7.1 Space missile symbols. This section includes the lists of icons and modifiers for building space missile symbols.

C.7.2 Space missile icons. Table C-VI depicts the lone space missile icon. The space missile icon requires the vertical bounding octagon.





TABLE C-VI. Space missile icon.

DESCRIPTION	ICON	REMARKS
Missile Type: Entity Symbol Set: 06 Value: **11**0000 Icon Type: Main		

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.



C.7.3 Space missile sector 1 modifiers. Space missile sector 1 modifiers denote launch origin or missile class categories. Table C-VII lists missile sector 1 modifiers and illustrates their placement within the bounding octagon.

TABLE C-VII. Space missile sector 1 modifiers.

DESCRIPTION	CATEGORY	MODIFIER	REMARKS
Ballistic Symbol Set: 06 Value: 01	Missile Class		N/A
Space Symbol Set: 06 Value: 02	Launch Origin		N/A
Interceptor Symbol Set: 06 Value: 03	Missile Class		N/A
Hypersonic Symbol Set: 02 Value: 04	Missile Class		N/A










C.7.4 Space missile sector 2 modifiers. Space missile sector 2 modifiers denote projected missile destination, missile status, missile type, or missile range categories. Table C-VIII lists the missile sector 2 modifiers and illustrates their placement within the bounding octagon.

TABLE C-VIII. Space missile sector 2 modifiers.

DESCRIPTION	CATEGORY	MODIFIER	REMARKS
Short Range Symbol Set: 06 Value: 01	Missile Range		1000km or less.
Medium Range Symbol Set: 06 Value: 02	Missile Range		1000km to 3500km.





Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE C-VIII. Space missile sector 2 modifiers - Continued.

DESCRIPTION	CATEGORY	MODIFIER	REMARKS
Intermediate Range Symbol Set: 06 Value: 03	Missile Range		1000km to 3500km.
Long Range Symbol Set: 06 Value: 04	Missile Range		3500km to 5500km.
Intercontinental Symbol Set: 06 Value: 05	Missile Range		5500km or greater.
Arrow Symbol Set: 06 Value: 06	Missile Type-BMD		Used with Interceptor modifier 1 only.
Ground-Based Interceptor (GBI) Symbol Set: 06 Value: 07	Missile Type-BMD		Used with Interceptor modifier 1 only.
Patriot Symbol Set: 06 Value: 08	Missile Type-BMD		Used with Interceptor modifier 1 only.
Standard Missile - Terminal Phase (SM-T) Symbol Set: 06 Value: 09	Missile Type-BMD		Used with Interceptor modifier 1 only.
Standard Missile - 3 (SM-3) Symbol Set: 06 Value: 10	Missile Type-BMD		Used with Interceptor modifier 1 only.
Terminal High-Altitude Area Defense (THAAD) Symbol Set: 06 Value: 11	Missile Type-BMD		Used with Interceptor modifier 1 only.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE C-VIII. Space missile sector 2 modifiers - Continued.

DESCRIPTION	CATEGORY	MODIFIER	REMARKS
Space Symbol Set: 06 Value: 12	Launch Origin		N/A
Close Range (CRBM) Symbol Set: 06 Value: 13	Missile Range		N/A
Debris Symbol Set: 06 Value: 14	Missile Type-BMD		N/A
Unknown Symbol Set: 06 Value: 15	Missile Type-BMD		N/A

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

PAGE INTENTIONALLY LEFT BLANK

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

AIR SYMBOLS

D.1 SCOPE

D.1.1 Scope. This appendix addresses symbols that support air equipment and weapons in the C2 domain. The tables in this appendix present the icons and modifiers for the air symbol sets. This appendix is divided into two sections (see figure D-1): 1) equipment and platform symbols (see D.6) and 2) missile symbols (see D.7). The information contained herein is intended for compliance.




FIGURE D-1. Air appendix sections.

D.2 APPLICABLE DOCUMENTS

Specific documents in 2.2 of this standard apply to this appendix.

D.3 DEFINITIONS

The definitions in section 3 of this standard apply to this appendix.

D.4 GENERAL REQUIREMENTS

D.4.1 Organization. This appendix contains technical specifications, a symbol coding scheme, a symbology hierarchy and air symbology.

D.5 DETAILED REQUIREMENTS

D.5.1 Technical specifications. Composition, construction and display of symbols are explained in the detailed requirements section of the standard.

D.5.2 Symbol identification coding scheme. A symbol identification code (SIDC) is a numeric string that may be used to provide the unique identifier necessary to display or exchange symbol information between MIL-STD-2525 compliant systems. Refer to Appendix A for SIDC positions and descriptions.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

D.5.3 Composition of air symbols. A standard method for constructing symbols is presented. Refer to 5.3.10 for an explanation of symbol composition. Figure D-2 shows an example of an air equipment symbol.








FIGURE D-2. Air symbol components.


D.5.3.1 Symbol building process. Table D-I depicts the symbol building process for air symbols. The process is identical for icons and modifiers requiring the vertical bounding octagon.

TABLE D-I. Air symbol building process.

STEP	DESCRIPTION	EXAMPLE
1.	Choose the frame that matches the dimension of the object from the appropriate column in tables I, II, or III and standard identity (table A-II). In this example, the dimension is air and the standard identity is friend. The example depicts a “friendly air track.”	
2.	Choose an icon for the main sector of the bounding octagon. In this example, the icon is “military rotary-wing,” an air entity type. The example depicts a “friendly military rotary-wing aircraft.”	
3.	If required, choose a modifier to depict an additional characteristic of the icon. In this example, the modifier is “cyberspace,” a sector 1 modifier. The example depicts a “friendly military rotary-wing aircraft with cyberspace capability.”	
4.	If required, choose a modifier to depict another characteristic of the icon. In this example, the modifier is “light,” a sector 2 modifier. The example depicts a “friendly military light rotary-wing aircraft with cyberspace capability.”	

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE D-I. Air symbol building process - Continued.

STEP	DESCRIPTION	EXAMPLE
5.	The finished symbol will appear as shown in the example.	

D.5.3.2 Icons and modifiers. All icons shall be placed within the main sector of the bounding octagon (see table D-I). When depicted, modifiers shall be placed in sectors 1 or 2 as appropriate (see table D-I). Only one modifier may be placed in each sector at a given time. Multiple modifiers in the same position are prohibited due to legibility concerns.

D.5.3.3 Amplifiers.

D.5.3.3.1 Text amplifiers. The purpose of the static text amplifiers described in this appendix is to standardize the display of additional alphanumerical information on identity, movement and location and capabilities. See 5.3.7 for more information on amplifiers. Figure D-3 shows the placement of air symbol amplifiers around the friend symbol frame. Table D-II provides descriptions and formats of each amplifier.

D.5.3.3.2 Graphic amplifiers. Graphic amplifiers can be static, located in a fixed position in relation to a track's symbol, or dynamic and move about the symbol based on the track's characteristics. See 5.3.7 for more information on amplifiers, including examples of dynamic amplifiers.




FIGURE D-3. Placement of air symbol amplifiers.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE D-II. Descriptions and formats of air symbol amplifiers.

FIELD	FIELD TITLE	DESCRIPTION	FORMAT
A	Air Vehicle/Air Vehicle Type Icon	The innermost part of a symbol, comprised of an icon and optional modifiers, that represents a joint military object (see 5.3.4).	
G	Staff Comments	A text amplifier for units, equipment, and installations; content is implementation specific.	
H	Additional Information	A text amplifier for units, equipment and installations; content is implementation specific.	
Q	Direction of Movement Indicator	A graphic amplifier that identifies the direction of movement or intended movement of an object (see 5.3.7.9 and figure 14).	
T	Unique Designation (Track Number)	A text amplifier for units, equipment and installations that uniquely identifies a particular symbol or track number.	Prefix = TN:##### Example: TN:13579
V	Type	A text amplifier for equipment that indicates types of equipment.	
X	Altitude	A text amplifier for units that displays altitude/ flight level. See 5.3.7.6 for content.	Measurement units shall be displayed within the string Example: 1500MSL FL150
Z	Speed	A text amplifier for units and equipment that displays velocity (see 5.3.7.7).	
AF	Common Identifier	Example: “Hawk” for Hawk SAM system.	
AL	Operational Condition	A graphic amplifier for equipment or installations that indicates operational condition or capacity.	Operational Condition amplifier, if used, shall be comprised of only one color. Ex. Aircraft: Red - damaged, Green – fully capable Ex: Missile: Red – imminent threat, Green – no threat
AQ	Guarded Unit	During ballistic missile defense, some tracks are designated as guarded by a particular unit.	
AS	Country	A three-letter code that indicates the country of origin of the organization (US systems shall use GENC).	






Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

D.6 AIR EQUIPMENT AND PLATFORM SYMBOLS

D.6.1 Air equipment and platform symbols. This section includes the lists of icons and modifiers for building air equipment and platform symbols.







D.6.2 Air equipment and platform icons. Table D-III depicts air equipment and platform icons. Military symbols are depicted with black-filled icons, whereas civilian symbols are depicted with white-filled icons.

TABLE D-III. Air equipment and platform icons.

DESCRIPTION	ICON	REMARKS
Military Type: Entity Symbol Set: 01 Value: **11**0000 Icon Type: Main	N/A	Reserved for hierarchical purposes.
Fixed-Wing Type: Entity Type Entity: Military Symbol Set: 01 Value: 11**01**00 Icon Type: Main		N/A
Medical Evacuation (Medevac) Type: Entity Subtype Entity/Entity Type: Military/Fixed-Wing Symbol Set: 01 Value: 1101**01** Icon Type: Main		N/A
Attack/Strike Type: Entity Subtype Entity/Entity Type: Military/Fixed-Wing Symbol Set: 01 Value: 1101**02** Icon Type: Main		N/A
Bomber Type: Entity Subtype Entity/Entity Type: Military/Fixed-Wing Symbol Set: 01 Value: 1101**03** Icon Type: Main		N/A
Fighter Type: Entity Subtype Entity/Entity Type: Military/Fixed-Wing Symbol Set: 01 Value: 1101**04** Icon Type: Main		N/A



Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE D-III. Air equipment and platform icons - Continued.

DESCRIPTION	ICON	REMARKS
Fighter/Bomber Type: Entity Subtype Entity/Entity Type: Military/Fixed-Wing Symbol Set: 01 Value: 110105 Icon Type: Main		N/A
Cargo Type: Entity Subtype Entity/Entity Type: Military/Fixed-Wing Symbol Set: 01 Value: 110107 Icon Type: Main		N/A
Electronic/Combat (EC)/ Jammer Type: Entity Subtype Entity/Entity Type: Military/Fixed-Wing Symbol Set: 01 Value: 110108 Icon Type: Main		N/A
Tanker Type: Entity Subtype Entity/Entity Type: Military/Fixed-Wing Symbol Set: 01 Value: 110109 Icon Type: Main		N/A
Patrol Type: Entity Subtype Entity/Entity Type: Military/Fixed-Wing Symbol Set: 01 Value: 110110 Icon Type: Main		N/A
Reconnaissance Type: Entity Subtype Entity/Entity Type: Military/Fixed-Wing Symbol Set: 01 Value: 110111 Icon Type: Main		N/A
Trainer Type: Entity Subtype Entity/Entity Type: Military/Fixed-Wing Symbol Set: 01 Value: 110112 Icon Type: Main		N/A

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE D-III. Air equipment and platform icons - Continued.

DESCRIPTION	ICON	REMARKS
Utility Type: Entity Subtype Entity/Entity Type: Military/Fixed-Wing Symbol Set: 01 Value: 110113 Icon Type: Main		N/A
VSTOL Type: Entity Subtype Entity/Entity Type: Military/Fixed-Wing Symbol Set: 01 Value: 110114 Icon Type: Main		N/A
Airborne Command Post (ACP) Type: Entity Subtype Entity/Entity Type: Military/Fixed-Wing Symbol Set: 01 Value: 110115 Icon Type: Main		N/A
Airborne Early Warning (AEW) Type: Entity Subtype Entity/Entity Type: Military/Fixed-Wing Symbol Set: 01 Value: 110116 Icon Type: Main		N/A
Antisurface Warfare Type: Entity Subtype Entity/Entity Type: Military/Fixed-Wing Symbol Set: 01 Value: 110117 Icon Type: Main		N/A
Antisubmarine Warfare Type: Entity Subtype Entity/Entity Type: Military/Fixed-Wing Symbol Set: 01 Value: 110118 Icon Type: Main		N/A
Communications Type: Entity Subtype Entity/Entity Type: Military/Fixed-Wing Symbol Set: 01 Value: 110119 Icon Type: Main		N/A


Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE D-III. Air equipment and platform icons - Continued.

DESCRIPTION	ICON	REMARKS
Combat Search and Rescue (CSAR) Type: Entity Subtype Entity/Entity Type: Military/ Fixed-Wing Symbol Set: 01 Value: 110120 Icon Type: Main		N/A
Electronic Support (ES) Type: Entity Subtype Entity/Entity Type: Military/ Fixed-Wing Symbol Set: 01 Value: 110121 Icon Type: Main		N/A
Government Type: Entity Subtype Entity/Entity Type: Military/ Fixed-Wing Symbol Set: 01 Value: 110122 Icon Type: Main		N/A
Mine Countermeasures (MCM) Type: Entity Subtype Entity/Entity Type: Military/ Fixed-Wing Symbol Set: 01 Value: 110123 Icon Type: Main		N/A
Personnel Recovery Type: Entity Subtype Entity/Entity Type: Military/ Fixed-Wing Symbol Set: 01 Value: 110124 Icon Type: Main		N/A
Search and Rescue Type: Entity Subtype Entity/Entity Type: Military/ Fixed-Wing Symbol Set: 01 Value: 110125 Icon Type: Main		N/A
Special Operations Forces Type: Entity Subtype Entity/Entity Type: Military/ Fixed-Wing Symbol Set: 01 Value: 110126 Icon Type: Main		N/A





Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE D-III. Air equipment and platform icons - Continued.

DESCRIPTION	ICON	REMARKS
Ultra Light Type: Entity Subtype Entity/Entity Type: Military/ Fixed-Wing Symbol Set: 01 Value: 110127 Icon Type: Main		N/A
Photographic Reconnaissance Type: Entity Subtype Entity/Entity Type: Military/ Fixed-Wing Symbol Set: 01 Value: 110128 Icon Type: Main		N/A
Very Important Person (VIP) Type: Entity Subtype Entity/Entity Type: Military/ Fixed-Wing Symbol Set: 01 Value: 110129 Icon Type: Main		N/A
Suppression Of Enemy Air Defense Type: Entity Subtype Entity/Entity Type: Military/ Fixed-Wing Symbol Set: 01 Value: 110130 Icon Type: Main		N/A
Passenger Type: Entity Subtype Entity/Entity Type: Military/ Fixed-Wing Symbol Set: 01 Value: 110131 Icon Type: Main		N/A
Escort Type: Entity Subtype Entity/Entity Type: Military/ Fixed-Wing Symbol Set: 01 Value: 110132 Icon Type: Main		N/A
Electromagnetic Attack (EA) Type: Entity Subtype Entity/Entity Type: Military/ Fixed-Wing Symbol Set: 01 Value: 110133 Icon Type: Main		N/A







Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE D-III. Air equipment and platform icons - Continued.

DESCRIPTION	ICON	REMARKS
Rotary-Wing Type: Entity Type Entity: Military Symbol Set: 01 Value: 11**02**00 Icon Type: Main		N/A
Unmanned Aircraft (UA)/ Unmanned Aerial Vehicle (UAV)/ Unmanned Aircraft System (UAS)/ Remote Piloted Vehicle (RPV) Type: Entity Type Entity: Military Symbol Set: 01 Value: 11**03**00 Icon Type: Main		N/A
Vertical-Takeoff UAV (VT-UAV) Type: Entity Type Entity: Military Symbol Set: 01 Value: 11**04**00 Icon Type: Main		N/A
Lighter Than Air Type: Entity Type Entity: Military Symbol Set: 01 Value: 11**05**00 Icon Type: Main		N/A
Airship Type: Entity Type Entity: Military Symbol Set: 01 Value: 11**06**00 Icon Type: Main		N/A
Tethered Lighter Than Air Type: Entity Type Entity: Military Symbol Set: 01 Value: 11**07**00 Icon Type: Main		N/A
Civilian Type: Entity Symbol Set: 01 Value: **12**0000 Icon Type: Main	N/A	Reserved for hierarchical purposes.


Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE D-III. Air equipment and platform icons - Continued.

DESCRIPTION	ICON	REMARKS
Fixed-Wing Type: Entity Type Entity: Civilian Symbol Set: 01 Value: 12**01**00 Icon Type: Main		N/A
Rotary-Wing Type: Entity Type Entity: Civilian Symbol Set: 01 Value: 12**02**00 Icon Type: Main		N/A
Unmanned Aircraft (UA)/ Unmanned Aerial Vehicle (UAV)/ Unmanned Aircraft System (UAS)/ Remote Piloted Vehicle Type: Entity Type Entity: Civilian Symbol Set: 01 Value: 12**03**00 Icon Type: Full Octagon		N/A
Lighter Than Air Type: Entity Type Entity: Civilian Symbol Set: 01 Value: 12**04**00 Icon Type: Main		N/A
Airship Type: Entity Type Entity: Civilian Symbol Set: 01 Value: 12**05**00 Icon Type: Main		N/A
Tethered Lighter Than Air Type: Entity Type Entity: Civilian Symbol Set: 01 Value: 12**06**00 Icon Type: Main		N/A
Weapon Type: Entity Symbol Set: 01 Value: **13**0000 Icon Type: Main	N/A	Reserved for hierarchical purposes.




Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE D-III. Air equipment and platform icons - Continued.

DESCRIPTION	ICON	REMARKS
Bomb Type: Entity Type Entity: Weapon Symbol Set: 01 Value: 13**01**00 Icon Type: Main		N/A
Decoy Type: Entity Type Entity: Weapon Symbol Set: 01 Value: 13**02**00 Icon Type: Main		N/A
Manual Track Type: Entity (Local) Symbol Set: 01 Value: **14**0000 Icon Type: Full Octagon		N/A










D.6.3 Air equipment and platform sector 1 modifiers. Air equipment and platform sector 1 modifiers denote aircraft type and mission area categories. Table D-IV lists air equipment and platform sector 1 modifiers and illustrates their placement within the bounding octagon. Additional sector 1 modifiers, where required, are included in table B-I and are accessed using the modifier extension flag.

TABLE D-IV. Air equipment and platform sector 1 modifiers.

DESCRIPTION	CATEGORY	MODIFIER	REMARKS
Bomber Symbol Set: 01 Value: 02	Military Aircraft Type		N/A
Fighter Symbol Set: 01 Value: 04	Military Aircraft Type		N/A
Tanker Symbol Set: 01 Value: 06	Aircraft Type		N/A










Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE D-IV. Air equipment and platform sector 1 modifiers - Continued.

DESCRIPTION	CATEGORY	MODIFIER	REMARKS
Passenger Symbol Set: 01 Value: 09	Aircraft Type		N/A
Ultra Light Symbol Set: 01 Value: 10	Aircraft Type		N/A
Airborne Command Post (ACP) Symbol Set: 01 Value: 11	Military Aircraft Type		N/A
Airborne Early Warning (AEW) Symbol Set: 01 Value: 12	Military Aircraft Type		N/A
Electronic Combat (EC)/Jammer Symbol Set: 01 Value: 16	Military Mission Area		N/A
Patrol Symbol Set: 01 Value: 17	Mission Area		N/A
Reconnaissance Symbol Set: 01 Value: 18	Mission Area		N/A
Trainer Symbol Set: 01 Value: 19	Mission Area		N/A
Photographic (Reconnaissance) Symbol Set: 01 Value: 20	Mission Area		N/A





Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE D-IV. Air equipment and platform sector 1 modifiers - Continued.

DESCRIPTION	CATEGORY	MODIFIER	REMARKS
Personnel Recovery Symbol Set: 01 Value: 21	Mission Area		N/A
Antisubmarine Warfare Symbol Set: 01 Value: 22	Military Mission Area		N/A
Communications Symbol Set: 01 Value: 23	Mission Area		N/A
Electronic Support (ES) Symbol Set: 01 Value: 24	Military Mission Area		N/A
Very Important Person (VIP) Transport Symbol Set: 01 Value: 29	Mission Area		N/A
Combat Search and Rescue (CSAR) Symbol Set: 01 Value: 30	Military Mission Area		N/A
Antisurface Warfare Symbol Set: 01 Value: 32	Military Mission Area		N/A
Fighter/Bomber Symbol Set: 01 Value: 33	Military Aircraft Type		N/A
Intensive Care Symbol Set: 01 Value: 34	Mission Area		N/A




Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE D-IV. Air equipment and platform sector 1 modifiers - Continued.

DESCRIPTION	CATEGORY	MODIFIER	REMARKS
Electromagnetic Attack (EA) Symbol Set: 01 Value: 35	Military Mission Area		N/A
Multi-Mission Symbol Set: 01 Value: 36	Mission Area		N/A
ASW HELO- Lamps Symbol Set: 01 Value: 38	Mission Area		Must be paired in conjunction with rotary wing icon
ASW HELO – SH-60R Symbol Set: 01 Value: 39	Mission Area		Must be paired in conjunction with rotary wing icon


D.6.4 Air equipment and platform sector 2 modifiers. Air equipment and platform sector 2 modifiers denote capacity, re-fueling capability, range and track link availability categories. Table D-V lists air equipment and platform sector 2 modifiers and illustrates their placement within the bounding octagon. Additional sector 2 modifiers, where required, are included in table B-II and are accessed using the modifier extension flag.

TABLE D-V. Air equipment and platform sector 2 modifiers.

DESCRIPTION	CATEGORY	MODIFIER	REMARKS
Boom-Only Symbol Set: 01 Value: 04	Re-Fueling Capability		Used with tanker only.
Drogue-Only Symbol Set: 01 Value: 05	Re-Fueling Capability		Used with tanker only.
Boom and Drogue Symbol Set: 01 Value: 06	Re-Fueling Capability		Used with tanker only.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE D-V. Air equipment and platform sector 2 modifiers - Continued.


DESCRIPTION	CATEGORY	MODIFIER	REMARKS
Downlinked Symbol Set: 01 Value: 11	Track Link Availability		N/A

D.7 AIR MISSILE SYMBOLS

D.7.1 Air missile symbols. This section includes the lists of icons and modifiers for building air missile symbols.




D.7.2 Air missile icons. Table D-VI depicts the lone air missile icon. The air missile icon requires the vertical bounding octagon.

TABLE D-VI. Air missile icon.

DESCRIPTION	ICON	REMARKS
Missile Type: Entity Symbol Set: 02 Value: **11**0000 Icon Type: Main		







D.7.3 Air missile sector 1 modifiers. Air missile sector 1 modifiers denote launch origin or missile class categories. Table D-VII lists missile sector 1 modifiers and illustrates their placement within the bounding octagon.

TABLE D-VII. Air missile sector 1 modifiers.

DESCRIPTION	CATEGORY	MODIFIER	REMARKS
Air Symbol Set: 02 Value: 01	Launch Origin		N/A
Surface Symbol Set: 02 Value: 02	Launch Origin		N/A
Subsurface Symbol Set: 02 Value: 03	Launch Origin		N/A

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.









TABLE D-VII. Air missile sector 1 modifiers- Continued.

DESCRIPTION	CATEGORY	MODIFIER	REMARKS
Space Symbol Set: 02 Value: 04	Launch Origin		N/A
Anti-Ballistic Symbol Set: 02 Value: 05	Missile Class		N/A
Ballistic Symbol Set: 02 Value: 06	Missile Class		N/A
Cruise Symbol Set: 02 Value: 07	Missile Class		N/A
Interceptor Symbol Set: 02 Value: 08	Missile Class		N/A
Hypersonic Symbol Set: 02 Value: 09	Missile Class		

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.








D.7.4 Air missile sector 2 modifiers. Air missile sector 2 modifiers denote projected missile destination, missile status, missile type-BMD, missile type-AAW, or missile range categories. Table D-VIII lists the missile sector 2 modifiers and illustrates their placement within the bounding octagon.

TABLE D-VIII. Air missile sector 2 modifiers.

DESCRIPTION	CATEGORY	MODIFIER	REMARKS
Air Symbol Set: 02 Value: 01	Missile Destination		N/A
Surface Symbol Set: 02 Value: 02	Missile Destination		N/A
Subsurface Symbol Set: 02 Value: 03	Missile Destination		N/A
Space Symbol Set: 02 Value: 04	Missile Destination		N/A
Launched Symbol Set: 02 Value: 05	Missile Status		N/A
Patriot Symbol Set: 02 Value: 07	Missile Type-BMD		Used with INTERCEPTOR modifier 1 only.
Standard Missile – 2 (SM-2) Symbol Set: 02 Value: 08	Missile Type-AAW		Used with INTERCEPTOR modifier 1 only.
Standard Missile – 6 (SM-6) Symbol Set: 02 Value: 09	Missile Type-AAW		Used with INTERCEPTOR modifier 1 only.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE D-VIII. Air missile sector 2 modifiers - Continued.

DESCRIPTION	CATEGORY	MODIFIER	REMARKS
Evolved Sea Sparrow Missile (ESSM) Symbol Set: 02 Value: 10	Missile Type-AAW		Used with INTERCEPTOR modifier 1 only.
Rolling Airframe Missile (RAM) Symbol Set: 02 Value: 11	Missile Type-AAW		Used with INTERCEPTOR modifier 1 only.
Short Range Symbol Set: 02 Value: 12	Missile Range		1000km or less.
Medium Range Symbol Set: 02 Value: 13	Missile Range		1000km to 3500km. Typically used in reference to surface-to-air missile
Intermediate Range Symbol Set: 02 Value: 14	Missile Range		1000km to 3500km. Typically used in reference to ballistic missile
Long Range Symbol Set: 02 Value: 15	Missile Range		3500km to 5500km.
Intercontinental Symbol Set: 02 Value: 16	Missile Range		5500km or greater.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

PAGE INTENTIONALLY LEFT BLANK

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

LAND SYMBOLS

E.1 SCOPE

E.1.1 Scope. This appendix addresses symbols that support land units, equipment and installations in the C2 domain. The tables in this appendix present the icons and modifiers for the land symbol sets. This appendix is divided into four sections (see figure E-1): 1) unit symbols (see E.6), 2) civilian unit/organization symbols (see E.7), 3) equipment symbols (see E.8) and 4) installation symbols (see E.9). The information contained herein is intended for compliance.




FIGURE E-1. Land appendix sections.

E.2 APPLICABLE DOCUMENTS

Specific documents in 2.2 of this standard apply to this appendix.

E.3 DEFINITIONS

The definitions in section 3 of this standard apply to this appendix.

E.4 GENERAL REQUIREMENTS

E.4.1 Organization. This appendix contains technical specifications, a symbol coding scheme, a symbology hierarchy and land symbology.

E.5 DETAILED REQUIREMENTS

E.5.1 Technical specifications. Composition, construction and display of symbols are explained in the detailed requirements section of the standard.

E.5.2 Symbol identification coding scheme. A symbol identification code (SIDC) is a numeric string that may be used to provide the unique identifier necessary to display or exchange symbol information between MIL-STD-2525 compliant systems. Refer to Appendix A for SIDC positions and descriptions.

E.5.3 Composition of land symbols. A standard method for constructing symbols is presented. Refer to 5.3.10 for an explanation of symbol composition. Figure E-2 shows an example of a land unit symbol.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.








FIGURE E-2. Land symbol components.

E.5.3.1 Symbol building process. Table E-I depicts the symbol building process for land symbols. The process is identical for icons and modifiers requiring the vertical bounding octagon.

TABLE E-I. Land symbol building process.

STEP	DESCRIPTION	EXAMPLE
1.	Choose the frame that matches the dimension of the object from the appropriate column in tables I, II, or III and standard identity (table A-II). In this example, the dimension is land unit and the standard identity is friend. The example depicts a “friendly unit.”	
2.	Choose an icon for the symbol. In this example, the icon is “infantry,” a land entity type. The infantry icon is a full frame icon; therefore, the friend version of the infantry icon shall be used with the friend frame. If the frame was hostile, then the hostile version of the infantry icon would be used. The example depicts a “friendly infantry unit.”	
3.	If required, choose a modifier to depict an additional characteristic of the icon. In this example, the modifier is “airborne,” a sector 2 modifier. The example depicts a “friendly airborne infantry unit.”	
4.	The finished symbol will appear as shown in the example.	

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

E.5.3.2 Icons and modifiers. All icons shall be placed within the main sector of the bounding octagon (see table E-I). When depicted, modifiers shall be placed in sectors 1 or 2 as appropriate (see table E-I). Only one modifier may be placed in each sector at a given time. Multiple modifiers in the same position are prohibited due to legibility concerns.

E.5.3.3 Amplifiers. Refer to the appropriate section for the placement and description of the land symbol amplifiers for units, equipment, and installations.

E.5.3.3.1 Text amplifiers. The purpose of the static text amplifiers described in this appendix is to standardize the display of additional alphanumerical information on identity, movement and location and capabilities. See 5.3.7 for more information on amplifiers.

E.5.3.3.2 Graphic amplifiers. Graphic amplifiers can be static, located in a fixed position in relation to a track's symbol, or dynamic and move about the symbol based on the track's characteristics. See 5.3.7 for more information on amplifiers, including examples of dynamic amplifiers.

E.6 LAND UNIT SYMBOLS

E.6.1 Land unit symbols. This section includes the lists of amplifiers, icons, and modifiers for building land unit symbols.

E.6.2 Land unit amplifiers. The purpose of amplifier fields is to standardize the display of additional alphanumerical information that graphically describes a unit, and provides additional information on capabilities, status, location, etc. Figure E-3 shows the placement of land unit symbol amplifiers around the friend symbol frame. Table E-II provides descriptions and formats of each amplifier.




FIGURE E-3. Placement of land unit and civilian organization symbol amplifiers.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE E-II. Descriptions and formats of land unit and civilian organization symbol amplifiers.

FIELD	FIELD TITLE	DESCRIPTION	FORMAT
A	Symbol Icon	The innermost part of a symbol, comprised of an icon and optional modifiers, that represents a joint military object (see 5.3.4).	
B	Echelon	A graphic amplifier in a unit symbol that identifies command level (see table Table-VII and in the base document appendix).	
D	Task Force Indicator	A graphic amplifier that identifies a unit or an activity symbol as a task force (see 5.3.7.3 and figure 14 in the base document).	
F	Reinforced or Reduced	A text amplifier in a unit symbol that displays (+) for reinforced, (-) for reduced, (±) reinforced and reduced.	
G	Staff Comments	A text amplifier for units, equipment, and installations; content is implementation specific.	
H	Additional Information	A text amplifier for units, equipment, and installations; content is implementation specific.	
J	Evaluation Rating	A text amplifier for units, equipment and installations that consists of a single-letter reliability rating and a single digit credibility rating: (See ATP 2-33.4) **Reliability Ratings:** A-completely reliable B-usually reliable C-fairly reliable D-not usually reliable E-unreliable F-reliability cannot be judged. **Credibility Ratings:** 1-confirmed by other sources 2-probably true 3-possibly true 4-doubtfully true 5-improbable 6-truth cannot be judged.	
K	Combat Effectiveness	A text amplifier for units and installations that indicates effectiveness. **The entries are:** fully operational (FO) substantially operational (SO) marginally operational (MO) not operational (NO) unknown (UNK)	

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE E-II. Descriptions and formats of land unit and civilian organization symbol amplifiers - Continued.

FIELD	FIELD TITLE	DESCRIPTION	FORMAT
L	Signature Equipment	A text amplifier for hostile equipment; "**!**" indicates detectable electronic signatures.	
M	Higher Formation	A text amplifier for units that indicates a number or title of a higher echelon command (Corps is designated by Roman numerals).	
P	IFF/SIF	A text amplifier displaying one or more IFF/SIF Identification modes and codes. **Display priority:** Mode 5, Mode S, Mode 2, Mode 3.	Mode 2 Prefix: 2:#### **Example**: 2:1234
Q	Direction of Movement Indicator	A graphic amplifier that identifies the direction of movement or intended movement of an object (see 5.3.7.9 and figure 14 in the base document).	
R	Mobility Indicator	A graphic amplifier for equipment that depicts the mobility of an object (see 5.3.7.10, figure 14 and table III).	
S	Headquarters Staff Indicator	A graphic amplifier for units, installations and activities that identifies them as a headquarters (see figure 13 and figure 14).	
T	Unique Designation (Track Number)	A text amplifier for units, equipment, and installations that uniquely identifies a particular symbol or track number.	Prefix = TN:##### **Example**: TN:13579
V	Type	A text amplifier for equipment that indicates types of equipment.	
W	Date-Time Group (DTG)	An alphanumeric designator for displaying a date-time group. The date-time group is composed of a group of six numeric digits with a time zone suffix and the standardized three-letter abbreviation for the month followed by four digits representing the year. The first pair of digits represents the day; the second pair, the hour; the third pair, the minutes. For automated systems, two digits may be added before the time zone suffix and after the minutes to designate seconds (see 5.3.7.8).	(DDHHMMSSZMONYYYY) or "O/O" for on order
X	Altitude/Depth	A text amplifier for units, equipment and installations that displays either altitude, flight level, depth for submerged objects, or height of equipment or structures on the ground. See 5.3.7.6 for content.	Measurement units shall be displayed within the string **Examples**: 1500MSL FL150

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.




TABLE E-II. Descriptions and formats of land unit and civilian organization symbol amplifiers - Continued.

FIELD	FIELD TITLE	DESCRIPTION	FORMAT
Y	Location	A text amplifier for units, equipment and installations that displays a symbol's location in degrees, minutes and decimal minutes (or in MGRS, GARS, or other applicable display formats).	3317.0921N 04412.6332E 38SMB2649083145
Z	Speed	A text amplifier for units and equipment that displays velocity (see 5.3.7.7).	
AA	Special C2 Headquarters	A text modifier for units; the indicator is contained inside the frame. A named command such as SHAPE, PACOM, CENTCOM, joint, multinational, or coalition commands such as CJTF, JTF, and MJTF.	
AD	Platform Type	Electronic intelligence notation (ELNOT) or communications intelligence notation (CENOT)	
AE	Equipment Teardown Time	Equipment teardown time in minutes.	
AF	Common Identifier	Example: "Hawk" for Hawk SAM system.	
AL	Operational Condition	A graphic amplifier for equipment or installations that indicates operational condition or capacity.	Operational Condition amplifier, if used, shall be comprised of only one color. **Ex. Aircraft**: Red - damaged, Green – fully capable **Ex: Missile**: Red – imminent threat, Green – no threat
AO	Engagement Bar	A graphic amplifier placed immediately atop the symbol. May denote: 1) local/remote status 2) engagement status 3) weapon type.	A:BBB:CC, where A = remote/local BBB = engagement status CC = weapon asset
AQ	Guarded Unit	During ballistic missile defense, some tracks are designated as guarded by a particular unit.	
AS	Country	A three-letter code that indicates the country of origin of the organization (US systems shall use GENC).	

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.







E.6.3 Land unit icons. Table E-III depicts land unit icons. The information in gray is provided for orientation only and is not part of the icon.

TABLE E-III. Land unit icons.

DESCRIPTION	ICON	REMARKS
Command and Control Type: Entity Symbol Set: 10 Value: **11**0000 Icon Type: Main		Reserved for Amplifier field {AA} only. See table E-II
Broadcast Transmitter Antennae Type: Entity Type Entity: Command and Control Symbol Set: 10 Value: 11**01**00 Icon Type: Full Octagon		N/A
Civil Affairs Type: Entity Type Entity: Command and Control Symbol Set: 10 Value: 11**02**00 Icon Type: Main		N/A
Civil-Military Cooperation Type: Entity Type Entity: Command and Control Symbol Set: 10 Value: 11**03**00 Icon Type: Main		N/A
Information Operations Type: Entity Type Entity: Command and Control Symbol Set: 10 Value: 11**04**00 Icon Type: Main		N/A
Liaison Type: Entity Type Entity: Command and Control Symbol Set: 10 Value: 11**05**00 Icon Type: Main		N/A







Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE E-III. Land unit icons - Continued.

DESCRIPTION	ICON	REMARKS
Military Information Support Operations (MISO) Type: Entity Type Entity: Command and Control Symbol Set: 10 Value: 11**06**00 Icon Type: Main		N/A
Broadcast Transmitter Antennae Type: Entity Subtype Entity/Entity Type: Command and Control/Military Information Support Operations (Miso) Symbol Set: 10 Value: 1106**01** Icon Type: Full Octagon		N/A
Radio Type: Entity Type Entity/Entity Type: Command and Control Symbol Set: 10 Value: 11**07**00 Icon Type: Main		N/A
Radio Relay Type: Entity Type Entity/Entity Type: Command and Control Symbol Set: 10 Value: 11**08**00 Icon Type: Main		N/A
Radio Teletype Center Type: Entity Type Entity/Entity Type: Command and Control Symbol Set: 10 Value: 11**09**00 Icon Type: Main		N/A
Signal Type: Entity Type Entity: Command and Control Symbol Set: 10 Value: 11**10**00 Icon Type: Full Frame		The gray box is not to be drawn. It is shown here only as a reference to position and proportion of the icon within the frame






Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE E-III. Land unit icons - Continued.

DESCRIPTION	ICON	REMARKS
Signal – Radio Type: Entity Subtype Entity: Signal Symbol Set: 10 Value: 1110**01** Icon Type: Full Frame		The gray box is not to be drawn. It is shown here only as a reference to position and proportion of the icon within the frame
Signal – Radio Relay Type: Entity Subtype Entity: Signal Symbol Set: 10 Value: 1110**02** Icon Type: Full Frame		The gray box is not to be drawn. It is shown here only as a reference to position and proportion of the icon within the frame
Signal – Teletype Type: Entity Subtype Entity: Signal Symbol Set: 10 Value: 1110**03** Icon Type: Full Frame		The gray box is not to be drawn. It is shown here only as a reference to position and proportion of the icon within the frame
Signal - Video Imagery (Combat Camera) Type: Entity Subtype Entity: Signal Symbol Set: 10 Value: 1110**05** Icon Type: Full Frame		The gray box is not to be drawn. It is shown here only as a reference to position and proportion of the icon within the frame
Video Imagery (Combat Camera) Type: Entity Type Entity: Command and Control Symbol Set: 10 Value: 11**12**00 Icon Type: Main		N/A
Space Type: Entity Type Entity: Command and Control Symbol Set: 10 Value: 11**13**00 Icon Type: Main		N/A







Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE E-III. Land unit icons - Continued.

DESCRIPTION	ICON	REMARKS
Special Troops Type: Entity Type Entity: Command and Control Symbol Set: 10 Value: 11**14**00 Icon Type: Main		N/A
Multi-Domain Operations Type: Entity Type Entity: Command and Control Symbol Set: 10 Value: 11**15**00 Icon Type: Main		N/A
Movement and Maneuver Type: Entity Symbol Set: 10 Value: **12**0000	N/A	Reserved for hierarchical purposes.
Air Assault with Organic Lift Type: Entity Type Entity: Movement and Maneuver Symbol Set: 10 Value: 12**01**00 Icon Type: Full Frame		The gray box is not to be drawn. It is shown here only as a reference to position and proportion of the icon within the frame.
Air Traffic Services/Airfield Operations Type: Entity Type Entity: Movement and Maneuver Symbol Set: 10 Value: 12**02**00 Icon Type: Main		N/A
Antitank/Antiarmor Type: Entity Type Entity: Movement and Maneuver Symbol Set: 10 Value: 12**04**00 Icon Type: Full Frame		The gray box is not to be drawn. It is shown here only as a reference to position and proportion of the icon within the frame.
Armored Type: Entity Type Entity: Movement and Maneuver/ Antitank/Antiarmor Symbol Set: 10 Value: 1204**01** Icon Type: Full Frame		The gray box is not to be drawn. It is shown here only as a reference to position and proportion of the icon within the frame.






Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE E-III. Land unit icons - Continued.

DESCRIPTION	ICON	REMARKS
Motorized Type: Entity Type Entity: Movement and Maneuver/ Antitank/Antiarmor Symbol Set: 10 Value: 120**402** Icon Type: Full Frame		The gray box is not to be drawn. It is shown here only as a reference to position and proportion of the icon within the frame.
Armor/Mechanized Type: Entity Type Entity: Movement and Maneuver Symbol Set: 10 Value: 12**05**00 Icon Type: Main		N/A
Reconnaissance/Cavalry/Scout Type: Entity Type Entity: Movement and Maneuver/Armor/Armored/ Mechanized/Self-Propelled/Tracked Symbol Set: 10 Value: 1205**01** Icon Type: Full Frame		The gray box is not to be drawn. It is shown here only as a reference to position and proportion of the icon within the frame.
Amphibious Type: Entity Type Entity: Movement and Maneuver/Armor/Armored/ Mechanized/Self-Propelled/Tracked Symbol Set: 10 Value: 1205**02** Icon Type: Full Frame		The gray box is not to be drawn. It is shown here only as a reference to position and proportion of the icon within the frame.
Army Aviation/Aviation Rotary Wing Type: Entity Type Entity: Movement and Maneuver Symbol Set: 10 Value: 12**06**00 Icon Type: Main		N/A
Reconnaissance Type: Entity Type Entity: Movement and Maneuver/ Army Aviation/Aviation Rotary Wing Symbol Set: 10 Value: 1206**01** Icon Type: Full Frame		The gray box is not to be drawn. It is shown here only as a reference to position and proportion of the icon within the frame.







Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE E-III. Land unit icons - Continued.

DESCRIPTION	ICON	REMARKS
Aviation Composite Type: Entity Type Entity: Movement and Maneuver Symbol Set: 10 Value: 12**07**00 Icon Type: Main		N/A
Aviation Fixed Wing Type: Entity Type Entity: Movement and Maneuver Symbol Set: 10 Value: 12**08**00 Icon Type: Main		N/A
Reconnaissance Type: Entity Type Entity: Movement and Maneuver/ Army Aviation/Aviation Fixed Wing Symbol Set: 10 Value: 1208**01** Icon Type: Full Frame		The gray box is not to be drawn. It is shown here only as a reference to position and proportion of the icon within the frame.
Combat Type: Entity Type Entity: Movement and Maneuver Symbol Set: 10 Value: 12**09**00 Icon Type: Main		N/A
Combined Arms Type: Entity Type Entity: Movement and Maneuver Symbol Set: 10 Value: 12**10**00 Icon Type: Main		N/A
Infantry Type: Entity Type Entity: Movement and Maneuver Symbol Set: 10 Value: 12**11**00 Icon Type: Full Frame		The gray box is not to be drawn. It is shown here only as a reference to position and proportion of the icon within the frame.
Amphibious Type: Entity Subtype Entity/Entity Type: Movement and Maneuver/Infantry Symbol Set: 10 Value: 1211**01** Icon Type: Full Frame		The gray box is not to be drawn. It is shown here only as a reference to position and proportion of the icon within the frame.






Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE E-III. Land unit icons - Continued.

DESCRIPTION	ICON	REMARKS
Armored/Mechanized/ Tracked Type: Entity Subtype Entity/Entity Type: Movement and Maneuver/Infantry Symbol Set: 10 Value: 121**02** Icon Type: Main		The gray box is not to be drawn. It is shown here only as a reference to position and proportion of the icon within the frame.
Main Gun System, Infantry Type: Entity Subtype Entity/Entity Type: Movement and Maneuver/Infantry Symbol Set: 10 Value: 121**03** Icon Type: Full Frame		The gray box is not to be drawn. It is shown here only as a reference to position and proportion of the icon within the frame.
Motorized Type: Entity Subtype Entity/Entity Type: Movement and Maneuver/Infantry Symbol Set: 10 Value: 121**04** Icon Type: Full Frame		The gray box is not to be drawn. It is shown here only as a reference to position and proportion of the icon within the frame.
Infantry Fighting Vehicle Type: Entity Subtype Entity/Entity Type: Movement and Maneuver/Infantry Symbol Set: 10 Value: 121**05** Icon Type: Full Frame		The gray box is not to be drawn. It is shown here only as a reference to position and proportion of the icon within the frame.
Main Gun System Type: Entity Subtype Entity/Entity Type: Movement and Maneuver/Infantry Symbol Set: 10 Value: 121**06** Icon Type: Full Frame		The gray box is not to be drawn. It is shown here only as a reference to position and proportion of the icon within the frame.
Observer Type: Entity Type Entity: Movement and Maneuver Symbol Set: 10 Value: 12**1**200 Icon Type: Main		N/A




Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE E-III. Land unit icons - Continued.

DESCRIPTION	ICON	REMARKS
Reconnaissance/Cavalry/ Scout Type: Entity Type Entity: Movement and Maneuver Symbol Set: 10 Value: 12**13**00 Icon Type: Full Frame		The gray box is not to be drawn. It is shown here only as a reference to position and proportion of the icon within the frame.
Reconnaissance and Surveillance Type: Entity Type Entity: Movement and Maneuver/Reconnaissance/Cavalry/Scout Symbol Set: 10 Value: 1213**01** Icon Type: Full Frame		The gray box is not to be drawn. It is shown here only as a reference to position and proportion of the icon within the frame.
Marine Type: Entity Type Entity: Movement and Maneuver/Reconnaissance/Cavalry/Scout Symbol Set: 10 Value: 1213**02** Icon Type: Full Frame		The gray box is not to be drawn. It is shown here only as a reference to position and proportion of the icon within the frame.
Motorized Type: Entity Type Entity: Movement and Maneuver/Reconnaissance/Cavalry/Scout Symbol Set: 10 Value: 1213**03** Icon Type: Full Frame		The gray box is not to be drawn. It is shown here only as a reference to position and proportion of the icon within the frame.
Sea Air Land (SEAL) Type: Entity Type Entity: Movement and Maneuver Symbol Set: 10 Value: 12**14**00 Icon Type: Main		N/A
Sniper Type: Entity Type Entity: Movement and Maneuver Symbol Set: 10 Value: 12**15**00 Icon Type: Main		N/A






Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE E-III. Land unit icons - Continued.

DESCRIPTION	ICON	REMARKS
Surveillance Type: Entity Type Entity: Movement and Maneuver Symbol Set: 10 Value: 12**16**00 Icon Type: Main		N/A
Special Forces Type: Entity Type Entity: Movement and Maneuver Symbol Set: 10 Value: 12**17**00 Icon Type: Main		N/A
Special Operations Forces (SOF) Type: Entity Type Entity: Movement and Maneuver Symbol Set: 10 Value: 12**18**00 Icon Type: Main		N/A
Fixed Wing Miso Type: Entity Subtype Entity: Movement and Maneuver/Special Operations Forces (Sof) Symbol Set: 10 Value: 1218**01** Icon Type: Full Octagon		N/A
Ground Type: Entity Subtype Entity: Movement and Maneuver/Special Operations Forces (Sof) Symbol Set: 10 Value: 1218**02** Icon Type: Full Frame		The gray box is not to be drawn. It is shown here only as a reference to position and proportion of the icon within the frame.
Underwater Demolition Type: Entity Subtype Entity: Movement and Maneuver/Special Operations Forces (SOF) Symbol Set: 10 Value: 1218**05** Icon Type: Main		N/A







Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE E-III. Land unit icons - Continued.

DESCRIPTION	ICON	REMARKS
Unmanned Aerial Systems Type: Entity Type Entity: Movement and Maneuver Symbol Set: 10 Value: 12**19**00 Icon Type: Main		N/A
Ranger Type: Entity Type Entity: Movement and Maneuver Symbol Set: 10 Value: 12**20**00 Icon Type: Main		N/A
Fires Type: Entity Symbol Set: 10 Value: **13**0000	N/A	Reserved for hierarchical purposes.
Air Defense Type: Entity Type Entity: Fires Symbol Set: 10 Value: 13**01**00 Icon Type: Full Frame		The gray box is not to be drawn. It is shown here only as a reference to position and proportion of the icon within the frame.
Main Gun System Type: Entity Subtype Entity: Fires/Air Defense Symbol Set: 10 Value: 1301**01** Icon Type: Full Frame		The gray box is not to be drawn. It is shown here only as a reference to position and proportion of the icon within the frame.
Missile Type: Entity Subtype Entity: Fires/Air Defense Symbol Set: 10 Value: 1301**02** Icon Type: Full Frame		The gray box is not to be drawn. It is shown here only as a reference to position and proportion of the icon within the frame.
Air and Missile Defense Type: Entity Subtype Entity: Fires/Air Defense Symbol Set: 10 Value: 1301**03** Icon Type: Full Frame		The gray box is not to be drawn. It is shown here only as a reference to position and proportion of the icon within the frame.







Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE E-III. Land unit icons - Continued.

DESCRIPTION	ICON	REMARKS
Air/Land Naval Gunfire Liaison Type: Entity Type Entity: Fires Symbol Set: 10 Value: 13**02**00 Icon Type: Full Frame		The gray box is not to be drawn. It is shown here only as a reference to position and proportion of the icon within the frame.
Field Artillery Type: Entity Type Entity: Fires Symbol Set: 10 Value: 13**03**00 Icon Type: Main		N/A
Field Artillery Observer Type: Entity Type Entity: Fires Symbol Set: 10 Value: 13**04**00 Icon Type: Main		N/A
Joint Fire Support Type: Entity Type Entity: Fires Symbol Set: 10 Value: 13**05**00 Icon Type: Main		N/A
Meteorological Type: Entity Type Entity: Fires Symbol Set: 10 Value: 13**06**00 Icon Type: Main		N/A
Missile Type: Entity Type Entity: Fires Symbol Set: 10 Value: 13**07**00 Icon Type: Main		N/A
Mortar Type: Entity Type Entity: Fires Symbol Set: 10 Value: 13**08**00 Icon Type: Main		N/A





Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE E-III. Land unit icons - Continued.

DESCRIPTION	ICON	REMARKS
Self-Propelled Wheeled Type: Entity Subtype Entity/Entity Type: Fires/Mortar Symbol Set: 10 Value: 1308**02** Icon Type: Full Octagon		N/A
Survey Type: Entity Type Entity: Fires Symbol Set: 10 Value: 13**09**00 Icon Type: Main		N/A
Protection Type: Entity Symbol Set: 10 Value: **14**0000	N/A	Reserved for hierarchical purposes.
Chemical Biological Radiological Nuclear Defense Type: Entity Type Entity: Protection Symbol Set: 10 Value: 14**01**00 Icon Type: Main		N/A
Motorized Type: Entity Subtype Entity: Protection/Chemical Biological Radiological Nuclear Defense Symbol Set: 10 Value: 1401**02** Icon Type: Main		
Reconnaissance Type: Entity Subtype Entity: Protection/Chemical Biological Radiological Nuclear Defense Symbol Set: 10 Value: 1401**03** Icon Type: Full Frame		The gray box is not to be drawn. It is shown here only as a reference to position and proportion of the icon within the frame.
Reconnaissance Equipped Type: Entity Subtype Entity: Protection/Chemical Biological Radiological Nuclear Defense Symbol Set: 10 Value: 1401**05** Icon Type: Full Frame		The gray box is not to be drawn. It is shown here only as a reference to position and proportion of the icon within the frame.






Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE E-III. Land unit icons - Continued.

DESCRIPTION	ICON	REMARKS
Chemical, Biological, Radiological, Nuclear, and High-Yield Explosives Type: Entity Subtype Entity: Protection/Chemical Biological Radiological Nuclear Defense Symbol Set: 10 Value: 1401**06** Icon Type: Main		N/A
Combat Support (Maneuver Enhancement) Type: Entity Type Entity: Protection Symbol Set: 10 Value: 1**40**200 Icon Type: Main		N/A
Criminal Investigation Division Type: Entity Type Entity: Protection Symbol Set: 10 Value: 1**40**300 Icon Type: Main		N/A
Diving Type: Entity Type Entity: Protection Symbol Set: 10 Value: 1**40**400 Icon Type: Main		N/A
Dog Type: Entity Type Entity: Protection Symbol Set: 10 Value: 1**40**500 Icon Type: Main		N/A
Drilling Type: Entity Type Entity: Protection Symbol Set: 10 Value: 1**40**600 Icon Type: Main		N/A
Engineer Type: Entity Type Entity: Protection Symbol Set: 10 Value: 1**40**700 Icon Type: Main		N/A





Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE E-III. Land unit icons - Continued.

DESCRIPTION	ICON	REMARKS
Mechanized Type: Entity Subtype Entity: Protection/Engineer Symbol Set: 10 Value: 1407**01** Icon Type: Main		
Motorized Type: Entity Subtype Entity: Protection/Engineer Symbol Set: 10 Value: 1407**02** Icon Type: Full Octagon		The gray box is not to be drawn. It is shown here only as a reference to position and proportion of the icon within the frame.
Reconnaissance Type: Entity Subtype Entity: Protection/Engineer Symbol Set: 10 Value: 1407**03** Icon Type: Full Frame		The gray box is not to be drawn. It is shown here only as a reference to position and proportion of the icon within the frame.
Explosive Ordnance Disposal (EOD) Type: Entity Type Entity: Protection Symbol Set: 10 Value: 14**08**00 Icon Type: Main		N/A
Field Camp Construction Type: Entity Type Entity: Protection Symbol Set: 10 Value: 14**09**00 Icon Type: Main+1		N/A
Fire Fighting/Fire Protection Type: Entity Type Entity: Protection Symbol Set: 10 Value: 14**10**00 Icon Type: Main		N/A
Geospatial Support/Geospatial Information Support Type: Entity Type Entity: Protection Symbol Set: 10 Value: 14**11**00 Icon Type: Main		N/A




Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE E-III. Land unit icons - Continued.

DESCRIPTION	ICON	REMARKS
Military Police Type: Entity Type Entity: Protection Symbol Set: 10 Value: 14**12**00 Icon Type: Main		N/A
Mine Type: Entity Type Entity: Protection Symbol Set: 10 Value: 14**13**00 Icon Type: Main		N/A
Mine Clearing Type: Entity Type Entity: Protection Symbol Set: 10 Value: 14**14**00 Icon Type: Full Octagon		N/A
Mine Launching Type: Entity Type Entity: Protection Symbol Set: 10 Value: 14**15**00 Icon Type: Full Octagon		N/A
Mine Laying Type: Entity Type Entity: Protection Symbol Set: 10 Value: 14**16**00 Icon Type: Full Octagon		N/A
Security Type: Entity Type Entity: Protection Symbol Set: 10 Value: 14**17**00 Icon Type: Main		N/A
Motorized Type: Entity Subtype Entity: Protection/Security Symbol Set: 10 Value: 1417**02** Icon Type: Main		The gray box is not to be drawn. It is shown here only as a reference to position and proportion of the icon within the frame.




Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE E-III. Land unit icons - Continued.

DESCRIPTION	ICON	REMARKS
Search and Rescue Type: Entity Type Entity: Protection Symbol Set: 10 Value: 14**18**00 Icon Type: Main		N/A
Isolated Personnel Type: Entity Subtype Entity: Protection/Search and Rescue Symbol Set: 10 Value: 1418**01** Icon Type: Main		N/A
Shore Patrol/Security Police Type: Entity Type Entity: Protection Symbol Set: 10 Value: 14**20**00 Icon Type: Main		N/A
Topographic/Geospatial Type: Entity Type Entity: Protection Symbol Set: 10 Value: 14**21**00 Icon Type: Main		N/A
Missile Defense Type: Entity Type Entity: Protection Symbol Set: 10 Value: 14**22**00 Icon Type: Main		N/A
Intelligence Type: Entity Symbol Set: 10 Value: **15**0000	N/A	Reserved for hierarchical purposes.
Analysis Type: Entity Type Entity: Intelligence Symbol Set: 10 Value: 15**01**00 Icon Type: Full Octagon		N/A




Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE E-III. Land unit icons - Continued.

DESCRIPTION	ICON	REMARKS
Counterintelligence Type: Entity Type Entity: Intelligence Symbol Set: 10 Value: 15**02**00 Icon Type: Main		N/A
Direction Finding Type: Entity Type Entity: Intelligence Symbol Set: 10 Value: 15**03**00 Icon Type: Full Octagon		N/A
Electronic Ranging Type: Entity Type Entity: Intelligence Symbol Set: 10 Value: 15**04**00 Icon Type: Main		N/A
Electromagnetic Warfare Type: Entity Type Entity: Intelligence Symbol Set: 10 Value: 15**05**00 Icon Type: Main		N/A
Analysis Type: Entity Subtype Entity/Entity Type: Intelligence/Electromagnetic Warfare Symbol Set: 10 Value: 1505**01** Icon Type: Full Octagon		N/A
Direction Finding Type: Entity Subtype Entity/Entity Type: Intelligence/Electromagnetic Warfare Symbol Set: 10 Value: 1505**02** Icon Type: Full Octagon		N/A




Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE E-III. Land unit icons - Continued.

DESCRIPTION	ICON	REMARKS
Intercept Type: Entity Subtype Entity/Entity Type: Intelligence/Electromagnetic Warfare Symbol Set: 10 Value: 150**503** Icon Type: Full Octagon		N/A
Jamming Type: Entity Subtype Entity/Entity Type: Intelligence/Electromagnetic Warfare Symbol Set: 10 Value: 150**504** Icon Type: Full Frame		The gray box is not to be drawn. It is shown here only as a reference to position and proportion of the icon within the frame.
Search Type: Entity Subtype Entity/Entity Type: Intelligence/Electromagnetic Warfare Symbol Set: 10 Value: 150**505** Icon Type: Full Octagon		N/A
Intercept (Search and Recording) Type: Entity Type Entity: Intelligence Symbol Set: 10 Value: 15**06**00 Icon Type: Full Octagon		N/A
Interrogation Type: Entity Type Entity: Intelligence Symbol Set: 10 Value: 15**07**00 Icon Type: Main		N/A
Jamming Type: Entity Type Entity: Intelligence Symbol Set: 10 Value: 15**08**00 Icon Type: Full Frame		The gray box is not to be drawn. It is shown here only as a reference to position and proportion of the icon within the frame.





Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE E-III. Land unit icons - Continued.

DESCRIPTION	ICON	REMARKS
Joint Intelligence Center Type: Entity Type Entity: Intelligence Symbol Set: 10 Value: 15**09**00 Icon Type: Main		N/A
Military Intelligence Type: Entity Type Entity: Intelligence Symbol Set: 10 Value: 15**10**00 Icon Type: Main		N/A
Search Type: Entity Type Entity: Intelligence Symbol Set: 10 Value: 15**11**00 Icon Type: Full Octagon		N/A
Sensor Type: Entity Type Entity: Intelligence Symbol Set: 10 Value: 15**12**00 Icon Type: Main		N/A
Military History Type: Entity Type Entity: Intelligence Symbol Set: 10 Value: 15**13**00 Icon Type: Main		N/A
Sustainment Type: Entity Symbol Set: 10 Value: **16**0000 Icon Type: Main		N/A
Administrative Type: Entity Type Entity: Sustainment Symbol Set: 10 Value: 16**01**00 Icon Type: Main		N/A







Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE E-III. Land unit icons - Continued.

DESCRIPTION	ICON	REMARKS
All Classes of Supply Type: Entity Type Entity: Sustainment Symbol Set: 10 Value: 16**02**00 Icon Type: Full Frame		The gray box is not to be drawn. It is shown here only as a reference to position and proportion of the icon within the frame.
Ammunition Type: Entity Type Entity: Sustainment Symbol Set: 10 Value: 16**04**00 Icon Type: Main		N/A
Band Type: Entity Type Entity: Sustainment Symbol Set: 10 Value: 16**05**00 Icon Type: Main		N/A
Army Music Type: Entity Subtype Entity: Sustainment/Band Symbol Set: 10 Value: 160**501** Icon Type: Main		N/A
Combat Service Support Type: Entity Type Entity: Sustainment Symbol Set: 10 Value: 16**06**00 Icon Type: Main		N/A
Finance Type: Entity Type Entity: Sustainment Symbol Set: 10 Value: 16**07**00 Icon Type: Main		N/A
Judge Advocate General Type: Entity Type Entity: Sustainment Symbol Set: 10 Value: 16**08**00 Icon Type: Main		N/A






Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE E-III. Land unit icons - Continued.

DESCRIPTION	ICON	REMARKS
Labor Type: Entity Type Entity: Sustainment Symbol Set: 10 Value: 16**09**00 Icon Type: Main		N/A
Laundry/Bath Type: Entity Type Entity: Sustainment Symbol Set: 10 Value: 16**10**00 Icon Type: Main		N/A
Maintenance Type: Entity Type Entity: Sustainment Symbol Set: 10 Value: 16**11**00 Icon Type: Main		N/A
Material Type: Entity Type Entity: Sustainment Symbol Set: 10 Value: 16**12**00 Icon Type: Full Frame		The gray box is not to be drawn. It is shown here only as a reference to position and proportion of the icon within the frame.
Medical Type: Entity Type Entity: Sustainment Symbol Set: 10 Value: 16**13**00 Icon Type: Full Frame		The gray box is not to be drawn. It is shown here only as a reference to position and proportion of the icon within the frame.
Medical Treatment Facility Type: Entity Type Entity: Sustainment Symbol Set: 10 Value: 16**14**00 Icon Type: Full Frame		The gray box is not to be drawn. It is shown here only as a reference to position and proportion of the icon within the frame.
Morale, Welfare and Recreation Type: Entity Type Entity: Sustainment Symbol Set: 10 Value: 16**15**00 Icon Type: Main		N/A




Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE E-III. Land unit icons - Continued.

DESCRIPTION	ICON	REMARKS
Mortuary Affairs/Graves Registration Type: Entity Type Entity: Sustainment Symbol Set: 10 Value: 161600 Icon Type: Main		N/A
Multiple Classes of Supply Type: Entity Type Entity: Sustainment Symbol Set: 10 Value: 161700 Icon Type: Full Frame		The gray box is not to be drawn. It is shown here only as a reference to position and proportion of the icon within the frame.
NATO Supply Class I Type: Entity Type Entity: Sustainment Symbol Set: 10 Value: 161800 Icon Type: Full Frame		These classes are referenced in NATO APP-06. Items of subsistence, e.g. food and forage, which are consumed by personnel or animals at an approximately uniform rate, irrespective of local changes in combat or terrain conditions.
NATO Supply Class III Type: Entity Type Entity: Sustainment Symbol Set: 10 Value: 162000 Icon Type: Full Frame		These classes are referenced in NATO APP-06 Petroleum, oil and lubricants (POL) for all purposes, except for operating aircraft or for use in weapons such as flamethrowers, e.g. gasoline, fuel oil, greases, coal and coke. (Class IIIa - aviation fuel and lubricants)
NATO Supply Class IV Type: Entity Type Entity: Sustainment Symbol Set: 10 Value: 162100 Icon Type: Full Frame		These classes are referenced in NATO APP-06 Supplies for which initial issue allowances are not prescribed by approved issue tables. Normally includes fortification and construction materials, as well as additional quantities of items identical to those authorized for initial issue (Class II) such as additional vehicles.







Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE E-III. Land unit icons - Continued.

DESCRIPTION	ICON	REMARKS
Ordnance Type: Entity Type Entity: Sustainment Symbol Set: 10 Value: 16**23**00 Icon Type: Main		N/A
Personnel Services Type: Entity Type Entity: Sustainment Symbol Set: 10 Value: 16**24**00 Icon Type: Main		N/A
Petroleum, Oil and Lubricants Type: Entity Type Entity: Sustainment Symbol Set: 10 Value: 16**25**00 Icon Type: Main		N/A
Public Affairs/Public Information Type: Entity Type Entity: Sustainment Symbol Set: 10 Value: 16**28**00 Icon Type: Main		N/A
Quartermaster Type: Entity Type Entity: Sustainment Symbol Set: 10 Value: 16**29**00 Icon Type: Main		N/A
Religious Support Type: Entity Type Entity: Sustainment Symbol Set: 10 Value: 16**31**00 Icon Type: Main		N/A
Replacement Holding Unit Type: Entity Type Entity: Sustainment Symbol Set: 10 Value: 16**32**00 Icon Type: Main		N/A




Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE E-III. Land unit icons - Continued.

DESCRIPTION	ICON	REMARKS
Joint Information Bureau (JIB) Type: Entity Type Entity: Sustainment Symbol Set: 10 Value: 16**35**00 Icon Type: Main		N/A
Transportation Type: Entity Type Entity: Sustainment Symbol Set: 10 Value: 16**36**00 Icon Type: Main		N/A
Us Supply Class I Type: Entity Type Entity: Sustainment Symbol Set: 10 Value: 16**37**00 Icon Type: Full Frame		Referenced in STANAG 2961 Classes of Supply of NATO Land Forces Subsistence (food), gratuitous (free) health and comfort items.
Us Supply Class IV Type: Entity Type Entity: Sustainment Symbol Set: 10 Value: 16**40**00 Icon Type: Full Frame		Referenced in STANAG 2961 Classes of Supply of NATO Land Forces Construction materials, including installed equipment and all fortification and barrier materials.
Us Supply Class VI Type: Entity Type Entity: Sustainment Symbol Set: 10 Value: 16**42**00 Icon Type: Full Frame		Referenced in STANAG 2961 Classes of Supply of NATO Land Forces Personal demand items (such as health and hygiene products, soaps and toothpaste, writing material, snack food, beverages, cigarettes, batteries, alcohol and cameras—nonmilitary sales items).
Us Supply Class VII Type: Entity Type Entity: Sustainment Symbol Set: 10 Value: 16**43**00 Icon Type: Full Frame		Referenced in STANAG 2961 Classes of Supply of NATO Land Forces Major end items such as launchers, tanks, mobile machine shops and vehicles.



Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE E-III. Land unit icons - Continued.

DESCRIPTION	ICON	REMARKS
Us Supply Class VIII Type: Entity Type Entity: Sustainment Symbol Set: 10 Value: 164400 Icon Type: Full Frame		Referenced in STANAG 2961 Classes of Supply of NATO Land Forces Medical material (equipment and consumables) including repair parts peculiar to medical equipment. (Class VIIIa – Medical consumable supplies not including blood & blood products; Class VIIIb – Blood & blood components (whole blood, platelets, plasma, packed red cells, etc.).
Us Supply Class IX Type: Entity Type Entity: Sustainment Symbol Set: 10 Value: 164500 Icon Type: Full Frame		Referenced in STANAG 2961 Classes of Supply of NATO Land Forces Repair parts and components to include kits, assemblies and subassemblies (repairable or non-repairable) required for maintenance support of all equipment.
Us Supply Class X Type: Entity Type Entity: Sustainment Symbol Set: 10 Value: 164600 Icon Type: Full Frame		Referenced in STANAG 2961 Classes of Supply of NATO Land Forces Material to support nonmilitary programs such as agriculture and economic development (not included in Classes I through IX).
Water Purification Type: Entity Type Entity: Sustainment Symbol Set: 10 Value: 164800 Icon Type: Main		N/A
Broadcast Type: Entity Type Entity: Sustainment Symbol Set: 10 Value: 164900 Icon Type: Main		N/A


Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE E-III. Land unit icons - Continued.

DESCRIPTION	ICON	REMARKS
Interpreter/Translator Type: Entity Type Entity: Sustainment Symbol Set: 10 Value: 16**51**00 Icon Type: Main		N/A
Support Type: Entity Type Entity: Sustainment Symbol Set: 10 Value: 16**52**00 Icon Type: Main		N/A
Army Field Support Type: Entity Type Entity: Sustainment Symbol Set: 10 Value: 16**53**00 Icon Type: Main		N/A
Contracting Services Type: Entity Type Entity: Sustainment Symbol Set: 10 Value: 16**54**00 Icon Type: Main		N/A
Parachute Rigger Type: Entity Type Entity: Sustainment Symbol Set: 10 Value: 16**55**00 Icon Type: Main		N/A
Human Resources Type: Entity Type Entity: Sustainment Symbol Set: 10 Value: 16**56**00 Icon Type: Main		N/A


Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE E-III. Land unit icons - Continued.

DESCRIPTION	ICON	REMARKS
Naval Type: Entity Symbol Set: 10 Value: 17**00**00	N/A	Reserved for hierarchical purposes.
Naval Type: Entity Type Entity: Naval Symbol Set: 10 Value: 17**01**00 Icon Type: Main		N/A
Named Headquarters Type: Entity Symbol Set: 10 Value: **18**0000	N/A	Reserved for hierarchical purposes.
Allied Command Europe Rapid Reaction Corps (ARRC) Type: Entity Type Entity: Named Headquarters Symbol Set: 10 Value: 18**01**00 Icon Type: Main		N/A
Allied Command Operations Type: Entity Type Entity: Named Headquarters Symbol Set: 10 Value: 18**02**00 Icon Type: Main		N/A
International Security Assistance Force (ISAF) Type: Entity Type Entity: Named Headquarters Symbol Set: 10 Value: 18**03**00 Icon Type: Main		N/A
Multinational (MN) Type: Entity Type Entity: Named Headquarters Symbol Set: 10 Value: 18**04**00 Icon Type: Main		N/A


Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE E-III. Land unit icons - Continued.

DESCRIPTION	ICON	REMARKS
Emergency Operation Type: Entity Symbol Set: 10 Value: **19**0000 Icon Type: Full Octagon		N/A
Law Enforcement Type: Entity Symbol Set: 10 Value: **20**0000 Icon Type: Full Octagon		N/A
Bureau of Alcohol, Tobacco, Firearms and Explosives (ATF) (Department of Justice) Type: Entity Type Entity: Law Enforcement Symbol Set: 10 Value: 20**01**00 Icon Type: Main		N/A
Border Patrol Type: Entity Type Entity: Law Enforcement Symbol Set: 10 Value: 20**02**00 Icon Type: Full Octagon		N/A
Customs Service Type: Entity Type Entity: Law Enforcement Symbol Set: 10 Value: 20**03**00 Icon Type: Full Octagon		N/A
Drug Enforcement Administration (DEA) Type: Entity Type Entity: Law Enforcement Symbol Set: 10 Value: 20**04**00 Icon Type: Main		N/A
Department of Justice (DOJ) Type: Entity Type Entity: Law Enforcement Symbol Set: 10 Value: 20**05**00 Icon Type: Full Octagon		N/A


Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE E-III. Land unit icons - Continued.

DESCRIPTION	ICON	REMARKS
Federal Bureau of Investigation (FBI) Type: Entity Type Entity: Law Enforcement Symbol Set: 10 Value: 20**06**00 Icon Type: Main		N/A
Police Type: Entity Type Entity: Law Enforcement Symbol Set: 10 Value: 20**07**00 Icon Type: Main		N/A
Prison Type: Entity Type Entity: Law Enforcement Symbol Set: 10 Value: 20**08**00 Icon Type: Full Octagon		N/A
United States Secret Service (USSS) Type: Entity Type Entity: Law Enforcement Symbol Set: 10 Value: 20**09**00 Icon Type: Main		N/A
Transportation Security Administration (TSA) Type: Entity Type Entity: Law Enforcement Symbol Set: 10 Value: 20**10**00 Icon Type: Main		N/A
US Coast Guard Type: Entity Type Entity: Law Enforcement Symbol Set: 10 Value: 20**11**00 Icon Type: Full Octagon		N/A
Us Marshals Service Type: Entity Type Entity: Law Enforcement Symbol Set: 10 Value: 20**12**00 Icon Type: Full Octagon		N/A





Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE E-III. Land unit icons - Continued.

DESCRIPTION	ICON	REMARKS
Internal Security Force Type: Entity Type Entity: Law Enforcement Symbol Set: 10 Value: 20**13**00 Icon Type: Main		N/A
Cyber Type: Entity Symbol Set: 10 Value: **21**0000 Icon Type: Main		N/A










E.6.4 Land unit sector 1 modifiers. Land unit sector 1 modifiers denote mobility, capability and composite loss categories. Table E-IV lists land unit sector 1 modifiers and illustrates their placement within the bounding octagon. Additional sector 1 modifiers, where required, are included in table B-I and are accessed using the modifier extension flag.

TABLE E-IV. Land unit sector 1 modifiers.

DESCRIPTION	CATEGORY	MODIFIER	REMARKS
Tactical Satellite Communications Symbol Set: 10 Value: 01	Capability		N/A
Area Symbol Set: 10 Value: 02	Capability		N/A
Biological Symbol Set: 10 Value: 04	Capability		N/A
Border Symbol Set: 10 Value: 05	Capability		N/A










Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE E-IV. Land unit sector 1 modifiers – Continued.

DESCRIPTION	CATEGORY	MODIFIER	REMARKS
Communications Contingency Package Symbol Set: 10 Value: 11	Capability		N/A
Construction Symbol Set: 10 Value: 12	Capability		N/A
Cross Cultural Communication Symbol Set: 10 Value: 13	Capability		N/A
Detention Symbol Set: 10 Value: 16	Capability		N/A
Direct Communications Symbol Set: 10 Value: 17	Capability		N/A
Diving Symbol Set: 10 Value: 18	Capability		N/A
Division Symbol Set: 10 Value: 19	Capability		N/A
Dog Symbol Set: 10 Value: 20	Capability		N/A
Drilling Symbol Set: 10 Value: 21	Capability		N/A










Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE E-IV. Land unit sector 1 modifiers – Continued.

DESCRIPTION	CATEGORY	MODIFIER	REMARKS
Electro-Optical Symbol Set: 10 Value: 22	Capability		N/A
Enhanced Symbol Set: 10 Value: 23	Capability		N/A
Fire Direction Center Symbol Set: 10 Value: 25	Capability		N/A
Force Symbol Set: 10 Value: 26	Capability		N/A
Forward Symbol Set: 10 Value: 27	Capability		N/A
Ground Station Module Symbol Set: 10 Value: 28	Capability		N/A
Landing Support Symbol Set: 10 Value: 29	Capability		N/A
Meteorological Symbol Set: 10 Value: 32	Capability		N/A
Missile Symbol Set: 10 Value: 34	Capability		N/A









Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE E-IV. Land unit sector 1 modifiers – Continued.

DESCRIPTION	CATEGORY	MODIFIER	REMARKS
Mobile Advisor and Support Symbol Set: 10 Value: 35	Capability		N/A
Mobile Subscriber Equipment Symbol Set: 10 Value: 36	Capability		N/A
Mobility Support Symbol Set: 10 Value: 37	Capability		N/A
Multinational Symbol Set: 10 Value: 39	Capability		N/A
Multinational Specialized Unit Symbol Set: 10 Value: 40	Capability		N/A
Multiple Rocket Launcher Symbol Set: 10 Value: 41	Capability		N/A
NATO Medical Role 1 Symbol Set: 10 Value: 42	Capability		Modifier is offset so that the modifier is not compromised by the main sector icon.
NATO Medical Role 2 Symbol Set: 10 Value: 43	Capability		Modifier is offset so that the modifier is not compromised by the main sector icon.
NATO Medical Role 3 Symbol Set: 10 Value: 44	Capability		Modifier is offset so that the modifier is not compromised by the main sector icon.










Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE E-IV. Land unit sector 1 modifiers – Continued.

DESCRIPTION	CATEGORY	MODIFIER	REMARKS
NATO Medical Role 4 Symbol Set: 10 Value: 45	Capability		Modifier is offset so that the modifier is not compromised by the main sector icon.
Naval Symbol Set: 10 Value: 46	Capability		N/A
Unmanned Aerial Systems (UAS) Symbol Set: 10 Value: 47	Capability		N/A
Operations Symbol Set: 10 Value: 49	Capability		N/A
Radar Symbol Set: 10 Value: 50	Capability		N/A
Radio Frequency Identification (RFID) Interrogator/Sensor Symbol Set: 10 Value: 51	Capability		N/A
Sensor Symbol Set: 10 Value: 55	Capability		N/A
Signal Intelligence Symbol Set: 10 Value: 57	Capability		N/A










Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE E-IV. Land unit sector 1 modifiers – Continued.

DESCRIPTION	CATEGORY	MODIFIER	REMARKS
Single Rocket Launcher Symbol Set: 10 Value: 59	Capability		N/A
Smoke Symbol Set: 10 Value: 60	Capability		N/A
Sound Ranging Symbol Set: 10 Value: 62	Capability		N/A
Survey Symbol Set: 10 Value: 65	Capability		N/A
Tactical Exploitation Symbol Set: 10 Value: 66	Capability		N/A
Target Acquisition Symbol Set: 10 Value: 67	Capability		N/A
Topographic/Geospatial Symbol Set: 10 Value: 68	Capability		N/A
Video Imagery (Combat Camera) Symbol Set: 10 Value: 70	Capability		N/A
Mobility Assault Symbol Set: 10 Value: 71	Capability		N/A









Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE E-IV. Land unit sector 1 modifiers – Continued.

DESCRIPTION	CATEGORY	MODIFIER	REMARKS
Amphibious Warfare Ship Symbol Set: 10 Value: 72	Capability		N/A
Load Handling System Symbol Set: 10 Value: 73	Capability		N/A
Palletized Load System Symbol Set: 10 Value: 74	Capability		N/A
Support Symbol Set: 10 Value: 77	Capability		N/A
Route, Reconnaissance, and Clearance Symbol Set: 10 Value: 79	Capability		N/A
Assault Symbol Set: 10 Value: 84	Capability		N/A
Criminal Investigation Division Symbol Set: 10 Value: 86	Capability		N/A
Digital Symbol Set: 10 Value: 87	Capability		N/A
Network or Network Operations Symbol Set: 10 Value: 88	Capability		N/A

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.









TABLE E-IV. Land unit sector 1 modifiers – Continued.

DESCRIPTION	CATEGORY	MODIFIER	REMARKS
Airfield, Aerial Port of Debarkation, or Aerial Port of Embarkation Symbol Set: 10 Value: 89	Capability		N/A
Pipeline Symbol Set: 10 Value: 90	Capability		N/A
Postal Symbol Set: 10 Value: 91	Capability		N/A
Theater Symbol Set: 10 Value: 94	Capability		N/A
Army or Theater Army Symbol Set: 10 Value: 95	Capability		N/A
Corps Symbol Set: 10 Value: 96	Capability		N/A
Headquarters or Headquarters Staff Element Symbol Set: 10 Value: 98	Capability		The gray box is not to be drawn. It is shown here only as a reference to position and proportion of the icon within the frame.
Multi-Domain Operations Symbol Set: 10 Value: 99	Capability		N/A

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.










E.6.5 Land unit sector 2 modifiers. Land unit sector 2 modifiers denote close range and control, mobility and capability categories. Table E-V lists land unit sector 2 modifiers and illustrates their placement within the bounding octagon. Additional sector 2 modifiers, where required, are included in table B-II and are accessed using the modifier extension flag.

TABLE E-V. Land unit sector 2 modifiers.

DESCRIPTION	CATEGORY	MODIFIER	REMARKS
Arctic Symbol Set: 10 Value: 02	Mobility		N/A
Battle Damage Repair Symbol Set: 10 Value: 03	Capability		N/A
Casualty Staging Symbol Set: 10 Value: 05	Capability		Modifier is offset so that the modifier is not compromised by the main sector icon.
Clearing Symbol Set: 10 Value: 06	Capability		N/A
Control Symbol Set: 10 Value: 08	Capability		N/A
Decontamination Symbol Set: 10 Value: 09	Capability		N/A
Demolition Symbol Set: 10 Value: 10	Capability		N/A
Dental Symbol Set: 10 Value: 11	Capability		Modifier is offset so that the modifier is not compromised by the main sector icon.










Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE E-V. Land unit sector 2 modifiers - Continued.

DESCRIPTION	CATEGORY	MODIFIER	REMARKS
Digital Symbol Set: 10 Value: 12	Capability		N/A
Enhanced Position Location Reporting System (EPLRS) Symbol Set: 10 Value: 13	Capability		N/A
Equipment Symbol Set: 10 Value: 14	Capability		APP-06
High Altitude Symbol Set: 10 Value: 16	Capability		N/A
Intermodal Symbol Set: 10 Value: 17	Capability		N/A
Intensive Care Symbol Set: 10 Value: 18	Capability		Modifier is offset so that the modifier is not compromised by the main sector icon.
Laboratory Symbol Set: 10 Value: 20	Capability		N/A
Launcher Symbol Set: 10 Value: 21	Capability		N/A
Low Altitude Symbol Set: 10 Value: 23	Capability		N/A










Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE E-V. Land unit sector 2 modifiers - Continued.

DESCRIPTION	CATEGORY	MODIFIER	REMARKS
Medium Altitude Symbol Set: 10 Value: 25	Capability		N/A
High to Medium Altitude Symbol Set: 10 Value: 28	Capability		N/A
Multi-Channel Symbol Set: 10 Value: 29	Capability		N/A
Optical (Flash) Symbol Set: 10 Value: 30	Capability		N/A
Pack Animal Symbol Set: 10 Value: 31	Capability		N/A
Patient Evacuation Coordination Symbol Set: 10 Value: 32	Capability		Modifier is offset so that the modifier is not compromised by the main sector icon.
Preventive Maintenance Symbol Set: 10 Value: 33	Capability		N/A
Psychological Symbol Set: 10 Value: 34	Capability		Modifier is offset so that the modifier is not compromised by the main sector icon.
Radio Relay Line of Sight Symbol Set: 10 Value: 35	Capability		N/A









Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE E-V. Land unit sector 2 modifiers - Continued.

DESCRIPTION	CATEGORY	MODIFIER	REMARKS
Recovery (Unmanned Systems) Symbol Set: 10 Value: 37	Capability		N/A
Recovery (Maintenance) Symbol Set: 10 Value: 38	Capability		N/A
Rescue Coordination Center Symbol Set: 10 Value: 39	Capability		Modifier is offset so that the modifier is not compromised by the main sector icon.
Riverine Symbol Set: 10 Value: 40	Mobility		N/A
Single Channel Symbol Set: 10 Value: 41	Capability		N/A
Strategic Symbol Set: 10 Value: 44	Capability		N/A
Support Symbol Set: 10 Value: 45	Capability		N/A
Tactical Symbol Set: 10 Value: 46	Capability		N/A
Towed Symbol Set: 10 Value: 47	Mobility		N/A










Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE E-V. Land unit sector 2 modifiers - Continued.

DESCRIPTION	CATEGORY	MODIFIER	REMARKS
Troop Symbol Set: 10 Value: 48	Capability		N/A
Vertical or Short Take-Off and Landing (VTOL/VSTOL) Symbol Set: 10 Value: 49	Mobility		N/A
Veterinary Symbol Set: 10 Value: 50	Capability		Modifier is offset so that the modifier is not compromised by the main sector icon.
High to Low Altitude Symbol Set: 10 Value: 52	Capability		N/A
Medium to Low Altitude Symbol Set: 10 Value: 53	Capability		N/A
Refuel Symbol Set: 10 Value: 55	Capability		N/A
Utility Symbol Set: 10 Value: 56	Capability		N/A
Combat Search and Rescue Symbol Set: 10 Value: 57	Capability		N/A










Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE E-V. Land unit sector 2 modifiers - Continued.

DESCRIPTION	CATEGORY	MODIFIER	REMARKS
Guerrilla Symbol Set: 10 Value: 58	Capability		N/A
Air Assault Symbol Set: 10 Value: 59	Mobility		N/A
Amphibious Symbol Set: 10 Value: 60	Mobility		The gray box is not to be drawn. It is shown here only as a reference to position and proportion of the icon within the frame.
Very Heavy Symbol Set: 10 Value: 61	Capability		N/A
Supply Symbol Set: 10 Value: 62	Capability		The gray box is not to be drawn. It is shown here only as a reference to position and proportion of the icon within the frame.
Barge, Self-Propelled Symbol Set: 10 Value: 64	Mobility		N/A
Barge, Not Self-Propelled Symbol Set: 10 Value: 65	Mobility		N/A
Launch Symbol Set: 10 Value: 66	Mobility		N/A
Landing Craft Symbol Set: 10 Value: 67	Mobility		N/A







Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE E-V. Land unit sector 2 modifiers - Continued.

DESCRIPTION	CATEGORY	MODIFIER	REMARKS
Landing Ship Symbol Set: 10 Value: 68	Mobility		N/A
Service Craft/Yard Symbol Set: 10 Value: 69	Mobility		N/A
Tug Harbor Symbol Set: 10 Value: 70	Mobility		N/A
Ocean Going Tug Boat Symbol Set: 10 Value: 71	Mobility		N/A
Surface Deployment and Distribution Command Symbol Set: 10 Value: 72	Capability		N/A
Noncombatant Generic Vessel Symbol Set: 10 Value: 73	Mobility		N/A
Composite Symbol Set: 10 Value: 74	Capability		N/A
Shelter Symbol Set: 10 Value: 75	Capability		N/A
Surgical Symbol Set: 10 Value: 81	Capability		N/A

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE E-V. Land unit sector 2 modifiers - Continued.

DESCRIPTION	CATEGORY	MODIFIER	REMARKS
Blood Symbol Set: 10 Value: 82	Capability		N/A
Combat and Operational Stress Control Symbol Set: 10 Value: 83	Capability		N/A
Jamming Symbol Set: 10 Value: 84	Capability		The gray box is not to be drawn. It is shown here only as a reference to position and proportion of the icon within the frame.
Optometry Symbol Set: 10 Value: 86	Capability		N/A
Preventive Medicine Symbol Set: 10 Value: 87	Capability		N/A
Air Defense Symbol Set: 10 Value: 89	Capability		The gray box is not to be drawn. It is shown here only as a reference to position and proportion of the icon within the frame.





Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

E.7 LAND CIVILIAN INDIVIDUALS/ORGANIZATION SYMBOLS

E.7.1 Land civilian individuals/organization symbols. This section includes the lists of icons and modifiers for building land civilian unit symbols.




E.7.2 Land civilian individuals/organization icons. Table E-VI depicts land civilian unit icons.

TABLE E-VI. Land civilian individuals/organization icons.

DESCRIPTION	ICON	REMARKS
Civilian Type: Entity Symbol Set: 11 Value: **11**0000 Icon Type: Main	N/A	Reserved for hierarchical purposes.
Environmental Protection Type: Entity Type Entity: Civilian Symbol Set: 11 Value: 11**01**00 Icon Type: Main		N/A
Government Organization Type: Entity Type Entity: Civilian Symbol Set: 11 Value: 11**02**00 Icon Type: Main		N/A
Individual Type: Entity Type Entity: Civilian Symbol Set: 11 Value: 11**03**00 Icon Type: Main		N/A
Organization or Group Type: Entity Type Entity: Civilian Symbol Set: 11 Value: 11**04**00 Icon Type: Main		N/A
Killing Victim Type: Entity Type Entity: Civilian Symbol Set: 11 Value: 11**05**00 Icon Type: Main		N/A

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.








TABLE E-VI. Land civilian individuals/organization icons - Continued.

DESCRIPTION	ICON	REMARKS
Killing Victims Type: Entity Type Entity: Civilian Symbol Set: 11 Value: 11**06**00 Icon Type: Main		N/A
Victim of an Attempted Killing Type: Entity Type Entity: Civilian Symbol Set: 11 Value: 11**07**00 Icon Type: Main		N/A
Spy Type: Entity Type Entity: Civilian Symbol Set: 11 Value: 11**08**00 Icon Type: Main		N/A
Composite Loss Type: Entity Type Entity: Civilian Symbol Set: 11 Value: 11**09**00 Icon Type: Main		N/A
Emergency Medical Operation Type: Entity Type Entity: Civilian Symbol Set: 11 Value: 111000 Icon Type: Full Octagon		N/A

E.7.3 Land civilian unit/organization sector 1 modifiers. Land civilian unit sector 1 modifiers denote crime and organization categories. Table E-VII lists land civilian unit sector 1 modifiers and illustrates their placement within the bounding octagon. Additional sector 1 modifiers, where required, are included in table B-I and are accessed using the modifier extension flag.







Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE E-VII. Land civilian unit/organization sector 1 modifiers.

DESCRIPTION	CATEGORY	MODIFIER	REMARKS
Murder Victims Symbol Set: 11 Value: 03	Crime		N/A
Displaced Person(s), Refugee(s) and Evacuee(s) Symbol Set: 11 Value: 09	Organization		N/A
Foreign Fighter(s) Symbol Set: 11 Value: 10	Organization		N/A
Gang Member or Gang Symbol Set: 11 Value: 11	Organization		N/A
Leader or Leadership Symbol Set: 11 Value: 13	Organization		N/A
Nongovernmental Organization Member or Nongovernmental Organization Symbol Set: 11 Value: 14	Organization		N/A
Unwilling/Coerced Recruit Symbol Set: 11 Value: 15	Organization		N/A
Willing Recruit Symbol Set: 11 Value: 16	Organization		N/A


Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE E-VII. Land civilian unit/organization sector 1 modifiers - Continued.

DESCRIPTION	CATEGORY	MODIFIER	REMARKS
Religious or Religious Organization Symbol Set: 11 Value: 17	Organization		N/A
Targeted Individual or Organization Symbol Set: 11 Value: 18	Organization		N/A
Terrorist or Terrorist Organization Symbol Set: 11 Value: 19	Organization		N/A
Speaker Symbol Set: 11 Value: 20	Organization		N/A
Other Symbol Set: 11 Value: 23	Composite Loss		N/A
Loot Symbol Set: 11 Value: 24	Crime		N/A

E.7.4 Land civilian unit sector 2 modifiers. Land civilian unit sector 2 modifiers denote organization category. Table E-VIII lists the land civilian unit sector 2 modifiers and illustrates their placement within the bounding octagon. Additional sector 2 modifiers, where required, are included in table B-II and are accessed using the modifier extension flag.

TABLE E-VIII. Land civilian unit/organization sector 2 modifiers.

DESCRIPTION	CATEGORY	MODIFIER	REMARKS
Leader or Leadership Symbol Set: 11 Value: 01	Organization		N/A

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

E.8 LAND EQUIPMENT SYMBOLS

E.8.1 Land equipment symbols. This section includes the lists of icons and modifiers for building land equipment symbols. Figure E-4 shows the placement of land equipment symbol amplifiers around the friend symbol frame. Table E-IX provides descriptions and formats of each amplifier.




FIGURE E-4. Placement of land equipment symbol amplifiers.

TABLE E-IX. Descriptions and formats of land equipment symbol amplifiers.

FIELD	FIELD TITLE	DESCRIPTION	FORMAT
A	Symbol Icon	The innermost part of a symbol, comprised of an icon and optional modifiers, that represents a joint military object (see 5.3.4).	
C	Quantity	A text amplifier in an equipment symbol that identifies the number of items present.	
G	Staff Comments	A text amplifier for units, equipment, and installations; content is implementation specific.	
H	Additional Information	A text amplifier for units, equipment, and installations; content is implementation specific.	

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE E-IX. Descriptions and formats of land equipment symbol amplifiers - Continued.

FIELD	FIELD TITLE	DESCRIPTION	FORMAT
J	Evaluation Rating	A text amplifier for units, equipment and installations that consists of a single-letter reliability rating and a single digit credibility rating: (See ATP 2-33.4) **Reliability Ratings:** A-completely reliable B-usually reliable C-fairly reliable D-not usually reliable E-unreliable F-reliability cannot be judged. **Credibility Ratings:** 1-confirmed by other sources 2-probably true 3-possibly true 4-doubtfully true 5-improbable 6-truth cannot be judged.	
K	Combat Effectiveness	A text amplifier for units and installations that indicates effectiveness. The entries are: fully operational (FO) substantially operational (SO) marginally operational (MO) not operational (NO) unknown (UNK)	
L	Signature Equipment	A text amplifier for hostile equipment; "**!**" indicates detectable electronic signatures.	
M	Higher Formation	A text amplifier for units that indicates number or title of higher echelon command (Corps is designated by Roman numerals).	
P	IFF/SIF	A text amplifier displaying one or more IFF/SIF Identification modes and codes. **Display priority:** Mode 5, Mode S, Mode 2, Mode 3.	Mode 2 Prefix: 2:#### **Example**: 2:1234
Q	Direction of Movement Indicator	A graphic amplifier that identifies the direction of movement or intended movement of an object (see 5.3.7.9 and figure 14).	
R	Mobility Indicator	A graphic amplifier for equipment that depicts the mobility of an object (see 5.3.7.10, figure 14 and table III).	
T	Unique Designation (Track Number)	A text amplifier for units, equipment and installations that uniquely identifies a particular symbol or track number.	Prefix = TN:##### **Example**: TN:13579
V	Type	A text amplifier for equipment that indicates types of equipment.	

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE E-IX. Descriptions and formats of land equipment symbol amplifiers - Continued.

FIELD	FIELD TITLE	DESCRIPTION	FORMAT
W	Date-Time Group (DTG)	An alphanumeric designator for displaying a date-time group (DDHHMMSSZMONYYYY) or "O/O" for on order. The date-time group is composed of a group of six numeric digits with a time zone suffix and the standardized three-letter abbreviation for the month followed by four digits representing the year. The first pair of digits represents the day; the second pair, the hour; the third pair, the minutes. For automated systems, two digits may be added before the time zone suffix and after the minutes to designate seconds (see 5.3.7.8).	
X	Altitude/Depth	A text amplifier for units, equipment and installations that displays either altitude, flight level, depth for submerged objects, or height of equipment or structures on the ground. See 5.3.7.6 for content.	Measurement units shall be displayed within the string **Examples**: 1500MSL FL150
Y	Location	A text amplifier for units, equipment and installations that displays a symbol's location in degrees, minutes and decimal minutes (or in MGRS, GARS, or other applicable display formats).	3317.0921N 04412.6332E 38SMB2649083145
Z	Speed	A text amplifier for units and equipment that displays velocity (see 5.3.7.7).	
AD	Platform Type	Electronic intelligence notation (ELNOT) or communications intelligence notation (CENOT)	
AE	Equipment Teardown Time	Equipment teardown time in minutes.	
AF	Common Identifier	Example: "Hawk" for Hawk SAM system.	
AG	Auxiliary Equipment Indicator	Towed sonar array indicator: A graphic amplifier for equipment that indicates the presence of a towed sonar array (see 5.3.7.11, and figure 14).	
AL	Operational Condition	A graphic amplifier for equipment or installations that indicates operational condition or capacity.	Operational Condition amplifier, if used, shall be comprised of only one color. **Ex. Aircraft**: Red - damaged, Green – fully capable **Ex: Missile**: Red – imminent threat, Green – no threat




Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE E-IX. Descriptions and formats of land equipment symbol amplifiers - Continued.

FIELD	FIELD TITLE	DESCRIPTION	FORMAT
AO	Engagement Bar	A graphic amplifier placed immediately atop the symbol. May denote: 1) local/remote status 2) engagement status 3) weapon type.	A:BBB:CC, where A = remote/local BBB = engagement status CC = weapon asset
AQ	Guarded Unit	During ballistic missile defense, some tracks are designated as guarded by a particular unit.	
AS	Country	A three-letter code that indicates the country of origin of the organization (US systems shall use GENC).	







E.8.2 Land equipment icons. Table E-X depicts land equipment icons.

TABLE E-X. Land equipment icons.

DESCRIPTION	ICON	REMARKS
Weapon/Weapon System Type: Entity Symbol Set: 15 Value: **11**0000 Icon Type: Full Octagon	N/A	Reserved for hierarchical purposes.
Rifle Type: Entity Type Entity: Weapon/Weapon System Symbol Set: 15 Value: 11**01**00 Icon Type: Full Octagon		N/A
Single Shot Rifle Type: Entity Subtype Entity/Entity Type: Weapon/Weapon System/Rifle Symbol Set: 15 Value: 1101**01** Icon Type: Full Octagon		N/A
Semiautomatic Rifle Type: Entity Subtype Entity/Entity Type: Weapon/Weapon System/Rifle Symbol Set: 15 Value: 1101**02** Icon Type: Main		N/A







Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE E-X. Land equipment icons - Continued.

DESCRIPTION	ICON	REMARKS
Automatic Rifle Type: Entity Subtype Entity/Entity Type: Weapon/Weapon System/Rifle Symbol Set: 15 Value: 1101**03** Icon Type: Main		N/A
Machine Gun Type: Entity Type Entity: Weapon/Weapon System Symbol Set: 15 Value: 11**02**00 Icon Type: Main		N/A
Machine Gun – Light Type: Entity Subtype Entity/Entity Type: Weapon/Weapon System/Machine Gun Symbol Set: 15 Value: 1102**01** Icon Type: Main		N/A
Machine Gun – Medium Type: Entity Subtype Entity/Entity Type: Weapon/Weapon System/Machine Gun Symbol Set: 15 Value: 1102**02** Icon Type: Main		N/A
Machine Gun – Heavy Type: Entity Subtype Entity/Entity Type: Weapon/Weapon System/Machine Gun Symbol Set: 15 Value: 1102**03** Icon Type: Main		N/A
Grenade Launcher Type: Entity Type Entity/Entity Type: Weapon/Weapon System/Grenade Launcher Symbol Set: 15 Value: 11**03**00 Icon Type: Main		N/A







Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE E-X. Land equipment icons - Continued.

DESCRIPTION	ICON	REMARKS
Grenade Launcher – Light Type: Entity Subtype Entity/Entity Type: Weapon/Weapon System/Grenade Launcher Symbol Set: 15 Value: 1103**01** Icon Type: Main		N/A
Grenade Launcher – Medium Type: Entity Subtype Entity/Entity Type: Weapon/Weapon System/Grenade Launcher Symbol Set: 15 Value: 1103**02** Icon Type: Main		N/A
Grenade Launcher – Heavy Type: Entity Subtype Entity/Entity Type: Weapon/Weapon System/Grenade Launcher Symbol Set: 15 Value: 1103**03** Icon Type: Main		N/A
Flame Thrower Type: Entity Type Entity: Weapon/Weapon System Symbol Set: 15 Value: 11**04**00 Icon Type: Main		N/A
Air Defense Gun Type: Entity Type Entity/Entity Type: Weapon/Weapon System/Gun Symbol Set: 15 Value: 11**05**00 Icon Type: Main		N/A
Air Defense Gun – Light Type: Entity Subtype Entity/Entity Type: Weapon/Weapon System/Air Defense Gun Symbol Set: 15 Value: 110**501** Icon Type: Main		N/A







Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE E-X. Land equipment icons - Continued.

DESCRIPTION	ICON	REMARKS
Air Defense Gun – Medium Type: Entity Subtype Entity/Entity Type: Weapon/Weapon System/Air Defense Gun Symbol Set: 15 Value: 110502 Icon Type: Main		N/A
Air Defense Gun – Heavy Type: Entity Subtype Entity/Entity Type: Weapon/Weapon System/Air Defense Gun Symbol Set: 15 Value: 110503 Icon Type: Main		N/A
Antitank Gun Type: Entity Type Entity/Entity Type: Weapon/Weapon System/ Antitank Gun Symbol Set: 15 Value: 110600 Icon Type: Main		N/A
Antitank Gun – Light Type: Entity Subtype Entity/Entity Type: Weapon/Weapon System/ Antitank Gun Symbol Set: 15 Value: 110601 Icon Type: Main		N/A
Antitank Gun – Medium Type: Entity Subtype Entity/Entity Type: Weapon/Weapon System/Antitank Gun Symbol Set: 15 Value: 110602 Icon Type: Main		N/A
Antitank Gun – Heavy Type: Entity Subtype Entity/Entity Type: Weapon/Weapon System/Antitank Gun Symbol Set: 15 Value: 110603 Icon Type: Main		N/A







Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE E-X. Land equipment icons - Continued.

DESCRIPTION	ICON	REMARKS
Direct Fire Gun Type: Entity Type Entity/Entity Type: Weapon/Weapon System/Direct Fire Gun Symbol Set: 15 Value: 11**07**00 Icon Type: Main		N/A
Direct Fire Gun – Light Type: Entity Subtype Entity/Entity Type: Weapon/Weapon System/ Direct Fire Gun Symbol Set: 15 Value: 11070**1** Icon Type: Main		N/A
Direct Fire Gun – Medium Type: Entity Subtype Entity/Entity Type: Weapon/Weapon System/Direct Fire Gun Symbol Set: 15 Value: 11070**2** Icon Type: Main		N/A
Direct Fire Gun – Heavy Type: Entity Subtype Entity/Entity Type: Weapon/Weapon System/Direct Fire Gun Symbol Set: 15 Value: 11070**3** Icon Type: Main		N/A
Recoilless Gun Type: Entity Type Entity/Entity Type: Weapon/Weapon System/ Recoilless Gun Symbol Set: 15 Value: 11**08**00 Icon Type: Main		N/A
Recoilless Gun – Light Type: Entity Subtype Entity/Entity Type: Weapon/Weapon System/ Recoilless Gun Symbol Set: 15 Value: 11080**1** Icon Type: Main		N/A







Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE E-X. Land equipment icons - Continued.

DESCRIPTION	ICON	REMARKS
Recoilless Gun – Medium Type: Entity Subtype Entity/Entity Type: Weapon/Weapon System/Recoilless Gun Symbol Set: 15 Value: 1108**02** Icon Type: Main		N/A
Recoilless Gun – Heavy Type: Entity Subtype Entity/Entity Type: Weapon/Weapon System/ Recoilless Gun Symbol Set: 15 Value: 1108**03** Icon Type: Main		N/A
Howitzer Type: Entity Type Entity: Weapon/Weapon System Symbol Set: 15 Value: 11**09**00 Icon Type: Main		N/A
Howitzer – Light Type: Entity Subtype Entity/Entity Type: Weapon/Weapon System/Howitzer Symbol Set: 15 Value: 1109**01** Icon Type: Main		N/A
Howitzer – Medium Type: Entity Subtype Entity/Entity Type: Weapon/Weapon System/Howitzer Symbol Set: 15 Value: 1109**02** Icon Type: Main		N/A
Howitzer – Heavy Type: Entity Subtype Entity/Entity Type: Weapon/Weapon System/Howitzer Symbol Set: 15 Value: 1109**03** Icon Type: Main		N/A






Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE E-X. Land equipment icons - Continued.

DESCRIPTION	ICON	REMARKS
Missile Launcher Type: Entity Type Entity: Weapon/Weapon System Symbol Set: 15 Value: 11**10**00 Icon Type: Main		N/A
Missile Launcher – Light Entity/Entity Subtype: Weapon/Weapon System/Missile Launcher Symbol Set: 15 Value: 1110**01** Icon Type: Main		N/A
Missile Launcher – Medium Entity/Entity Subtype: Weapon/Weapon System/Missile Launcher Symbol Set: 15 Value: 1110**02** Icon Type: Main		N/A
Missile Launcher – Heavy Entity/Entity Subtype: Weapon/Weapon System/Missile Launcher Symbol Set: 15 Value: 1110**03** Icon Type: Main		N/A
Air Defense Missile Launcher Type: Entity Type Entity: Weapon/Weapon System Symbol Set: 15 Value: 11**11**00 Icon Type: Main		N/A
Air Defense Missile Launcher – Light Type: Entity Subtype Entity/Entity Type: Weapon/Weapon System/ Air Defense Missile Launcher Symbol Set: 15 Value: 1111**01** Icon Type: Main		N/A







Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE E-X. Land equipment icons - Continued.

DESCRIPTION	ICON	REMARKS
Air Defense Missile Launcher – Light, TLAR Type: Entity Subtype Entity/Entity Type: Weapon/Weapon System/ Air Defense Missile Launcher Symbol Set: 15 Value: 1111**02** Icon Type: Full Octagon		N/A
Air Defense Missile Launcher – Light, TELAR Type: Entity Subtype Entity/Entity Type: Weapon/Weapon System/ Air Defense Missile Launcher Symbol Set: 15 Value: 1111**03** Icon Type: Full Octagon		N/A
Air Defense Missile Launcher – Medium Type: Entity Subtype Entity/Entity Type: Weapon/Weapon System/Air Defense Missile Launcher Symbol Set: 15 Value: 1111**04** Icon Type: Main		N/A
Air Defense Missile Launcher – Medium, Tlar Type: Entity Subtype Entity/Entity Type: Weapon/Weapon System/ Air Defense Missile Launcher Symbol Set: 15 Value: 1111**05** Icon Type: Full Octagon		N/A
Air Defense Missile Launcher – Medium, Telar Type: Entity Subtype Entity/Entity Type: Weapon/Weapon System/ Air Defense Missile Launcher Symbol Set: 15 Value: 1111**06** Icon Type: Full Octagon		N/A







Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE E-X. Land equipment icons - Continued.

DESCRIPTION	ICON	REMARKS
Air Defense Missile Launcher – Heavy Type: Entity Subtype Entity/Entity Type: Weapon/Weapon System/ Air Defense Missile Launcher Symbol Set: 15 Value: 1111**07** Icon Type: Main		N/A
Air Defense Missile Launcher – Heavy, TLAR Type: Entity Subtype Entity/Entity Type: Weapon/Weapon System/ Air Defense Missile Launcher Symbol Set: 15 Value: 111108 Icon Type: Full Octagon		N/A
Air Defense Missile Launcher – Heavy, TELAR Type: Entity Subtype Entity/Entity Type: Weapon/Weapon System/ Air Defense Missile Launcher Symbol Set: 15 Value: 111109 Icon Type: Full Octagon		N/A
Antitank Missile Launcher Type: Entity Type Entity: Weapon/Weapon System Symbol Set: 15 Value: 11**12**00 Icon Type: Main		N/A
Antitank Missile Launcher – Light Type: Entity Subtype Entity/Entity Type: Weapon/Weapon System/Antitank Missile Launcher Symbol Set: 15 Value: 1112**01** Icon Type: Main		N/A
Antitank Missile Launcher – Medium Type: Entity Subtype Entity/Entity Type: Weapon/Weapon System/ Antitank Missile Launcher Symbol Set: 15 Value: 1112**02** Icon Type: Main		N/A







Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE E-X. Land equipment icons - Continued.

DESCRIPTION	ICON	REMARKS
Antitank Missile Launcher – Heavy Type: Entity Subtype Entity/Entity Type: Weapon/Weapon System/ Antitank Missile Launcher Symbol Set: 15 Value: 1112**03** Icon Type: Main		N/A
Surface-To-Surface Missile Launcher Type: Entity Type Entity/Entity Type: Weapon/Weapon System Symbol Set: 15 Value: 11**13**00 Icon Type: Main		N/A
Surface-To-Surface Missile Launcher – Light Type: Entity Subtype Entity/Entity Type: Weapon/Weapon System/Surface-To-Surface Missile Launcher Symbol Set: 15 Value: 1113**01** Icon Type: Main		N/A
Surface-To-Surface Missile Launcher – Medium Type: Entity Subtype Entity/Entity Type: Weapon/Weapon System/ Surface-To-Surface Missile Launcher Symbol Set: 15 Value: 1113**02** Icon Type: Main		N/A
Surface-To-Surface Missile Launcher – Heavy Type: Entity Subtype Entity/Entity Type: Weapon/Weapon System/ Surface-To-Surface Missile Launcher Symbol Set: 15 Value: 1113**03** Icon Type: Main		N/A
Mortar Type: Entity Type Entity: Weapon/Weapon System Symbol Set: 15 Value: 11**14**00 Icon Type: Main		N/A







Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE E-X. Land equipment icons - Continued.

DESCRIPTION	ICON	REMARKS
Mortar – Light Type: Entity Subtype Entity/Entity Type: Weapon/Weapon System/Mortar Symbol Set: 15 Value: 1114**01** Icon Type: Main		N/A
Mortar – Medium Type: Entity Subtype Entity/Entity Type: Weapon/Weapon System/Mortar Symbol Set: 15 Value: 1114**02** Icon Type: Main		N/A
Mortar – Heavy Type: Entity Subtype Entity/Entity Type: Weapon/Weapon System/Mortar Symbol Set: 15 Value: 1114**03** Icon Type: Main		N/A
Single Rocket Launcher Type: Entity Type Entity: Weapon/Weapon System Symbol Set: 15 Value: 11**15**00 Icon Type: Main		N/A
Single Rocket Launcher – Light Type: Entity Subtype Entity/Entity Type: Weapon/Weapon System/Single Rocket Launcher Symbol Set: 15 Value: 1115**01** Icon Type: Main		N/A
Single Rocket Launcher – Medium Type: Entity Subtype Entity/Entity Type: Weapon/Weapon System/Single Rocket Launcher Symbol Set: 15 Value: 1115**02** Icon Type: Main		N/A







Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE E-X. Land equipment icons - Continued.

DESCRIPTION	ICON	REMARKS
Single Rocket Launcher – Heavy Type: Entity Subtype Entity/Entity Type: Weapon/Weapon System/Single Rocket Launcher Symbol Set: 15 Value: 111**5**03 Icon Type: Main		N/A
Multiple Rocket Launcher Type: Entity Type Entity: Weapon/Weapon System Symbol Set: 15 Value: 11**16**00 Icon Type: Main		N/A
Multiple Rocket Launcher – Light Type: Entity Subtype Entity/Entity Type: Weapon/Weapon System/Multiple Rocket Launcher Symbol Set: 15 Value: 1116**01** Icon Type: Main		N/A
Multiple Rocket Launcher – Medium Type: Entity Subtype Entity/Entity Type: Weapon/Weapon System/Multiple Rocket Launcher Symbol Set: 15 Value: 1116**02** Icon Type: Main		N/A
Multiple Rocket Launcher – Heavy Type: Entity Subtype Entity/Entity Type: Weapon/Weapon System/Multiple Rocket Launcher Symbol Set: 15 Value: 1116**03** Icon Type: Main		N/A
Antitank Rocket Launcher Type: Entity Type Entity: Weapon/Weapon System Symbol Set: 15 Value: 11**17**00 Icon Type: Main		N/A







Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE E-X. Land equipment icons - Continued.

DESCRIPTION	ICON	REMARKS
Antitank Rocket Launcher – Light Type: Entity Subtype Entity/Entity Type: Weapon/Weapon System/Antitank Rocket Launcher Symbol Set: 15 Value: 111**701** Icon Type: Main		N/A
Antitank Rocket Launcher – Medium Type: Entity Subtype Entity/Entity Type: Weapon/Weapon System/Antitank Rocket Launcher Symbol Set: 15 Value: 111**702** Icon Type: Main		N/A
Antitank Rocket Launcher – Heavy Type: Entity Subtype Entity/Entity Type: Weapon/Weapon System/Antitank Rocket Launcher Symbol Set: 15 Value: 111**703** Icon Type: Main		N/A
Nonlethal Weapon Type: Entity Type Entity: Weapon/Weapon System Symbol Set: 15 Value: 11**18**00 Icon Type: Main		N/A
Taser Nonlethal Type: Entity Type Entity: Weapon/Weapon System Symbol Set: 15 Value: 11**19**00 Icon Type: Main		N/A
Water Cannon Nonlethal Type: Entity Type Entity: Weapon/Weapon System Symbol Set: 15 Value: 11**20**00 Icon Type: Main		N/A
Vehicle Type: Entity Symbol Set: 15 Value: **12**0000	N/A	Reserved for hierarchical purposes.








Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE E-X. Land equipment icons - Continued.

DESCRIPTION	ICON	REMARKS
Armored Type: Entity Type Entity: Vehicle Symbol Set: 15 Value: 12**01**00	N/A	Reserved for hierarchical purposes.
Armored Fighting Vehicle Type: Entity Subtype Entity/Entity Type: Vehicle/Armored Symbol Set: 15 Value: 1201**01** Icon Type: Main		N/A
Armored Fighting Vehicle Command and Control Type: Entity Subtype Entity/Entity Type: Vehicle/Armored Symbol Set: 15 Value: 1201**02** Icon Type: Main		N/A
Armored Personnel Carrier Type: Entity Subtype Entity/Entity Type: Vehicle/Armored Symbol Set: 15 Value: 1201**03** Icon Type: Main		N/A
Armored Personnel Carrier Ambulance Type: Entity Subtype Entity/Entity Type: Vehicle/Armored Symbol Set: 15 Value: 1201**04** Icon Type: Main		N/A
Armored Protected Vehicle Type: Entity Subtype Entity/Entity Type: Vehicle/Armored Symbol Set: 15 Value: 1201**05** Icon Type: Main		N/A
Armored Personnel Carrier, Recovery Type: Entity Subtype Entity/Entity Type: Vehicle/Armored Symbol Set: 15 Value: 1201**08** Icon Type: Main		N/A







Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE E-X. Land equipment icons - Continued.

DESCRIPTION	ICON	REMARKS
Combat Service Support Vehicle Type: Entity Subtype Entity/Entity Type: Vehicle/Armored Symbol Set: 15 Value: 120109 Icon Type: Main		N/A
Light Armored Reconnaissance Type: Entity Subtype Entity/Entity Type: Vehicle/Armored Symbol Set: 15 Value: 120111 Icon Type: Full Frame		The gray circle is not to be drawn. It is shown here only as a reference to position and proportion of the icon within the frame.
Tank Type: Entity Type Entity: Vehicle Symbol Set: 15 Value: 120200 Icon Type: Main		N/A
Tank – Light Type: Entity Subtype Entity/Entity Type: Vehicle/Tank Symbol Set: 15 Value: 120201 Icon Type: Full Octagon		N/A
Tank – Medium Type: Entity Subtype Entity/Entity Type: Vehicle/Tank Symbol Set: 15 Value: 120202 Icon Type: Full Octagon		N/A
Tank – Heavy Type: Entity Subtype Entity/Entity Type: Vehicle/Tank Symbol Set: 15 Value: 120203 Icon Type: Full Octagon		N/A
Engineer Vehicle and Equipment Type: Entity Symbol Set: 15 Value: 130000 Icon Type: Full Octagon		N/A





Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE E-X. Land equipment icons - Continued.

DESCRIPTION	ICON	REMARKS
Bridge Type: Entity Type Entity: Engineer Vehicle and Equipment Symbol Set: 15 Value: 13**01**00 Icon Type: Main		N/A
Fixed Bridge Type: Entity Type Entity: Engineer Vehicle and Equipment Symbol Set: 15 Value: 13**03**00 Icon Type: Full Octagon		N/A
Floating Bridge Type: Entity Type Entity: Engineer Vehicle and Equipment Symbol Set: 15 Value: 13**04**00 Icon Type: Full Octagon		N/A
Folding Girder Bridge Type: Entity Type Entity: Engineer Vehicle and Equipment Symbol Set: 15 Value: 13**05**00 Icon Type: Main		N/A
Hollow Deck Bridge Type: Entity Type Entity: Engineer Vehicle and Equipment Symbol Set: 15 Value: 13**06**00 Icon Type: Main		N/A
Drill Type: Entity Type Entity: Engineer Vehicle and Equipment Symbol Set: 15 Value: 13**07**00 Icon Type: Full Octagon		N/A
Drill Mounted on Utility Vehicle Type: Entity Subtype Entity/Entity Type: Engineer Vehicle and Equipment/Drill Symbol Set: 15 Value: 1307**01** Icon Type: Full Octagon		N/A





Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE E-X. Land equipment icons - Continued.

DESCRIPTION	ICON	REMARKS
Earthmover Type: Entity Type Entity: Engineer Vehicle and Equipment Symbol Set: 15 Value: 13**08**00 Icon Type: Full Octagon		N/A
Multifunctional Earthmover/Digger Type: Entity Subtype Entity/Entity Type: Engineer Vehicle and Equipment/ Earthmover Symbol Set: 15 Value: 1308**01** Icon Type: Full Octagon		N/A
Mine Clearing Equipment Type: Entity Type Entity: Engineer Vehicle and Equipment Symbol Set: 15 Value: 13**09**00 Icon Type: Full Octagon		N/A
Mine Clearing Equipment on Tank Chassis Type: Entity Subtype Entity/Entity Type: Engineer Vehicle and Equipment/ Mine Clearing Equipment Symbol Set: 15 Value: 1309**02** Icon Type: Full Octagon		N/A
Assault Breacher Vehicle (ABV) with Combat Dozer Blade Type: Entity Subtype Entity/Entity Type: Engineer Vehicle and Equipment/ Mine Clearing Equipment Symbol Set: 15 Value: 1309**03** Icon Type: Full Octagon		N/A
Medium Capability Equipment Type: Entity Subtype Entity/Entity Type: Engineer Vehicle and Equipment/ Mine Clearing Equipment Symbol Set: 15 Value: 1309**04** Icon Type: Full Octagon		N/A







Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE E-X. Land equipment icons - Continued.

DESCRIPTION	ICON	REMARKS
Heavy Capability Equipment Type: Entity Subtype Entity/Entity Type: Engineer Vehicle and Equipment/ Mine Clearing Equipment Symbol Set: 15 Value: 1309**05** Icon Type: Full Octagon		N/A
Mine Laying Equipment Type: Entity Type Entity: Engineer Vehicle and Equipment Symbol Set: 15 Value: 13**10**00 Icon Type: Full Octagon		N/A
Mine Laying Equipment on Utility Vehicle Type: Entity Subtype Entity/Entity Type: Engineer Vehicle and Equipment/ Mine Laying Equipment Symbol Set: 15 Value: 1310**01** Icon Type: Full Octagon		N/A
Armored Carrier with Volcano Type: Entity Subtype Entity/Entity Type: Engineer Vehicle and Equipment/ Mine Laying Equipment Symbol Set: 15 Value: 1310**02** Icon Type: Full Octagon		N/A
Truck Mounted with Volcano Type: Entity Subtype Entity/Entity Type: Engineer Vehicle and Equipment/ Mine Laying Equipment Symbol Set: 15 Value: 1310**03** Icon Type: Full Octagon		N/A
Dozer, Tank Chassis Type: Entity Type Entity/Entity Type: Engineer Vehicle and Equipment Symbol Set: 15 Value: 13**11**00 Icon Type: Full Octagon		N/A







Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE E-X. Land equipment icons - Continued.

DESCRIPTION	ICON	REMARKS
Dozer, Armored Type: Entity Subtype Entity/Entity Type: Engineer Vehicle and Equipment/Dozer Symbol Set: 15 Value: 1311**01** Icon Type: Full Octagon		N/A
Armored Assault Type: Entity Type Entity/Entity Type: Engineer Vehicle and Equipment Symbol Set: 15 Value: 13**12**00 Icon Type: Full Octagon		N/A
Armored Engineer Recon Vehicle (AERV) Type: Entity Type Entity/Entity Type: Engineer Vehicle and Equipment Symbol Set: 15 Value: 13**13**00 Icon Type: Full Octagon		N/A
Backhoe Type: Entity Type Entity/Entity Type: Engineer Vehicle and Equipment Symbol Set: 15 Value: 13**14**00 Icon Type: Full Octagon		N/A
Construction Vehicle Type: Entity Type Entity/Entity Type: Engineer Vehicle and Equipment Symbol Set: 15 Value: 13**15**00 Icon Type: Full Octagon		N/A
Ferry Transporter Type: Entity Type Entity/Entity Type: Engineer Vehicle and Equipment Symbol Set: 15 Value: 13**16**00 Icon Type: Full Octagon		N/A








Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE E-X. Land equipment icons - Continued.

DESCRIPTION	ICON	REMARKS
Utility Vehicle Type: Entity Symbol Set: 15 Value: **14**0000	N/A	Reserved for hierarchical purposes.
Vehicle (Generic) Type: Entity Type Entity: Utility Vehicle Symbol Set: 15 Value: 14**01**00 Icon Type: Main		N/A
Medical Type: Entity Type Entity: Utility Vehicle Symbol Set: 15 Value: 14**02**00 Icon Type: Full Octagon		N/A
Mobile Emergency Physician Type: Entity Type Entity: Utility Vehicle Symbol Set: 15 Value: 14**04**00 Icon Type: Full Octagon		N/A
Bus Type: Entity Type Entity: Utility Vehicle Symbol Set: 15 Value: 14**05**00 Icon Type: Full Octagon		N/A
Semi-Trailer and Truck Type: Entity Type Entity: Utility Vehicle Symbol Set: 15 Value: 14**06**00 Icon Type: Full Octagon		N/A
Semi-Trailer and Truck - Light Type: Entity Subtype Entity/Entity Type: Utility Vehicle/Semi-Trailer and Truck Symbol Set: 15 Value: 1406**01** Icon Type: Full Octagon		N/A




Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE E-X. Land equipment icons - Continued.

DESCRIPTION	ICON	REMARKS
Semi-Trailer and Truck - Medium Type: Entity Subtype Entity/Entity Type: Utility Vehicle/Semi-Trailer and Truck Symbol Set: 15 Value: 1406**02** Icon Type: Full Octagon		N/A
Semi-Trailer and Truck - Heavy Type: Entity Subtype Entity/Entity Type: Utility Vehicle/Semi-Trailer and Truck Symbol Set: 15 Value: 1406**03** Icon Type: Full Octagon		N/A
Limited Cross-Country Truck Type: Entity Type Entity: Utility Vehicle Symbol Set: 15 Value: 1**40**700 Icon Type: Full Octagon		N/A
Cross-Country Truck Type: Entity Type Entity: Utility Vehicle Symbol Set: 15 Value: 1**40**800 Icon Type: Full Octagon		N/A
Petroleum, Oil and Lubricant Type: Entity Type Entity: Utility Vehicle Symbol Set: 15 Value: 1**40**900 Icon Type: Full Octagon		N/A
Water Type: Entity Type Entity: Utility Vehicle Symbol Set: 15 Value: 1**41**000 Icon Type: Full Octagon		N/A
Amphibious Utility Wheeled Vehicle Type: Entity Type Entity: Utility Vehicle Symbol Set: 15 Value: 1**41**100 Icon Type: Full Octagon		N/A








Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE E-X. Land equipment icons - Continued.

DESCRIPTION	ICON	REMARKS
Tow Truck Type: Entity Type Entity: Utility Vehicle Symbol Set: 15 Value: 14**12**00 Icon Type: Full Octagon		N/A
Tow Truck, Light Type: Entity Subtype Entity/ Entity Type: Utility Vehicle/Tow Truck Symbol Set: 15 Value: 1412**01** Icon Type: Full Octagon		N/A
Tow Truck, Heavy Type: Entity Subtype Entity/ Entity Type: Utility Vehicle/Tow Truck Symbol Set: 15 Value: 1412**02** Icon Type: Full Octagon		N/A
Train Type: Entity Symbol Set: 15 Value: **15**0000	N/A	Reserved for hierarchical purposes.
Locomotive Type: Entity Type Entity: Train Symbol Set: 15 Value: 15**01**00 Icon Type: Full Octagon		N/A
Civilian Vehicle Type: Entity Symbol Set: 15 Value: **16**0000	N/A	Reserved for hierarchical purposes.
Automobile Type: Entity Type Entity: Civilian Vehicle Symbol Set: 15 Value: 16**01**00 Icon Type: Main		N/A


Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE E-X. Land equipment icons - Continued.

DESCRIPTION	ICON	REMARKS
Open-Bed Truck Type: Entity Type Entity: Civilian Vehicle Symbol Set: 15 Value: 16**02**00 Icon Type: Main		N/A
Multiple Passenger Vehicle Type: Entity Type Entity: Civilian Vehicle Symbol Set: 15 Value: 16**03**00 Icon Type: Main		N/A
Utility Vehicle Type: Entity Type Entity: Civilian Vehicle Symbol Set: 15 Value: 16**04**00 Icon Type: Main		N/A
Jeep Type Vehicle Type: Entity Type Entity: Civilian Vehicle Symbol Set: 15 Value: 16**05**00 Icon Type: Main		N/A
Tractor Trailer Truck with Box Type: Entity Type Entity: Civilian Vehicle Symbol Set: 15 Value: 16**06**00 Icon Type: Main		N/A
Tractor Trailer Truck with Flatbed Trailer Type: Entity Type Entity: Civilian Vehicle Symbol Set: 15 Value: 16**07**00 Icon Type: Main		N/A
Known Insurgent Vehicle Type: Entity Type Entity: Civilian Vehicle Symbol Set: 15 Value: 16**08**00 Icon Type: Main		N/A




Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE E-X. Land equipment icons - Continued.

DESCRIPTION	ICON	REMARKS
Drug Vehicle Type: Entity Type Entity: Civilian Vehicle Symbol Set: 15 Value: 16**09**00 Icon Type: Main		N/A
Law Enforcement Type: Entity Symbol Set: 15 Value: 170000 Icon Type: Full Octagon		N/A
Bureau of Alcohol, Tobacco, Firearms and Explosives (ATF) (Department Of Justice) Type: Entity Type Entity: Law Enforcement Symbol Set: 15 Value: 17**01**00 Icon Type: Main		N/A
Border Patrol Type: Entity Type Entity: Law Enforcement Symbol Set: 15 Value: 17**02**00 Icon Type: Full Octagon		N/A
Customs Service Type: Entity Type Entity: Law Enforcement Symbol Set: 15 Value: 17**03**00 Icon Type: Full Octagon		N/A
Drug Enforcement Administration (DEA) Type: Entity Type Entity: Law Enforcement Symbol Set: 15 Value: 17**04**00 Icon Type: Main		N/A
Department of Justice (DOJ) Type: Entity Type Entity/Entity Type: Law Enforcement Symbol Set: 15 Value: 17**05**00 Icon Type: Full Octagon		N/A


Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE E-X. Land equipment icons - Continued.

DESCRIPTION	ICON	REMARKS
Federal Bureau of Investigation (FBI) Type: Entity Type Entity/Entity Type Law Enforcement Symbol Set: 15 Value: 17**06**00 Icon Type: Main		N/A
Police Type: Entity Type Entity/Entity Type: Law Enforcement Symbol Set: 15 Value: 17**07**00 Icon Type: Main		N/A
United States Secret Service (USSS) Type: Entity Type Entity/Entity Type: Law Enforcement Symbol Set: 15 Value: 17**08**00 Icon Type: Main		N/A
Transportation Security Administration (TSA) Type: Entity Type Entity/Entity Type: Law Enforcement Symbol Set: 15 Value: 17**09**00 Icon Type: Main		N/A
US Coast Guard Type: Entity Type Entity/Entity Type: Law Enforcement Symbol Set: 15 Value: 17**10**00 Icon Type: Full Octagon		N/A
US Marshals Service Type: Entity Type Entity/Entity Type: Law Enforcement Symbol Set: 15 Value: 17**11**00 Icon Type: Full Octagon		N/A
Pack Animals Type: Entity Symbol Set: 15 Value: **18**0000 Icon Type: Full Octagon		N/A





Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE E-X. Land equipment icons - Continued.

DESCRIPTION	ICON	REMARKS
Missile Support Type: Entity Symbol Set: 15 Value: **19**0000 Icon Type: Full Octagon		N/A
Transloader Type: Entity Type Entity: Missile Support Symbol Set: 15 Value: 19**01**00 Icon Type: Full Octagon		N/A
Transporter Type: Entity Type Entity: Missile Support Symbol Set: 15 Value: 19**02**00 Icon Type: Full Octagon		N/A
Crane/Loading Device Type: Entity Type Entity: Missile Support Symbol Set: 15 Value: 19**03**00 Icon Type: Full Octagon		N/A
Propellant Transporter Type: Entity Type Entity: Missile Support Symbol Set: 15 Value: 19**04**00 Icon Type: Full Octagon		N/A
Warhead Transporter Type: Entity Type Entity: Missile Support Symbol Set: 15 Value: 19**05**00 Icon Type: Full Octagon		N/A
Other Equipment Type: Entity Symbol Set: 15 Value: **20**0000	N/A	Reserved for hierarchical purposes.




Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE E-X. Land equipment icons - Continued.

DESCRIPTION	ICON	REMARKS
Antennae Type: Entity Type Entity: Other Equipment Symbol Set: 15 Value: 20**01**00 Icon Type: Full Octagon		N/A
Bomb Type: Entity Type Entity: Other Equipment Symbol Set: 15 Value: 20**02**00 Icon Type: Full Octagon		N/A
Booby Trap Type: Entity Type Entity: Other Equipment Symbol Set: 15 Value: 20**03**00 Icon Type: Full Octagon		N/A
CBRN Equipment Type: Entity Type Entity: Other Equipment Symbol Set: 15 Value: 20**04**00 Icon Type: Full Octagon		N/A
Computer System Type: Entity Type Entity: Other Equipment Symbol Set: 15 Value: 20**05**00 Icon Type: Full Octagon		N/A
Command Launch Equipment (CLE) Type: Entity Type Entity: Other Equipment Symbol Set: 15 Value: 20**06**00 Icon Type: Main		N/A
Generator Set Type: Entity Type Entity: Other Equipment Symbol Set: 15 Value: 20**07**00 Icon Type: Full Octagon		N/A





Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE E-X. Land equipment icons - Continued.

DESCRIPTION	ICON	REMARKS
Ground-Based Midcourse Defense (GMD) Fire Control (GFC) Center Type: Entity Type Entity: Other Equipment Symbol Set: 15 Value: 20**08**00 Icon Type: Main		N/A
In-Flight Interceptor Communications System (IFICS) Data Terminal (IDT) Type: Entity Type Entity: Other Equipment Symbol Set: 15 Value: 20**09**00 Icon Type: Main		N/A
Directed Energy Type: Entity Type Entity: Other Equipment Symbol Set: 15 Value: 20**10**00 Icon Type: Main Icon		N/A
Military Information Support Operations (MISO) Type: Entity Type Entity: Other Equipment Symbol Set: 15 Value: 20**11**00 Icon Type: Full Octagon		N/A
Sustainment Shipments Type: Entity Type Entity: Other Equipment Symbol Set: 15 Value: 20**12**00 Icon Type: Main		N/A
Tent Type: Entity Type Entity: Other Equipment Symbol Set: 15 Value: 20**13**00 Icon Type: Full Octagon	N/A	Reserved for hierarchical purposes.





Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE E-X. Land equipment icons - Continued.

DESCRIPTION	ICON	REMARKS
Civilian Type: Entity Subtype Entity: Other Equipment/Tent Symbol Set: 15 Value: 2013**01** Icon Type: Main		N/A
Military Type: Entity Subtype Entity: Other Equipment/Tent Symbol Set: 15 Value: 2013**02** Icon Type: Main		N/A
Unit Deployment Shipments Type: Entity Type Entity: Other Equipment Symbol Set: 15 Value: 20**14**00 Icon Type: Main		N/A
Emergency Medical Operation Type: Entity Type Entity: Other Equipment Symbol Set: 15 Value: 20**15**00 Icon Type: Full Octagon		N/A
Land Mines Type: Entity Symbol Set: 15 Value: **21**0000	N/A	Reserved for hierarchical purposes.
Land Mine Type: Entity Type Entity: Land Mine Symbol Set: 15 Value: 21**01**00 Icon Type: Full Octagon		N/A
Antipersonnel Land Mine (APL) Type: Entity Type Entity: Land Mine Symbol Set: 15 Value: 21**02**00 Icon Type: Full Octagon		N/A



Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE E-X. Land equipment icons - Continued.

DESCRIPTION	ICON	REMARKS
Antitank Mine Type: Entity Type Entity: Land Mine Symbol Set: 15 Value: 21**03**00 Icon Type: Full Octagon		N/A
Improvised Explosive Device (IED) Type: Entity Type Entity: Land Mine Symbol Set: 15 Value: 21**04**00 Icon Type: Main		Used with hostile standard identity only
Less Than Lethal Type: Entity Type Entity: Land Mine Symbol Set: 15 Value: 21**05**00 Icon Type: Full Octagon		N/A
Sensors Type: Entity Symbol Set: 15 Value: **22**0000	N/A	Reserved for hierarchical purposes.
Sensor Type: Entity Type Symbol Set: 15 Value: 22**01**00 Icon Type: Main		N/A
Sensor Emplaced Type: Entity Type Entity: Sensor Symbol Set: 15 Value: 22**02**00 Icon Type: Main+1		N/A
Radar Type: Entity Type Entity: Sensor Symbol Set: 15 Value: 22**03**00 Icon Type: Full Octagon		N/A



Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE E-X. Land equipment icons - Continued.

DESCRIPTION	ICON	REMARKS
Emergency Operation Type: Entity Symbol Set: 15 Value: **23**0000 Icon Type: Full Octagon		N/A
Fire Fighting/Fire Protection Type: Entity Type Entity/Entity Type: Emergency Operation Symbol Set: 15 Value: 23**02**00 Icon Type: Main		N/A
Manual Track Type: Entity (Local) Symbol Set: 15 Value:**24**0000 Icon Type: Full Octagon		N/A
Rotary Wing Type: Entity Symbol Set: 15 Value:**25**0000 Icon Type: Main		N/A





E.8.3 Land equipment sector 1 modifiers. Land equipment sector 1 modifiers denote sensor type or capability category. Table E-XI lists land equipment sector 1 modifiers and illustrates their placement within the bounding octagon. Additional sector 1 modifiers, where required, are included in table B-I and are accessed using the modifier extension flag.

TABLE E-XI. Land equipment sector 1 modifiers.

DESCRIPTION	CATEGORY	MODIFIER	REMARKS
Biological Symbol Set: 15 Value: 01	Sensor Type		N/A
Early Warning Radar Symbol Set: 15 Value: 03	Sensor Type		N/A


Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE E-XI. Land equipment sector 1 modifiers - Continued.

DESCRIPTION	CATEGORY	MODIFIER	REMARKS
Intrusion Symbol Set: 15 Value: 04	Sensor Type		N/A
Upgraded Early Warning Radar Symbol Set: 15 Value: 07	Sensor Type		N/A
Multi-Purpose Blade Symbol Set: 15 Value: 12	Capability		N/A
Tank-Width Mine Plow Symbol Set: 15 Value: 13	Capability		N/A

E.8.4 Land equipment sector 2 modifiers. Land equipment sector 2 modifiers denote capability category. Table E-XII lists the land equipment sector 2 modifiers and illustrates their placement within the bounding octagon. Additional sector 2 modifiers, where required, are included in table B-II and are accessed using the modifier extension flag.

TABLE E-XII. Land equipment sector 2 modifiers.

DESCRIPTION	CATEGORY	MODIFIER	REMARKS
Tractor Trailer Symbol Set: 15 Value: 06	Capability		N/A

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

E.9 LAND INSTALLATION SYMBOLS

E.9.1 Land installation symbols. This section includes the lists of icons and modifiers for building land installation symbols. Figure E-5 shows the placement of land installation symbol amplifiers around the friend symbol frame. Table E-XIII provides descriptions and formats of each amplifier.




FIGURE E-5. Placement of land installation symbol amplifiers.

TABLE E-XIII. Descriptions and formats of land installation symbol amplifiers.

FIELD	FIELD TITLE	DESCRIPTION	FORMAT
A	Symbol Icon	The innermost part of a symbol, comprised of an icon and optional modifiers, that represents a joint military object (see 5.3.4).	
G	Staff Comments	A text amplifier for units, equipment, and installations; content is implementation specific.	
H	Additional Information	A text amplifier for units, equipment, and installations; content is implementation specific.	

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE E-XIII. Descriptions and formats of land installation symbol amplifiers - Continued.

FIELD	FIELD TITLE	DESCRIPTION	FORMAT
J	Evaluation Rating	A text amplifier for units, equipment and installations that consists of a single-letter reliability rating and a single digit credibility rating: (See ATP 2-33.4). **Reliability Ratings:** A-completely reliable B-usually reliable C-fairly reliable D-not usually reliable E-unreliable F-reliability cannot be judged. **Credibility Ratings:** 1-confirmed by other sources 2-probably true 3-possibly true 4-doubtfully true 5-improbable 6-truth cannot be judged.	
K	Combat Effectiveness	A text amplifier for units and installations that indicates effectiveness. **The entries are:** fully operational (FO) substantially operational (SO) marginally operational (MO) not operational (NO) unknown (UNK)	
M	Higher Formation	A text amplifier for units that indicates number or title of higher echelon command (Corps is designated by Roman numerals).	
P	IFF/SIF	A text amplifier displaying one or more IFF/SIF Identification modes and codes. **Display priority:** Mode 5, Mode S, Mode 2, Mode 3.	Mode 2 Prefix: 2:#### **Example**: 2:1234
S	Headquarters Staff Indicator	A graphic amplifier for units, installations and stability operations that identifies them as a headquarters (see figure 14).	
T	Unique Designation (Track Number)	A text amplifier for units, equipment and installations that uniquely identifies a particular symbol or track number.	Prefix = TN:##### **Example**: TN:13579

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.





TABLE E-XIII. Descriptions and formats of land installation symbol amplifiers - Continued.

FIELD	FIELD TITLE	DESCRIPTION	FORMAT
W	Date-Time Group (DTG)	An alphanumeric designator for displaying a date-time group (DDHHMMSSZMONYYYY) or "O/O" for on order. The date-time group is composed of a group of six numeric digits with a time zone suffix and the standardized three-letter abbreviation for the month followed by four digits representing the year. The first pair of digits represents the day; the second pair, the hour; the third pair, the minutes. For automated systems, two digits may be added before the time zone suffix and after the minutes to designate seconds (see 5.3.7.8).	
X	Altitude/Depth	A text amplifier for units, equipment and installations that displays either altitude, flight level, depth for submerged objects, or height of equipment or structures on the ground. See 5.3.7.6 for content.	Measurement units shall be displayed within the string **Examples**: 1500MSL FL150
Y	Location	A text amplifier for units, equipment and installations that displays a symbol's location in degrees, minutes and decimal minutes (or in MGRS, GARS, or other applicable display formats).	3317.0921N 04412.6332E 38SMB2649083145
AE	Equipment Teardown Time	Equipment teardown time in minutes.	
AL	Operational Condition	A graphic amplifier for equipment or installations that indicates operational condition or capacity.	Operational Condition amplifier, if used, shall be comprised of only one color. **Ex. Aircraft**: Red - damaged, Green – fully capable **Ex: Missile**: Red – imminent threat, Green – no threat
AQ	Guarded Unit	During ballistic missile defense, some tracks are designated as guarded by a particular unit.	
AS	Country	A three-letter code that indicates the country of origin of the organization (US systems shall use GENC).	

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.






E.9.2 Land installation icons. Table E-XIV depicts land installation icons.

TABLE E-XIV. Land installation icons.

DESCRIPTION	ICON	REMARKS
Installation Type: Entity Symbol Set: 20 Value: **11**0000	N/A	Reserved for hierarchical purposes.
Aircraft Production/Assembly Type: Entity Type Entity: Installation Symbol Set: 20 Value: 110100 Icon Type: Main		N/A
Ammunition and Explosives Production Type: Entity Type Entity: Installation Symbol Set: 20 Value: 110200 Icon Type: Full Octagon		N/A
Ammunition Cache Type: Entity Type Entity: Installation Symbol Set: 20 Value: 11**03**00 Icon Type: Full Frame		The gray box is not to be drawn. It is shown here only as a reference to position and proportion of the icon within the frame.
Armament Production Type: Entity Type Entity: Installation Symbol Set: 20 Value: 110400 Icon Type: Full Octagon		N/A
Black List Location Type: Entity Type Entity: Installation Symbol Set: 20 Value: 11**05**00 Icon Type: Main		N/A
Chemical, Biological, Radiological and Nuclear (CBRN) Type: Entity Type Entity: Installation Symbol Set: 20 Value: 11**06**00 Icon Type: Main		N/A






Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE E-XIV. Land installation icons - Continued.

DESCRIPTION	ICON	REMARKS
Engineer Equipment Production Type: Entity Type Entity: Installation Symbol Set: 20 Value: 110700 Icon Type: Full Octagon		N/A
Bridge Type: Entity Type Entity: Installation/Engineer Equipment Production Symbol Set: 20 Value: 110701 Icon Type: Main		N/A
Equipment Manufacture Type: Entity Type Entity: Installation Symbol Set: 20 Value: 110800 Icon Type: Full Octagon		N/A
Government Leadership Type: Entity Type Entity: Installation Symbol Set: 20 Value: 110900 Icon Type: Main		N/A
Gray List Location Type: Entity Type Entity: Installation Symbol Set: 20 Value: 11**1**000 Icon Type: Main		N/A
Mass Grave Site Type: Entity Type Entity: Installation Symbol Set: 20 Value: 11**1**100 Icon Type: Main		N/A
Materiel Type: Entity Type Entity: Installation Symbol Set: 20 Value: 111200 Icon Type: Full Frame		The gray box is not to be drawn. It is shown here only as a reference to position and proportion of the icon within the frame.



Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE E-XIV. Land installation icons - Continued.

DESCRIPTION	ICON	REMARKS
Mine Type: Entity Type Entity: Installation Symbol Set: 20 Value: 11**13**00 Icon Type: Main		N/A
Missile and Space System Production Type: Entity Type Entity: Installation Symbol Set: 20 Value: 111400 Icon Type: Full Octagon		N/A
Nuclear (Non CBRN Defense) Type: Entity Type Entity: Installation Symbol Set: 20 Value: 11**15**00 Icon Type: Main		N/A
Printed Media Type: Entity Type Entity: Installation Symbol Set: 20 Value: 11**16**00 Icon Type: Main		N/A
Safe House Type: Entity Type Entity: Installation Symbol Set: 20 Value: 11**17**00 Icon Type: Main		N/A
White List Location Type: Entity Type Entity: Installation Symbol Set: 20 Value: 11**18**00 Icon Type: Main		N/A
Tented Camp Type: Entity Type Entity: Installation Symbol Set: 20 Value: 11**19**00 Icon Type: Full Octagon		N/A


Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE E-XIV. Land installation icons - Continued.

DESCRIPTION	ICON	REMARKS
Displaced Persons/Refugee/Evacuees Camp Type: Entity Subtype Entity/Entity Type: Installation/Tented Camp Symbol Set: 20 Value: 111**01** Icon Type: Full Octagon		N/A
Training Camp Type: Entity Subtype Entity/Entity Type: Installation/Tented Camp Symbol Set: 20 Value: 111**02** Icon Type: Full Octagon		N/A
Warehouse/Storage Facility Type: Entity Type Entity: Installation Symbol Set: 20 Value: 11**20**00 Icon Type: Full Octagon		N/A
Grenade Type: Entity Subtype Entity/Entity Type: Installation/Warehouse/Storage Facility Symbol Set: 20 Value: 1120**01** Icon Type: Main		N/A
Law Enforcement Type: Entity Type Entity: Installation Symbol Set: 20 Value: 11**21**00 Icon Type: Full Octagon		N/A
Bureau of Alcohol, Tobacco, Firearms and Explosives (ATF) (Department of Justice) Type: Entity Subtype Entity/Entity Type: Installation/Law Enforcement Symbol Set: 20 Value: 1121**01** Icon Type: Main		N/A

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE E-XIV. Land installation icons - Continued.

DESCRIPTION	ICON	REMARKS
Border Patrol Type: Entity Subtype Entity/Entity Type: Installation/Law Enforcement Symbol Set: 20 Value: 1121**02** Icon Type: Full Octagon		N/A
Customs Service Type: Entity Subtype Entity/Entity Type: Installation/Law Enforcement Symbol Set: 20 Value: 1121**03** Icon Type: Full Octagon		N/A
Drug Enforcement Agency (DEA) Type: Entity Subtype Entity/Entity Type: Installation/Law Enforcement Symbol Set: 20 Value: 1121**04** Icon Type: Main		N/A
Department of Justice (DOJ) Type: Entity Subtype Entity/Entity Type: Installation/Law Enforcement Symbol Set: 20 Value: 1121**05** Icon Type: Full Octagon		N/A
Federal Bureau of Investigation (FBI) Type: Entity Subtype Entity/Entity Type: Installation/Law Enforcement Symbol Set: 20 Value: 1121**06** Icon Type: Main		N/A
Police Type: Entity Subtype Entity/Entity Type: Installation/Law Enforcement Symbol Set: 20 Value: 1121**07** Icon Type: Main		N/A



Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE E-XIV. Land installation icons - Continued.

DESCRIPTION	ICON	REMARKS
Prison Type: Entity Subtype Entity/Entity Type: Installation/Law Enforcement Symbol Set: 20 Value: 1121**08** Icon Type: Full Octagon		N/A
United States Secret Service (USSS) Type: Entity Subtype Entity/Entity Type: Installation/Law Enforcement Symbol Set: 20 Value: 1121**09** Icon Type: Main		N/A
Transportation Security Administration (TSA) Type: Entity Subtype Entity/Entity Type: Installation/Law Enforcement Symbol Set: 20 Value: 1121**10** Icon Type: Main		N/A
US Coast Guard Type: Entity Subtype Entity/Entity Type: Installation/Law Enforcement Symbol Set: 20 Value: 1121**11** Icon Type: Full Octagon		N/A
US Marshals Service Type: Entity Subtype Entity/Entity Type: Installation/Law Enforcement Symbol Set: 20 Value: 1121**12** Icon Type: Full Octagon		N/A
Emergency Operation Type: Entity Type Entity: Installation Symbol Set: 20 Value: 11**22**00 Icon Type: Full Octagon		N/A





Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE E-XIV. Land installation icons - Continued.

DESCRIPTION	ICON	REMARKS
Fire Station Type: Entity Subtype Entity/Entity Type: Installation/Emergency Operation Symbol Set: 20 Value: 1122**01** Icon Type: Full Octagon		N/A
Emergency Medical Operation Type: Entity Type Entity: Installation/Emergency Operation Symbol Set: 20 Value: 1122**02** Icon Type: Full Octagon		N/A
Home/House Type: Entity Type Entity/Entity Type: Installation Symbol Set: 20 Value: 11**23**00 Icon Type: Main		N/A
Infrastructure Type: Entity Symbol Set: 20 Value: **12**0000	N/A	Reserved for hierarchical purposes.
Agriculture and Food Type: Entity Type Entity: Infrastructure Symbol Set: 20 Value: 12**01**00 Icon Type: Full Octagon		N/A
Agricultural Laboratory Type: Entity Subtype Entity/Entity Type: Infrastructure/Agricultural and Food Symbol Set: 20 Value: 120**01** Icon Type: Full Octagon		N/A
Animal Feedlot Type: Entity Subtype Entity/Entity Type: Infrastructure/Agricultural and Food Symbol Set: 20 Value: 120**02** Icon Type: Full Octagon		N/A

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE E-XIV. Land installation icons - Continued.

DESCRIPTION	ICON	REMARKS
Commercial Food Distribution Center Type: Entity Subtype Entity/Entity Type: Infrastructure/Agricultural and Food Symbol Set: 20 Value: 120103 Icon Type: Full Frame		The gray box is not to be drawn. It is shown here only as a reference to position and proportion of the icon within the frame.
Farm/Ranch Type: Entity Subtype Entity/Entity Type: Infrastructure/Agricultural and Food Symbol Set: 20 Value: 120104 Icon Type: Full Octagon		N/A
Food Distribution Type: Entity Subtype Entity/Entity Type: Infrastructure/Agricultural and Food Symbol Set: 20 Value: 120105 Icon Type: Full Frame		The gray box is not to be drawn. It is shown here only as a reference to position and proportion of the icon within the frame.
Food Production Center Type: Entity Subtype Entity/Entity Type: Infrastructure/ Agricultural and Food Symbol Set: 20 Value: 120106 Icon Type: Full Frame		The gray box is not to be drawn. It is shown here only as a reference to position and proportion of the icon within the frame.
Food Retail Type: Entity Subtype Entity/Entity Type: Infrastructure/Agricultural and Food Symbol Set: 20 Value: 120107 Icon Type: Full Frame		The gray box is not to be drawn. It is shown here only as a reference to position and proportion of the icon within the frame.
Grain Storage Type: Entity Subtype Entity/Entity Type: Infrastructure/Agricultural and Food Symbol Set: 20 Value: 120108 Icon Type: Full Octagon		N/A




Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE E-XIV. Land installation icons - Continued.

DESCRIPTION	ICON	REMARKS
Banking Finance and Insurance Type: Entity Type Entity: Infrastructure Symbol Set: 20 Value: 12**02**00 Icon Type: Full Octagon		N/A
Atm Type: Entity Subtype Entity/Entity Type: Infrastructure/Banking Finance and Insurance Symbol Set: 20 Value: 1202**01** Icon Type: Full Octagon		N/A
Bank Type: Entity Subtype Entity/Entity Type: Infrastructure/Banking Finance and Insurance Symbol Set: 20 Value: 1202**02** Icon Type: Full Octagon		N/A
Bullion Storage Type: Entity Subtype Entity/Entity Type: Infrastructure/ Banking Finance and Insurance Symbol Set: 20 Value: 1202**03** Icon Type: Full Octagon		N/A
Economic Infrastructure Asset Type: Entity Subtype Entity/Entity Type: Infrastructure/Banking Finance and Insurance Symbol Set: 20 Value: 1202**04** Icon Type: Main		N/A
Federal Reserve Bank Type: Entity Subtype Entity/Entity Type: Infrastructure/Banking Finance and Insurance Symbol Set: 20 Value: 1202**05** Icon Type: Full Octagon		N/A


Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE E-XIV. Land installation icons - Continued.

DESCRIPTION	ICON	REMARKS
Financial Exchange Type: Entity Subtype Entity/Entity Type: Infrastructure/Banking Finance and Insurance Symbol Set: 20 Value: 120**206** Icon Type: Full Octagon		N/A
Financial Services, Other Type: Entity Subtype Entity/Entity Type: Infrastructure/Banking Finance and Insurance Symbol Set: 20 Value: 120**207** Icon Type: Full Octagon		N/A
Commercial Type: Entity Type Entity: Infrastructure Symbol Set: 20 Value: 12**03**00 Icon Type: Full Octagon		N/A
Chemical Plant Type: Entity Subtype Entity/Entity Type: Infrastructure/Commercial Symbol Set: 20 Value: 12030**1** Icon Type: Full Octagon		N/A
Firearms Manufacturer Type: Entity Subtype Entity/Entity Type: Infrastructure/Commercial Symbol Set: 20 Value: 12030**2** Icon Type: Full Octagon		N/A
Firearms Retailer Type: Entity Subtype Entity/Entity Type: Infrastructure/Commercial Symbol Set: 20 Value: 12030**3** Icon Type: Full Octagon		N/A
Hazardous Material Production Type: Entity Subtype Entity/Entity Type: Infrastructure/Commercial Symbol Set: 20 Value: 120304 Icon Type: Full Octagon		N/A





Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE E-XIV. Land installation icons - Continued.

DESCRIPTION	ICON	REMARKS
Hazardous Material Storage Type: Entity Subtype Entity/Entity Type: Infrastructure/Commercial Symbol Set: 20 Value: 120**05** Icon Type: Full Octagon		N/A
Industrial Site Type: Entity Subtype Entity/Entity Type: Infrastructure/Commercial Symbol Set: 20 Value: 120**06** Icon Type: Full Octagon		N/A
Landfill Type: Entity Subtype Entity/Entity Type: Infrastructure/Commercial Symbol Set: 20 Value: 120**07** Icon Type: Full Octagon		N/A
Pharmaceutical Manufacturer Type: Entity Subtype Entity/Entity Type: Infrastructure/Commercial Symbol Set: 20 Value: 120**08** Icon Type: Full Octagon		N/A
Contaminated Hazardous Waste Site Type: Entity Subtype Entity/Entity Type: Infrastructure/Commercial Symbol Set: 20 Value: 120**09** Icon Type: Full Octagon		N/A
Toxic Release Inventory Type: Entity Subtype Entity/Entity Type: Infrastructure/Commercial Symbol Set: 20 Value: 120**10** Icon Type: Full Octagon		N/A
Educational Facilities Type: Entity Type Entity: Infrastructure Symbol Set: 20 Value: 12**04**00 Icon Type: Full Octagon		N/A




Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE E-XIV. Land installation icons - Continued.

DESCRIPTION	ICON	REMARKS
College/University Type: Entity Subtype Entity/Entity Type: Infrastructure/Educational Facilities Symbol Set: 20 Value: 120**401** Icon Type: Full Octagon		N/A
School Type: Entity Subtype Entity/Entity Type: Infrastructure/Educational Facilities Symbol Set: 20 Value: 120**402** Icon Type: Full Octagon		N/A
Energy Facilities Type: Entity Type Entity: Infrastructure Symbol Set: 20 Value: 12**05**00 Icon Type: Full Octagon		N/A
Electric Power Type: Entity Subtype Entity/Entity Type: Infrastructure/Energy Facilities Symbol Set: 20 Value: 120**501** Icon Type: Main		N/A
Generation Station Type: Entity Subtype Entity/Entity Type: Infrastructure/Energy Facilities Symbol Set: 20 Value: 120**502** Icon Type: Full Octagon		N/A
Natural Gas Facility Type: Entity Subtype Entity/Entity Type: Infrastructure/Energy Facilities Symbol Set: 20 Value: 120**503** Icon Type: Full Octagon		N/A





Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE E-XIV. Land installation icons - Continued.

DESCRIPTION	ICON	REMARKS
Petroleum Facility Type: Entity Subtype Entity/Entity Type: Infrastructure/Energy Facilities Symbol Set: 20 Value: 120**05** Icon Type: Full Octagon		N/A
Propane Facility Type: Entity Subtype Entity/Entity Type: Infrastructure/Energy Facilities Symbol Set: 20 Value: 120**06** Icon Type: Full Octagon		N/A
Government Site Type: Entity Type Entity: Infrastructure Symbol Set: 20 Value: 12**06**00 Icon Type: Full Octagon		N/A
Medical Infrastructure Type: Entity Type Entity: Infrastructure Symbol Set: 20 Value: 12**07**00	N/A	Reserved for hierarchical purposes.
Medical Type: Entity Subtype Entity/Entity Type: Infrastructure/Medical Infrastructure Symbol Set: 20 Value: 1207**01** Icon Type: Full Frame		The gray box is not to be drawn. It is shown here only as a reference to position and proportion of the icon within the frame.
Medical Treatment Facility (Hospital) Type: Entity Type Entity/Entity Type: Infrastructure/Medical Infrastructure Symbol Set: 20 Value: 1207**02** Icon Type: Full Frame		The gray box is not to be drawn. It is shown here only as a reference to position and proportion of the icon within the frame.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE E-XIV. Land installation icons - Continued.

DESCRIPTION	ICON	REMARKS
Military Type: Entity Type Entity: Infrastructure Symbol Set: 20 Value: 12**08**00 Icon Type: Full Octagon		N/A
Military Armory Type: Entity Subtype Entity/Entity Type: Infrastructure/Military Symbol Set: 20 Value: 1208**01** Icon Type: Full Octagon		N/A
Military Base Type: Entity Subtype Entity/Entity Type: Infrastructure/Military Symbol Set: 20 Value: 1208**02** Icon Type: Full Octagon		N/A
Airport/Air Base Type: Entity Subtype Entity/Entity Type: Infrastructure/Military Symbol Set: 20 Value: 1208**03** Icon Type: Main		N/A
Postal Service Type: Entity Type Entity: Infrastructure Symbol Set: 20 Value: 12**09**00 Icon Type: Full Octagon		N/A
Postal Distribution Center Type: Entity Subtype Entity/Entity Type: Infrastructure/Postal Service Symbol Set: 20 Value: 1209**01** Icon Type: Full Octagon		N/A
Post Office Type: Entity Subtype Entity/Entity Type: Infrastructure/Postal Service Symbol Set: 20 Value: 1209**02** Icon Type: Full Octagon		N/A



Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE E-XIV. Land installation icons - Continued.

DESCRIPTION	ICON	REMARKS
Public Venues Type: Entity Type Entity: Infrastructure Symbol Set: 20 Value: 12**10**00 Icon Type: Full Octagon		N/A
Enclosed Facility (Public Venue) Type: Entity Subtype Entity/Entity Type: Infrastructure/Public Venues Symbol Set: 20 Value: 1210**01** Icon Type: Full Octagon		N/A
Open Facility (Public Venue) Type: Entity Subtype Entity/Entity Type: Infrastructure/Public Venues Symbol Set: 20 Value: 1210**02** Icon Type: Full Octagon		N/A
Recreational Area Type: Entity Subtype Entity/Entity Type: Infrastructure/Public Venues Symbol Set: 20 Value: 1210**03** Icon Type: Full Octagon		N/A
Religious Type: Entity Subtype Entity/Entity Type: Infrastructure/Public Venues Symbol Set: 20 Value: 1210**04** Icon Type: Full Octagon		N/A
Special Needs Type: Entity Type Entity: Infrastructure Symbol Set: 20 Value: 12**11**00 Icon Type: Full Octagon		N/A





Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE E-XIV. Land installation icons - Continued.

DESCRIPTION	ICON	REMARKS
Adult Day Care Type: Entity Subtype Entity/Entity Type: Infrastructure/Special Needs Symbol Set: 20 Value: 1211**01** Icon Type: Full Octagon		N/A
Child Day Care Type: Entity Subtype Entity/Entity Type: Infrastructure/Special Needs Symbol Set: 20 Value: 1211**02** Icon Type: Full Octagon		N/A
Elder Care Type: Entity Subtype Entity/Entity Type: Infrastructure/Special Needs Symbol Set: 20 Value: 1211**03** Icon Type: Full Octagon		N/A
Telecommunications Type: Entity Type Entity: Infrastructure Symbol Set: 20 Value: 12**12**00 Icon Type: Full Octagon		N/A
Broadcast Transmitter Antennae Type: Entity Subtype Entity/Entity Type: Infrastructure/Telecommunications Symbol Set: 20 Value: 1212**01** Icon Type: Full Octagon		N/A
Telecommunications (Civilian) Type: Entity Subtype Entity/Entity Type: Infrastructure/Telecommunications Symbol Set: 20 Value: 1212**02** Icon Type: Main		N/A





Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE E-XIV. Land installation icons - Continued.

DESCRIPTION	ICON	REMARKS
Telecommunications Tower Type: Entity Subtype Entity/Entity Type: Infrastructure/Telecommunications Symbol Set: 20 Value: 1212**03** Icon Type: Full Octagon		N/A
Transportation Type: Entity Type Entity: Infrastructure Symbol Set: 20 Value: 12**13**00 Icon Type: Full Octagon		N/A
Aerial Port of Debarkation/Aerial Port of Embarkation Type: Entity Subtype Entity/Entity Type: Infrastructure/Transportation Symbol Set: 20 Value: 1213**01** Icon Type: Main+1		N/A
Air Traffic Control Facility Type: Entity Subtype Entity/Entity Type: Infrastructure/Transportation Symbol Set: 20 Value: 1213**02** Icon Type: Main		N/A
Bus Station Type: Entity Subtype Entity/Entity Type: Infrastructure/Transportation Symbol Set: 20 Value: 1213**03** Icon Type: Full Octagon		N/A
Ferry Terminal Type: Entity Subtype Entity/Entity Type: Infrastructure/Transportation Symbol Set: 20 Value: 1213**04** Icon Type: Full Octagon		N/A


Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE E-XIV. Land installation icons - Continued.

DESCRIPTION	ICON	REMARKS
Helicopter Landing Site Type: Entity Subtype Entity/Entity Type: Infrastructure/Transportation Symbol Set: 20 Value: 121305 Icon Type: Full Octagon		N/A
Maintenance Facility Type: Entity Subtype Entity/Entity Type: Infrastructure/Transportation Symbol Set: 20 Value: 121306 Icon Type: Full Octagon		N/A
Railhead/Railroad Station Type: Entity Subtype Entity/Entity Type: Infrastructure/Transportation Symbol Set: 20 Value: 121307 Icon Type: Main+1		N/A
Rest Stop Type: Entity Subtype Entity/Entity Type: Infrastructure/Transportation Symbol Set: 20 Value: 121308 Icon Type: Full Octagon		N/A
Sea Port/Naval Base Type: Entity Subtype Entity/Entity Type: Infrastructure/Transportation Symbol Set: 20 Value: 121309 Icon Type: Main+1		N/A
Ship Yard Type: Entity Subtype Entity/Entity Type: Infrastructure/Transportation Symbol Set: 20 Value: 121310 Icon Type: Main+1		N/A



Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE E-XIV. Land installation icons - Continued.

DESCRIPTION	ICON	REMARKS
Toll Facility Type: Entity Subtype Entity/Entity Type: Infrastructure/Transportation Symbol Set: 20 Value: 121311 Icon Type: Full Octagon		N/A
Traffic Inspection Facility Type: Entity Subtype Entity/Entity Type: Infrastructure/Transportation Symbol Set: 20 Value: 121312 Icon Type: Full Octagon		N/A
Tunnel Type: Entity Subtype Entity/Entity Type: Infrastructure/Transportation Symbol Set: 20 Value: 121313 Icon Type: Full Octagon		N/A
Water Supply Type: Entity Type Entity: Infrastructure Symbol Set: 20 Value: 121400 Icon Type: Full Octagon	N/A	Reserved for hierarchical purposes.
Control Valve Type: Entity Subtype Entity/Entity Type: Infrastructure/Water Supply Symbol Set: 20 Value: 121401 Icon Type: Full Octagon		N/A
Dam Type: Entity Subtype Entity/Entity Type: Infrastructure/Water Supply Symbol Set: 20 Value: 121402 Icon Type: Full Octagon		N/A



Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE E-XIV. Land installation icons - Continued.

DESCRIPTION	ICON	REMARKS
Discharge Outfall Type: Entity Subtype Entity/Entity Type: Infrastructure/Water Supply Symbol Set: 20 Value: 121**403** Icon Type: Full Octagon		N/A
Ground Water Well Type: Entity Subtype Entity/Entity Type: Infrastructure/Water Supply Symbol Set: 20 Value: 121**404** Icon Type: Full Octagon		N/A
Pumping Station Type: Entity Subtype Entity/Entity Type: Infrastructure/Water Supply Symbol Set: 20 Value: 121**405** Icon Type: Full Octagon		N/A
Reservoir Type: Entity Subtype Entity/Entity Type: Infrastructure/Water Supply Symbol Set: 20 Value: 121**406** Icon Type: Full Octagon		N/A
Storage Tower Type: Entity Subtype Entity/Entity Type: Infrastructure/Water Supply Symbol Set: 20 Value: 121**407** Icon Type: Full Octagon		N/A
Surface Water Intake Type: Entity Subtype Entity/Entity Type: Infrastructure/Water Supply Symbol Set: 20 Value: 121**408** Icon Type: Full Octagon		N/A



Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE E-XIV. Land installation icons - Continued.

DESCRIPTION	ICON	REMARKS
Wastewater Treatment Facility Type: Entity Subtype Entity/Entity Type: Infrastructure/Water Supply Symbol Set: 20 Value: 121**409** Icon Type: Full Octagon		N/A
Water Type: Entity Subtype Entity/Entity Type: Infrastructure/Water Supply Symbol Set: 20 Value: 121**410** Icon Type: Main		N/A
Water Treatment Type: Entity Subtype Entity/Entity Type: Infrastructure/Water Supply Symbol Set: 20 Value: 121**411** Icon Type: Main		N/A






E.9.3 Land installation sector 1 modifiers. Land installation sector 1 modifiers denote CBRN type, electric power type and civilian telecommunications type categories. Table E-XV lists land installation sector 1 modifiers and illustrates their placement within the bounding octagon. Additional sector 1 modifiers, where required, are included in table B-I and are accessed using the modifier extension flag.

TABLE E-XV. Land installation sector 1 modifiers.

DESCRIPTION	CATEGORY	MODIFIER	REMARKS
Biological Symbol Set: 20 Value: 01	CBRN		N/A
Coal Symbol Set: 20 Value: 06	Electric Power Type		Used with Electric Power only



Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE E-XV. Land installation sector 1 modifiers - Continued.

DESCRIPTION	CATEGORY	MODIFIER	REMARKS
Geothermal Symbol Set: 20 Value: 07	Electric Power Type		Used with Electric Power only
Hydroelectric Symbol Set: 20 Value: 08	Electric Power Type		Used with Electric Power only
Natural Gas Symbol Set: 20 Value: 09	Electric Power Type		Used with Electric Power only
Civilian Telephone Symbol Set: 20 Value: 12	Civilian Telecommunications Type		N/A
Civilian Television Symbol Set: 20 Value: 13	Civilian Telecommunications Type		N/A








E.9.4 Land installation sector 2 modifiers. Land installation sector 2 modifiers denote capability category. Table E-XVI lists the land installation sector 2 modifiers and illustrates their placement within the bounding octagon. Additional sector 2 modifiers, where required, are included in table B-II and are accessed using the modifier extension flag.

TABLE E-XVI. Land installation sector 2 modifiers.

DESCRIPTION	CATEGORY	MODIFIER	REMARKS
Biological Warfare Production Symbol Set: 20 Value: 01	Capability		N/A
Chemical Warfare Production Symbol Set: 20 Value: 02	Capability		N/A

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE E-XVI. Land installation sector 2 modifiers - Continued.

DESCRIPTION	CATEGORY	MODIFIER	REMARKS
Nuclear Warfare Production Symbol Set: 20 Value: 03	Capability		N/A
Radiological Warfare Production Symbol Set: 20 Value: 04	Capability		N/A
Atomic Energy Reactor Symbol Set: 20 Value: 05	Capability		N/A
Nuclear Material Production Symbol Set: 20 Value: 06	Capability		N/A
Nuclear Material Storage Symbol Set: 20 Value: 07	Capability		N/A
Weapons Grade Production Symbol Set: 20 Value: 08	Capability		N/A
Transportation Symbol Set: 20 Value: 10	Capability		N/A

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

DISMOUNTED INDIVIDUAL SYMBOLS

F.1 SCOPE

F.1.1 Scope. This appendix addresses symbols that support land symbols representing individuals in the C2 domain. The tables in this appendix present the icons and modifiers for dismounted soldiers and other individuals. The information contained herein is intended for compliance.

F.2 APPLICABLE DOCUMENTS

Specific documents in 2.2 of this standard apply to this appendix.

F.3 DEFINITIONS

The definitions in section 3 of this standard apply to this appendix.

F.4 GENERAL REQUIREMENTS

F.4.1 Organization. This appendix contains technical specifications, a symbol coding scheme, a symbology hierarchy and land symbology.

F.5 DETAILED REQUIREMENTS

F.5.1 Technical specifications. Composition, construction and display of symbols are explained in the detailed requirements section of the standard.

F.5.2 Symbol identification coding scheme. A symbol identification code (SIDC) is a numeric string that may be used to provide the unique identifier necessary to display or exchange symbol information between MIL-STD-2525 compliant systems. Refer to Appendix A for SIDC positions and descriptions.

F.5.3 Composition of land symbols. A standard method for constructing symbols is presented. Refer to 5.3.10 for an explanation of symbol composition. Figure F-1 shows an example of a dismounted individual symbol.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.







FIGURE F-1. Dismounted individual symbol components.

F.5.3.1 Symbol building process. Table F-I depicts the symbol building process for dismounted individual symbols. The process is identical for icons and modifiers requiring the horizontal bounding octagon.

TABLE F-I. Dismounted individual symbol building process.

STEP	DESCRIPTION	EXAMPLE
1.	Choose the frame that matches the dimension of the object from the appropriate column in tables I, II, or III and standard identity (table A-II). In this example, the dimension is dismounted individual and the standard identity is friend The example depicts a “friendly individual.”	
2.	Choose an icon for the symbol. In this example, the icon is “rifle”. The example depicts a “friendly individual with rifle.”	
3.	If required, choose a modifier to depict an additional characteristic of the icon. In this example, the modifier is “squad,” a sector 1 modifier. The example depicts a “friendly individual with rifle from a squad.”	
4.	If required, choose another modifier to depict an additional characteristic of the icon. In this example, the modifier is “rank code OR-7,” a sector 2 modifier. The example depicts a “friendly individual, rank OR-7, with rifle from a squad.”	

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE F-I. Dismounted individual symbol building process - Continued.

STEP	DESCRIPTION	EXAMPLE
5.	If required, choose a leadership indicator amplifier. In this example, the leadership indicator amplifier is “Leader”. The example depicts a “friendly individual, rank OR-7, squad leader with rifle.”	
6.	The finished symbol will appear as shown in the example.	

F.5.3.2 Icons and modifiers. All icons shall be placed within the main sector of the bounding octagon (see Table F-I). When depicted, modifiers shall be placed in sectors 1 or 2 as appropriate (see Table F-I). Only one modifier may be placed in each sector at a given time. Multiple modifiers in the same position are prohibited due to legibility concerns.

F.5.3.3 Amplifiers.

F.5.3.3.1 Text amplifiers. The purpose of the static text amplifiers described in this appendix is to standardize the display of additional alphanumerical information on identity, movement and location and capabilities. See 5.3.7 for more information on amplifiers. Figure B-3 shows the placement of space symbol amplifiers around the friend symbol frame. Table B-II provides descriptions and formats of each amplifier.

F.5.3.3.2 Graphic amplifiers. Graphic amplifiers can be static, located in a fixed position in relation to a track’s symbol, or dynamic and move about the symbol based on the track’s characteristics. See 5.3.7 for more information on amplifiers, including examples of dynamic amplifiers.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.




FIGURE F-2. Placement of dismounted individual symbol amplifiers.

TABLE F-II. Descriptions and formats of dismounted individual symbol amplifiers.

FIELD	FIELD TITLE	DESCRIPTION	FORMAT
A	Symbol Icon	The innermost part of a symbol, comprised of an icon and optional modifiers, that represents a joint military object (see 5.3.4).	
G	Staff Comments	A text amplifier for units, equipment, and installations; content is implementation specific.	
H	Additional Information	A text amplifier for units, equipment, and installations; content is implementation specific.	
J	Evaluation Rating	A text amplifier for units, equipment, installations, and dismounted individuals that consists of a single-letter reliability rating and a single digit credibility rating: (See ATP 2-33.4). **Reliability Ratings:** A-completely reliable B-usually reliable C-fairly reliable D-not usually reliable E-unreliable F-reliability cannot be judged. **Credibility Ratings:** 1-confirmed by other sources 2-probably true 3-possibly true 4-doubtfully true 5-improbable 6-truth cannot be judged.	

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE F-II. Descriptions and formats of dismounted individual symbol amplifiers - Continued.

FIELD	FIELD TITLE	DESCRIPTION	FORMAT
K	Combat Effectiveness	A text amplifier for units, installations, and dismounted individuals that indicates effectiveness. **The entries are:** fully operational (FO) substantially operational (SO) marginally operational (MO) not operational (NO) unknown (UNK)	
M	Higher Formation	A text amplifier for units that indicates number or title of higher echelon command (Corps is designated by Roman numerals).	
P	IFF/SIF	A text amplifier displaying one or more IFF/SIF Identification modes and codes. **Display priority**: Mode 5, Mode S, Mode 2, Mode 3.	Mode 2 Prefix: 2:#### **Example**: 2:1234
Q	Direction of Movement Indicator	A graphic amplifier that identifies the direction of movement or intended movement of an object (see 5.3.7.9 and figure 14 in the base document).	
S2	Offset Location Indicator	A graphic amplifier used to indicate the offset or precise location of a single point symbol (see 5.3.7.5, 5.3.13, and figure 14).	
T	Unique Designation (Track Number)	A text amplifier for units, equipment and installations that uniquely identifies a particular symbol or track number.	Prefix = TN:##### **Example**: TN:13579
V	Type	A text amplifier for equipment that indicates types of equipment.	
W	Date-Time Group (DTG)	An alphanumeric designator for displaying a date-time group. The date-time group is composed of a group of six numeric digits with a time zone suffix and the standardized three-letter abbreviation for the month followed by four digits representing the year. The first pair of digits represents the day; the second pair, the hour; the third pair, the minutes. For automated systems, two digits may be added before the time zone suffix and after the minutes to designate seconds (see 5.3.7.8).	(DDHHMMSSZMONYYYY) or "O/O" for on order
X	Altitude/Depth	A text amplifier for units, equipment and installations that displays either altitude, flight level, depth for submerged objects, or height of equipment or structures on the ground. See 5.3.7.6 for content.	Measurement units shall be displayed within the string. **Examples**: 1500MSL FL150

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE F-II. Descriptions and formats of dismounted individual symbol amplifiers - Continued.

FIELD	FIELD TITLE	DESCRIPTION	FORMAT
Y	Location	A text amplifier for units, equipment and installations that displays a symbol's location in degrees, minutes and decimal minutes (or in MGRS, GARS, or other applicable display formats).	3317.0921N 04412.6332E 38SMB2649083145
Z	Speed	A text amplifier for units and equipment that displays velocity (see 5.3.7.7).	
AF	Common Identifier	Example: "Marine" for service affiliation.	
AS	Country	A three-letter code that indicates the country of origin of the organization (US systems shall use GENC).	

F.6 DISMOUNTED INDIVIDUAL SYMBOLS

F.6.1 Dismounted individual symbols. This section includes the lists of icons and modifiers for building dismounted individual symbols.





F.6.2 Dismounted individual icons. Table F-III depicts dismounted individual icons.

TABLE F-III. Dismounted individuals.

DESCRIPTION	ICON	REMARKS
Military Type: Entity Symbol Set: 27 Value: **11**0000	N/A	Reserved for hierarchical purposes.
Activity/Task Type: Entity Type Entity: Military Symbol Set: 27 Value: 11**02**00	N/A	Reserved for hierarchical purposes.
Explosive Ordnance Disposal (EOD) Type: Entity Subtype Entity/Entity Type: Military/Activity/Task Symbol Set: 27 Value: 11020**1** Icon Type: Main		N/A






Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE F-III. Dismounted individuals - Continued.

DESCRIPTION	ICON	REMARKS
Field Artillery Observer Type: Entity Subtype Entity/Entity Type: Military/Activity/Task Symbol Set: 27 Value: 110**02** Icon Type: Main		N/A
Joint Fire Support Type: Entity Subtype Entity/Entity Type: Military/Activity/Task Symbol Set: 27 Value: 110**03** Icon Type: Main		N/A
Liaison Type: Entity Subtype Entity/Entity Type: Military/Activity/Task Symbol Set: 27 Value: 110**04** Icon Type: Main		N/A
Messenger Type: Entity Subtype Entity/Entity Type: Military/Activity/Task Symbol Set: 27 Value: 110**05** Icon Type: Main		N/A
Military Police Type: Entity Subtype Entity/Entity Type: Military/Activity/Task Symbol Set: 27 Value: 110**06** Icon Type: Main		N/A
Observer Type: Entity Subtype Entity/Entity Type: Military/Activity/Task Symbol Set: 27 Value: 110**07** Icon Type: Main		N/A
Security Type: Entity Subtype Entity/Entity Type: Military/Activity/Task Symbol Set: 27 Value: 110208 Icon Type: Main		N/A






Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE F-III. Dismounted individuals - Continued.

DESCRIPTION	ICON	REMARKS
Sniper Type: Entity Subtype Entity/Entity Type: Military/Activity/Task Symbol Set: 27 Value: 110**09** Icon Type: Main		N/A
Special Operations Forces Type: Entity Subtype Entity/Entity Type: Military/Activity/Task Symbol Set: 27 Value: 110**10** Icon Type: Main		N/A
Designated Marksman Type: Entity Subtype Entity/Entity Type: Military/Activity/Task Symbol Set: 27 Value: 110**11** Icon Type: Main		N/A
Medic Type: Entity Subtype Entity/Entity Type: Military/Activity/Task Symbol Set: 27 Value: 110**12** Icon Type: Main		N/A
Signaler Type: Entity Subtype Entity/Entity Type: Military/Activity/Task Symbol Set: 27 Value: 110**13** Icon Type: Main		N/A
Reconnaissance Type: Entity Subtype Entity/Entity Type: Military/Activity/Task Symbol Set: 27 Value: 110**14** Icon Type: Main		N/A
Infantry Type: Entity Subtype Entity/Entity Type: Military/Activity/Task Symbol Set: 27 Value: 110**15** Icon Type: Main		N/A








Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE F-III. Dismounted individuals - Continued.

DESCRIPTION	ICON	REMARKS
Close Protection Type: Entity Subtype Entity/Entity Type: Military/Activity/Task Symbol Set: 27 Value: 110**216** Icon Type: Main		N/A
Crowd and Riot Control Type: Entity Subtype Entity/Entity Type: Military/Activity/Task Symbol Set: 27 Value: 110**217** Icon Type: Main		N/A
Special Weapons and Tactics (SWAT) Type: Entity Subtype Entity/Entity Type: Military/Activity/Task Symbol Set: 27 Value: 110**218** Icon Type: Main		N/A
Demolition Type: Entity Subtype Entity/Entity Type: Military/Activity/Task Symbol Set: 27 Value: 110**219** Icon Type: Main		N/A
Commander (CDR) Type: Entity Subtype Entity/Entity Type: Military/Activity/Task Symbol Set: 27 Value: 110**220** Icon Type: Main		N/A
Second in Command (SIC) Type: Entity Subtype Entity/Entity Type: Military/Activity/Task Symbol Set: 27 Value: 110**221** Icon Type: Main		N/A
Lethal Weapons Type: Entity Type Entity: Military Symbol Set: 27 Value: 11**03**00	N/A	Reserved for hierarchical purposes.








Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE F-III. Dismounted individuals - Continued.

DESCRIPTION	ICON	REMARKS
Rifle Type: Entity Subtype Entity/Entity Type: Military/Lethal Weapons Symbol Set: 27 Value: 110301 Icon Type: Main		N/A
Single Shot Rifle Type: Entity Subtype Entity/Entity Type: Military/Lethal Weapons Symbol Set: 27 Value: 110302 Icon Type: Main		N/A
Semiautomatic Rifle Type: Entity Subtype Entity/Entity Type: Military/Lethal Weapons Symbol Set: 27 Value: 110303 Icon Type: Main		N/A
Automatic Rifle Type: Entity Subtype Entity/Entity Type: Military/Lethal Weapons Symbol Set: 27 Value: 110304 Icon Type: Main		N/A
Machine Gun Type: Entity Subtype Entity/Entity Type: Military/Lethal Weapons Symbol Set: 27 Value: 110305 Icon Type: Main		N/A
Machine Gun – Light Type: Entity Subtype Entity/Entity Type: Military/Lethal Weapons Symbol Set: 27 Value: 110306 Icon Type: Main		N/A
Machine Gun – Medium Type: Entity Subtype Entity/Entity Type: Military/Lethal Weapons Symbol Set: 27 Value: 110307 Icon Type: Main		N/A






Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE F-III. Dismounted individuals - Continued.

DESCRIPTION	ICON	REMARKS
Machine Gun – Heavy Type: Entity Subtype Entity/Entity Type: Military/Lethal Weapons Symbol Set: 27 Value: 110308 Icon Type: Main		N/A
Grenade Launcher Type: Entity Subtype Entity/Entity Type: Military/Lethal Weapons Symbol Set: 27 Value: 110309 Icon Type: Main		N/A
Grenade Launcher – Light Type: Entity Subtype Entity/Entity Type: Military/Lethal Weapons Symbol Set: 27 Value: 110310 Icon Type: Main		N/A
Grenade Launcher – Medium Type: Entity Subtype Entity/Entity Type: Military/Lethal Weapons Symbol Set: 27 Value: 110311 Icon Type: Main		N/A
Grenade Launcher – Heavy Type: Entity Subtype Entity/Entity Type: Military/Lethal Weapons Symbol Set: 27 Value: 110312 Icon Type: Main		N/A
Flame Thrower Type: Entity Subtype Entity/Entity Type: Military/Lethal Weapons Symbol Set: 27 Value: 110313 Icon Type: Main		N/A
Mortar Type: Entity Subtype Entity/Entity Type: Military/Lethal Weapons Symbol Set: 27 Value: 110314 Icon Type: Main		N/A

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.








TABLE F-III. Dismounted individuals - Continued.

DESCRIPTION	ICON	REMARKS
Single Rocket Launcher Type: Entity Subtype Entity/Entity Type: Military/Lethal Weapons Symbol Set: 27 Value: 1103**15** Icon Type: Main		N/A
Antitank Rocket Launcher Type: Entity Subtype Entity/Entity Type: Military/Lethal Weapons Symbol Set: 27 Value: 1103**16** Icon Type: Main		N/A
Nonlethal Weapons Type: Entity Type Entity: Military Symbol Set: 27 Value: 11**04**00	N/A	Reserved for hierarchical purposes.
Nonlethal Weapon Type: Entity Subtype Entity/Entity Type: Military/Nonlethal Weapons Symbol Set: 27 Value: 1104**01** Icon Type: Main		N/A
Nonlethal Grenade Launcher Type: Entity Subtype Entity/Entity Type: Military/Nonlethal Weapons Symbol Set: 27 Value: 1104**02** Icon Type: Main		N/A
Taser Type: Entity Subtype Entity/Entity Type: Military/Nonlethal Weapons Symbol Set: 27 Value: 1104**03** Icon Type: Main		N/A

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.









F.6.3 Dismounted individual sector 1 modifiers. Dismounted individual sector 1 modifiers capability category. Table F-IV lists dismounted individual sector 1 modifiers and illustrates their placement within the bounding octagon. Additional sector 1 modifiers, where required, are included in table B-I and are accessed using the modifier extension flag.

TABLE F-IV. Dismounted individual sector 1 modifiers.

DESCRIPTION	CATEGORY	MODIFIER	REMARKS
Non-Governmental Organization Member Symbol Set: 27 Value: 07	Capability		N/A
Field Artillery Observer Symbol Set: 27 Value: 11	Capability		N/A
Joint Fire Support Symbol Set: 27 Value: 12	Capability		N/A
Liaison Symbol Set: 27 Value: 13	Capability		N/A
Messenger Symbol Set: 27 Value: 14	Capability		N/A
Military Police Symbol Set: 27 Value: 15	Capability		N/A
Observer Symbol Set: 27 Value: 16	Capability		N/A
Designated Marksman Symbol Set: 27 Value: 17	Capability		N/A

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE F-IV. Dismounted individual sector 1 modifiers - Continued.









DESCRIPTION	CATEGORY	MODIFIER	REMARKS
Signaler Symbol Set: 27 Value: 20	Capability		N/A
Reconnaissance **Symbol Set**: 27 Value: 21	Capability		N/A
Infantry Symbol Set: 27 Value: 22			N/A
Commander (CDR) Symbol Set: 27 Value: 23			N/A
Second in Command (SIC) Symbol Set: 27 Value: 24			N/A
Demolition Symbol Set: 27 Value: 25	Capability		N/A
Police Symbol Set: 27 Value: 26	Capability		N/A
Below icons are usually accompanied by leadership amplifier or a functional staff area modifier in Sector 2. Indicates the echelon at which the individual fulfils a specific role (Platoon Commander, Battalion J3, etc.).			
INDIVIDUAL Symbol Set: 27 Value: 46			N/A

F.6.4 Dismounted individual sector 2 modifiers. Dismounted individual sector 2 modifiers capability category. Table F-V lists dismounted individual sector 2 modifiers and

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.













illustrates their placement within the bounding octagon. Additional sector 2 modifiers, where required, are included in table B-II and are accessed using the modifier extension flag.

TABLE F-V. Dismounted individual sector 2 modifiers.

DESCRIPTION	CATEGORY	MODIFIER	REMARKS
Video Imagery (Combat Camera) Symbol Set: 27 Value: 03	Capability		N/A
Functional Staff Area J1 Symbol Set: 27 Value: 04	Command Level		N/A
Functional Staff Area J2 Symbol Set: 27 Value: 05	Command Level		N/A
Functional Staff Area J3 Symbol Set: 27 Value: 06	Command Level		N/A
Functional Staff Area J4 Symbol Set: 27 Value: 07	Command Level		N/A
Functional Staff Area J5 Symbol Set: 27 Value: 08	Command Level		N/A
Functional Staff Area J6 Symbol Set: 27 Value: 09	Command Level		N/A
Functional Staff Area J7 Symbol Set: 27 Value: 10	Command Level		N/A













Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE F-V. Dismounted individual sector 2 modifiers- Continued.

DESCRIPTION	CATEGORY	MODIFIER	REMARKS
Functional Staff Area J8 Symbol Set: 27 Value: 11	Command Level		N/A
Functional Staff Area J9 Symbol Set: 27 Value: 12	Command Level		N/A
Officer Rank			
Rank O-1/O-2 Symbol Set Value: 27 Value: 14	Command Level		 APP-06 Version
Rank O-3 Symbol Set Value: 27 Value: 15	Command Level		 APP-06 Version
Rank O-4 Symbol Set Value: 27 Value: 16	Command Level		 APP-06 Version
Rank O-5 Symbol Set Value: 27 Value: 17	Command Level		 APP-06 Version
Rank O-6 Symbol Set Value: 27 Value: 18	Command Level		 APP-06 Version













Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE F-V. Dismounted individual sector 2 modifiers- Continued.

DESCRIPTION	CATEGORY	MODIFIER	REMARKS
Rank O-7 Symbol Set Value: 27 Value: 19	Command Level		 APP-06 Version
Rank O -8 Symbol Set Value: 27 Value: 20	Command Level		 APP-06 Version
Rank O-9 Symbol Set Value: 27 Value: 21	Command Level		 APP-06 Version
Rank O-10 Symbol Set Value: 27 Value: 22	Command Level		 APP-06 Version
Rank O-11 Symbol Set Value: 27 Value: 23	Command Level		 APP-06 Version
Enlisted Rank			
Rank E-1 Symbol Set Value: 27 Value: 25	Command Level		 APP-06 Version










Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE F-V. Dismounted individual sector 2 modifiers- Continued.

DESCRIPTION	CATEGORY	MODIFIER	REMARKS
Rank E-2 Symbol Set Value: 27 Value: 26	Command Level		 APP-06 Version
Rank E-3 Symbol Set Value: 27 Value: 27	Command Level		 APP-06 Version
Rank E-4 Symbol Set Value: 27 Value: 28	Command Level		 APP-06 Version
Rank E-5 Symbol Set Value: 27 Value: 29	Command Level		 APP-06 Version
Rank E-6 Symbol Set Value: 27 Value: 30	Command Level		 APP-06 Version
Rank E-7 Symbol Set Value: 27 Value: 31	Command Level		 APP-06 Version

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE F-V. Dismounted individual sector 2 modifiers- Continued.

DESCRIPTION	CATEGORY	MODIFIER	REMARKS
Rank E-8 Symbol Set Value: 27 Value: 32	Command Level		 APP-06 Version
Rank E-9 Symbol Set Value: 27 Value: 33	Command Level		 APP-06 Version
Warrant Officer Rank			
WO-1 Symbol Set Value: 27 Value: 34	Command Level		N/A
WO-2 Symbol Set Value: 27 Value: 35	Command Level		N/A
WO-3 Symbol Set Value: 27 Value: 36	Command Level		N/A
WO-4 Symbol Set Value: 27 Value: 37	Command Level		N/A
WO-5 Symbol Set Value: 27 Value: 38	Command Level		N/A

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

PAGE INTENTIONALLY LEFT BLANK

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

SEA SURFACE SYMBOLS

G.1 SCOPE

G.1.1 Scope. This appendix addresses symbols that support sea surface units, equipment and installations in the C2 domain. The tables in this appendix present the icons and modifiers for the sea surface symbol set. The information contained herein is intended for compliance.

G.2 APPLICABLE DOCUMENTS

Specific documents in 2.2 of this standard apply to this appendix.

G.3 DEFINITIONS

The definitions in section 3 of this standard apply to this appendix.

G.4 GENERAL REQUIREMENTS

G.4.1 Organization. This appendix contains technical specifications, a symbol coding scheme, a symbology hierarchy and sea surface symbology.

G.5 DETAILED REQUIREMENTS

G.5.1 Technical specifications. Composition, construction and display of symbols are explained in the detailed requirements section of the standard.

G.5.2 Symbol identification coding scheme. A symbol identification code (SIDC) is a numeric string that may be used to provide the unique identifier necessary to display or exchange symbol information between MIL-STD-2525 compliant systems. Refer to Appendix A for SIDC positions and descriptions.

G.5.3 Composition of sea surface symbols. A standard method for constructing symbols is presented. Refer to 5.3.10 for an explanation of symbol composition. Figure G-1 shows an example of a sea surface equipment symbol.








FIGURE G-1. Sea surface symbol components.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

G.5.3.1 Symbol building process. Table G-I depicts the symbol building process for sea surface symbols. The process is identical for icons and modifiers requiring the vertical bounding octagon.

TABLE G-I. Sea surface symbol building process.

STEP	DESCRIPTION	EXAMPLE
1.	Choose the frame that matches the dimension of the object from the appropriate column in tables I, II, or III and standard identity (table A-II). In this example, the dimension is sea surface and the standard identity is friend. The example depicts a “friendly sea surface track.”	
2.	Choose an icon for the main sector of the bounding octagon. In this example, the icon is “carrier,” a sea surface entity type. The example depicts a “friendly military combatant carrier.”	
3.	If required, choose a modifier to depict an additional characteristic of the icon. In this example, the modifier is “helicopter equipped/VTOL,” a sector 1 modifier. The example depicts a “friendly military combatant carrier, helicopter equipped/VTOL.”	
4.	If required, choose a modifier to depict another characteristic of the icon. In this example, the modifier is “nuclear powered,” a sector 2 modifier. The example depicts a “friendly military combatant carrier, helicopter equipped/VTOL, nuclear powered.”	
5.	The finished symbol will appear as shown in the example.	

G.5.3.2 Icons and modifiers. All icons shall be placed within the main sector of the bounding octagon (see table G-I). When depicted, modifiers shall be placed in sectors 1 or 2 as appropriate (see table G-I). Only one modifier may be placed in each sector at a given time. Multiple modifiers in the same position are prohibited due to legibility concerns.

G.5.3.3 Amplifiers.

G.5.3.3.1 Text amplifiers. The purpose of the static text amplifiers described in this appendix is to standardize the display of additional alphanumerical information on identity, movement and location and capabilities. See 5.3.7 for more information on amplifiers. Figure G-2 shows the placement of sea surface symbol amplifiers around the friend symbol frame. Table G-II provides descriptions and formats of each amplifier.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.




FIGURE G-2. Placement of sea surface symbol amplifiers.

TABLE G-II. Descriptions and formats of sea surface symbol amplifiers.

FIELD	FIELD TITLE	DESCRIPTION	FORMAT
A	Ship/Ship Type Icon	The innermost part of a symbol, comprised of an icon and optional modifiers, that represents a joint military object (see 5.3.4).	
G	Staff Comments	A text amplifier for units, equipment, and installations; content is implementation specific.	
H	Additional Information	A text amplifier for units, equipment, and installations; content is implementation specific.	
P	Automatic Identification System (AIS)	A text amplifier displaying the maritime Automatic Identification System.	
Q	Direction of Movement Indicator	A graphic amplifier that identifies the direction of movement or intended movement of an object (see 5.3.7.9 and figure 14 in the base document).	
S2	Offset Location Indicator	A graphic amplifier used to indicate the offset or precise location of a single point symbol (see 5.3.7.5, 5.3.13, and figure 14).	
T	Unique Designation (Track Number)	A text amplifier for units, equipment and installations that uniquely identifies a particular symbol or track number.	Prefix = TN:##### Example: TN:13579
V	Type	A text amplifier for equipment that indicates types of equipment.	
Y	Location	A text amplifier for units, equipment and installations that displays a symbol's location in degrees, minutes decimal minutes, (or in MGRS, GARS, or other applicable display formats).	3317.0921N 04412.6332E 38SMB2649083145
Z	Speed	A text amplifier for CBRN, units and equipment that displays velocity (see 5.3.7.7).	

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE G-II. Descriptions and formats of sea surface symbol amplifiers - Continued.

FIELD	FIELD TITLE	DESCRIPTION	FORMAT
AG	Auxiliary Equipment Indicator	Towed sonar array indicator: A graphic amplifier for equipment that indicates the presence of a towed sonar array (see 5.3.7.10, figure 13 and table IX).	
AL	Operational Condition	A graphic amplifier for equipment or installations that indicates an operational condition or capacity.	Operational Condition amplifier, if used, shall be comprised of only one color. Ex. Aircraft: Red - damaged, Green – fully capable Ex: Missile: Red – imminent threat, Green – no threat
AO	Engagement Bar	A graphic amplifier placed immediately atop the symbol. May denote: 1) local/remote status 2) engagement status 3) weapon type.	A:BBB-CC, where A = remote/local BBB = engagement status CC = weapon asset
AQ	Guarded Unit	During ballistic missile defense, some tracks are designated as guarded by a particular unit.	The 2-character string, BG
AR	Special Designator	Special track designators, such as Non-Real Time (NRT) and Tactically Significant (SIG) tracks, are denoted here.	The 3-character strings, NRT or SIG
AS	Country	A three-letter code that indicates the country of origin of the organization (US systems shall use GENC).	

G.5.3.3.2 Graphic amplifiers. Graphic amplifiers can be static, located in a fixed position in relation to a track's symbol, or dynamic and move about the symbol based on the track's characteristics. See 5.3.7 for more information on amplifiers, including examples of dynamic amplifiers.

G.6 SEA SURFACE UNIT, EQUIPMENT AND INSTALLATION SYMBOLS



G.6.1 Sea surface unit, equipment and installation symbols. This section includes the lists of icons and modifiers for building sea surface unit, equipment and installation symbols.

G.6.2 Sea surface unit, equipment and installation icons. Table G-III depicts sea surface unit, equipment and installation icons.

In accordance with Standard Ship Designator System (STANAG 1166/APP-20), single letter codes specify the type of merchant ship, while two- and three-letter codes specify the type of military ship. For other types of civilian surface vessels, the letter codes of the icon are without a STANAG reference. Military symbols are depicted with black-filled icons, whereas civilian symbols are depicted with white-filled icons.




Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE G-III. Sea surface unit, equipment and installation icons.

DESCRIPTION	ICON	REMARKS
Military Type: Entity Symbol Set: 30 Value: **11**0000 Icon Type: Main	N/A	Reserved for hierarchical purposes.
Military Combatant Type: Entity Symbol Set: 30 Value: **12**0000 Icon Type: Main	N/A	Reserved for hierarchical purposes.
Carrier Type: Entity Type Entity: Military Combatant Symbol Set: 30 Value: 12**01**00 Icon Type: Main		N/A
Surface Combatant, Line Type: Entity Type Entity: Military Combatant Symbol Set: 30 Value: 12**02**00 Icon Type: Main		N/A
Battleship Type: Entity Subtype Entity/Entity Type: Military Combatant/Surface Combatant, Line Symbol Set: 30 Value: 120**01** Icon Type: Main		N/A
Cruiser Type: Entity Subtype Entity/Entity Type: Military Combatant/Surface Combatant, Line Symbol Set: 30 Value: 120**02** Icon Type: Main		N/A
Destroyer Type: Entity Subtype Entity/Entity Type: Military Combatant/Surface Combatant, Line Symbol Set: 30 Value: 120**03** Icon Type: Main		N/A

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE G-III. Sea surface unit, equipment and installation icons - Continued.

DESCRIPTION	ICON	REMARKS
Frigate Type: Entity Subtype Entity/Entity Type: Military Combatant/Surface Combatant, Line Symbol Set: 30 Value: 120**04** Icon Type: Main		N/A
Corvette Type: Entity Subtype Entity/Entity Type: Military Combatant/Surface Combatant, Line Symbol Set: 30 Value: 120**05** Icon Type: Main		N/A
Littoral Combatant Ship Type: Entity Subtype Entity/Entity Type: Military Combatant/Surface Combatant, Line Symbol Set: 30 Value: 120**06** Icon Type: Main		N/A
Amphibious Warfare Ship Type: Entity Type Entity: Military Combatant Symbol Set: 30 Value: 12**03**00 Icon Type: Main		N/A
Amphibious Command Ship Type: Entity Subtype Entity/Entity Type: Military Combatant/Amphibious Warfare Ship Symbol Set: 30 Value: 120**01** Icon Type: Main		N/A
Amphibious Assault, Non-Specified Type: Entity Subtype Entity/Entity Type: Military Combatant/Amphibious Warfare Ship Symbol Set: 30 Value: 120**02** Icon Type: Main		N/A


Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE G-III. Sea surface unit, equipment and installation icons - Continued.

DESCRIPTION	ICON	REMARKS
Amphibious Assault Ship, General Type: Entity Subtype Entity/Entity Type: Military Combatant/Amphibious Warfare Ship Symbol Set: 30 Value: 120**303** Icon Type: Main		N/A
Amphibious Assault Ship, Multipurpose Type: Entity Subtype Entity/Entity Type: Military Combatant/Amphibious Warfare Ship Symbol Set: 30 Value: 120**304** Icon Type: Main		N/A
Amphibious Assault Ship, Helicopter Type: Entity Subtype Entity/Entity Type: Military Combatant/Amphibious Warfare Ship Symbol Set: 30 Value: 120**305** Icon Type: Main		N/A
Amphibious Transport Dock Type: Entity Subtype Entity/Entity Type: Military Combatant/Amphibious Warfare Ship Symbol Set: 30 Value: 120**306** Icon Type: Main		N/A
Landing Ship Type: Entity Subtype Entity/Entity Type: Military Combatant/Amphibious Warfare Ship Symbol Set: 30 Value: 120**307** Icon Type: Main		N/A
Landing Craft Type: Entity Subtype Entity/Entity Type: Military Combatant/Amphibious Warfare Ship Symbol Set: 30 Value: 120**308** Icon Type: Main		N/A




Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE G-III. Sea surface unit, equipment and installation icons - Continued.

DESCRIPTION	ICON	REMARKS
Mine Warfare Ship Type: Entity Type Entity: Military Combatant Symbol Set: 30 Value: 12**04**00 Icon Type: Main		N/A
Mine Layer Type: Entity Subtype Entity/Entity Type: Military Combatant/Mine Warfare Ship Symbol Set: 30 Value: 1204**01** Icon Type: Main		N/A
Mine Sweeper Type: Entity Subtype Entity/Entity Type: Military Combatant/Mine Warfare Ship Symbol Set: 30 Value: 1204**02** Icon Type: Main		N/A
Mine Sweeper, Drone Type: Entity Subtype Entity/Entity Type: Military Combatant/Mine Warfare Ship Symbol Set: 30 Value: 1204**03** Icon Type: Main		N/A
Mine Hunter Type: Entity Subtype Entity/Entity Type: Military Combatant/Mine Warfare Ship Symbol Set: 30 Value: 1204**04** Icon Type: Main		N/A
Mine Countermeasures Type: Entity Subtype Entity/Entity Type: Military Combatant/Mine Warfare Ship Symbol Set: 30 Value: 1204**05** Icon Type: Main		N/A




Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE G-III. Sea surface unit, equipment and installation icons - Continued.

DESCRIPTION	ICON	REMARKS
Mine Countermeasures, Support Ship Type: Entity Subtype Entity/Entity Type: Military Combatant/Mine Warfare Ship Symbol Set: 30 Value: 120**406** Icon Type: Main		N/A
Patrol Boat Type: Entity Type Entity: Military Combatant Symbol Set: 30 Value: 12**05**00 Icon Type: Main		N/A
Patrol Craft, Submarine Chaser/Escort, General Type: Entity Subtype Entity/Entity Type: Military Combatant/Patrol Boat Symbol Set: 30 Value: 120**501** Icon Type: Main		N/A
Patrol Ship, General Type: Entity Subtype Entity/Entity Type: Military Combatant/Patrol Boat Symbol Set: 30 Value: 120**502** Icon Type: Main		N/A
Decoy Type: Entity Type Entity: Military Combatant Symbol Set: 30 Value: 12**06**00 Icon Type: Main		N/A
Unmanned Surface Water Vehicle (USV) Type: Entity Type Entity: Military Combatant Symbol Set: 30 Value: 12**07**00 Icon Type: Main		N/A




Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE G-III. Sea surface unit, equipment and installation icons - Continued.

DESCRIPTION	ICON	REMARKS
Speedboat Type: Entity Type Entity: Military Combatant Symbol Set: 30 Value: 12**08**00 Icon Type: Main		N/A
Rigid-Hull Inflatable Boat (RHIB) Type: Entity Subtype Entity/Entity Type: Military Combatant/Speedboat Symbol Set: 30 Value: 1208**01** Icon Type: Main		N/A
Jet Ski Type: Entity Type Entity: Military Combatant Symbol Set: 30 Value: 12**09**00 Icon Type: Main		N/A
Navy Task Organization Type: Entity Type Entity: Military Combatant Symbol Set: 30 Value: 12**10**00 Icon Type: Main		N/A
Navy Task Element Type: Entity Subtype Entity/Entity Type: Military Combatant/Navy Task Organization Symbol Set: 30 Value: 1210**01** Icon Type: Main		N/A
Navy Task Force Type: Entity Subtype Entity/Entity Type: Military Combatant/Navy Task Organization Symbol Set: 30 Value: 1210**02** Icon Type: Main		N/A

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE G-III. Sea surface unit, equipment and installation icons - Continued.

DESCRIPTION	ICON	REMARKS
Navy Task Group Type: Entity Subtype Entity/Entity Type: Military Combatant/Navy Task Organization Symbol Set: 30 Value: 121**03** Icon Type: Main		N/A
Navy Task Unit Type: Entity Subtype Entity/Entity Type: Military Combatant/Navy Task Organization Symbol Set: 30 Value: 121**04** Icon Type: Main		N/A
Convoy Type: Entity Subtype Entity/Entity Type: Military Combatant/Navy Task Organization Symbol Set: 30 Value: 121**05** Icon Type: Main		N/A
Sea-Based X-Band (SBX) Radar Type: Entity Type Entity: Military Combatant Symbol Set: 30 Value: 12**11**00 Icon Type: Main		N/A
Military Noncombatant Type: Entity Symbol Set: 30 Value: **13**0000 Icon Type: Main	N/A	Reserved for hierarchical purposes.
Auxiliary Ship Type: Entity Type Entity: Military Noncombatant Symbol Set: 30 Value: 13**01**00 Icon Type: Main		N/A

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE G-III. Sea surface unit, equipment and installation icons - Continued.

DESCRIPTION	ICON	REMARKS
Ammunition Ship Type: Entity Subtype Entity/Entity Type: Military Noncombatant/Auxiliary Ship Symbol Set: 30 Value: 130101 Icon Type: Main		N/A
Naval Stores Ship Type: Entity Subtype Entity/Entity Type: Military Noncombatant/Auxiliary Ship Symbol Set: 30 Value: 130102 Icon Type: Main		N/A
Auxiliary Flag Ship Type: Entity Subtype Entity/Entity Type: Military Noncombatant/Auxiliary Ship Symbol Set: 30 Value: 130103 Icon Type: Main		N/A
Intelligence Collector Type: Entity Subtype Entity/Entity Type: Military Noncombatant/Auxiliary Ship Symbol Set: 30 Value: 130104 Icon Type: Main		N/A
Oceanographic Research Ship Type: Entity Subtype Entity/Entity Type: Military Noncombatant/Auxiliary Ship Symbol Set: 30 Value: 130105 Icon Type: Main		N/A
Survey Ship Type: Entity Subtype Entity/Entity Type: Military Noncombatant/Auxiliary Ship Symbol Set: 30 Value: 130106 Icon Type: Main		N/A



Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE G-III. Sea surface unit, equipment and installation icons - Continued.

DESCRIPTION	ICON	REMARKS
Hospital Ship Type: Entity Subtype Entity/Entity Type: Military Noncombatant/Auxiliary Ship Symbol Set: 30 Value: 130107 Icon Type: Main		N/A
Naval Cargo Ship Type: Entity Subtype Entity/Entity Type: Military Noncombatant/Auxiliary Ship Symbol Set: 30 Value: 130108 Icon Type: Main		N/A
Combat Support Ship, Fast Type: Entity Subtype Entity/Entity Type: Military Noncombatant/Auxiliary Ship Symbol Set: 30 Value: 130109 Icon Type: Main		N/A
Oiler, Replenishment Type: Entity Subtype Entity/Entity Type: Military Noncombatant/Auxiliary Ship Symbol Set: 30 Value: 130110 Icon Type: Main		N/A
Repair Ship Type: Entity Subtype Entity/Entity Type: Military Noncombatant/Auxiliary Ship Symbol Set: 30 Value: 130111 Icon Type: Main		N/A
Submarine Tender Type: Entity Subtype Entity/Entity Type: Military Noncombatant/Auxiliary Ship Symbol Set: 30 Value: 130112 Icon Type: Main		N/A


Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE G-III. Sea surface unit, equipment and installation icons - Continued.

DESCRIPTION	ICON	REMARKS
Tug, Ocean Going Type: Entity Subtype Entity/Entity Type: Military Noncombatant/Auxiliary Ship Symbol Set: 30 Value: 1301**13** Icon Type: Main		N/A
Service Craft/Yard Type: Entity Type Entity: Military Noncombatant Symbol Set: 30 Value: 13**02**00 Icon Type: Main		N/A
Barge, Not Self-Propelled Type: Entity Subtype Entity/Entity Type: Military Noncombatant/Service Craft/Yard Symbol Set: 30 Value: 13020**1** Icon Type: Main		N/A
Barge, Self-Propelled Type: Entity Subtype Entity/Entity Type: Military Noncombatant/Service Craft/Yard Symbol Set: 30 Value: 13020**2** Icon Type: Main		N/A
Tug, Harbor Type: Entity Subtype Entity/Entity Type: Military Noncombatant/Service Craft/Yard Symbol Set: 30 Value: 13020**3** Icon Type: Main		N/A
Launch Type: Entity Subtype Entity/Entity Type: Military Noncombatant/Service Craft/Yard Symbol Set: 30 Value: 13020**4** Icon Type: Main		N/A



Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE G-III. Sea surface unit, equipment and installation icons - Continued.

DESCRIPTION	ICON	REMARKS
Civilian Type: Entity Symbol Set: 30 Value: **14**0000 Icon Type: Main		N/A
Merchant Ship Type: Entity Type Entity: Civilian Symbol Set: 30 Value: 14**01**00 Icon Type: Full Octagon		N/A
Cargo, General Type: Entity Subtype Entity/Entity Type: Civilian/Merchant Ship Symbol Set: 30 Value: 1401**01** Icon Type: Full Octagon		N/A
Container Ship Type: Entity Subtype Entity/Entity Type: Civilian/Merchant Ship Symbol Set: 30 Value: 1401**02** Icon Type: Full Octagon		N/A
Dredge Type: Entity Subtype Entity/Entity Type: Civilian/Merchant Ship Symbol Set: 30 Value: 1401**03** Icon Type: Full Octagon		N/A
Roll On/Roll Off Type: Entity Subtype Entity/Entity Type: Civilian/Merchant Ship Symbol Set: 30 Value: 1401**04** Icon Type: Full Octagon		N/A
Ferry Type: Entity Subtype Entity/Entity Type: Civilian/Merchant Ship Symbol Set: 30 Value: 1401**05** Icon Type: Full Octagon		N/A


Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE G-III. Sea surface unit, equipment and installation icons - Continued.

DESCRIPTION	ICON	REMARKS
Heavy Lift Type: Entity Subtype Entity/Entity Type: Civilian/Merchant Ship Symbol Set: 30 Value: 140106 Icon Type: Full Octagon		N/A
Hovercraft Type: Entity Subtype Entity/Entity Type: Civilian/Merchant Ship Symbol Set: 30 Value: 140107 Icon Type: Full Octagon		N/A
Lash Carrier (with Barges) Type: Entity Subtype Entity/Entity Type: Civilian/Merchant Ship Symbol Set: 30 Value: 140108 Icon Type: Full Octagon		N/A
Oiler/Tanker Type: Entity Subtype Entity/Entity Type: Civilian/Merchant Ship Symbol Set: 30 Value: 140109 Icon Type: Full Octagon		N/A
Passenger Type: Entity Subtype Entity/Entity Type: Civilian/Merchant Ship Symbol Set: 30 Value: 140110 Icon Type: Full Octagon		N/A
Tug, Ocean Going Type: Entity Subtype Entity/Entity Type: Civilian/Merchant Ship Symbol Set: 30 Value: 140111 Icon Type: Full Octagon		N/A
Tow Type: Entity Subtype Entity/Entity Type: Civilian/Merchant Ship Symbol Set: 30 Value: 140112 Icon Type: Full Octagon		N/A





Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE G-III. Sea surface unit, equipment and installation icons - Continued.

DESCRIPTION	ICON	REMARKS
Transport Ship, Hazardous Material Type: Entity Subtype Entity/Entity Type: Civilian/Merchant Ship Symbol Set: 30 Value: 140**13** Icon Type: Full Octagon		N/A
Junk/Dhow Type: Entity Subtype Entity/Entity Type: Civilian/Merchant Ship Symbol Set: 30 Value: 140**14** Icon Type: Full Octagon		N/A
Barge, Not Self-Propelled Type: Entity Subtype Entity/Entity Type: Civilian/Merchant Ship Symbol Set: 30 Value: 140**15** Icon Type: Full Octagon		N/A
Hospital Ship Type: Entity Subtype Entity/Entity Type: Civilian/Merchant Ship Symbol Set: 30 Value: 140**16** Icon Type: Full Octagon		N/A
Fishing Vessel Type: Entity Type Entity: Civilian Symbol Set: 30 Value: 1**40**200 Icon Type: Full Octagon		N/A
Drifter Type: Entity Subtype Entity/Entity Type: Civilian/Fishing Vessel Symbol Set: 30 Value: 1402**01** Icon Type: Full Octagon		N/A
Trawler Type: Entity Subtype Entity/Entity Type: Civilian/Fishing Vessel Symbol Set: 30 Value: 1402**02** Icon Type: Full Octagon		N/A


Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE G-III. Sea surface unit, equipment and installation icons - Continued.

DESCRIPTION	ICON	REMARKS
Dredger Type: Entity Subtype Entity/Entity Type: Civilian/Fishing Vessel Symbol Set: 30 Value: 1402**03** Icon Type: Full Octagon		N/A
Law Enforcement Vessel Type: Entity Type Entity: Civilian Symbol Set: 30 Value: 14**03**00 Icon Type: Full Octagon		N/A
Leisure Craft, Sailing Type: Entity Type Entity: Civilian Symbol Set: 30 Value: 14**04**00 Icon Type: Full Octagon		N/A
Leisure Craft, Motorized Type: Entity Type Entity: Civilian Symbol Set: 30 Value: 14**05**00 Icon Type: Main		N/A
Rigid-Hull Inflatable Boat (RHIB) Type: Entity Subtype Entity/Entity Type: Civilian/Leisure Craft, Motorized Symbol Set: 30 Value: 140501 Icon Type: Main		N/A
Speedboat Type: Entity Subtype Entity/Entity Type: Civilian/Leisure Craft, Motorized Symbol Set: 30 Value: 140502 Icon Type: Main		N/A
Jet Ski Type: Entity Type Entity: Civilian Symbol Set: 30 Value: 14**06**00 Icon Type: Main		N/A






Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE G-III. Sea surface unit, equipment and installation icons - Continued.

DESCRIPTION	ICON	REMARKS
Unmanned Surface Water Vehicle (USV) Type: Entity Type Entity: Civilian Symbol Set: 30 Value: 14**07**00 Icon Type: Full Octagon		N/A






G.6.3 Sea surface unit, equipment and installation sector 1 modifiers. Sea surface unit, equipment, and installation sector 1 modifiers denote mission area, weapons capability, and asset capability categories. Modifiers are not permitted with civilian sea surface symbols. Table G-IV lists sea surface unit, equipment and installation sector 1 modifiers and illustrates their placement within the bounding octagon. Additional sector 1 modifiers, where required, are included in table B-I and are accessed using the modifier extension flag.

TABLE G-IV. Sea surface unit, equipment and installation sector 1 modifiers .

DESCRIPTION	CATEGORY	MODIFIER	REMARKS
Own Ship Symbol Set: 30 Value: 01	Mission Area		APP-06
Antiair Warfare Symbol Set: 30 Value: 02	Mission Area		N/A
Electromagnetic Warfare Symbol Set: 30 Value: 05	Mission Area		N/A
Missile Defense Symbol Set: 30 Value: 08	Mission Area		N/A
Remote Multi-Mission Vehicle (RMV) Symbol Set: 30 Value: 11	Mission Area		US only


Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE G-IV. Sea surface unit, equipment and installation sector 1 modifiers - Continued.

DESCRIPTION	CATEGORY	MODIFIER	REMARKS
Torpedo Symbol Set: 30 Value: 17	Weapons Capability		N/A
Drone Equipped Symbol Set: 30 Value: 18	Asset Capability		N/A
Helicopter Equipped/VSTOL Symbol Set: 30 Value: 19	Asset Capability		N/A
Ballistic Missile Defense, Long-Range Surveillance and Track (LTS&T) Symbol Set: 30 Value: 21	Mission Area		N/A
Sea-Base X-Band Symbol Set: 30 Value: 22	Mission Area		Used with SBX Radar (Value: 121**1**100) only









G.6.4 Sea surface unit, equipment, and installation sector 2 modifiers. Sea surface unit, equipment and installation sector 2 modifiers denote ship propulsion, ship capacity, cargo capacity, ship mobility and USV control categories. Modifiers are not permitted with civilian sea surface symbols. Table G-V lists sea surface unit, equipment and installation sector 2 modifiers and illustrates their placement within the bounding octagon. Additional sector 2 modifiers, where required, are included in table B-II and are accessed using the modifier extension flag.

TABLE G-V. Sea surface unit, equipment and installation sector 2 modifiers.

DESCRIPTION	CATEGORY	MODIFIER	REMARKS
Nuclear Powered Symbol Set: 30 Value: 01	Ship Propulsion		N/A

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE G-V. Sea surface unit, equipment and installation sector 2 modifiers - Continued.

DESCRIPTION	CATEGORY	MODIFIER	REMARKS
Dock Symbol Set: 30 Value: 05	Cargo Capacity		N/A
Logistics Symbol Set: 30 Value: 06	Cargo Capacity		N/A
Tank Symbol Set: 30 Value: 07	Cargo Capacity		N/A
Vehicle Symbol Set: 30 Value: 08	Cargo Capacity		N/A
Fast Symbol Set: 30 Value: 09	Cargo Capacity		N/A
Air-Cushioned (US) Symbol Set: 30 Value: 10	Ship Mobility		N/A
Air-Cushioned (NATO) Symbol Set: 30 Value: 11	Ship Mobility		N/A
Hydrofoil Symbol Set: 30 Value: 12	Ship Mobility		N/A

G.6.5 Sea surface local tracks. Local tracks are tracks internal to a particular Combat Information Center (CIC). These tracks are not intended to be transmitted outside the ship's CIC. Table G-VII depicts local tracks. Modifiers are not permitted with local track symbols.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

G.6.5.1 Fused tracks. Fused tracks are tracks in the process of classification. Multiple sources of incoming information need to be adjudicated and combined (fused) into a single track. Fused tracks are denoted by a question mark ("?") encapsulated within an hourglass icon (see Table G-VII). All fused tracks have a pending standard identity frame.

TABLE G-VI. Own Ship.

DESCRIPTION	ICON	REMARKS
Own Ship Type: Entity (Local) Symbol Set: 30 Value: **15**0000 Icon Type: Full Octagon		The diameter of the icon shall be 1L. This icon shall be used with a friend standard identity only.

TABLE G-VII. Sea surface local tracks.

DESCRIPTION	ICON	REMARKS
Fused Track Type: Entity (Local) Symbol Set: 30 Value: **16**0000 Icon Type: Full Octagon		All fused tracks shall have a pending standard identity frame.
Manual Track Type: Entity (Local) Symbol Set: 30 Value: **17**0000 Icon Type: Full Octagon		N/A

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

SEA SUBSURFACE SYMBOLS

H.1 SCOPE

H.1.1 Scope. This appendix addresses symbols that support sea subsurface units, equipment and installations in the C2 domain. The tables in this appendix present the icons and modifiers for the sea subsurface symbol sets. This appendix is divided into two sections (see figure H-1): 1) unit, equipment and installation symbols, see H.6, and 2) mine warfare symbols, see H.7. The information contained herein is intended for compliance.




FIGURE H-1. Sea subsurface appendix sections.

H.2 APPLICABLE DOCUMENTS

Specific documents in 2.2 of this standard apply to this appendix.

H.3 DEFINITIONS

The definitions in section 3 of this standard apply to this appendix.

H.4 GENERAL REQUIREMENTS

H.4.1 Organization. This appendix contains technical specifications, a symbol coding scheme, a symbology hierarchy and sea subsurface symbology.

H.5 DETAILED REQUIREMENTS

H.5.1 Technical specifications. Composition, construction and display of symbols are explained in the detailed requirements section of the standard.

H.5.2 Symbol identification coding scheme. A symbol identification code (SIDC) is a numeric string that may be used to provide the unique identifier necessary to display or exchange symbol information between MIL-STD-2525 compliant systems. Refer to Appendix A for SIDC positions and descriptions.

H.5.3 Composition of sea subsurface symbols. A standard method for constructing symbols is presented. Refer to 5.3.10 for an explanation of symbol composition. Figure H-2 shows an example of a sea subsurface equipment symbol.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.









FIGURE H-2. Sea subsurface symbol components.

H.5.3.1 Symbol building process. Table H-I depicts the symbol building process for sea subsurface symbols. The process is identical for icons and modifiers requiring the vertical bounding octagon.

TABLE H-I. Sea subsurface symbol building process.

STEP	DESCRIPTION	EXAMPLE
1.	Choose the frame that matches the dimension of the object from the appropriate column in tables I, II, or III and standard identity (table A-II). In this example, the dimension is sea subsurface and the standard identity is friend. The example depicts a “friendly sea subsurface track.”	
2.	Choose an icon for the main sector of the bounding octagon. In this example, the icon is “submarine,” a sea subsurface entity type. The example depicts a “friendly submarine.”	
3.	If required, choose a modifier to depict an additional characteristic of the icon. In this example, the modifier is “ballistic missile,” a sector 1 modifier. The example depicts a “friendly submarine with guided missile weapons capability.”	
4.	If required, choose a modifier to depict another characteristic of the icon. In this example, the modifier is “nuclear powered,” a sector 2 modifier. The example depicts a “friendly nuclear powered submarine with guided missile weapons capability.”	
5.	The finished symbol will appear as shown in the example.	

H.5.3.2 Icons and modifiers. All icons shall be placed within the main sector of the bounding octagon or fill the octagon, as indicated in table H-I. When depicted, modifiers shall be

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

placed in sectors 1 or 2 as appropriate (see table H-I). Only one modifier may be placed in each sector at a given time. Multiple modifiers in the same position are prohibited due to legibility concerns.

H.5.3.3 Amplifiers.

H.5.3.3.1 Text amplifiers. The purpose of the static text amplifiers described in this appendix is to standardize the display of additional alphanumerical information on identity, movement and location and capabilities. See 5.3.7 for more information on amplifiers. Figure H-3 shows the placement of sea subsurface symbol amplifiers around the friend symbol frame. Table H-II provides descriptions and formats of each amplifier.




FIGURE H-3. Placement of sea subsurface symbol amplifiers.

TABLE H-II. Descriptions and formats of sea subsurface symbol amplifiers.

FIELD	FIELD TITLE	DESCRIPTION	FORMAT
A	Sea Subsurface/Sea Subsurface Type Icon	The innermost part of a symbol, comprised of an icon and optional modifiers, that represents a joint military object (see 5.3.4).	
G	Staff Comments	A text amplifier for units, equipment, and installations; content is implementation specific.	
H	Additional Information	A text amplifier for units, equipment, and installations; content is implementation specific.	
P	IFF/SIF	A text amplifier displaying one or more IFF/SIF Identification modes and codes. **Display priority:** Mode 5, Mode S, Mode 2, Mode 3.	Mode 2 Prefix: 2:#### **Example**: 2:1234
Q	Direction of Movement Indicator	A graphic amplifier that identifies the direction of movement or intended movement of an object (see 5.3.7.9 and figure 14 in the base document).	

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE H-II. Descriptions and formats of sea subsurface symbol amplifiers - Continued.

FIELD	FIELD TITLE	DESCRIPTION	FORMAT
S2	Offset Location Indicator	A graphic amplifier used to indicate the offset or precise location of a single point symbol (see 5.3.7.5, 5.3.13, and figure 14).	
T	Unique Designation (Track Number)	A text amplifier for units, equipment and installations that uniquely identifies a particular symbol or track number.	Prefix = TN:##### Example: TN:13579
V	Type	A text amplifier for equipment that indicates types of equipment.	
X	Depth	A text amplifier for equipment that displays depth for submerged objects.	Measurement units (FT, M) shall be displayed within the string. Ex: 105 FT
Y	Location	A text amplifier for units, equipment and installations that displays a symbol's location in degrees, minutes, and decimal minutes (or in MGRS, GARS, or other applicable display formats).	3317.0921N 04412.6332E 38SMB2649083145
Z	Speed	A text amplifier for units and equipment that displays velocity (see 5.3.7.7).	
AG	Auxiliary Equipment Indicator	Towed sonar array indicator: A graphic amplifier for equipment that indicates the presence of a towed sonar array (see 5.3.7.10, figure 13 and table IX).	
AL	Operational Condition	A graphic amplifier for equipment or installations that indicates an operational condition or capacity.	Operational Condition amplifier, if used, shall be comprised of only one color. Ex. Aircraft: Red - damaged, Green – fully capable Ex: Missile: Red – imminent threat, Green – no threat
AO	Engagement Bar	A graphic amplifier placed immediately atop the symbol. May denote: 1) local/remote status, 2) engagement status, 3) weapon type.	A:BBB-CC, where A = remote/local BBB = engagement status CC = weapon asset
AR	Special Designator	Special track designators such as Non-Real Time (NRT) and Tactically Significant (SIG) tracks are denoted here.	The 3-character strings, NRT or SIG
AS	Country	A three-letter code that indicates the country of origin of the organization (US systems shall use GENC).	

H.5.3.3.2 Graphic amplifiers. Graphic amplifiers can be static, located in a fixed position in relation to a track's symbol, or dynamic and move about the symbol based on the track's characteristics. See 5.3.7 for more information on amplifiers, including examples of dynamic amplifiers.




Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

H.6 SEA SUBSURFACE UNIT, EQUIPMENT AND INSTALLATION SYMBOLS

H.6.1 Sea subsurface unit, equipment and installation symbols. This section includes the lists of icons and modifiers for building sea subsurface unit, equipment and installation symbols.





H.6.2 Sea subsurface unit, equipment and installation icons. Table H-III depicts sea subsurface unit, equipment and installation icons. Military symbols are depicted with black-filled icons, whereas civilian symbols are depicted with white-filled icons. Sea mines and sea mine decoys are presented in H.7.

TABLE H-III. Sea subsurface unit, equipment and installation icons.

DESCRIPTION	ICON	REMARKS
Military Type: Entity Symbol Set: 35 Value: **11**0000 Icon Type: Main		N/A
Submarine Type: Entity Type Entity: Military Symbol Set: 35 Value: 11**01**00 Icon Type: Main		N/A
Submarine, Surfaced Type: Entity Subtype Entity/Entity Type: Military/Submarine Symbol Set: 35 Value: 1101**01** Icon Type: Main		N/A
Submarine, Snorkeling Type: Entity Subtype Entity/Entity Type: Military/Submarine Symbol Set: 35 Value: 1101**02** Icon Type: Main		N/A
Submarine, Bottomed Type: Entity Subtype Entity/Entity Type: Military/Submarine Symbol Set: 35 Value: 1101**03** Icon Type: Main		N/A






Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE H-III. Sea subsurface unit, equipment and installation icons - Continued.

DESCRIPTION	ICON	REMARKS
Other Submersible Type: Entity Type Entity: Military Symbol Set: 35 Value: 11**02**00 Icon Type: Main		N/A
Nonsubmarine Type: Entity Type Entity: Military Symbol Set: 35 Value: 11**03**00 Icon Type: Full Octagon		N/A
Autonomous Underwater Vehicle (AUV)/Unmanned Underwater Vehicle (UUV) Type: Entity Type Entity: Military Symbol Set: 35 Value: 11**04**00 Icon Type: Main		N/A
Diver Type: Entity Type Entity: Military Symbol Set: 35 Value: 11**05**00 Icon Type: Main		N/A
Civilian Type: Entity Symbol Set: 35 Value: **1**20000 Icon Type: Main		N/A
Submersible Type: Entity Type Entity: Civilian Symbol Set: 35 Value: 12**01**00 Icon Type: Main		N/A

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.








TABLE H-III. Sea subsurface unit, equipment and installation icons - Continued.

DESCRIPTION	ICON	REMARKS
Autonomous Underwater Vehicle (AUV)/Unmanned Underwater Vehicle (UUV) Type: Entity Type Entity: Civilian Symbol Set: 35 Value: 12**02**00 Icon Type: Main		N/A
Diver Type: Entity Type Entity: Civilian Symbol Set: 35 Value: 12**03**00 Icon Type: Main		N/A
Weapon Type: Entity Symbol Set: 35 Value: **13**0000 Icon Type: Main		N/A
Torpedo Type: Entity Type Entity: Weapon Symbol Set: 35 Value: 13**01**00 Icon Type: Main		N/A
Improvised Explosive Device (IED) Type: Entity Type Entity: Weapon Symbol Set: 35 Value: 13**02**00 Icon Type: Main		Used with hostile standard identity only.
Decoy Type: Entity Type Entity: Weapon Symbol Set: 35 Value: 13**03**00 Icon Type: Main		N/A

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.


H.6.3 Sea subsurface unit, equipment and installation sector 1 modifiers. Sea subsurface unit, equipment and installation sector 1 modifiers denote mission area, weapons capability, asset capability and submarine confidence categories. Table H-IV lists sea subsurface unit, equipment and installation sector 1 modifiers and illustrates their placement within the bounding octagon. Additional sector 1 modifiers, where required, are included in table B-I and are accessed using the modifier extension flag.

TABLE H-IV. Sea subsurface unit, equipment and installation sector 1 modifiers.

DESCRIPTION	CATEGORY	MODIFIER	REMARKS
Auxiliary Symbol Set: 35 Value: 02	Mission Area		Used with SUBMARINE entity type only.
Possible Submarine - Low 1 Symbol Set: 35 Value: 13	Submarine Confidence		Used with SUBMARINE entity type only.
Possible Submarine - Low 2 Symbol Set: 35 Value: 14	Submarine Confidence		Used with SUBMARINE entity type only.
Possible Submarine - High 3 Symbol Set: 35 Value: 15	Submarine Confidence		Used with SUBMARINE entity type only.
Possible Submarine - High 4 Symbol Set: 35 Value: 16	Submarine Confidence		Used with SUBMARINE entity type only.
Probable Submarine Symbol Set: 35 Value: 17	Submarine Confidence		Used with SUBMARINE entity type only.
Certain Submarine Symbol Set: 35 Value: 18	Submarine Confidence		Used with SUBMARINE entity type only.






Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE H-IV. Sea subsurface unit, equipment and installation sector 1 modifiers - Continued.

DESCRIPTION	CATEGORY	MODIFIER	REMARKS
Anti-Torpedo Torpedo Symbol Set: 35 Value: 19	Weapons Capability		Used with TORPEDO entity type only.









H.6.4 Sea subsurface unit, equipment, and installation sector 2 modifiers. Sea subsurface unit, equipment and installation sector 2 modifiers denote ship propulsion and UUV control categories. Table H-V lists sea subsurface unit, equipment and installation sector 2 modifiers and illustrates their placement within the bounding octagon. Additional sector 2 modifiers, where required, are included in table B-II and are accessed using the modifier extension flag.

TABLE H-V. Sea subsurface unit, equipment and installation sector 2 modifiers.

DESCRIPTION	CATEGORY	MODIFIER	REMARKS
Air Independent Propulsion Symbol Set: 35 Value: 01	Ship Propulsion		Used with Submarine entity type only.
Diesel Electric, General Symbol Set: 35 Value: 02	Ship Propulsion		Used with Submarine entity type only.
Diesel - Type 1 Symbol Set: 35 Value: 03	Ship Propulsion		Used with Submarine entity type only.
Diesel - Type 2 Symbol Set: 35 Value: 04	Ship Propulsion		Used with Submarine entity type only.
Diesel - Type 3 Symbol Set: 35 Value: 05	Ship Propulsion		Used with Submarine entity type only.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE H-V. Sea subsurface unit, equipment and installation sector 2 modifiers - Continued.

DESCRIPTION	CATEGORY	MODIFIER	REMARKS
Nuclear Powered, General Symbol Set: 35 Value: 06	Ship Propulsion		Used with Submarine entity type only.
Nuclear - Type 1 Symbol Set: 35 Value: 07	Ship Propulsion		Used with Submarine entity type only.
Nuclear - Type 2 Symbol Set: 35 Value: 08	Ship Propulsion		Used with Submarine entity type only.
Nuclear - Type 3 Symbol Set: 35 Value: 09	Ship Propulsion		Used with Submarine entity type only.
Nuclear - Type 4 Symbol Set: 35 Value: 10	Ship Propulsion		Used with Submarine entity type only.
Nuclear - Type 5 Symbol Set: 35 Value: 11	Ship Propulsion		Used with Submarine entity type only.
Nuclear - Type 6 Symbol Set: 35 Value: 12	Ship Propulsion		Used with Submarine entity type only.
Nuclear - Type 7 Symbol Set: 35 Value: 13	Ship Propulsion		Used with Submarine entity type only.

H.6.5 Sea subsurface local tracks. Local tracks are tracks internal to a particular Combat Information Center (CIC). These tracks are not intended to be transmitted outside the ship's CIC. Table H-VI depicts local tracks. Modifiers are not permitted with local track symbols.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

H.6.5.1 Fused tracks. Fused tracks are tracks in the process of classification. Multiple sources of incoming information need to be adjudicated and combined (fused) into a single track. Fused tracks are denoted by a question mark (?) encapsulated within an hourglass icon (see table H-VI). All fused tracks have a pending standard identity frame.

TABLE H-VI. Sea subsurface local tracks.

DESCRIPTION	ICON	REMARKS
Echo Tracker Classifier (ETC)/Possible Contact (POSCON) Type: Entity (Local) Symbol Set: 35 Value: **14**0000 Icon Type: Full Octagon		All ETC/POSCON tracks shall have a pending standard identity frame.
Fused Track Type: Entity (Local) Symbol Set: 35 Value: **15**0000 Icon Type: Full Octagon		All fused tracks shall have a pending standard identity frame.
Manual Track Type: Entity (Local) Symbol Set: 35 Value: **16**0000 Icon Type: Full Octagon		N/A

H.7 MINE WARFARE SYMBOLS

H.7.1 Mine warfare symbols. This section includes the lists of icons for building mine warfare (MIW) symbols. There are no modifiers in MIW symbols.

H.7.2 Mine warfare icons. MIW symbols are represented using Mine Warfare Environmental Decision Aids Library (MEDAL) icons embedded within MIL-STD-2525 standard identity frames. The color in MEDAL icons represents the threat level of that contact. Red denotes mine, orange denotes mine-like contact (MILCO), yellow denotes mine-like echo (MILEC), dark green denotes non-mine mine-like object (or non-mine) and bright green denotes neutralized mine. An alternative icon set directly corresponding to MEDAL icons may also be used. The alternative set depicts the same MEDAL icons, but depicts them as black icons eliminating the color threat coding scheme. The MEDAL icons shall be used with unfilled sea subsurface frames. The alternative icons shall be used with the normal sea subsurface frames (see tables H-I, H-II and H-III). Figure H-4 shows examples of framed MEDAL and alternative icons. Table H-VII depicts mine warfare icons.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.






FIGURE H-4. Framing examples of MEDAL and alternative mine warfare icon

TABLE H-VII. Mine warfare icons.

DESCRIPTION	MEDAL ICON	ALTERNATIVE ICON	REMARKS
Sea Mine, General Type: Entity Symbol Set: 36 Value: **11**0000 Icon Type: Full Octagon			N/A
Sea Mine, Bottom Type: Entity Type Entity: Sea Mine, General Symbol Set: 36 Value: 11**01**00 Icon Type: Full Octagon			N/A
Sea Mine, Moored Type: Entity Type Entity: Sea Mine, General Symbol Set: 36 Value: 11**02**00 Icon Type: Full Octagon			N/A
Sea Mine, Floating Type: Entity Type Entity: Sea Mine, General Symbol Set: 36 Value: 11**03**00 Icon Type: Full Octagon			N/A
Sea Mine, Rising Type: Entity Type Entity: Sea Mine, General Symbol Set: 36 Value: 11**04**00 Icon Type: Full Octagon			N/A


Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE H-VII. Mine warfare icons - Continued.

DESCRIPTION	MEDAL ICON	ALTERNATIVE ICON	REMARKS
Sea Mine, Other Position Type: Entity Type Entity: Sea Mine, General Symbol Set: 36 Value: 11**05**00 Icon Type: Full Octagon			N/A
Kingfisher Type: Entity Type Entity: Sea Mine, General Symbol Set: 36 Value: 11**06**00 Icon Type: Full Octagon	N/A		There is no MEDAL icon associated with this symbol.
Small Object, Mine-Like Type: Entity Type Entity: Sea Mine, General Symbol Set: 36 Value: 11**07**00 Icon Type: Full Octagon	N/A		There is no MEDAL icon associated with this symbol.
Exercise Mine, General Type: Entity Type Entity: Sea Mine, General Symbol Set: 36 Value: 11**08**00 Icon Type: Full Octagon			Used with exercise frame only.
Exercise Mine, Bottom Type: Entity Subtype Entity/Entity Type: Sea Mine, General/Exercise Mine, General Symbol Set: 36 Value: 1108**01** Icon Type: Full Octagon			Used with exercise frame only.
Exercise Mine, Moored Type: Entity Subtype Entity/Entity Type: Sea Mine, General/Exercise Mine, General Symbol Set: 36 Value: 1108**02** Icon Type: Full Octagon			Used with exercise frame only.



Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE H-VII. Mine warfare icons - Continued.

DESCRIPTION	MEDAL ICON	ALTERNATIVE ICON	REMARKS
Exercise Mine, Floating Type: Entity Subtype Entity/Entity Type: Sea Mine, General/Exercise Mine, General Symbol Set: 36 Value: 1108**03** Icon Type: Full Octagon			Used with exercise frame only.
Exercise Mine, Rising Type: Entity Subtype Entity/Entity Type: Sea Mine, General/Exercise Mine, General Symbol Set: 36 Value: 1108**04** Icon Type: Full Octagon			Used with exercise frame only.
Neutralized Mine, General Type: Entity Type Entity: Sea Mine, General Symbol Set: 36 Value: 11**09**00 Icon Type: Full Octagon			N/A
Neutralized Mine, Bottom Type: Entity Subtype Entity/Entity Type: Sea Mine, General/Neutralized Mine, General Symbol Set: 36 Value: 1109**01** Icon Type: Full Octagon			N/A
Neutralized Mine, Moored Type: Entity Subtype Entity/Entity Type: Sea Mine, General/Neutralized Mine, General Symbol Set: 36 Value: 1109**02** Icon Type: Full Octagon			N/A
Neutralized Mine, Floating Type: Entity Subtype Entity/Entity Type: Sea Mine, General/Neutralized Mine, General Symbol Set: 36 Value: 1109**03** Icon Type: Full Octagon			N/A



Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE H-VII. Mine warfare icons - Continued.

DESCRIPTION	MEDAL ICON	ALTERNATIVE ICON	REMARKS
Neutralized Mine, Rising Type: Entity Subtype Entity/Entity Type: Sea Mine, General/Neutralized Mine, General Symbol Set: 36 Value: 110**04** Icon Type: Full Octagon			N/A
Neutralized Mine, Other Position Type: Entity Subtype Entity/Entity Type: Sea Mine, General/Neutralized Mine, General Symbol Set: 36 Value: 110**05** Icon Type: Full Octagon			N/A
Unexploded Ordnance Type: Entity Symbol Set: 36 Value: **12**0000 Icon Type: Full Octagon			N/A
Sea Mine Decoy Type: Entity Symbol Set: 36 Value: **13**0000 Icon Type: Full Octagon			N/A
Sea Mine Decoy, Bottom Type: Entity Type Entity: Sea Mine Decoy Symbol Set: 36 Value: 13**01**00 Icon Type: Full Octagon			N/A
Sea Mine Decoy, Moored Type: Entity Type Entity: Sea Mine Decoy Symbol Set: 36 Value: 13**02**00 Icon Type: Full Octagon			N/A
Mine-Like Contact (MILCO) Type: Entity Symbol Set: 36 Value: **14**0000	N/A	N/A	Reserved for hierarchical purposes.


Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE H-VII. Mine warfare icons - Continued.

DESCRIPTION	MEDAL ICON	ALTERNATIVE ICON	REMARKS
Milco - General Type: Entity Type Entity: Milco Symbol Set: 36 Value: 14**01**00 Icon Type: Full Octagon			N/A
Milco - General, Confidence Level 1 Type: Entity Subtype Entity/Entity Type: MILCO/MILCO-General Symbol Set: 36 Value: 1401**01** Icon Type: Full Octagon			N/A
Milco - General, Confidence Level 2 Type: Entity Subtype Entity/Entity Type: MILCO/MILCO-General Symbol Set: 36 Value: 1401**02** Icon Type: Full Octagon			N/A
Milco - General, Confidence Level 3 Type: Entity Subtype Entity/Entity Type: MILCO/MILCO-General Symbol Set: 36 Value: 1401**03** Icon Type: Full Octagon			N/A
Milco - General, Confidence Level 4 Type: Entity Subtype Entity/Entity Type: MILCO/MILCO-General Symbol Set: 36 Value: 1401**04** Icon Type: Full Octagon			N/A



Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE H-VII. Mine warfare icons - Continued.

DESCRIPTION	MEDAL ICON	ALTERNATIVE ICON	REMARKS
Milco - General, Confidence Level 5 Type: Entity Subtype Entity/Entity Type: MILCO/MILCO-General Symbol Set: 36 Value: 1401**05** Icon Type: Full Octagon			N/A
Milco - Bottom Type: Entity Type Entity: Milco Symbol Set: 36 Value: 1**40**200 Icon Type: Full Octagon			N/A
Milco - Bottom, Confidence Level 1 Type: Entity Subtype Entity/Entity Type: MILCO/MILCO-Bottom Symbol Set: 36 Value: 1402**01** Icon Type: Full Octagon			N/A
Milco - Bottom, Confidence Level 2 Type: Entity Subtype Entity/Entity Type: MILCO/MILCO-Bottom Symbol Set: 36 Value: 1402**02** Icon Type: Full Octagon			N/A
Milco - Bottom, Confidence Level 3 Type: Entity Subtype Entity/Entity Type: MILCO/MILCO-Bottom Symbol Set: 36 Value: 1402**03** Icon Type: Full Octagon			N/A



Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE H-VII. Mine warfare icons - Continued.

DESCRIPTION	MEDAL ICON	ALTERNATIVE ICON	REMARKS
Milco - Bottom, Confidence Level 4 Type: Entity Subtype Entity/Entity Type: MILCO/MILCO-Bottom Symbol Set: 36 Value: 1402**04** Icon Type: Full Octagon			N/A
Milco - Bottom, Confidence Level 5 Type: Entity Subtype Entity/Entity Type: MILCO/MILCO-Bottom Symbol Set: 36 Value: 1402**05** Icon Type: Full Octagon			N/A
Milco - Moored Type: Entity Type Entity: Milco Symbol Set: 36 Value: 14**03**00 Icon Type: Full Octagon			N/A
Milco - Moored, Confidence Level 1 Type: Entity Subtype Entity/Entity Type: MILCO/MILCO -Moored Symbol Set: 36 Value: 1403**01** Icon Type: Full Octagon			N/A
Milco - Moored, Confidence Level 2 Type: Entity Subtype Entity/Entity Type: MILCO/MILCO -Moored Symbol Set: 36 Value: 1403**02** Icon Type: Full Octagon			N/A


Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE H-VII. Mine warfare icons - Continued.

DESCRIPTION	MEDAL ICON	ALTERNATIVE ICON	REMARKS
Milco - Moored, Confidence Level 3 Type: Entity Subtype Entity/Entity Type: MILCO/MILCO -Moored Symbol Set: 36 Value: 140**03** Icon Type: Full Octagon			N/A
Milco - Moored, Confidence Level 4 Type: Entity Subtype Entity/Entity Type: MILCO/MILCO -Moored Symbol Set: 36 Value: 140**04** Icon Type: Full Octagon			N/A
Milco - Moored, Confidence Level 5 Type: Entity Subtype Entity/Entity Type: MILCO/MILCO -Moored Symbol Set: 36 Value: 140**05** Icon Type: Full Octagon			N/A
Milco - Floating Type: Entity Type Entity: Milco Symbol Set: 36 Value: 1**40**400 Icon Type: Full Octagon			N/A
Milco - Floating, Confidence Level 1 Type: Entity Subtype Entity/Entity Type: MILCO/MILCO-Floating Symbol Set: 36 Value: 140**01** Icon Type: Full Octagon			N/A



Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE H-VII. Mine warfare icons - Continued.

DESCRIPTION	MEDAL ICON	ALTERNATIVE ICON	REMARKS
Milco - Floating, Confidence Level 2 Type: Entity Subtype Entity/Entity Type: MILCO/MILCO-Floating Symbol Set: 36 Value: 140**02** Icon Type: Full Octagon			N/A
Milco - Floating, Confidence Level 3 Type: Entity Subtype Entity/Entity Type: MILCO/MILCO-Floating Symbol Set: 36 Value: 140**03** Icon Type: Full Octagon			N/A
Milco - Floating, Confidence Level 4 Type: Entity Subtype Entity/Entity Type: MILCO/MILCO-Floating Symbol Set: 36 Value: 140**04** Icon Type: Full Octagon			N/A
Milco - Floating, Confidence Level 5 Type: Entity Subtype Entity/Entity Type: MILCO/MILCO-Floating Symbol Set: 36 Value: 140**05** Icon Type: Full Octagon			N/A
Mine-Like Echo (MILEC), General Type: Entity Symbol Set: 36 Value: **15**0000 Icon Type: Full Octagon			N/A
Mine-Like Echo, Bottom Type: Entity Type Entity: Mine-Like Echo (MILEC), General Symbol Set: 36 Value: 15**01**00 Icon Type: Full Octagon			N/A

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE H-VII. Mine warfare icons - Continued.

DESCRIPTION	MEDAL ICON	ALTERNATIVE ICON	REMARKS
Mine-Like Echo, Moored Type: Entity Type Entity: Mine-Like Echo (MILEC), General Symbol Set: 36 Value: 15**02**00 Icon Type: Full Octagon			N/A
Mine-Like Echo, Floating Type: Entity Type Entity: Mine-Like Echo (MILEC), General Symbol Set: 36 Value: 15**03**00 Icon Type: Full Octagon			N/A
Negative Reacquisition, General Type: Entity Symbol Set: 36 Value: **16**0000 Icon Type: Full Octagon			N/A
Negative Reacquisition, Bottom Type: Entity Type Entity: Negative Reacquisition, General Symbol Set: 36 Value: 16**01**00 Icon Type: Full Octagon			N/A
Negative Reacquisition, Moored Type: Entity Type Entity: Negative Reacquisition, General Symbol Set: 36 Value: 16**02**00 Icon Type: Full Octagon			N/A
Negative Reacquisition, Floating Type: Entity Type Entity: Negative Reacquisition, General Symbol Set: 36 Value: 16**03**00 Icon Type: Full Octagon			N/A





Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE H-VII. Mine warfare icons - Continued.

DESCRIPTION	MEDAL ICON	ALTERNATIVE ICON	REMARKS
Obstructor Type: Entity Symbol Set: 36 Value: **1**70000 Icon Type: Full Octagon			N/A
Neutralized Obstructor Type: Entity Type Entity: Obstructor Symbol Set: 36 Value: 17**01**00 Icon Type: Full Octagon			N/A
General Mine Anchor Type: Entity Symbol Set: 36 Value: **18**0000 Icon Type: Full Octagon			N/A
Non-Mine Mine-Like Object (NMLO), General Type: Entity Symbol Set: 36 Value: **19**0000 Icon Type: Full Octagon			N/A
Non-Mine Mine-Like Object, Bottom Type: Entity Type Entity: Non-Mine Mine-Like Object (NMLO), General Symbol Set: 36 Value: 19**01**00 Icon Type: Full Octagon			N/A
Non-Mine Mine-Like Object, Moored Type: Entity Type Entity: Non-Mine Mine-Like Object (NMLO), General Symbol Set: 36 Value: 19**02**00 Icon Type: Full Octagon			N/A

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE H-VII. Mine warfare icons - Continued.

DESCRIPTION	MEDAL ICON	ALTERNATIVE ICON	REMARKS
Non-Mine Mine-Like Object, Floating Type: Entity Type Entity: Non-Mine Mine-Like Object (NMLO), General Symbol Set: 36 Value: 19**03**00 Icon Type: Full Octagon			N/A
Environmental Report Location Type: Entity Symbol Set: 36 Value: **20**0000 Icon Type: Full Octagon			N/A
Dive Report Location Type: Entity Symbol Set: 36 Value: **21**0000 Icon Type: Full Octagon			N/A

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

PAGE INTENTIONALLY LEFT BLANK

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

ACTIVITIES SYMBOLS

I.1 SCOPE

I.1.1 Scope. In this appendix, activities across the range of military operations use various symbols to predominately show support. Activities include stability operations, defense support of civil authorities, foreign humanitarian assistance, incidents, natural events, and operations. Among the types of activities represented are acts of terrorism, sabotage, crime, natural disasters, relief operations, and the uncontrolled movement of large numbers of people. The tables in this appendix present the icons and modifiers used for such operations and means of assistance. Many of these icons represent emergency first response events used in a civilian community. The information contained herein is intended for compliance.

I.2 APPLICABLE DOCUMENTS

Specific documents in 2.2 of this standard apply to this appendix.

I.3 DEFINITIONS

The definitions in section 3 of this standard apply to this appendix.

I.4 GENERAL REQUIREMENTS

I.4.1 Organization. This appendix contains technical specifications, a symbol coding scheme, a symbology hierarchy and supports activities symbology.

I.5 DETAILED REQUIREMENTS

I.5.1 Technical specifications. Composition, construction and display of symbols are explained in the detailed requirements section of the standard.

I.5.2 Symbol identification coding scheme. A symbol identification code (SIDC) is a numeric string that may be used to provide the unique identifier necessary to display or exchange symbol information between MIL-STD-2525 compliant systems. Refer to Appendix A for SIDC positions and descriptions.

I.5.3 Composition of activities symbols. A standard method for constructing symbols is presented. Refer to 5.3.10 for an explanation of symbol composition. Figure I-1 shows an example of an activities symbol.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.








FIGURE I-1. Activities components.

I.5.3.1 Symbol building process. Table I-I depicts the symbol building process for activities symbols. The process is identical for icons and modifiers requiring the vertical bounding octagon. Activities symbols use the land frames for units, equipment and installations, as well as the activity/event frames for incidents.

TABLE I-I. Activities symbol building process.

STEP	DESCRIPTION	EXAMPLE
1.	Choose the frame that matches the dimension of the object from the appropriate column in tables I, II, or III and standard identity (table A-II). In this example, the dimension is activities, and the standard identity is friend. The example depicts a “hostile incident.”	
2.	Choose an icon for the symbol. In this example, the icon is “IED,” an equipment entity subtype. The example depicts a “hostile IED incident.”	
3.	If required, choose a modifier to depict an additional characteristic of the icon. In this example, the modifier is “hoax,” a sector 1 modifier. The example depicts “hostile IED hoax incident.” Note: There are no sector 2 modifiers in activities symbols.	
4.	The finished symbol will appear as shown in the example.	

I.5.3.2 Icons and modifiers. All icons shall be placed within the main sector of the bounding octagon (see table I-I). When depicted, modifiers shall be placed in sectors 1 or 2 as appropriate (see table I-I). Only one modifier may be placed in each sector at a given time. Multiple modifiers in the same position are prohibited due to legibility concerns.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

I.5.3.3 Amplifiers.

I.5.3.3.1 Text amplifiers. The purpose of the static text amplifiers described in this appendix is to standardize the display of additional alphanumerical information on identity, movement and location and capabilities. See 5.3.7 for more information on amplifiers. Figure I-2 shows the placement of activities symbol amplifiers around the friend symbol frame. Table I-II provides descriptions and formats of each amplifier.




FIGURE I-2. Placement of activities symbol amplifiers.

TABLE I-II. Description and formats of activities symbol amplifiers.

Field	Field Title	Description	Text/Graphic
A	Symbol	The innermost part of a symbol, comprised of an icon and optional modifiers, that represents a joint military object (see 5.3.4).	Either
G	Staff Comments	Free text. Can be used by staff for information required by commander.	Text
H	Additional Information	Free text.	Text

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE I-II. Description and formats of activities symbol amplifiers - Continued.

Field	Field Title	Description	Text/Graphic
J	Evaluation Rating	Degree of confidence that may be placed on the information represented by the symbol. It is shown as one letter and one number made up of Reliability of Source and Credibility of Information. (See ATP 2-33.4) Reliability of Source: A. Completely reliable B. Usually reliable C. Fairly reliable D. Not usually reliable E. Unreliable F. Reliability cannot be judged. Credibility of Information: 1. Confirmed by other sources 2. Probably true 3. Possibly true 4. Doubtful 5. Improbable 6. Truth cannot be judged.	Text
Q	Direction of Movement Indicator	A graphic amplifier that identifies the direction of movement or intended movement of an object (see 5.3.7.9 and figure 14 in the base document).	
S2	Offset Location Indicator	A graphic amplifier used to indicate the offset or precise location of a single point symbol (see 5.3.7.5, 5.3.13, and figure 14).	Graphic
T	Unique Designation (Track Number)	A text amplifier for units, equipment and installations that uniquely identifies a particular symbol or track number.	Prefix = TN:##### Example: TN:13579
W	Date-Time Group	An alphanumeric designator for displaying a date-time group (DDHHMMSSZMONYY) or "O/O" for on order. The date-time group is composed of a group of six numeric digits with a time zone suffix and the standardized three-letter abbreviation for the month followed by two digits. The first pair of digits represents the day; the second pair, the hour; the third pair, the minutes. The last two digits of the year are after the month. For automated systems, two digits may be added before the time zone suffix and after the minutes to designate seconds (see 5.3.7.8).	Text Example: 3317.0921N 04412.6332E 38SMB2649083145
Y	Location	A text amplifier for units, equipment and installations that displays a symbol's location in degrees, minutes, and decimal minutes (or in MGRS, GARS, or other applicable display formats).	Text
AS	Country Indicator	A three-letter code that indicates the country of origin of the organization (US systems shall use GENC).	Text

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.


I.5.3.3.2 Graphic amplifiers. Graphic amplifiers can be static, located in a fixed position in relation to a track's symbol, or dynamic and move about the symbol based on the track's characteristics. See 5.3.7 for more information on amplifiers, including examples of dynamic amplifiers.

I.6 ACTIVITIES SYMBOLS

I.6.1 Activities symbols. This section includes the lists of icons and modifiers for building activities symbols.




I.6.2 Activities icons. Table I-III depicts activities icons.

TABLE I-III. Activities icons.

DESCRIPTION	ICON	REMARKS
Incident Type: Entity Symbol Set: 40 Value: **11**0000	N/A	Reserved for hierarchical purposes.
Criminal Activity Incident Type: Entity Type Entity: Incident Symbol Set: 40 Value: 11**01**00 Icon Type: Full Octagon		N/A
Arrest/Apprehend/Detain Type: Entity Subtype Entity: Incident/Criminal Activity Incident Symbol Set: 40 Value: 1101**01** Icon Type: Full Octagon		N/A
Arson Type: Entity Subtype Entity/Entity Type: Incident/Criminal Activity Incident Symbol Set: 40 Value: 1101**02** Icon Type: Full Octagon		N/A
Drive-By Shooting Type: Entity Subtype Entity/Entity Type: Incident/Criminal Activity Incident Symbol Set: 40 Value: 1101**04** Icon Type: Full Octagon		N/A

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE I-III. Activities icons - Continued.

DESCRIPTION	ICON	REMARKS
Extortion Type: Entity Subtype Entity/Entity Type: Incident/Criminal Activity Incident Symbol Set: 40 Value: 1101**06** Icon Type: Full Octagon		N/A
Graffiti Type: Entity Subtype Entity/Entity Type: Incident/Criminal Activity Incident Symbol Set: 40 Value: 1101**07** Icon Type: Full Octagon		N/A
Killing Type: Entity Subtype Entity/Entity Type: Incident/Criminal Activity Incident Symbol Set: 40 Value: 1101**08** Icon Type: Main		N/A
Poisoning Type: Entity Subtype Entity/Entity Type: Incident/Criminal Activity Incident Symbol Set: 40 Value: 1101**09** Icon Type: Full Octagon		N/A
Civil Rioting Type: Entity Subtype Entity/Entity Type: Incident/Criminal Activity Incident Symbol Set: 40 Value: 1101**10** Icon Type: Main		N/A
Booby Trap Type: Entity Subtype Entity/Entity Type: Incident/Criminal Activity Incident Symbol Set: 40 Value: 1101**11** Icon Type: Full Octagon		N/A


Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE I-III. Activities icons - Continued.

DESCRIPTION	ICON	REMARKS
Black Marketing Type: Entity Subtype Entity/Entity Type: Incident/Criminal Activity Incident Symbol Set: 40 Value: 110113 Icon Type: Full Octagon		N/A
Vandalism/Loot/Ransack/Plunder Type: Entity Subtype Entity/Entity Type: Incident/Criminal Activity Incident Symbol Set: 40 Value: 110114 Icon Type: Full Octagon		N/A
Jail Break Type: Entity Subtype Entity/Entity Type: Incident/Criminal Activity Incident Symbol Set: 40 Value: 110115 Icon Type: Full Octagon		N/A
Robbery Type: Entity Subtype Entity/Entity Type: Incident/Criminal Activity Incident Symbol Set: 40 Value: 110116 Icon Type: Main		N/A
Theft Type: Entity Subtype Entity/Entity Type: Incident/Criminal Activity Incident Symbol Set: 40 Value: 110117 Icon Type: Main		N/A
Burglary Type: Entity Subtype Entity/Entity Type: Incident/Criminal Activity Incident Symbol Set: 40 Value: 110118 Icon Type: Main		N/A




Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE I-III. Activities icons - Continued.

DESCRIPTION	ICON	REMARKS
Smuggling Type: Entity Subtype Entity/Entity Type: Incident/Criminal Activity Incident Symbol Set: 40 Value: 1101**19** Icon Type: Main		N/A
Rock Throwing Type: Entity Subtype Entity/Entity Type: Incident/Criminal Activity Incident Symbol Set: 40 Value: 1101**20** Icon Type: Full Octagon		N/A
Dead Body Type: Entity Subtype Entity/Entity Type: Incident/Criminal Activity Incident Symbol Set: 40 Value: 1101**21** Icon Type: Full Octagon		N/A
Sabotage Type: Entity Subtype Entity/Entity Type: Incident/Criminal Activity Incident Symbol Set: 40 Value: 1101**22** Icon Type: Main		N/A
Suspicious Activity Type: Entity Subtype Entity/Entity Type: Incident/Criminal Activity Incident Symbol Set: 40 Value: 1101**23** Icon Type: Full Octagon		N/A
Bomb/Bombing Type: Entity Type Entity: Incident Symbol Set: 40 Value: 11**02**00 Icon Type: Main		N/A




Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE I-III. Activities icons - Continued.

DESCRIPTION	ICON	REMARKS
Bomb Threat Type: Entity Subtype Entity/Entity Type: Incident/Bomb/Bombing Symbol Set: 40 Value: 1102**01** Icon Type: Full Octagon		N/A
IED Event Type: Entity Type Entity: Incident Symbol Set: 40 Value: 11**03**00 Icon Type: Main		N/A
IED Explosion Type: Entity Subtype Entity/Entity Type: Incident/IED Event Symbol Set: 40 Value: 1103**01** Icon Type: Full Octagon		N/A
Premature IED Explosion Type: Entity Subtype Entity/Entity Type: Incident/IED Event Symbol Set: 40 Value: 1103**02** Icon Type: Full Octagon		N/A
IED Cache Type: Entity Subtype Entity/Entity Type: Incident/IED Event Symbol Set: 40 Value: 1103**03** Icon Type: Full Frame		The gray box is not to be drawn. It is shown here only as a reference to position and proportion of the icon within the frame.
IED Suicide Bomber Type: Entity Subtype Entity/Entity Type: Incident/IED Event Symbol Set: 40 Value: 1103**04** Icon Type: Full Octagon		N/A
Shooting Type: Entity Type Entity: Incident Symbol Set: 40 Value: 11**04**00 Icon Type: Full Octagon		N/A




Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE I-III. Activities icons - Continued.

DESCRIPTION	ICON	REMARKS
Sniping Type: Entity Subtype Entity/Entity Type: Incident/Shooting Symbol Set: 40 Value: 1104**01** Icon Type: Full Octagon		N/A
Illegal Drug Operation Type: Entity Type Entity: Incident Symbol Set: 40 Value: 11**05**00 Icon Type: Main		N/A
Trafficking Type: Entity Subtype Entity/Entity Type: Incident/Illegal Drug Operation Symbol Set: 40 Value: 1105**01** Icon Type: Full Octagon		N/A
Illegal Drug Lab Type: Entity Subtype Entity/Entity Type: Incident/Illegal Drug Operation Symbol Set: 40 Value: 1105**02** Icon Type: Full Octagon		N/A
Explosion Type: Entity Type Entity: Incident Symbol Set: 40 Value: 11**06**00 Icon Type: Full Octagon		N/A
Grenade Explosion Type: Entity Subtype Entity: Incident/Explosion Symbol Set: 40 Value: 1106**01** Icon Type: Full Octagon		N/A
Incendiary Explosion Type: Entity Subtype Entity: Incident/Explosion Symbol Set: 40 Value: 1106**02** Icon Type: Full Octagon		N/A




Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE I-III. Activities icons - Continued.

DESCRIPTION	ICON	REMARKS
Mine Explosion Type: Entity Subtype Entity: Incident/Explosion Symbol Set: 40 Value: 110**03** Icon Type: Full Octagon		N/A
Mortar Fire Explosion Type: Entity Subtype Entity: Incident/Explosion Symbol Set: 40 Value: 110**04** Icon Type: Full Octagon		N/A
Rocket Explosion Type: Entity Subtype Entity: Incident/Explosion Symbol Set: 40 Value: 110**05** Icon Type: Full Octagon		N/A
Bomb Explosion Type: Entity Subtype Entity: Incident/Explosion Symbol Set: 40 Value: 110**06** Icon Type: Full Octagon		N/A
Home/House Type: Entity Type Entity/Entity Type: Incident Symbol Set: 40 Value: 11**07**00 Icon Type: Main		N/A
Civil Disturbance Type: Entity Symbol Set: 40 Value: **12**0000 Icon Type: Full Octagon		
Demonstration Type: Entity Type Entity/Entity Type: Civil Disturbance Symbol Set: 40 Value: 12**01**00 Icon Type: Main		N/A



Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE I-III. Activities icons - Continued.

DESCRIPTION	ICON	REMARKS
Operation Type: Entity Symbol Set: 40 Value: **13**0000	N/A	Reserved for hierarchical purposes.
Patrolling Type: Entity Type Entity: Operation Symbol Set: 40 Value: 13**01**00 Icon Type: Full Octagon		N/A
Military Information Support Operation (MISO) Type: Entity Type Entity: Operation Symbol Set: 40 Value: 13**02**00 Icon Type: Full Octagon		N/A
TV and Radio Propaganda Type: Entity Subtype Entity/Entity Type: Operation/MISO Operation Symbol Set: 40 Value: 1302**01** Icon Type: Full Frame		The gray box is not to be drawn. It is shown here only as a reference to position and proportion of the icon within the frame.
Foraging/Searching Type: Entity Type Entity: Operation Symbol Set: 40 Value: 13**03**00 Icon Type: Full Octagon		N/A
Recruitment Type: Entity Type Entity: Operation Symbol Set: 40 Value: 13**04**00	N/A	Reserved for hierarchical purposes.
Willing Type: Entity Subtype Entity/Entity Type: Operation/Recruitment Symbol Set: 40 Value: 1304**01** Icon Type: Full Octagon		N/A



Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE I-III. Activities icons - Continued.

DESCRIPTION	ICON	REMARKS
Unwilling/Coerced Type: Entity Subtype Entity/Entity Type: Operation/Recruitment Symbol Set: 40 Value: 130**402** Icon Type: Full Octagon		N/A
Mine Laying Type: Entity Type Entity: Operation Symbol Set: 40 Value: 13**05**00 Icon Type: Main		N/A
Spy Type: Entity Type Entity: Operation Symbol Set: 40 Value: 13**06**00 Icon Type: Main		N/A
Warrant Served Type: Entity Type Entity: Operation Symbol Set: 40 Value: 13**07**00 Icon Type: Main		N/A
Exfiltration Type: Entity Type Entity: Operation Symbol Set: 40 Value: 13**08**00 Icon Type: Full Octagon		N/A
Infiltration Type: Entity Type Entity: Operation Symbol Set: 40 Value: 13**09**00 Icon Type: Full Octagon		N/A
Meeting Type: Entity Type Entity: Operation Symbol Set: 40 Value: 13**10**00 Icon Type: Full Octagon		N/A


Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE I-III. Activities icons - Continued.

DESCRIPTION	ICON	REMARKS
Polling Place/Election Type: Entity Type Entity: Operation/Meeting Symbol Set: 40 Value: 1310**01** Icon Type: Main		N/A
Emergency Operation Type: Entity Type Entity: Operation Symbol Set: 40 Value: 13**12**00 Icon Type: Full Octagon		N/A
Emergency Collection Evacuation Point Type: Entity Subtype Entity/Entity Type: Operation/Emergency Operation Symbol Set: 40 Value: 1312**01** Icon Type: Full Octagon		N/A
Emergency Food Distribution Type: Entity Type Entity: Operation Symbol Set: 40 Value: 1312**02** Icon Type: Full Frame		The gray box is not to be drawn. It is shown here only as a reference to position and proportion of the icon within the frame.
Emergency Incident Command Center Type: Entity Subtype Entity/Entity Type: Operation/Emergency Operation Symbol Set: 40 Value: 1312**03** Icon Type: Full Octagon		N/A
Emergency Operations Center Type: Entity Subtype Entity/Entity Type: Operation/Emergency Operation Symbol Set: 40 Value: 1312**04** Icon Type: Full Octagon		N/A



Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE I-III. Activities icons - Continued.

DESCRIPTION	ICON	REMARKS
Emergency Public Information Center Type: Entity Subtype Entity/Entity Type: Operation/Emergency Operation Symbol Set: 40 Value: 1312**05** Icon Type: Full Octagon		N/A
Emergency Shelter Type: Entity Subtype Entity/Entity Type: Operation/Emergency Operation Symbol Set: 40 Value: 1312**06** Icon Type: Full Octagon		N/A
Emergency Staging Area Type: Entity Subtype Entity/Entity Type: Operation/Emergency Operation Symbol Set: 40 Value: 1312**07** Icon Type: Full Octagon		N/A
Emergency Water Distribution Center Type: Entity Subtype Entity/Entity Type: Operation/Emergency Operation Symbol Set: 40 Value: 1312**08** Icon Type: Full Frame		The gray box is not to be drawn. It is shown here only as a reference to position and proportion of the icon within the frame.
Emergency Medical Operations Type: Entity Type Entity: Operation Symbol Set: 40 Value: 13**13**00 Icon Type: Full Octagon		N/A
EMT Station Location Type: Entity Subtype Entity/Entity Type: Operation/Emergency Medical Operation Symbol Set: 40 Value: 1313**01** Icon Type: Full Octagon		N/A


Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE I-III. Activities icons - Continued.

DESCRIPTION	ICON	REMARKS
Health Department Facility Type: Entity Subtype Entity/Entity Type: Operation/Emergency Medical Operation Symbol Set: 40 Value: 131**02** Icon Type: Full Octagon		N/A
Medical Facilities Outpatient Type: Entity Subtype Entity/Entity Type: Operation/Emergency Medical Operation Symbol Set: 40 Value: 131**03** Icon Type: Full Octagon		N/A
Morgue Type: Entity Subtype Entity/Entity Type: Operation/Emergency Medical Operation Symbol Set: 40 Value: 131**04** Icon Type: Full Octagon		N/A
Pharmacy Type: Entity Subtype Entity/Entity Type: Operation/Emergency Medical Operation Symbol Set: 40 Value: 131**05** Icon Type: Full Octagon		N/A
Triage Type: Entity Subtype Entity/Entity Type: Operation/Emergency Medical Operation Symbol Set: 40 Value: 131**06** Icon Type: Full Octagon		N/A
Fire Fighting Operation Type: Entity Type Entity: Operation Symbol Set: 40 Value: 13**14**00 Icon Type: Main		N/A


Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE I-III. Activities icons - Continued.

DESCRIPTION	ICON	REMARKS
Fire Hydrant Type: Entity Subtype Entity/Entity Type: Operation/Fire Fighting Operation Symbol Set: 40 Value: 1314**01** Icon Type: Full Octagon		N/A
Other Water Supply Location Type: Entity Type Entity/Entity Type: Operation/Fire Fighting Operation Symbol Set: 40 Value: 1314**03** Icon Type: Full Octagon		N/A
Law Enforcement Operation Type: Entity Type Entity: Operation Symbol Set: 40 Value: 13**15**00 Icon Type: Full Octagon		N/A
Bureau of Alcohol, Tobacco, Firearms and Explosives (ATF) (Department of Justice) Type: Entity Subtype Entity/Entity Type: Operation/Law Enforcement Operation Symbol Set: 40 Value: 1315**01** Icon Type: Main		N/A
Border Patrol Type: Entity Subtype Entity/Entity Type: Operation/Law Enforcement Operation Symbol Set: 40 Value: 1315**02** Icon Type: Full Octagon		N/A
Customs Service Type: Entity Subtype Entity/Entity Type: Operation/Law Enforcement Operation Symbol Set: 40 Value: 1315**03** Icon Type: Full Octagon		N/A

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE I-III. Activities icons - Continued.

DESCRIPTION	ICON	REMARKS
Drug Enforcement Administration (DEA) Type: Entity Subtype Entity/Entity Type: Operation/Law Enforcement Operation Symbol Set: 40 Value: 131**04** Icon Type: Main		N/A
Department of Justice (DOJ) Type: Entity Subtype Entity/Entity Type: Operation/Law Enforcement Operation Symbol Set: 40 Value: 131**05** Icon Type: Full Octagon		N/A
Federal Bureau of Investigations (FBI) Type: Entity Subtype Entity/Entity Type: Operation/Law Enforcement Operation Symbol Set: 40 Value: 131**06** Icon Type: Main		N/A
Police Type: Entity Subtype Entity/Entity Type: Operation/Law Enforcement Operation Symbol Set: 40 Value: 131**07** Icon Type: Main		N/A
Prison Type: Entity Subtype Entity/Entity Type: Operation/Law Enforcement Operation Symbol Set: 40 Value: 131**08** Icon Type: Full Octagon		N/A
United States Secret Service (USSS) Type: Entity Subtype Entity/Entity Type: Operation/Law Enforcement Operation Symbol Set: 40 Value: 131**09** Icon Type: Main		N/A

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE I-III. Activities icons - Continued.

DESCRIPTION	ICON	REMARKS
Transportation Security Administration (TSA) Type: Entity Subtype Entity/Entity Type: Operation/Law Enforcement Operation Symbol Set: 40 Value: 131**10** Icon Type: Main		N/A
US Coast Guard Type: Entity Subtype Entity/Entity Type: Operation/Law Enforcement Operation Symbol Set: 40 Value: 131**11** Icon Type: Full Octagon		N/A
US Marshals Service Type: Entity Subtype Entity/Entity Type: Operation/Law Enforcement Operation Symbol Set: 40 Value: 131**12** Icon Type: Full Octagon		N/A
Internal Security Force Type: Entity Subtype Entity/Entity Type: Operation/Law Enforcement Operation Symbol Set: 40 Value: 131**13** Icon Type: Main		N/A
Fire Event Type: Entity Symbol Set: 40 Value: **14**0000 Icon Type: Full Octagon		N/A
Fire Origin Type: Entity Type Entity/Entity Type: Fire Event Symbol Set: 40 Value: 14**01**00 Icon Type: Full Octagon		N/A


Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE I-III. Activities icons - Continued.

DESCRIPTION	ICON	REMARKS
Smoke Type: Entity Type Entity/Entity Type: Fire Event Symbol Set: 40 Value: 140200 Icon Type: Full Octagon		N/A
Hot Spot Type: Entity Type Entity/Entity Type: Fire Event Symbol Set: 40 Value: 140300 Icon Type: Full Octagon		N/A
Non-Residential Fire Type: Entity Type Entity/Entity Type: Fire Event Symbol Set: 40 Value: 140400 Icon Type: Full Octagon		N/A
Residential Fire Type: Entity Type Entity/Entity Type: Fire Event Symbol Set: 40 Value: 140500 Icon Type: Full Octagon		N/A
School Fire Type: Entity Type Entity/Entity Type: Fire Event Symbol Set: 40 Value: 140600 Icon Type: Full Octagon		N/A
Special Needs Fire Type: Entity Type Entity/Entity Type: Fire Event Symbol Set: 40 Value: 140700 Icon Type: Full Octagon		N/A
Wildfire Type: Entity Subtype Entity/Entity Type: Incident/Fire Event Symbol Set: 40 Value: 140800 Icon Type: Full Octagon		N/A

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE I-III. Activities icons - Continued.

DESCRIPTION	ICON	REMARKS
Hazardous Materials Type: Entity Symbol Set: 40 Value: **15**0000	N/A	Reserved for hierarchical purposes.
Hazardous Materials Incident Type: Entity Type Entity: Incident Symbol Set: 40 Value: 15**01**00 Icon Type: Full Octagon		N/A
Chemical Agent Type: Entity Subtype Entity/Entity Type: Hazardous Materials /Hazardous Materials Incident Symbol Set: 40 Value: 150101 Icon Type: Full Octagon		N/A
Corrosive Material Type: Entity Subtype Entity/Entity Type: Hazardous Materials /Hazardous Materials Incident Symbol Set: 40 Value: 150102 Icon Type: Full Octagon		N/A
Hazardous When Wet Type: Entity Subtype Entity/Entity Type: Hazardous Materials /Hazardous Materials Incident Symbol Set: 40 Value: 150103 Icon Type: Full Octagon		N/A
Explosive Material Type: Entity Subtype Entity/Entity Type: Hazardous Materials /Hazardous Materials Incident Symbol Set: 40 Value: 150104 Icon Type: Full Octagon		N/A

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE I-III. Activities icons - Continued.

DESCRIPTION	ICON	REMARKS
Flammable Gas Type: Entity Subtype Entity/Entity Type: Hazardous Materials /Hazardous Materials Incident Symbol Set: 40 Value: 150105 Icon Type: Full Octagon		N/A
Flammable Liquid Type: Entity Subtype Entity/Entity Type: Hazardous Materials /Hazardous Materials Incident Symbol Set: 40 Value: 150106 Icon Type: Full Octagon		N/A
Flammable Solid Type: Entity Subtype Entity/Entity Type: Hazardous Materials /Hazardous Materials Incident Symbol Set: 40 Value: 150107 Icon Type: Full Octagon		N/A
Non-Flammable Gas Type: Entity Subtype Entity/Entity Type: Hazardous Materials /Hazardous Materials Incident Symbol Set: 40 Value: 150108 Icon Type: Full Octagon		N/A
Organic Peroxide Type: Entity Subtype Entity/Entity Type: Hazardous Materials /Hazardous Materials Incident Symbol Set: 40 Value: 150109 Icon Type: Full Octagon		N/A
Oxidizer Type: Entity Subtype Entity/Entity Type: Hazardous Materials /Hazardous Materials Incident Symbol Set: 40 Value: 150110 Icon Type: Full Octagon		N/A






Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE I-III. Activities icons - Continued.

DESCRIPTION	ICON	REMARKS
Radioactive Material Type: Entity Subtype Entity/Entity Type: Hazardous Materials /Hazardous Materials Incident Symbol Set: 40 Value: 150**11** Icon Type: Full Octagon		N/A
Spontaneously Combustible Material Type: Entity Subtype Entity/Entity Type: Hazardous Materials /Hazardous Materials Incident Symbol Set: 40 Value: 150**12** Icon Type: Full Octagon		N/A
Toxic Gas Type: Entity Subtype Entity/Entity Type: Hazardous Materials /Hazardous Materials Incident Symbol Set: 40 Value: 150**13** Icon Type: Full Octagon		N/A
Toxic Infectious Material Type: Entity Subtype Entity/Entity Type: Incident/Hazardous Materials Incident Symbol Set: 40 Value: 150**14** Icon Type: Full Octagon		N/A
Unexploded Ordnance Type: Entity Subtype Entity/Entity Type: Incident/Hazardous Materials Incident Symbol Set: 40 Value: 150**15** Icon Type: Full Octagon		N/A
Transportation Incident Type: Entity Symbol Set: 40 Value: **16**0000 Icon Type: Full Octagon	N/A	Reserved for hierarchical purposes.



Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE I-III. Activities icons - Continued.

DESCRIPTION	ICON	REMARKS
Air Type: Entity Type Entity: Transportation Incident Symbol Set: 40 Value: 16**01**00 Icon Type: Main		N/A
Marine Type: Entity Type Entity: Transportation Incident Symbol Set: 40 Value: 16**02**00 Icon Type: Main		N/A
Rail Type: Entity Type Entity: Transportation Incident Symbol Set: 40 Value: 16**03**00 Icon Type: Main		N/A
Vehicle Type: Entity Type Entity: Transportation Incident Symbol Set: 40 Value: 16**04**00 Icon Type: Main		N/A
Wheeled Vehicle Explosion Type: Entity Type Entity: Transportation Incident Symbol Set: 40 Value: 16**05**00 Icon Type: Full Octagon		N/A
Natural Event Type: Entity Symbol Set: 40 Value: **1**70000 Icon Type: Main	N/A	Reserved for hierarchical purposes.
Geologic Type: Entity Type Entity: Natural Event Symbol Set: 40 Value: 17**01**00 Icon Type: Main	N/A	Reserved for hierarchical purposes.


Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE I-III. Activities icons - Continued.

DESCRIPTION	ICON	REMARKS
Aftershock Type: Entity Subtype Entity/Entity Type: Natural Event/Geologic Symbol Set: 40 Value: 170101 Icon Type: Full Octagon		N/A
Avalanche Type: Entity Subtype Entity/Entity Type: Natural Event/Geologic Symbol Set: 40 Value: 170102 Icon Type: Full Octagon		N/A
Earthquake Epicenter Type: Entity Subtype Entity/Entity Type: Natural Event/Geologic Symbol Set: 40 Value: 170103 Icon Type: Full Octagon		N/A
Landslide Type: Entity Subtype Entity/Entity Type: Natural Event/Geologic Symbol Set: 40 Value: 170104 Icon Type: Full Octagon		N/A
Subsidence Type: Entity Subtype Entity/Entity Type: Natural Event/Geologic Symbol Set: 40 Value: 170105 Icon Type: Full Octagon		N/A
Volcanic Eruption Type: Entity Subtype Entity/Entity Type: Natural Event/Geologic Symbol Set: 40 Value: 170106 Icon Type: Full Octagon		N/A
Volcanic Threat Type: Entity Subtype Entity/Entity Type: Natural Event/Geologic Symbol Set: 40 Value: 170107 Icon Type: Full Octagon		N/A


Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE I-III. Activities icons - Continued.

DESCRIPTION	ICON	REMARKS
Cave Entrance Type: Entity Subtype Entity/Entity Type: Natural Event/Geologic Symbol Set: 40 Value: 170108 Icon Type: Full Octagon		N/A
Hydro-Meteorological Type: Entity Type Entity: Natural Event Symbol Set: 40 Value: 170200 Icon Type: Main	N/A	Reserved for hierarchical purposes.
Drought Type: Entity Subtype Entity/Entity Type: Natural Event/Hydro-Meteorological Symbol Set: 40 Value: 170201 Icon Type: Full Octagon		N/A
Flood Type: Entity Subtype Entity/Entity Type: Natural Event/Hydro-Meteorological Symbol Set: 40 Value: 170202 Icon Type: Full Octagon		N/A
Tsunami Type: Entity Subtype Entity/Entity Type: Natural Event/Hydro-Meteorological Symbol Set: 40 Value: 170203 Icon Type: Full Octagon		N/A
Infestation Type: Entity Type Entity: Natural Event Symbol Set: 40 Value: 170300 Icon Type: Main	N/A	Reserved for hierarchical purposes.


Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE I-III. Activities icons - Continued.

DESCRIPTION	ICON	REMARKS
Bird Type: Entity Subtype Entity/Entity Type: Natural Event/Infestation Symbol Set: 40 Value: 170301 Icon Type: Full Octagon		N/A
Insect Type: Entity Subtype Entity/Entity Type: Natural Event/Infestation Symbol Set: 40 Value: 170302 Icon Type: Full Octagon		N/A
Microbial Type: Entity Subtype Entity/Entity Type: Natural Event/Infestation Symbol Set: 40 Value: 170303 Icon Type: Full Octagon		N/A
Reptile Type: Entity Subtype Entity/Entity Type: Natural Event/Infestation Symbol Set: 40 Value: 170304 Icon Type: Full Octagon		N/A
Rodent Type: Entity Subtype Entity/Entity Type: Natural Event/Infestation Symbol Set: 40 Value: 170305 Icon Type: Full Octagon		N/A
Individual Type: Entity Symbol Set: 40 Value: 180000	N/A	Reserved for hierarchical purposes.
Religious Leader Type: Entity Type Entity: Individual Symbol Set: 40 Value: 180100 Icon Type: Full Octagon		N/A






Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE I-III. Activities icons - Continued.

DESCRIPTION	ICON	REMARKS
Speaker Type: Entity Type Entity: Individual Symbol Set: 40 Value: 18**02**00 Icon Type: Full Octagon		N/A









I.6.3 Activities sector 1 modifiers. Activities sector 1 modifiers denote crime, military information support operations, IED and incident qualifier categories. Table I-IV lists activities sector 1 modifiers and illustrates their placement within the bounding octagon. Additional sector 1 modifiers, where required, are included in table B-I and are accessed using the modifier extension flag.

TABLE I-IV. Activities sector 1 modifiers.

DESCRIPTION	CATEGORY	MODIFIER	REMARKS
House-To-House Symbol Set: 40 Value: 04	Military Information Support Operations		N/A
Murder Symbol Set: 40 Value: 06	Crime		N/A
Written Military Information Support Operations Symbol Set: 40 Value: 09	Military Information Support Operations		N/A
Pirate Symbol Set: 40 Value: 10	Crime		N/A
False Symbol Set: 40 Value: 11	IED Category		N/A

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE I-IV. Activities sector 1 modifiers - Continued.

DESCRIPTION	CATEGORY	MODIFIER	REMARKS
Find Symbol Set: 40 Value: 12	IED Category		N/A
Found and Cleared Symbol Set: 40 Value: 13	IED Category		N/A
Hoax (Decoy) Symbol Set: 40 Value: 14	IED Category		N/A
Attempted Symbol Set: 40 Value: 15	Incident Qualifier		N/A
Incident Symbol Set: 40 Value: 17	Incident Qualifier		N/A
Theft Symbol Set: 40 Value: 18	Crime		N/A
Eviction Symbol Set: 40 Value: 21	Incident Qualifier		N/A
Raid Symbol Set: 40 Value: 22	Incident Qualifier		N/A

I.6.4 Activities sector 2 modifiers. Activities sector 2 modifiers denote capability category. Additional sector 2 modifiers, where required, are included in table B-II and are accessed using the modifier extension flag. There are currently no activities sector 2 modifiers.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

PAGE INTENTIONALLY LEFT BLANK

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

SIGNALS INTELLIGENCE SYMBOLS

J.1 SCOPE

J.1.1 Scope. This appendix addresses symbols that support signals intelligence (SIGINT) in the C2 domain. The tables in this appendix present the icons and modifiers for the SIGINT symbol sets. The information contained herein is intended for compliance.

J.2 APPLICABLE DOCUMENTS

Specific documents in 2.2 of this standard apply to this appendix.

J.3 DEFINITIONS

The definitions in section 3 of this standard apply to this appendix.

J.4 GENERAL REQUIREMENTS

J.4.1 Organization. This appendix contains technical specifications, a symbol coding scheme, a symbology hierarchy and SIGINT symbology.

J.5 DETAILED REQUIREMENTS

J.5.1 Technical specifications. Composition, construction and display of symbols are explained in the detailed requirements section of the standard.

J.5.2 Symbol identification coding scheme. A symbol identification code (SIDC) is a numeric string that may be used to provide the unique identifier necessary to display or exchange symbol information between MIL-STD-2525 compliant systems. Refer to Appendix A for SIDC positions and descriptions.

J.5.3 Composition of SIGINT symbols. A standard method for constructing symbols is presented. Refer to 5.3.10 for an explanation of symbol composition. Figure J-1 shows an example of a SIGINT symbol.








FIGURE J-1. Signals intelligence symbol components.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

J.5.3.1 Symbol building process. Table J-1 depicts the symbol building process for SIGINT symbols. The process is identical for icons and modifiers requiring the vertical bounding octagon.

TABLE J-I. Signal intelligences symbol building process.

STEP	DESCRIPTION	EXAMPLE
1.	Choose the frame that matches the dimension of the object from the appropriate column in tables I, II, or III and standard identity (table A-II). In this example, the dimension is space, and the standard identity is friend. The example depicts a “friendly space track.”	
2.	Choose an icon for the main sector of the bounding octagon. In this example, the icon is “radar,” a SIGINT entity type. The example depicts a “friendly space radar.”	
3.	If required, choose a modifier to depict an additional characteristic of the icon. In this example, the modifier is “data transmission,” a sector 1 modifier. The example depicts a “friendly space radar with data transmission capability.” **Note**: There are no sector 2 modifiers in SIGINT symbols.	
4.	The finished symbol will appear as shown in the example.	

J.5.4 Icons and modifiers. All icons shall be placed within the main sector of the bounding octagon (see table J-I). When depicted, modifiers shall be placed in sector 1 as appropriate (see table J-I). There are no sector 2 modifiers in SIGINT. Only one modifier may be placed in each sector at a given time. Multiple modifiers in the same position are prohibited due to legibility concerns.

J.5.5 Amplifiers. The display of additional alphanumerical and graphical information on identity, movement and location and capabilities of a SIGINT symbol is dependent on the dimension of that symbol. A SIGINT symbol may be in the space, air, land equipment, sea surface, or sea subsurface dimension. For example, if the SIGINT symbol is in the space dimension, then that symbol shall follow the amplifier requirements as stated in the space appendix. See 5.3.7 for more information on amplifiers.




Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

J.6 SIGINT SYMBOLS

J.6.1 SIGINT symbols. This section includes the lists of icons and modifiers for building SIGINT symbols.


J.6.2 SIGINT icons. Table J-II depicts SIGINT icons.

TABLE J-II. Signals intelligence icons.

DESCRIPTION	ICON	REMARKS
Signal Intercept Type: Entity Symbol Set: 50 Value: **11**0000	N/A	Reserved for hierarchical purposes.
Communications Type: Entity Type Entity: Signal Intercept Symbol Set: 50 Value: 11**01**00 Icon Type: Main		N/A
Jammer Type: Entity Type Entity: Signal Intercept Symbol Set: 50 Value: 11**02**00 Icon Type: Main		N/A
Radar Type: Entity Type Entity: Signal Intercept Symbol Set: 50 Value: 11**03**00 Icon Type: Main		N/A










J.6.3 SIGINT sector 1 modifiers. The SIGINT sector 1 modifiers denote communications and radar categories. Table J-III lists SIGINT sector 1 modifiers and illustrates their placement within the bounding octagon. Additional sector 1 modifiers, where required, are included in table B-I and are accessed using the modifier extension flag.

TABLE J-III. Signals intelligence sector 1 modifiers.

DESCRIPTION	CATEGORY	MODIFIER	REMARKS
Anti-Aircraft Fire Control Symbol Set: 50 Value: 01	Land/Sea Surface Radar		N/A










Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE J-III. Signals intelligence sector 1 modifiers - Continued.

DESCRIPTION	CATEGORY	MODIFIER	REMARKS
Airborne Search and Bombing Symbol Set: 50 Value: 02	Air Radar		N/A
Airborne Intercept Symbol Set: 50 Value: 03	Air Radar		N/A
Altimeter Symbol Set: 50 Value: 04	Air Radar		N/A
Airborne Reconnaissance and Mapping Symbol Set: 50 Value: 05	Air Radar		N/A
Air Traffic Control Symbol Set: 50 Value: 06	Air/Land/Sea Surface Radar		N/A
Beacon Transponder (Not IFF) Symbol Set: 50 Value: 07	Air/Land/Sea Surface/Sea Subsurface Radar		N/A
Battlefield Surveillance Symbol Set: 50 Value: 08	Air/Land Radar		N/A
Controlled Approach Symbol Set: 50 Value: 09	Land/Sea Surface Radar		N/A
Controlled Intercept Symbol Set: 50 Value: 10	Air/Land/Sea Surface Radar		N/A










Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE J-III. Signals intelligence sector 1 modifiers - Continued.

DESCRIPTION	CATEGORY	MODIFIER	REMARKS
Cellular/Mobile Symbol Set: 50 Value: 11	Air/Land/Sea Surface/Sea Subsurface Communications		N/A
Coastal Surveillance Symbol Set: 50 Value: 12	Land Radar		N/A
Decoy/Mimic Symbol Set: 50 Value: 13	Air/Land/Sea Surface/Sea Subsurface Radar		N/A
Data Transmission Symbol Set: 50 Value: 14	Space/Air/Land/Sea Surface/Sea Subsurface Radar		N/A
Earth Surveillance Symbol Set: 50 Value: 15	Space Radar		N/A
Early Warning Symbol Set: 50 Value: 16	Air/Land/Sea Surface/Sea Subsurface Radar		N/A
Fire Control Symbol Set: 50 Value: 17	Air/Land/Sea Surface Radar		N/A
Ground Mapping Symbol Set: 50 Value: 18	Air Radar		N/A
Height Finding Symbol Set: 50 Value: 19	Land/Sea Surface Radar		N/A









Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE J-III. Signals intelligence sector 1 modifiers - Continued.

DESCRIPTION	CATEGORY	MODIFIER	REMARKS
Harbor Surveillance Symbol Set: 50 Value: 20	Land Radar		N/A
Identification, Friend or Foe (Interrogator) Symbol Set: 50 Value: 21	Space/Air/Land/Sea Surface/Sea Subsurface Radar		N/A
Instrument Landing System Symbol Set: 50 Value: 22	Land/Sea Surface Radar		N/A
Ionospheric Sounding Symbol Set: 50 Value: 23	Air/Land Radar		N/A
Identification, Friend or Foe (Transponder) Symbol Set: 50 Value: 24	Space/Air/Land/Sea Surface/Sea Subsurface Radar		N/A
Barrage Jammer Symbol Set: 50 Value: 25	Space/Air/Land/Sea Surface/Sea Subsurface Jammer		N/A
Click Jammer Symbol Set: 50 Value: 26	Space/Air/Land/Sea Surface/Sea Subsurface Jammer		N/A
Deceptive Jammer Symbol Set: 50 Value: 27	Space/Air/Land/Sea Surface/Sea Subsurface Jammer		N/A
Frequency Swept Jammer Symbol Set: 50 Value: 28	Space/Air/Land/Sea Surface/Sea Subsurface Jammer		N/A









Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE J-III. Signals intelligence sector 1 modifiers - Continued.

DESCRIPTION	CATEGORY	MODIFIER	REMARKS
Jammer (General) Symbol Set: 50 Value: 29	Space/Air/Land/Sea Surface/Sea Subsurface Jammer		N/A
Noise Jammer Symbol Set: 50 Value: 30	Space/Air/Land/Sea Surface/Sea Subsurface Jammer		N/A
Pulsed Jammer Symbol Set: 50 Value: 31	Space/Air/Land/Sea Surface/Sea Subsurface Jammer		N/A
Repeater Jammer Symbol Set: 50 Value: 32	Space/Air/Land/Sea Surface/Sea Subsurface Jammer		N/A
Spot Noise Jammer Symbol Set: 50 Value: 33	Space/Air/Land/Sea Surface/Sea Subsurface Jammer		N/A
Transponder Jammer Symbol Set: 50 Value: 34	Space/Air/Land/Sea Surface/Sea Subsurface Jammer		N/A
Missile Acquisition Symbol Set: 50 Value: 35	Air/Land/Sea Surface Radar		N/A
Missile Control Symbol Set: 50 Value: 36	Space/Air/Land/Sea Surface/Sea Subsurface Jammer		N/A









Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE J-III. Signals intelligence sector 1 modifiers - Continued.

DESCRIPTION	CATEGORY	MODIFIER	REMARKS
Missile Downlink Symbol Set: 50 Value: 37	Air Radar		N/A
Meteorological Symbol Set: 50 Value: 38	Air/Land/Sea Surface Radar		N/A
Multi-Function Symbol Set: 50 Value: 39	Space/Air/Land/Sea Surface/Sea Subsurface Jammer		Two or more of EW, TA, TT, MG, TI
Missile Guidance Symbol Set: 50 Value: 40	Air/Land/Sea Surface Radar		N/A
Missile Homing Symbol Set: 50 Value: 41	Air Radar		N/A
Missile Tracking Symbol Set: 50 Value: 42	Space/Air/Land/Sea Surface/Sea Subsurface Jammer		N/A
Navigational/General Symbol Set: 50 Value: 43	Space/Air/Land/Sea Surface/Sea Subsurface Jammer		N/A
Navigational/Distance Measuring Equipment Symbol Set: 50 Value: 44	Space/Air/Land/Sea Surface/Sea Subsurface Jammer		N/A









Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE J-III. Signals intelligence sector 1 modifiers - Continued.

DESCRIPTION	CATEGORY	MODIFIER	REMARKS
Navigational/Terrain Following Symbol Set: 50 Value: 45	Space/Air/Land/Sea Surface/Sea Subsurface Jammer		N/A
Navigational/Weather Avoidance Symbol Set: 50 Value: 46	Air/Land/Sea Surface/Sea Subsurface Jammer		N/A
Omni-Line of Sight (LOS) Symbol Set: 50 Value: 47	Air/Land/Sea Surface/Sea Subsurface Communications		N/A
Proximity Fuse Symbol Set: 50 Value: 48	Air Radar		N/A
Point-To-Point Line of Sight (LOS) Symbol Set: 50 Value: 49	Space/Air/Land/Sea Surface/Sea Subsurface Communications		N/A
Instrumentation Symbol Set: 50 Value: 50	Space/Air/Land/Sea Surface/Sea Subsurface Radar		N/A
Range Only Symbol Set: 50 Value: 51	Space/Air/Land/Sea Surface/Sea Subsurface Radar		N/A
Sonobuoy Symbol Set: 50 Value: 52	Sea Surface/Sea Subsurface Radar		N/A





Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE J-III. Signals intelligence sector 1 modifiers - Continued.

DESCRIPTION	CATEGORY	MODIFIER	REMARKS
Satellite Downlink Symbol Set: 50 Value: 53	Space Communications		N/A
Space Symbol Set: 50 Value: 54	Space/Air/Land/Sea Surface/Sea Subsurface Radar		N/A
Surface Search Symbol Set: 50 Value: 55	Space/Air/Land/Sea Surface/Sea Subsurface Radar		N/A
Shell Tracking Symbol Set: 50 Value: 56	Land Radar		N/A
Satellite Uplink Symbol Set: 50 Value: 57	Air/Land/Sea Surface/Sea Subsurface Communications		N/A
Target Acquisition Symbol Set: 50 Value: 58	Space/Air/Land/Sea Surface/Sea Subsurface Radar		N/A
Target Illumination Symbol Set: 50 Value: 59	Air/Land/Sea Surface Radar		N/A
Tropospheric Scatter Symbol Set: 50 Value: 60	Land Communications		N/A

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE J-III. Signals intelligence sector 1 modifiers - Continued.

DESCRIPTION	CATEGORY	MODIFIER	REMARKS
Target Tracking Symbol Set: 50 Value: 61	Space/Air/Land/Sea Surface/Sea Subsurface Radar		N/A
Unknown Symbol Set: 50 Value: 62	Space/Air/Land/Sea Surface/Sea Subsurface Radar		N/A
Video Remoting Symbol Set: 50 Value: 63	Space/Air/Land/Sea Surface/Sea Subsurface Radar		N/A
Experimental Symbol Set: 50 Value: 64	Space/Air/Land/Sea Surface/Sea Subsurface Radar		N/A

J.6.4 SIGINT sector 2 modifiers. The SIGINT sector 2 modifiers denote communications and radar categories. Additional sector 2 modifiers, where required, are included in table B-II and are accessed using the modifier extension flag. There are currently no sector 2 signal intelligence modifiers.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

PAGE INTENTIONALLY LEFT BLANK

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

CYBERSPACE SYMBOLS

K.1 SCOPE

K.1.1 Scope. This appendix addresses symbols that support cyberspace operations within the cyberspace symbol set. The tables in this appendix present the icons for organizations conducting operations within the virtual and physical cyberspace domain. The information contained herein is intended for compliance.

K.2 APPLICABLE DOCUMENTS

Specific documents in 2.2 of this standard apply to this appendix.

K.3 DEFINITIONS

The definitions in section 3 of this standard apply to this appendix.

K.4 GENERAL REQUIREMENTS

K.4.1 Organization. This appendix contains technical specifications, a symbol coding scheme, a symbology hierarchy and cyberspace symbology.

K.5 DETAILED REQUIREMENTS

K.5.1 Technical specifications. Composition, construction and display of symbols are explained in the detailed requirements section of the standard.

K.5.2 Symbol identification coding scheme. A symbol identification code (SIDC) is a numeric string that may be used to provide the unique identifier necessary to display or exchange symbol information between MIL-STD-2525 compliant systems. Refer to Appendix A for SIDC positions and descriptions.

K.5.3 Composition of cyberspace symbols. A standard method for constructing symbols is presented. Refer to 5.3.10 for an explanation of symbol composition. Figure K-1 shows an example of a cyberspace symbol.





FIGURE K-1. Cyberspace symbol components.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

K.5.3.1 Symbol building process. Table K-I depicts the symbol building process for cyberspace symbols. The process is identical for icons and modifiers requiring the vertical bounding octagon.

TABLE K-I. Cyberspace symbol building process.

STEP	DESCRIPTION	EXAMPLE
1.	Choose the frame that matches the dimension of the object from the appropriate column in tables I, II, or III and standard identity (table A-II). In this example, the dimension is cyberspace, and the standard identity is friend. The example depicts a “friendly virtual cyberspace.”	
2.	Choose an icon for the main sector of the bounding octagon. In this example, the icon is “cyber protection team,” a cyberspace entity type. The example depicts a “friendly cyber protection team.” Note: There are no modifiers in cyberspace symbols.	
3.	The finished symbol will appear as shown in the example.	

K.5.3.2 Icons and modifiers. All icons shall be placed within the main sector of the bounding octagon (see table K-I).

K.5.4 Amplifiers.

K.5.4.1 Text amplifiers. The purpose of the static text amplifiers described in this appendix is to standardize the display of additional alphanumerical information on identity, movement and location and capabilities. See 5.3.7 for more information on amplifiers. Figure K-2 shows the placement of space symbol amplifiers around the friend symbol frame. Table K-II provides descriptions and formats of each amplifier.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.




FIGURE K-2. Placement of cyberspace symbol amplifiers.

TABLE K-II. Descriptions and formats of cyberspace symbol amplifiers.

FIELD	FIELD TITLE	DESCRIPTION	FORMAT
A	Cyberspace Icon	The innermost part of a symbol, comprised of an icon and optional modifiers, that represents a joint military object (see 5.3.4).	
B	Echelon	A graphic amplifier in a unit symbol that identifies command level (see figure 14).	
D	Task Force Indicator	A graphic amplifier that identifies a unit or an activity symbol as a task force (see 5.3.7.4 and figure 14 in the base document).	
F	Reinforced or Reduced	A text amplifier in a unit symbol that displays (+) for reinforced, (-) for reduced, (±) reinforced and reduced.	
G	Staff Comments	A text amplifier for units, equipment, and installations; content is implementation specific.	
H	Additional Information	A text amplifier for units, equipment, and installations; content is implementation specific.	
K	Combat Effectiveness	A text amplifier for units and installations that indicates effectiveness. **The entries are:** fully operational (FO) substantially operational (SO) marginally operational (MO) not operational (NO) unknown (UNK)	
L	Signature Equipment	A text amplifier for hostile equipment; "**!**" indicates detectable electronic signatures.	
M	Higher Formation	A text amplifier for units that indicates number or title of higher echelon command (Corps is designated by Roman numerals).	
S	Headquarters Staff Indicator	A graphic amplifier for units, installations and activities that identifies them as a headquarters (see figure 4 and figure 14).	

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE K-II. Descriptions and formats of cyberspace symbol amplifiers - Continued.

FIELD	FIELD TITLE	DESCRIPTION	FORMAT
S2	Offset Location Indicator	A graphic amplifier used to indicate the offset or precise location of a single point symbol (see 5.3.7.5, 5.3.13, and figure 14).	
T	Unique Designation (Track Number)	A text amplifier for units, equipment and installations that uniquely identifies a particular symbol or track number.	Prefix = TN:##### **Example**: TN:13579
V	Type	A text amplifier for equipment that indicates types of equipment.	
W	Date-Time Group (DTG)	An alphanumeric designator for displaying a date-time group (DDHHMMSSZMONYYYY) or "O/O" for on order. The date-time group is composed of a group of six numeric digits with a time zone suffix and the standardized three-letter abbreviation for the month followed by four digits representing the year. The first pair of digits represents the day; the second pair, the hour; the third pair, the minutes. For automated systems, two digits may be added before the time zone suffix and after the minutes to designate seconds (see 5.3.7.8).	
Y	Location	A text amplifier for units, equipment and installations that displays a symbol's location in degrees, minutes and decimal minutes (or in MGRS, GARS, or other applicable display formats).	3317.0921N 04412.6332E 38SMB2649083145
AO	Engagement Bar	A graphic amplifier placed immediately atop the symbol. May denote : 1) local/remote status 2) engagement status 3) weapon type.	A:BBB:CC, where A = remote/local BBB = engagement status CC = weapon asset
AS	Country	A three-letter code that indicates the country of origin of the organization (US systems shall use GENC).	

K.5.4.2 Graphic amplifiers. Graphic amplifiers can be static, located in a fixed position in relation to a track's symbol, or dynamic and move about the symbol based on the track's characteristics. See 5.3.7 for more information on amplifiers, including examples of dynamic amplifiers.



Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

K.6 CYBERSPACE SYMBOLS

K.6.1 Cyberspace symbols. This section includes the lists of icons and modifiers for building cyberspace symbols.





K.6.2 Cyberspace icons. Table K-III depicts cyberspace icons.

TABLE K-III. Cyberspace icons.

DESCRIPTION	ICON	REMARKS
Cyberspace Unit Type: Entity Symbol Set: 60 Value: **11**0000	N/A	Reserved for hierarchical purposes.
Combat Mission Team Type: Entity Type Entity: Cyberspace Unit Symbol Set: 60 Value: 11**01**00 Icon Type: Main		N/A
National Mission Team Type: Entity Type Entity: Cyberspace Unit Symbol Set: 60 Value: 11**02**00 Icon Type: Main		N/A
Cyber Protection Team Type: Entity Type Entity: Cyberspace Unit Symbol Set: 60 Value: 11**03**00 Icon Type: Main		N/A
Defensive Cyberspace Operation Type: Entity Type Entity: Cyberspace Unit Symbol Set Value: 60 Value: 11**06**00 Icon Type: Main		N/A
Offensive Cyberspace Operation Type: Entity Type Entity: Cyberspace Unit Symbol Set Value: 60 Value: 11**07**00 Icon Type: Main		N/A






Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE K-III. Cyberspace icons - Continued.

DESCRIPTION	ICON	REMARKS
Internet Service Provider Type: Entity Type Entity: Cyberspace Unit Symbol Set Value: 60 Value: 11**08**00 Icon Type: Main		N/A
Security Type: Entity Type Entity: Cyberspace Unit Symbol Set Value: 60 Value: 11**09**00 Icon Type: Main		N/A
Operations Type: Entity Type Entity: Cyberspace Unit Symbol Set Value: 60 Value: 11**10**00 Icon Type: Main		N/A
Threat Actor Type: Entity Symbol Set Value: 60 Value: **12**0000 Icon Type: Main		N/A
Insider Type: Entity Type Entity: Cyberspace Threat Actor Symbol Set Value: 60 Value: 12**02**00 Icon Type: Main		N/A
Agent Type: Entity Symbol Set Value: 60 Value: **13**0000 Icon Type: Main	N/A	Reserved for hierarchical purposes.







Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE K-III. Cyberspace icons - Continued.

DESCRIPTION	ICON	REMARKS
Firewall Type: Entity Type Entity: Agent Symbol Set Value: 60 Value: 13**01**00 Icon Type: Main		N/A
Firmware Type: Entity Type Entity: Agent Symbol Set Value: 60 Value: 13**02**00 Icon Type: Main		N/A
Application Type: Entity Symbol Set Value: 60 Value: **14**0000 Icon Type: Main		White filed for visibility
Search Engine Type: Entity Type Entity: Application Symbol Set Value: 60 Value: 14**03**00 Icon Type: Main		N/A
Social Media Type: Entity Type Entity: Application Symbol Set Value: 60 Value: 14**04**00 Icon Type: Main		N/A
Threat Type: Entity Symbol Set Value: 60 Value: **15**0000 Icon Type: Main	N/A	Reserved for hierarchical purposes.





Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE K-III. Cyberspace icons - Continued.

DESCRIPTION	ICON	REMARKS
Malware Type: Entity Type Entity: Threat Symbol Set Value: 60 Value: 15**01**00 Icon Type: Main		N/A
Phishing Type: Entity Type Entity: Threat Symbol Set Value: 60 Value: 15**02**00 Icon Type: Main		N/A
Spear Phishing Type: Entity Type Entity: Threat Symbol Set Value: 60 Value: 15**03**00 Icon Type: Main		N/A
Whale Phishing Type: Entity Type Entity: Threat Symbol Set Value: 60 Value: 15**04**00 Icon Type: Main		N/A
Data Type: Entity Symbol Set Value: 60 Value: **16**0000 Icon Type: Main		N/A
Digital Currency Type: Entity Type Entity: Data Symbol Set Value: 60 Value: 16**01**00 Icon Type: Main		N/A






Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE K-III. Cyberspace icons - Continued.

DESCRIPTION	ICON	REMARKS
Persona Type: Entity Type Entity: Data Symbol Set Value: 60 Value: 16**02**00 Icon Type: Main		N/A
End Point Type: Entity Value: **1**70000 Icon Type: Main	N/A	Reserved for hierarchical purposes.
Server Type: Entity Type Entity: Endpoint Symbol Set Value: 60 Value: 17**01**00 Icon Type: Main		N/A
Workstation Type: Entity Type Entity: End Point Symbol Set Value: 60 Value: 17**02**00 Icon Type: Main		N/A
Portable Electronic Device (PED) Type: Entity Type Entity: End Point Value: 17**03**00 Icon Type: Main	N/A	Reserved for hierarchical purposes.
Smartphone Type: Entity Subtype Entity/Entity Subtype: End Point/Portable Electronic Device (PED) Symbol Set Value: 60 Value: 1703**01** Icon Type: Main		N/A






Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE K-III. Cyberspace icons - Continued.

DESCRIPTION	ICON	REMARKS
Tablet Type: Entity Subtype Entity: End Point/Portable Electronic Device (PED) Symbol Set Value: 60 Value: 170**302** Icon Type: Main		N/A
Laptop Type: Entity Subtype Entity/Entity Subtype: End Point/Portable Electronic Device (PED) Symbol Set Value: 60 Value: 170**303** Icon Type: Main		N/A
Health Monitor Type: Entity Subtype Entity/Entity Subtype: End Point/Portable Electronic Device (PED) Symbol Set Value: 60 Value: 170**304** Icon Type: Main		N/A
Smartvest Type: Entity Subtype Entity/Entity Subtype: End Point/Portable Electronic Device (PED) Symbol Set Value: 60 Value: 170**305** Icon Type: Main		N/A
Smartwatch Type: Entity Subtype Entity/Entity Subtype: End Point/Portable Electronic Device (PED) Symbol Set Value: 60 Value: 170**306** Icon Type: Main		N/A

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.









TABLE K-III. Cyberspace icons - Continued.

DESCRIPTION	ICON	REMARKS
Wearable Type: Entity Subtype Entity/Entity Subtype: End Point/Portable Electronic Device (PED) Symbol Set Value: 60 Value: 170**307** Icon Type: Main		N/A
Internet of Things Device Type: Entity Type Entity: End Point Symbol Set Value: 60 Value: 17**04**00 Icon Type: Main		N/A
Printer Type: Entity Type Entity: End Point Symbol Set Value: 60 Value: 17**05**00 Icon Type: Main		N/A
Router Type: Entity Type Entity: End Point Symbol Set Value: 60 Value: 17**06**00 Icon Type: Main		N/A
Switch Type: Entity Type Entity: End Point Symbol Set Value: 60 Value: 17**07**00 Icon Type: Main		N/A
Network Type: Entity Symbol Set Value: 60 Value: **18**0000 Icon Type: Main		N/A

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.







K.6.3 Cyberspace sector 1 modifiers. The cyberspace sector 1 modifiers denote capability and service categories. Table K-IV lists Cyberspace sector 1 modifiers and illustrates their placement within the bounding octagon. Additional sector 1 modifiers, where required, are included in table B-I and are accessed using the modifier extension flag.

TABLE K-IV. Cyberspace sector 1 modifiers.

DESCRIPTION	CATEGORY	MODIFIER	REMARKS
Defensive Cyberspace Symbol Set Value: 60 Value: 01	Capability		N/A
Offensive Cyberspace Symbol Set Value: 60 Value: 02	Capability		N/A
Social Symbol Set Value: 60 Value: 03	Capability		N/A
Wired Symbol Set Value: 60 Value: 04	Capability		 APP-06 version
Wireless Symbol Set Value: 60 Value: 05	Capability		N/A
Radio Frequency Symbol Set Value: 60 Value: 06	Capability		N/A
Operation System Symbol Set Value: 60 Value: 07	Capability		N/A


Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE K-IV. Cyberspace sector 1 modifiers.

DESCRIPTION	CATEGORY	MODIFIER	REMARKS
Continuity of Operations Symbol Set Value: 60 Value: 08	Capability		N/A
Internet Service Provider (ISP) Symbol Set Value: 60 Value: 09	Capability		N/A
Finance Symbol Set Value: 60 Value: 10	Capability		N/A
Out of Band Symbol Set Value: 60 Value: 11	Capability		N/A
Cloud Symbol Set Value: 60 Value: 12	Service		N/A
Data Symbol Set Value: 60 Value: 13			N/A







K.6.4 Cyberspace sector 2 modifiers. The cyberspace sector 1 modifiers denote capability categories. Table K-V lists Cyberspace sector 1 modifiers and illustrates their placement within the bounding octagon. Additional sector 2 modifiers, where required, are included in table B-II and are accessed using the modifier extension flag.

TABLE K-V. Cyberspace sector 2 modifiers.

DESCRIPTION	CATEGORY	MODIFIER	REMARKS
Secured Symbol Set Value: 60 Value: 01	Capability		N/A

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE K-V. Cyberspace sector 2 modifiers - Continued.

DESCRIPTION	CATEGORY	MODIFIER	REMARKS
Unsecured Symbol Set Value: 60 Value: 02	Capability		N/A
Response Actions Symbol Set Value: 60 Value: 03	Capability		N/A
Internal Defense Measures Symbol Set Value: 60 Value: 05	Capability		N/A
Advanced Persistent Threat Symbol Set Value: 60 Value: 06	Capability		N/A
Nation State Symbol Set Value: 60 Value: 07			N/A
Nation State Sponsored Symbol Set Value: 60 Value: 08			N/A

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

CONTROL MEASURE SYMBOLS

L.1 SCOPE

L.1.1 Scope. This appendix contains symbols that represent control measures and chemical, biological, radiological and nuclear (CBRN) incidents in the C2 domain. The tables in this appendix present the icons and amplifiers for control measures and CBRN. The information contained herein is intended for compliance. Ultimately, the joint force commander and their forces must be capable of accomplishing their mission, either directly or indirectly, by the employment of capabilities to create physical or psychological effects and be able to sustain such operations for as long as is necessary to achieve operational objectives. The principal method by which this capability is delivered is through the combination of joint operational capabilities and a range of mechanisms and control measures. This appendix establishes a standard system for the development and use of control measure symbols. Within this standard system there are a series of control measure symbols that follow standard formats and there are control measure symbols that follow stand-alone formats. This appendix provides rules for automated and hand-drawn symbols and examples for all control measure symbols. These control measure symbols are the standard for all command and control systems and simulations, including those used in live, virtual and planning. For many control measure symbols, there is a corresponding definition provided in this section. These definitions are provided to help add clarity in using these symbols. For ease of understanding and use, the control measure symbols have been broken down into groups that correspond to the joint functions of command and control to include joint targeting, maneuver and fires, intelligence, force protection, sustainment and deception under information operations.

L.2 APPLICABLE DOCUMENTS

Specific documents in 2.2 of this standard apply to this appendix.

L.3 DEFINITIONS

The definitions in section 3 of this standard apply to this appendix.

L.4 GENERAL REQUIREMENTS

L.4.1 Organization. This appendix contains technical specifications, a symbol coding scheme, a symbology hierarchy and control measures symbology.

L.5 DETAILED REQUIREMENTS

L.5.1 Control measure symbols. Control measures are directives given to assign responsibilities, coordinate fires and maneuvers and control operations. They may be boundaries, special area designations and other unique markings related to operational environment geometry and necessary for planning and management of operations. Control measure symbols provide operational information that cannot be displayed via icon-based symbols alone. Control measures can be displayed as points, lines, areas, or tactical mission tasks.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

L.5.1.1 Composition of control measure symbols. Control measure symbols can be combined with other symbols, icons and amplifiers to display operational information (see figure L-1). They do not follow the same building rules as the icon-based symbols but shall be built in accordance with the rules specified in the control measure appendix.




FIGURE L-1. Composition of control measure symbols.






L.5.1.1.1 Standard identity (color rules) for control measure symbols. The control measure symbols for monochrome systems shall be black or white, depending on display background. For color systems, control measures shall be black, blue (friendly), red (hostile), green (neutral or obstacles), or yellow (unknown or chemical, biological, radiological and nuclear hatched contaminated area fill). If red is not available for hostile standard identity, the symbol shall be drawn in black (with the abbreviation "ENY" placed on the graphic in at least two places for linear and multi point control measures and in one place for single point control measures.)

L.5.1.1.2 Point control measure height. Unless specifically indicated otherwise in the size/shape parameter of a point control measure's notes, the default point control measure symbol height should be 1L, where L is the default length and height of the bounding octagon (see 5.3.1).

L.5.1.1.3 Status. Status refers to whether a control measure exists at the location identified (status is "present") or will in the future reside at that location (status is "planned", "anticipated", or "suspected"). If a control measure is on order, the status code shall be specified "A – Anticipated/Planned" and field amplifier "W" shall be present and specified "O/O". In general, linear control measures (including boundary lines) and area control measures shall be a solid line when indicating present status and a dashed line when indicating anticipated or planned status, as depicted in table L-I. There are certain control measures such as counterattack which are drawn in the "present'" status with dashed lines. The codes for status in the SIDC are provided in the appendix for each symbology set.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE L-I. Present and planned status for control measures symbols.

	POINT GRAPHICS	BOUNDARY LINE GRAPHICS	AREA GRAPHICS
PRESENT POSITION (P)			
ANTICIPATED, PLANNED, SUSPECTED, OR ON ORDER (A)			

L.5.1.1.4 Amplifiers. An amplifier provides optional additional information about a control measure symbol. The field ID, field title, description and maximum allowable display lengths of control measure symbol amplifiers are presented in table L-II. An example of each amplifier (both text and graphic indicators) is included in figure L-2.The default placement of amplifiers in fields for boundary lines, points, and areas are shown in figures L-9, L-13, L-14 and L-15, respectively. An example of chemical, biological, radiological and nuclear (CBRN) events can be seen in table L-XX. As indicated in figures L-9, L-12, L-14 and L-15, certain fields can be displayed more than once within a control measure symbol. In some cases, a control measure symbol may require multiple instances of a given amplifier in order to fully create or represent an object: examples of these fields are H, T, W and Y. The unnumbered fields shall be filled before the numbered fields (i.e., fields W, H and T shall be used before fields W1, H1 and T1) As indicated in table L-II, not all amplifiers are applicable to all control measure symbols. However, when any such amplifier is displayed, it shall be defined in accordance with the contents of this table and positioned in accordance with figures L-2, L-9, L-13, L-14 and L-15.

TABLE L-II. Amplifier descriptions and maximum lengths for control measure symbols.

FIELD	FIELD TITLE	DESCRIPTION	FORMAT
B	Echelon	An amplifier in a unit symbol that identifies command level (see 5.3.7.1 and table VII).	Graphic
C	Quantity	An amplifier in an equipment symbol that identifies the number of items present. Examples include: 350 Beds 50 Gallons	Alphanumeric - {1,19} [#########] [XXXXXXXXXX]

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE L-II. Amplifier descriptions and maximum lengths for control measure symbols - Continued.

FIELD	FIELD TITLE	DESCRIPTION	FORMAT
H	Additional Information	A text amplifier for units, equipment, and installations; content is implementation specific.	
N	Hostile (Enemy)	An amplifier for equipment; letters "ENY" denote hostile symbols.	Graphic
Q	Direction of Movement Indicator	A graphic amplifier that identifies the direction of movement or intended movement of an object (see 5.3.7.9 and figure 14).	
S2	Offset Location Indicator	An amplifier used to indicate the offset or precise location of a single point symbol (see 5.3.7.5, 5.3.12, and figure 14).	Graphic
T	Unique Designation (Track Number)	A text amplifier for units, equipment and installations that uniquely identifies a particular symbol or track number.	Prefix = TN:##### **Example**: TN:13579
V	Type	A text amplifier for equipment that indicates types of equipment.	
W	Date-Time Group (DTG)	An alphanumeric designator for displaying a date-time group (DDHHMMSSZMONYYYY) or “O/O” for on order. The date-time group is composed of a group of six numeric digits with a time zone suffix and the standardized three-letter abbreviation for the month followed by four digits representing the year. The first pair of digits represents the day; the second pair, the hour; the third pair, the minutes. For automated systems, two digits may be added before the time zone suffix and after the minutes to designate seconds (see 5.3.7.8).	
X	Altitude/Depth	A text amplifier for units, equipment and installations that displays either altitude, flight level, depth for submerged objects, or height of equipment or structures on the ground. See 5.3.7.6 for content.	Measurement units shall be displayed within the string **Examples**: 1500MSL FL150
Y	Location	A text amplifier for units, equipment and installations that displays a symbol’s location in degrees, minutes and decimal minutes (or in MGRS, GARS, or other applicable display formats).	3317.0921N 04412.6332E 38SMB2649083145
AM	Distance	An amplifier that displays a minimum, maximum, or a specific distance (range, radius, width, length, etc.), in meters.	Alphanumeric - {3,9} [#] [X]

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE L-II. Amplifier descriptions and maximum lengths for control measure symbols - Continued.

FIELD	FIELD TITLE	DESCRIPTION	FORMAT
AN	Azimuth	An amplifier that displays an angle measured from true north to any other line in degrees.	Alphanumeric - {7,8} [#####] [XXX]
AP	Target Number	An amplifier used in Fire Support operations to uniquely designate targets in accordance with STANAG 2934.	Alphanumeric - {6,6} [XX][####]
AP1	Target Number Extension	An amplifier used to identify a target number extension which is a sequentially assigned number identifying the individual elements in a target (MIL-STD-6017),	Numeric – {2,3} [-##]
AS	Country	A three-letter code that indicates the country of origin of the organization (US systems shall use GENC).	




FIGURE L-2. Graphic amplifiers for control measure symbols.

L.5.1.1.5 Direction of movement indicator. The direction of movement indicator is an arrow identifying the direction of movement of events. The arrow extends downward from the center of the icon and points in the direction of movement. The indicator is represented in field Q as defined in table L-II and positioned as shown in figure 14.

L.5.1.1.6 Echelon indicator. The echelon indicator provides a graphic representation of command level and is used to show the element echelon on boundary lines, lines, and areas. Echelon indicator codes are listed in table VIII of the base document. The indicator is

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

represented in field B as defined in table L-II and positioned as shown in figure L-2 and figure L-15.

L.5.1.1.7 Offset location indicator. The offset location indicator is used when placing an object away from its actual location. The indicator is a line extending downward from an appropriate anchor point on an icon. The actual location (field Y) is given in latitude and longitude. The indicator is represented in field **S2** in table L-II and positioned as shown in figures L-2, L-9, L-13, L-14, L-15 and table L-XX.

L.5.1.1.8 Text amplifier. Table L-II defines the specific content, length and type of each text amplifier. Additional information is contained in field H, with the content of this field being implementation specific, provided the maximum number of characters in each field is not exceeded.

L.5.1.1.9 Altitude/depth amplifier. This field may contain alternate value formats. Enter a description of the altitude/depth (X) using one of the following.

L.5.1.1.10 Altitude base reference point. Legal values are “GL” ground level and “MSL” mean sea level.

L.5.1.1.10.1 Relative altitude. The relative altitude is a composite field consisting of multiple parts, the numeric altitude, the altitude unit of measurement and the altitude vertical dimension. Legal values for the numeric altitude are (minus) -99999 through 99999 in increments of 1. Legal values for altitude units of measure is feet “FT,” meters “M,” kilometers “KM,” and statute miles “SM.” The legal value for the depth unit of measure is feet “FT.” Legal values for the vertical dimension are “AGL” above ground level, “AMSL” above mean sea level, “HAE” height above ellipsoid and “BMSL” below mean sea level. BMSL is used only for depth of submerged objects, reported in feet. A space may be added between the values in the field to make it easier to read.

Examples: 1250 FT AGL, 1000 FT AMSL, 1524 M HAE, 35760 FT BMSL.

L.5.1.1.10.2 Flight level. By definition, flight level (FL) is, “Surfaces of constant atmospheric pressure which are related to a specific pressure datum, 1013.2 mb (29.92 in) and are separated by specific pressure intervals. (Flight levels are expressed in three digits that represent hundreds of feet; e.g., flight level 250 represents a barometric altimeter indication of 25,000 feet and flight level 255 is an indication of 25,500 feet.).” The legal value for flight level indicator is “FL.” A space may be added between the values in the field to make it easier to read. The legal value for context quantity is 000-999, in increments of one.

Example: FL 290.

L.5.1.1.10.3 Multiple instances of altitude/depth amplifiers. When multiple instances of the “X” amplifier are present in a single instance of a symbol or graphic (ex., Minimum Altitude “X,” Maximum Altitude “X1”), for display purposes, the fields may be separated by a hyphen “-,” or a space, hyphen and space “ - .”

Examples:

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

500 FT AGL – 1250 FT AGL

25 FT AMSL – 150 FT AMSL

FL 250 – FL 290

MSL – 35760 FT BMSL

L.5.1.1.11 Date-time group. Date-time group (DTG) is defined as the date and time expressed in an alphanumeric combination. The alphanumeric combination used is day-time-time zone-month-year. The alphanumeric combination can be displayed in a number of ways. In its longest form, sixteen characters, it is composed of eight digits (first pair of digits denotes the date, second pair denotes the hours, third pair denotes the minutes and fourth pair denotes the seconds) followed by the time zone suffix, followed by a three-letter month abbreviation and four digits for the year: DDHHMMSSZMONYYYY. It can also be expressed in shorter forms by removing characters, such as DDHHMMZMONYY. On order (O/O) is a valid substitute for DTG (see example below).




FIGURE L-3. On Order

L.5.1.1.12 Location of control measure symbols sector 1 and 2 modifiers. The location of sector 1 and sector 2 modifiers in control measure symbols is different from other symbols within this standard as control measure symbols do not use a bounding octagon. The physical location is defined in the applicable control measure symbol template within this appendix.

L.5.1.1.12.1 Control measure sector 1 modifier. The control measure sector 1 modifiers in table L-XXV under category identified as mine type provides a graphic representation of the type(s) of mines used in a minefield or mined area. The mine types within the control measure symbols sector 1 modifier shall only be used with minefields and mined area control measure symbols. A minefield or mined area can contain a single mine type or multiple mine types, with a maximum of three (3) mine types in a single minefield or mined area.

L.5.1.1.12.2 Mine types. The seven mine types are Unspecified Mine, Antipersonnel Mine, Antipersonnel Mine with Directional Effects, Antitank Mine, Antitank Mine with Anti-handling Device, Wide Area Antitank Mine, and Mine Cluster.

L.5.1.1.12.3 Default mine type. All minefields and mined areas shall contain a minimum of one Mine Type. The default mine type is the Unspecified Mine, sector 1 modifier code “13”.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

When the type of mines in a minefield or mined area are known, then the actual mine types shall be used, not the default Unspecified Mine.

L.5.1.1.12.4 Mine type(s) as a fill pattern. For the Minefield, Dynamic Depiction, Mined Area, and Mined Area, Fenced control measure symbols, the specified mine types will be used to create a fill pattern.

L.5.1.1.13 Feint/decoy/dummy indicator. Refer to 5.3.7.4 in base document for general guidance for this indicator. Additional guidance specific to control measure symbols is below.




FIGURE L-4. Feint, decoy, or dummy indicator construction.

L.5.1.1.13.1 Feint, decoy, or dummy indicator line style. The line style of the feint, decoy, or dummy indicator when used with control measure symbols shall always be rendered in accordance with 5.3.7.4.4 - as dashed lines, even when the status of the control measure symbols is present and the control measure symbol line style is solid.

L.5.1.1.13.2 Position of the feint, decoy, or dummy indicator for single point control measure symbols. The feint, decoy, or dummy indicator can be used with some sustainment, CBRN decontamination and/or special C2 point symbols. For these instances, the feint, decoy, or dummy indicator shall be positioned in relation to the frame as shown in Figure L-5. Point "A" shall be rendered 0.4L above the top of the top edge and 0.25L to the left of the left edge of the frame. Point "C" shall be rendered 0.4L above the top of the frame and 0.25L to the right of the right edge of the frame. This spacing will support any authorized amplifier(s) to be applied to the symbol without overlapping the indicator. The location of point "B" shall be calculated per the information and illustrations in this section.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.




FIGURE L-5. Feint, decoy, or dummy indicator positioning for single point control measure symbols.

L.5.1.1.13.3 Feint, decoy, or dummy indicator rendering for most linear and area (polygon) control measure symbols. The rendering of the feint, decoy, or dummy indicator for most linear control measures and most area (polygon) control measures that do not contain a large directional arrow is described in figure L-6. This does not apply to any Axis of Advance and/or Direction of Attack control measure symbols (they have large arrows); see L.5.1.1.14.4 for rendering guidance for Axis of Advance and Direction of Attack control measure symbols.

L.5.1.1.13.3.1 The feint, decoy, or dummy indicators point "A" x/y coordinate is calculated using the left most edge of the symbol area as the "x" (see red dotted line) and the top most edge of the symbol area as the "y" (see blue dotted line).

L.5.1.1.13.3.2 The feint, decoy, or dummy indicator point "C" x/y coordinate is calculated using the right most edge of the symbol area as the "x" (see green dotted line) and the top most edge of the symbol portion as the "y" (see blue dotted line).

L.5.1.1.13.3.3 For the feint, decoy, or dummy indicator portion point "B", x/y coordinate is calculated per L.5.1.1.14.2.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.




FIGURE L-6. Feint, decoy, or dummy indicator positioning for most linear and area (polygon) control measure symbols

L.5.1.1.13.4 Feint, decoy, or dummy indicator rendering for Axis of Advance and Direction of Attack control measure symbols. The rendering of the feint, decoy, or dummy indicator for Axis of Advance and/or Direction of Attack control measure symbols is described in figure L-7. This section is an exception to L.5.1.1.14.3, rendering guidance for most linear and area polygon control measure symbols that do not contain a large directional arrow.

L.5.1.1.13.4.1 The feint, decoy, or dummy indicator point "A" x/y coordinate is calculated using the left most edge of the symbol's arrow head as the "x" (see red dotted line) and the pointed end of the arrow head side line as the "y" (see blue dotted line).

L.5.1.1.13.4.2 The feint, decoy, or dummy indicator point "C" x/y coordinate is calculated using the right most edge of the symbol's arrow head as the "x" (see green dotted line) and the pointed end of the arrow head side line as the "y" (see blue dotted line).

L.5.1.1.13.4.3 For the feint, decoy, or dummy indicator portion point "B", x/y coordinate is calculated per L.5.1.1.14.2.

L.5.1.1.13.4.4 The feint, decoy, or dummy indicator shall be positioned in relation to the orientation of the arrow head portion of the Axis of Advance and/or Direction of Attack control measure symbols as follows. Given the base of the arrow head is distance "w" (see blue dotted line, width) in figures L-7 and L-8 below, then the feint, decoy, or dummy indicator baseline "AC" (not rendered) shall be positioned 0.5w in front of the symbol arrow head and shall be rendered such that the yellow dotted line (not rendered) is centered in the middle of and perpendicular to the base of the arrow head (see blue dotted line, not rendered) and the yellow dotted line (not rendered) intersects feint, decoy, or dummy indicator point "B".

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.




FIGURE L-7. Feint, decoy, or dummy indicator positioning for axis' of advance.




FIGURE L-8. Feint, decoy, or dummy indicator positioning for direction of attack.

L.5.2 Construction of control measure symbols. The rules for constructing control measure symbols vary depending on whether the object is point, line, or area based. The latter category of objects includes various forms of linear control measure symbols such as boundaries, areas of all shapes and sizes and complex figures such as an air corridor.

L.5.2.1 Point control measure symbols. A point-based control measure symbol, such as a casualty collection point, is constructed in the same manner as an unframed tactical symbol. Rules concerning the relative size of symbol components and placement of amplifiers in tactical symbols also apply to point based control measure symbols.

L.5.2.2 Line and area control measure symbols. A line or area control measure symbol is constructed using the anchor points, size and orientation defined for the control measure symbol. This appendix includes these parameters for the line and area graphics in the C2 domain. The size of the control measure symbol is determined by these parameters and the scale of the background on which the control measure symbols is placed. As a general rule, the line width and pattern height shall be scaled proportionally to the change in icon size required by its change in background scale (map or image). For control measure symbols, line width is dependent on the distance between the points to be depicted and may vary (i.e., be reduced or enlarged) as display scale changes. Orientation is determined by the order in which the anchor points are entered.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

L.5.3 Coloring. All friendly control measure symbols will be shown in black or blue when drawn manually or on a color computer-generated display. Hostile control measure symbols shall be shown in red. If red is not available, they will be drawn in black with the abbreviation “ENY” placed on the symbols in one place for single point symbols and at least two places for Area and Line symbols. All obstacles as shown in this appendix, friendly, hostile, neutral, or unknown, shall be drawn using the color green. If the color green is not available obstacles should be drawn using black. The color yellow will be used for the hatching for CBRN contaminated areas. NOTE: The use of green and yellow for obstacles and CBRN is in contradiction to the standard identities.

L.5.4 Labeling. All text labeling shall be in upper case letters. The reader should be able to read the labels for all text labels of amplifier fields for control measures symbols when the bottom of the overlay is closest to the reader. Labeling written on an angle should be readable to the viewer, so they do not have to turn their head. Where space is limited within an area, the amplifying information may be shown in a stacked manner, rather than side by side as displayed in the templates.

L.5.4.1 Fonts. Font sizes shall be scaled as appropriate in order for the information to be readable to the viewer.

L.5.5 Command and control. The exercise of authority and direction by a properly designated commander over assigned and attached forces in the accomplishment of the mission. Command and control functions are performed through an arrangement of personnel, equipment, communications, facilities, and procedures employed by a commander in planning, directing, coordinating, and controlling forces and operations in the accomplishment of the mission.

L.5.5.1 Boundaries. In land warfare, a boundary is a line by which areas of responsibility between adjacent units/formations are defined. For boundaries, all field labels are displayed perpendicular to the boundary line. Figure L-9 “Orientation of boundary lines” below provides the orientation of field labels for horizontal (east/west) and vertical (north/south orientation) boundary line segments. The symbol for the highest echelon (Field B) unit on lateral boundaries is used for the boundary line. The graphic for the lower echelon (Field B) unit on a rear or forward boundary is used for the boundary line (see figure L-9). When units of the same echelon are adjacent to each other, the abbreviated unique designator (Field T) can be omitted from the alphanumeric designator. Tables L-XXVI and L-XXVII at the end of the appendix provide a list of abbreviations and acronyms to be used for Field T. For all boundaries, use Arabic numerals to show the number of units, except for a corps boundary, use Roman numerals to show the number of corps. When the boundary is between units of different countries, the country trigraph (Field AS) is shown in parenthesis behind or below the unit designation.

L.5.5.2 Boundary line segment orientation determination. For the purpose of determining boundary line segment orientation, which is required to correctly position the field labels, the following additional guidance applies.

L.5.5.2.1 Horizontal (East/West) orientation boundary line segments are those line segments that are oriented between 46 and 135 degrees.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

L.5.5.2.2 Vertical (North/South) orientation boundary line segments are those line segments that are oriented between 315 and 45 degrees.




FIGURE L-9. Orientation of boundary lines.

L.5.5.2.3 Boundary line operational examples. The boundary line can be operationally used to depict a lateral boundary (figure L-10), a forward boundary (figure L-11), or a rear boundary (figure L-12). A lateral boundary is a control measure that defines the left or right limit of a unit's operational area; together with the rear and forward boundaries and a coordinating altitude, lateral boundaries define the area of operations for a commander. A forward boundary is the farthest limit, in the direction of the enemy, of an organization's responsibility. A rear boundary is the line that defines the rear area of operations assigned to a particular unit; the area behind the rear boundary belongs to the next higher commander and positioning of elements behind it must be coordinated with that commander.




FIGURE L-10. Lateral boundary example.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.




FIGURE L-11. Forward boundary example.




FIGURE L-12. Rear boundary example.

L.5.5.2.4 Control measure draw rules. Draw rules listed below are used to create both the control measures and mission tasks listed in the following tables within this appendix.

TABLE L-III. Control measure draw rules.

TYPE	DRAW RULE
Area1	**Anchor Points:** This symbol requires at least three anchor points to define the boundary of the area. Add as many points as necessary to accurately reflect the area's size and shape. **Size/Shape:** Determined by the anchor points. The information fields should be moveable and scalable as a block within the area.
Area2	**Anchor Points:** This symbol requires at least three anchor points to define the boundary of the area. Add as many points as necessary to accurately reflect the area's size and shape. **Size/Shape:** Determined by the anchor points. The information fields should be moveable and scalable as a block within the area.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE L-III. Control measure draw rules - Continued.

TYPE	DRAW RULE
Area3	**Anchor Points:** This symbol requires at least three anchor points to define the boundary of the area. Add as many points as necessary to accurately reflect the area's size and shape. **Size/Shape:** Determined by the anchor points.
Area4	**Anchor Points:** This symbol requires at least three anchor points to define the boundary of the area. Add as many points as necessary to accurately reflect the area's size and shape. **Size/Shape:** Determined by the anchor points. The information fields should be moveable and scalable as a block within the area. The default tic length should be the same as the text height of the echelon field (B). Spacing between the tics should also be the height of B. Users should be provided a facility to allow them to manually alter the height of B, which in turn should affect the tic length and spacing accordingly.
Area5	**Anchor Points:** This symbol requires three anchor points. Points 1 and 2 define the endpoints of the semicircle's opening. Point 3 defines the end of the arrow. **Size/Shape:** Points 1 and 2 determine the diameter of the semicircle and point 3 determines the length of the arrow. The tip of the arrowhead will be at the center point of the semicircle's diameter and will project perpendicularly from the line between points 1 and 2. The default tic length should be the same as the text height of the echelon field (B). Spacing between the tics should also be the height of B. Users should be provided a facility to allow them to manually alter the height of B, which in turn should affect the tic length and spacing accordingly.
Area6	**Anchor Points:** This symbol requires two anchor points. Point 1 defines the center point of the symbol and point 2 defines the symbol's start point and radius. **Size/Shape:** Points 1 and 2 will determine a radius that is long enough for the graphic to encompass the feature(s) being retained. The opening will be a 30-degree arc of the circle. The default tic length should be the same as the text height of the echelon field (R). Spacing between the tics should also be the height of R. Users should be provided a facility to allow them to manually alter the height of R, which in turn should affect the tic length and spacing accordingly.
Area7	**Anchor Points:** This symbol requires three anchor points. Point 1 is the tip of the arrowhead. Points 2 and 3 define the endpoints of the straight line on the back side of the symbol. **Size/Shape:** Points 2 and 3 determine the length of the straight line on the back side of the symbol. The rear of the arrowhead line shall connect to the midpoint of the line between points 2 and 3. The arrowhead line shall be perpendicular to the line formed by points 2 and 3.
Area8	**Anchor Points:** This symbol requires four anchor points. Points 1 and 2 define the endpoints of the straight line on the back side of the symbol. Points 3 and 4 define the tips of the arrowheads. **Size/Shape:** Points 1 and 2 determine the length of the straight line on the back side of the symbol. The rear of the arrows should connect to points 1 and 2.
Area9	**Anchor Points:** This symbol requires at least three anchor points to define the boundary of the area. Add as many points as necessary to accurately reflect the area's size and shape. **Size/Shape:** Determined by the anchor points.
Area10	**Anchor Points:** This symbol requires a minimum of three (3) and a maximum of six (6) anchor points to define the boundary of the area. The anchor points shall be sequentially numbered, in increments of one (1), beginning with point one (1). **Size/Shape:** Determined by the anchor points. The information fields should be moveable and scalable within the area.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE L-III. Control measure draw rules - Continued.

TYPE	DRAW RULE
Area11	**Anchor Points:** This symbol requires three anchor points. Points 1 and 2 define the endpoints of the symbol's vertical line. Point 3 defines the endpoint of the symbol's horizontal line. **Size/Shape:** Points 1 and 2 determine the length of the vertical line. The length of the horizontal line is determined by plotting point 3 on a plane extending perpendicularly from the midpoint of the vertical line.
Area12	**Anchor Points:** This symbol requires three anchor points. Points 1 and 2 define the end points of the symbol's vertical line. Point 3 defines the tip of the longest arrow. **Size/Shape:** Points 1 and 2 determine the height of the symbol and point 3 determines its length. The spacing between the symbol's arrows will stay proportional to the symbol's vertical line. The length of the short arrows will remain in proportion to the length of the longest arrow.
Area13	**Anchor Points:** This symbol requires at least two anchor points. Points 1 and 2 define the corners of the symbol. **Size/Shape:** Points 1 and 2 determine the length of the straight line. The radius of the semicircle is ½ the length of the straight line.
Area14	**Anchor Points:** This symbol requires three anchor points. The center point defines the center of the symbol. Points 1 and 2 define the radii of circles 1 and 2. **Size/Shape:** As defined by the operator.
Area15	**Anchor Points:** This symbol requires two anchor points. Point 1 defines the center point of the symbol and point 2 defines the symbol's start point and radius. **Size/Shape:** The radius will be long enough for the symbol to encompass the UEI(s) or feature(s) being isolated. The opening will be a 30-degree arc of the circle.
Area16	**Anchor Points:** This symbol requires two anchor points. Point 1 defines the center point of the symbol and point 2 defines the symbol's start point and radius. **Size/Shape:** Points 1 and 2 will determine a radius that is long enough for the symbol to encompass the feature(s) being occupied. The opening will be a 30-degree arc of the circle.
Area17	**Anchor Points:** This symbol requires three anchor points. Points 1 and 2 define the endpoints of the symbol's vertical line. Point 3 defines the rear of the symbol. **Size/Shape:** Points 1 and 2 determine the height of the symbol and point 3 determines its length. The arrow will project perpendicularly from the midpoint of the vertical line.
Area18	**Anchor Points:** This symbol requires four anchor points. Point 1 defines the tip of the first arrowhead. Point 2 defines the end of the straight-line portion of the first arrow. Point 3 defines the tip of the second arrowhead. Point 4 defines the end of the second arrow. **Size/Shape:** Points 1 and 2 and points 3 and 4 determine the length of each arrow. Points 2 and 3 shall be connected by a smooth, curved line.
Area19	**Anchor Points:** This symbol requires two anchor points. Point 1 defines the center point of the symbol and point 2 defines the symbol's start point and radius. **Size/Shape:** Points 1 and 2 will determine a radius that is long enough for the symbol to encompass the feature(s) being secured. The opening will be a 30-degree arc of the circle.
Area20	**Anchor Points:** This symbol requires at least three anchor points to define the boundary of the area. Add as many points as necessary to accurately reflect the area's size and shape. **Size/Shape:** Determined by the anchor points.
Area21	**Anchor Points:** This symbol requires three anchor points. Point 1 defines the vertex of the symbol. Points 2 and 3 define the tips of the arrowheads. **Size/Shape:** Points 1 and 2 and points 1 and 3 determine the length of the arrows. The length and orientation of the arrows can vary independently.
Area22	**Anchor Points:** This symbol requires one anchor point. The center point defines the center of the symbol. **Size/Shape:** Static.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE L-III. Control measure draw rules - Continued.

TYPE	DRAW RULE
Area23	**Anchor Points:** This symbol requires at least three anchor points to define the boundary of the area. **Size/Shape:** Determined by the anchor points
Area24	**Anchor Points:** This symbol requires three anchor points. Points 1 and 2 define the endpoints of the symbol's vertical line. Point 3 defines the endpoint of the symbol's horizontal line. **Size/Shape:** Points 1 and 2 determine the length of the vertical line. Points 2 and 3 determine the length of the horizontal line, which will project perpendicularly from the midpoint of the vertical line.
Area25	*{Disused}*
Area26	**Anchor Points:** This symbol requires a minimum of 6 anchor points. Add as many pairs of points as needed to accurately define the areas. The number of points shall always be an even number, with an equal number of points for both polygons. Points 1 through N/2 define the inner safe zone (zone 1). Points N/2 +1 though point N defines the outer zone (zone 2). **Size/Shape:** Determined by the anchor points.
Point1	**Anchor Points:** This symbol requires one anchor point. The anchor point defines/is the tip of the inverted cone. **Size/Shape:** Static.
Point2	**Anchor Points:** This symbol requires one anchor point. The center point defines/is the center of the symbol. **Size/Shape:** Static.
Point3	**Anchor Points:** This symbol requires one anchor point. The center point defines the center of the symbol. **Size/Shape:** Static. Maneuver area symbol shall be drawn with a black border. Maneuver areas may be either unfilled or filled with performance-contoured color options.
Point4	**Anchor Points:** This symbol requires one anchor point. The point defines the bottom of the central vertical line in the symbol where the curved and vertical lines meet. **Size/Shape:** Static.
Point5	**Anchor Points:** This symbol requires one anchor point. The point defines the point where all the lines meet. **Size/Shape:** Static.
Point6	**Anchor Points:** This symbol requires one anchor point. The anchor point defines/is the center of the bottom of the control measure symbol as shown in the template and example. **Size/Shape:** Static.
Point7	**Anchor Points:** This symbol requires one anchor point. The anchor point defines the midpoint of the symbol's base. **Size/Shape:** Static.
Point8	**Anchor Points:** This symbol requires one anchor point. The center point defines the center of the symbol. **Size/Shape:** Static. The symbol's corners form a 70- degree angle.
Point9	**Anchor Points:** This symbol requires one anchor (center) point. The point defines the center of the symbol. **Size/Shape:** Static. The symbol's height should be 2x the symbol's width.
Point10	**Anchor Points:** This symbol requires one anchor point. The point defines the center of the circle. **Size/Shape:** Static. The diameter of the circle should be 1/2 the height of the symbol.
Point11	**Anchor Points:** This symbol requires one center point. The point defines the center of the symbol. **Size/Shape:** Static. Length is 2x the size of height.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE L-III. Control measure draw rules - Continued.

TYPE	DRAW RULE
Point12	**Anchor Points:** This symbol requires three anchor points. Points 1 and 2 define the tips of the arrowheads and point 3 defines the rear of the symbol. **Size/Shape:** Points 1 and 2 determine the symbol's height and point 3 determines its length. The vertical line at the rear of the symbol shall be the same length as the opening and shall be perpendicular to the parallel lines formed with the rear of symbol vertical line and the lines ending with points 1 and 2.
Point13	**Anchor Points:** This symbol requires one anchor point. The center point defines the center of the circle. **Size/Shape:** Static.
Point14	**Anchor Points:** This symbol requires one anchor point. The center point defines the center of the symbol. **Size/Shape:** There should be 45 degrees of angular separation between the two arrows.
Point15	**Anchor Points:** This symbol requires one anchor point. The anchor point defines "nose" of the symbol. **Size/Shape:** Static.
Point16	**Anchor Points:** This symbol requires one anchor point; the point defines the circle at the base of the tower. **Size/Shape:** The symbol is a high-angle cone.
Point17	**Anchor Points:** This symbol requires one anchor point. This anchor point represents the center of the rectangle and, therefore, the geographic location of that rectangle. **Size/Shape:** The size and shape of this symbol is determined by three additional numeric values; a length (AM1), a width (AM2), and a rotation angle. The length and width should be expressed in the appropriate map distance units. The length is aligned with the axis of rotation. The width is aligned perpendicular to the axis of rotation.
Point18	**Anchor Points:** This symbol requires one anchor point that defines the axis of angular rotation. **Size/Shape:** The size and shape of this symbol is determined by additional numeric values; a search axis azimuth, a start range, a stop range and a stop relative bearing. The stop relative bearing is an equal angle either side of the search axis. The start and stop range should be expressed in the appropriate map distance units. Field T should be positioned in the center of the search area aligned with the search axis.
Line1	**Anchor Points:** This symbol requires at least two anchor points, points 1 and 2, to define the line. Additional points can be defined to extend the line. **Size/Shape:** The first and last anchor points determine the length of the line. Any end-of line information will typically be posted at the ends of the line as it is displayed on the screen.
Line2	*{Disused}*
Line3	**Anchor Points:** This symbol requires three anchor points. Point 1 defines the vertex of the symbol. Points 2 and 3 define the tips of the arrowheads. **Size/Shape:** The length and orientation of the arrows can vary independently.
Line4	**Anchor Points:** This symbol requires two anchor points. Points 1 and 2 define the corner points of the symbol. **Size/Shape:** The symbol varies only in length.
Line5	**Anchor Points:** This symbol requires two anchor points. Points 1 and 2 define the endpoints of the symbol. **Size/Shape:** The symbol varies only in length. **Orientation:** One point defines the origin from which the bearing is being taken and the other point defines the location or direction from which a contact is made.
Line6	*{Disused}*

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE L-III. Control measure draw rules - Continued.

TYPE	DRAW RULE
Line7	**Anchor Points:** This symbol requires at least two anchor points, points 1 and 2, to define the line. Additional points can be defined to extend the line. **Size/Shape:** The first and last anchor points determine the length of the line. The line information will be posted once at the center of the line as it is displayed on the screen.
Line8	**Anchor Points:** This symbol requires a minimum of two (2) anchor points. Up to 298 additional points can be added to extend the line. The first point (point 1) defines the start point. The last point defines the endpoint. The points are numbered sequentially beginning with point one (1), in increments of one. **Size/Shape:** The anchor points define the size and shape.
Line9	**Anchor Points:** This symbol requires 2 anchor points. Point 1 defines the tip of the arrowhead and point 2 defines the rear of the symbol. **Size/Shape:** Points 1 and 2 determine the length of the symbol, which varies only in length.
Line10	**Anchor Points:** This symbol requires two anchor points. Point 1 defines the tip of the arrowhead and point 2 defines the rear of the symbol. Point 3 defines the 90 degree arc. **Size/Shape:** Points 1 and 2 are connected by a 90 degree arc. Point 3 indicates on which side of the line the arc is placed.
Line11	**Anchor Points:** This symbol requires four points. Points 1 and 2 define one side of the gap and points 3 and 4 define the opposite side of the gap. Size/Shape. Determined by the anchor points.
Line12	**Anchor Points:** This symbol requires three anchor points. Points 1 and 2 define the endpoints of the symbol and point 3 defines the location of one side of the symbol. **Size/Shape:** Points 1 and 2 determine the centerline of the symbol and point 3 determines its width.
Line13	**Anchor Points:** This symbol requires at least two anchor points, points 1 and 2, to define the line. Additional points can be defined to extend the line. **Size/Shape:** The first and last anchor points determine the length of the line. The size of the tooth does not change.
Line14	**Anchor Points:** This symbol requires two anchor points. Points 1 and 2 define the tips of the arrowheads. **Size/Shape:** Points 1 and 2 determine the length of the symbol, which varies only in length. The lines of the arrowhead will form an acute angle.
Line15	**Anchor Points:** This symbol requires two anchor points. Points 1 and 2 define the length and orientation of the straight line (trip wire) portion of the symbol. **Size/Shape:** Points 1 and 2 determine the length and orientation of the line drawn from the physical mine to the end of the trip wire. The distance between the line connecting points 1 and 2 is the length of the trip wire connected to the mine.
Line16	**Anchor Points:** This symbol requires four points. Points 1 and 2 define one side of the assault crossing site and points 3 and 4 define the opposite side of the assault crossing site. **Size/Shape:** Determined by the anchor points.
Line17	**Anchor Points:** This symbol requires three anchor points. Points 1 and 2 define the endpoints of the first line. Point 3 defines the location of the parallel line. **Size/Shape:** Points 1 and 2 determine the length of the symbol. Point 3 determines its width.
Line18	**Anchor Points:** This symbol requires two anchor points. Points 1 and two define the tips of the arrowheads. **Size/Shape:** Points 1 and 2 determine the length of the symbol, which varies only in length. The arrowheads will be filled-in versions of a common arrowhead.
Line19	**Anchor Points:** This symbol requires two anchor points. Points 1 and two define the corners on the front of the symbol. **Size/Shape:** Points 1 and 2 determine the length of the symbol, which varies only in length.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE L-III. Control measure draw rules - Continued.

TYPE	DRAW RULE
Line20	**Anchor Points:** This graphic requires two anchor points. Point 1 defines the tip of the arrowhead, and point 2 defines the rear of the graphic. **Size/Shape:** Points 1 and 2 determine the length of the graphic, which varies only in length.
Line21	**Anchor Points:** This symbol requires at least two anchor points to define the line. Additional points can be defined to extend and shape the line. **Size/Shape:** The first and last anchor points determine the length of the line. The line segment between each pair of anchor points will repeat all information associated with the line segment. **Orientation:** Orientation is determined by the anchor points.
Line22	*{Disused}*
Line23	**Anchor Points:** This symbol requires three anchor points. Points 1 and 2 define the endpoints of the symbol's vertical line and point 3 defines the rear of the symbol. **Size/Shape:** Points 1 and 2 determine the symbol's height and point 3 determines its length. The spacing between the symbol's arrows will stay proportional to the symbol's height. The tip of the middle arrowhead will be at the midpoint of the vertical line. The arrows will stay perpendicular to the vertical line, regardless of the rotational orientation of the symbol as a whole.
Line24	**Anchor Points:** This symbol requires three anchor points. Point 1 defines the tip of the arrowhead. Point 2 defines the end of the straight line portion of the symbol. Point 3 defines the diameter and orientation of the 180 degree circular arc. **Size/Shape:** Points 1 and 2 determine the length of the straight line portion of the symbol. Point 3 defines which side of the line the arc is on and the diameter of the arc.
Line25	**Anchor Points:** This symbol requires exactly two anchor points. Point 1 defines the tip of the arrowhead and point 2 defines the rear of the symbol. **Size/Shape:** Points 1 and 2 determine the length of the symbol, which varies only in length.
Line26	**Anchor Points:** This symbol requires four points. Point 1 and Point 2 define the ends of one arrow and Point 3 and Point 4 define the ends of the other arrow. Point 1 and Point 4 define the ends of their respective arrowheads. **Size/Shape:** Points 1 and 2 and Points 3 and 4 determine the length of the arrows. The length and orientation of the arrows can vary independently.
Line27	**Anchor Points:** This symbol requires four points. Point 1 defines the center of the circle. Point 2 defines the radius of the circle. Point 3 defines the curvature of the arc. Point 4 defines the end of the arrow. **Size/Shape:** Points 1 and 2 define the size of the circle, which should be adjusted as needed to contain the unit assigned the task. Point 3 controls the curvature of the arc. Point 4 defines the end of the arrow.
Line28	*{Disused}*
Line29	**Anchor Points:** This symbol requires three anchor points. Point 1 is the tip of the arrowhead. Points 2 and 3 define the endpoints of the curved line on the back side of the symbol. **Size/Shape:** Points 2 and 3 determine the length of the curved line on the back side of the symbol. The rear of the arrowhead line shall connect to the midpoint of the line between points 2 and 3. The arrowhead line shall be perpendicular to the line formed by points 2 and 3.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE L-III. Control measure draw rules - Continued.

TYPE	DRAW RULE
Corridor1	**Anchor Points:** This symbol may contain multiple segments. Each segment requires 2 anchor points. Point numbers that define the trace of the segment are sequential beginning with point 1, in increments of 1, up to a max of 99 points. Each anchor point defines the endpoint of a segment's centerline. The anchor points are Air Control Points (ACP), Communications Checkpoints (CCP) or both. **Size/Shape:** Points 1 and 2 determine the length of a segment. The information field inside each segment should be moveable and scalable within each segment. The information box outside the symbol should be placed between points 1 and 2 in such a way it does not obscure the symbol.
Axis1	**Anchor Points:** The symbol requires N anchor points, where N is between 3 and 50. Point 1 defines the tip of the arrowhead. Point N-1 defines the rear of the symbol. Point N defines the back of the arrowhead. Anchor points are numbered sequentially beginning with point number one (1), in increments of one (1). **Size/Shape:** Points 1 through N-1 and 2 determine the symbol's centerline and Point N determines the width. The crossover point on the symbol shall occur between Points 1 and 2.
Axis2	**Anchor Points:** The symbol requires N anchor points, where N is between 3 and 50. Point 1 defines the tip of the arrowhead. Point N-1 defines the rear of the symbol. Point N defines the back of the arrowhead. Anchor points are numbered sequentially beginning with point number one (1), in increments of one (1). **Size/Shape:** Points 1 through N-1 and 2 determine the symbol's centerline and Point N determines the width.
Polyline1	**Anchor Points:** This symbol requires three anchor points. Points 1 and 2 define the endpoints of the infiltration lane and point 3 defines the width on one side of the lane. **Size/Shape:** Points 1 and 2 determine the centerline of the symbol and point 3 determines the width of the infiltration lane. The rest of the symbol stays proportional to the length of the centerline.
Ellipse1	**Anchor Points:** This symbol requires one anchor point. This anchor point represents the center of an ellipse and, therefore, the geographic location of that ellipse. **Size/Shape:** The size and shape of this symbol is determined by three additional numeric values; A major axis radius, a minor axis radius, and a rotation angle. The radii should be expressed in the appropriate map distance units.
Rectangular1	**Anchor Points:** This symbol requires two anchor points and a width, defined in meters, to define the boundary of the area. Points 1 and 2 will be located in the center of two opposing sides of the rectangle. **Size/Shape:** Size is determined by the anchor points. The anchor points determine the length of the rectangle. The width, defined in meters, will determine the width of the rectangle. Shape: Rectangle. The information fields should be moveable and scalable.
Rectangular2	**Anchor Points:** This symbol requires one (1) anchor point to define the center of the area. **Size/Shape:** Size is determined by the anchor point, the target length (in meters) and target width (in meters). A rectangular target is wider and longer than 200 meters. The information fields should be moveable and saleable within the area. Shape: Rectangle.
Rectangular3	**Anchor Points:** This symbol requires one anchor (center) point to define the center of the symbol. The target tactical symbol shall be centered upon the center of the area. The size and the orientation of the target symbol are fixed within the area. **Size/Shape:** Is determined by the anchor points. The anchor points determine the area's length. Width, determined in meters, will define the width of the rectangle.







Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE L-III. Control measure draw rules - Continued.

TYPE	DRAW RULE
Circular1	**Anchor Points:** This symbol requires one (1) anchor point and a radius. Point 1 defines the center point of the symbol. **Size/Shape:** Size: The radius defines the size. Shape: Circle. The information fields should be scalable within the circle.
Circular2	**Anchor Points:** This symbol requires one anchor point that defines an object at a dynamic grid location. This coordinate, which pinpoints the current physical location of a specific unit, weapon, or acquisition system, may change with the movement of the object. The symbol for that object is located at the anchor point. **Size/Shape:** The size is determined by the distance in meters from the object at the center of the range fan. The shapes are concentric circles. A minimum of one (1) and a maximum of three (3) concentric circles can be used.
Arc1	**Anchor Points:** This graphic requires one anchor point that defines an object at a dynamic grid location. This coordinate, which pinpoints the current physical location of a specific unit, weapon, or sensor system, may change with the movement of the object. The symbol for that object is located at the anchor point. **Size/Shape:** Determined by the anchor point, azimuths measured from true north, and the distance (range) in meters. The Left Sector Azimuth is the angle measured from true north to the left sector limit/edge of the Sector Range Fan. The Right Sector Azimuth is the angle measured from true north to the right sector limit/edge of the Sector Range Fan. Multiple distances (ranges) and/or left and right sector limits/edges of the sector, as well as altitude, may be added as required to define the sector. All azimuths are in degrees. All distances (ranges) are in meters. All altitudes are in feet.





Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE L-IV. Command and control lines.

CONTROL MEASURE	TEMPLATE	EXAMPLE Note: The symbols that have been colored gray are used to help explain how the control measure is used, but they are not a part of the control measure.
Command and Control Lines Type: Entity Symbol Set: 25 Value: **11**0000	Reserved for hierarchical purposes.	N/A
Boundary Type: Entity Type Entity Type: Command and Control Lines Symbol Set: 25 Value:11**01**00 Draw Rules: Line1 – Dynamic		   
Light Line Type: Entity Type Entity Type: Command and Control Lines Symbol Set: 25 Value: 11**02**00 Draw Rules: Line1 - Dynamic	 Designated line forward of which vehicles are required to use black-out lights at night.	

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE L-IV. Command and control lines - Continued.

CONTROL MEASURE	TEMPLATE	EXAMPLE Note: The symbols that have been colored gray are used to help explain how the control measure is used, but they are not a part of the control measure.
Engineer Work Line Type: Entity Type Entity Type: Command and Control Lines Symbol Set: 25 Value: 11**03**00 Draw Rules: Line1 - Dynamic	 A coordinated boundary used to compartmentalize an area of operations to indicate where specific engineer units have primary responsibility (FM 3-34).	
Generic Type: Entity Type Entity Type: Command and Control Lines Symbol Set: 25 Value: 11**04**00 Draw Rules: Line1 - Dynamic		

L.5.6 Points. In a number of tables (sustainment, CBRN decontamination and special C2) that follow there are single point control measure symbols that follow a specific format as shown in figure L-13 below. Supply points follow this same format with a modification to the symbol. Supply points use the same icon used for supply units. The supply icon is placed toward the bottom of the box as shown in figure L-13 below. This format is only for use with these types of points, as there are other points (contact, coordination, decision, targets, etc.) as displayed throughout this section on land control measure symbols that are formatted differently. In building points, the type of point is abbreviated and positioned inside the top part of the point symbol, displayed as a grey box in figure L-13 below. For supply symbols this may be a graphic depiction. In addition, below the abbreviation of the point name, the designation of the unit servicing that point may be included in field T1. To differentiate points, the point is numbered, lettered, or a combination. The number, letter or combination is placed on the outside of the symbol on the right side at the top in field T. On the outside of the point on the left side at the top and middle, date-time groups can be associated with the point. On the outside of the point at the top, additional information can be provided in field H. Text will not be written on an angle for single point symbols. **For dynamic displays, if the system has the capability to rotate the map display in the direction of movement, a single point symbol may optionally be rotated on its anchor point to retain its an upright orientation for the user(s) of the display. For a single point symbol, unless otherwise stated in the symbol's template, the symbol's anchor shall be the center of the symbol.**

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.




FIGURE L-13. Template for point (left) and supply point (right) control measure symbols.

L.5.7 Lines. In the tables that follow there are line control measure symbols that follow a specific format as shown in figure L-14 below. Most lines are also named as a phase line for easy reference for use in orders and during transmissions. A phase line will be marked as PL with the name in the T field. Other lines that have a specific purpose and are also named as phase lines should have the primary purpose in the T1 field (such as restrictive fire line "RFL") labeled on top of the line at both ends of the line inside the lateral boundaries or as often as necessary for clarity. The T field is used for fire support coordination measures to show the designation of the controlling headquarters. The use of phase lines to mark line control measure symbols is not mandatory. The gray box in figure L-14 is a placeholder for a specific symbol which is determined based on what control measure is being displayed.




FIGURE L-14. Template for line control measure symbols.

L.5.8 Areas. In the tables that follow there are area control measure symbols that follow a specific format as shown in figure L-15. Areas will normally be marked with the abbreviation for the type of area in the A field followed by a name in the T field. This labeling should be in the center of the area unless the area is too small, or the labeling would interfere with the locating of units. Not all fields are required for each area; some areas may use only one field, while other will use several. The gray box in figure L-15 is a placeholder for a specific symbol which is determined based on what control measure is being displayed.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.





FIGURE L-15. Template for area control measure symbols.









L.5.9 Area of operations. An area of operations is an operational area defined by a joint commander for land or maritime forces to conduct military activities. Normally, an area of operations does not encompass the entire joint operations area of the joint commander but is sufficient in size for the joint force component commander to accomplish assigned missions and protect forces. Operational area is an overarching term encompassing more descriptive terms for geographic areas in which military operations are conducted. Operational areas include, but are not limited to, such descriptors as area of responsibility, theatre of war, theatre of operations, joint operations area, amphibious objective area, joint special operations area, and area of operations.

TABLE L-V. Command and control areas.

DESCRIPTION	TEMPLATE	EXAMPLE **Note:** Symbols colored gray are used to help explain how the control measure is used and are not a part of the control measure.
Command and Control Areas Type: Entity Symbol Set: 25 Value: **12**0000	Reserved for hierarchical purposes.	N/A
Area of Operations Type: Entity Type Entity: Command and Control Areas Symbol Set: 25 Value: 12**01**00 Draw Rules: Area1 - Dynamic		




Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE L-V. Command and control areas - Continued.

DESCRIPTION	TEMPLATE	EXAMPLE **Note:** Symbols colored gray are used to help explain how the control measure is used and are not a part of the control measure.
Named Area of Interest Type: Entity Type Entity: Command and Control Areas Symbol Set: 25 Value: 12**02**00 Draw Rules: Area1 - Dynamic		
A geographical area where information is gathered to satisfy specific intelligence requirements.		
Target Area of Interest Type: Entity Type Entity: Command and Control Areas Symbol Set: 25 Value: 12**03**00 Draw Rules: Area1 - Dynamic		
The geographical area where high-value targets can be acquired and engaged by friendly forces.		
Airfield Zone Type: Entity Type Entity: Command and Control Areas Symbol Set: 25 Value: 12**04**00 Draw Rules: Area20 - Dynamic		
Note: The Field "H" for this symbol includes type of airfield, length of runway and other pertinent information.		
Base Camp Type: Entity Type Entity: Command and Control Areas Symbol Set: 25 Value: 12**05**00 Draw Rules: Area1 - Dynamic		
An evolving military facility that supports military operations of a deployed unit and provides the necessary support and services for sustained operations (ATP 3-37.10 / MCRP 3-17.7N).		

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE L-V. Command and control areas - Continued.

DESCRIPTION	TEMPLATE	EXAMPLE **Note:** Symbols colored gray are used to help explain how the control measure is used and are not a part of the control measure.
Guerrilla Base Type: Entity Type Entity: Command and Control Areas Symbol Set: 25 Value: 12**06**00 Draw Rules: Area1 - Dynamic	 	
	A temporary site where guerrilla installations, headquarters, and units are located (ATP 3-05.1).	
Generic Type: Entity Type Entity: Command and Control Areas Symbol Set: 25 Value: 12**07**00 Draw Rules: Area1 - Dynamic		






L.5.10 Command and control measure symbols. These symbols are used in the exercise of authority and direction by a properly designated commander over assigned and attached forces in the accomplishment of the mission.

TABLE L-VI. Command and control points.

DESCRIPTION	TEMPLATE	EXAMPLE **Note:** Symbols colored gray are used to help explain how the control measure is used and are not a part of the control measure.
Command and Control Points Type: Entity Symbol Set: 25 Value: **13**0000	Reserved for hierarchical purposes.	N/A







Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE L-VI. Command and control points - Continued.

DESCRIPTION	TEMPLATE	EXAMPLE **Note:** Symbols colored gray are used to help explain how the control measure is used and are not a part of the control measure.
Action Point (General) Type: Entity Type Entity: Command and Control Points Symbol Set: 25 Value: 13**01**00 Draw Rules: Point1 – Static		Examples follow
Amnesty Point Type: Entity Type Entity: Command and Control Points Symbol Set: 25 Value: 13**02**00 Draw Rules: Point1 – Static		
Checkpoint Type: Entity Type Entity: Command and Control Points Symbol Set: 25 Value: 13**03**00 Draw Rules: Point1 – Static		
	Predetermined point on the surface of the earth used as a means of controlling movement, a registration target for fire adjustment, or reference for location.	







Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE L-VI. Command and control points - Continued.

DESCRIPTION	TEMPLATE	EXAMPLE **Note:** Symbols colored gray are used to help explain how the control measure is used and are not a part of the control measure.
Center of Main Effort Type: Entity Type Entity: Command and Control Points Symbol Set: 25 Value: 13**04**00 Draw Rules: Point1 – Static		
	Note: The symbol can be rotated so that the lines at the top of the symbol are oriented toward the point of main effort.	
Contact Point Type: Entity Type Entity: Command and Control Points Symbol Set: 25 Value: 13**05**00 Draw Rules: Point2 – Static		
	In land warfare, a point on the terrain, easily identifiable, where two or more units are required to make contact.	
Coordinating Point Type: Entity Type Entity: Command and Control Points Symbol Set: 25 Value: 13**06**00 Draw Rules: Point2 – Static		
	Designated point at which, in all types of combat, adjacent units/formations must make contact for purposes of control and coordination.	
Decision Point Type: Entity Type Entity: Command and Control Points Symbol Set: 25 Value: 13**07**00 Draw Rules: Point2 – Static		
	A point in space and time, identified during the planning process, where it is anticipated that the commander must make a decision concerning a specific course of action.	







Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE L-VI. Command and control points - Continued.

DESCRIPTION	TEMPLATE	EXAMPLE **Note:** Symbols colored gray are used to help explain how the control measure is used and are not a part of the control measure.
Distress Call Type: Entity Type Entity: Command and Control Points Symbol Set: 25 Value: 13**08**00 Draw Rules: Point1 – Static		
Entry Control Point Type: Entity Type Entity: Command and Control Points Symbol Set: 25 Value: 13**09**00 Draw Rules: Point1 – Static		
Fly-To-Point Type: Entity Type Entity: Command and Control Points Symbol Set: 25 Value: 13**10**00	Reserved for hierarchical purposes.	N/A
Fly-To-Point (Sonobuoy) Type: Entity Subtype Entity/Entity Type: Command and Control Points and Fly-To-Point Symbol Set: 25 Value: 1310**01** Draw Rules: Point1 – Static		







Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE L-VI. Command and control points - Continued.

DESCRIPTION	TEMPLATE	EXAMPLE **Note:** Symbols colored gray are used to help explain how the control measure is used and are not a part of the control measure.
Fly-To-Point (Weapon) Type: Entity Subtype Entity/Entity Type: Command and Control Points and Fly-To-Point Symbol Set: 25 Value: 131**02** Draw Rules: Point1 – Static		
Fly-To-Point (Normal) Type: Entity Subtype Entity/Entity Type: Command and Control Points and Fly-To-Point Symbol Set: 25 Value: 131**03** Draw Rules: Point1 – Static		
Linkup Point Type: Entity Type Entity: Command and Control Points Symbol Set: 25 Value: 13**11**00 Draw Rules: Point1 – Static	 A point where two infiltrating elements in the same or different infiltration lanes are scheduled to meet to consolidate before proceeding with their missions.	







Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE L-VI. Command and control points - Continued.

DESCRIPTION	TEMPLATE	EXAMPLE **Note:** Symbols colored gray are used to help explain how the control measure is used and are not a part of the control measure.
Passage Point Type: Entity Type Entity: Command and Control Points Symbol Set: 25 Value: 131**2**00 Draw Rules: Point1 – Static		
	A specifically designated place where the passing units will pass through the stationary unit.	
Point of Interest Type: Entity Type Entity: Command and Control Points Symbol Set: 25 Value: 131**3**00 Draw Rules: Point1 – Static		
Point of Interest – Launch Event Type: Entity Subtype Entity/Entity Type: Command and Control Points and Point of Interest Symbol Set: 25 Value: 1313**01** Draw Rules: Point1 – Static		









Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE L-VI. Command and control points - Continued.

DESCRIPTION	TEMPLATE	EXAMPLE **Note:** Symbols colored gray are used to help explain how the control measure is used and are not a part of the control measure.
Rally Point Type: Entity Type Entity: Command and Control Points Symbol Set: 25 Value: 131**4**00 Draw Rules: Point1 – Static		
	An easily identifiable point on the ground at which units can reassemble and reorganize if they become dispersed.	
Release Point Type: Entity Type Entity: Command and Control Points Symbol Set: 25 Value: 131**5**00 Draw Rules: Point1 – Static		
	In road movements, a well-defined point on a route at which the elements composing a column return under the authority of their respective commanders, each one of these elements continuing its movement towards its own appropriate destination.	
Start Point Type: Entity Type Entity: Command and Control Points Symbol Set: 25 Value: 131**6**00 Draw Rules: Point1 – Static		
	A well-defined point on a route at which a movement of vehicles begins to be under the control of the commander of this movement. It is at this point that the column is formed by the successive passing, at an appointed time, of each of the elements composing the column. In addition to the principal start point of a column there may be secondary start points for its different elements.	



Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE L-VI. Command and control points - Continued.

DESCRIPTION	TEMPLATE	EXAMPLE **Note:** Symbols colored gray are used to help explain how the control measure is used and are not a part of the control measure.
Special Point Type: Entity Type Entity: Command and Control Points Symbol Set: 25 Value: 131700 Draw Rules: Point2 – Static		
Waypoint Type: Entity Type Entity: Command and Control Points Symbol Set: 25 Value: 131800 Draw Rules: Point2 – Static		
	Designated point or series of points loaded and stored in a global positioning system or other electronic navigational aid system to facilitate movement.	
Airfield **(AEGIS Only)** Type: Entity Type Entity: Command and Control Points Symbol Set: 25 Value: 131900 Draw Rules: Point2 – Static		
Target Handover Type: Entity Type Entity: Command and Control Points Symbol Set: 25 Value: 132000		

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE L-VI. Command and control points - Continued.

DESCRIPTION	TEMPLATE	EXAMPLE **Note:** Symbols colored gray are used to help explain how the control measure is used and are not a part of the control measure.
Draw Rules: Point2 – Static	Depicts a direct fire Target Handover mission is in progress, facilitates orientation of direct fires in order to maximize combat effectiveness and minimize fratricide	
Key Terrain Type: Entity Type Entity: Command and Control Points Symbol Set: 25 Value: 13**2**100 Draw Rules: Point2 – Static	 Key Terrain is any locality, or area, the seizure or retention of which affords a marked advantage to either combatant (JP 2-01.3). **Note:** The key terrain point uses medium purple with an RGB value of (128, 0, 128).	
Control Point Type: Entity Type Entity: Command and Control Points Symbol Set: 25 Value: 13**2**200 Draw Rules: Point1 – Static		

L.5.11 Maneuver control measure symbols.

L.5.11.1 Maneuver is the employment of forces on the battlefield through movement in combination with fire, or fire potential, to achieve a position of advantage in respect to the enemy in order to accomplish the mission.

TABLE L-VII. Maneuver control measure symbols.


DESCRIPTION	TEMPLATE	EXAMPLE **Note:** Symbols colored gray are used to help explain how the control measure is used and are not a part of the control measure.
Maneuver Lines Type: Entity Symbol Set: 25 Value: **14**0000	Reserved for hierarchical purposes.	N/A

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.


TABLE L-VII. Maneuver control measure symbols - Continued.


<table>
<tr><th>DESCRIPTION</th><th>TEMPLATE</th><th>EXAMPLE
Note: Symbols colored gray are used to help explain how the control measure is used and are not a part of the control measure.</th></tr>
<tr><td rowspan="3">Forward Line of Own Troops (FLOT)


Type: Entity Type
Entity: Maneuver Lines
Symbol Set: 25
Value: 140100

Draw Rules:
Line1 - Dynamic</td><td rowspan="3"> 

A line which indicates the most forward positions of forces in any kind of military operation at a specific time.


Note: The open side of the arc reflects the reported unit.</td><td> 



Friendly Present</td></tr>
<tr><td> 

Friendly Planned</td></tr>
<tr><td> 
Enemy Suspected or Templated</td></tr>
<tr><td colspan="2">Line of Contact

A general trace delineating the locations where two opposing forces are engaged.








The line of contact symbol is created when both the friendly and enemy forward line of troops symbols are displayed.

Note: The open side of the arc reflects the reported unit.</td><td> 
</td></tr>
<tr><td>Phase Line

Type: Entity Type
Entity: Maneuver Lines
Symbol Set: 25
Value: 140300</td><td> 
</td><td> 
</td></tr>
</table>






Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE L-VII. Maneuver control measure symbols - Continued.

DESCRIPTION	TEMPLATE	EXAMPLE **Note:** Symbols colored gray are used to help explain how the control measure is used and are not a part of the control measure.
Draw Rules: Line1- Dynamic	A line utilized for control and coordination of military operations, usually a terrain feature extending across the zone of action.	
Forward Edge of the Battle Area Type: Entity Type Entity: Maneuver Lines Symbol Set: 25 Value: 14**04**00 Draw Rules: Line1- Dynamic		
	The foremost limits of a series of areas in which ground combat units are deployed, excluding the areas in which the covering or screening forces are operating, designated to coordinate fire support, the positioning of forces or the maneuver of units.	
Principal Direction of Fire Type: Entity Type Entity: Maneuver Lines Symbol Set: 25 Value: 14**05**00 Draw Rules: Line3 - Dynamic		
	Orientation is determined by the anchor points. The arrowheads may touch other symbols that define the limits of the task. The top of the tactical symbol indicator may touch point 1	
Areas		
Maneuver Areas Type: Entity Symbol Set: 25 Value: **15**0000	Reserved for hierarchical purposes.	N/A
Area Type: Entity Type Entity: Maneuver Areas Symbol Set: 25 Value: 15**01**00 Draw Rules: Area1 - Dynamic		 Friendly Area  Planned








Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE L-VII. Maneuver control measure symbols - Continued.

DESCRIPTION	TEMPLATE	EXAMPLE **Note:** Symbols colored gray are used to help explain how the control measure is used and are not a part of the control measure.
		 Enemy
Assembly Area (AA) Type: Entity Type Entity: Maneuver Areas Symbol Set: 25 Value: 150**2**200 Draw Rules: Area1 - Dynamic		
	An area in which a command is assembled preparatory to further action.	
Action Area Type: Entity Type Entity Type: Maneuver Lines Symbol Set: 25 Value: 150**5**500	Reserved for hierarchical purposes.	N/A
Joint Tactical Action Area (JTAA) Type: Entity Subtype Entity/Entity Type: Maneuver Lines/Action Area Symbol Set: 25 Value: 15050**1** Draw Rules: Area1 - Dynamic		






Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE L-VII. Maneuver control measure symbols - Continued.

DESCRIPTION	TEMPLATE	EXAMPLE **Note:** Symbols colored gray are used to help explain how the control measure is used and are not a part of the control measure.
Submarine Action Area (SAA) Type: Entity Subtype Entity/Entity Type: Maneuver Lines/Action Area Symbol Set: 25 Value: 150**502** Draw Rules: Area1 - Dynamic		
Submarine- Generated Action Area (SGAA) Type: Entity Subtype Entity/Entity Type: Maneuver Lines/Action Area Symbol Set: 25 Value: 150**503** Draw Rules: Area1 - Dynamic		
Drop Zone (DZ) Type: Entity Type Entity: Maneuver Areas Symbol Set: 25 Value: 15**06**00 Draw Rules: Area1 - Dynamic	 A specified area upon which airborne troops, equipment, or supplies are airdropped.	
Extraction Zone (EZ) Type: Entity Type Entity: Maneuver Areas Symbol Set: 25 Value: 15**07**00 Draw Rules: Area1 - Dynamic	 A specified drop zone used for the delivery of supplies and/or equipment by means of an extraction technique from an aircraft flying very close to the ground.	
Landing Zone (LZ) Type: Entity Type Entity: Maneuver Areas Symbol Set: 25		







Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE L-VII. Maneuver control measure symbols - Continued.

DESCRIPTION	TEMPLATE	EXAMPLE **Note:** Symbols colored gray are used to help explain how the control measure is used and are not a part of the control measure.
Value: 15**08**00 Draw Rules: Area1 - Dynamic	A specified zone used for the landing of aircraft on land, water or deck.	
Pickup Zone (PZ) Type: Entity Type Entity: Maneuver Areas Symbol Set: 25 Value: 15**09**00 Draw Rules: Area1 - Dynamic	 A geographic area used to pick up troops or equipment by helicopter.	
Fortified Area Type: Entity Type Entity: Maneuver Areas Symbol Set: 25 Value: 15**10**00 Draw Rules: Area1 - Dynamic		
Limited Access Area Type: Entity Type Entity: Maneuver Areas Symbol Set: 25 Value: 15**11**00 Draw Rules: Area2 - Dynamic		







Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE L-VIII. Maneuver control measure symbols - Continued.

DESCRIPTION	TEMPLATE	EXAMPLE **Note:** Symbols colored gray are used to help explain how the control measure is used and are not a part of the control measure.
Areas		
Encirclement The loss of freedom of maneuver resulting from enemy control of all ground routes of evacuation and reinforcement. Type: Entity Type Entity: Maneuver Areas Symbol Set: 25 Value: 151**8**00 Draw Rules: Area1 - Dynamic	N/A **Note**: Although unit symbols are not part of a control measure symbol area, numerous unit symbols can be included in the area for presentation.	 Friendly  Enemy
Penetration Box Type: Entity Type Entity: Maneuver Areas Symbol Set: 25 Value: 151**9**00 Draw Rules: Area1 - Dynamic		
Attack By Fire Type: Entity Type Entity: Maneuver Areas Symbol Set: 25 Value: 152**0**00 Draw Rules: Area7 - Dynamic	 **Orientation:** Orientation is determined by the anchor points. The back side of the symbol encompasses the firing position, while the arrowhead typically points at the target.	






Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE L-VIII. Maneuver control measure symbols - Continued.

DESCRIPTION	TEMPLATE	EXAMPLE **Note:** Symbols colored gray are used to help explain how the control measure is used and are not a part of the control measure.
Support by Fire Type: Entity Type Entity: Maneuver Areas Symbol Set: 25 Value: 15**2**100 Draw Rules: Area8 - Dynamic		
	Orientation: Orientation is determined by the anchor points. The back side of the symbol encompasses the firing position, while the arrowheads typically indicate the left and right limits of coverage that the firing position is meant to support.	
Search Area/Reconnaissance Area Type: Entity Type Entity: Maneuver Areas Symbol Set: 25 Value: 15**22**00 Draw Rules: Area21 - Dynamic		
	Orientation: Orientation is determined by the anchor points. The arrowheads may touch other symbols that define the limits of the task. The tactical symbol indicator is centered over point 1.	
Airhead Line Type: Entity Type Entity Type: Maneuver Lines Symbol Set: 25 Value: 14**1**300 Draw Rules: Area1 - Dynamic	 AIRHEAD LINE	 AIRHEAD LINE
	A line denoting the limits of the objective area for an airborne assault. Airhead: A designated area in a hostile or threatened territory which, when seized and held, ensures the continuous air landing of troops and materiel and provides the maneuver space necessary for projected operations. Normally it is the area seized in the assault phase of an airborne operation.	




Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE L-VIII. Maneuver control measure symbols - Continued.

DESCRIPTION	TEMPLATE	EXAMPLE **Note:** Symbols colored gray are used to help explain how the control measure is used and are not a part of the control measure.
Lines		
Bridgehead Line (BL) The planned, temporary limit of the objective area in the development of the bridgehead. Type: Entity Type Entity Type: Maneuver Lines Symbol Set: 25 Value: 14**1**400 Draw Rules: Line1- Dynamic		
Holding Line (HL) Type: Entity Type Entity Type: Maneuver Lines Symbol Set: 25 Value: 14**1**500 Draw Rules: Line1- Dynamic		
	In retrograde river crossing operations, the outer limit of the area established between the enemy and the water obstacle to preclude direct and observed indirect fires into the crossings.	
Release Line Type: Entity Type Entity Type: Maneuver Lines Symbol Set: 25 Value: 14**1**600 Draw Rules: Line1- Dynamic		
	Phase line used in river crossing operations that delineates a change in the headquarters controlling movement.	

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE L-VIII. Maneuver control measure symbols - Continued.









DESCRIPTION	TEMPLATE	EXAMPLE **Note:** Symbols colored gray are used to help explain how the control measure is used and are not a part of the control measure.
Ambush Type: Entity Type Entity Type: Maneuver Lines Symbol Set: 25 Value: 141700 Draw Rules: Line29 - Dynamic		
A surprise attack by fire from concealed positions on a moving or temporarily halted enemy. Orientation is determined by the anchor points. The back side of the symbol encompasses the ambush position, while the arrowhead typically points at the target.		
Handover Line Type: Entity Type Entity Type: Maneuver Lines Symbol Set: 25 Value: 141800 Draw Rules: Line1- Dynamic		
Battle Handover Line Type: Entity Type Entity Type: Maneuver Lines Symbol Set: 25 Value: 141900 Draw Rules: Line1- Dynamic		

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

L.5.12 Defensive maneuver. Defensive operations defeat an enemy attack, buy time, economize forces, or develop conditions favorable for offensive operations.





L.5.12.1 Areas.

TABLE L-IX. Defensive control measure symbols.

DESCRIPTION	TEMPLATE	EXAMPLE **Note:** Symbols colored gray are used to help explain how the control measure is used and are not a part of the control measure.
Battle Position Type: Entity Type Entity: Maneuver Areas Symbol Set: 25 Value: 15**12**00 Draw Rules: Area3 - Dynamic		
	A defensive location oriented on a likely enemy avenue of approach. **Orientation:** The side opposite Field B (Echelon) faces toward the hostile force.	
Battle Position Prepared (P) but not Occupied Type: Entity Subtype Entity/Entity Type: Maneuver Areas/Battle Position Symbol Set: 25 Value: 1512**02** Draw Rules: Area3 - Dynamic		
	Orientation: The side opposite Field B (Echelon) faces toward the hostile force.	
Strong Point Type: Entity Subtype Entity/Entity Type: Maneuver Areas/Battle Position Symbol Set: 25 Value: 1512**03** Draw Rules: Area4 - Dynamic		
	A key point in a defensive position usually strongly fortified and heavily armed with automatic weapons, around which other positions are grouped for its protection. ‘See ADP 3-90 for more information.’	
Contain Type: Entity Subtype Entity/Entity Type: Maneuver Areas/Battle Position Symbol Set: 25		

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE L-IX. Defensive control measure symbols – Continued.

DESCRIPTION	TEMPLATE	EXAMPLE **Note:** Symbols colored gray are used to help explain how the control measure is used and are not a part of the control measure.
Value: 151**04** Draw Rules: Area5 - Dynamic	**Orientation:** The opening typically faces enemy forces.	
Retain Type: Entity Subtype Entity/Entity Type: Maneuver Areas/Battle Position Symbol Set: 25 Value: 151**05** Draw Rules: Area6 - Dynamic	 **Orientation:** The opening will be on the friendly side of the symbol.	
Engagement Area (EA) Type: Entity Type Entity: Maneuver Areas Symbol Set: 25 Value: 15**12**00 Symbol Set: 25 Value: 15**13**00 Draw Rules: Area1 - Dynamic	 An area where the commander intends to contain and destroy an enemy force with the massed effects of all available weapons and supporting systems.	







L.5.12.2 Observation post. A position from which military observations are made, or fire directed and adjusted, and which possesses appropriate communications; may be airborne.

TABLE L-X. Observation post.

DESCRIPTION	TEMPLATE	EXAMPLE **Note:** Symbols colored gray are used to help explain how the control measure is used and are not a part of the control measure.
Maneuver Points Type: Entity Symbol Set: 25 Value: **16**0000	Reserved for hierarchical purposes.	N/A






Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE L-X. Observation post - Continued.

DESCRIPTION	TEMPLATE	EXAMPLE **Note:** Symbols colored gray are used to help explain how the control measure is used and are not a part of the control measure.
Observation Post /Outpost (Unspecified) Type: Entity Type Entity: Maneuver Points Symbol Set: 25 Value: 16**01**00 Draw Rules: Point2 – Static		
Observation Post /Outpost (Specified) Type: Entity Type Entity: Maneuver Points Symbol Set: 25 Value: 16**02**00	N/A Templates follow.	N/A Examples follow.
Reconnaissance Outpost Type: Entity Subtype Entity/Entity Type: Maneuver Points/Observation Post/Outpost (specified) Symbol Set: 25 Value: 1602**01** Draw Rules: Point2 – Static		
Forward Observer Spotter Outpost/ Position Type: Entity Subtype Entity/Entity Type: Maneuver Points/Observation Post/Outpost (specified) Symbol Set: 25 Value: 1602**02** Draw Rules: Point2 – Static		



Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE L-X. Observation post - Continued.

DESCRIPTION	TEMPLATE	EXAMPLE **Note:** Symbols colored gray are used to help explain how the control measure is used and are not a part of the control measure.
CBRN Observation Outpost Type: Entity Subtype Entity/Entity Type: Maneuver Points/Observation Post/Outpost (specified) Symbol Set: 25 Value: 160**03** Draw Rules: Point2 – Static		
Sensor Outpost/Listening Post Type: Entity Subtype Entity/Entity Type: Maneuver Points/Observation Post/Outpost (specified) Symbol Set: 25 Value: 160**04** Draw Rules: Point2 – Static		
Combat Outpost Type: Entity Subtype Entity/Entity Type: Maneuver Points/Observation Post/Outpost (specified) Symbol Set: 25 Value: 160**05** Draw Rules: Point2 – Static		

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.



TABLE L-X. Observation post - Continued.

DESCRIPTION	TEMPLATE	EXAMPLE **Note:** Symbols colored gray are used to help explain how the control measure is used and are not a part of the control measure.
Target Reference Point Type: Entity Type Entity: Maneuver Points Symbol Set: 25 Value: 16**03**00 Draw Rules: Point2 – Static		
	"A predetermined point of reference, normally a permanent structure or terrain feature that can be used when describing a target location. Also called TRP." (JP 3-09.3)	

L.5.13 Offensive maneuver. Offensive operations aim at destroying or defeating an enemy.






L.5.14 Axis of advance. A line of advance assigned for purposes of control; often a road or a group of roads, or a designated series of locations, extending in the direction of the enemy.

TABLE L-XI. Offensive Control Measure Symbols.

DESCRIPTION	TEMPLATE	EXAMPLE **Note:** Symbols colored gray are used to help explain how the control measure is used and are not a part of the control measure.
Axis of Advance Type: Entity Type Entity: Maneuver Areas Symbol Set: 25 Value: 15**14**00	Reserved for hierarchical purposes.	N/A
Friendly Airborne/ Aviation Type: Entity Subtype Entity/Entity Type: Maneuver Areas/Axis of Advance Symbol Set: 25 Value: 1514**01** Draw Rules:		 Airborne





Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE L-XI. Offensive Control Measure Symbols - Continued.

DESCRIPTION	TEMPLATE	EXAMPLE **Note:** Symbols colored gray are used to help explain how the control measure is used and are not a part of the control measure.
Axis1 - Dynamic **Orientation:** The arrowhead typically points toward enemy forces.		 Aviation
Attack Helicopter Type: Entity Subtype Entity/Entity Type: Maneuver Areas/Axis of Advance Symbol Set: 25 Value: 151**402** Draw Rules: Axis1 - Dynamic **Orientation:** The arrowhead typically points toward enemy forces.		
Main Attack Type: Entity Subtype Entity/Entity Type: Maneuver Areas/Axis of Advance Symbol Set: 25 Value: 151**403** Draw Rules: Axis2 - Dynamic **Orientation:** The arrowhead typically points toward enemy forces.	 The principal attack or effort into which the commander throws the full weight of the offensive power at his disposal.	

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.








TABLE L-XI. Offensive Control Measure Symbols - Continued.

DESCRIPTION	TEMPLATE	EXAMPLE **Note:** Symbols colored gray are used to help explain how the control measure is used and are not a part of the control measure.
Supporting Attack Type: Entity Subtype Entity/Entity Type: Maneuver Areas/Axis of Advance Symbol Set: 25 Value: 151**04** Draw Rules: Axis2 - Dynamic **Orientation:** The arrowhead typically points toward enemy forces.		 Supporting Attack
	An offensive operation carried out in conjunction with a main attack and designed to achieve one or more of the following: a. deceive the enemy; b. destroy or pin down enemy forces which could interfere with the main attack; c. control ground whose occupation by the enemy will hinder the main attack; or d. force the enemy to commit reserves prematurely or in an indecisive area.	 Planned
		 Enemy Templated or Suspected

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.








L.5.14.1 Direction of attack. A specific direction or route that the main attack or center of mass of the unit will follow.

TABLE L-XII. Offensive Control Measure Symbols.

DESCRIPTION	TEMPLATE	EXAMPLE **Note:** Symbols colored gray are used to help explain how the control measure is used and are not a part of the control measure.
Friendly Aviation Type: Entity Type Entity/Entity Subtype: Maneuver Lines/Direction of Attack Symbol Set: 25 Value: 1406**01** Draw Rules: Line1 - Dynamic		
Friendly Direction of Main Attack Type: Entity Type Entity/Entity Subtype: Maneuver Lines/Direction of Attack Symbol Set: 25 Value: 1406**02** Draw Rules: Line1 - Dynamic		
Friendly Direction of Supporting Attack Type: Entity Type Entity/Entity Subtype: Maneuver Lines/Direction of Attack Symbol Set: 25 Value: 1406**03** Draw Rules: Line1 – Dynamic		 Direction of Supporting Attack  Planned  Enemy Templated or Suspected






Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE L-XII. Offensive Control Measure Symbols - Continued.

DESCRIPTION	TEMPLATE	EXAMPLE **Note:** Symbols colored gray are used to help explain how the control measure is used and are not a part of the control measure.
Final Coordination Line Type: Entity Type Entity Type: Maneuver Lines Symbol Set: 25 Value: 14**07**00 Draw Rules: Line1- Dynamic		
	A line close to the enemy position used to coordinate the lifting or shifting of supporting fires with the final deployment of maneuver elements.	
Infiltration Lane Type: Entity Type Entity Type: Maneuver Lines Symbol Set: 25 Value: 14**08**00 Draw Rules: Polyline1 - Dynamic		
	A control measure that coordinates forward and lateral movement of infiltrating units and fixes fire planning responsibilities. Orientation is determined by points 1 and 2.	
Limit of Advance Type: Entity Type Entity Type: Maneuver Lines Symbol Set: 25 Value: 14**09**00 Draw Rules: Line1- Dynamic		
	An easily recognized terrain feature beyond which attacking elements will not advance.	
Line of Departure Type: Entity Type Entity Type: Maneuver Lines Symbol Set: 25 Value: 14**10**00 Draw Rules: Line1- Dynamic		
	In land warfare, a line designated to coordinate the departure of attack elements. In amphibious warfare, a suitably marked offshore coordinating line to assist assault craft to land on designated beaches at scheduled times.	





Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE L-XII. Offensive Control Measure Symbols - Continued.

DESCRIPTION	TEMPLATE	EXAMPLE **Note:** Symbols colored gray are used to help explain how the control measure is used and are not a part of the control measure.
Line of Departure / Line of Contact Type: Entity Type Entity Type: Maneuver Lines Symbol Set: 25 Value: 14**11**00 Draw Rules: Line1- Dynamic		
	The designation of forward friendly positions as the line of departure when opposing forces are in contact.	
Probable Line of Deployment Type: Entity Type Entity Type: Maneuver Lines Symbol Set: 25 Value: 14**12**00 Draw Rules: Line1- Dynamic		
	A line selected on the ground, usually the last covered and concealed position prior to the objective and forward of the line of departure, where attacking units deploy prior to beginning an assault; it is generally used under conditions of limited visibility. **Note**: The dashed lines in this symbol shall be displayed in present and anticipated status.	
Areas		
Assault Position Type: Entity Type Entity: Maneuver Areas Symbol Set: 25 Value: 15**15**00 Draw Rules: Area1 - Dynamic		
	That position between the line of departure and the objective in an attack from which forces assault the objective. Ideally, it is the last covered and concealed position before reaching the objective.	

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE L-XII. Offensive Control Measure Symbols - Continued.




DESCRIPTION	TEMPLATE	EXAMPLE **Note:** Symbols colored gray are used to help explain how the control measure is used and are not a part of the control measure.
Attack Position The last position occupied by the assault echelon before crossing the start line/line of departure. Type: Entity Type Entity: Maneuver Areas Symbol Set: 25 Value: 15**16**00 Draw Rules: Area1 - Dynamic		
Objective Area Type: Entity Type Entity: Maneuver Areas Symbol Set: 25 Value: 15**17**00 Draw Rules: Area1 - Dynamic	 A defined geographical area within which is located an objective to be captured or reached by the military forces. This area is defined by competent authority for purposes of command and control.	
Points		
Point of Departure Type: Entity Type Entity: Maneuver Points Symbol Set: 25 Value: 16**04**00 Draw Rules: Point1 – Static	 A specific place where a unit will cross the line of departure. **Note:** The offset indicator is used in the example to allow the viewer to better see the LD. It is not required.	

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

L.5.15 Airspace coordinating measures.

L.5.15.1 Airspace coordinating measures. Measures employed to facilitate the efficient use of airspace to accomplish missions and simultaneously provide safeguards for friendly forces. Also called ACMs. (See JP 3-52 for more reference)

TABLE L-XIII. Airspace coordinating measures.



DESCRIPTION	TEMPLATE	EXAMPLE **Note:** Symbols colored gray are used to help explain how the control measure is used and are not a part of the control measure.
Corridors (Areas)		
Airspace Control (Corridors) Areas Type: Entity Symbol Set: 25 Value: **17**0000	N/A	N/A
Air Corridor Type: Entity Entity Type: Airspace Control (Corridors) Areas Symbol Set: 25 Value: 17**01**00 Draw Rules: Corridor1 - Dynamic	 A restricted air route of travel specified for use by friendly aircraft and established for the purpose of preventing friendly aircraft from being fired on by friendly forces. (JP-3-52)	
Air Corridor with Multiple Segments		

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.



TABLE L-XIII. Airspace coordinating measures - Continued.

<table>
<tr><th>DESCRIPTION</th><th>TEMPLATE</th><th>EXAMPLE
Note: Symbols colored gray are used to help explain how the control measure is used and are not a part of the control measure.</th></tr>
<tr><td rowspan="2">Low-Level Transit Route (LLTR)



Type: Entity
Entity Type: Airspace Control (Corridors)
Areas
Symbol Set: 25
Value: 170200

Draw Rules:
Corridor1 - Dynamic</td><td> 
</td><td> 
</td></tr>
<tr><td colspan="2">A temporary corridor of defined dimensions established in the forward area to minimize the risk to friendly aircraft from friendly air defenses or surface forces. Also called (LLTR). (JP 3-52)</td></tr>
<tr><td rowspan="2">Minimum-Risk Route (MMR)

Type: Entity
Entity Type: Airspace Control (Corridors)
Areas
Symbol Set: 25
Value: 170300




Draw Rules:
Corridor1 - Dynamic</td><td> 
</td><td> 
</td></tr>
<tr><td colspan="2">A temporary corridor of defined dimensions recommended for use by high-speed, fixed-wing aircraft that presents the minimum known hazards to low-flying aircraft transiting the combat zone. Also called MMR. (JP-3-52)</td></tr>
<tr><td rowspan="2">Safe Lane (NATO)

Type: Entity
Entity Type: Airspace Control (Corridors)
Areas
Symbol Set: 25
Value: 170400

Draw Rules:
Corridor1 - Dynamic</td><td> 
</td><td> 
</td></tr>
<tr><td colspan="2">A bi-directional lane connecting an airbase, landing site and/or base defense zone to adjacent routes/corridors. Safe lanes may also be used to connect adjacent activated routes/ corridors. (AJP-3.3.5)</td></tr>
</table>







Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE L-XIII. Airspace coordinating measures - Continued.

DESCRIPTION	TEMPLATE	EXAMPLE **Note:** Symbols colored gray are used to help explain how the control measure is used and are not a part of the control measure.
Standard Use Army Aircraft Flight Route (SAAFR) Type: Entity Entity Type: Airspace Control (Corridors) Areas Symbol Set: 25 Value: 170500 Draw Rules: Corridor1 - Dynamic		Name: BLUE Width: 600FT Min Alt: 150FT AGL Max Alt: 3000FT AGL DTG Start: 260930ZMAY2008 DTG End: 280700ZMAY2008 
(US) Route established below the coordination level to facilitate the movement of Army aviation assets; it is normally located in the corps through brigade rear areas of operation and does not require approval by the airspace control authority. (JP 3-52)		
Transit Corridors Type: Entity Entity Type: Airspace Control (Corridors) Areas Symbol Set: 25 Value: 170600 Draw Rules: Corridor1 - Dynamic		Name: KING Width: 900FT Min Alt: 2100FT AGL Max Alt: 6000FT AGL DTG Start: 260700ZMAR2008 DTG End: 280700ZMAR2008 
Transit Corridor (TC) Bi-directional corridor in the rear area. Air traffic services not normally provided. (AJP-3.3.5)		
Special Corridor Type: Entity Entity Type: Airspace Control (Corridors) Areas Symbol Set: 25 Value: 170700 Draw Rules: Corridor1 - Dynamic		Name: DRAGON Width: 1200FT Min Alt: 1500FT AGL Max Alt: 12000FT AGL DTG Start: 200700ZMAY2008 DTG End: 210700ZMAY2008 
In air operations, an air corridor established to accommodate the special routing requirements of specific missions. (AJP-3.3.5)		







Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE L-XIII. Airspace coordinating measures - Continued.

DESCRIPTION	TEMPLATE	EXAMPLE **Note:** Symbols colored gray are used to help explain how the control measure is used and are not a part of the control measure.
Areas (Zones)		
Base Defense Zone (BDZ) Type: Entity Entity Type: Airspace Control (Corridors) Areas Symbol Set: 25 Value: 17**08**00 Draw Rules: Area22 - Static		
	"An air defense zone established around an air base and limited to the engagement envelope of short-range air defense systems defending that base." (JP 3-52) **Orientation:** The symbol is typically centered over the desired location.	
High-Density Airspace Control Zone (HIDACZ) Type: Entity Entity Type: Airspace Control (Corridors) Areas Symbol Set: 25 Value: 17**09**00 Draw Rules: Area1 - Dynamic		
	"Airspace designated in an airspace control plan or airspace control order in which there is a concentrated employment of numerous and varied weapons and airspace users. Also called HIDACZ." (JP 3-52)	
Restricted Operations Zones		
Restricted Operations Zone (ROZ) Type: Entity Entity Type: Airspace Control (Corridors) Areas Symbol Set: 25 Value: 17**10**00 Draw Rules: Area1 - Dynamic		
	Airspace reserved for specific activities in which the operations of one or more airspace users is restricted. Also called ROZ. (See JP 3-52 for more information)	







Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE L-XIII. Airspace coordinating measures - Continued.

DESCRIPTION	TEMPLATE	EXAMPLE **Note:** Symbols colored gray are used to help explain how the control measure is used and are not a part of the control measure.
Air-to-Air Restricted Operations Zone (AARROZ) Type: Entity Entity Type: Airspace Control (Corridors) Areas Symbol Set: 25 Value: 171**1**100 Draw Rules: Area1 - Dynamic		
Unmanned Aircraft Restricted Operations Zone (UA-ROZ) Type: Entity Entity Type: Airspace Control (Corridors) Areas Symbol Set: 25 Value: 171**2**00 Draw Rules: Area1 - Dynamic		
Weapons Engagement Zones		
Weapon Engagement Zone Type: Entity Entity Type: Airspace Control (Corridors) Areas Symbol Set: 25 Value: 171**3**00 Draw Rules: Area1 - Dynamic	 In air defense, airspace of defined dimensions within which the responsibility for engagement normally rests with a particular weapon system.	







Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE L-XIII. Airspace coordinating measures - Continued.

DESCRIPTION	TEMPLATE	EXAMPLE **Note:** Symbols colored gray are used to help explain how the control measure is used and are not a part of the control measure.
Fighter Engagement Zone (FEZ) Type: Entity Entity Type: Airspace Control (Corridors) Areas Symbol Set: 25 Value: 171**4**00 Draw Rules: Area1 - Dynamic		
	In air defense, airspace of defined dimensions within which the responsibility for engagement normally rests with a particular weapon system.	
Joint Engagement Zone (JEZ) Type: Entity Entity Type: Airspace Control (Corridors) Areas Symbol Set: 25 Value: 171**5**00 Draw Rules: Area1 - Dynamic		
	In air defense, that airspace of defined dimensions within which multiple air defense systems (surface-to-air missiles and aircraft) are simultaneously employed to engage air threats.	
Missile Engagement Zone (MEZ) Type: Entity Entity Type: Airspace Control (Corridors) Areas Symbol Set: 25 Value: 171**6**00 Draw Rules: Area1 - Dynamic		
	In air defense, airspace of defined dimensions within which the responsibility for engagement normally rests with a particular weapon system.	






Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE L-XIII. Airspace coordinating measures - Continued.

DESCRIPTION	TEMPLATE	EXAMPLE **Note:** Symbols colored gray are used to help explain how the control measure is used and are not a part of the control measure.
Low (Altitude) Missile Engagement Zone (LOMEZ) Type: Entity Entity Type: Airspace Control (Corridors) Areas Symbol Set: 25 Value: 171700 Draw Rules: Area1 - Dynamic		
High (Altitude) Missile Engagement Zone (HIMEZ) Type: Entity Entity Type: Airspace Control (Corridors) Areas Symbol Set: 25 Value: 171800 Draw Rules: Area1 - Dynamic		
Short Range Air Defense Engagement Zone (SHORADEZ) Type: Entity Entity Type: Airspace Control (Corridors) Areas Symbol Set: 25 Value: 171900 Draw Rules: Area1 - Dynamic	 In air defense, airspace of defined dimensions within which the responsibility for engagement normally rests with a particular weapon system. **Note**: Replaces Forward Area Air Defense Engagement Zone (FAADEZ)	







Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE L-XIII. Airspace coordinating measures - Continued.

DESCRIPTION	TEMPLATE	EXAMPLE **Note:** Symbols colored gray are used to help explain how the control measure is used and are not a part of the control measure.
Weapons Free Zone Type: Entity Entity Type: Airspace Control (Corridors) Areas Symbol Set: 25 Value: 172**0**00 Draw Rules: Area1 - Dynamic		
	An air defense zone established around key assets or facilities other than airbases which merit special protection by ground based air defense assets where weapons may be fired at any target not positively identified as friendly. (AJP-3.3.5) **Note:** Upward diagonal lines are part of the fill.	
Points		
Airspace Control Points Type: Airspace Control Points Symbol Set: 25 Value: **18**0000 Draw Rules: Point2 – Static	Reserved for hierarchical purposes.	N/A
Air Control Point Type: Entity Type Entity: Airspace Control Points Symbol Set: 25 Value: 18**01**00 Draw Rules: Point2 – Static		
Communications Check Point Type: Entity Type Entity: Airspace Control Points Symbol Set: 25 Value: 18**02**00 Draw Rules: Point2 – Static		





Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE L-XIII. Airspace coordinating measures - Continued.

DESCRIPTION	TEMPLATE	EXAMPLE **Note:** Symbols colored gray are used to help explain how the control measure is used and are not a part of the control measure.
Isolated Personnel Recovery Point Type: Entity Type Entity: Airspace Control Points Symbol Set: 25 Value: 18**03**00 Draw Rules: Point1 – Static		
Pop-Up Point (PUP) Type: Entity Type Entity: Airspace Control Points Symbol Set: 25 Value: 18**04**00 Draw Rules: Point2 – Static		
	The location at which aircraft quickly gain altitude for target acquisition and engagement.	
Air Control Rendezvous Type: Entity Type Entity: Airspace Control Points Symbol Set: 25 Value: 18**05**00 Draw Rules: Point2 – Static		
Tactical Air Navigation (TACAN) Type: Entity Type Entity: Airspace Control Points Symbol Set: 25 Value: 18**06**00 Draw Rules: Point2 – Static		







Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE L-XIII. Airspace coordinating measures - Continued.

DESCRIPTION	TEMPLATE	EXAMPLE **Note:** Symbols colored gray are used to help explain how the control measure is used and are not a part of the control measure.
Combat Air Patrol (CAP) Station Type: Entity Type Entity: Airspace Control Points Symbol Set: 25 Value: 18**0**700 Draw Rules: Point2 – Static		
Airborne Early Warning (AEW) Station Type: Entity Type Entity: Airspace Control Points Symbol Set: 25 Value: 18**0**800 Draw Rules: Point2 – Static		
ASW (Helo and F/W) Station Type: Entity Type Entity: Airspace Control Points Symbol Set: 25 Value: 18**0**900 Draw Rules: Point2 – Static		
Strike Initial Point Type: Entity Type Entity: Airspace Control Points Symbol Set: 25 Value: 18**1**000 Draw Rules: Point2 – Static		







Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE L-XIII. Airspace coordinating measures - Continued.

DESCRIPTION	TEMPLATE	EXAMPLE **Note:** Symbols colored gray are used to help explain how the control measure is used and are not a part of the control measure.
Replenishment Station Type: Entity Type Entity: Airspace Control Points Symbol Set: 25 Value: 18**1**100 Draw Rules: Point2 – Static		
Tanking Type: Entity Type Entity: Airspace Control Points Symbol Set: 25 Value: 18**1**200 Draw Rules: Point2 – Static		
Antisubmarine Warfare, Rotary Wing Type: Entity Type Entity: Airspace Control Points Symbol Set: 25 Value: 18**1**300 Draw Rules: Point2 – Static		
Surface Combat Air Patrol (SUCAP) – Fixed Wing Type: Entity Type Entity: Airspace Control Points Symbol Set: 25 Value: 18**1**400 Draw Rules: Point2 – Static		







Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE L-XIII. Airspace coordinating measures - Continued.

DESCRIPTION	TEMPLATE	EXAMPLE **Note:** Symbols colored gray are used to help explain how the control measure is used and are not a part of the control measure.
SUCAP – Rotary Wing Type: Entity Type Entity: Airspace Control Points Symbol Set: 25 Value: 18**15**00 Draw Rules: Point2 – Static		
MIW – Fixed Wing Type: Entity Type Entity: Airspace Control Points Symbol Set: 25 Value: 18**16**00 Draw Rules: Point2 – Static		
MIW – Rotary Wing Type: Entity Type Entity: Airspace Control Points Symbol Set: 25 Value: 18**17**00 Draw Rules: Point2 – Static		
Tomcat Type: Entity Type Entity: Airspace Control Points Symbol Set: 25 Value: 18**18**00 Draw Rules: Point2 – Static		







Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE L-XIII. Airspace coordinating measures - Continued.

DESCRIPTION	TEMPLATE	EXAMPLE **Note:** Symbols colored gray are used to help explain how the control measure is used and are not a part of the control measure.
Rescue Type: Entity Type Entity: Airspace Control Points Symbol Set: 25 Value: 18**19**00 Draw Rules: Point2 – Static		
Unmanned Aerial System (UAS/UA) Type: Entity Type Entity: Airspace Control Points Symbol Set: 25 Value: 18**20**00 Draw Rules: Point2 – Static		
Vertical Take-off and Landing (VTOL)Tactical Unmanned Aircraft (VTUA) Type: Entity Type Entity: Airspace Control Points Symbol Set: 25 Value: 18**21**00 Draw Rules: Point2 – Static		
Orbit Type: Entity Type Entity: Airspace Control Points Symbol Set: 25 Value: 18**22**00 Draw Rules: Point2 – Static		

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE L-XIII. Airspace coordinating measures - Continued.

DESCRIPTION	TEMPLATE	EXAMPLE **Note:** Symbols colored gray are used to help explain how the control measure is used and are not a part of the control measure.
Orbit – Figure Eight Type: Entity Type Entity: Airspace Control Points Symbol Set: 25 Value: 18**2**300 Draw Rules: Point2 – Static		
Orbit – Race Track Type: Entity Type Entity: Airspace Control Points Symbol Set: 25 Value: 18**2**400 Draw Rules: Point2 – Static		
Orbit – Random Closed Type: Entity Type Entity: Airspace Control Points Symbol Set: 25 Value: 18**2**500 Draw Rules: Point2 – Static		
Isolated Personnel Location Type: Entity Type Entity: Airspace Control Points Symbol Set: 25 Value: 18**2**600 Draw Rules: Point2 - Static		
Lines		
Airspace Control Lines Type: Entity Symbol Set: 25 Value: **1**90000	N/A	N/A

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE L-XIII. Airspace coordinating measures - Continued.

DESCRIPTION	TEMPLATE	EXAMPLE **Note:** Symbols colored gray are used to help explain how the control measure is used and are not a part of the control measure.
Identification, Friend-or-Foe (IFF) Off Line Type: Entity Type Entity: Airspace Control Lines Symbol Set: 25 Value: 19**01**00 Draw Rules: Line1- Dynamic		
	Line demarking where friendly aircraft en-route to targets stop emitting an IFF signal. (AJP-3.3.5)	
Identification, Friend-or-Foe (IFF) On Line Type: Entity Type Entity: Airspace Control Lines Symbol Set: 25 Value: 19**02**00 Draw Rules: Line1- Dynamic		
	Line demarking where friendly aircraft returning to friendly territory start emitting an IFF signal. (AJP-3.3.5)	

L.5.16 Maritime control measures.





L.5.16.1 Maritime control measures. Are used by NATO to help the maritime component commander and their subordinate commanders to direct action by establishing responsibilities and to prevent ships, units, or aircraft from impeding one another and to impose necessary coordination. They aide the cooperation among forces without imposing needless restrictions on their freedom of action. In general terms, maritime control measures can be broken down into the following groups: points, lines and areas.

TABLE L-XIV. Maritime control measures.

DESCRIPTION	TEMPLATE	EXAMPLE **Note:** Symbols colored gray are used to help explain how the control measure is used and are not a part of the control measure.
Maritime Control Area Type: Entity Symbol Set: 25 Value: **20**0000	N/A	N/A






Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE L-XIV. Maritime control measures - Continued.

DESCRIPTION	TEMPLATE	EXAMPLE **Note:** Symbols colored gray are used to help explain how the control measure is used and are not a part of the control measure.
Launch Area Type: Entity Type Entity: Maritime Control Areas Symbol Set: 25 Value: 20**01**00	N/A	N/A
Launch Area, Ellipse/Circle (AEGIS only) Type: Entity Subtype Entity/Entity Type: Maritime Control Areas/Launch Area Symbol Set: 25 Value: 2001**01** Draw Rules: Ellipse1 - Dynamic		
	Note: Launch Area may be depicted as orange (RGB: 255,155,0) where, the area fill is 75% transparent. The orientation of this symbol is determined by the rotation angle provided, where 0 degrees is east/west and a positive rotation angle rotates the ellipse in a counter-clockwise direction.	
Defended Area Type: Entity Type Entity: Maritime Control Areas Symbol Set: 25 Value: 20**02**00	N/A	N/A
Defended Area, Ellipse/Circle (AEGIS only) Type: Entity Subtype Entity/Entity Type: Maritime Control Areas/Defended Area Symbol Set: 25 Value: 2002**01** Draw Rules: Ellipse1 - Dynamic		
	Note: Defended Area may be depicted as gray (RGB:85,119,136) where the gray area fill is 75% transparent. The orientation of this symbol is determined by the rotation angle provided, where 0 degrees is east/west and a positive rotation angle rotates the ellipse in a counter-clockwise direction.	






Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE L-XIV. Maritime control measures - Continued.

DESCRIPTION	TEMPLATE	EXAMPLE **Note:** Symbols colored gray are used to help explain how the control measure is used and are not a part of the control measure.
Defended Area, Rectangle (AEGIS only) Type: Entity Subtype Entity/Entity Type: Maritime Control Areas/Defended Area Symbol Set: 25 Value: 200**02** Draw Rules: Rectangular1 - Dynamic		
	Note: Defended Area may be depicted as gray (RGB:85,119,136) where the gray area fill is 75% transparent. **Orientation:** As determined by the anchor points.	
No Attack (NOTACK) Zone (AEGIS only) Type: Entity Type Entity: Maritime Control Areas Symbol Set: 25 Value: 20**03**00 Draw Rules: Circular1 - Dynamic		
Ship Area of Interest, Maneuver Areas (AEGIS only) **Note**: Maneuver areas can only occur within a Ship AOI graphic. Type: Entity Type Entity: Maritime Control Areas Symbol Set: 25 Value: 20**04**00 Draw Rules: Point3 - Dynamic		
	Note: Gray background is used to show white border and is not part of the symbol	





Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE L-XIV. Maritime control measures - Continued.

DESCRIPTION	TEMPLATE	EXAMPLE **Note:** Symbols colored gray are used to help explain how the control measure is used and are not a part of the control measure.
Ship Area of Interest, Eclipse/Circle (AEGIS only) Type: Entity Subtype Entity/Entity Type: Maritime Control Areas/Ship Area of Interest Symbol Set: 25 Value: 200401 Draw Rules: Ellipse1 - Dynamic	 AOI	 AOI  AOI White-Colored Option
	The orientation of this symbol is determined by the rotation angle provided, where 0 degrees is east/west and a positive rotation angle rotates the ellipse in a counter-clockwise direction.	
Ship Area of Interest, Rectangle (AEGIS only) Type: Entity Subtype Entity/Entity Type: Maritime Control Areas/Ship Area of Interest Symbol Set: 25 Value: 200402 Draw Rules: Rectangular1 - Dynamic	 AOI	 AOI  AOI White-Colored Option
	Orientation: As determined by the anchor points.	
Active Maneuver Area (AEGIS only) Type: Entity Type Entity: Maritime Control Areas Symbol Set: 25 Value: 200500 Draw Rules: Point2 – Static	 CENTER POINT	








Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE L-XIV. Maritime control measures - Continued.

DESCRIPTION	TEMPLATE	EXAMPLE **Note:** Symbols colored gray are used to help explain how the control measure is used and are not a part of the control measure.
Cued Acquisition Doctrine (AEGIS only) Type: Entity Type Entity: Maritime Control Areas Symbol Set: 25 Value: 20**06**00 Draw Rules: Point17 – Dynamic **Orientation:** The orientation of this symbol is determined by the rotation angle provided, where 0 degrees is North and a positive rotation angle rotates the rectangle in a clockwise direction.		
	Note1: Cued Acquisition Doctrine symbol has a white border (RGB: 255,255,255) with a 75% transparent gray fill (RGB: 85.119,136) **Note2:** Gray background is used to show white border and is not part of the symbol	
Radar Search Doctrine (AEGIS only) Type: Entity Type Entity: Maritime Control Areas Symbol Set: 25 Value: 20**07**00 Draw Rules: Point18 – Dynamic **Orientation:** The orientation of this symbol is determined by the search axis azimuth provided.		
	Note: RSD Graphic has a dark cyan border (RGB: 51,136,136) with a 75% transparent dark cyan fill (RGB: 51,136,136)	
Maritime Control Points Type: Entity Symbol Set: 25 Value: **21**0000	N/A	N/A







Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE L-XIV. Maritime control measures - Continued.

DESCRIPTION	TEMPLATE	EXAMPLE **Note:** Symbols colored gray are used to help explain how the control measure is used and are not a part of the control measure.
Plan Ship Type: Entity Type Entity: Maritime Control Points Symbol Set: 25 Value: 21**01**00 Draw Rules: Point2 – Static		
Aim Point Type: Entity Type Entity: Maritime Control Points Symbol Set: 25 Value: 21**02**00 Draw Rules: Point2 – Static		
Defended Asset Type: Entity Type Entity: Maritime Control Points Symbol Set: 25 Value: 21**03**00 Draw Rules: Point2 – Static		
Drop Point Symbol Set: 25 Value: 21**04**00 Draw Rules: Point4 - Static		







Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE L-XIV. Maritime control measures - Continued.

DESCRIPTION	TEMPLATE	EXAMPLE **Note:** Symbols colored gray are used to help explain how the control measure is used and are not a part of the control measure.
Entry Point Type: Entity Type Entity: Maritime Control Points Symbol Set: 25 Value: 21**05**00 Draw Rules: Point5 - Static		
Air Detonation Type: Entity Type Entity: Maritime Control Points Symbol Set: 25 Value: 21**06**00 Draw Rules: Point2 – Static		
Ground Zero Type: Entity Type Entity: Maritime Control Points Symbol Set: 25 Value: 21**07**00 Draw Rules: Point6 - Static		
Impact Point Type: Entity Type Entity: Maritime Control Points Symbol Set: 25 Value: 21**08**00 Draw Rules: Point2 – Static		







Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE L-XIV. Maritime control measures - Continued.

DESCRIPTION	TEMPLATE	EXAMPLE **Note:** Symbols colored gray are used to help explain how the control measure is used and are not a part of the control measure.
Predicted Impact Point Type: Entity Type Entity: Maritime Control Points Symbol Set: 25 Value: 21**0**900 Draw Rules: Point2 – Static		
Launched Torpedo (AEGIS only) Type: Entity Type Entity: Maritime Control Points Symbol Set: 25 Value: 21**1**000 Draw Rules: Point7 - Static		
Missile Detection Point Type: Entity Type Entity: Maritime Control Points Symbol Set: 25 Value: 21**1**100 Draw Rules: Point7 - Static		
Sub-Surface Warfare		
Acoustic Countermeasure (Decoy) (AEGIS only) Type: Entity Type Entity: Maritime Control Points Symbol Set: 25 Value: 21**1**200 Draw Rules: Point7 - Static		








Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE L-XIV. Maritime control measures - Continued.

DESCRIPTION	TEMPLATE	EXAMPLE **Note:** Symbols colored gray are used to help explain how the control measure is used and are not a part of the control measure.
Electronic Countermeasures (ECM) Decoy (AEGIS only) Type: Entity Type Entity: Maritime Control Points Symbol Set: 25 Value: 211300 Draw Rules: Point2 – Static		
Brief Contact Type: Entity Type Entity: Maritime Control Points Symbol Set: 25 Value: 211400 Draw Rules: Point7 - Static		
Datum Lost Contact Type: Entity Type Entity: Maritime Control Points Symbol Set: 25 Value: 211500 Draw Rules: Point2 – Static	 **Note:** The symbol will be oriented as shown above and will be centered over the datum.	
BT Buoy Drop Type: Entity Type Entity: Maritime Control Points Symbol Set: 25 Value: 211600 Draw Rules: Point9 - Static		








Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE L-XIV. Maritime control measures - Continued.

DESCRIPTION	TEMPLATE	EXAMPLE **Note:** Symbols colored gray are used to help explain how the control measure is used and are not a part of the control measure.
Reported Bottomed Sub Type: Entity Type Entity: Maritime Control Points Symbol Set: 25 Value: 211700 Draw Rules: Point2 – Static		
Moving Haven Type: Entity Type Entity: Maritime Control Points Symbol Set: 25 Value: 211800 Draw Rules: Point2 – Static		
Screen Center Type: Entity Type Entity: Maritime Control Points Symbol Set: 25 Value: 211900 Draw Rules: Point2 – Static		
Lost Contact Type: Entity Type Entity: Maritime Control Points Symbol Set: 25 Value: 212000 Draw Rules: Point7 - Static		








Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE L-XIV. Maritime control measures - Continued.

DESCRIPTION	TEMPLATE	EXAMPLE **Note:** Symbols colored gray are used to help explain how the control measure is used and are not a part of the control measure.
Sinker Type: Entity Type Entity: Maritime Control Points Symbol Set: 25 Value: 21**21**00 Draw Rules: Point7 - Static		
Trial Track Type: Entity Type Entity: Maritime Control Points Symbol Set: 25 Value: 21**22**00 Draw Rules: Point7 - Static		
Fix		
Acoustic Fix Type: Entity Type Entity: Maritime Control Points Symbol Set: 25 Value: 21**23**00 Draw Rules: Point2 – Static		
Electromagnetic Fix Type: Entity Type Entity: Maritime Control Points Symbol Set: 25 Value: 21**24**00 Draw Rules: Point2 – Static		







Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE L-XIV. Maritime control measures - Continued.

DESCRIPTION	TEMPLATE	EXAMPLE **Note:** Symbols colored gray are used to help explain how the control measure is used and are not a part of the control measure.
Electromagnetic - Magnetic Anomaly Detection (MAD) Type: Entity Type Entity: Maritime Control Points Symbol Set: 25 Value: 21**25**00 Draw Rules: Point2 – Static		
Optical Fix Type: Entity Type Entity: Maritime Control Points Symbol Set: 25 Value: 21**26**00 Draw Rules: Point2 – Static		
Formation Type: Entity Type Entity: Maritime Control Points Symbol Set: 25 Value: 21**27**00 Draw Rules: Point2 – Static		
Harbor Type: Entity Type Entity: Maritime Control Points Symbol Set: 25 Value: 21**28**00 Draw Rules: Point8 - Static	 **Note**: Normally, the H field has four possible entries as shown in the harbor entrance point entry below. However, a user can use this symbol to define a new type of point if the following selections or the selection that follows are not sufficient.	









Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE L-XIV. Maritime control measures - Continued.

DESCRIPTION	TEMPLATE	EXAMPLE **Note:** Symbols colored gray are used to help explain how the control measure is used and are not a part of the control measure.
Harbor Entrance Point Type: Entity Type Entity: Maritime Control Points Symbol Set:25 Value: 21**29**00 Draw Rules: Point8 - Static	Reserved for hierarchical purposes.	N/A
Harbor Entrance Point A Type: Entity Subtype Entity/Entity Type: Maritime Control Points/Harbor Entrance Point Symbol Set: 25 Value: 2129**01** Draw Rules: Point8 - Static		
Harbor Entrance Point Q Type: Entity Subtype Entity/Entity Type: Maritime Control Points/Harbor Entrance Point Symbol Set: 25 Value: 212902 Draw Rules: Point8 - Static		
Harbor Entrance Point X Type: Entity Subtype Entity/Entity Type: Maritime Control Points/Harbor Entrance Point Symbol Set: 25 Value: 2129**03** Draw Rules: Point8 - Static		









Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE L-XIV. Maritime control measures - Continued.

DESCRIPTION	TEMPLATE	EXAMPLE **Note:** Symbols colored gray are used to help explain how the control measure is used and are not a part of the control measure.
Harbor Entrance Point Y Type: Entity Subtype Entity/Entity Type: Maritime Control Points/Harbor Entrance Point Symbol Set: 25 Value: 2129**04** Draw Rules: Point8 - Static		
Search		
Dip Position Type: Entity Type Entity: Maritime Control Points Symbol Set: 25 Value: 21**30**00 Draw Rules: Point2 – Static		
Search Type: Entity Type Entity: Maritime Control Points Symbol Set: 25 Value: 21**31**00 Draw Rules: Point2 – Static		
Search Area Type: Entity Type Entity: Maritime Control Points Symbol Set: 25 Value: 21**32**00 Draw Rules: Point2 – Static		









Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE L-XIV. Maritime control measures - Continued.

DESCRIPTION	TEMPLATE	EXAMPLE **Note:** Symbols colored gray are used to help explain how the control measure is used and are not a part of the control measure.
Search Center Type: Entity Type Entity: Maritime Control Points Symbol Set: 25 Value: 21**33**00 Draw Rules: Point2 – Static		
Navigational Reference Point Type: Entity Type Entity: Maritime Control Points Symbol Set: 25 Value: 21**34**00 Draw Rules: Point2 – Static		
Sonobuoys		
Sonobuoy Type: Entity Type Entity: Maritime Control Points Symbol Set: 25 Value: 21**35**00 Draw Rules: Point10 - Static		
Ambient Noise Type: Entity Subtype Entity/Entity Type: Maritime Control Points/Sonobuoy Symbol Set: 25 Value: 2135**01** Draw Rules: Point10 - Static		







Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE L-XIV. Maritime control measures - Continued.

DESCRIPTION	TEMPLATE	EXAMPLE **Note:** Symbols colored gray are used to help explain how the control measure is used and are not a part of the control measure.
Air Transportable Communication (ATAC) Type: Entity Subtype Entity/Entity Type: Maritime Control Points/Sonobuoy Symbol Set: 25 Value: 2135**02** Draw Rules: Point10 - Static		
Barra Type: Entity Subtype Entity/Entity Type: Maritime Control Points/Sonobuoy Symbol Set: 25 Value: 2135**03** Draw Rules: Point10 - Static		
Bathythermograph Transmitting (BT) Type: Entity Subtype Entity/Entity Type: Maritime Control Points/Sonobuoy Symbol Set: 25 Value: 2135**04** Draw Rules: Point10 - Static		
Command Active Multi-Beam Sonobuoy (CAMBS) Type: Entity Subtype Entity/Entity Type: Maritime Control Points/Sonobuoy Symbol Set: 25 Value: 2135**05** Draw Rules: Point10 - Static		









Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE L-XIV. Maritime control measures - Continued.

DESCRIPTION	TEMPLATE	EXAMPLE **Note:** Symbols colored gray are used to help explain how the control measure is used and are not a part of the control measure.
Command Active Sonobuoy Directional Command Active Sonobuoy System (CASS) Type: Entity Subtype Entity/Entity Type: Maritime Control Points/Sonobuoy Symbol Set: 25 Value: 213506 Draw Rules: Point10 - Static		
Directional Frequency Analyzing and Recording (DIFAR) Type: Entity Subtype Entity/Entity Type: Maritime Control Points/Sonobuoy Symbol Set: 25 Value: 213507 Draw Rules: Point10 - Static		
Directional Command Active Sonobuoy System (DICASS) Type: Entity Subtype Entity/Entity Type: Maritime Control Points/Sonobuoy Symbol Set: 25 Value: 213508 Draw Rules: Point10 - Static		









Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE L-XIV. Maritime control measures - Continued.

DESCRIPTION	TEMPLATE	EXAMPLE **Note:** Symbols colored gray are used to help explain how the control measure is used and are not a part of the control measure.
Expendable Reliable Acoustic Path Sonobuoy (ERAPS) Type: Entity Subtype Entity/Entity Type: Maritime Control Points/Sonobuoy Symbol Set: 25 Value: 213509 Draw Rules: Point10 - Static		
Expired Type: Entity Subtype Entity/Entity Type: Maritime Control Points/Sonobuoy Symbol Set: 25 Value: 213510 Draw Rules: Point10 - Static		
Kingpin Type: Entity Subtype Entity/Entity Type: Maritime Control Points/Sonobuoy Symbol Set: 25 Value: 213511 Draw Rules: Point10 - Static		
Low Frequency Analysis and Recording (LOFAR) Type: Entity Subtype Entity/Entity Type: Maritime Control Points/Sonobuoy Symbol Set: 25 Value: 213512 Draw Rules: Point10 - Static		









Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE L-XIV. Maritime control measures - Continued.

DESCRIPTION	TEMPLATE	EXAMPLE **Note:** Symbols colored gray are used to help explain how the control measure is used and are not a part of the control measure.
Pattern Center Type: Entity Subtype Entity/Entity Type: Maritime Control Points/Sonobuoy Symbol Set: 25 Value: 213513 Draw Rules: Point10 - Static		
Range Only Type: Entity Subtype Entity/Entity Type: Maritime Control Points/Sonobuoy Symbol Set: 25 Value: 213514 Draw Rules: Point10 - Static		
Vertical Line Array Directional Frequency Analysis and Recording (DIFAR) Type: Entity Subtype Entity/Entity Type: Maritime Control Points/Sonobuoy Symbol Set: 25 Value: 213515 Draw Rules: Point10 - Static		
Reference Points		
Reference Point Type: Entity Type Entity: Maritime Control Points Symbol Set: 25 Value: 213600 Draw Rules: Point2 – Static		









Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE L-XIV. Maritime control measures - Continued.

DESCRIPTION	TEMPLATE	EXAMPLE **Note:** Symbols colored gray are used to help explain how the control measure is used and are not a part of the control measure.
Special Point Type: Entity Type Entity: Maritime Control Points Symbol Set: 25 Value: 213700 Draw Rules: Point2 – Static		
Navigational Reference Point Type: Entity Type Entity: Maritime Control Points Symbol Set: 25 Value: 213800 Draw Rules: Point2 – Static		
Data Link Reference Point Type: Entity Type Entity: Maritime Control Points Symbol Set: 25 Value: 213900 Draw Rules: Point2 – Static		
Vital Area Center Type: Entity Type Entity: Maritime Control Points Symbol Set: 25 Value: 214100 Draw Rules: Point2 – Static		








Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE L-XIV. Maritime control measures - Continued.

DESCRIPTION	TEMPLATE	EXAMPLE **Note:** Symbols colored gray are used to help explain how the control measure is used and are not a part of the control measure.
Corridor Tab Point Type: Entity Type Entity: Maritime Control Points Symbol Set: 25 Value: 21**4**200 Draw Rules: Point2 – Static		
Enemy Point Type: Entity Type Entity: Maritime Control Points Symbol Set: 25 Value: 21**4**300 Draw Rules: Point2 – Static		
Marshall Point Type: Entity Type Entity: Maritime Control Points Symbol Set: 25 Value: 21**4**400 Draw Rules: Point2 – Static		
Position and Intended Movement (PIM) Type: Entity Type Entity: Maritime Control Points Symbol Set: 25 Value: 21**4**500 Draw Rules: Point2 – Static		









Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE L-XIV. Maritime control measures - Continued.

DESCRIPTION	TEMPLATE	EXAMPLE **Note:** Symbols colored gray are used to help explain how the control measure is used and are not a part of the control measure.
Pre-Landfall Waypoint Type: Entity Type Entity: Maritime Control Points Symbol Set: 25 Value: 214600 Draw Rules: Point2 – Static		
Estimated Position (EP) Type: Entity Type Entity: Maritime Control Points Symbol Set: 25 Value: 214700 Draw Rules: Point2 – Static		
Waypoint Type: Entity Type Entity: Maritime Control Points Symbol Set: 25 Value: 214800 Draw Rules: Point2 – Static		
Sea Subsurface Stations		
General Sea Subsurface Station Type: Entity Type Entity: Maritime Control Points Symbol Set: 25 Value: 214900 Draw Rules: Point2 – Static		





Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE L-XIV. Maritime control measures - Continued.

DESCRIPTION	TEMPLATE	EXAMPLE **Note:** Symbols colored gray are used to help explain how the control measure is used and are not a part of the control measure.
Submarine Sea Subsurface Station Type: Entity Type Entity: Maritime Control Points Symbol Set: 25 Value: 21**5**000 Draw Rules: Point2 – Static		
Submarine Antisubmarine Warfare Sea Subsurface Station Type: Entity Type Entity: Maritime Control Points Symbol Set: 25 Value: 21**5**100 Draw Rules: Point2 – Static		
Unmanned Underwater Vehicle Sea Subsurface Station Type: Entity Type Entity: Maritime Control Points Symbol Set: 25 Value: 21**5**200 Draw Rules: Point2 – Static		
Antisubmarine Warfare (ASW) Unmanned Underwater Vehicle Sea Subsurface Station Type: Entity Type Entity: Maritime Control Points Symbol Set: 25 Value: 21**5**300 Draw Rules: Point2 – Static		



Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE L-XIV. Maritime control measures - Continued.

DESCRIPTION	TEMPLATE	EXAMPLE **Note:** Symbols colored gray are used to help explain how the control measure is used and are not a part of the control measure.
Mine Warfare Unmanned Underwater Vehicle Sea Subsurface Station Type: Entity Type Entity: Maritime Control Points Symbol Set: 25 Value: 21**5**400 Draw Rules: Point2– Static		
Sea Surface Warfare Unmanned Underwater Vehicle Sea Subsurface Station Type: Entity Type Entity: Maritime Control Points Symbol Set: 25 Value: 21**5**500 Draw Rules: Point2 – Static		
Sea Surface Stations		
General Sea Surface Station Type: Entity Type Entity: Maritime Control Points Symbol Set: 25 Value: 21**5**600 Draw Rules: Point2 – Static		


Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE L-XIV. Maritime control measures - Continued.

DESCRIPTION	TEMPLATE	EXAMPLE **Note:** Symbols colored gray are used to help explain how the control measure is used and are not a part of the control measure.
Antisubmarine Warfare (ASW) Sea Surface Station Type: Entity Type Entity: Maritime Control Points Symbol Set: 25 Value: 215700 Draw Rules: Point2 – Static		
Mine Warfare Sea Surface Station Type: Entity Type Entity: Maritime Control Points Symbol Set: 25 Value: 215800 Draw Rules: Point2 – Static		
Non-Combatant Sea Surface Station Type: Entity Type Entity: Maritime Control Points Symbol Set: 25 Value: 215900 Draw Rules: Point2 – Static		
Picket Sea Surface Station Type: Entity Type Entity: Maritime Control Points Symbol Set: 25 Value: 216000 Draw Rules: Point2 – Static		






Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE L-XIV. Maritime control measures - Continued.

DESCRIPTION	TEMPLATE	EXAMPLE **Note:** Symbols colored gray are used to help explain how the control measure is used and are not a part of the control measure.
Rendezvous Sea Surface Station Type: Entity Type Entity: Maritime Control Points Symbol Set: 25 Value: 21**61**00 Draw Rules: Point2 – Static		
Replenishment at Sea Surface Station Type: Entity Type Entity: Maritime Control Points Symbol Set: 25 Value: 21**62**00 Draw Rules: Point2 – Static		
Rescue Sea Surface Station Type: Entity Type Entity: Maritime Control Points Symbol Set: 25 Value: 21**63**00 Draw Rules: Point2 – Static		
Surface Warfare Sea Surface Station Type: Entity Type Entity: Maritime Control Points Symbol Set: 25 Value: 21**64**00 Draw Rules: Point2 – Static		







Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE L-XIV. Maritime control measures - Continued.

DESCRIPTION	TEMPLATE	EXAMPLE **Note:** Symbols colored gray are used to help explain how the control measure is used and are not a part of the control measure.
Unmanned Underwater Vehicle Sea Surface Station Type: Entity Type Entity: Maritime Control Points Symbol Set: 25 Value: 21**6**500 Draw Rules: Point2 – Static		
Antisubmarine Warfare (ASW) Unmanned Underwater Vehicle Sea Surface Station Type: Entity Type Entity: Maritime Control Points Symbol Set: 25 Value: 21**6**600 Draw Rules: Point2 – Static		
Mine Warfare Unmanned Underwater Vehicle Sea Surface Station Type: Entity Type Entity: Maritime Control Points Symbol Set: 25 Value: 21**6**700 Draw Rules: Point2 – Static		









Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE L-XIV. Maritime control measures - Continued.

DESCRIPTION	TEMPLATE	EXAMPLE **Note:** Symbols colored gray are used to help explain how the control measure is used and are not a part of the control measure.
Remote Multi-Mission Vehicle Unmanned Underwater Vehicle Sea Surface Station Type: Entity Type Entity: Maritime Control Points Symbol Set: 25 Value: 21**68**00 Draw Rules: Point2 – Static		
Surface Warfare Unmanned Underwater Vehicle Sea Surface Station Type: Entity Type Entity: Maritime Control Points Symbol Set: 25 Value: 21**69**00 Draw Rules: Point2 – Static		
Shore Control Station Type: Entity Type Entity: Maritime Control Points Symbol Set: 25 Value: 21**70**00 Draw Rules: Point2 – Static		
Routes		
General Route Type: Entity Type Entity: Maritime Control Points Symbol Set: 25 Value: 21**71**00 Draw Rules: Point2 – Static		









Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE L-XIV. Maritime control measures - Continued.

DESCRIPTION	TEMPLATE	EXAMPLE **Note:** Symbols colored gray are used to help explain how the control measure is used and are not a part of the control measure.
Diversion Route Type: Entity Type Entity: Maritime Control Points Symbol Set: 25 Value: 217200 Draw Rules: Point2 – Static		
Position and Intended Movement (PIM) Route Type: Entity Type Entity: Maritime Control Points Symbol Set: 25 Value: 217300 Draw Rules: Point2 – Static		
Picket Route Type: Entity Type Entity: Maritime Control Points Symbol Set: 25 Value: 217400 Draw Rules: Point2 – Static		
Point R Route Type: Entity Type Entity: Maritime Control Points Symbol Set: 25 Value: 217500 Draw Rules: Point2 – Static		









Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE L-XIV. Maritime control measures - Continued.

DESCRIPTION	TEMPLATE	EXAMPLE **Note:** Symbols colored gray are used to help explain how the control measure is used and are not a part of the control measure.
Rendezvous Route Type: Entity Type Entity: Maritime Control Points Symbol Set: 25 Value: 217600 Draw Rules: Point2 – Static		
Waypoint Route Type: Entity Type Entity: Maritime Control Points Symbol Set: 25 Value: 217700 Draw Rules: Point2 – Static		
Clutter, Stationary or Cease Reporting Type: Entity Type Entity: Maritime Control Points Symbol Set: 25 Value: 217800 Draw Rules: Point2 – Static		
Tentative or Provisional Track Type: Entity Type Entity: Maritime Control Points Symbol Set: 25 Value: 217900 Draw Rules: Point2 – Static		








Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE L-XIV. Maritime control measures - Continued.

DESCRIPTION	TEMPLATE	EXAMPLE **Note:** Symbols colored gray are used to help explain how the control measure is used and are not a part of the control measure.
Emergency		
Distressed Vessel Type: Entity Type Entity: Maritime Control Points Symbol Set: 25 Value: 21**80**00 Draw Rules: Point2 – Static		
Ditched Aircraft/Downed Aircraft Type: Entity Type Entity: Maritime Control Points Symbol Set: 25 Value: 21**81**00 Draw Rules: Point2 – Static		
Person In Water/ Bailout Type: Entity Type Entity: Maritime Control Points Symbol Set: 25 Value: 21**82**00 Draw Rules: Point2 – Static		
Hazard		
Iceberg Type: Entity Type Entity: Maritime Control Points Symbol Set: 25 Value: 21**83**00 Draw Rules: Point2 – Static		









Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE L-XIV. Maritime control measures - Continued.

DESCRIPTION	TEMPLATE	EXAMPLE **Note:** Symbols colored gray are used to help explain how the control measure is used and are not a part of the control measure.
Navigational Type: Entity Type Entity: Maritime Control Points Symbol Set: 25 Value: 21**8**400 Draw Rules: Line4 - Dynamic	 Orientation is determined by the anchor points.	
Oil Rig Type: Entity Type Entity: Maritime Control Points Symbol Set: 25 Value: 21**8**500 Draw Rules: Point2 – Static		
Sea Mine-Like Type: Entity Type Entity: Maritime Control Points Symbol Set: 25 Value: 21**8**600 Draw Rules: Point2 – Static	 **Note**: The orientation of symbol can be rotated in 90 degree increments.	
Sea Subsurface Returns		
Bottom Return/ Non-Mine, Mine-Like Bottom Object (NOMBO) Type: Entity Type Entity: Maritime Control Points Symbol Set: 25 Value: 21**8**700 Draw Rules: Point7 - Static		







Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE L-XIV. Maritime control measures - Continued.

DESCRIPTION	TEMPLATE	EXAMPLE **Note:** Symbols colored gray are used to help explain how the control measure is used and are not a part of the control measure.
Bottom Return/ Non-Mine, Mine-Like Bottom Object (NOMBO)/Installation/ Manmade Type: Entity Type Entity: Maritime Control Points Symbol Set: 25 Value: 21**88**00 Draw Rules: Point7 - Static		
Marine Life Type: Entity Type Entity: Maritime Control Points Symbol Set: 25 Value: 21**89**00 Draw Rules: Point15 - Static		
Sea Anomaly (Wake, Current, Knuckle) Type: Entity Type Entity: Maritime Control Points Symbol Set: 25 Value: 21**90**00 Draw Rules: Point2 – Static		
Bottom Return/Non-MILCO, Wreck, Dangerous Type: Entity Type Entity: Maritime Control Points Symbol Set: 25 Value: 21**91**00 Draw Rules: Point2 – Static		







Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE L-XIV. Maritime control measures - Continued.

DESCRIPTION	TEMPLATE	EXAMPLE **Note:** Symbols colored gray are used to help explain how the control measure is used and are not a part of the control measure.
Bottom Return/Non-MILCO, Wreck, Non Dangerous Type: Entity Type Entity: Maritime Control Points Symbol Set: 25 Value: 21**92**00 Draw Rules: Point2 – Static		
Maritime Control Lines Type: Entity Symbol Set: 25 Value: **22**0000	N/A	N/A
Bearing lines orientation: One point defines the origin from which the bearing is being taken and the other point defines the location or direction from which a contact is made.		
Bearing Line Type: Entity Type Entity: Maritime Control Lines Symbol Set: 25 Value: 22**01**00 Draw Rules: Line5 - Dynamic		
Bearing Line, Electronic Type: Entity Subtype Entity/Entity Type: Maritime Control Lines/Bearing Line Symbol Set: 25 Value: 2201**01** Draw Rules: Line5 - Dynamic		







Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE L-XIV. Maritime control measures - Continued.

DESCRIPTION	TEMPLATE	EXAMPLE **Note:** Symbols colored gray are used to help explain how the control measure is used and are not a part of the control measure.
Bearing Line, Electromagnetic Warfare (EW) Type: Entity Subtype Entity/Entity Type: Maritime Control Lines/Bearing Line Symbol Set: 25 Value: 220102 Draw Rules: Line5 - Dynamic		
	Note: "H" field may contain the following identifiers: •"MSL" – missile •"MCU" – missile control unit •"TENT - tentative	
Bearing Line, Acoustic Type: Entity Subtype Entity/Entity Type: Maritime Control Lines/Bearing Line Symbol Set: 25 Value: 220103 Draw Rules: Line5 - Dynamic		
	Note: "H" field may contain the following identifiers: •"L3-ACT" – LAMPS, active •"L3-pHELO" – LAMPS, Helicopter, passive •"L3-pSHIP" – LAMPS, Ship, passive •"L3-OSC" – LAMPS, Operator Specified Contact, passive •"L3-ATT" – LAMPS, Acoustic Target Track, passive	
Bearing Line, Acoustic (Ambiguous) Type: Entity Subtype Entity/Entity Type: Maritime Control Lines/Bearing Line Symbol Set: 25 Value: 220104 Draw Rules: Line5 - Dynamic		
	Note: "H" field may contain the following identifiers: •"L3-ACT" – LAMPS, active •"L3-pHELO" – LAMPS, Helicopter, passive •"L3-pSHIP" – LAMPS, Ship, passive •"L3-OSC" – LAMPS, Operator Specified Contact, passive •"L3-ATT" – LAMPS, Acoustic Target Track, passive	



Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE L-XIV. Maritime control measures - Continued.

DESCRIPTION	TEMPLATE	EXAMPLE **Note:** Symbols colored gray are used to help explain how the control measure is used and are not a part of the control measure.
Bearing Line, Torpedo Type: Entity Subtype Entity/Entity Type: Maritime Control Lines/Bearing Line Symbol Set: 25 Value: 220105 Draw Rules: Line5 - Dynamic		
Bearing Line, Electro-Optical Intercept Type: Entity Subtype Entity/Entity Type: Maritime Control Lines/Bearing Line Symbol Set: 25 Value: 220106 Draw Rules: Line5 - Dynamic		
Bearing Line, Jammer Type: Entity Subtype Entity/Entity Type: Maritime Control Lines/Bearing Line Symbol Set: 25 Value: 220107 Draw Rules: Line5 - Dynamic	 **Note:** "H" field may only contain the "PAT-1" – PAT-1 Jammer	

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE L-XIV. Maritime control measures - Continued.

DESCRIPTION	TEMPLATE	EXAMPLE **Note:** Symbols colored gray are used to help explain how the control measure is used and are not a part of the control measure.
Bearing Line, Radio Direction Finder (RDF) Type: Entity Subtype Entity/Entity Type: Maritime Control Lines/Bearing Line Symbol Set: 25 Value: 220**108** Draw Rules: Line5 - Dynamic		

L.5.17 Fire support coordination measures.






L.5.17.1 Fire support coordination measures. Measures employed by land or amphibious commanders to facilitate the rapid engagement of targets and simultaneously provide safeguards for friendly forces. Fire support control measures should be labeled with the abbreviation of the control measure, the controlling headquarters (Field T) and the effective times (Field W/W1). For lines this labeling should be on both ends of the line and repeated as often as necessary for clarity along any line that passes through many boundaries.

TABLE L-XV. Fire support coordination measures.

DESCRIPTION	TEMPLATE	EXAMPLE **Note:** Symbols colored gray are used to help explain how the control measure is used and are not a part of the control measure.
Fire Areas Type: Entity Symbol Set: 25 Value: **24**0000	Reserved for hierarchical purposes.	N/A
Airspace Coordination Area (ACA) "A three-dimensional block of airspace in a target area, established by the appropriate commander, in which friendly aircraft are reasonably safe from friendly surface fires. Also called ACA." (JP 3-09.3)		
Airspace Coordination Area (ACA) Type: Entity Type Entity: Fire Areas Symbol Set: 25 Value: 24**01**00	Reserved for hierarchical purposes.	N/A

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE L-XV. Fire support coordination measures - Continued.



DESCRIPTION	TEMPLATE	EXAMPLE **Note:** Symbols colored gray are used to help explain how the control measure is used and are not a part of the control measure.
Airspace Coordination Area (ACA) - Irregular Type: Entity Subtype Entity/Entity Type: Fire Areas/Airspace Coordination Area Symbol Set: 25 Value: 240**101** Draw Rules: Area1 - Dynamic	 Note: T-1 is a Unit	
Airspace Coordination Area (ACA) - Rectangle Type: Entity Subtype Entity/Entity Type: Fire Areas/Airspace Coordination Area Symbol Set: 25 Value: 240**102** Draw Rules: Rectangular1 - Dynamic	 Note: T-1 is a Unit	
	Orientation: As determined by the anchor points.	
Airspace Coordination Area (ACA) – Circular Type: Entity Subtype Entity/Entity Type: Fire Areas/Airspace Coordination Area Symbol Set: 25 Value: 240**103** Draw Rules: Circular1 - Dynamic	 Note: T-1 is a Unit	
Free Fire Area (FFA) Type: Entity Type Entity: Fire Areas Symbol Set: 25 Value: 24**02**00	Reserved for hierarchical purposes.	N/A

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.



TABLE L-XV. Fire support coordination measures - Continued.

<table>
<tr><th>DESCRIPTION</th><th>TEMPLATE</th><th>EXAMPLE
Note: Symbols colored gray are used to help explain how the control measure is used and are not a part of the control measure.</th></tr>
<tr><td>Free Fire Area (FFA) – Irregular



Type: Entity Subtype
Entity/Entity Type: Fire Areas/Free Fire Area
Symbol Set: 25
Value: 24001

Draw Rules:
Area1 - Dynamic</td><td> 
</td><td> 
</td></tr>
<tr><td rowspan="2">Free Fire Area (FFA) – Rectangle

Type: Entity Subtype
Entity/Entity Type: Fire Areas/Free Fire Area
Symbol Set: 25
Value: 24002

Draw Rules:
Rectangular1 - Dynamic</td><td> 
</td><td> 
</td></tr>
<tr><td colspan="2">Orientation: As determined by the anchor points.</td></tr>
<tr><td>Free Fire Area (FFA) – Circular







Type: Entity Subtype
Entity/Entity Type: Fire Areas/Free Fire Area
Symbol Set: 25
Value: 24003

Draw Rules:
Circular1 - Dynamic</td><td> 
</td><td> 
</td></tr>
<tr><td colspan="3">No Fire Area (NFA)
An area designated by the appropriate commander into which fires or their effects are prohibited. Also called NFA. (JP 3-09.3)</td></tr>
<tr><td>No Fire Area (NFA)

Type: Entity Type
Entity: Fires Areas
Symbol Set: 25
Value: 240300</td><td>Reserved for hierarchical purposes.</td><td>N/A</td></tr>
</table>







Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE L-XV. Fire support coordination measures - Continued.

DESCRIPTION	TEMPLATE	EXAMPLE **Note:** Symbols colored gray are used to help explain how the control measure is used and are not a part of the control measure.
No Fire Area (NFA) - Irregular Type: Entity Subtype Entity/Entity Type: Fire Areas/No Fire Area Symbol Set: 25 Value: 240301 Draw Rules: Area1 - Dynamic		
No Fire Area (NFA) – Rectangular Type: Entity Subtype Entity/Entity Type: Fire Areas/No Fire Area Symbol Set: 25 Value: 240302 Draw Rules: Rectangular1 - Dynamic	 **Orientation:** As determined by the anchor points.	
No Fire Area (NFA) – Circular Type: Entity Subtype Entity/Entity Type: Fire Areas/No Fire Area Symbol Set: 25 Value: 240303 Draw Rules: Circular1 - Dynamic		
Restricted Fire Area (RFA) An area designated by the appropriate commander into which fires or their effects are prohibited. Also called NFA. See also fires. (JP 3-09.3)		
Restricted Fire Area (RFA) Type: Entity Type Entity: Fire Areas Symbol Set: 25 Value: 240400	Reserved for hierarchical purposes.	N/A







Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE L-XV. Fire support coordination measures - Continued.

DESCRIPTION	TEMPLATE	EXAMPLE **Note:** Symbols colored gray are used to help explain how the control measure is used and are not a part of the control measure.
Restrictive Fire Area (RFA) - Irregular Type: Entity Subtype Entity/Entity Type: Fire Areas/Restricted Fire Area Symbol Set: 25 Value: 240**401** Draw Rules: Area1 – Dynamic		
Restrictive Fire Area (RFA) – Rectangular Type: Entity Subtype Entity/Entity Type: Fire Areas/Restricted Fire Area Symbol Set: 25 Value: 240**402** Draw Rules: Rectangular1 - Dynamic	 **Orientation:** As determined by the anchor points.	
Restrictive Fire Area (RFA) – Circular Type: Entity Subtype Entity/Entity Type: Fire Areas/Restricted Fire Area Symbol Set: 25 Value: 240**403** Draw Rules: Circular1 - Dynamic		
Position Area For Artillery (PAA) Type: Entity Type Entity: Fire Areas Symbol Set: 25 Value: 24**05**00	Reserved for hierarchical purposes.	N/A








Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE L-XV. Fire support coordination measures - Continued.

DESCRIPTION	TEMPLATE	EXAMPLE **Note:** Symbols colored gray are used to help explain how the control measure is used and are not a part of the control measure.
Position Area for Artillery (PAA) - Rectangular Type: Entity Subtype Entity/Entity Type: Fire Areas/Position Area For Artillery (PAA) Symbol Set: 25 Value: 240**01** Draw Rules: Rectangular1 - Dynamic	 **Orientation:** As determined by the anchor points.	
Position Area for Artillery (PAA) - Circular Type: Entity Subtype Entity/Entity Type: Fire Areas/Position Area For Artillery (PAA) Symbol Set: 25 Value: 240**02** Draw Rules: Circular1 - Dynamic		
Position Area for Artillery (PAA) - Irregular Type: Entity Subtype Entity/Entity Type: Fire Areas/Position Area For Artillery (PAA) Symbol Set: 25 Value: 240**03** Draw Rules: Area1 – Dynamic		
Fire Lines Type: Entity Symbol Set: 25 Value: **26**0000	Reserved for hierarchical purposes.	N/A




Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE L-XV. Fire support coordination measures - Continued.

DESCRIPTION	TEMPLATE	EXAMPLE **Note:** Symbols colored gray are used to help explain how the control measure is used and are not a part of the control measure.
Fire Support Coordination Line (FSCL) Type: Entity Type Entity: Fire Lines Symbol Set: 25 Value: 26**01**00 Draw Rules: Line1- Dynamic		 The end-of line information will typically be posted at the ends of the line as it is shown in the example.
	"A fire support coordination measure established by the land or amphibious force commander to support common objectives within an area of operation, beyond which all fires must be coordinated with affected commanders prior to engagement and, short of the line, all fires must be coordinated with the establishing commander prior to engagement. Also called FSCL." JP 3-09. Orientation: determined by the order in which the anchor points are entered.	
Coordinated Fire Line (CFL) Type: Entity Type Entity: Fire Lines Symbol Set: 25 Value: 26**02**00 Draw Rules: Line7 - Dynamic		
	"A line beyond which conventional surface-to-surface direct fire and indirect fire support means may fire at any time within the boundaries of the establishing headquarters without additional coordination but does not eliminate the responsibility to coordinate the airspace required to conduct the mission. Also called CFL." (JP 3-09) Orientation: determined by the order in which the anchor points are entered.	
No Fire Line Type: Entity Type Entity: Fire Lines Symbol Set: 25 Value: 26**03**00 Draw Rules: Line1- Dynamic		
Battlefield Coordination Line (BCL) Type: Entity Type Entity: Fire Lines Symbol Set: 25		

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE L-XV. Fire support coordination measures - Continued.

DESCRIPTION	TEMPLATE	EXAMPLE **Note:** Symbols colored gray are used to help explain how the control measure is used and are not a part of the control measure.
Value: 26**04**00 Draw Rules: Line1- Dynamic	A fire support coordination measure that facilitates the expeditious attack of targets with surface indirect fires and aviation fires between the measure and the fire support coordination line (FSCL). (MCWP-16) Orientation: determined by the order in which the anchor points are entered.	
Restrictive Fire Line (RFL) Type: Entity Type Entity: Fire Lines Symbol Set: 25 Value: 26**05**00 Draw Rules: Line1- Dynamic		
	"A specific boundary established between converging, friendly surface forces that prohibits fires or their effects from crossing. Also called **RFL**." (JP 3-09) **Orientation:** determined by the order in which the anchor points are entered.	
Munition Flight Path Type: Entity Type Entity: Fire Lines Symbol Set: 25 Value: 26**06**00 Draw Rules: Line8 - Dynamic The orientation is determined by the anchor points.		
	Note 1. "MFP" shall be displayed once at the approximate center of the overall length of the Munition Flight Path. **Note 2**. The MFP begins at a weapon system/surface-to-surface fires unit and terminates at a target. **Note 3**. The effective DTG of the MFP is the shot/launch time of the projectile. The expiration DTG of the MFP is the splash/time of impact of the projectile. DTGs are not required to be displayed. If the DTG is displayed, it shall be displayed one time mid-way between Point 1 and midpoint of the graphic. **Note 4**. The 3D display of a MFP requires a height value for each anchor point.	

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

L.5.18 Targets.




L.5.18.1 Targets. Are the objects of a particular action, for example a geographic area, a complex, an installation, a force, equipment, an individual, a group or a system, planned for capture, exploitation, neutralization or destruction by military forces.

TABLE L-XVI. Target control measure symbols.

<table>
<tr><th>DESCRIPTION</th><th>TEMPLATE</th><th>EXAMPLE
Note: Symbols colored gray are used to help explain how the control measure is used and are not a part of the control measure.</th></tr>
<tr><td colspan="3">Point Targets</td></tr>
<tr><td>Point Targets



Type: Entity Type
Entity: Fire Areas
Symbol Set: 25
Value: 240600</td><td>Reserved for hierarchical purposes.</td><td>N/A</td></tr>
<tr><td rowspan="3">Point or Single Target

Type: Entity Subtype
Entity/Entity Type: Fires Areas/Point Targets
Symbol Set: 25
Value: 240601

Draw Rules:
Point2 – Static</td><td rowspan="2"> 
</td><td> 
</td></tr>
<tr><td> 
</td></tr>
<tr><td colspan="2">A target which requires the accurate placement of bombs or fire.









Note: Guidance on building target numbers is found in AArtyP-1.</td></tr>
<tr><td rowspan="2">Nuclear Target

Type: Entity Subtype
Entity/Entity Type: Fires Areas/Point Targets
Symbol Set: 25
Value: 240602

Draw Rules:
Point2 – Static</td><td> 
</td><td> 
</td></tr>
<tr><td colspan="2">Note: The point at the center of the target represents the desired ground zero.</td></tr>
</table>







Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE L-XVI. Target control measure symbols – Continued.

DESCRIPTION	TEMPLATE	EXAMPLE **Note:** Symbols colored gray are used to help explain how the control measure is used and are not a part of the control measure.
Target-Recorded (AEGIS Only) Type: Entity Subtype Entity/Entity Type: Fires Areas/Point Targets Symbol Set: 25 Value: 2406**03** Draw Rules: Point11 - Static	 Center Point	
Linear Targets Type: Entity Type Entity: Fire Areas Symbol Set: 25 Value: 24**07**00	Reserved for hierarchical purposes.	N/A
Linear Target Type: Entity Subtype Entity/Entity Type: Fire Areas/Linear Targets Symbol Set: 25 Value: 2407**01** Draw Rules: Line5 - Dynamic		
Linear Smoke Target Type: Entity Subtype Entity/Entity Type: Fire Areas/Linear Targets Symbol Set: 25 Value: 2407**02** Draw Rules: Line5 - Dynamic		
Final Protective Fire (FPF) Type: Entity Subtype Entity/Entity Type: Fire Areas/Linear Targets Symbol Set: 25 Value: 2407**03** Draw Rules: Line5 - Dynamic	 An immediately available prearranged barrier of fire designed to impede enemy movement across defensive lines or areas.	

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE L-XVI. Target control measure symbols – Continued.

DESCRIPTION	TEMPLATE	EXAMPLE **Note:** Symbols colored gray are used to help explain how the control measure is used and are not a part of the control measure.
Area Targets Type: Entity Type Entity: Fire Areas Symbol Set: 25 Value: 24**08**00	Reserved for hierarchical purposes.	N/A
Area Target Type: Entity Subtype Entity/Entity Type: Fire Areas/Area Targets Symbol Set: 25 Value: 2408**01** Draw Rules: Area1 - Dynamic		
Rectangular Target Type: Entity Subtype Entity/Entity Type: Fire Areas/Area Targets Symbol Set: 25 Value: 2408**02** Draw Rules: Rectangular2 - Dynamic	 **Orientation:** As determined by the Target Attitude (in mils).	
Circular Target Type: Entity Subtype Entity/Entity Type: Fire Areas/Area Targets Symbol Set: 25 Value: 2408**03** Draw Rules: Circular1 - Dynamic		
Rectangular Target – Single Target (AEGIS Only) Type: Entity Subtype Entity/Entity Type: Fire Areas/Area Targets Symbol Set: 25 Value: 2408**04** Draw Rules: Rectangular3 - Dynamic		


Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE L-XVI. Target control measure symbols – Continued.

<table>
<tr><th>DESCRIPTION</th><th>TEMPLATE</th><th>EXAMPLE
Note: Symbols colored gray are used to help explain how the control measure is used and are not a part of the control measure.</th></tr>
<tr><td></td><td colspan="2">Area: This symbol requires two anchor points and a width (defined in meters) to define the boundary of the area. Points 1 and 2 will be located on the opposite sides of the area.
Orientation: As determined by the anchor points. The center point of the area shall always have the target symbol with the same upright orientation.</td></tr>
<tr><td rowspan="3">Series or Group of Targets





Type: Entity Subtype
Entity/Entity Type: Fire Areas/Area Targets
Symbol Set: 25
Value: 240805

Draw Rules:
Area9 - Dynamic




Note: The area will encompass two or more fire support symbols (point/single target, nuclear target, circular target, rectangular target, or area target).
The naming convention determines whether the area describes a series or group of targets.</td><td rowspan="2"> 

In artillery and naval fire support, a number of targets and/or group(s) of targets planned to support a maneuver phase.

A series of targets may be indicated by a nickname.







A group of targets is designated by a letter/number combination or a nickname.</td><td> 
 
Point Targets</td></tr>
<tr><td> 
Linear Targets</td></tr>
<tr><td> 
Area Targets</td></tr>
<tr><td>Smoke

Type: Entity Subtype
Entity/Entity Type: Fire Areas/Area Targets
Symbol Set: 25
Value: 240806

Draw Rules:
Area1 - Dynamic</td><td>  </td><td> 
 
Planned</td></tr>
</table>





Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE L-XVI. Target control measure symbols – Continued.

DESCRIPTION	TEMPLATE	EXAMPLE **Note:** Symbols colored gray are used to help explain how the control measure is used and are not a part of the control measure.
Bomb Area Type: Entity Subtype Entity/Entity Type: Fire Areas/Area Targets Symbol Set: 25 Value: 2408**08** Draw Rules: Area1 - Dynamic		
Naval Gunfire		
Fire Support Station Type: Entity Type Entity: Fire Area Symbol Set: 25 Value: 24**09**00 Draw Rules: Point2 – Static		
	An exact location at sea within a fire support area from which a fire support ship delivers fire.	
Fire Support Area An appropriate maneuver area assigned to fire support ships by the naval force commander from which they can deliver gunfire support to an amphibious operation. Also called FSA. (JP 3-09)		
Fire Support Area Type: Entity Type Entity: Fire Area Symbol Set: 25 Value: 24**10**00	Reserved for hierarchical purposes.	N/A
Fire Support Area - Irregular Type: Entity Subtype Entity/Entity Type: Fire Area/Fire Support Area Symbol Set: 25 Value: 2410**01** Draw Rules: Area1 - Dynamic		









Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE L-XVI. Target control measure symbols – Continued.

DESCRIPTION	TEMPLATE	EXAMPLE **Note:** Symbols colored gray are used to help explain how the control measure is used and are not a part of the control measure.
Fire Support Area - Rectangular Type: Entity Subtype Entity/Entity Type: Fire Area/Fire Support Area Symbol Set: 25 Value: 241**02** Draw Rules: Rectangular1 - Dynamic	 **Orientation:** As determined by the anchor points.	010700ZJAN2008 - 010745ZJAN2008 
Fire Support Area - Circular Type: Entity Subtype Entity/Entity Type: Fire Area/Fire Support Area Symbol Set: 25 Value: 241**03** Draw Rules: Circular1 - Dynamic		010700ZJAN2008 - 010745ZJAN2008 
Kill Box A three-dimensional permissive fire support coordination measure with an associated airspace coordinating measure used to facilitate the integration of fires. (JP 3-09)		
Kill Box Type: Entity Type Entity: Fire Area Symbol Set: 25 Value: 24**23**00 Static/Dynamic: D	Reserved for hierarchical purposes.	N/A
Blue Kill Box, Irregular Type: Entity Subtype Entity/Entity Type: Fire Areas/Kill Box Symbol Set: 25 Value: 2423**01** Draw Rules: Area10 - Dynamic		020300ZDEC2018 - 090500ZDEC2018 







Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE L-XVI. Target control measure symbols – Continued.

DESCRIPTION	TEMPLATE	EXAMPLE **Note:** Symbols colored gray are used to help explain how the control measure is used and are not a part of the control measure.
Blue Kill Box, Rectangular Type: Entity Subtype Entity/Entity Type: Fire Areas/Kill Box Symbol Set: 25 Value: 242302 Draw Rules: Rectangular1 - Dynamic	 **Orientation:** As determined by the anchor points.	020300ZDEC2018 - 090500ZDEC2018 
Blue Kill Box, Circular Type: Entity Subtype Entity/Entity Type: Fire Areas/Kill Box Symbol Set: 25 Value: 242303 Draw Rules: Circular1 - Dynamic		020300ZDEC2018 - 090500ZDEC2018 
Purple Kill Box, Irregular Type: Entity Subtype Entity/Entity Type: Fire Areas/Kill Box Symbol Set: 25 Value: 242304 Draw Rules: Area10 - Dynamic		020300ZDEC2018 - 090500ZDEC2018 
Purple Kill Box, Rectangular Type: Entity Subtype Entity/Entity Type: Fire Areas/Kill Box Symbol Set: 25 Value: 242305 Draw Rules: Rectangular1 - Dynamic	 **Orientation:** As determined by the anchor points.	020300ZDEC2018 - 090500ZDEC2018 









Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE L-XVI. Target control measure symbols – Continued.

DESCRIPTION	TEMPLATE	EXAMPLE **Note:** Symbols colored gray are used to help explain how the control measure is used and are not a part of the control measure.
Purple Kill Box, Circular Type: Entity Subtype Entity/Entity Type: Fire Areas/Kill Box Symbol Set: 25 Value: 242306 Draw Rules: Circular1 - Dynamic		
Field Artillery		
Fires Points Type: Entity Symbol Set: 25 Value: 250000	Reserved for hierarchical purposes.	N/A
Firing Point Type: Entity Type Entity Fires Points Symbol Set: 25 Value: 250100 Draw Rules: Point1 – Static		
Hide Point Type: Entity Type Entity Fires Points Symbol Set: 25 Value: 250200 Draw Rules: Point1 – Static		

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE L-XVI. Target control measure symbols – Continued.




DESCRIPTION	TEMPLATE	EXAMPLE **Note:** Symbols colored gray are used to help explain how the control measure is used and are not a part of the control measure.
Launch Point Type: Entity Type Entity Fires Points Symbol Set: 25 Value: 25**03**00 Draw Rules: Point1 – Static		
Reload Point Type: Entity Type Entity Fires Points Symbol Set: 25 Value: 25**04**00 Draw Rules: Point1 – Static		
Survey Control Point Type: Entity Type Entity Fires Points Symbol Set: 25 Value: 25**05**00 Draw Rules: Point1 – Static		
Known Point Type: Entity Type Entity Fires Points Symbol Set: 25 Value: 25**06**00 Draw Rules: Point2 – Static	 A point known to both the observer and the FDC and recorded or plotted in the FDC. (ATP 3-09.30)	

L.5.19 Target acquisition.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.






L.5.19.1 Target acquisition. The detection, identification and location of a target in sufficient detail to permit the effective employment of weapons.

TABLE L-XVII. Target acquisition control measure symbols.

DESCRIPTION	TEMPLATE	EXAMPLE **Note:** Symbols colored gray are used to help explain how the control measure is used and are not a part of the control measure.
Artillery Target Intelligence Zone (ATI) Type: Entity Type Entity: Fire Areas Symbol Set: 25 Value: 24**11**00	Reserved for hierarchical purposes.	N/A
Artillery Target Intelligence Zone (ATI), Irregular Type: Entity Subtype Entity/Entity Type: Fire Areas/Artillery Target Intelligence Zone Symbol Set: 25 Value: 2411**01** Draw Rules: Area10 - Dynamic	 An area in enemy territory that the commander wishes to monitor closely.	020300ZDEC2008 - 090500ZDEC2008 
Artillery Target Intelligence Zone (ATI), Rectangular Type: Entity Subtype Entity/Entity Type: Fire Areas/Artillery Target Intelligence Zone Symbol Set: 25 Value: 2411**02** Draw Rules: Rectangular1 - Dynamic	 **Orientation:** As determined by the anchor points.	020300ZDEC2008 - 090500ZDEC2008 









Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE L-XVII. Target acquisition control measure symbols - Continued.

DESCRIPTION	TEMPLATE	EXAMPLE **Note:** Symbols colored gray are used to help explain how the control measure is used and are not a part of the control measure.
Artillery Target Intelligence Zone (ATI), Circular Type: Entity Subtype Entity/Entity Type: Fire Areas/Artillery Target Intelligence Zone Symbol Set: 25 Value: 241103 Draw Rules: Circular1 - Dynamic		020300ZDEC2008 - 090500ZDEC2008 
Call For Fire Zone (CFFZ) Type: Entity Type Entity: Fire Area Symbol Set: 25 Value: 241200	Reserved for hierarchical purposes.	N/A
Call For Fire Zone (CFFZ), Irregular Type: Entity Subtype Entity/Entity Type: Fire Areas/Call For Fire Zone Symbol Set: 25 Value: 241201 Draw Rules: Area10 - Dynamic	 A radar search area from which the commander wants to attack hostile firing systems. (FM 1-02.1/FM 3-09)	020300ZDEC2008 - 090500ZDEC2008 
Call For Fire Zone (CFFZ), Rectangular Type: Entity Subtype Entity/Entity Type: Fire Areas/Call For Fire Zone Symbol Set: 25 Value: 241202 Draw Rules: Rectangular1 - Dynamic	 **Orientation:** As determined by the anchor points.	020300ZDEC2008 - 090500ZDEC2008 






Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE L-XVII. Target acquisition control measure symbols - Continued.

DESCRIPTION	TEMPLATE	EXAMPLE **Note:** Symbols colored gray are used to help explain how the control measure is used and are not a part of the control measure.
Call For Fire Zone (CFFZ), Circular Type: Entity Subtype Entity/Entity Type: Fire Areas/Call For Fire Zone Symbol Set: 25 Value: 241**03** Draw Rules: Circular1 - Dynamic		020300ZDEC2008 - 090500ZDEC2008 
Censor Zone Type: Entity Type Entity: Fire Area Symbol Set: 25 Value: 24**13**00	Reserved for hierarchical purposes. An area from which weapons locating radar is prohibited from reporting acquisitions. (FM 3-09)	N/A
Censor Zone, Irregular Type: Entity Subtype Entity/Entity Type: Fire Areas/Censor Zone Symbol Set: 25 Value: 241**01** Draw Rules: Area10 - Dynamic		020300ZDEC2008 - 090500ZDEC2008 
Censor Zone, Rectangular Type: Entity Subtype Entity/Entity Type: Fire Areas/Censor Zone Symbol Set: 25 Value: 241**02** Draw Rules: Rectangular1 - Dynamic	 **Orientation:** As determined by the anchor points.	020300ZDEC2018 - 090500ZDEC2018 
Censor Zone, Circular Type: Entity Subtype Entity/Entity Type: Fire Areas/Censor Zone Symbol Set: 25 Value: 241**03** Draw Rules: Circular1 - Dynamic		020300ZDEC2018 - 090500ZDEC2018 







Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE L-XVII. Target acquisition control measure symbols - Continued.

DESCRIPTION	TEMPLATE	EXAMPLE **Note:** Symbols colored gray are used to help explain how the control measure is used and are not a part of the control measure.
Critical Friendly Zone (CFZ) Type: Entity Type Entity: Fire Area Symbol Set: 25 Value: 24**1**400	Reserved for hierarchical purposes.	N/A
Critical Friendly Zone (CFZ), Irregular Type: Entity Subtype Entity/Entity Type: Fire Areas/Critical Friendly Zone Symbol Set: 25 Value: 2414**01** Draw Rules: Area10 - Dynamic	 An area, usually a friendly unit or location that the maneuver commander designates as critical to the protection of an asset whose loss would seriously jeopardize the mission.	020300ZDEC2018 - 090500ZDEC2018 
Critical Friendly Zone (CFZ), Rectangular Type: Entity Subtype Entity/Entity Type: Fire Areas/Critical Friendly Zone Symbol Set: 25 Value: 2414**02** Draw Rules: Rectangular1 - Dynamic	 **Orientation:** As determined by the anchor points.	020300ZDEC2018 - 090500ZDEC2018 
Critical Friendly Zone (CFZ), Circular Type: Entity Subtype Entity/Entity Type: Fire Areas/Critical Friendly Zone Symbol Set: 25 Value: 2414**03** Draw Rules: Circular1 - Dynamic		020300ZDEC2018 - 090500ZDEC2018 
Dead Space Area Type: Entity Type Entity: Fire Area Symbol Set: 25 Value: 24**15**00	Reserved for hierarchical purposes.	N/A







Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE L-XVII. Target acquisition control measure symbols - Continued.

DESCRIPTION	TEMPLATE	EXAMPLE **Note:** Symbols colored gray are used to help explain how the control measure is used and are not a part of the control measure.
Dead Space Area, Irregular Type: Entity Subtype Entity/Entity Type: Fire Areas/Dead Space Area Symbol Set: 25 Value: 241**501** Draw Rules: Area10 - Dynamic		060300ZNOV2017 - 090500ZNOV2017 
	An area where hostile weapons cannot be detected.	
Dead Space Area, Rectangular Type: Entity Subtype Entity/Entity Type: Fire Areas/Dead Space Area Symbol Set: 25 Value: 241**502** Draw Rules: Rectangular1 - Dynamic		060300ZNOV2017 - 090500ZNOV2017 
	Orientation: As determined by the anchor points.	
Dead Space Area, Circular Type: Entity Subtype Entity/Entity Type: Fire Areas/Dead Space Area Symbol Set: 25 Value: 241**503** Draw Rules: Circular1 - Dynamic		060300ZNOV2017 - 090500ZNOV2017 
Target Build-up Area Type: Entity Type Entity: Fire Area Symbol Set: 25 Value: 24**17**00	Reserved for hierarchical purposes.	N/A






Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE L-XVII. Target acquisition control measure symbols - Continued.

DESCRIPTION	TEMPLATE	EXAMPLE **Note:** Symbols colored gray are used to help explain how the control measure is used and are not a part of the control measure.
Target Build-up Area, Irregular Type: Entity Subtype Entity/Entity Type: Fire Areas/Target Value Area Symbol Set: 25 Value: 241**701** Draw Rules: Area10 - Dynamic		020300ZDEC2018 - 090500ZDEC2018 
Target Build-up Area, Rectangular Type: Entity Subtype Entity/Entity Type: Fire Areas/Target Value Area Symbol Set: 25 Value: 241**702** Draw Rules: Rectangular1 - Dynamic	 **Orientation:** As determined by the anchor points.	020300ZDEC2008 - 090500ZDEC2008 
Target Build-up Area, Circular Type: Entity Subtype Entity/Entity Type: Fire Areas/Target Value Area Symbol Set: 25 Value: 241**703** Draw Rules: Circular1 - Dynamic		020300ZDEC2008 - 090500ZDEC2008 
Target Value Area Type: Entity Type Entity: Fire Area Symbol Set: 25 Value: 24**18**00	Reserved for hierarchical purposes.	N/A








Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE L-XVII. Target acquisition control measure symbols - Continued.

DESCRIPTION	TEMPLATE	EXAMPLE **Note:** Symbols colored gray are used to help explain how the control measure is used and are not a part of the control measure.
Target Value Area, Irregular Type: Entity Subtype Entity/Entity Type: Fire Areas/Target Value Area Symbol Set: 25 Value: 241801 Draw Rules: Area10 - Dynamic		020300ZDEC2008 - 090500ZDEC2008 
Target Value Area, Rectangular Type: Entity Subtype Entity/Entity Type: Fire Areas/Target Value Area Symbol Set: 25 Value: 241802 Draw Rules: Rectangular1 - Dynamic	 **Orientation:** As determined by the anchor points.	020300ZDEC2008 - 090500ZDEC2008 
Target Value Area, Circular Type: Entity Subtype Entity/Entity Type: Fire Areas/Target Value Area Symbol Set: 25 Value: 241803 Draw Rules: Circular1 - Dynamic		020300ZDEC2008 - 090500ZDEC2008 
Zone of Responsibility Type: Entity Type Entity: Fire Area Symbol Set: 25 Value: 241900	N/A	N/A



Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE L-XVII. Target acquisition control measure symbols - Continued.

DESCRIPTION	TEMPLATE	EXAMPLE **Note:** Symbols colored gray are used to help explain how the control measure is used and are not a part of the control measure.
Zone of Responsibility, Irregular Type: Entity Subtype Entity/Entity Type: Fire Areas/Zone of Responsibility Symbol Set: 25 Value: 241**01** Draw Rules: Area10 - Dynamic		
Zone of Responsibility, Rectangular Type: Entity Subtype Entity/Entity Type: Fire Areas/Zone of Responsibility Symbol Set: 25 Value: 241**02** Draw Rules: Rectangular1 - Dynamic	 **Orientation:** As determined by the anchor points.	
Zone of Responsibility, Circular Type: Entity Subtype Entity/Entity Type: Fire Areas/Zone of Responsibility Symbol Set: 25 Value: 241**03** Draw Rules: Circular1 - Dynamic		
Terminally Guided Munition Footprint (TGMF) Type: Entity Type Entity: Fire Area Symbol Set: 25 Value: 24**20**00 Draw Rules: Area10 - Dynamic		



Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE L-XVII. Target acquisition control measure symbols - Continued.

DESCRIPTION	TEMPLATE	EXAMPLE **Note:** Symbols colored gray are used to help explain how the control measure is used and are not a part of the control measure.
Weapon/Sensor Range fan, Circular Type: Entity Type Entity: Fire Area Symbol Set: 25 Value: 24**21**00 Draw Rules: Circular2 - Dynamic **Orientation:** The center point is typically centered over the known location of a weapon or sensor system.		
	The display of distance and altitude numerical values is not required. An altitude of zero indicates surface level.	

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE L-XVII. Target acquisition control measure symbols - Continued.

DESCRIPTION	TEMPLATE	EXAMPLE **Note:** Symbols colored gray are used to help explain how the control measure is used and are not a part of the control measure.
Weapon/Sensor Range fan, Sector Type: Entity Type Entity: Fire Area Symbol Set: 25 Value: 24**22**00 Draw Rules: Arc1 - Dynamic **Orientation:** The center point is typically centered over the known location of a weapon or sensor system. The orientation may change as the object moves or changes.		
	Minimum and maximum distances (ranges), center of sector, left and right sector limits, and altitude may be displayed if desired but are not required to be displayed. An altitude of zero indicates surface level.	

L.5.20 Obstacles.







L.5.20.1 Obstacles. Natural or man-made restrictions to movement which will impose delay and which will normally require specific equipment or munitions to overcome. Obstacles are normally shown in green. If color is not available, they are to be shown in black. Regardless of whether green or black is used for color, ENY shall be used.

TABLE L-XVIII. Obstacle control measure symbols.

DESCRIPTION	TEMPLATE	EXAMPLE **Note:** Symbols colored gray are used to help explain how the control measure is used and are not a part of the control measure.
Protection Areas Type: Entity Symbol Set: 25 Value: **27**0000	Reserved for hierarchical purposes.	N/A







Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE L-XVIII. Obstacle control measure symbols - Continued.

DESCRIPTION	TEMPLATE	EXAMPLE **Note:** Symbols colored gray are used to help explain how the control measure is used and are not a part of the control measure.
Obstacle Belt Type: Entity Type Entity: Protection Areas Symbol Set: 25 Value: 270100 Draw Rules: Area1 - Dynamic		
	An area designated at brigade level in which barrier operations are focused.	
Obstacle Zone Type: Entity Type Entity: Protection Areas Symbol Set: 25 Value: 270200 Draw Rules: Area1 - Dynamic		
	An area designated at corps or division level in which barrier operations are focused. It may be subdivided, below division, into a number of obstacle belts.	
Obstacle Free Zone Type: Entity Type Entity: Protection Areas Symbol Set: 25 Value: 270300 Draw Rules: Area1 - Dynamic		
Obstacle Restricted Zone Type: Entity Type Entity: Protection Areas Symbol Set: 25 Value: 270400 Draw Rules: Area1 – Dynamic		





Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE L-XVIII. Obstacle control measure symbols - Continued.

DESCRIPTION	TEMPLATE	EXAMPLE **Note:** Symbols colored gray are used to help explain how the control measure is used and are not a part of the control measure.
Obstacle Effects Type: Entity Type Entity: Protection Areas Symbol Set: 25 Value: 27**05**00	Reserved for hierarchical purposes.	N/A
Block Type: Entity Subtype Entity/Entity Type: Protection Areas/Obstacle Effects Symbol Set: 25 Value: 27050**1** Draw Rules: Area11 – Dynamic **Orientation:** The head of the "T" typically faces enemy forces.	 An obstacle effect that integrates fire planning and obstacle effort to stop an attacker along a specific avenue of approach or to prevent him from passing through an engagement area. The horizontal line is the limit of the enemy advance. The vertical line indicates where obstacles tie into terrain that is untrafficable.	
Disrupt Type: Entity Subtype Entity/Entity Type: Protection Areas/Obstacle Effects Symbol Set: 25 Value: 27050**2** Draw Rules: Area12 - Dynamic **Orientation:** The arrows point away from enemy forces.	 An obstacle effect that focuses fire planning and obstacle effort to cause the enemy to break up their formation and tempo, interrupt their timetable, commit breaching assets prematurely and attack in a piecemeal effort. Short arrow indicates where enemy is disrupted by obstacles. Longer arrows indicate where movement is allowed and enemy is attacked by fires.	
Fix Type: Entity Subtype Entity/Entity Type: Protection Areas/Obstacle Effects Symbol Set: 25 Value: 27050**3**		







Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE L-XVIII. Obstacle control measure symbols - Continued.

DESCRIPTION	TEMPLATE	EXAMPLE **Note:** Symbols colored gray are used to help explain how the control measure is used and are not a part of the control measure.
Draw Rules: Line9 - Dynamic The orientation is determined by the anchor points.	An obstacle effect that focuses fire planning and obstacle effort to slow an attacker's movement within a specified area, normally an engagement area. **Note**: From the tip of the arrow to the back of the irregular part of the symbol indicates where enemy advance is slowed by obstacles.	
Turn Type: Entity Subtype Entity/Entity Type: Protection Areas/Obstacle Effects Symbol Set: 25 Value: 270504 Draw Rules: Line10 - Dynamic		
	An obstacle effect that integrates fire planning and obstacle effort to drive an enemy formation from one avenue of approach to an adjacent avenue of approach or into an engagement area. **Note**: Direction of the arrow indicates the desired direction of turn. **Orientation:** The rear of the symbol identifies the enemy's location and the arrow points in the direction the obstacle should force the enemy to turn.	
Obstacle Bypass Type: Entity Type Entity: Protection Areas Symbol Set: 25 Value: 270600	Reserved for hierarchical purposes.	N/A
Obstacle Bypass Easy Type: Entity Subtype Entity/Entity Type: Protection Areas/Obstacle Bypass Symbol Set: 25 Value: 270601 Draw Rules: Point12 - Dynamic		
	Note: The opening typically faces the applicable obstacle.	







Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE L-XVIII. Obstacle control measure symbols - Continued.

DESCRIPTION	TEMPLATE	EXAMPLE **Note:** Symbols colored gray are used to help explain how the control measure is used and are not a part of the control measure.
Obstacle Bypass Difficult Type: Entity Subtype Entity/Entity Type: Protection Areas/Obstacle Bypass Symbol Set: 25 Value: 270**602** Draw Rules: Point12 - Dynamic		
	Note: The opening typically faces the applicable obstacle.	
Obstacle Bypass Impossible Type: Entity Subtype Entity/Entity Type: Protection Areas/Obstacle Bypass Symbol Set: 25 Value: 270**603** Draw Rules: Point12 - Dynamic		
	Note: The opening typically faces the applicable obstacle.	
Bridge or Gap Type: Entity Type Entity: Protection Areas Symbol Set: 25 Value: 27**11**00 Draw Rules: Line11 - Dynamic		
	An area within a minefield or obstacle belt, free of live mines or obstacles, whose width and direction will allow a friendly force to pass through in tactical formation.	
Roadblocks, Craters and Blown Bridges Type: Entity Type Entity: Protection Areas Symbol Set: 25 Value: 27**12**00	Reserved for hierarchical purposes.	N/A
	Crater obstacle – An obstacle consisting of one or more craters, created normally in a roadway using demolitions. Orientation is determined by the anchor points.	






Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE L-XVIII. Obstacle control measure symbols - Continued.

DESCRIPTION	TEMPLATE	EXAMPLE **Note:** Symbols colored gray are used to help explain how the control measure is used and are not a part of the control measure.
Planned Type: Entity Subtype Entity/Entity Type: Protection Areas/Roadblocks, Craters and Blown Bridges Symbol Set: 25 Value: 271**01** Draw Rules: Line12 - Dynamic		
Explosives, State of Readiness 1 (Safe) Type: Entity Subtype Entity/Entity Type: Protection Areas/Roadblocks, Craters and Blown Bridges Symbol Set: 25 Value: 271**02** Draw Rules: Line12 - Dynamic		
Explosives, State of Readiness 2 (armed but passable) Type: Entity Subtype Entity/Entity Type: Protection Areas/Roadblocks, Craters and Blown Bridges Symbol Set: 25 Value: 271**03** Draw Rules: Line12 - Dynamic		








Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE L-XVIII. Obstacle control measure symbols - Continued.

DESCRIPTION	TEMPLATE	EXAMPLE **Note:** Symbols colored gray are used to help explain how the control measure is used and are not a part of the control measure.
Roadblock Complete (Executed) Type: Entity Subtype Entity/Entity Type: Protection Areas/Roadblocks, Craters and Blown Bridges Symbol Set: 25 Value: 271**04** Draw Rules: Line12 - Dynamic		
Protection Points Type: Entity Symbol Set: 25 Value: **28**0000	Reserved for hierarchical purposes.	N/A
Abatis Type: Entity Type Entity: Protection Points Symbol Set: 25 Value: 28**01**00 Draw Rules: Line13 - Dynamic	 An obstacle constructed by the felling and interlacing of trees across a route. Orientation is determined by the anchor points.	
Protection Lines Type: Entity Symbol Set: 25 Value: **29**0000	Reserved for hierarchical purposes.	N/A
Obstacle Line Type: Entity Type Entity: Protection Lines Symbol Set: 25 Value: 29**01**00 Draw Rules: Line1 - Dynamic	 A conceptual control measure used at battalion or brigade level to show placement intent without specifying a particular type of linear obstacle.	
Mineline		Monochrome 






Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE L-XVIII. Obstacle control measure symbols - Continued.

DESCRIPTION	TEMPLATE	EXAMPLE **Note:** Symbols colored gray are used to help explain how the control measure is used and are not a part of the control measure.
Type: Entity Subtype Entity/Entity Type: Protection Lines/Obstacle Line Symbol Set: 25 Value: 290101 Draw Rules: Line1 - Dynamic		
Antitank Obstacles Type: Entity Type Entity: Protection Lines Symbol Set: 25 Value: 290200	Reserved for hierarchical purposes.	N/A
	A ditch which is impassable to vehicles unaided. It may be prepared using machinery or explosives.	
Ditch – Under Construction Type: Entity Subtype Entity/Entity Type: Protection Lines/ Antitank Obstacles Symbol Set: 25 Value: 290201 Draw Rules: Line1 - Dynamic		
Ditch – Completed Type: Entity Subtype Entity/Entity Type: Protection Lines/ Antitank Obstacles Symbol Set: 25 Value: 290202 Draw Rules: Line1 – Dynamic		
Ditch Reinforced, with Antitank Mines Type: Entity Subtype Entity/Entity Type: Protection Lines/ Antitank Obstacles		







Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE L-XVIII. Obstacle control measure symbols - Continued.

DESCRIPTION	TEMPLATE	EXAMPLE **Note:** Symbols colored gray are used to help explain how the control measure is used and are not a part of the control measure.
Symbol Set: 25 Value: 290**03** Draw Rules: Line1 - Dynamic	**Note**: The teeth typically point toward enemy forces.	
Antitank Wall Type: Entity Subtype Entity/Entity Type: Protection Lines/ Antitank Obstacles Symbol Set: 25 Value: 290**04** Draw Rules: Line1 - Dynamic	 **Note**: The teeth typically point toward enemy forces.	
Wire Obstacles Type: Entity Type Entity: Protection Lines Symbol Set: 25 Value: 29**03**00	Reserved for hierarchical purposes.	N/A
Unspecified Type: Entity Subtype Entity/Entity Type: Protection Lines/Wire Obstacles Symbol Set: 25 Value: 2903**01** Draw Rules: Line1 - Dynamic		
Single Fence Type: Entity Subtype Entity/Entity Type: Protection Lines/Wire Obstacles Symbol Set: 25 Value: 2903**02** Draw Rules: Line1 - Dynamic		









Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE L-XVIII. Obstacle control measure symbols - Continued.

DESCRIPTION	TEMPLATE	EXAMPLE **Note:** Symbols colored gray are used to help explain how the control measure is used and are not a part of the control measure.
Double Fence Type: Entity Subtype Entity/Entity Type: Protection Lines/Wire Obstacles Symbol Set: 25 Value: 290303 Draw Rules: Line1 - Dynamic		
Double Apron Fence Type: Entity Subtype Entity/Entity Type: Protection Lines/Wire Obstacles Symbol Set: 25 Value: 290304 Draw Rules: Line1 - Dynamic		
Low Wire Fence Type: Entity Subtype Entity/Entity Type: Protection Lines/Wire Obstacles Symbol Set: 25 Value: 290305 Draw Rules: Line1 - Dynamic		
High Wire Fence Type: Entity Subtype Entity/Entity Type: Protection Lines/Wire Obstacles Symbol Set: 25 Value: 290306 Draw Rules: Line1 - Dynamic		







Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE L-XVIII. Obstacle control measure symbols - Continued.

DESCRIPTION	TEMPLATE	EXAMPLE **Note:** Symbols colored gray are used to help explain how the control measure is used and are not a part of the control measure.
Single Concertina Type: Entity Subtype Entity/Entity Type: Protection Lines/Wire Obstacles Symbol Set: 25 Value: 290307 Draw Rules: Line1 - Dynamic		
Double Strand Concertina Type: Entity Subtype Entity/Entity Type: Protection Lines/Wire Obstacles Symbol Set: 25 Value: 290308 Draw Rules: Line1 - Dynamic		
Triple Strand Concertina Type: Entity Subtype Entity/Entity Type: Protection Lines/Wire Obstacles Symbol Set: 25 Value: 290309 Draw Rules: Line1 - Dynamic		
Lane Type: Entity Type Entity: Protection Lines Symbol Set: 25 Value: 290600 Draw Rules: Line14 - Dynamic Orientation is determined by the anchor points.		









Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE L-XVIII. Obstacle control measure symbols - Continued.

DESCRIPTION	TEMPLATE	EXAMPLE **Note:** Symbols colored gray are used to help explain how the control measure is used and are not a part of the control measure.
	A route through an enemy or friendly obstacle that provides a passing force safe passage.	
Minefield Type: Entity Type Entity: Protection Areas Symbol Set: 25 Value: 27**07**00	Reserved for hierarchical purposes.	N/A
	In land mine warfare, a defined area in which mines have been emplaced.	
Static Depiction Type: Entity Subtype Entity/Entity Type: Protection Areas/Minefield Symbol Set: 25 Value: 27070**1** Draw Rules: Point2 – Static		
	Note: this example depicts a minefield reinforced with scatterable mines. This is depicted using "+S" in the Additional information "H" amplifier field.	
Dynamic Depiction Type: Entity Subtype Entity/Entity Type: Protection Areas/Minefield Symbol Set: 25 Value: 27070**7** Draw Rules: Area23 - Dynamic		
Mined Area Type: Entity Type Entity: Protection Areas Symbol Set: 25 Value: 27**08**00 Draw Rules: Area1 - Dynamic		
	An area which is dangerous because of the presence or suspected presence of mines.	









Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE L-XVIII. Obstacle control measure symbols - Continued.

DESCRIPTION	TEMPLATE	EXAMPLE **Note:** Symbols colored gray are used to help explain how the control measure is used and are not a part of the control measure.
Mined Area, Fenced Type: Entity Subtype Entity/Entity Type: Protection Areas/Mine Area Symbol Set: 25 Value: 270801 Draw Rules: Area1 - Dynamic		
Unexploded Explosive Ordnance (UXO) Area Type: Entity Type Entity: Protection Areas Symbol Set: 25 Value: 271000 Draw Rules: Area1 - Dynamic		
Antipersonnel Mine Type: Entity Type Entity: Protection Areas Symbol Set: 25 Value: 280200 Draw Rules: Point2 – Static	 In land mine warfare, a mine designed to be exploded by the presence, proximity or contact of a person and that will incapacitate, wound or kill one or more persons.	
Antipersonnel Mine with Directional Effects Type: Entity Subtype Entity/Entity Type: Protection Points/Antipersonnel Mine Symbol Set: 25 Value: 280201 Draw Rules: Point2 – Static		







Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE L-XVIII. Obstacle control measure symbols - Continued.

DESCRIPTION	TEMPLATE	EXAMPLE **Note:** Symbols colored gray are used to help explain how the control measure is used and are not a part of the control measure.
Antitank Mine Type: Entity Type Entity: Protection Areas Symbol Set: 25 Value: 28**03**00 Draw Rules: Point2 – Static		
	A mine designed to immobilize or destroy a tank.	
Antitank Mine with Anti-handling Device Type: Entity Type Entity: Protection Areas Symbol Set: 25 Value: 28**04**00 Draw Rules: Point2 – Static		
	A device intended to protect a mine and which is part of, linked to, attached to or placed under the mine and which activates when an attempt is made to tamper with or otherwise intentionally disturb the mine.	
Wide Area Antitank Mine Type: Entity Type Entity: Protection Areas Symbol Set: 25 Value: 28**05**00 Draw Rules: Point2 – Static		
	An antitank mine that detects and acquires targets then launches submunition(s) that attacks the top of the targets.	
Unspecified Mine Type: Entity Type Entity: Protection Areas Symbol Set: 25 Value: 28**06**00 Draw Rules: Point2 – Static		







Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE L-XVIII. Obstacle control measure symbols - Continued.

DESCRIPTION	TEMPLATE	EXAMPLE **Note:** Symbols colored gray are used to help explain how the control measure is used and are not a part of the control measure.
Booby Trap Type: Entity Type Entity: Protection Areas Symbol Set: 25 Value: 28**0**700 Draw Rules: Point13 - Static		
	A device designed, constructed or adapted to kill or injure, which functions when a person disturbs or approaches an apparently harmless object or performs an apparently safe act.	
Tetrahedrons, Dragons Teeth, and Other Similar Obstacles Type: Entity Type Entity: Protection Points Symbol Set: 25 Value: 28**1**900 Draw Rules: Point7 - Static	Reserved for hierarchical purposes.	N/A
Fixed and Prefabricated Type: Entity Subtype Entity/Entity Type: Protection Points/ Tetrahedrons, Dragons Teeth, and Other Similar Obstacles Symbol Set: 25 Value: 2819**01** Draw Rules: Point7 - Static		
Movable Type: Entity Subtype Entity/Entity Type: Protection Points/ Tetrahedrons, Dragons Teeth, and Other Similar Obstacles Symbol Set: 25 Value: 2819**02** Draw Rules: Point7 - Static		






Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE L-XVIII. Obstacle control measure symbols - Continued.

DESCRIPTION	TEMPLATE	EXAMPLE **Note:** Symbols colored gray are used to help explain how the control measure is used and are not a part of the control measure.
Movable and Prefabricated Type: Entity Subtype Entity/Entity Type: Protection Points/ Tetrahedrons, Dragons Teeth, and Other Similar Obstacles Symbol Set: 25 Value: 281**03** Draw Rules: Point7 - Static		
Mine Cluster Type: Entity Type Entity: Protection Lines Symbol Set: 25 Value: 29**04**00 Draw Rules: Area13 - Dynamic	 **Note**: The dashed lines in this symbol shall be displayed in present and anticipated status.	
Trip Wire Type: Entity Type Entity: Protection Lines Symbol Set: 25 Value: 29**05**00 Draw Rules: Line15 – Dynamic	 Orientation is determined by the anchor points.	
Vertical Obstructions Type: Entity Type Entity: Protection Points Symbol Set: 25 Value: 28**20**00	Reserved for hierarchical purposes.	N/A









Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE L-XVIII. Obstacle control measure symbols - Continued.

DESCRIPTION	TEMPLATE	EXAMPLE **Note:** Symbols colored gray are used to help explain how the control measure is used and are not a part of the control measure.
Tower, Low Type: Entity Subtype Entity/Entity Type: Protection Points/ Vertical Obstructions Symbol Set: 25 Value: 282**01** Draw Rules: Point16 - Dynamic **Color**: Purple (RGB 128,0,128)		
	Note: Towers less than 1000 Ft AGL. **Orientation:** The symbol will remain upright.	
Tower, High Type: Entity Subtype Entity/Entity Type: Protection Points/ Vertical Obstructions Symbol Set: 25 Value: 282**02** Draw Rules: Point16 - Dynamic **Color**: Purple (RGB 128,0,128)		
	Note: Towers 1000 Ft and Higher AGL. **Orientation:** The symbol will remain upright.	
Overhead Wire Type: Entity Subtype Entity/Entity Type: Protection Points/ Vertical Obstructions Symbol Set: 25 Value: 282**03** Draw Rules: Line1 – Dynamic **Color**: Purple (RGB 128,0,128)		





Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE L-XVIII. Obstacle control measure symbols - Continued.

DESCRIPTION	TEMPLATE	EXAMPLE **Note:** Symbols colored gray are used to help explain how the control measure is used and are not a part of the control measure.
Water Crossing Site The location of a single bridge or rafting site, or in an initial assault a site for the crossing of assault boats, or for the swimming or fording of vehicles on a broad front.		
Assault Crossing Type: Entity Type Entity: Protection Areas Symbol Set: 25 Value: 271300 Draw Rules: Line16 - Dynamic		
Ford Easy Type: Entity Type Entity: Protection Areas Symbol Set: 25 Value: 271500 Draw Rules: Line17 - Dynamic	 Orientation is determined by the anchor points.	
Ford Difficult Type: Entity Type Entity: Protection Areas Symbol Set: 25 Value: 271600 Draw Rules: Line17 - Dynamic	 Orientation is determined by the anchor points.	
Engineer Regulating Point Type: Entity Type Entity: Protection Areas Symbol Set: 25 Value: 280800 Draw Rules: Point1 – Static **Orientation**: The symbol will typically be oriented upright	 Checkpoint to ensure that vehicles do not exceed the capacity of the crossing means and to give drivers final instructions on site-specific procedures and information, such as speed and vehicle interval.	

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE L-XVIII. Obstacle control measure symbols - Continued.

DESCRIPTION	TEMPLATE	EXAMPLE **Note:** Symbols colored gray are used to help explain how the control measure is used and are not a part of the control measure.
Ferry Type: Entity Type Entity: Protection Lines Symbol Set: 25 Value: 29**0**700 Draw Rules: Line18 - Dynamic		
	Orientation is determined by the anchor points.	
Raft Site Type: Entity Type Entity: Protection Lines Symbol Set: 25 Value: 29**08**00 Draw Rules: Line14 - Dynamic		
	Orientation is determined by the anchor points.	

L.5.21 Field fortification control measures.







L.5.21.1 Field fortification. Is an emplacement or shelter of a temporary nature which can be constructed with reasonable facility by units requiring no more than minor engineer supervisory and equipment participation.

TABLE L-XIX. Field fortification control measure symbols.

DESCRIPTION	TEMPLATE	EXAMPLE **Note:** Symbols colored gray are used to help explain how the control measure is used and are not a part of the control measure.
Shelter Type: Entity Type Entity: Protection Areas Symbol Set: 25 Value: 28**09**00 Draw Rules: Point2 – Static		

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE L-XIX. Field fortification control measure symbols - Continued.

DESCRIPTION	TEMPLATE	EXAMPLE **Note:** Symbols colored gray are used to help explain how the control measure is used and are not a part of the control measure.
Above Ground Shelter Type: Entity Type Entity: Protection Areas Symbol Set: 25 Value: 28**1**000 Draw Rules: Point2 – Static		
Below Ground Shelter Type: Entity Type Entity: Protection Areas Symbol Set: 25 Value: 28**1**100 Draw Rules: Point2 – Static		
Fort Type: Entity Type Entity: Protection Areas Symbol Set: 25 Value: 28**1**200 Draw Rules: Point2 – Static		
Fortified Line Type: Entity Type Entity: Protection Lines Symbol Set: 25 Value: 29**0**900 Draw Rules: Line1 - Dynamic	 **Note**: The ramparts typically point toward enemy forces.	
Fighting Position Type: Entity Type Entity: Protection Lines Symbol Set: 25 Value: 29**1**000 Draw Rules:		

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.







TABLE L-XIX. Field fortification control measure symbols - Continued.

DESCRIPTION	TEMPLATE	EXAMPLE **Note:** Symbols colored gray are used to help explain how the control measure is used and are not a part of the control measure.
Line19 - Dynamic	**Note**: The symbol typically faces enemy forces. **Orientation** is determined by the anchor points	

L.5.22 CBRN defense control measure symbols.









L.5.22.1 CBRN defense. These control measure symbols depict those conditions found in an area resulting from immediate or persisting effects of chemical, biological, radiological or nuclear attacks or events (release other than attack).

TABLE L-XX. CBRN defense control measure symbols.

DESCRIPTION	TEMPLATE	EXAMPLE **Note:** Symbols colored gray are used to help explain how the control measure is used and are not a part of the control measure.
Contaminated Areas		
Biological Contaminated Area Type: Entity Type Entity: Protection Areas Symbol Set: 25 Value: 271700 Draw Rules: Area1 - Dynamic		
Chemical Contaminated Area Type: Entity Type Entity: Protection Areas Symbol Set: 25 Value: 271800 Draw Rules: Area1 - Dynamic		
Nuclear Contaminated Area Type: Entity Type Entity: Protection Areas Symbol Set: 25 Value: 271900 Draw Rules: Area1 - Dynamic		









Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE L-XX. CBRN defense control measure symbols - Continued.

DESCRIPTION	TEMPLATE	EXAMPLE **Note:** Symbols colored gray are used to help explain how the control measure is used and are not a part of the control measure.
Radiological Contaminated Area Type: Entity Type Entity: Protection Areas Symbol Set: 25 Value: 27**2**000 Draw Rules: Area1 - Dynamic		
Minimum Safe Distance Zone Type: Entity Type Entity: Protection Areas Symbol Set: 25 Value: 27**2**100 Draw Rules: Area14 - Dynamic		
	Orientation: The center point is typically centered over Ground Zero (GZ) or Designated Ground Zero (DGZ).	
Multiple Strike - (STRIKWARN) Type: Entity Subtype Entity/Entity Type: Protection Areas/Minimum Safe Distance Symbol Set: 25 Value: 2721**01** Draw Rules: Area26 - Static		
	Orientation: The symbol will typically be oriented upright.	
Radiation Dose Rate Contour Line Type: Entity Type Entity: Protection Areas Symbol Set: 25 Value: 27**2**200 Draw Rules: Area1 - Dynamic		
	A line on a map, diagram or overlay joining all points at which the radiation dose rate at a given time is the same.	







Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE L-XX. CBRN defense control measure symbols - Continued.

DESCRIPTION	TEMPLATE	EXAMPLE **Note:** Symbols colored gray are used to help explain how the control measure is used and are not a part of the control measure.
Chemical Event Type: Entity Type Entity: Protection Areas Symbol Set: 25 Value: 28**1**300 Draw Rules: Point7 - Static		
Biological Event Type: Entity Type Entity: Protection Areas Symbol Set: 25 Value: 28**1**400 Draw Rules: Point7 - Static		
Nuclear Event Type: Entity Type Entity: Protection Areas Symbol Set: 25 Value: 28**1**500 Draw Rules: Point7 - Static		
Nuclear Fallout Producing Event Type: Entity Type Entity: Protection Areas Symbol Set: 25 Value: 28**1**600 Draw Rules: Point7 - Static		







Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE L-XX. CBRN defense control measure symbols - Continued.

DESCRIPTION	TEMPLATE	EXAMPLE **Note:** Symbols colored gray are used to help explain how the control measure is used and are not a part of the control measure.
Radiological Event Type: Entity Type Entity: Protection Areas Symbol Set: 25 Value: 28**1**700 Draw Rules: Point7 - Static		
Decontamination Points/Sites		
General De-contamination Point/Site Type: Entity Type Entity: Protection Areas Symbol Set: 25 Value: 28**1**800 Draw Rules: Point1 – Static		
Alternate De-contamination Point/Site Type: Entity Subtype Entity/Entity Type: Protection Points/General Decontamination Point/Site Symbol Set: 25 Value: 2818**01** Draw Rules: Point1 – Static		







Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE L-XX. CBRN defense control measure symbols - Continued.

DESCRIPTION	TEMPLATE	EXAMPLE **Note:** Symbols colored gray are used to help explain how the control measure is used and are not a part of the control measure.
Equipment De-contamination Point/Site Type: Entity Subtype Entity/Entity Type: Protection Points/General Decontamination Point/Site Symbol Set: 25 Value: 281**02** Draw Rules: Point1 – Static		
Troop De-contamination Point/Site Type: Entity Subtype Entity/Entity Type: Protection Points/General Decontamination Point/Site Symbol Set: 25 Value: 281**03** Draw Rules: Point1 – Static		
Equipment / Troop De-contamination Point/Site Type: Entity Subtype Entity/Entity Type: Protection Points/General Decontamination Point/Site Symbol Set: 25 Value: 281**04** Draw Rules: Point1 – Static		





Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE L-XX. CBRN defense control measure symbols - Continued.

DESCRIPTION	TEMPLATE	EXAMPLE **Note:** Symbols colored gray are used to help explain how the control measure is used and are not a part of the control measure.
Operational De-contamination Point/Site Type: Entity Subtype Entity/Entity Type: Protection Points/General Decontamination Point/Site Symbol Set: 25 Value: 281**05** Draw Rules: Point1 – Static		
Thorough De-contamination Point/Site Type: Entity Subtype Entity/Entity Type: Protection Points/General Decontamination Point/Site Symbol Set: 25 Value: 281**06** Draw Rules: Point1 – Static		
Main Equipment De-contamination Point/Site Type: Entity Subtype Entity/Entity Type: Protection Points/General Decontamination Point/Site Symbol Set: 25 Value: 281**07** Draw Rules: Point1 – Static		

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE L-XX. CBRN defense control measure symbols - Continued.





DESCRIPTION	TEMPLATE	EXAMPLE **Note:** Symbols colored gray are used to help explain how the control measure is used and are not a part of the control measure.
Forward Troop De-contamination Point/Site Type: Entity Subtype Entity/Entity Type: Protection Points/General Decontamination Point/Site Symbol Set: 25 Value: 281**08** Draw Rules: Point1 – Static		
Wounded Personnel De-contamination Site Type: Entity Subtype Entity/Entity Type: Protection Points/General Decontamination Point/Site Symbol Set: 25 Value: 281**09** Draw Rules: Point1 – Static		

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

L.5.23 Sustainment control measures.







L.5.23.1 Sustainment control measures. The provision of logistics and personnel services required to maintain and prolong operations until successful mission accomplishment.

TABLE L-XXI. Sustainment point control measure symbols.

DESCRIPTION	TEMPLATE	EXAMPLE **Note:** Symbols colored gray are used to help explain how the control measure is used and are not a part of the control measure.
Sustainment Points Type: Entity Symbol Set: 25 Value: **32**0000	Reserved for hierarchical purposes.	N/A
Ambulance Points Type: Entity Type Entity: Sustainment Points Symbol Set: 25 Value: 32**01**00	Reserved for hierarchical purposes.	N/A
Ambulance Exchange Point Type: Entity Subtype Entity/Entity Type: Sustainment Points/Ambulance Points Symbol Set: 25 Value: 32010**1** Draw Rules: Point1 – Static	 A location where a patient is transferred from one ambulance to another en-route to a medical treatment facility. (ATP 4-02.2)	
Ambulance Control Point Type: Entity Subtype Entity/Entity Type: Sustainment Points/Ambulance Points Symbol Set: 25 Value: 32010**2** Draw Rules: Point1 – Static	 A point where ambulances may take one of two or more directions to reach loading points. (ATP 4-02.2)	









Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE L-XXI. Sustainment point control measure symbols - Continued.

DESCRIPTION	TEMPLATE	EXAMPLE **Note:** Symbols colored gray are used to help explain how the control measure is used and are not a part of the control measure.
Ambulance Load Point Type: Entity Subtype Entity/Entity Type: Sustainment Points/Ambulance Points Symbol Set: 25 Value: 320103 Draw Rules: Point1 – Static		
A point where one or more ambulances are stationed ready to receive patients for evacuation. (ATP 4-02.2)		
Ambulance Relay Point Type: Entity Subtype Entity/Entity Type: Sustainment Points/Ambulance Points Symbol Set: 25 Value: 320104 Draw Rules: Point1 – Static		
A point where one or more empty ambulances are stationed. (ATP 4-02.2)		
Ammunition Supply Point Type: Entity Type Entity: Sustainment Points Symbol Set: 25 Value: 320200 Draw Rules: Point1 – Static		
An area designated to receive, store, reconfigure and issue Class V material.		









Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE L-XXI. Sustainment point control measure symbols - Continued.

DESCRIPTION	TEMPLATE	EXAMPLE **Note:** Symbols colored gray are used to help explain how the control measure is used and are not a part of the control measure.
Ammunition Transfer Point Type: Entity Type Entity: Sustainment Points Symbol Set: 25 Value: 32**03**00 Draw Rules: Point1 – Static		
	A designated temporary site from which Class V material is transferred to unit vehicles.	
Cannibalization Point Type: Entity Type Entity: Sustainment Points Symbol Set: 25 Value: 32**04**00 Draw Rules: Point1 – Static		
Casualty Collection Point Type: Entity Type Entity: Sustainment Points Symbol Set: 25 Value: 32**05**00 Draw Rules: Point1 – Static		
	A specific location where casualties are assembled to be transported to a medical treatment facility, for example, a company aid post.	
Civilian Collection Point Type: Entity Type Entity: Sustainment Points Symbol Set: 25 Value: 32**06**00 Draw Rules: Point1 – Static		
	A specific location where civilians are assembled to be transported to another location.	









Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE L-XXI. Sustainment point control measure symbols - Continued.

DESCRIPTION	TEMPLATE	EXAMPLE **Note:** Symbols colored gray are used to help explain how the control measure is used and are not a part of the control measure.
Detainee Collection Point Type: Entity Type Entity: Sustainment Points Symbol Set: 25 Value: 32**0**700 Draw Rules: Point1 – Static		
	A specific location where detainee are assembled to be transported to another location.	
Enemy Prisoner of War (EPW) Collection Point Type: Entity Type Entity: Sustainment Points Symbol Set: 25 Value: 32**0**800 Draw Rules: Point1 – Static		
	A specific location where enemy prisoners of war are assembled to be transported to another location.	
Logistics Release Point (LRP) Type: Entity Type Entity: Sustainment Points Symbol Set: 25 Value: 32**0**900 Draw Rules: Point1 – Static		
Maintenance Collection Point (MCP) Type: Entity Type Entity: Sustainment Points Symbol Set: 25 Value: 32**1**000 Draw Rules: Point1 – Static		
	A point established to collect equipment awaiting repair, controlled exchange, cannibalization, or evacuation. It may be operated by the user or by the direct support maintenance units.	







Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE L-XXI. Sustainment point control measure symbols - Continued.

DESCRIPTION	TEMPLATE	EXAMPLE **Note:** Symbols colored gray are used to help explain how the control measure is used and are not a part of the control measure.
Medical Evacuation (MEDEVAC) Pick-up Point Type: Entity Type Entity: Sustainment Points Symbol Set: 25 Value: 32**11**00 Draw Rules: Point1 – Static		
Rearm, Refuel and Resupply Point (R3P) Type: Entity Type Entity: Sustainment Points Symbol Set: 25 Value: 32**12**00 Draw Rules: Point1 – Static		
	A designated point through which a unit passes where it receives fuel, ammunition and other necessary supplies to continue operations.	
Refuel On the Move (ROM) Point Type: Entity Type Entity: Sustainment Points Symbol Set: 25 Value: 32**13**00 Draw Rules: Point1 – Static		
	An area established to ensure that fuel tanks on combat and fuel servicing vehicles are full before they arrive in the unit's tactical assembly area.	
Traffic Control Post (TCP) Type: Entity Type Entity: Sustainment Points Symbol Set: 25 Value: 32**14**00 Draw Rules: Point1 – Static		
	Manned post used to preclude interruption of traffic flow or movement along designated routes.	

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE L-XXI. Sustainment point control measure symbols - Continued.





DESCRIPTION	TEMPLATE	EXAMPLE **Note:** Symbols colored gray are used to help explain how the control measure is used and are not a part of the control measure.
Trailer Transfer Point (TTP) Type: Entity Type Entity: Sustainment Points Symbol Set: 25 Value: 32**1**500 Draw Rules: Point1 – Static **Orientation**: The symbol will typically be oriented upright		
	A location where trailers are transferred from one carrier to another while en-route.	
Unit Maintenance Collection Point (UMCP) Type: Entity Type Entity: Sustainment Points Symbol Set: 25 Value: 32**1**600 Draw Rules: Point1 – Static		
	A location or series of locations, operated by a battalion maintenance platoon, that is the nearest point to the combat unit to which equipment can be recovered and where limited parts are available, and some repairs can be performed.	
Mortuary Affairs Collection Point Type: Entity Type Entity: Sustainment Points Symbol Set: 25 Value: 32**1**900 Draw Rules: Point1 – Static		

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

L.5.24 Supply points.







L.5.24.1 Supply point. Any point where supplies are issued in detail. Supply points follow the format as shown above with a modification to the symbol. As with the symbol for supply units, there is an additional line placed toward the bottom of the box. In building points, the name/type of the point is abbreviated and positioned inside the top part of the point symbol in field "A". For some supply symbols this may be a symbol icon. STANAG 2961 provides comparison charts for NATO and NATO nation classes of supply.

TABLE L-XXII. Supply point control measure symbols.

DESCRIPTION	TEMPLATE	EXAMPLE **Note:** Symbols colored gray are used to help explain how the control measure is used and are not a part of the control measure.
General Supply Point Type: Entity Type Entity: Sustainment Points Symbol Set: 25 Value: 32**1**700 Draw Rules: Point1 – Static		
NATO Class I Type: Entity Subtype Entity/Entity Type: Sustainment Points/General Supply Point Symbol Set: 25 Value: 3217**01** Draw Rules: Point1 – Static		
	Those items which are consumed by personnel or animals at the approximately uniform rate, irrespective of local changes in combat or terrain conditions. (STANAG 2961)	







Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE L-XXII. Supply point control measure symbols - Continued.

DESCRIPTION	TEMPLATE	EXAMPLE **Note:** Symbols colored gray are used to help explain how the control measure is used and are not a part of the control measure.
NATO Class II Type: Entity Subtype Entity/Entity Type: Sustainment Points/General Supply Point Symbol Set: 25 Value: 321**02** Draw Rules: Point1 – Static		
Supplies for which allowances are established by tables of organization and equipment. (STANAG 2961)		
NATO Class III Type: Entity Subtype Entity/Entity Type: Sustainment Points/General Supply Point Symbol Set: 25 Value: 321**03** Draw Rules: Point1 – Static		
Fuels and lubricants for all purposes, except for operating aircraft or for use in weapons such as flame throwers. (STANAG 2961)		
NATO Class IV Type: Entity Subtype Entity/Entity Type: Sustainment Points/General Supply Point Symbol Set: 25 Value: 321**04** Draw Rules: Point1 – Static		
Supplies for which initial issue allowances are not prescribed by approved issue tables. (STANAG 2961)		









Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE L-XXII. Supply point control measure symbols - Continued.

DESCRIPTION	TEMPLATE	EXAMPLE **Note:** Symbols colored gray are used to help explain how the control measure is used and are not a part of the control measure.
NATO Class V Type: Entity Subtype Entity/Entity Type: Sustainment Points/General Supply Point Symbol Set: 25 Value: 321**705** Draw Rules: Point1 – Static		
Ammunition, explosives and chemical agents of all types. (STANAG 2961)		
NATO Multiple Supply Class Point. Type: Entity Subtype Entity/Entity Type: Sustainment Points/General Supply Point Symbol Set: 25 Value: 321**706** Draw Rules: Point1 – Static		
Note: Use supply class numbers (I, II, III, IV and V) for a field or ALL for all classes of supply.		
US Class I Type: Entity Subtype Entity/Entity Type: Sustainment Points/General Supply Point Symbol Set: 25 Value: 321**707** Draw Rules: Point1 – Static		









Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE L-XXII. Supply point control measure symbols - Continued.

DESCRIPTION	TEMPLATE	EXAMPLE **Note:** Symbols colored gray are used to help explain how the control measure is used and are not a part of the control measure.
US Class II Type: Entity Subtype Entity/Entity Type: Sustainment Points/General Supply Point Symbol Set: 25 Value: 321**708** Draw Rules: Point1 – Static		
US Class III Type: Entity Subtype Entity/Entity Type: Sustainment Points/General Supply Point Symbol Set: 25 Value: 321**709** Draw Rules: Point1 – Static		
US Class IV Type: Entity Subtype Entity/Entity Type: Sustainment Points/General Supply Point Symbol Set: 25 Value: 321**710** Draw Rules: Point1 – Static		
US Class V Type: Entity Subtype Entity/Entity Type: Sustainment Points/General Supply Point Symbol Set: 25 Value: 321**711** Draw Rules: Point1 – Static		






Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE L-XXII. Supply point control measure symbols - Continued.

DESCRIPTION	TEMPLATE	EXAMPLE **Note:** Symbols colored gray are used to help explain how the control measure is used and are not a part of the control measure.
US Class VI Type: Entity Subtype Entity/Entity Type: Sustainment Points/General Supply Point Symbol Set: 25 Value: 3217**12** Draw Rules: Point1 – Static		
US Class VII Type: Entity Subtype Entity/Entity Type: Sustainment Points/General Supply Point Symbol Set: 25 Value: 3217**13** Draw Rules: Point1 – Static		
US Class VIII Type: Entity Subtype Entity/Entity Type: Sustainment Points/General Supply Point Symbol Set: 25 Value: 3217**14** Draw Rules: Point1 – Static		
US Class IX Type: Entity Subtype Entity/Entity Type: Sustainment Points/General Supply Point Symbol Set: 25 Value: 3217**15** Draw Rules: Point1 – Static		






Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE L-XXII. Supply point control measure symbols - Continued.

DESCRIPTION	TEMPLATE	EXAMPLE **Note:** Symbols colored gray are used to help explain how the control measure is used and are not a part of the control measure.
US Class X Type: Entity Subtype Entity/Entity Type: Sustainment Points/General Supply Point Symbol Set: 25 Value: 3217**16** Draw Rules: Point1 – Static		
Medical Supply Point Type: Entity Type Entity: Sustainment Points Symbol Set: 25 Value: 32**18**00 Draw Rules: Point1 – Static		
Sustainment Areas Type: Entity Symbol Set: 25 Value: **31**0000	Reserved for hierarchical purposes.	N/A
Detainee Holding Area Type: Entity Type Entity: Sustainment Areas Symbol Set: 25 Value: 31**01**00 Draw Rules: Area1 - Dynamic		









Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE L-XXII. Supply point control measure symbols - Continued.

DESCRIPTION	TEMPLATE	EXAMPLE **Note:** Symbols colored gray are used to help explain how the control measure is used and are not a part of the control measure.
Enemy Prisoner of War (EPW) Holding Area Type: Entity Type Entity: Sustainment Areas Symbol Set: 25 Value: 31**02**00 Draw Rules: Area1 - Dynamic		
Forward Arming and Refueling Point (FARP) Type: Entity Type Entity: Sustainment Areas Symbol Set: 25 Value: 31**03**00 Draw Rules: Area1 - Dynamic	 (DOD) "A temporary facility — organized, equipped, and deployed to provide fuel and ammunition necessary for the employment of aviation maneuver units in combat. Also called FARP. (JP 3-09.3) Referenced in ATP 3-17.2"	
Refugee Holding Area Type: Entity Type Entity: Sustainment Areas Symbol Set: 25 Value: 31**04**00 Draw Rules: Area1 - Dynamic		
Support Area		
Regimental Support Area Type: Entity Type Entity: Sustainment Areas Symbol Set: 25 Value: 31**05**00 Draw Rules: Area1 - Dynamic		







Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE L-XXII. Supply point control measure symbols - Continued.

DESCRIPTION	TEMPLATE	EXAMPLE **Note:** Symbols colored gray are used to help explain how the control measure is used and are not a part of the control measure.
Brigade Support Area (BSA) Type: Entity Type Entity: Sustainment Areas Symbol Set: 25 Value: 31**06**00 Draw Rules: Area1 - Dynamic		
	A designated area in which combat service support elements from division support command and corps support command provide logistic support to a brigade.	
Division Support Area Type: Entity Type Entity: Sustainment Areas Symbol Set: 25 Value: 31**07**00 Draw Rules: Area1 - Dynamic		
	An area normally located in the division rear and often positioned near air-landing facilities along the main supply route.	
Corps Support Area Type: Entity Type Entity: Sustainment Areas Symbol Set: 25 Value: 31**08**00 Draw Rules: Area1 - Dynamic		
Sustainment Lines Type: Entity Symbol Set: 25 Value: **33**0000	Reserved for hierarchical purposes.	N/A
Moving Convoy Type: Entity Type Entity: Sustainment Line Symbol Set: 25 Value: 33**01**00 Draw Rules: Line9 - Dynamic		
	Note: The arrow points in the direction the convoy is moving. The orientation is determined by the anchor points.	








Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE L-XXII. Supply point control measure symbols - Continued.

DESCRIPTION	TEMPLATE	EXAMPLE **Note:** Symbols colored gray are used to help explain how the control measure is used and are not a part of the control measure.
Halted Convoy Type: Entity Type Entity: Sustainment Line Symbol Set: 25 Value: 33**02**00 Draw Rules: Line20 - Dynamic		
	Orientation: The arrow points to the location where the convoy has halted.	
Supply Routes - Orientation is determined by the anchor points.		
Main Supply Route (MSR) Type: Entity Type Entity: Sustainment Line Symbol Set: 25 Value: 33**03**00 Draw Rules: Line21 - Dynamic		
	The route or routes designated within an area of operations upon which the bulk of traffic flows in support of military operations.	
One Way Traffic Type: Entity Subtype Entity/Entity Type: Sustainment Lines/Main Supply Route (MSR) Symbol Set: 25 Value: 330**01** Draw Rules: Line21 - Dynamic		
Two Way Traffic Type: Entity Subtype Entity/Entity Type: Sustainment Lines/Main Supply Route (MSR) Symbol Set: 25 Value: 330**02** Draw Rules: Line21 - Dynamic		







Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE L-XXII. Supply point control measure symbols - Continued.

DESCRIPTION	TEMPLATE	EXAMPLE **Note:** Symbols colored gray are used to help explain how the control measure is used and are not a part of the control measure.
Alternating Traffic Type: Entity Subtype Entity/Entity Type: Sustainment Lines/Main Supply Route (MSR) Symbol Set: 25 Value: 330**303** Draw Rules: Line21 - Dynamic		
Alternate Supply Route (ASR) Type: Entity Type Entity: Sustainment Line Symbol Set: 25 Value: 33**04**00 Draw Rules: Line21 - Dynamic	 A route or routes designated within an area of operations to provide for the movement of traffic when main supply routes become disabled or congested.	
One Way Traffic Type: Entity Subtype Entity/Entity Type: Sustainment Lines/Alternate Supply Route (ASR) Symbol Set: 25 Value: 330**401** Draw Rules: Line21 - Dynamic		
Two Way Traffic Type: Entity Subtype Entity/Entity Type: Sustainment Lines/Alternate Supply Route (ASR) Symbol Set: 25 Value: 330**402** Draw Rules: Line21 - Dynamic		

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE L-XXII. Supply point control measure symbols - Continued.





DESCRIPTION	TEMPLATE	EXAMPLE **Note:** Symbols colored gray are used to help explain how the control measure is used and are not a part of the control measure.
Alternating Traffic Type: Entity Subtype Entity/Entity Type: Sustainment Lines/Alternate Supply Route (ASR) Symbol Set: 25 Value: 330**403** Draw Rules: Line21 - Dynamic		
Traffic Route Type: Entity Type Entity: Sustainment Line Symbol Set: 25 Value: 33**05**00 Draw Rules: Line21 - Dynamic		
One Way Traffic Type: Entity Subtype Entity/Entity Type: Sustainment Lines/Traffic Route Symbol Set: 25 Value: 3305**01** Draw Rules: Line21 - Dynamic		
Alternating Traffic Type: Entity Subtype Entity/Entity Type: Sustainment Lines/Traffic Route Symbol Set: 25 Value: 3305**02** Draw Rules: Line21 - Dynamic		

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

L.5.25 Mission and operational tasks.









L.5.25.1 Mission and operational task symbols. A specific activity performed by a unit while executing a form of tactical operation or form of maneuver.

TABLE L-XXIII. Mission task symbols.

DESCRIPTION	TEMPLATE	EXAMPLE **Note:** Symbols colored gray are used to help explain how the control measure is used and are not a part of the control measure.
Mission Tasks Type: Entity Symbol Set: 25 Value: **34**0000 Static/Dynamic: N/A	Reserved for hierarchical purposes.	N/A
Block Type: Entity Type Entity: Mission Tasks Symbol Set: 25 Value: 34**01**00 Draw Rules: Area24 - Dynamic		
	Note: The head of the "T" typically faces enemy forces.	
Breach Type: Entity Type Entity: Mission Tasks Symbol Set: 25 Value: 34**02**00 Draw Rules: Point12 - Dynamic		
	Note: The opening typically faces the enemy forces.	
Bypass Type: Entity Type Entity: Mission Tasks Symbol Set: 25 Value: 34**03**00 Draw Rules: Point12 - Dynamic		
	Note: The opening typically faces the applicable obstacle.	







Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE L-XXIII. Mission task symbols - Continued.

DESCRIPTION	TEMPLATE	EXAMPLE **Note:** Symbols colored gray are used to help explain how the control measure is used and are not a part of the control measure.
Canalize Type: Entity Type Entity: Mission Tasks Symbol Set: 25 Value: 34**04**00 Draw Rules: Point12 - Dynamic		
Note: The opening typically faces the applicable obstacle.		
Clear Type: Entity Type Entity: Mission Tasks Symbol Set: 25 Value: 34**05**00 Draw Rules: Line23 - Dynamic		
Note: The arrows typically point toward enemy forces.		
Counterattack Type: Entity Type Entity: Mission Tasks Symbol Set: 25 Value: 34**06**00 Draw Rules: Axis2 - Dynamic **Orientation:** The arrowhead typically points toward enemy forces.		
Note: The dashed lines in this graphic shall be displayed in present and anticipated status.		
Counterattack by Fire Type: Entity Type Entity: Mission Tasks Symbol Set: 25 Value: 34**07**00 Draw Rules: Axis2 - Dynamic **Orientation:** The arrowhead typically points toward enemy forces.		
Note: The dashed lines in this graphic shall be displayed in present and anticipated status.		









Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE L-XXIII. Mission task symbols - Continued.

DESCRIPTION	TEMPLATE	EXAMPLE **Note:** Symbols colored gray are used to help explain how the control measure is used and are not a part of the control measure.
Delay Type: Entity Type Entity: Mission Tasks Symbol Set: 25 Value: 34**08**00 Draw Rules: Line24 - Dynamic		
	Orientation: The arrow points in the direction of the action. The tip of the arrowhead may indicate the location where the action is to conclude. The unit's current location is typically represented at the base of the arc. The 180 degree circular arc is always perpendicular to the line.	
Destroy Type: Entity Type Entity: Mission Tasks Symbol Set: 25 Value: 34**09**00 Draw Rules: Point2 – Static **Orientation**: The symbol is typically centered over the desired location.		
Disrupt Type: Entity Type Entity: Mission Tasks Symbol Set: 25 Value: 34**10**00 Draw Rules: Area12 - Dynamic		
	Note: The arrows typically point toward enemy forces.	
Fix Type: Entity Type Entity: Mission Tasks Symbol Set: 25 Value: 34**11**00 Draw Rules: Line9 - Dynamic		
	Note: The arrow typically points toward enemy forces with the tip of the arrowhead indicating the location of the action.	









Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE L-XXIII. Mission task symbols - Continued.

DESCRIPTION	TEMPLATE	EXAMPLE **Note:** Symbols colored gray are used to help explain how the control measure is used and are not a part of the control measure.
Follow and Assume Type: Entity Type Entity: Mission Tasks Symbol Set: 25 Value: 34**1**200 Draw Rules: Line25 - Dynamic		
	Note: The dashed lines in this graphic shall be displayed in present and anticipated status. The arrow typically points in the direction of the action.	
Follow and Support Type: Entity Type Entity: Mission Tasks Symbol Set: 25 Value: 34**1**300 Draw Rules: Line25 - Dynamic		
	Note: The arrow typically points in the direction of the action.	
Interdict Type: Entity Type Entity: Mission Tasks Symbol Set: 25 Value: 34**1**400 Draw Rules: Point14 - Static		
Isolate Type: Entity Type Entity: Mission Tasks Symbol Set: 25 Value: 34**1**500 Draw Rules: Area15 - Dynamic		
	Orientation: The opening will be on the friendly side of the symbol.	







Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE L-XXIII. Mission task symbols - Continued.

DESCRIPTION	TEMPLATE	EXAMPLE **Note:** Symbols colored gray are used to help explain how the control measure is used and are not a part of the control measure.
Neutralize Type: Entity Type Entity: Mission Tasks Symbol Set: 25 Value: 341600 Draw Rules: Point2 – Static		
	Note: The dashed lines in this graphic shall be displayed in present and anticipated status.	
Occupy Type: Entity Type Entity: Mission Tasks Symbol Set: 25 Value: 341700 Draw Rules: Area16 - Dynamic		
	Orientation: The opening will be on the friendly side of the control measure.	
Penetrate Type: Entity Type Entity: Mission Tasks Symbol Set: 25 Value: 341800 Draw Rules: Area17 - Dynamic		
	Orientation: The arrow points toward enemy forces.	
Relief in Place (RIP) Type: Entity Type Entity: Mission Tasks Symbol Set: 25 Value: 341900 Draw Rules: Area18 - Dynamic		









Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE L-XXIII. Mission task symbols - Continued.

DESCRIPTION	TEMPLATE	EXAMPLE **Note:** Symbols colored gray are used to help explain how the control measure is used and are not a part of the control measure.
	Orientation: Determined by the anchor points. The unit being relieved is typically located at the base of the curve and the unit performing the relief is typically located at the end of the symbol. The arrowhead typically points to the location the relieved unit should move to.	
Retire/ Retirement Type: Entity Type Entity: Mission Tasks Symbol Set: 25 Value: 34**20**00 Draw Rules: Line24 - Dynamic		
	Orientation: The arrow points in the direction of the action. The tip of the arrowhead may indicate the location where the action is to conclude. The unit's current location is typically represented at the base of the arc. The 180 degree circular arc is always perpendicular to the line.	
Secure Type: Entity Type Entity: Mission Tasks Symbol Set: 25 Value: 34**21**00 Draw Rules: Area19 - Dynamic		
	Note: The opening will be on the friendly side of the symbol.	
Security Type: Entity Type Entity: Mission Tasks Symbol Set: 25 Value: 34**22**00	N/A	N/A
Cover Type: Entity Subtype Entity/Entity Type: Mission Tasks/Security Symbol Set: 25 Value: 3422**01** Draw Rules: Line26 - Dynamic		
	Orientation is determined by the anchor points. The arrowheads may touch other symbols that define the limits of the task. The tactical symbol indicator is centered between point 2 and point 3.	







Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE L-XXIII. Mission task symbols - Continued.

DESCRIPTION	TEMPLATE	EXAMPLE **Note:** Symbols colored gray are used to help explain how the control measure is used and are not a part of the control measure.
Guard Type: Entity Subtype Entity/Entity Type: Mission Tasks/Security Symbol Set: 25 Value: 3422**02** Draw Rules: Line26 - Dynamic		
	Orientation is determined by the anchor points. The arrowheads may touch other symbols that define the limits of the task. The tactical symbol indicator is centered between point 2 and point 3.	
Screen Type: Entity Subtype Entity/Entity Type: Mission Tasks/Security Symbol Set: 25 Value: 3422**03** Draw Rules: Line26 - Dynamic		
	Orientation is determined by the anchor points. The arrowheads may touch other symbols that define the limits of the task. The tactical symbol indicator is centered between point 2 and point 3.	
Seize Type: Entity Type Entity: Mission Tasks Symbol Set: 25 Value: 34**23**00 Draw Rules: Line27 - Dynamic		
	Orientation: The arrowhead identifies the location/object to be seized and the circle identifies the unit(s) assigned the task. See 5.3.11 for options to accommodate multiple units.	
Withdraw Type: Entity Type Entity: Mission Tasks Symbol Set: 25 Value: 34**24**00 Draw Rules: Line24 - Dynamic		







Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE L-XXIII. Mission task symbols - Continued.

DESCRIPTION	TEMPLATE	EXAMPLE **Note:** Symbols colored gray are used to help explain how the control measure is used and are not a part of the control measure.
	Orientation: The arrow points in the direction of the action. The tip of the arrowhead may indicate the location where the action is to conclude. The unit's current location is typically represented at the base of the arc. The 180 degree circular arc is always perpendicular to the line.	
Withdraw Under Pressure Type: Entity Type Entity: Mission Tasks Symbol Set: 25 Value: 34**25**00 Draw Rules: Line24 - Dynamic		
	Orientation: The arrow points in the direction of the action. The tip of the arrowhead may indicate the location where the action is to conclude. The unit's current location is typically represented at the base of the arc. The 180 degree circular arc is always perpendicular to the line.	
Cordon and Knock Type: Entity Type Entity: Mission Tasks Symbol Set: 25 Value: 34**26**00 Draw Rules: Area15 - Dynamic		
	Orientation: The opening will be on the friendly side of the symbol.	
Cordon and Search Type: Entity Type Entity: Mission Tasks Symbol Set: 25 Value: 34**27**00 Draw Rules: Area15 - Dynamic		
	Orientation: The opening will be on the friendly side of the symbol.	

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE L-XXIII. Mission task symbols - Continued.



DESCRIPTION	TEMPLATE	EXAMPLE **Note:** Symbols colored gray are used to help explain how the control measure is used and are not a part of the control measure.
Suppress Type: Entity Type Entity: Mission Tasks Symbol Set: 25 Value: 34**28**00 Draw Rules: Point2 – Static **Orientation**: The symbol is typically centered over the desired location.	 **Note:** The dashed lines in this graphic shall be displayed in present and anticipated status.	
Forward Passage of Lines Type: Entity Type Entity: Mission Tasks Symbol Set: 25 Value: 34**41**00 Draw Rules: Line24 - Dynamic	 **Orientation:** The arrow points in the direction of the action. The tip of the arrowhead may indicate the location where the action is to conclude. The unit's current location is typically represented at the base of the arc. The 180 degree circular arc is always perpendicular to the line.	
Rearward Passage of Lines Type: Entity Type Entity: Mission Tasks Symbol Set: 25 Value: 34**42**00 Draw Rules: Line24 - Dynamic	 **Orientation:** The arrow points in the direction of the action. The tip of the arrowhead may indicate the location where the action is to conclude. The unit's current location is typically represented at the base of the arc. The 180 degree circular arc is always perpendicular to the line.	

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

L.5.26 Intelligence control measures.

L.5.26.1 Intelligence control measure symbols. Support the planning, execution and support the acquisition of timely, tailored, and accurate intelligence in relation with the commander's mission.

TABLE L-XXIV. Intelligence control measure symbols.

DESCRIPTION	TEMPLATE	EXAMPLE **Note:** Symbols colored gray are used to help explain how the control measure is used and are not a part of the control measure.
Intelligence Lines Type: Entity Symbol Set: 25 Value: **30**0000	N/A	N/A
Intelligence Coordination Line (ICL) Type: Entity Type Entity: Intelligence Lines Symbol Set: 25 Value: 30**01**00 Draw Rules: Line1- Dynamic		

L.5.27 Control measure sector 1 modifiers. The physical location of the sector 1 modifiers in control measure symbol is different from the other appendices in this standard as it differs for each symbol. The physical location when applicable is depicted in the symbol template.

TABLE L-XXV. Control measures sector 1 modifiers.

DESCRIPTION	CATEGORY	MODIFIER	REMARKS
Wheeled (Limited Cross Country) Symbol Set: 25 Value: 01	Mobility		For use with Limited Access Area only
Wheeled (Cross Country) Symbol Set: 25 Value: 02	Mobility		For use with Limited Access Area only
Tracked Symbol Set: 25 Value: 03	Mobility		For use with Limited Access Area only

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE L-XXV. Control measures sector 1 modifiers - Continued.

DESCRIPTION	CATEGORY	MODIFIER	REMARKS
Wheeled and Tracked Combination Symbol Set: 25 Value: 04	Mobility		For use with Limited Access Area only
Towed Symbol Set: 25 Value: 05	Mobility		For use with Limited Access Area only
Railway Symbol Set: 25 Value: 06	Mobility		For use with Limited Access Area only
Over-Snow (Prime Mover) Symbol Set: 25 Value: 07	Mobility		For use with Limited Access Area only
Sled Symbol Set: 25 Value: 08	Mobility		For use with Limited Access Area only
Pack Animal Symbol Set: 25 Value: 09	Mobility		For use with Limited Access Area only
Barge Symbol Set: 25 Value: 10	Mobility		For use with Limited Access Area only
Amphibious Symbol Set: 25 Value: 11	Mobility		For use with Limited Access Area only
No Vehicles Symbol Set: 25 Value: 12	Mobility	ALL	For use with Limited Access Area only
Unspecified Symbol Set: 25 Value: 13	Mine Type		
Antipersonnel Mine Symbol Set: 25 Value: 14	Mine Type		
Antipersonnel Mine with Directional Effects Symbol Set: 25 Value: 15	Mine Type		

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE L-XXV. Control measures sector 1 modifiers - Continued.

DESCRIPTION	CATEGORY	MODIFIER	REMARKS
Antitank Mine Symbol Set: 25 Value: 16	Mine Type		
Antitank Mine with Antihandling Device Symbol Set: 25 Value: 17	Mine Type		
Wide Area Antitank Mine Symbol Set: 25 Value: 18	Mine Type		
Mine Cluster Symbol Set: 25 Value: 19	Mine Type		
Antipersonnel Mine and Antipersonnel Mine with Directional Effects Symbol Set: 25 Value: 20	Mine Type		
Antipersonnel Mine and Antitank Mine Symbol Set: 25 Value: 21	Mine Type		
Antipersonnel Mine and Antitank Mine with Antihandling Device Symbol Set: 25 Value: 22	Mine Type		
Antipersonnel Mine and Wide Area Antitank Mine Symbol Set: 25 Value: 23	Mine Type		
Antipersonnel Mine and Mine Cluster Symbol Set: 25 Value: 24	Mine Type		
Antipersonnel Mine with Directional Effects and Antitank Mine Symbol Set: 25 Value: 25	Mine Type		


Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE L-XXV. Control measures sector 1 modifiers - Continued.

DESCRIPTION	CATEGORY	MODIFIER	REMARKS
Antipersonnel Mine with Directional Effects and Antitank Mine with Antihandling Device Symbol Set: 25 Value: 26	Mine Type		
Antipersonnel Mine with Directional Effects and Wide Area Antitank Mine Symbol Set: 25 Value: 27	Mine Type		
Antipersonnel Mine with Directional Effects and Mine Cluster Symbol Set: 25 Value: 28	Mine Type		
Antitank Mine and Antitank Mine with Antihandling Device Symbol Set: 25 Value: 29	Mine Type		
Antitank Mine and Wide Area Antitank Mine Symbol Set: 25 Value: 30	Mine Type		
Antitank Mine and Mine Cluster Symbol Set: 25 Value: 31	Mine Type		
Antitank Mine with Antihandling Device and Wide Area Antitank Mine Symbol Set: 25 Value: 32	Mine Type		
Antitank Mine with Antihandling Device and Mine Cluster Symbol Set: 25 Value: 33	Mine Type		
Wide Area Antitank Mine and Mine Cluster Symbol Set: 25 Value: 34	Mine Type		

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE L-XXV. Control measures sector 1 modifiers - Continued.

DESCRIPTION	CATEGORY	MODIFIER	REMARKS
Antipersonnel Mine, Antipersonnel Mine with Directional Effects, and Antitank Mine Symbol Set: 25 Value: 35	Mine Type		
Antipersonnel Mine, Antipersonnel Mine with Directional Effects, and Antitank Mine with Antihandling Device Symbol Set: 25 Value: 36	Mine Type		
Antipersonnel Mine, Antipersonnel Mine with Directional Effects, and Wide Area Antitank Mine Symbol Set: 25 Value: 37	Mine Type		
Antipersonnel Mine, Antipersonnel Mine with Directional Effects, and Mine Cluster Symbol Set: 25 Value: 38	Mine Type		
Antipersonnel Mine, Antitank Mine, and Antitank Mine with Antihandling Device Symbol Set: 25 Value: 39	Mine Type		
Antipersonnel Mine, Antitank Mine, and Wide Area Antitank Mine Symbol Set: 25 Value: 40	Mine Type		
Antipersonnel Mine, Antitank Mine, and Mine Cluster Symbol Set: 25 Value: 41	Mine Type		
Antipersonnel Mine, Antitank Mine with Antihandling Device, and Wide Area Antitank Mine Symbol Set: 25 Value: 42	Mine Type		

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE L-XXV. Control measures sector 1 modifiers - Continued.

DESCRIPTION	CATEGORY	MODIFIER	REMARKS
Antipersonnel Mine, Antitank Mine with Antihandling Device, and Mine Cluster Symbol Set: 25 Value: 43	Mine Type		
Antipersonnel Mine, Wide Area Antitank Mine, and Mine Cluster Symbol Set: 25 Value: 44	Mine Type		
Antipersonnel Mine with Directional Effects, Antitank Mine, and Antitank Mine with Antihandling Device Symbol Set: 25 Value: 45	Mine Type		
Antipersonnel Mine with Directional Effects, Antitank Mine, and Wide Area Antitank Mine Symbol Set: 25 Value: 46	Mine Type		
Antipersonnel Mine with Directional Effects, Antitank Mine, and Mine Cluster Symbol Set: 25 Value: 47	Mine Type		
Antipersonnel Mine with Directional Effects, Antitank Mine with Antihandling Device, and Wide Area Antitank Mine Symbol Set: 25 Value: 48	Mine Type		
Antipersonnel Mine with Directional Effects, Antitank Mine with Antihandling Device, and Mine Cluster Symbol Set: 25 Value: 49	Mine Type		
Antipersonnel Mine with Directional Effects, Wide Area Antitank Mine, and Mine Cluster Symbol Set: 25 Value: 50	Mine Type		

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

L.5.28 Abbreviations and acronyms for use with control measure symbols.

L.5.28.1 Boundary abbreviations and acronyms. Table L-XXVI provides a list of abbreviations and acronyms for echelons and functional organizations to be used with boundaries. The asterisk behind the abbreviation indicates that it is in NATOTerm.

TABLE L-XXVI. Abbreviations and acronyms for use with boundaries.

ECHELON	ABBREVIATION /ACRONYM	EXAMPLES Note: Any Unit identification can be followed by a 3-letter country code in parenthesis.
Army Group	AG*	1AG
Army	A*	3A
Corps	Does not require an abbreviation. Corps is the only echelon to use Roman numerals.	II
Marine Expeditionary Force	MEF*	III MEF (Use Roman numerals)
Marine Air-Ground Task Force	MAGTF*	4MAGTF
Division	DIV*	1DIV
Air Assault Division	AAD	101AAD
Airborne Division	ABD*	6ABD
Armored Division	AD*	2AD
Cavalry Division	CD	1CD
Infantry Division	ID*	52ID
Marine Division	MARD	1MARD
Mechanized Division	MD*	4MD
Mountain Division	MTND	10MTND
Multinational Division	MND*	1MND or MND(S).
Note: Multinational divisions may use geographical references in parenthesis		
Brigade	BDE*	2BDE
Air Assault Brigade	AAB*	8AAB
Airborne Brigade	ABB*	3ABB
Marine Expeditionary Brigade	MEB*	6MEB
Multinational Brigade	MNB*	2MNB
Naval Infantry Brigade	NIB*	4NIB
Regiment	REGT*	21REGT
Airborne Regiment	ABR*	901ABR
Marine Expeditionary Unit	MEU*	3MEU
Group	GP	41GP
Battle Group	BG*	5BG
Battalion	BN*	7BN
Company	COY*	ACOY or 2COY
Platoon	PLT	2PLT
Team	TM	BTM

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

L.5.28.2 Unit functions abbreviation and acronyms. Table L-XXVII provides a list of abbreviations and acronyms for unit functions to be used with control measures. The asterisk behind the abbreviation indicates that it is in NATOTerm.

TABLE L-XXVII. Abbreviation and acronyms used in control measure symbols for unit functions.

Function	Abbreviation /Acronyms
Air Defense Artillery	ADA*
Antitank/Antiarmor	AT*
Armor	AR*
Aviation	AVN*
Chemical Biological Radiological Nuclear (CBRN)	CB
Civil Affairs	CA*
Combined Arms	CAR
Counterintelligence	CI*
Electromagnetic Warfare	EW*
Engineer	EN
Explosive Ordnance Disposal	EOD*
Field Artillery	FA*
Infantry	IN
Logistics	LOG*
Maintenance	MNT
Medical	MED*
Military Intelligence	MI*
Military Police	MP*
Naval	NAV
Ordnance	ORD
Quartermaster	QM
Reconnaissance	REC
Signal	SIG
Special Forces	SF
Special Operations Force	SOF
Surveillance	SUR
Sustainment	SUST
Transportation	TPT

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

PAGE INTENTIONALLY LEFT BLANK

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

METEOROLOGICAL AND OCEANOGRAPHIC SYMBOLOGY

M.1 SCOPE

M.1.1 Scope. This appendix addresses control measure symbols in the meteorological and oceanographic (METOC) symbol sets. Although the symbology in this domain is outside the configuration management of the Symbology Standards Management Committee (SSMC), it is beneficial to present the information to users of this standard as a separate appendix. This appendix has been coordinated and approved by the joint METOC community and is a mandatory part of this standard. The information contained herein is intended for compliance.




FIGURE M-1. Meteorological and oceanographic appendix sections.

M.2 APPLICABLE DOCUMENTS

Specific documents in 2.2 of this standard apply to this appendix.

M.3 DEFINITIONS

The definitions in section 3 of this standard apply to this appendix.

M.4 GENERAL REQUIREMENTS

M.4.1 Organization. This appendix contains technical specifications, a symbol coding scheme, a symbology hierarchy and METOC symbology.

M.5 DETAILED REQUIREMENTS

M.5.1 Technical specifications. Composition, construction and display of symbols are explained in the detailed requirements section of the standard.

M.5.2 Symbology identification coding scheme. A symbol identification code (SIDC) is a numeric string that may be used to provide the unique identifier necessary to display or exchange symbol information between MIL-STD-2525 compliant systems. Refer to Appendix A for SIDC positions and descriptions.

M.5.3 Symbology set. The following graphics are some of those more commonly used to depict weather and should only be used on weather-related displays. These graphics must be implemented as a separate layer or classification since they may conflict with other symbols or icons used in the warrior icon set. These graphics are based on approved symbols and icons from the World Meteorological Organization (WMO). For dynamic displays, if the system has the

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

capability to rotate the map display in the direction of movement, a single point symbol may optionally be rotated on its anchor point for upright orientation. For a single point symbol, unless otherwise stated in the symbol's template, the symbol's anchor shall be the center of the symbol operator-centered over the desired location.

TABLE M-I. Standard Draw Rules.

Draw Rule Type	Draw Rule
Area1	**Anchor Points:** This graphic requires at least three anchor points to define the boundary of the area. Add as many points as necessary to accurately reflect the area's size and shape. **Size/Shape:** Scalable.
Area2	**Anchor Points:** This graphic requires at least three anchor points to define the boundary of the area. Add as many points as necessary to accurately reflect the area's size and shape. **Size/Shape:** Determined by the anchor points. The operator may depict the area color filled with no outer boundary line and include a legend to simplify depiction.
Point1	**Anchor Points:** This graphic requires one anchor point. The center point defines the center of the graphic. **Size/Shape:** Scalable.
Point2	**Anchor Points:** This graphic requires one anchor point. The center point defines the geometric center of the graphic. **Size/Shape:** Scalable.
Point3	**Anchor Points:** This graphic requires one anchor point. The center point defines the center of the graphic. **Size/Shape:** Scalable.
Point4	**Anchor Points:** This graphic requires one anchor point. The center point defines the center of the graphic. **Size/Shape:** Scalable.
Point5	**Anchor Points:** This graphic requires a minimum of two anchor points. The first point defines the location of the plot circle. Additional points define the wind shaft and the speed of the wind. Wind speed is depicted on the shaft using a combination of the shaft alone (1-2 knots), half barbs (5 knots), barbs (10 knots) and pennants (50 knots). Wind speeds 5 knots or greater are rounded to the nearest 5 knots. Missing wind speed is depicted by an "X" at the end of the wind shaft. Winds with missing direction are not displayed. **Size/Shape:** Not applicable. **Orientation:** The shaft of the graphic is oriented with reference to true north in the direction from which the wind is blowing to the nearest 10 degrees. The barbs and pennants lie back from the shaft at an angle of 120 degrees and are oriented to the left of the shaft in the Northern Hemisphere and to the right in the Southern Hemisphere. The graphic is operator-centered over the desired location.
Point6	**Anchor Points:** This graphic requires one anchor point. The center point defines the center of the graphic. **Size/Shape:** Scalable.
Point7	**Anchor Points:** This graphic requires one anchor point. The center point defines the center of the graphic. **Size/Shape:** Scalable.
Point8	**Anchor Points:** This graphic requires one anchor point. The center point defines the center of the graphic. **Size/Shape:** Scalable.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE M-I. Standard Draw Rules - Continued.

Draw Rule Type	Draw Rule
Line1	**Anchor Points:** This graphic requires at least two anchor points, points 1 and 2, to define the line. Additional points can be defined to extend the line. **Size/Shape:** Scalable/Curve. The curvature of the line is operator defined.
Line2	**Anchor Points:** This graphic requires at least two anchor points, points 1 and 2, to define the line. Additional points can be defined to extend the line. **Size/Shape:** Scalable/Curve. The points are typically connected with a straight line consisting of a short line section and an alternating V shape. The curvature and amplitude of the waves of the line are operator defined.
Line3	**Anchor Points:** This graphic requires at least two anchor points, points 1 and 2, to define the line. Additional points can be defined to extend the line. **Size/Shape:** Scalable/Curve. The points are typically connected with a straight line consisting of a short line section and alternating two dots. The curvature and amplitude of the waves of the line are operator defined.
Line4	**Anchor Points:** This graphic requires at least two anchor points, points 1 and 2, to define the line. Additional points can be defined to extend the line. **Size/Shape:** Scalable/Curve. The points are typically connected with a curved/wavy line consisting of a short line and one dot. The curvature and amplitude of the waves of the line are operator defined.
Line5	**Anchor Points:** This graphic requires at least three anchor points to define the boundary of the area. Add as many points as necessary to accurately reflect the area's size and shape. **Size/Shape:** Determined by the anchor points. The dual line segments will be parallel to slightly wider at the western end.
Line6	**Anchor Points:** This graphic requires at least two anchor points, points 1 and 2, to define the line. Additional points can be defined to extend the line. **Size/Shape:** Scalable/Curve. The points are typically connected with a solid straight line with alternating slanted lines connected as depicted in the example to indicate convergence.
Line7	**Anchor Points:** This graphic requires at least two anchor points, points 1 and 2, to define the line. Additional points can be defined to extend the line. **Size/Shape:** Scalable/Curve. The points are typically connected with a dashed straight or curved line. The curvature of the line is operator defined. The red and green line segments will alternate along the line.
Line8	**Anchor Points:** This graphic requires at least two anchor points, points 1 and 2, to define the line. Additional points can be defined to extend the line. **Size/Shape:** Scalable.

TABLE M-II. Atmospheric icons.

DESCRIPTION	ICON	NOTES
PRESSURE SYSTEMS Static/Dynamic: N/A Symbol Set: 45 Value: **11**0000	N/A	N/A

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE M-II. Atmospheric icons - Continued.

DESCRIPTION	ICON	NOTES
Pressure Systems **Low Pressure Center** Static/Dynamic: D Symbol Set: 45 Value: 11**01**00 **Color**: Red (RGB 255,0,0) Draw Rules: Point1 - Static		The graphic is a letter 'L' with a dynamic tag 'P' below it that represents the lowest atmospheric pressure of the system. The value is three or 4 digits and represents the pressure in hectopascals (millibars). The value below, 998, represents 998 hectopascals. A value above 1000 hectopascals would be reflected in 4 digits like 1008 hectopascals.
Pressure Systems Low Pressure Center **Cyclone Center** Static/Dynamic: S Symbol Set: 45 Value: 1101**01** **Color**: Red (RGB 255,0,0) Draw Rules: Point1 - Static		The graphic is a letter 'C' that represents the atmospheric circulation center of the system.
Pressure Systems Low Pressure Center **Tropopause Low** Static/Dynamic: D Symbol Set: 45 Value: 1101**02** **Color**: Black Draw Rules: Point1 - Static		The center of the graphic is the pressure center. The low point of the Tropopause topography is indicated by the letter 'L' and the height (H in 3 digits) above mean sea level in hundreds of feet (or meters) is included within the graphic
Pressure Systems **High Pressure Center** Static/Dynamic: D Symbol Set: 45 Value: 11**02**00 **Color**: Blue (RGB 0,0,255) Draw Rules: Point1 - Static		The graphic is a letter 'H' with a dynamic tag 'P' below it that represents the highest atmospheric pressure of the system. The value is three or four digits and represents the pressure in hectopascals (millibars). The value below, 1016, represents 1016 hectopascals. A value below 1000 hectopascals would be reflected in three digits like 998 hectopascals.


Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE M-II. Atmospheric icons - Continued.

DESCRIPTION	ICON	NOTES
Pressure Systems High Pressure Center **Anticyclone Center** Static/Dynamic: S Symbol Set: 45 Value: 110**01** **Color**: Blue (RGB 0,0,255) Draw Rules: Point1 - Static		The graphic is a letter 'A' that represents the atmospheric circulation center of the system. .
Pressure Systems High Pressure Center **Tropopause High** Static/Dynamic: D Symbol Set: 45 Value: 110**02** **Color**: Black Draw Rules: Point1 - Static		The center of the graphic is the pressure center. The high point of the Tropopause topography is indicated by the letter 'H' and the height (X in 3 digits) above mean sea level in hundreds of feet (or meters) is included within the graphic.
Pressure Systems **Frontal Systems** Symbol Set: 45 Value: 11**03**00	N/A	For special lines that are not symmetrical, such as Fronts, the sequence of anchor points determines the proper alignment of the line. For two anchor points that describe the position of the front or a section of the front, with L (for left point) and R (for right point): (1) If R comes before L in sequence, the front is rendered in the way shown, (2) If L comes before R in sequence, the front is rendered in the reverse with pips shown facing the opposite direction.).
Pressure Systems Frontal Systems **Cold Front** Symbol Set: 45 Value: 1103**01** **Color**: Blue (RGB 0,0,255) Draw Rules: Line1 - Dynamic		The points are typically connected with a curved line with solid, triangular pips spaced evenly along the line. The line should be drawn from the pressure center to the extent of the front. The pips will be evenly spaced along the line and point in the direction the front is moving.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE M-II. Atmospheric icons - Continued.

DESCRIPTION	ICON	NOTES
Pressure Systems Frontal Systems Cold Front **Upper Cold Front** Symbol Set: 45 Value: 110302 **Color**: Blue (RGB 0,0,255) Draw Rules: Line1 - Dynamic		The points are typically connected with a curved line with hollow, triangular pips spaced evenly along the line. The line should be drawn from the pressure center to the extent of the front. The pips will be evenly spaced along the line and point in the direction the front is moving.
Pressure Systems Frontal Systems Cold Front **Cold Frontogenesis** Symbol Set: 45 Value: 110303 **Color**: Blue (RGB 0,0,255) Draw Rules: Line1 - Dynamic		The points are typically connected with a curved line with solid, triangular pips spaced evenly along the line separated by one dot. The line should be drawn from the pressure center to the extent of the front. The pips will be evenly spaced along the line and point in the direction the front is moving.
Pressure Systems Frontal Systems Cold Front **Cold Frontolysis** Symbol Set: 45 Value: 110304 **Color**: Blue (RGB 0,0,255) Draw Rules: Line1 - Dynamic		The points are typically connected with a curved line with solid, triangular pips spaced evenly along the line separated by a crossed line. The line should be drawn from the pressure center to the extent of the front. The pips will be evenly spaced along the line and point in the direction the front is moving.
Pressure Systems Frontal Systems **Warm Front** Symbol Set: 45 Value: 110305 **Color**: Red (RGB 255,0,0) Draw Rules: Line1 - Dynamic		The points are typically connected with a curved line with solid, half-circle pips spaced evenly along the line. The line should be drawn from the pressure center to the extent of the front. The pips will be evenly spaced along the line and point in the direction the front is moving.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE M-II. Atmospheric icons - Continued.

DESCRIPTION	ICON	NOTES
Pressure Systems Frontal Systems Warm Front **Upper Warm Front** Symbol Set: 45 Value: 110**306** **Color**: Red (RGB 255,0,0) Draw Rules: Line1 - Dynamic		The points are typically connected with a curved line with hollow, half-circle pips spaced evenly along the line. The line should be drawn from the pressure center to the extent of the front. The pips will be evenly spaced along the line and point in the direction the front is moving.
Pressure Systems Frontal Systems Warm Front **Warm Frontogenesis** Symbol Set: 45 Value: 110**307** **Color**: Red (RGB 255,0,0) Draw Rules: Line1 - Dynamic		The points are typically connected with a curved line with solid, half-circle pips spaced evenly along the line separated by one dot. The line should be drawn from the pressure center to the extent of the front. The pips will be evenly spaced along the line and point in the direction the front is moving.
Pressure Systems Frontal Systems Warm Front **Warm Frontolysis** Symbol Set: 45 Value: 110**308** **Color**: Red (RGB 255,0,0) Draw Rules: Line1 - Dynamic		The points are typically connected with a curved line with solid, half-circle pips spaced evenly along the line separated by a crossed line. The line should be drawn from the pressure center to the extent of the front. The pips will be evenly spaced along the line and point in the direction the front is moving.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE M-II. Atmospheric icons - Continued.

DESCRIPTION	ICON	NOTES
Pressure Systems Frontal Systems **Occluded Front** Symbol Set: 45 Value: 110309 **Color**: Purple (RGB 111,49,152) Draw Rules: Line1 - Dynamic		The points are typically connected with a curved line with alternating solid, triangular and half-circle pips spaced evenly along the line. The line should be drawn from the pressure center to the extent of the front. The pips will be evenly spaced along the line and point in the direction the front is moving. An occluded front is where a cold front has overtaken a warm front and is the discontinuity between colder air and cooler air and the colder air forces the cooler air aloft.
Pressure Systems Frontal Systems Occluded Front **Upper Occluded Front** Symbol Set: 45 Value: 110310 **Color**: Purple (RGB 111,49,152) Draw Rules: Line1 - Dynamic		The points are typically connected with a curved line with alternating hollow, triangular and half-circle pips spaced evenly along the line. The line should be drawn from the pressure center to the extent of the front. The pips will be evenly spaced along the line and point in the direction the front is moving.
Pressure Systems Frontal Systems Occluded Front **Occluded Frontolysis** Symbol Set: 45 Value: 110311 **Color**: Purple (RGB 111,49,152) Draw Rules: Line1 - Dynamic		The points are typically connected with a curved line with alternating solid, triangular and half-circle pips spaced evenly along the line separated by a crossed line. The line should be drawn from the pressure center to the extent of the front. The pips will be evenly spaced along the line and point in the direction the front is moving.


Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE M-II. Atmospheric icons - Continued.

DESCRIPTION	ICON	NOTES
Pressure Systems Frontal Systems **Stationary Front** Symbol Set: 45 Value: 110312 **Color**: Alternate Red (RGB 255,0,0) & Blue (RGB 0,0,255) Draw Rules: Line1 - Dynamic		The points are typically connected with a curved line with solid, triangular and half-circle pips spaced evenly on alternating sides of the line. The line should be drawn from the pressure center to the extent of the front. The pips will be evenly spaced along the line and point in the direction the front is moving. Since the front is not moving, pips alternate with warm (red) pointing one direction (normally to left or up) and the cold (blue) pointing the other (normally right or down).
Pressure Systems Frontal Systems Stationary Front **Upper Stationary Front** Symbol Set: 45 Value: 110313 **Color**: Alternate Red (RGB 255,0,0) & Blue (RGB 0,0,255) Draw Rules: Line1 - Dynamic		The points are typically connected with a curved line with hollow, triangular and half-circle pips spaced evenly on alternating sides of the line. The line should be drawn from the pressure center to the extent of the front. The pips will be evenly spaced along the line and point in the direction the front is moving. Since the front is not moving, pips alternate with warm (red) pointing one direction (normally to left or up) and the cold (blue) pointing the other (normally right or down).
Pressure Systems Frontal Systems Stationary Front **Stationary Frontogenesis** Symbol Set: 45 Value: 110314 **Color**: Alternate Red (RGB 255,0,0) & Blue (RGB 0,0,255) Draw Rules: Line1 - Dynamic		The points are typically connected with a curved line with solid, triangular and half-circle pips spaced evenly on alternating sides of the line separated by one dot. The line should be drawn from the pressure center to the extent of the front. The pips will be evenly spaced along the line and point in the direction the front is moving. Since the front is not moving, pips alternate with warm (red) pointing one direction (normally to left or up) and the cold (blue) pointing the other (normally right or down).

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE M-II. Atmospheric icons - Continued.

DESCRIPTION	ICON	NOTES
Pressure Systems Frontal Systems Stationary Front **Stationary Frontolysis** Symbol Set: 45 Value: 1103**15** **Color**: Alternate Red (RGB 255,0,0) & Blue (RGB 0,0,255) Draw Rules: Line1 - Dynamic		The points are typically connected with a curved line with solid, triangular and half-circle pips spaced evenly on alternating sides of the line separated by a crossed line. The line should be drawn from the pressure center to the extent of the front. The pips will be evenly spaced along the line and point in the direction the front is moving. Since the front is not moving, pips alternate with warm (red) pointing one direction (normally to left or up) and the cold (blue) pointing the other (normally right or down)..
Pressure Systems **Lines** Static/Dynamic: N/A Symbol Set: 45 Value: 11**04**00	N/A	
Pressure Systems Lines **Trough Axis** Symbol Set: 45 Value: 1104**01** **Color**: Black Draw Rules: Line1 - Dynamic		This is a surface feature.
Pressure Systems Lines **Trough** Symbol Set: 45 Value: 1104**02** **Color**: Black Draw Rules: Line1 - Dynamic		The points are typically connected with a curved line and should be drawn along the trough axis.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE M-II. Atmospheric icons - Continued.

DESCRIPTION	ICON	NOTES
Pressure Systems Lines **Ridge Axis** Symbol Set: 45 Value: 110**403** **Color**: Black Draw Rules: Line1 - Dynamic		The points are typically connected with a solid zigzag line. The line should be drawn along the ridge axis. The zigzag of the line will be placed at regular intervals along the entire length of the line.
Pressure Systems Lines **Severe Squall Line** Symbol Set: 45 Value: 110**404** **Color**: Black Draw Rules: Line2 - Dynamic		This line type is rarely seen, but may appear in products from the Canadian meteorological service (Meteorological Services of Canada). The term “severe squall line” is generally implied by “squall line”
	Orientation: The line should be drawn so the "V" shapes are facing in the direction of movement. The "V" shapes and short line segment will alternate along the line.	
Pressure Systems Lines **Instability Line** Symbol Set: 45 Value: 110**405** **Color**: Black Draw Rules: Line3 - Dynamic		
Pressure Systems Lines **Shear Line** Symbol Set: 45 Value: 110**406** **Color**: Black Draw Rules: Line4 - Dynamic		A shear line is normally the convergent easterly winds where a cold front has intruded into a tropical region.




Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE M-II. Atmospheric icons - Continued.

DESCRIPTION	ICON	NOTES
Pressure Systems Lines **Inter-Tropical Convergence Zone** Symbol Set: 45 Value: 110**07** **Color**: Orange (RGB 255,128,0) Draw Rules: Line5 - Dynamic		The operator should place the modifier(s) to indicate areas of weather activity within the graphic. The Inter-Tropical Convergence Zone (ITCZ) is a region where the northeasterly and southeasterly trade winds converge.
Pressure Systems Lines **Convergence Line** Symbol Set: 45 Value: 110**08** **Color**: Orange (RGB 255,128,0) Draw Rules: Line6 - Dynamic		
Pressure Systems Lines **Inter-Tropical Discontinuity** Symbol Set: 45 Value: 110**09** **Color**: Alternate Red (RGB 255,0,0) and Green (RGB 13,223,39) Draw Rules: Line7 - Dynamic		
Pressure Systems **Pressure Tendency** Static/Dynamic: D Symbol Set: 45 Value: 11**05**00 **Note:** Each symbol within the pressure tendency group is static, but only one can be applied to a particular station plot, dependent upon the pressure tendency at that location. As such, the group of symbols is dynamic.	N/A	N/A
	Pressure tendency symbols are depicted to the right of the plot circle just after the text value for the actual pressure change. Pressure tendency is displayed in two digits in black immediately to right of the plot circle followed by the pressure tendency symbol. **Orientation:** The graphic is centered over the anchor location.	

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE M-II. Atmospheric icons - Continued.

DESCRIPTION	ICON	NOTES
Pressure Systems Pressure Tendency **Rise Then Fall Higher** Symbol Set: 45 Value: 110**501** **Color**: Black/Blue (RGB 0,0,255) Draw Rules: Point2 - Static		
Pressure Systems Pressure Tendency **Rise Then Steady** Symbol Set: 45 Value: 110**502** **Color**: Black/Blue (RGB 0,0,255) Draw Rules: Point2 - Static		
Pressure Systems Pressure Tendency **Rise** Symbol Set: 45 Value: 110**503** **Color**: Black/Blue (RGB 0,0,255) Draw Rules: Point2 - Static		
Pressure Systems Pressure Tendency **Rise Then Rise Higher** Symbol Set: 45 Value: 110**504** **Color**: Black/Blue (RGB 0,0,255) Draw Rules: Point2 - Static		


Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE M-II. Atmospheric icons - Continued.

DESCRIPTION	ICON	NOTES
Pressure Systems Pressure Tendency **Steady** Symbol Set: 45 Value: 110**05** **Color**: Black Draw Rules: Point2 - Static		
Pressure Systems Pressure Tendency **Fall Then Rise Lower** Symbol Set: 45 Value: 110**06** **Color**: Black/Red (RGB 255,0,0) Draw Rules: Point2 - Static		
Pressure Systems Pressure Tendency **Fall Then Steady** Symbol Set: 45 Value: 110**07** **Color**: Black/Red (RGB 255,0,0) Draw Rules: Point2 - Static		
Pressure Systems Pressure Tendency **Fall** Symbol Set: 45 Value: 110**08** **Color**: Black/Red (RGB 255,0,0) Draw Rules: Point2 - Static		


Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE M-II. Atmospheric icons - Continued.

DESCRIPTION	ICON	NOTES
Pressure Systems Pressure Tendency **Rise Then Fall Lower** Symbol Set: 45 Value: 110**09** **Color**: Black/Red (RGB 255,0,0) Draw Rules: Point2 - Static		
Turbulence Static/Dynamic: N/A Symbol Set: 45 Value: **12**0000	N/A	**Note**: USAF turbulence forecasts are based on Category II type aircraft.
Turbulence **Light** Static/Dynamic: D Symbol Set: 45 Value: 12**01**00 **Color**: Blue (RGB 0,0,255) Draw Rules: Point3 - Static		**Note:** Intensity is dependent upon the associated aircraft type. The turbulence is indicated by the graphic and the height (X in 3 digits) above mean sea level in hundreds of feet (or meters) is included within the graphic.
Turbulence **Moderate** Symbol Set: 45 Value: 12**02**00 **Color**: Blue (RGB 0,0,255) Draw Rules: Point3 - Static		Intensity is dependent upon the associated aircraft type. The turbulence is indicated by the graphic and the height (X in 3 digits) above mean sea level in hundreds of feet (or meters) is included within the graphic.
Turbulence **Severe** Symbol Set: 45 Value: 12**03**00 **Color**: Blue (RGB 0,0,255) Draw Rules: Point3 - Static		Intensity is dependent upon the associated aircraft type. The turbulence is indicated by the graphic and the height (X in 3 digits) above mean sea level in hundreds of feet (or meters) is included within the graphic.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE M-II. Atmospheric icons - Continued.

DESCRIPTION	ICON	NOTES
Turbulence **Extreme** Symbol Set: 45 **Value:** 12**04**00 Color: Blue (RGB 0,0,255) Draw Rules: Point3 - Static		Intensity is dependent upon the associated aircraft type. The turbulence is indicated by the graphic and the height (X in 3 digits) above mean sea level in hundreds of feet (or meters) is included within the graphic.
Turbulence **Mountain Waves** Symbol Set: 45 Value: 12**05**00 **Color**: Blue (RGB 0,0,255) Draw Rules: Point3 - Static		The turbulence is indicated by the graphic and the height (X in 3 digits) above mean sea level in hundreds of feet (or meters) is included within the graphic.
Icing Symbol Set: 45 Value: **13**0000	N/A	N/A
Icing **Clear Icing** Symbol Set: 45 Value: 13**01**00	N/A	N/A
Icing Clear Icing **Light** Symbol Set: 45 Value: 1301**01** **Color**: Brown (RGB 124,96,13) Draw Rules: Point3 - Static		The icing is indicated by the graphic and the height (X in 3 digits) above mean sea level in hundreds of feet (or meters) is included within the graphic.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE M-II. Atmospheric icons - Continued.

DESCRIPTION	ICON	NOTES
Icing Clear Icing **Moderate** Symbol Set: 45 Value: 1301**02** **Color**: Brown (RGB 124,96,13) Draw Rules: Point3 - Static		The icing is indicated by the graphic and the height (X in 3 digits) above mean sea level in hundreds of feet (or meters) is included within the graphic.
Icing Clear Icing **Severe** Symbol Set: 45 Value: 1301**03** **Color**: Brown (RGB 124,96,13) Draw Rules: Point3 - Static		The icing is indicated by the graphic and the height (X in 3 digits) above mean sea level in hundreds of feet (or meters) is included within the graphic.
Icing **Rime Icing** Symbol Set: 45 Value: 13**02**00	N/A	N/A
Icing Rime Icing **Light** Symbol Set: 45 Value: 1302**01** **Color**: Brown (RGB 124,96,13) Draw Rules: Point3 - Static		The icing is indicated by the graphic and the height (X in 3 digits) above mean sea level in hundreds of feet (or meters) is included within the graphic.
Icing Rime Icing **Moderate** Symbol Set: 45 Value: 1302**02** **Color**: Brown (RGB 124,96,13) Draw Rules: Point3 - Static		The icing is indicated by the graphic and the height (X in 3 digits) above mean sea level in hundreds of feet (or meters) is included within the graphic.




Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE M-II. Atmospheric icons - Continued.

DESCRIPTION	ICON	NOTES
Icing Rime Icing **Severe** Symbol Set: 45 Value: 1302**03** **Color**: Brown (RGB 124,96,13) Draw Rules: Point3 - Static		The icing is indicated by the graphic and the height (X in 3 digits) above mean sea level in hundreds of feet (or meters) is included within the graphic.
Icing **Mixed Icing** Symbol Set: 45 Value: 13**03**00	N/A	
Icing Mixed Icing **Light** Symbol Set: 45 Value: 1303**01** **Color**: Brown (RGB 124,96,13) Draw Rules: Point3 - Static		The icing is indicated by the graphic and the height (X in 3 digits) above mean sea level in hundreds of feet (or meters) is included within the graphic.
Icing Mixed Icing **Moderate** Symbol Set: 45 Value: 1303**02** **Color**: Brown (RGB 124,96,13) Draw Rules: Point3 - Static		The icing is indicated by the graphic and the height (X in 3 digits) above mean sea level in hundreds of feet (or meters) is included within the graphic.
Icing Mixed Icing **Severe** Symbol Set: 45 Value: 1303**03** **Color**: Brown (RGB 124,96,13) Draw Rules: Point3 - Static		The icing is indicated by the graphic and the height (X in 3 digits) above mean sea level in hundreds of feet (or meters) is included within the graphic.


Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE M-II. Atmospheric icons - Continued.

DESCRIPTION	ICON	NOTES
Winds Symbol Set: 45 Value: **14**0000	N/A	
Winds **Calm Winds** Symbol Set: 45 Value: 14**01**00 **Color**: Black Draw Rules: Point4 - Static		
Winds **Wind Plot** Symbol Set: 45 Value: 14**02**00 **Color**: Black Draw Rules: Point5 - Static	Example 1 	Cloud coverage is typically depicted in the plot circle in accordance with cloud coverage graphics. The wind speed, direction and cloud coverage depicted in wind plot graphics are examples only. Example 1: From 270 degrees at 1-2 knots Example 2: From 270 degrees at 5 knots Example 3: From 250 degrees at 10 knots Example 4: From 110 degrees at 25 knots Example 5: From 250 degrees at 50 knots Example 6: From 270 degrees with missing wind speed
	Example 2 	
	Example 3 	
	Example 4 	
	Example 5 	
	Example 6 	




Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE M-II. Atmospheric icons - Continued.

DESCRIPTION	ICON	NOTES
Winds **Jet Stream** Symbol Set: 45 Value: 14**03**00 **Color**: Red or Black Draw Rules: Line1 - Dynamic		The arrowheads will be evenly spaced along the line.
Winds **Stream Line** Symbol Set: 45 Value: 14**04**00 **Color**: Operator Defined Draw Rules: Line1 - Dynamic		The arrowheads will be evenly spaced along the line.
Cloud Coverage Symbol Set: 45 Value: **15**0000	N/A	N/A
Cloud Coverage **Cloud Coverage Symbols** Symbol Set: 45 Value: 15**01**00	N/A	N/A
Cloud Coverage Cloud Coverage Symbols **Clear Sky** Symbol Set: 45 Value: 1501**01** **Color**: Black Draw Rules: Point6 - Static		


Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE M-II. Atmospheric icons - Continued.

DESCRIPTION	ICON	NOTES
Cloud Coverage Cloud Coverage Symbols **Few Coverage** Symbol Set: 45 Value: 150102 **Color**: Black Draw Rules: Point6 - Static		
Cloud Coverage Cloud Coverage Symbols **Scattered Coverage** Symbol Set: 45 Value: 150103 **Color**: Black Draw Rules: Point6 - Static		
Cloud Coverage Cloud Coverage Symbols **Broken Coverage** Symbol Set: 45 Value: 150104 **Color**: Black Draw Rules: Point6 - Static		
Cloud Coverage Cloud Coverage Symbols **Overcast Coverage** Symbol Set: 45 Value: 150105 **Color**: Black Draw Rules: Point6 - Static		


Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE M-II. Atmospheric icons - Continued.

DESCRIPTION	ICON	NOTES
Cloud Coverage Cloud Coverage Symbols **Sky Totally or Partially Obscured** Symbol Set: 45 Value: 1501**06** **Color**: Black Draw Rules: Point6 - Static		
Weather Symbols Symbol Set: 45 Value: **16**0000	N/A	
Weather Symbols **Rain** Symbol Set: 45 Value: 16**01**00	N/A	
Weather Symbols Rain **Intermittent Light** Symbol Set: 45 Value: 160**101** **Color**: Green Draw Rules: Point7 - Static		
Weather Symbols Rain Intermittent Light **Continuous Light** Symbol Set: 45 Value: 160**102** **Color**: Green Draw Rules: Point7 - Static		

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE M-II. Atmospheric icons - Continued.

DESCRIPTION	ICON	NOTES
Weather Symbols Rain **Intermittent Moderate** Symbol Set: 45 Value: 160103 **Color**: Green Draw Rules: Point7 - Static		
Weather Symbols Rain **Intermittent Moderate/Continuous Moderate** Symbol Set: 45 Value: 160104 **Color**: Green Draw Rules: Point7 - Static		
Weather Symbols Rain **Intermittent Heavy** Symbol Set: 45 Value: 160105 **Color**: Green Draw Rules: Point7 - Static		
Weather Symbols Rain **Intermittent Heavy/Continuous Heavy** Symbol Set: 45 Value: 160106 **Color**: Green Draw Rules: Point7 - Static		

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE M-II. Atmospheric icons - Continued.

DESCRIPTION	ICON	NOTES
Weather Symbols **Freezing Rain** Symbol Set: 45 Value: 16**02**00	N/A	
Weather Symbols Freezing Rain **Light** Symbol Set: 45 Value: 1602**01** **Color**: Red Draw Rules: Point7 - Static		
Weather Symbols Freezing Rain **Moderate/Heavy** Symbol Set: 45 Value: 1602**02** **Color**: Red Draw Rules: Point7 - Static		
Weather Symbols **Rain Showers** Symbol Set: 45 Value: 16**03**00	N/A	
Weather Symbols Rain Showers **Light** Symbol Set: 45 Value: 1603**01** **Color**: Green Draw Rules: Point7 - Static		

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE M-II. Atmospheric icons - Continued.

DESCRIPTION	ICON	NOTES
Weather Symbols Rain Showers **Moderate/Heavy** Symbol Set: 45 Value: 160**302** **Color**: Green Draw Rules: Point7 - Static		
Weather Symbols Rain Showers **Torrential** Symbol Set: 45 Value: 160**303** **Color**: Green Draw Rules: Point7 - Static		
Weather Symbols **Drizzle** Symbol Set: 45 Value: 16**04**00	N/A	
Weather Symbols Drizzle **Intermittent Light** Symbol Set: 45 Value: 1604**01** **Color**: Green Draw Rules: Point7 - Static		
Weather Symbols Drizzle **Intermittent Light/Continuous Light** Symbol Set: 45 Value: 1604**02** **Color**: Green Draw Rules: Point7 - Static		

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE M-II. Atmospheric icons - Continued.

DESCRIPTION	ICON	NOTES
Weather Symbols Drizzle **Intermittent Moderate** Symbol Set: 45 Value: 160**403** **Color**: Green Draw Rules: Point7 - Static		
Weather Symbols Drizzle **Intermittent Moderate/Continuous Moderate** Symbol Set: 45 Value: 160**404** **Color**: Green Draw Rules: Point7 - Static		
Weather Symbols Drizzle **Intermittent Heavy** Symbol Set: 45 Value: 160**405** **Color**: Green Draw Rules: Point7 - Static		
Weather Symbols Drizzle **Intermittent Heavy/Continuous Heavy** Symbol Set: 45 Value: 160**406** **Color**: Green Draw Rules: Point7 - Static		

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE M-II. Atmospheric icons - Continued.

DESCRIPTION	ICON	NOTES
Weather Symbols **Freezing Drizzle** Symbol Set: 45 Value: 16**05**00	N/A	N/A
Weather Symbols Freezing Drizzle **Light** Symbol Set: 45 Value: 1605**01** **Color**: Red Draw Rules: Point7 - Static		
Weather Symbols Freezing Drizzle **Moderate/Heavy** Symbol Set: 45 Value: 1605**02** **Color**: Red Draw Rules: Point7 - Static		
Weather Symbols **Rain and Snow Mixed** Symbol Set: 45 Value: 16**06**00	N/A	
Weather Symbols Rain and Snow Mixed **Rain or Drizzle and Snow – Light** Symbol Set: 45 Value: 1606**01** **Color**: Green Draw Rules: Point7 - Static		


Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE M-II. Atmospheric icons - Continued.

DESCRIPTION	ICON	NOTES
Weather Symbols Rain and Snow Mixed **Rain or Drizzle and Snow – Moderate/Heavy** Symbol Set: 45 Value: 160**602** **Color**: Green Draw Rules: Point7 - Static		
Weather Symbols Rain and Snow Mixed **Rain and Snow Showers - Light** Symbol Set: 45 Value: 160**603** **Color**: Green Draw Rules: Point7 - Static		
Weather Symbols Rain and Snow Mixed **Rain and Snow Showers - Moderate/Heavy** Symbol Set: 45 Value: 160**604** **Color**: Green Draw Rules: Point7 - Static		
Weather Symbols **Snow** Symbol Set: 45 Value: 16**0700**	N/A	


Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE M-II. Atmospheric icons - Continued.

DESCRIPTION	ICON	NOTES
Weather Symbols Snow **Intermittent Light** Symbol Set: 45 Value: 160701 **Color**: Green Draw Rules: Point7 - Static		
Weather Symbols Snow **Intermittent Light/Continuous Light** Symbol Set: 45 Value: 160702 **Color**: Green Draw Rules: Point7 - Static		
Weather Symbols Snow **Intermittent Moderate** Symbol Set: 45 Value: 160703 **Color**: Green Draw Rules: Point7 - Static		
Weather Symbols Snow **Intermittent Moderate/Continuous Moderate** Symbol Set: 45 Value: 160704 **Color**: Green Draw Rules: Point7 - Static		

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE M-II. Atmospheric icons - Continued.

DESCRIPTION	ICON	NOTES
Weather Symbols Snow **Intermittent Heavy** Symbol Set: 45 Value: 160705 **Color**: Green Draw Rules: Point7 - Static		
Weather Symbols Snow **Intermittent Heavy/Continuous Heavy** Symbol Set: 45 Value: 160706 **Color**: Green Draw Rules: Point7 - Static		
Weather Symbols Snow **Blowing Snow - Light/Moderate** Symbol Set: 45 Value: 160707 **Color**: Green Draw Rules: Point7 - Static		
Weather Symbols Snow **Blowing Snow – Heavy** Symbol Set: 45 Value: 160708 **Color**: Green Draw Rules: Point7 - Static		

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE M-II. Atmospheric icons - Continued.

DESCRIPTION	ICON	NOTES
Weather Symbols **Snow Grains** Symbol Set: 45 Value: 16**08**00 **Color**: Green Draw Rules: Point7 - Static		
Weather Symbols **Snow Showers** Symbol Set: 45 Value: 16**09**00	N/A	N/A
Weather Symbols Snow Showers **Light** Symbol Set: 45 Value: 16090**1** **Color**: Green Draw Rules: Point7 - Static		
Weather Symbols Snow Showers **Moderate/Heavy** Symbol Set: 45 Value: 16090**2** **Color**: Green Draw Rules: Point7 - Static		
Weather Symbols **Hail** Symbol Set: 45 Value: 16**10**00	N/A	N/A


Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE M-II. Atmospheric icons - Continued.

DESCRIPTION	ICON	NOTES
Weather Symbols Hail **Light Not Associated with Thunder** Symbol Set: 45 Value: 161**01** **Color**: Red Draw Rules: Point7 - Static		
Weather Symbols Hail **Moderate/Heavy Not Associated with Thunder** Symbol Set: 45 Value: 161**02** **Color**: Red Draw Rules: Point7 - Static		
Weather Symbols **Ice Crystals (Diamond Dust)** Symbol Set: 45 Value: 16**11**00 **Color**: Red Draw Rules: Point7 - Static		
Weather Symbols **Ice Pellets (Sleet)** Symbol Set: 45 Value: 16**12**00	N/A	N/A
Weather Symbols Ice Pellets (Sleet) **Light** Symbol Set: 45 Value: 1612**01** **Color**: Red Draw Rules: Point7 - Static		

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE M-II. Atmospheric icons - Continued.

DESCRIPTION	ICON	NOTES
Weather Symbols Ice Pellets (Sleet) **Moderate** Symbol Set: 45 Value: 161**02** **Color**: Red Draw Rules: Point7 - Static		
Weather Symbols Ice Pellets (Sleet) **Heavy** Symbol Set: 45 Value: 161**03** **Color**: Red Draw Rules: Point7 - Static		
Weather Symbols **Inversion** Symbol Set: 45 Value: 16**13**00 **Color**: Black Draw Rules: Point7 - Static		
Weather Symbols **Storms** Symbol Set: 45 Value: 16**14**00	N/A	
Weather Symbols Storms **Thunderstorm - No Precipitation** Symbol Set: 45 Value: 1614**01** **Color**: Red Draw Rules: Point7 - Static		


Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE M-II. Atmospheric icons - Continued.

DESCRIPTION	ICON	NOTES
Weather Symbols Storms **Thunderstorm Light to Moderate with Rain/Snow - No Hail** Symbol Set: 45 Value: 161**402** **Color**: Red Draw Rules: Point7 - Static		
Weather Symbols Storms **Thunderstorm Heavy with Rain/Snow - No Hail** Symbol Set: 45 Value: 161**403** **Color**: Red Draw Rules: Point7 - Static		
Weather Symbols Storms **Thunderstorm Light to Moderate - with Hail** Symbol Set: 45 Value: 161**404** **Color**: Red Draw Rules: Point7 - Static		
Weather Symbols Storms **Thunderstorm Heavy - with Hail** Symbol Set: 45 Value: 161**405** **Color**: Red Draw Rules: Point7 - Static		

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE M-II. Atmospheric icons - Continued.

DESCRIPTION	ICON	NOTES
Weather Symbols Storms **Funnel Cloud (Tornado/Waterspout)** Symbol Set: 45 Value: 161**406** **Color**: Red Draw Rules: Point7 - Static		
Weather Symbols Storms **Squall** Symbol Set: 45 Value: 161**407** **Color**: Red Draw Rules: Point7 - Static		
Weather Symbols Storms **Lightning** Symbol Set: 45 Value: 161**408** **Color**: Red Draw Rules: Point7 - Static		
Weather Symbols **Fog** Symbol Set: 45 Value: 16**15**00	N/A	
Weather Symbols Fog **Shallow Patches** Symbol Set: 45 Value: 161**501** **Color**: Yellow Draw Rules: Point7 - Static		

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE M-II. Atmospheric icons - Continued.

DESCRIPTION	ICON	NOTES
Weather Symbols Fog **Shallow Continuous** Symbol Set: 45 Value: 161**02** **Color**: Yellow Draw Rules: Point7 - Static		
Weather Symbols Fog **Patchy** Symbol Set: 45 Value: 161**03** **Color**: Yellow Draw Rules: Point7 - Static		
Weather Symbols Fog **Sky Visible** Symbol Set: 45 Value: 161**04** **Color**: Yellow Draw Rules: Point7 - Static		
Weather Symbols Fog **Sky Obscured** Symbol Set: 45 Value: 161**05** **Color**: Yellow Draw Rules: Point7 - Static		

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE M-II. Atmospheric icons - Continued.

DESCRIPTION	ICON	NOTES
Weather Symbols Fog **Freezing, Sky Visible** Symbol Set: 45 Value: 161**506** **Color**: Red Draw Rules: Point7 - Static		
Weather Symbols Fog **Freezing, Sky Obscured** Symbol Set: 45 Value: 161**507** **Color**: Red Draw Rules: Point7 - Static		
Weather Symbols **Mist** Symbol Set: 45 Value: 16**16**00 **Color**: Yellow Draw Rules: Point7 - Static		
Weather Symbols **Smoke** Symbol Set: 45 Value: 16**17**00 **Color**: Brown Draw Rules: Point7 - Static		

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE M-II. Atmospheric icons - Continued.

DESCRIPTION	ICON	NOTES
Weather Symbols **Haze** Symbol Set: 45 Value: 16**18**00 **Color**: Brown Draw Rules: Point7 - Static		
Weather Symbols **Dust or Sand** Symbol Set: 45 Value: 16**19**00	N/A	
Weather Symbols Dust or Sand **Light to Moderate** Symbol Set: 45 Value: 1619**01** **Color**: Brown Draw Rules: Point7 - Static		
Weather Symbols Dust or Sand **Severe** Symbol Set: 45 Value: 1619**02** **Color**: Brown Draw Rules: Point7 - Static		
Weather Symbols Dust or Sand **Dust Devil** Symbol Set: 45 Value: 1619**03** **Color**: Brown Draw Rules: Point7 - Static		


Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE M-II. Atmospheric icons - Continued.

DESCRIPTION	ICON	NOTES
Weather Symbols Dust or Sand **Blowing Dust or Sand** Symbol Set: 45 Value: 161**04** **Color**: Brown Draw Rules: Point7 - Static		
Weather Symbols **Tropical Storm Systems** Symbol Set: 45 Value: 16**20**00	N/A	
Weather Symbols Tropical Storm Systems **Tropical Depression** Static/Dynamic: D Symbol Set: 45 Value: 1620**01** **Color**: Red, Purple or Black Draw Rules: Point8 - Static		*Red* or *Purple* - Current and Forecast Position *Black* - Past Position
Weather Symbols Tropical Storm Systems **Tropical Storm** Symbol Set: 45 Value: 1620**02** **Color**: Red, Purple or Black Draw Rules: Point8 - Static		*Red* or *Purple* - Current and Forecast Position *Black* - Past Position
Weather Symbols Tropical Storm Systems **Hurricane/Typhoon** Symbol Set: 45 Value: 1620**03** **Color**: Red, Purple or Black Draw Rules: Point8 - Static		*Red* or *Purple* - Current and Forecast Position *Black* - Past Position



Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE M-II. Atmospheric icons - Continued.

DESCRIPTION	ICON	NOTES
Weather Symbols Tropical Storm Systems **Tropical Storm Wind Areas and Date/Time Labels** Static/Dynamic: D Symbol Set: 45 Value: 162**04** **Color**: Red/Purple/Black *Red* - Outermost Area of Winds = 34 Knots *Purple* - Second Area of Winds = 50 Knots [=64 Knots Atlantic Only] *Red* or *Black* - Innermost Area of Winds = 100 Knots Draw Rules: Area1 - Dynamic		US Navy ship avoidance areas can be depicted using **Operator-Defined Freeform**.
Weather Symbols **Volcanic Eruption** Symbol Set: 45 Value: 16**21**00 **Color**: Black Draw Rules: Point7 - Static		
Weather Symbols Volcanic Eruption **Volcanic Ash** Symbol Set: 45 Value: 1621**01** **Color**: Black or Brown Draw Rules: Point7 - Static		


Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE M-II. Atmospheric icons - Continued.

DESCRIPTION	ICON	NOTES
Weather Symbols **Tropopause Level** Symbol Set: 45 Value: 16**22**00 **Color**: Black Draw Rules: Point7 - Static		
Weather Symbols **Freezing Level** Symbol Set: 45 Value: 16**23**00 **Color**: Black Draw Rules: Point7 - Static		
Weather Symbols **Precipitation of Unknown Type and Intensity** Symbol Set: 45 Value: 16**24**00 **Color**: Green Draw Rules: Point7 - Static		
Bounded Areas of Weather Symbol Set: 45 Value: **17**0000	N/A	
Bounded Areas of Weather **Instrument Flight Rule (IFR)** Symbol Set: 45 Value: 17**01**00 **Color**: Red Draw Rules: Area2 - Dynamic		

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE M-II. Atmospheric icons - Continued.

DESCRIPTION	ICON	NOTES
Bounded Areas of Weather **Marginal Visual Flight Rule (MVFR)** Symbol Set: 45 Value: 17**02**00 **Color**: Blue Draw Rules: Area2 - Dynamic		
Bounded Areas of Weather **Turbulence** Symbol Set: 45 Value: 17**03**00 **Color**: Blue Draw Rules: Area2 - Dynamic		
Bounded Areas of Weather **Icing** Symbol Set: 45 Value: 17**04**00 **Color**: Brown Draw Rules: Area2 - Dynamic		
Bounded Areas of Weather **Liquid Precipitation - Non-Convective Continuous or Intermittent** Symbol Set: 45 Value: 17**05**00 **Color**: Green Draw Rules: Area2 - Dynamic		

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE M-II. Atmospheric icons - Continued.

DESCRIPTION	ICON	NOTES
Bounded Areas of Weather Liquid Precipitation - Non-Convective Continuous or Intermittent **Liquid Precipitation – Convective** Symbol Set: 45 Value: 170**501** **Color**: Green Draw Rules: Area2 - Dynamic		
Bounded Areas of Weather **Freezing/Frozen Precipitation** Symbol Set: 45 Value: 17**06**00 **Color**: Red Draw Rules: Area2 - Dynamic		
Bounded Areas of Weather **Thunderstorm** Symbol Set: 45 Value: 17**07**00 **Color**: Red Draw Rules: Area2 - Dynamic		
Bounded Areas of Weather **Fog** Symbol Set: 45 Value: 17**08**00 **Color**: Yellow Draw Rules: Area2 - Dynamic		

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE M-II. Atmospheric icons - Continued.

DESCRIPTION	ICON	NOTES
Bounded Areas of Weather **Dust or Sand** Symbol Set: 45 Value: 17**09**00 **Color**: Brown Draw Rules: Area2 - Dynamic		
Bounded Areas of Weather **Operator-Defined Freeform** Symbol Set: 45 Value: 17**10**00 **Color**: Operator Defined Draw Rules: Area2 - Dynamic	 	(Used to designate areas of specific weather phenomenon as determined by the operator.)
Isopleths Symbol Set: 45 Value: **18**0000	N/A	N/A
Isopleths **Isobar – Surface** Symbol Set: 45 Value: 18**01**00 **Color**: Black Draw Rules: Line1 - Dynamic		Used on **surface analyses**. Although not part of the graphic, numerical values of the isopleth can be placed along the line for presentation. The modifier text will be placed at each end of the line and once in the middle of the line.



Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE M-II. Atmospheric icons - Continued.

DESCRIPTION	ICON	NOTES
Isopleths **Contour - Upper Air** Symbol Set: 45 Value: 18**02**00 **Color**: Black Draw Rules: Line1 - Dynamic		Used on **upper air analyses**. Although not part of the graphic, numerical values of the isopleth can be placed along the line for presentation. The modifier text will be placed at each end of the line and once in the middle of the line.
Isopleths **Isotherm** Symbol Set: 45 Value: 18**03**00 **Color**: Red Draw Rules: Line1 - Dynamic		The modifier text will be placed at each end of the line and once in the middle of the line.
Isopleths **Isotach** Symbol Set: 45 Value: 18**04**00 **Color**: Purple Draw Rules: Line1 - Dynamic		The modifier text will be placed at each end of the line and once in the middle of the line.
Isopleths **Isodrosotherm** Symbol Set: 45 Value: 18**05**00 **Color**: Green Draw Rules: Line1 - Dynamic		The modifier text will be placed at each end of the line and once in the middle of the line.
Isopleths **Thickness** Symbol Set: 45 Value: 18**06**00 **Color**: Red Draw Rules: Line1 - Dynamic		The modifier text will be placed at each end of the line and once in the middle of the line.




Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE M-II. Atmospheric icons - Continued.

DESCRIPTION	ICON	NOTES
Isopleths **Operator-Defined Freeform** Symbol Set: 45 Value: 18**07**00 **Color**: Operator Defined Draw Rules: Line1 - Dynamic		Used to display isopleth areas of specific weather parameters as determined by the operator. The modifier text will be placed at each end of the line and once in the middle of the line.
State of the Ground Symbol Set: 45 Value: **19**0000	N/A	
State of the Ground **Without Snow or Measurable Ice Cover** Symbol Set: 45 Value: 19**01**00	N/A	
State of the Ground Without Snow or Measurable Ice Cover **Surface Dry Without Cracks or Appreciable Dust or Loose Sand** Symbol Set: 45 Value: 19010**1** **Color**: Black Draw Rules: Point1 - Static		
State of the Ground Without Snow or Measurable Ice Cover **Surface Moist** Symbol Set: 45 Value: 19010**2** **Color**: Black Draw Rules: Point1 - Static		

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE M-II. Atmospheric icons - Continued.

DESCRIPTION	ICON	NOTES
State of the Ground Without Snow or Measurable Ice Cover **Surface Wet, Standing Water in Small or Large Pools** Symbol Set: 45 Value: 190103 **Color**: Black Draw Rules: Point1 - Static		
State of the Ground Without Snow or Measurable Ice Cover **Surface Flooded** Symbol Set: 45 Value: 190104 **Color**: Black Draw Rules: Point1 - Static		
State of the Ground Without Snow or Measurable Ice Cover **Surface Frozen** Symbol Set: 45 Value: 190105 **Color**: Black Draw Rules: Point1 - Static		
State of the Ground Without Snow or Measurable Ice Cover **Glaze (Thin Ice) On Ground** Static/Dynamic: S Symbol Set: 45 Value: 190106 **Color**: Black Draw Rules: Point1 - Static		




Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE M-II. Atmospheric icons - Continued.

DESCRIPTION	ICON	NOTES
State of the Ground Without Snow or Measurable Ice Cover **Loose Dry Dust or Sand Not Covering Ground Completely** Symbol Set: 45 Value: 190107 **Color**: Black Draw Rules: Point1 - Static		
State of the Ground Without Snow or Measurable Ice Cover **Thin Loose Dry Dust or Sand Covering Ground Completely** Symbol Set: 45 Value: 190108 **Color**: Black Draw Rules: Point1 - Static		
State of the Ground Without Snow or Measurable Ice Cover **Moderate/Thick Loose Dry Dust or Sand Covering Ground Completely** Symbol Set: 45 Value: 190109 **Color**: Black Draw Rules: Point1 - Static		
State of the Ground Without Snow or Measurable Ice Cover **Extremely Dry with Cracks** Symbol Set: 45 Value: 190110 **Color**: Black Draw Rules: Point1 - Static		



Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE M-II. Atmospheric icons - Continued.

DESCRIPTION	ICON	NOTES
State of the Ground **With Snow or Measurable Ice Cover** Symbol Set: 45 Value: 19**02**00	N/A	
State of the Ground with Snow or Measurable Ice Cover **Predominately Ice Covered** Symbol Set: 45 Value: 1902**01** **Color**: Black Draw Rules: Point1 - Static		
State of the Ground With Snow or Measurable Ice Cover **Compact or Wet Snow (with or Without Ice) Covering Less Than One-Half of Ground** Symbol Set: 45 Value: 1902**02** **Color**: Black Draw Rules: Point1 - Static		
State of the Ground With Snow or Measurable Ice Cover **Compact or Wet Snow (with or Without Ice) Covering At Least One-Half Ground, But Ground Not Completely Covered** Symbol Set: 45 Value: 1902**03** **Color**: Black Draw Rules: Point1 - Static		


Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE M-II. Atmospheric icons - Continued.

DESCRIPTION	ICON	NOTES
State of the Ground With Snow or Measurable Ice Cover **Even Layer of Compact or Wet Snow Covering Ground Completely** Symbol Set: 45 Value: 190**04** **Color**: Black Draw Rules: Point1 - Static		
State of the Ground With Snow or Measurable Ice Cover **Uneven Layer of Compact or Wet Snow Covering Ground Completely** Symbol Set: 45 Value: 190**05** **Color**: Black Draw Rules: Point1 - Static		
State of The Ground With Snow or Measurable Ice Cover **Loose Dry Snow Covering Less Than One-Half of Ground** Symbol Set: 45 Value: 190**06** **Color**: Black Draw Rules: Point1 - Static		
State of the Ground With Snow or Measurable Ice Cover **Loose Dry Snow Covering At Least One-Half Ground, But Ground Not Completely Covered** Symbol Set: 45 Value: 190**07** **Color**: Black Draw Rules: Point1 - Static		

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE M-II. Atmospheric icons - Continued.

DESCRIPTION	ICON	NOTES
State of the Ground With Snow or Measurable Ice Cover **Even Layer of Loose Dry Snow Covering Ground Completely** Symbol Set: 45 Value: 190**08** **Color**: Black Draw Rules: Point1 - Static		
State of the Ground With Snow or Measurable Ice Cover **Uneven Layer of Loose Dry Snow Covering Ground Completely** Symbol Set: 45 Value: 190**09** **Color**: Black Draw Rules: Point1 - Static		
State of the Ground With Snow or Measurable Ice Cover **Snow Covering Ground Completely, Deep Drifts** Symbol Set: 45 Value: 190**10** **Color**: Black Draw Rules: Point1 - Static		

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE M-III. Oceanographic icons.

DESCRIPTION	ICON	NOTES
Ice Systems Symbol Set: 46 Value: **11**0000	N/A	
Ice Systems **Icebergs** Symbol Set: 46 Value: 11**01**00 Color: Black	N/A	
Ice Systems Icebergs **Many Icebergs** Symbol Set: 46 Value: 1101**01** **Color**: Black Draw Rules: Point3 - Static		
Ice Systems Icebergs **Belts and Strips** Symbol Set: 46 Value: 1101**02** **Color**: Black Draw Rules: Point3 - Static		
Ice Systems Icebergs **General** Symbol Set: 46 Value: 1101**03** **Color**: Black Draw Rules: Point3 - Static		



Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE M-III. Oceanographic icons - Continued.

DESCRIPTION	ICON	NOTES
Ice Systems Icebergs **Many Icebergs – General** Symbol Set: 46 Value: 1101**04** **Color**: Black Draw Rules: Point3 - Static		
Ice Systems Icebergs **Bergy Bit** Symbol Set: 46 Value: 1101**05** **Color**: Black Draw Rules: Point3 - Static		
Ice Systems Icebergs **Many Bergy Bits** Symbol Set: 46 Value: 1101**06** **Color**: Black Draw Rules: Point3 - Static		
Ice Systems Icebergs **Growler** Symbol Set: 46 Value: 1101**07** **Color**: Black Draw Rules: Point3 - Static		


Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE M-III. Oceanographic icons - Continued.

DESCRIPTION	ICON	NOTES
Ice Systems Icebergs **Many Growlers** Symbol Set: 46 Value: 1101**08** **Color**: Black Draw Rules: Point3 - Static		
Ice Systems Icebergs **Floeberg** Symbol Set: 46 Value: 1101**09** **Color**: Black Top with White Bottom Draw Rules: Point3 - Static		
Ice Systems Icebergs **Ice Island** Symbol Set: 46 Value: 1101**10** **Color**: White Hexagon/Black Hatches Draw Rules: Point3 - Static		
Ice Systems **Ice Concentration** Symbol Set: 46 Value: 11**02**00	N/A	
Ice Systems Ice Concentration **Bergy Water** Symbol Set: 46 Value: 1102**01** **Color**: Black Draw Rules: Point3 - Static		


Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE M-III. Oceanographic icons - Continued.

DESCRIPTION	ICON	NOTES
Ice Systems Ice Concentration **Water with Radar Targets** Symbol Set: 46 Value: 110**02** **Color**: Black Draw Rules: Point3 - Static		
Ice Systems Ice Concentration **Ice Free** Symbol Set: 46 Value: 110**03** **Color**: Black Draw Rules: Point3 - Static		
Ice Systems **Dynamic Processes** Symbol Set: 46 Value: 11**03**00	N/A	
Ice Systems Dynamic Processes **Convergence** Symbol Set: 46 Value: 1103**01** **Color**: Black Draw Rules: Point3 - Static		
Ice Systems Dynamic Processes **Divergence** Symbol Set: 46 Value: 1103**02** **Color**: Black Draw Rules: Point3 - Static		

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE M-III. Oceanographic icons - Continued.

DESCRIPTION	ICON	NOTES
Ice Systems Dynamic Processes **Shearing or Shear Zone** Symbol Set: 46 Value: 110**03** **Color**: Black Draw Rules: Point3 - Static		
Ice Systems Dynamic Processes **Ice Drift (Direction)** Symbol Set: 46 Value: 110**04** **Color**: Black Draw Rules: Point3 - Static		
Ice Systems **Sea Ice** Symbol Set: 46 Value: 11**04**00 **Color**: Black Draw Rules: Point3 - Static		
Ice Systems Sea Ice **Ice Thickness (Observed)** Symbol Set: 46 Value: 1104**01** **Color**: Box with Black Outline Draw Rules: Point3 - Static		


Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE M-III. Oceanographic icons - Continued.

DESCRIPTION	ICON	NOTES
Ice Systems Sea Ice **Ice Thickness (Estimated)** Symbol Set: 46 Value: 110**402** **Color**: Box with Black Dashed Line Draw Rules: Point3 - Static		
Ice Systems Sea Ice **Melt Puddles or Flooded Ice** Symbol Set: 46 Value: 110**403** **Color**: Black Draw Rules: Point3 - Static		
Ice Systems **Limits** Symbol Set: 46 Value: 11**05**00	N/A	
Ice Systems Limits **Limits of Visual Observation** Symbol Set: 46 Value: 1105**01** **Color**: Black Draw Rules: Line1 - Dynamic		The ovals will be repeated the entire length of the line.
Ice Systems Limits **Limits of Undercast** Symbol Set: 46 Value: 1105**02** **Color**: Black Draw Rules: Line1- Dynamic		The wave-like shapes will be repeated the entire length of the line.


Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE M-III. Oceanographic icons - Continued.

DESCRIPTION	ICON	NOTES
Ice Systems Limits **Limits of Radar Observation** Symbol Set: 46 Value: 110**503** **Color**: Black Draw Rules: Line1- Dynamic		The ovals and x's will alternate the entire length of the line.
Ice Systems Limits **Observed Ice Edge or Boundary** Symbol Set: 46 Value: 110**504** **Color**: Black Draw Rules: Line1- Dynamic		The points are typically connected with a solid curved line.
Ice Systems Limits **Estimated Ice Edge or Boundary** Symbol Set: 46 Value: 110**505** **Color**: Black Draw Rules: Line1- Dynamic		The points are typically connected with a dashed curved line.
Ice Systems Limits **Ice Edge or Boundary From Radar** Symbol Set: 46 Value: 110**506** **Color**: Black Draw Rules: Line1- Dynamic		The points are typically connected with a curved line with Xs spaced evenly along the entire length of the line.
Ice Systems **Openings in the Ice** Symbol Set: 46 Value: 11**06**00	N/A	



Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE M-III. Oceanographic icons - Continued.

DESCRIPTION	ICON	NOTES
Ice Systems Openings in the Ice **Cracks** Symbol Set: 46 Value: 110**601** **Color**: Black Draw Rules: Line1- Dynamic		The points are typically connected with a curved line.
Ice Systems Openings in the Ice **Cracks At a Specific Location** Symbol Set: 46 Value: 110**602** **Color**: Black Draw Rules: Line1- Dynamic		The points are typically connected with a curved line with perpendicular lines spaced evenly along the line. The perpendicular lines will be placed at regular intervals along the entire length of the line.
Ice Systems Openings in the Ice **Lead** Symbol Set: 46 Value: 110**603** **Color**: Black Draw Rules: Line1- Dynamic		The points are typically connected with parallel curved lines.
Ice Systems Openings in the Ice **Frozen Lead** Symbol Set: 46 Value: 110**604** **Color**: Black Draw Rules: Line1- Dynamic		The points are typically connected with parallel curved lines connected by vertical lines spaced evenly along the line. The perpendicular lines joining the main lines will be placed at regular intervals along the entire length of the main lines.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE M-III. Oceanographic icons - Continued.

DESCRIPTION	ICON	NOTES
Ice Systems **Snow Cover** Symbol Set: 46 Value: 11**07**00 **Color**: Black Draw Rules: Point3 - Static		
Ice Systems Snow Cover **Sastrugi (with Orientation)** Symbol Set: 46 Value: 1107**01** **Color**: Black Draw Rules: Point3 - Static		
Ice Systems **Topographical Features** Static/Dynamic: N/A Symbol Set: 46 Value: 11**08**00	N/A	
Ice Systems Topographical Features **Ridges or Hummocks** Symbol Set: 46 Value: 1108**01** **Color**: Black Draw Rules: Point3 - Static		
Ice Systems Topographical Features **Rafting** Symbol Set: 46 Value: 1108**02** **Color**: Black Draw Rules: Point3 - Static		

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE M-III. Oceanographic icons - Continued.

DESCRIPTION	ICON	NOTES
Ice Systems Topographical Features **Jammed Brash Barrier** Symbol Set: 46 Value: 1108**03** **Color**: Black Draw Rules: Point3 - Static		
Hydrography Static/Dynamic: N/A Symbol Set: 46 Value: **12**0000	N/A	
Hydrography **Depth** Static/Dynamic: N/A Symbol Set: 46 Value: 12**01**00	N/A	
Hydrography Depth **Soundings** Symbol Set: 46 Value: 12010**1** **Color**: Gray Draw Rules: Point3 - Static		
Hydrography Depth **Depth Curve** Symbol Set: 46 Value: 12010**2** **Color**: Gray Thin Solid Line Draw Rules: Line1 - Dynamic		The points are typically connected with a solid curved line. The modifier text will be placed at each end of the line and at regular intervals along the line.



Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE M-III. Oceanographic icons - Continued.

DESCRIPTION	ICON	NOTES
Hydrography Depth **Depth Contour** Symbol Set: 46 Value: 120**103** **Color**: Gray Thin Solid Line Draw Rules: Line1 - Dynamic		The modifier text will be placed at each end of the line and at regular intervals along the line.
Hydrography Depth **Depth Area** Symbol Set: 46 Value: 120**104** **Color**: Blue/Pale Blue/White Draw Rules: Area2 - Dynamic		The points are connected with a solid line.
Hydrography **Coastal Hydrography** Static/Dynamic: N/A Symbol Set: 46 Value: 12**02**00	N/A	
Hydrography Coastal Hydrography **Coastline** Symbol Set: 46 Value: 120**201** **Color**: Gray Thin Solid Line Draw Rules: Line1 - Dynamic		The points are connected with a solid line.



Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE M-III. Oceanographic icons - Continued.

DESCRIPTION	ICON	NOTES
Hydrography Coastal Hydrography **Island** Static/Dynamic: S Symbol Set: 46 Value: 120**02** **Color**: Brown Solid Fill Draw Rules: Area2 - Dynamic		The points are connected with a solid line.
Hydrography Coastal Hydrography **Beach** Symbol Set: 46 Value: 120**03** **Color**: Beige Outline and Stipple Fill Draw Rules: Area2 - Dynamic		The points are connected with a solid line.
Hydrography Coastal Hydrography **Water** Static/Dynamic: S Symbol Set: 46 Value: 120**04** **Color**: White Fill Draw Rules: Area2 - Dynamic		The gray box is not to be drawn. It is shown here only as a reference to position and proportion of the icon.
Hydrography Coastal Hydrography **Foreshore - Line** Symbol Set: 46 Value: 120**05** **Color**: Yellow-Green Solid Line Draw Rules: Line1 - Dynamic		


Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE M-III. Oceanographic icons - Continued.

DESCRIPTION	ICON	NOTES
Hydrography Coastal Hydrography **Foreshore - Area** Symbol Set: 46 Value: 120**06** **Color**: Yellow-Green Solid Fill Draw Rules: Area2 - Dynamic		
Hydrography **Ports and Harbors** Static/Dynamic: N/A Symbol Set: 46 Value: 12**03**00	N/A	N/A
Hydrography Ports and Harbors **Ports** Static/Dynamic: N/A Symbol Set: 46 Value: 1203**01**	N/A	N/A
Hydrography Ports and Harbors Ports **Berths (Onshore)** Symbol Set: 46 Value: 1203**02** **Color**: Magenta Small Circle Draw Rules: Point1 - Static		
Hydrography Ports and Harbors Ports **Berths (Anchor)** Symbol Set: 46 Value: 1203**03** **Color**: Magenta Anchor W/ Small Circle Draw Rules: Point1 - Static		


Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE M-III. Oceanographic icons - Continued.

DESCRIPTION	ICON	NOTES
Hydrography Ports and Harbors Ports **Anchorage - Point** Symbol Set: 46 Value: 120**04** **Color**: Magenta Anchor Draw Rules: Point1 - Static		
Hydrography Ports and Harbors Ports **Anchorage - Line** Symbol Set: 46 Value: 120**05** **Color**: Magenta Dash/Chevron Line W/ Anchor Symbol Draw Rules: Line8 - Dynamic	 **Orientation:** The graphic is oriented upright on the display as shown in the example and operator-centered over the desired location.	
Hydrography Ports and Harbors Ports **Anchorage - Area** Symbol Set: 46 Value: 120**06** **Color**: Magenta Dash/Chevron Outline W/ Anchor Draw Rules: Area2 - Dynamic		

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE M-III. Oceanographic icons - Continued.

DESCRIPTION	ICON	NOTES
Hydrography Ports and Harbors Ports **Call In Point** Static/Dynamic: S Symbol Set: 46 Value: 120**07** **Color**: Magenta Circle W/ Two Cones Draw Rules: Point1 - Static		
Hydrography Ports and Harbors Ports **Pier/Wharf/Quay** Symbol Set: 46 Value: 120**08** **Color**: Gray Thin Solid Line Draw Rules: Line1 - Dynamic		
Hydrography Ports and Harbors **Fishing Harbor - Point** Symbol Set: 46 Value: 120**09** **Color**: Magenta Fish W/Arcs Above and Below Draw Rules: Point1 - Static		
Hydrography Ports and Harbors **Fish Weirs - Point** Symbol Set: 46 Value: 120**10** **Color**: Gray Fish Inside Net Draw Rules: Point1 - Static		



Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE M-III. Oceanographic icons - Continued.

DESCRIPTION	ICON	NOTES
Hydrography Ports and Harbors **Fish Stakes - Point** Symbol Set: 46 Value: 120**11** **Color**: Gray L **Style**: Repeating Pattern of Gray L's Draw Rules: Point1 - Static		
Hydrography Ports and Harbors **Fish Traps - Area** Symbol Set: 46 Value: 120**12** **Color**: Gray Rectangle Below Angle Line Pattern Fill Dashed Outline Draw Rules: Area2 - Dynamic		
Hydrography Ports and Harbors **Facilities** Static/Dynamic: N/A Symbol Set: 46 Value: 120**13**	N/A	N/A
Hydrography Ports and Harbors Facilities **Drydock** Symbol Set: 46 Value: 120**14** **Color**: Brown Solid Area W/ Black Thin Outline Draw Rules: Area2 - Dynamic		

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE M-III. Oceanographic icons - Continued.

DESCRIPTION	ICON	NOTES
Hydrography Ports and Harbors Facilities **Landing Place** Symbol Set: 46 Value: 120**15** **Color**: Magenta Yacht Inside Circle Draw Rules: Point1 - Static		
Hydrography Ports and Harbors Facilities **Offshore Loading Facility - Point** Symbol Set: 46 Value: 120**16** **Color**: Black Installation Buoy Draw Rules: Point1 - Static		
Hydrography Ports and Harbors Facilities **Offshore Loading Facility - Line** Symbol Set: 46 Value: 120**17** **Color**: Gray Thick Solid Line Draw Rules: Line1 - Dynamic		
Hydrography Ports and Harbors Facilities **Offshore Loading Facility - Area** Symbol Set: 46 Value: 120**18** **Color**: Brown Solid Fill Draw Rules: Area2 - Dynamic		


Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE M-III. Oceanographic icons - Continued.

DESCRIPTION	ICON	NOTES
Hydrography Ports and Harbors Facilities **Ramp - Above Water** Symbol Set: 46 Value: 120**19** **Color**: Black Solid Line Draw Rules: Line1 - Dynamic		
Hydrography Ports and Harbors Facilities **Ramp - Below Water** Symbol Set: 46 Value: 120**20** **Color**: Black Dashed Line Draw Rules: Line1 - Dynamic		
Hydrography Ports and Harbors Facilities **Landing Ring** Symbol Set: 46 Value: 120**21** **Color**: Dark Brown Filled Square W/ Black Outline Draw Rules: Point1 - Static		

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE M-III. Oceanographic icons - Continued.

DESCRIPTION	ICON	NOTES
Hydrography Ports and Harbors Facilities **Ferry Crossing** Symbol Set: 46 Value: 120**22** **Color**: Magenta Dashed Line W/ Boat Symbol Draw Rules: Point1 - Static		
Hydrography Ports and Harbors Facilities **Cable Ferry Crossing** Symbol Set: 46 Value: 120**23** **Color**: Black Black Dashed Line W/ Boat Symbol Draw Rules: Point1 - Static		
Hydrography Ports and Harbors Facilities **Dolphin** Symbol Set: 46 Value: 120**24** **Color**: Dark Brown Filled Square W/ Black Outline Draw Rules: Point1 - Static		
Hydrography Ports and Harbors **Shoreline Protection** Static/Dynamic: N/A Symbol Set: 46 Value: 120**25**	N/A	N/A




Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE M-III. Oceanographic icons - Continued.

DESCRIPTION	ICON	NOTES
Hydrography Ports and Harbors Shoreline Protection **Breakwater/Groin/Jetty - Above Water** Symbol Set: 46 Value: 120**26** **Color**: Gray Solid Line Draw Rules: Line1 - Dynamic		
Hydrography Ports and Harbors Shoreline Protection **Breakwater/Groin/Jetty - Below Water** Symbol Set: 46 Value: 120**27** **Color**: Gray Dashed Line Draw Rules: Line1 - Dynamic		
Hydrography Ports and Harbors Shoreline Protection **Seawall** Symbol Set: 46 Value: 120**28** **Color**: Gray Solid Line Draw Rules: Line1 - Dynamic		
Hydrography **Aids to Navigation** Static/Dynamic: N/A Symbol Set: 46 Value: 12**04**00	N/A	N/A

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE M-III. Oceanographic icons - Continued.

DESCRIPTION	ICON	NOTES
Hydrography Aids to Navigation **Beacon** Symbol Set: 46 Value: 120**401** **Color**: Black Beacon/Buoy Base Draw Rules: Point1 - Static		Anchor Points. This graphic requires one anchor point. The center point defines the center of the graphic. Size/Shape. Scalable. Orientation. The graphic is typically centered over the desired location.
Hydrography Aids to Navigation **Buoy Default** Symbol Set: 46 Value: 120**402** **Color**: Black/Magenta Draw Rules: Point1 - Static		Black default buoy beside magenta question mark
Hydrography Aids to Navigation **Marker** Symbol Set: 46 Value: 120**403** **Color**: Magenta Draw Rules: Point1 - Static		Magenta Inverted T with open circle at bottom below box
Hydrography Aids to Navigation **Perches/Stakes - Point** Symbol Set: 46 Value: 120**404** **Color**: Black Small Circle Draw Rules: Point1 - Static		


Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE M-III. Oceanographic icons - Continued.

DESCRIPTION	ICON	NOTES
Hydrography Aids to Navigation **Perches/Stakes - Area** Static/Dynamic: D Symbol Set: 46 Value: 120**05** **Color**: Blue Fill with Black Dot Outline Draw Rules: Area2 - Dynamic		
Hydrography Aids to Navigation **Light** Symbol Set: 46 Value: 120**06** **Color**: Magenta Flare Draw Rules: Point1 - Static		
Hydrography Aids to Navigation **Leading Line** Symbol Set: 46 Value: 120**07** **Color**: Black Solid to Dashed Line Draw Rules: Line1 - Dynamic		
Hydrography Aids to Navigation **Light Vessel/Light Ship** Symbol Set: 46 Value: 120**08** **Color**: Black Light Vessel Draw Rules: Point1 - Static		


Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE M-III. Oceanographic icons - Continued.

DESCRIPTION	ICON	NOTES
Hydrography Aids to Navigation **Lighthouse** Symbol Set: 46 Value: 120**09** **Color**: Black Lighthouse Symbol Draw Rules: Point1 - Static		
Hydrography **Dangers/Hazards** Static/Dynamic: N/A Symbol Set: 46 Value: 12**05**00	N/A	N/A
Hydrography Dangers/Hazards **Rock Submerged** Symbol Set: 46 Value: 1205**01** **Color**: Blue/Black Black Cross In Blue Solid Circle W/ Black Dotted Outline Draw Rules: Point1 - Static		
Hydrography Dangers/Hazards **Rock Awashed** Symbol Set: 46 Value: 1205**02** **Color**: Black 6 Point Asterisk Draw Rules: Point1 - Static		



Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE M-III. Oceanographic icons - Continued.

DESCRIPTION	ICON	NOTES
Hydrography Dangers/Hazards **Underwater Danger/Hazard** Symbol Set: 46 Value: 120**03** **Color**: Blue/Black Blue Fill W/ Black Dot Outline Draw Rules: Area2 - Dynamic		
Hydrography Dangers/Hazards **Foul Ground - Point** Symbol Set: 46 Value: 120**04** **Color**: Gray Pound (#) Symbol Draw Rules: Point1 - Static		
Hydrography Dangers/Hazards **Foul Ground - Area** Symbol Set: 46 Value: 120**05** **Color**: Gray Pound (#) Offset Pattern Fill Draw Rules: Area2 - Dynamic		
Hydrography Dangers/Hazards **Kelp/Seaweed - Point** Symbol Set: 46 Value: 120**06** **Color**: Gray Kelp Symbol Draw Rules: Point1 - Static		


Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE M-III. Oceanographic icons - Continued.

DESCRIPTION	ICON	NOTES
Hydrography Dangers/Hazards **Kelp/Seaweed - Area** Symbol Set: 46 Value: 120**507** **Color**: Gray Kelp Symbol Pattern Fill Draw Rules: Area2 - Dynamic		
Hydrography Dangers/Hazards **Snags/Stumps** Symbol Set: 46 Value: 120**508** **Color**: Blue Oval W/ Black Dotted Outline Draw Rules: Point1 - Static		
Hydrography Dangers/Hazards **Wreck (Uncovers)** Symbol Set: 46 Value: 120**509** **Color**: Gray Wreck Symbol Draw Rules: Point1 - Static		Anchor Points. This graphic requires one anchor point. The center point defines the center of the graphic. Size/Shape. Scalable. Orientation. The graphic is typically centered over the desired location.
Hydrography Dangers/Hazards **Wreck (Submerged)** Symbol Set: 46 Value: 120**510** **Color**: Black Horizontal Bar W/ 3 Ticks In Blue Solid Oval W/ Black Dotted Outline Draw Rules: Point1 - Static		

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE M-III. Oceanographic icons - Continued.

DESCRIPTION	ICON	NOTES
Hydrography Dangers/Hazards **Breakers** Symbol Set: 46 Value: 120**11** **Color**: Gray Thin Dashed Line Draw Rules: Line1 - Dynamic		
Hydrography Dangers/Hazards **Reef** Symbol Set: 46 Value: 120**12** **Color**: Black Jagged Line Draw Rules: Line1 - Dynamic		
Hydrography Dangers/Hazards **Eddies/Overfalls/Tide Rips** Symbol Set: 46 Value: 120**13** **Color**: Gray Draw Rules: Point1 - Static		
Hydrography Dangers/Hazards **Discolored Water** Symbol Set: 46 Value: 120**14** **Color**: Blue Filled W/ Black Dot Outline Draw Rules: Area2 - Dynamic		
Hydrography **Bottom Features** Static/Dynamic: N/A Symbol Set: 46 Value: 12**06**00	N/A	N/A

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE M-III. Oceanographic icons - Continued.

DESCRIPTION	ICON	NOTES
Hydrography Bottom Features **Bottom Characteristics - Sand** Symbol Set: 46 Value: 120**601** **Color**: Black Draw Rules: Point3 - Static		
Hydrography Bottom Features **Bottom Characteristics - Mud** Symbol Set: 46 Value: 120**602** **Color**: Black Draw Rules: Point3 - Static		
Hydrography Bottom Features **Bottom Characteristics - Clay** Symbol Set: 46 Value: 120**603** **Color**: Black Draw Rules: Point3 - Static		
Hydrography Bottom Features **Bottom Characteristics - Silt** Symbol Set: 46 Value: 120**604** **Color**: Black Draw Rules: Point3 - Static		

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE M-III. Oceanographic icons - Continued.

DESCRIPTION	ICON	NOTES
Hydrography Bottom Features **Bottom Characteristics - Stones** Symbol Set: 46 Value: 120**05** **Color**: Black Draw Rules: Point3 - Static		
Hydrography Bottom Features **Bottom Characteristics - Gravel** Symbol Set: 46 Value: 120**06** **Color**: Black Draw Rules: Point3 - Static		
Hydrography Bottom Features **Bottom Characteristics - Pebbles** Symbol Set: 46 Value: 120**07** **Color**: Black Draw Rules: Point3 - Static		
Hydrography Bottom Features **Bottom Characteristics - Cobbles** Symbol Set: 46 Value: 120**08** **Color**: Black Draw Rules: Point3 - Static		

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE M-III. Oceanographic icons - Continued.

DESCRIPTION	ICON	NOTES
Hydrography Bottom Features **Bottom Characteristics - Rock** Symbol Set: 46 Value: 120**609** **Color**: Black Draw Rules: Point3 - Static	*R*	
Hydrography Bottom Features **Bottom Characteristics - Coral** Symbol Set: 46 Value: 120**610** **Color**: Black Draw Rules: Point3 - Static	*Co*	
Hydrography Bottom Features **Bottom Characteristics - Shell** Symbol Set: 46 Value: 120**611** **Color**: Black Draw Rules: Point3 - Static	*Sh*	
Hydrography Bottom Features **Qualifying Terms - Fine** Symbol Set: 46 Value: 120**612** **Color**: Black Draw Rules: Point3 - Static	*f*	

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE M-III. Oceanographic icons - Continued.

DESCRIPTION	ICON	NOTES
Hydrography Bottom Features **Qualifying Terms - Medium** Symbol Set: 46 Value: 120**13** **Color**: Black Draw Rules: Point3 - Static		
Hydrography Bottom Features **Qualifying Terms - Coarse** Symbol Set: 46 Value: 120**14** **Color**: Black Draw Rules: Point3 - Static		
Hydrography **Tide and Current** Static/Dynamic: N/A Symbol Set: 46 Value: 12**07**00	N/A	N/A
Hydrography Tide and Current **Water Turbulence** Symbol Set: 46 Value: 12070**1** **Color**: Gray Wavy Line Draw Rules: Point1 - Static		
Hydrography Tide and Current **Current Flow - Ebb** Symbol Set: 46 Value: 120**702** **Color**: Gray Arrow W/ No Feather Draw Rules: Line1 - Dynamic		The line should be drawn in the direction of the flow.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE M-III. Oceanographic icons - Continued.

DESCRIPTION	ICON	NOTES
Hydrography Tide and Current **Current Flow - Flood** Symbol Set: 46 Value: 120**03** **Color**: Gray Arrow W/ One Feather Draw Rules: Line1 - Dynamic		The line should be drawn in the direction of the flow.
Hydrography Tide and Current **Tide Data Point** Symbol Set: 46 Value: 120**04** **Color**: Gray Diamond Draw Rules: Point1 - Static		
Hydrography Tide and Current **Tide Gauge** Symbol Set: 46 Value: 120**05** **Color**: Brown with Magenta Draw Rules: Point1 - Static		
Oceanography Static/Dynamic: N/A Symbol Set: 46 Value: **13**0000	N/A	N/A
Oceanography **Bioluminescence** Static/Dynamic: N/A Symbol Set: 46 Value: 13**01**00	N/A	N/A


Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE M-III. Oceanographic icons - Continued.

DESCRIPTION	ICON	NOTES
Oceanography Bioluminescence **Visual Detection Ratio (VDR) Level 1-2** Symbol Set: 46 Value: 130**01** **Color**: Dark Green (RGB 26:153:77) Draw Rules: Area2 - Dynamic		
Oceanography Bioluminescence **VDR Level 2-3** Symbol Set: 46 Value: 130**02** **Color**: Light Green (RGB 26:204:77) Draw Rules: Area2 - Dynamic		
Oceanography Bioluminescence **VDR Level 3-4** Symbol Set: 46 Value: 130**03** **Color**: Lime Green RGB (128:255:51) Draw Rules: Area2 - Dynamic		
Oceanography Bioluminescence **VDR Level 4-5** Symbol Set: 46 Value: 130**04** **Color**: Yellow-Green RGB (204:255:26) Draw Rules: Area2 - Dynamic		


Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE M-III. Oceanographic icons - Continued.

DESCRIPTION	ICON	NOTES
Oceanography Bioluminescence **VDR Level 5-6** Symbol Set: 46 Value: 130105 **Color**: Yellow RGB (255:255:0) Draw Rules: Area2 - Dynamic		
Oceanography Bioluminescence **VDR Level 6-7** Symbol Set: 46 Value: 130106 **Color**: Gold RGB (255:204:0) Draw Rules: Area2 - Dynamic		
Oceanography Bioluminescence **VDR Level 7-8** Symbol Set: 46 Value: 130107 **Color**: Light Orange RGB (255:128:0) Draw Rules: Area2 - Dynamic		
Oceanography Bioluminescence **VDR Level 8-9** Symbol Set: 46 Value: 130108 **Color**: Dark Orange RGB (255:77:0) Draw Rules: Area2 - Dynamic		


Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE M-III. Oceanographic icons - Continued.

DESCRIPTION	ICON	NOTES
Oceanography Bioluminescence **VDR Level 9-10** Symbol Set: 46 Value: 130109 **Color**: Red RGB (255:0:0) Draw Rules: Area2 - Dynamic		
Oceanography **Beach Slope** Static/Dynamic: N/A Symbol Set: 46 Value: 130200	N/A	N/A
Oceanography Beach Slope **Flat** Symbol Set: 46 Value: 130201 **Color**: Light Gray Draw Rules: Area2 - Dynamic		
Oceanography Beach Slope **Gentle** Symbol Set: 46 Value: 130202 **Color**: Dark Gray Draw Rules: Area2 - Dynamic		
Oceanography Beach Slope **Moderate** Symbol Set: 46 Value: 130203 **Color**: Light Gray Dot Fill with Gray Outline Draw Rules: Area2 - Dynamic		


Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE M-III. Oceanographic icons - Continued.

DESCRIPTION	ICON	NOTES
Oceanography Beach Slope **Steep** Symbol Set: 46 Value: 1302**04** **Color**: Dark Gray Dot Fill W/ Gray Outline Draw Rules: Area2 - Dynamic		
Geophysics/Acoustics Static/Dynamic: N/A Symbol Set: 46 Value: **14**0000	N/A	N/A
Geophysics/Acoustics **Mine Warfare (MIW) Bottom Descriptors** Static/Dynamic: N/A Symbol Set: 46 Value: 14**01**00	N/A	N/A
Geophysics/Acoustics Mine Warfare Bottom Descriptors **MIW-Bottom Sediments - Solid Rock** Symbol Set: 46 Value: 14010**1** **Color**: Purple (RGB 255:0:255) Draw Rules: Area2 - Dynamic		
Geophysics/Acoustics Mine Warfare Bottom Descriptors **MIW-Bottom Sediments - Clay** Symbol Set: 46 Value: 14010**2** **Color**: Periwinkle (RGB 100:130:255) Draw Rules: Area2 - Dynamic		


Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE M-III. Oceanographic icons - Continued.

DESCRIPTION	ICON	NOTES
Geophysics/Acoustics Mine Warfare Bottom Descriptors **MIW-Bottom Sediments - Very Coarse Sand** Symbol Set: 46 Value: 140103 **Color**: Gold (RGB 255:180:0) Draw Rules: Area2 - Dynamic		
Geophysics/Acoustics Mine Warfare Bottom Descriptors **MIW-Bottom Sediments - Coarse Sand** Symbol Set: 46 Value: 140104 **Color**: Light Gold (RGB 255:215:0) Draw Rules: Area2 - Dynamic		
Geophysics/Acoustics Mine Warfare Bottom Descriptors **MIW-Bottom Sediments - Medium Sand** Symbol Set: 46 Value: 140105 **Color**: Yellow (RGB 255:235:0) Draw Rules: Area2 - Dynamic		
Geophysics/Acoustics Mine Warfare Bottom Descriptors **MIW-Bottom Sediments - Fine Sand** Symbol Set: 46 Value: 140106 Color: Light Yellow (RGB 255:255:140) Draw Rules: Area2 - Dynamic		

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE M-III. Oceanographic icons - Continued.

DESCRIPTION	ICON	NOTES
Geophysics/Acoustics Mine Warfare Bottom Descriptors **MIW-Bottom Sediments - Very Fine Sand** Symbol Set: 46 Value: 140107 **Color**: Pale Yellow (RGB 255:255:220) Draw Rules: Area2 - Dynamic		
Geophysics/Acoustics Mine Warfare Bottom Descriptors **MIW-Bottom Sediments - Very Fine Silt** Symbol Set: 46 Value: 140108 **Color**: Turquoise (RGB 0:215:255) Draw Rules: Area2 - Dynamic		
Geophysics/Acoustics Mine Warfare Bottom Descriptors **MIW-Bottom Sediments - Fine Silt** Symbol Set: 46 Value: 140109 **Color**: Aquamarine (RGB 25:255:230) Draw Rules: Area2 - Dynamic		
Geophysics/Acoustics Mine Warfare Bottom Descriptors **MIW-Bottom Sediments - Medium Silt** Symbol Set: 46 Value: 140110 **Color**: Green (RGB 0:255:0) Draw Rules: Area2 - Dynamic		

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE M-III. Oceanographic icons - Continued.

DESCRIPTION	ICON	NOTES
Geophysics/Acoustics Mine Warfare Bottom Descriptors **MIW-Bottom Sediments - Coarse Silt** Symbol Set: 46 Value: 140**11** **Color**: Lime Green (RGB 200:255:105) Draw Rules: Area2 - Dynamic		
Geophysics/Acoustics Mine Warfare Bottom Descriptors **MIW-Bottom Sediments - Boulders** Symbol Set: 46 Value: 140**12** **Color**: Red (RGB 255:0:0) Draw Rules: Area2 - Dynamic		
Geophysics/Acoustics Mine Warfare Bottom Descriptors **MIW-Bottom Sediments - Cobbles, Oyster Shells** Symbol Set: 46 Value: 140**13** **Color**: Dark Peach (RGB 255:150:150) Draw Rules: Area2 - Dynamic		
Geophysics/Acoustics Mine Warfare Bottom Descriptors **MIW-Bottom Sediments - Pebbles, Shells** Symbol Set: 46 Value: 140**14** **Color**: Peach (RGB 255:190:190) Draw Rules: Area2 - Dynamic		



Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE M-III. Oceanographic icons - Continued.

DESCRIPTION	ICON	NOTES
Geophysics/Acoustics Mine Warfare Bottom Descriptors **MIW-Bottom Sediments - Sand and Shells** Symbol Set: 46 Value: 140115 **Color**: Light Peach (RGB 255:220:220) Draw Rules: Area2 - Dynamic		
Geophysics/Acoustics Mine Warfare Bottom Descriptors **MIW-Bottom Sediments - Land** Symbol Set: 46 Value: 140116 **Color**: Gray (RGB 220:220:220) Draw Rules: Area2 - Dynamic		
Geophysics/Acoustics Mine Warfare Bottom Descriptors **MIW-Bottom Sediments - No Data** Symbol Set: 46 Value: 140117 **Color**: Light Gray (RGB 230:230:230) Draw Rules: Area2 - Dynamic		
Geophysics/Acoustics Mine Warfare Bottom Descriptors **Bottom Roughness - Smooth** Symbol Set: 46 Value: 140118 **Color**: Green (RGB 0:255:0) Draw Rules: Area2 - Dynamic		


Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE M-III. Oceanographic icons - Continued.

DESCRIPTION	ICON	NOTES
Geophysics/Acoustics Mine Warfare Bottom Descriptors **Bottom Roughness - Moderate** Symbol Set: 46 Value: 140119 **Color**: Yellow (RGB 255:255:0) Draw Rules: Area2 - Dynamic		
Geophysics/Acoustics Mine Warfare Bottom Descriptors **Bottom Roughness - Rough** Symbol Set: 46 Value: 140120 **Color**: Red (RGB 0:255:0) Draw Rules: Area2 - Dynamic		
Geophysics/Acoustics Mine Warfare Bottom Descriptors **Clutter (Bottom) - Low** Symbol Set: 46 Value: 140121 **Color**: Green (RGB 255:255:0) Draw Rules: Area2 - Dynamic		
Geophysics/Acoustics Mine Warfare Bottom Descriptors **Clutter (Bottom) - Medium** Symbol Set: 46 Value: 140122 **Color**: Yellow (RGB 255:255:0) Draw Rules: Area2 - Dynamic		


Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE M-III. Oceanographic icons - Continued.

DESCRIPTION	ICON	NOTES
Geophysics/Acoustics Mine Warfare Bottom Descriptors **Clutter (Bottom) - High** Symbol Set: 46 Value: 140123 **Color**: Red (RGB 255:0:0) Draw Rules: Area2 - Dynamic		
Geophysics/Acoustics Mine Warfare Bottom Descriptors **Impact Burial - 0%** Symbol Set: 46 Value: 140124 **Color**: Blue RGB (0:0:255) Draw Rules: Area2 - Dynamic		
Geophysics/Acoustics Mine Warfare Bottom Descriptors **Impact Burial - 0-10%** Symbol Set: 46 Value: 140125 **Color**: Green RGB (0:255:0) Draw Rules: Area2 - Dynamic		
Geophysics/Acoustics Mine Warfare Bottom Descriptors **Impact Burial - 10-20%** Symbol Set: 46 Value: 140126 **Color**: Yellow (RGB 255:255:0) Draw Rules: Area2 - Dynamic		

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE M-III. Oceanographic icons - Continued.

DESCRIPTION	ICON	NOTES
Geophysics/Acoustics Mine Warfare Bottom Descriptors **Impact Burial - 20-75%** Symbol Set: 46 Value: 140127 **Color**: Orange (RGB 255:127:0) Draw Rules: Area2 - Dynamic		
Geophysics/Acoustics Mine Warfare Bottom Descriptors **Impact Burial - >75%** Symbol Set: 46 Value: 140128 **Color**: Red (RGB 255:0:00) Draw Rules: Area2 - Dynamic		
Geophysics/Acoustics Mine Warfare Bottom Descriptors **MIW Bottom Category - A** Symbol Set: 46 Value: 140129 **Color**: Green (RGB 0:255:0) Draw Rules: Area2 - Dynamic		
Geophysics/Acoustics Mine Warfare Bottom Descriptors **MIW Bottom Category - B** Symbol Set: 46 Value: 140130 **Color**: Yellow (RGB 255:255:0) Draw Rules: Area2 - Dynamic		


Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE M-III. Oceanographic icons - Continued.

DESCRIPTION	ICON	NOTES
Geophysics/Acoustics Mine Warfare Bottom Descriptors **MIW Bottom Category - C** Symbol Set: 46 **Value:** 140**31** Color: Red (RGB 255:0:0) Draw Rules: Area2 - Dynamic		
Geophysics/Acoustics Mine Warfare Bottom Descriptors **MIW Bottom Type - A1** Symbol Set: 46 Value: 140**32** **Color**: Green (RGB 48:255:0) Draw Rules: Area2 - Dynamic		
Geophysics/Acoustics Mine Warfare Bottom Descriptors **MIW Bottom Type - A2** Symbol Set: 46 Value: 140**33** **Color**: Light Green (RGB 127:255:0) Draw Rules: Area2 - Dynamic		
Geophysics/Acoustics Mine Warfare Bottom Descriptors **MIW Bottom Type - A3** Symbol Set: 46 Value: 140**34** **Color**: Lime Green (RGB 175:255:0) Draw Rules: Area2 - Dynamic		


Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE M-III. Oceanographic icons - Continued.

DESCRIPTION	ICON	NOTES
Geophysics/Acoustics Mine Warfare Bottom Descriptors **MIW Bottom Type - B1** Symbol Set: 46 Value: 140135 **Color**: Yellow-Green (RGB 207:255:0) Draw Rules: Area2 - Dynamic		
Geophysics/Acoustics Mine Warfare Bottom Descriptors **MIW Bottom Type - B2** Symbol Set: 46 Value: 140136 **Color**: Yellow (RGB 255:255:0) Draw Rules: Area2 - Dynamic		
Geophysics/Acoustics Mine Warfare Bottom Descriptors **MIW Bottom Type - B3** Symbol Set: 46 Value: 140137 **Color**: Gold (RGB 255:207:0) Draw Rules: Area2 - Dynamic		
Geophysics/Acoustics Mine Warfare Bottom Descriptors **MIW Bottom Type - C1** Symbol Set: 46 Value: 140138 **Color**: Orange (RGB 255:127:0) Draw Rules: Area2 - Dynamic		


Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE M-III. Oceanographic icons - Continued.

DESCRIPTION	ICON	NOTES
Geophysics/Acoustics Mine Warfare Bottom Descriptors **MIW Bottom Type - C2** Symbol Set: 46 Value: 140**39** **Color**: Dark Orange (RGB 255:80:0) Draw Rules: Area2 - Dynamic		
Geophysics/Acoustics Mine Warfare Bottom Descriptors **MIW Bottom Type - C3** Symbol Set: 46 Value: 140**40** **Color**: Orange-Red (RGB 255:48:0) Draw Rules: Area2 - Dynamic		
Limits Static/Dynamic: N/A Symbol Set: 46 Value: **15**0000	N/A	N/A
Limits **Maritime Limit Boundary** Symbol Set: 46 Value: 15**01**00 **Color**: Magenta Thin Short Dash Line Draw Rules: Line1 - Dynamic		
Limits **Maritime Area** Symbol Set: 46 Value: 15**02**00 **Color**: Magenta Draw Rules: Area2 - Dynamic		

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE M-III. Oceanographic icons - Continued.

DESCRIPTION	ICON	NOTES
Limits **Restricted Area** Symbol Set: 46 Value: 150300 **Color**: Magenta Dashed T Line Draw Rules: Line1 - Dynamic		
Limits **Swept Area** Symbol Set: 46 Value: 150400 **Color**: Pink Dots Draw Rules: Area2 - Dynamic		
Limits **Training Area** Symbol Set: 46 Value: 150500 **Color**: Magenta/Magenta ! In Circle W/ Dashed Outline Draw Rules: Area2 - Dynamic		
Limits **Operator-Defined** Symbol Set: 46 Value: 150600 **Color**: Orange Solid Outline Draw Rules: Area2 - Dynamic		
Man-Made Structures Static/Dynamic: N/A Symbol Set: 46 Value: **16**0000	N/A	N/A

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE M-III. Oceanographic icons - Continued.

DESCRIPTION	ICON	NOTES
Man-Made Structures **Submarine Cable** Symbol Set: 46 Value: 16**01**00 **Color**: Magenta Draw Rules: Line1 - Dynamic		**Line Style**: Repeating pattern wavy lines The points are typically connected with a solid curved lined.
Man-Made Structures **Submerged Crib** Symbol Set: 46 Value: 16**02**00 **Color**: Blue Fill W/ Black Dotted Outline Draw Rules: Area2 - Dynamic		
Man-Made Structures **Canal** Static/Dynamic: D Symbol Set: 46 Value: 16**03**00 **Color**: Black Solid Thick Line Draw Rules: Line1 - Dynamic		
Man-Made Structures **Ford** Symbol Set: 46 Value: 16**04**00 **Color**: Black Symbol Draw Rules: Point1 - Static		
Man-Made Structures **Lock** Symbol Set: 46 Value: 16**05**00 **Color**: Black Symbol Draw Rules: Point1 - Static		

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

TABLE M-III. Oceanographic icons - Continued.


DESCRIPTION	ICON	NOTES
Man-Made Structures **Oil/Gas Rig** Symbol Set: 46 Value: 16**06**00 **Color**: Black Symbol Draw Rules: Point1 - Static		
Man-Made Structures **Oil/Gas Rig Field** Symbol Set: 46 Value: 16**07**00 **Color**: Gray Dot Pattern Fill Draw Rules: Area2 - Dynamic		
Man-Made Structures **Pipelines/Pipe** Symbol Set: 46 Value: 16**08**00 **Color**: Gray Dash Line with Circle Draw Rules: Line1 - Dynamic		
Man-Made Structures **Pile/Piling/Post** Symbol Set: 46 Value: 16**09**00 **Color**: Black Dot Draw Rules: Point1 - Static		

TABLE M-IV. Meteorological space icons.

DESCRIPTION	ICON	DRAW RULES
SPACE Static/Dynamic: N/A Symbol Set: 47 Value: **11**0000	N/A	No icon is associated with this entity. It is for hierarchal purposes only.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

PAGE INTENTIONALLY LEFT BLANK

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

USE OF WARFIGHTING SYMBOLS IN PSEUDO-THREE-DIMENSIONAL DISPLAYS

N.1 SCOPE

N.1.1. Scope. This appendix provides definitions and guidelines for display of Common Warfighting Symbology in pseudo-three-dimensional displays, also known as 2.5D displays. In the context of this appendix, 2.5D display refers to the presentation of information that gives the perception of depth or varying distance, as in a non-orthogonal viewing angle. In other words, it is a viewing angle that is not perpendicular to the surface of the Earth. This is in contrast to several other emerging graphic technologies that will allow for viewing in stereographic or full three-dimensional display. In stereo display, dual images are used to recreate a three-dimensional perception in the human brain.

a. Although there is some discussion of the use of 2.5D symbols, the primary focus of this appendix is the display of the two-dimensional symbols contained in MIL-STD-2525 in a 2.5D display of the surrounding environment. Modeling and simulation standards and methods of portrayal would be more suitable for the display of 2.5D or full three-dimensional symbols and models.

b. This appendix is not a mandatory part of the standard. It is intended for guidance only.

N.2 REFERENCES

This section is not applicable to this standard.

N.3 DEFINITIONS

N.3.1. Billboarding: A method for portraying a symbol in a 2.5D display in which the symbol is perpendicular to the viewing angle.

N.3.2. Cubing: A method for portraying a symbol in a 2.5D display in which the symbol is overlaid on a cube to present a surface visible from the viewing angle.

N.3.3. Curve (line): One-dimensional geometric primitive representing the continuous image of a line.

N.3.4. Geospatial: Pertaining to the geographic location and characteristics of natural or constructed features and boundaries on, above, or below the Earth's surface; especially referring to data that is geographic and spatial in nature.

N.3.5. Glyph: A symbol (as a curved arrow on a road sign) that conveys information nonverbally.

N.3.6. Icon: A sign (as a word or graphic symbol) whose form suggests its meaning.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

N.3.7. Image: The optical counterpart of an object produced by an optical device (as a lens or mirror) or an electronic device.

N.3.8. Marker post (lollipop): A method for portraying a symbol in a 2.5D display in which the symbol is billboarded but also raised above or below the terrain surface by a vertical line.

N.3.9. Model: A miniature representation or simulation.

N.3.10. Pictograph: A picture representing a word or idea; a hieroglyph.

N.3.11. Point: Zero-dimensional geometric primitive, representing a position.

N.3.12. Solid (volume): Three-dimensional geometric primitive, representing the continuous image of a region of Euclidean three space.

N.3.13. Surface (area): Two-dimensional geometric primitive locally representing a continuous image of a region of a plane.

N.3.14. Symbicon: A hybrid of a symbol and icon which attempts to combine the best identification performance benefits of each representation.

N.3.15. Symbol: An object that presents information (MIL-STD-2525). An arbitrary or conventional sign used in writing or printing relating to a particular field to represent operations, quantities, elements, relations, or qualities.

N.3.16. Terrain draping: A method for portraying a symbol in a 2.5D display in which the symbol is overlaid on a terrain surface.

N.3.17. Three-dimensional: Giving the illusion of depth or varying distances.

N.3.18. Two-dimensional: Lacking depth of characterization.

N.4 PSEUDO-THREE-DIMENSIONAL (2.5D) SYMBOLIZATION

N.4.1. Introduction. Symbols are used to convey information about objects in space. In most traditional command and control applications, this has been accomplished by an orthogonal (directly overhead) view, such as when looking at a map. Command and control symbols have been overlaid on top of geospatial information or a “map background” to provide a geospatial context to locate the military object of interest at a geographic position. Attributes of the object are visually encoded in the symbol to communicate information about the object to the observer.

a. As command and control symbology has evolved from hand-annotated paper maps to automated computer display screens, views other than orthogonal have become practical. Non-overhead views or dynamic viewing positions such as “fly-through” displays provide new ways in which a warfighter can better perceive and understand the operational environment.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

b. This appendix establishes some basic terminology for addressing portrayal of information in 2.5D displays and provides advantages, disadvantages and guidance on some of these methods of display. Although some aspects of 2.5D symbols are discussed, the primary focus of this appendix is on portrayal of the two-dimensional symbols contained in MIL-STD-2525 in a 2.5D display. The modeling and simulation (M&S) community has been portraying the environment in 2.5D for a long time and there are M&S standards and symbol libraries available for 2.5D symbology (see N.5.2).

c. This appendix is not intended to be a "standard" as such. New developments in the information technology, computer graphics and the geospatial information systems (GIS) and modeling and simulation industries will undoubtedly eclipse the information provided here.

N.4.2. When to use 2.5D displays. The paramount point when considering the use of 2.5D displays is to recognize that a 2.5D display is not necessarily better than a two-dimensional display for every application. A 2.5D display may look neat and impress a viewing audience, but it must really be evaluated as to whether it presents information better or not as well as a traditional two-dimensional display.

N.4.2.1. Research indicates that using 2.5D displays provide advantages such as:

a. A visual representation that may be useful in understanding the shape or rough spatial layout of scenes

b. More intuitive and natural usage

c. Preferred by users

d. Clearer picture of tactical information (eliminate need to search text boxes for attributes such as altitude and to do mental integration of information from different views). These benefits may also be engineered into 2D displays.[1]

N.4.2.2. Conversely, 2.5D displays have several disadvantages, they are:

a. Prone to distortion (due to association with parameters of perspective)

b. Prone to clutter (less display area near horizon, so more objects are packed into a smaller area; addition of depth cues such as drop lines increase number of objects displayed)

c. Poor for tasks requiring precision, both about objects (e.g., realistic icons do not scale well; distant objects may be too small to recognize) and distances and angles (from foreshortening and inadequate and conflicting depth cues.

[1] Smallman, H. S., St. John, M., Oonk, H. M. and Cowen, M. B. (2001), Information availability in 2D and 3D displays, IEEE Computer Graphics and Application, 21, 51-57.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

N.4.2.3. Research is mixed concerning performance benefits of using 2D or 2.5D displays largely due to the great variety of factors considered in the studies. Also, users may prefer (or rate highly) displays that actually hinder rather than enhance their performance.[2]

N.4.3. Taxonomy of symbols and displays. Symbols can be classified many different ways, including subject area, data structure and visual aspects. A basic taxonomy might look something like this:

N.4.3.1. Subject area.

a. Operational symbols – military operations and control measures

b. Geospatial symbols – provides geospatial context (map background)

N.4.3.2. Delineation type.

a. Point – one coordinate point

b. Line – a series of coordinate points

c. Area – a series of coordinate points in which the line creates a polygon

d. Volume – a polygon or shape with a vertical component

N.4.3.3. Degree of Abstraction.

a. Abstract symbol – a symbol representing an object based on learned association

b. Pictograph or icon – a symbol representing an object based on the symbol looking like the object

c. Symbicon – a hybrid of a symbol and an icon which attempts to combine the best identification performance benefits of each representation.

d. Two-dimensional image – a picture of the object based on varying intensity of reflected energy from the object

e. Pseudo-three-dimensional model – a physical or digital representation of an object

N.4.3.4. Dimensionality.

a. Two-dimensional – a symbol lacking depth of characterization

[2] Smallman, H. S., St. John, M., Oonk, H. M. and Cowen, M. B. (2005), Niive Realism: Misplaced faith in the utility of realistic displays, Ergonomics in Design, 13(3), 6-13, Fernandes, K. Usability of 3D Perspective Displays, SPAWAR and St. John, M, Cowen, M.B., Smallman, H.S. and Oonk, H.M. (2001) The use of 2D and 3D displays for shape understanding versus relative position tasks. Human Factors, 43, 79-98.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

b. Pseudo-three-dimensional (2.5D) – a symbol giving the illusion of depth or varying distances

c. Three-dimensional – a symbol displayed by stereoscopic, holographic, or other means that provides a complete representation of three dimensions.

N.4.3.5. Relative to terrain.

a. Ground clamped – symbol is shown on terrain

b. Elevated – symbol is raised above terrain surface

N.4.4. Geospatial (map) symbols. Geospatial symbology generally follows the “earth surface” and can be draped over elevation data. Typically, operational symbols are shown on a map background to provide a positional reference. Digital geospatial information can be classified into two types.

N.4.4.1. Raster data. Raster data is a method of representing geospatial data characterized by a matrix of evenly spaced rows and columns of data points. These data points (called "pixels" in image and scanned map data) typically represent some value at that point, while the position within the columns and rows determines the geographic position. Raster data structures are typically used to record scanned maps and charts (MC&G graphic data), image data, or gridded data, such as terrain elevation posts in an elevation model.

N.4.4.2. Vector data. Vector data represents each cartographic feature by an entity description (feature code) and a spatial extent (geographic position). Geographic position may be two-dimensional (horizontal position only) or three-dimensional (including elevation). Features are categorized as point, line, or area features. The position of a point feature is described by a single coordinate pair (or triplet for three dimensional data). The spatial extent of a line feature is described by a string of coordinates of points lying along the line, while the extent of an area feature is described by treating its boundary as a line feature. Vector data may be stored in a sequential, chain node, or topological data structure.

N.4.5. Imagery. By its nature, imagery is not symbolized but instead relies on variations in intensity of captured light (or other portion of spectrum or other phenomena) to create a visual picture of the object or phenomena being represented. Imagery can be used as a background display or the picture of an object or piece of equipment.

a. There is a significant difference between raster geospatial data or an image and vector geospatial data. In vector data, geographic features can be filtered or turned on or off in a vector display. In a raster display, the map or image content is fixed and you see whatever was shown on the scanned paper map or image.

N.4.6. Optimum display method. Each type of symbolization has advantages and disadvantages. There is no one right answer. The intended application will determine which method best meets the intended use of the display.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

N.5 GUIDANCE AND PORTRAYAL CONSIDERATIONS IN PSEUDO-THREE-DIMENSIONAL (2.5D) DISPLAYS

N.5.1. Use of 2D symbols in 2.5D display. The symbols provided in the appendices of MIL-STD-2525 were designed for two-dimensional display. They can be used in a 2.5D display, using various visualization techniques, some of which are described below. The visualizations described here are not intended to be an all-encompassing or comprehensive list but merely some of the more common approaches. The intent of this appendix is to provide guidance to implementers on some of the advantages and disadvantages of these visualization techniques.

N.5.1.1. Visualization of icons. The symbols in the various appendices of MIL-STD-2525 for space, air, land, maritime (sea surface and sea subsurface), meteorology, signals intelligence, etc., symbolize units, equipment and installations as point symbols. Each is associated with a single geographic coordinate. The following paragraphs describe several methods of symbolizing point icons.

N.5.1.1.1. Terrain draping. One simple method of displaying two-dimensional symbols in a 2.5D display is to simply place the 2D symbols over the 2.5D surface model (see figure N-1). This makes it appear as if operational symbols were large flags laid out on the ground. With draping, no changes to existing 2D symbols are required. Since the viewing angle is not perpendicular, symbols may be distorted in shape. Depending on the underlying terrain, some symbols may be obscured by higher terrain in between the symbol and the viewing position.




FIGURE N-1. Example of terrain draping of icons.
(Static MOLE layer displayed in ArcGlobe)

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

N.5.1.1.2. Billboarding. Billboarding is a technique in which a two-dimensional symbol is positioned vertically or perpendicular to the view angle (see figure N-2). This makes symbols easier to see than if they were draped over the terrain but is much more computationally demanding, sometimes affecting system performance. Although used in systems, the performance benefits of billboarding have not been validated with performance data. There are several factors that must be considered when orienting the billboard as well. Symbols placed on the ground have to be elevated enough so the entire symbol is visible. If the center of the symbol was co-located with the position on the ground surface, the bottom half of the symbol would be obscured. Billboarding is conceptually different from lollipopping. In fact most billboard displays are raised above ground level. Billboarding refers to placing the 2D symbol perpendicular to view angle, while lollipopping or using a marker post refers to elevating the symbol above or below the terrain surface.




FIGURE N-2. Example of billboarding of icons.
(TOC 3D display)

N.5.1.1.3. Cubing. An alternative to billboarding is to project the 2D symbol onto a 2.5D shape, such as a cube (see figure N-3). As with billboarding, cubes can also be elevated above the terrain surface.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.




FIGURE N-3. Example of cubing of icons.

N.5.1.1.4. Marker post. In many cases, billboarded or cubed symbols are raised above the ground surface using a marker post, a technique sometimes called “lollipopping” (see figure N-4). The user can set an arbitrary height above ground surface and drop down lines connect the symbol to its ground location. In a 2.5D display, tracks that are actually above or below ground or water surface can be portrayed in their actual location. Lollipopping has the potential to create confusion with the actual altitude of an above or below-ground/water track. For example, it might appear that a helicopter is flying underneath a tank. Care must also be taken to distinguish between symbols raised to an arbitrary height above or below the terrain and those symbols showing an actual altitude/depth, if both types are used in the same display.




FIGURE N-4. Example of marker posts.
(TOC 3D display)

N.5.1.2. Visualization of control measure symbols. The control measure symbols in MIL-STD-2525 are more complex than the simple icons in appendix A and contain point, line and area symbols. The techniques for portrayal of line and area symbols are generally similar to the point symbols. Lines may be “draped” over the terrain; but, as with points, draping creates the

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

potential for a symbol to be obscured by intervening terrain (see figure N-5). Line symbols can be extruded above the terrain for visual emphasis, forming what appear to be walls on the terrain surface (see figure N-6). These walls could be used as a background for presenting additional information, such as echelon, status, etc.




FIGURE N-5. Example of draped control measure symbols.
(MOLE in ArcGlobe)




FIGURE N-6. Example of extruded control measure symbols.
(TOC 3D display)

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

N.5.1.3. Symbicon. A symbicon is a hybrid of an abstract symbol with a pictograph or icon that increases the ease of identifying an object[3] (see figure N-7). A typical symbicon may combine the identification code of a symbol, for example "B" for bomber, with the stylized silhouette of an aircraft.




FIGURE N-7. Example of a symbicon.

N.5.2. Pseudo-three-dimensional models. Many systems are starting to use 2.5D models to represent military objects, rather than the 2D symbols contained in MIL-STD-2525 (see figure N-8). Models may work well for portrayal of individual platforms or systems, such as a tank or aircraft, but models work less well or may be impractical for symbolizing larger units. Although in general, users prefer to look at realistic icons, they result in slower, error-prone performance.[4] The level of detail provided by the model may also create recognition problems in the display that reflect the situation in the real world. For example, if an operator were unfamiliar with the appearance of a particular weapons system, it would not make much sense to use a 2.5D model of that weapons system to identify the equipment type. You would also expect recognition errors to occur if two weapons systems were similar in appearance. Overall, traditional symbols were more useful when determining platform identity and affiliation were required. Icons are better for determining some aspects of direction of movement.[5]



FIGURE N-8. Examples of pseudo-three-dimensional models.

N.5.2.1. Modeling and simulation (M&S) standards. The International Organization for Standardization (ISO) 18023, Computer Graphics and Image Processing – Synthetic Environment Data Representation and Interchange Specification (SEDRIS) suite of standards are available for the exchange of modeling and simulation data.

[3] Symbicons: Advanced Symbology for Two-dimensional and Three-dimensional Displays, SPAWAR TR 1850, February 2001
[4] Smallman, H.S., St. John, M.B., Oonk, H.M. and Cowen, M.B. (2000) Track recognition using two-dimensional symbols or three-dimensional realistic icons. SPAWAR Technical Report 1818.
[5] Searching for Tracks Imaged as Symbols or Realistic Icons: A Comparison Between Two-Dimensional and Three-Dimensional Displays, SPAWAR TR 1854, April 2001

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

N.5.2.2. Model libraries. The DOD maintains several libraries of reusable digital models of weapons systems at:

a. Army Model Exchange: https://modelexchange.army.mil

b. M&S Glossary: https://www.msco.mil/MSGlossary_ABR_M.html

c. M&S Coordination Office: https://msco.mil/

d. M&S Resource Repository System: https://www.msco.mil/resource_discovery.html

N.5.3. Design considerations for symbology in a 2.5D display.

N.5.3.1. Symbol location. One important function of a symbol is to indicate where the object is located. MIL-STD-2525, 5.3.13 requires that point icons be positioned so the geometric center, or center of mass of the symbol, corresponds to the actual location of the object. Certain other control measure symbols have specified "anchor points" that differ from the center of mass of the symbol.

N.5.3.1.1. Submergence of symbols. If a symbol is overlain on the terrain ie., terrain draping, it is possible to tie the center of mass of the symbol to the symbol location as in a two-dimensional display and conform to the general rules of MIL-STD-2525. If, however, the symbols are billboarded or shown vertically, then linking the symbol location to the center of mass of the symbol will result in the bottom half of the symbol being below the terrain surface. Billboarding displays generally place bottom of the symbol on the terrain surface. This problem does not occur if the object is an air or sub-surface track and is far enough above or below the terrain surface (ground/water).

N.5.3.1.2. Height above/below terrain surface. Some 2.5D displays use the "lollipop" technique to elevate symbols a fixed distance above the terrain surface. This works well for ground tracks but may cause confusion if ground and air tracks were shown in the same display, since some symbols will be raised an arbitrary height while air tracks will generally show actual altitude of the track.

N.5.3.1.3. Estimating track position. Studies have shown that estimating a track position in a 2.5D display is difficult because many of the visual cues that the human brain uses to estimate a location cannot be duplicated in a 2.5D digital display. Operator performance is increased if artificial cues are added, typically a drop line or drop shadow. A drop line is a vertical line from the above-surface object to the terrain surface. A drop shadow is a silhouette of the object on the terrain surface. These artificial cues can contribute to display clutter. Even two-dimensional displays will benefit by having a distinct "locator point" on the symbol, rather than just using the center of mass of the symbol.[6]

N.5.3.2. Perspective. In a traditional two-dimensional (map-like) display, the perspective is "orthogonal" or viewed from directly overhead; so, there is no change of scale over the display. In a 2.5D view the scale of the display decreases (gets smaller) as distance from the

[6] Track Location Enhancements for Perspective View Displays, SPAWAR TR 1847, December 2000

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

observer increases. This creates difficulty in perceiving the actual location of an object in space. In a two-dimensional display, the elevation of an object is not obvious, but the horizontal position (x,y coordinates) is not in doubt. In a 2.5D display, the latitude, longitude and elevation (x, y and z) aspects of location are each ambiguous. When viewing an object in the real world, a human observer uses a number of visual cues to determine location in three-dimensional space. Objects become smaller with increasing distance. Illumination provides variation in light and dark to specify shape in depth. Closer objects block out objects that are farther away. People see in stereo vision and can judge how far away an object is based on the slight differences in the image in their right and left eyes. In a digital display, many of these real-world cues are impossible or impractical to reproduce. Varying symbol size with distance and closer objects obscuring more distant objects are the most easily implemented visual cues. These visual cues have limitations when implemented in a digital display. Symbols can only be made so small before they becomes unrecognizable; yet, exaggerating their size to make them more legible distorts the appearance of location, making them appear closer than they really are. Closer symbols obscuring symbols that are farther away also makes legibility difficult. Artificial visual cues, not found in the real world but possible on a digital display, such as drop lines and drop shadows (discussed previously), enhance a human's ability to determine the location of an object in a 2.5D display.[6]

N.5.3.3. Direction indicators. In a 2.5D display, the viewing angle is variable, dependent on the viewing position selected by the operator. Typical viewing angles range from 25 to 65 degrees. Unlike map displays, where north is generally displayed oriented to the top of the display, the 2.5D display can be viewed from any direction. In a "fly-through" the viewing direction is changing frequently. There are sezveral methods to provide a visual cue for direction of view, including placing north arrows in the display or showing the heading and attitude in a "heads-up display" type symbol (see figure N-9).




FIGURE N-9. Example of visual cue for direction of view.
(TOC 3D display)

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

N.5.4. Text amplifiers for symbols. Many symbols in MIL-STD-2525 have text fields around them to present additional information. Text fields for point icons are defined in figure 2. Text fields are also found on the control measure symbols and control measures. Showing text around symbols in a 2.5D display creates a number of difficulties. Perhaps the greatest is the perspective in the display. One of the visual cues to create the impression of three dimensions is to show objects that are farther away in a smaller size; however, reducing symbol size, including text, also reduces legibility. Occultation is another visual cue, in which closer objects obscure more distant objects. Closer objects with text around them just create a larger "footprint" in the visual plane, potentially obscuring distant symbols or terrain features. Finally, the text will only be visible if there is enough contrast between the text and the background.

N.5.5. Speed vectors and trailing lines. A speed vector is a line extending in front of a symbol or icon, whose length is proportional to the speed of the object. The speed vector is an easy way to symbolize the speed and the heading of the platform. They are generally used on fast-moving platforms such as air tracks. A trailing line is a line showing the track of a platform, indicating where it has been for a period of time in the past. In a 2.5D perspective display, the record of a track of a platform is sometimes enhanced by using drop lines to indicate the position on the terrain surface. Drop lines are sometimes filtered by time to show only a limited trail and to reduce display clutter.

N.5.6. Incomplete data. One of the difficulties facing implementers of 2.5D displays is that sometimes the track data being symbolized may be incomplete. For example, the latitude and longitude of an air track may be known, but the altitude unknown. This is not a great problem in an overhead two-dimensional display, but in a 2.5D display, where should the air track be shown? If the direction of travel is unknown, which direction should be symbolized? The implementer might choose to ignore the missing data (show the air track on the ground) or infer it from other sources. In either case, a warning indicator should be included with the symbol to indicate to the operator that the track has been symbolized based on incomplete information.

N.5.7. Vertical exaggeration of terrain and tactical symbols. In 2.5D displays, the vertical dimension is often exaggerated to highlight variation in the terrain (see figure N-10). This particular example has a vertical exaggeration of x15. This vertical exaggeration may create distortions in the display, when tactical symbols are also used. For example, if the vertical exaggeration was x3, then the altitude of the air track would also have to be exaggerated by x3 to keep relative position with the terrain.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.




FIGURE N-10. Example of vertical exaggeration.
(TOC 3D display)

N.5.8. Implications for training and doctrine. The use of 2.5D displays in the command and control community is growing. Research into human performance has shown, however, that a 2.5D display is not necessarily the best way to accomplish all tasks. In fact, some tasks are better performed using a conventional "overhead" 2D display or even a conventional map. The types of tasks performed on a C4ISR system should be conducted using a display mode (2D or 2.5D) that best fits the intended task. Operators should be trained to understand which tasks are accomplished best using each display type. User preference often has little bearing on the choice because an operator may like one type of display, even though their performance is degraded, compared to other display modes. Some tasks may be accomplished best using a combination of 2.5D to get an overall impression of the situation and 2D views to do the specific locational analysis needed to accomplish the task.

N.6 NOTES

N.6.1. Graphics displayed in this appendix are from the 3D Visualization and Tactical Symbology Considerations for Command, Control, Communications, Computers, Intelligence, Surveillance and Reconnaissance (C4ISR) Applications, Concurrent Technologies Corporation (CTC) White Paper, April 2, 2004.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.

CONCLUDING MATERIAL

Custodians:
Army – AC
Navy – OM
Air Force – 93
NGA – MP

Preparing activity:
DISA – DC3
(INST-2023-001)

NOTE: The activities listed above were interested in this document as of the date of this document. Since organizations and responsibilities can change, you should verify the currency of the information above using the ASSIST Online database at https://assist.dla.mil.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T07:59Z
Check the source to verify that this is the current version before use.