MILITARY SPECIFICATION
PROJECTILE, 60MM, H.E., M49A3 METAL PARTS ASSEMBLY
(DUCTILE IRON)

1. SCOPE

1.1 This specification covers Projectile 60MM, H.E., M49A3, Metal Parts (ductile iron).

2. APPLICABLE DOCUMENTS

2.1 The following documents of the issue in effect on date of invitation for bids or request for proposal form a part of the specification to the extent specified herein:

SPECIFICATIONS

Military

MIL-A-2550	- Ammunition and Special Weapons, General Specification For
MIL-I-6868	- Inspection Process, Magnetic Particle
MIL-R-11471	- Radiographic Inspection of Metals

STANDARDS

Federal

FED-STD-141	- Paint, Varnish, Lacquer and Related Materials
FED-STD-151	- Metals Test Methods

Military

MIL-STD-105	- Sampling Procedures and Tables for Inspection by Attributes
MIL-STD-109	- Quality Assurance Terms and Definitions
MIL-STD-410	- Qualification of Inspection Personnel (Magnetic Particle and Penetrant)
MIL-STD-1167	- Ammunition Data Card
MIL-STD-1169	- Packaging, Packing and Marking of Inert Ammunition Components
MIL-STD-1235	- Single and Multilevel Continuous Sampling Procedures and Tables for Inspection by Attributes

FSC 1310

Source: https://assist.dla.mil -- Downloaded: 2026-10-18T04:57Z
Check the source to verify that this is the current version before use.

2.1 (Cont'd)

PUBLICATIONS

PA-PD-792 - Equipment, Testing or Measuring For Ammunition Items

DRAWINGS

Munitions Command

D10551909 - Projectile, 60MM, H.E., M49A3 Metal Parts (ductile iron)

IEL-10551909 - Inspection Equipment List for Projectile, 60MM, H.E., M49A3, Metal Parts (ductile iron)

(Copies of specifications, standards, drawings and publications required by suppliers in connection with specific procurement functions should be obtained from the procuring activity or as directed by the contracting officer.)

2.2 Other publications.-The following document forms a part of this specification to the extent specified herein. Unless otherwise indicated, the issue in effect on the date of invitation for bids or request for proposal shall apply.

ASA-B46.1 - Surface texture

(Application for copies should be addressed to the American Standards Association, 10 East 40th Street, New York, New York).

3. REQUIREMENTS

3.1 General.-Materials, parts, and assemblies shall comply with the requirements specified on the applicable drawings, referenced specifications and the following:

3.2 Heat treatment.-The heat treatment of the body casting shall be uniform throughout each lot and shall be austenitized, quenched, and tempered to produce in each body casting the mechanical properties specified on the applicable drawing.

3.3 Metal defects.-The body casting shall be free from cracks, cold shuts, hot tears, inclusions, porosity.

3.3.1 Soundness of casting.-Gas holes, sponge or foreign material shall not exceed the radiographic standards specified below.

Source: https://assist.dla.mil -- Downloaded: 2026-10-18T04:57Z
Check the source to verify that this is the current version before use.

3.3.1.1 Gas holes.

3.3.1.1.1 Area A.

a. Maximum acceptable indications - 6.

b. Maximum dimension of any indication - in accordance with plate for 1/8 inch thick section; view number 6 of ASTM, E192.

c. Minimum spacing between the indications - 3 times the largest dimension of the largest of the two adjacent holes.

3.3.1.1.2 Area B.

a. Maximum acceptable indications - 4.

b. Maximum dimension of any indication - in accordance with plate for 3/8 inch thick section; view number 6 of ASTM, E192.

c. Minimum spacing between two indications - 3 times the largest dimension of the largest of the two adjacent holes.

3.3.1.2 Shrinkage sponge.

3.3.1.2.1 Area A.

a. Maximum acceptable indications - 3.

b. Maximum acceptable dimension of any indication - in accordance with plate for 1/8 inch thick section; view number 6 of ASTM, E192.

3.3.1.2.2 Area B.

a. Maximum acceptable indications - 3.

b. Maximum acceptable dimension of any indication - in accordance with plate for 3/8 inch thick section; view number 6 of ASTM, E192.

3.3.1.3 Foreign material less dense.

3.3.1.3.1 Area A.-In accordance with plate for 1/8 inch section; view number 6 of ASTM, E192.

3.3.1.3.2 Area B.-In accordance with plate for 3/8 inch thick section; view number 4 of ASTM, E192.

Source: https://assist.dla.mil -- Downloaded: 2026-10-18T04:57Z
Check the source to verify that this is the current version before use.

3.4 Protective coating.-Protective coating shall be in accordance with the applicable drawing and the specifications referenced thereon.

3.5 Proving ground functional tests.-The projectile metal parts assembly shall reveal no evidence of failure when tested at excess and service pressure. Metal parts failure shall be:

a. Projectile body deformation attributable to noncompliance with drawing and specification requirements.

b. Breakup of the component, in the mortor tube or in flight.

3.6 Workmanship.-The requirements for workmanship are as shown on the applicable drawings, in the applicable specifications, and the following:

3.6.1 Surface finish.-The requirements for surface finish are as detailed on the applicable drawings. The cavity shall be free of burrs, scale, fins, deep seams, pits or other surface discontinuities.

3.6.2 Threads.-Threads shall be full and undamaged for the entire minimum length as required by the applicable drawings and shall be in accordance with the provisions of MIL-A-2550.

3.6.3 Burr.-No part shall have a burr which might interfere with the assembly or function of the round or which might be injurious to personnel handling the item.

3.6.4 Foreign matter.-No part of assembly shall contain dirt, grease, chips, rust, corrosion or other foreign matter. Particular attention shall be given to the cavity of the assembly to insure that no grit, scale or other foreign matter remains therein after final cleaning.

4. QUALITY ASSURANCE PROVISIONS

4.1 Responsibility for inspection.-Unless otherwise specified in the contract or purchase order, the supplier is responsible for the performance of all inspection requirements specified herein. Except as otherwise specified in the contract or order, the supplier may use his own, or any other facilities suitable for the performance of the inspection requirements specified herein, unless disapproved by the Government. The Government reserves the right to perform any of the inspections set forth in the specification where such inspections are deemed necessary to assure supplies and services conform to prescribed requirements.

Source: https://assist.dla.mil -- Downloaded: 2026-10-18T04:57Z
Check the source to verify that this is the current version before use.

4.1.1 Quality assurance terms and definitions.-Reference shall be made to MIL-STD-109 to define quality assurance terms used.

4.1.2 Inspection.-Inspection shall be in accordance with MIL-A-2550, except as specified herein.

4.1.3 Inspection criteria.

a. Successful passage of all inspections required by the drawings and specifications shall be considered as a condition precedent to performing the proving ground functional tests (see 3.5).

b. Acceptance or rejection of a lot by the Government shall be contingent on successful passage of the proving ground functional tests.

4.2 First article sample.

4.2.1 Initial production sample.-At the beginning of regular production a sample shall be submitted in accordance with contract requirements and shall consist of 70 metal parts assemblies as follows:

55 metal parts assemblies complete, painted
15 metal parts assemblies complete, unpainted

Fifty of the above-painted metal parts assemblies shall be forwarded to a designated proving ground for ballistic testing. The sample shall be manufactured using the same materials, equipment, processes and procedures as used in regular production. All parts and materials, including packaging and packing, shall be the same as used for regular production and shall be obtained from the same source of supply.

4.2.1.1 Examination and test.-After inspection and provisional acceptance at source, the sample shall be inspected for all requirements of the drawings and specifications at a Government laboratory or such other facility specified in the contract.

4.2.1.2 Initial production sample failure.-Failure of the sample to comply with the requirements of the drawings and specifications shall result in sample disapproval.

4.3 Inspection.

4.3.1 Lot.

4.3.1.1 Submission of product.-The product shall be submitted in accordance with MIL-STD-105.

Source: https://assist.dla.mil -- Downloaded: 2026-10-18T04:57Z
Check the source to verify that this is the current version before use.

4.3.1.2 Heat treatment lot.-A heat treatment lot shall consist of one or more casting lots not to exceed four hours of continuous foundry production or a maximum of 5,000 items, whichever is greater. All castings in a heat treatment lot shall be subjected to the same heat treatment cycle (temperature and time) in the same type of furnace equipment. The lot thus constituted shall be the basis for selection of sample castings to be used for the tension test hereinafter prescribed.

4.3.2 Examination.-One hundred percent examination shall be performed on all critical defects. Examination for major and minor defects shall be performed on a defect basis in accordance with the classification of defects contained herein, using the sampling plans contained in MIL-STD-105. Continuous sampling plans in accordance with MIL-STD-1235 may be used if approved by the procuring activity. An AQL of 0.40 percent for each major defect and an AQL of 0.65 percent for each minor defect shall be used. All nonconforming material shall be rejected. Four power (4X) magnification may be used in performing visual examination. The roughness comparison specimens prescribed by ASA-B46.1 shall be used as a basis for surface roughness determination.

4.3.2.1 Tool control dimensions.-Dimensions marked tool control shall be gaged at the beginning of each eight hours production from each machine in operation and whenever tooling is replaced. Where destruction of components is necessary to inspect these dimensions, measurements of the tool may be substituted provided that the contractor has established correlation between the tool dimensions and the component dimensions prior to the start of production. The contractor shall be responsible for maintaining adequate surveillance to assure that drawing requirements are being met throughout the life of the tool.

4.3.2.2 Metal parts, Drawing D10551909 (before paint).

Defect	Method of Inspection
CRITICAL	
1. Metal defective	Visual
MAJOR	
101. Weight	Approved Scale
102. Concentricity of large threads with bourrelet, including perpendicularity of front face	Gage
103. Concentricity of taper at nose with bourrelet	Gage
104. Concentricity of taper at rear with bourrelet	Gage
105. Concentricity of samll threads with bourrelet, including perpendicularity of rear face	Gage

Source: https://assist.dla.mil -- Downloaded: 2026-10-18T04:57Z
Check the source to verify that this is the current version before use.

4.3.2.2 (Cont'd)

	Defect	Method of Inspection
106.	Diameter of bourrelet, min.	Gage
107.	Diameter of body, min.	Gage
108.	Depth from front face to base of large cavity	Gage
109.	Depth from rear face to base of small cavity, max.	Gage
110.	Depth of bourrelet grooves	Gage
111.	Length from front face to first outside basic diameter	Gage
112.	Length from front face to second outside basic diameter	Gage
113.	Length from front face to third outside basic diameter	Gage
114.	Length from front face to fourth outside basic diameter	Gage
115.	Length from rear face to rear outside basic diameter	Gage
116.	Length from front face to rear of bourrelet	Gage
117.	Width of small thread undercut, max.	Gage
118.	Wall thickness at rear basic length	Gage
119.	Wall thickness at forward basic length	Gage
120.	Variation in wall thickness	Gage
121.	Foreign matter in cavity	Visual

MINOR

201.	Diameter of small thread cavity undercut	Gage
202.	Depth of large thread cavity, max.	Gage
203.	Length total	Gage
204.	Radii or chamfers missing or incorrect	Visual (See 6.1)
205.	Surface finish improper	Visual
206.	Burr	Visual
207.	Foreign matter (except as otherwise classified)	Visual

4.3.2.3 Metal parts, Drawing D10551909 (after paint).

CRITICAL

1.	Magnetic particle stamp missing (indicating failure to pass magnetic particle inspection)	Visual
2.	Hydrostatic test stamp missing (indicating failure to pass hydrostatic test)	Visual
3.	Air pressure stamp missing (indicating failure to pass air test)	Visual

Source: https://assist.dla.mil -- Downloaded: 2026-10-18T04:57Z
Check the source to verify that this is the current version before use.

4.3.2.3 (Cont'd)

Defect		Method of Inspection
MAJOR		
101.	Pitch diameter of large thread, max.	Gage
102.	Minor diameter of large thread, max.	Gage
103.	Pitch diameter of small thread, max.	Gage
104.	Minor diameter of small thread, max.	Gage
105.	Pitch diameter of large thread, min.	Gage
106.	Pitch diameter of small thread, min.	Gage
107.	Diameter of bourrelet, max.	Gage
108.	Length of effective thread, min. (forward)	Gage
109.	Length of thread, min. (rear)	Gage
110.	Paint in cavity inadequate	Visual
111.	Pool of paint in cavity	Visual
112.	Thread(s) damaged or not full	Visual
113.	Foreign matter	Visual
MINOR		
201.	Paint on threads	Visual
202.	Paint not dry	Visual/Taxtile
203.	Paint inadequate or damaged	Visual
204.	Marking missing, incorrect or illegible	Visual
205.	Corrosion preventive compound missing from rear threads	Visual
206.	Corrosion preventive compound missing from forward threads	Visual

4.3.2.4 Packed carton (prior to sealing).

CRITICAL		
	None defined	
MAJOR		
	None defined	
MINOR		
201.	Support missing or damaged	Visual
202.	Separator missing or damaged	Visual
203.	Improper assembly	Visual
204.	Incorrect number in carton	Visual

Source: https://assist.dla.mil -- Downloaded: 2026-10-18T04:57Z
Check the source to verify that this is the current version before use.

4.3.2.5 Packed carton (after sealing).

Defect	Method of Inspection
CRITICAL	
None defined	
MAJOR	
None defined	
MINOR	
201. Carton damaged, cut or gouged through all layers	Visual
202. Carton not completely sealed	Visual
203. Contents loose	Visual
204. Marking missing, incorrect or illegible	Visual

4.3.3 Inspection testing.-The following tests shall be performed in accordance with the provisions of 4.4:

4.3.3.1 Mechanical properties.

4.3.3.1.1 Hardness.

4.3.3.1.1.1 Heat treatment lots.-In order to determine uniformity of heat treatment, each body heat treated in the heat treatment lot (as defined by 4.3.1.2) shall be subjected to a hardness test by any method of hardness testing approved by the procuring activity.

4.3.3.2 Tension test.

4.3.3.2.1 Heat treatment lots.-Two bodies, one of the hardest and one of the saftest as determined by the hardness test shall be subjected to this test. Failure of any tension test specimen to comply with the mechanical properties requirements of the applicable drawing shall be cause for rejection of the lot.

4.3.3.3 Magnetic particle inspection.

4.3.3.3.1 The contractor shall perform 100 percent magnetic particle inspections on all body castings. The magnetic particle inspection shall be performed in accordance with the contractor's approved procedure and shall proceed through each cycle: i.e., magnetize, apply suspension, drain, visually inspect, demagnetize and clean.

Source: https://assist.dla.mil -- Downloaded: 2026-10-18T04:57Z
Check the source to verify that this is the current version before use.

4.3.3.3.1.1 If at any time a magnetic particle indication is present and the contractor is in doubt as to whether it is a true indication or not, he will be permitted to demagnetize the casting and re-inspect it.

4.3.3.3.1.2 All body castings containing magnetic particle indications shall be rejected. The Government reserves the right to have such castings examined by whatever means necessary to determine compliance or noncompliance with paragraph 3.3.

4.3.3.4 Hydrostatic test.-Prior to gaging, each body shall be subjected to an internal hydrostatic pressure to determine compliance with the applicable drawing. Failure of any body to comply shall be cause for rejection of the body. Bodies which comply shall be stamped with the letter "H" as indicated on the assembly drawing.

4.3.3.5 Air pressure test.-Each body that has passed the hydrostatic pressure test as indicated by the letter "H" stamped on the body, shall be subjected to a submerged air pressure test to determine compliance with the applicable drawing. Failure of any body to comply as evidenced by the presence of air bubbles rising to the surface of the water shall be cause for rejection of the body. Bodies which comply shall immediately upon removal from the test fixture be stamped with the letter "A" as indicated on the assembly drawing.

4.3.3.6 Radiographic inspection.

4.3.3.6.1 Finish machined projectiles from each foundry which have received visual examination for surface defects, hydrostatic test, air test and magnetic particle inspection and found acceptable shall be examined by radiographic inspection until 1500 consecutive projectiles have met the requirements of 3.3.1.

4.3.3.6.2 Reduced inspection may then be instituted, consisting of 12 finish machined projectiles which have received visual examination for surface defects, hydrostatic test, air test and magnetic particle inspection and found acceptable shall be randomly selected from each eight hours production or fraction thereof and examined by radiographic inspection. Failure of any projectile to comply with the requirements of 3.3.1 shall be cause for rejection of the production represented by the sample. In the event of a reject, the radiographic inspection shall revert back to 4.3.3.6.1.

Source: https://assist.dla.mil -- Downloaded: 2026-10-18T04:57Z
Check the source to verify that this is the current version before use.

4.3.3.7 Cleaning and application of protective coating.-The sample size and acceptance criteria for the inspection of cleaning the item and the application of protective coating shall be as specified in the applicable specification. Failure to comply with the requirements shall be cause for taking the corrective action recommended therein.

4.3.4 Functional.-The following proving ground tests will be performed by the Government:

4.3.4.1 First article sample.

4.3.4.1.1 Initial production sample.-The quantities listed in Table I shall be ballistically tested in the phases indicated.

TABLE I

Phase	Quantity
Excess pressure	25
Service pressure	25

4.3.4.2 Production lot sample.-The quantities listed in Table II shall be ballistically tested in the phases indicated.

TABLE II

Phase	Quantity
Excess pressure	10 each lot
Service pressure	10 each lot

4.3.4.3 Excess pressure.-Samples provided in accordance with Tables I and II will be subjected to this test. Failure of any projectile assembly to comply with 3.5 shall be cause for rejection of the initial production sample of the production lot represented by the sample.

4.3.4.4 Service pressure.-Samples provided in accordance with Tables I and II will be subjected to this test. Failure of any projectile assembly to comply with 3.5 shall be cause for rejection of the initial production sample or the production lot represented by the sample.

Source: https://assist.dla.mil -- Downloaded: 2026-10-18T04:57Z
Check the source to verify that this is the current version before use.

4.3.5 Inspection equipment.-Index of Inspection Equipment List Number IEL-10551909 identifies the inspection equipment required to perform the examination and tests prescribed herein. Equipment design shall be in accordance with the code designation on the applicable IEL. Reference is made to the index of inspection equipment list for definition of coding format.

4.4 Test methods and procedures.

4.4.1 Mechanical properties.

4.4.1.1 Hardness test.-Prior to finish machining, the hardness test shall be performed on the body. One hardness reading shall be taken at the location of the bourrelet area. The tests shall be performed using the equipment and procedures for performing this test as prescribed by Federal Test Method Standard No. 151.

4.4.1.2 Tension test.-From the samples provided by 4.3.3.2.1, two tension test specimens conforming to the largest obtainable standard "R" type specimen, as prescribed by Federal Test Method Standard No. 151 shall be taken longitudinally from each side of the body 180 degrees apart. The number of specimens and their location are for the convenience of the contractor and Government and shall not restrict the contractor or Government from testing additional specimens at other locations if necessary to determine that the mechanical properties of the projectile body meet the drawing requirements. Procedures and criteria for determining yield strength elongation shall be as prescribed by Federal Test Method Standard No. 151, Except that elongation shall be measured to the nearest thousandth (0.001) prior to conversion into percent elongation. Percent elongation shall be recorded to the nearest tenth (0.1).

4.4.2 Magnetic particle inspection.-The procedures for performing this test utilizing the wet fluorescent method shall be as specified in MIL-I-6868, for indirect magnetization by either the continuous method or the residual method, utilizing a circular magnetic field. The suspension shall be applied to the entire body, inside and outside. After draining, the body shall be thoroughly inspected in a darkened area under an ultra-violet light which will produce adequate fluorescence of the magnetic particles. The solid content of the suspension shall be maintained at 0.15 to 0.4 milliliter (ml) of solids per 100 ml of suspension. The suspension shall be checked at the start of each day's production and at intervals of not over 4 hours of continuous operation, utilizing the procedures and equipment prescribed by specification MIL-I-6868. When performing the test for solid content of the suspension, if it is determined that it does not comply, all projectile bodies that have been tested and accepted since the last satisfactory test was performed shall be re-tested after the suspension has been brought to the proper level. After acceptance the body shall be demagnetized and cleaned prior to stamping. The magnetic particle inspection shall be performed on equipment that complies with the requirements of PA-PD-792. The operator(s) of the equipment and inspector(s) making the determinations shall be certified in accordance with MIL-STD-410.

Source: https://assist.dla.mil -- Downloaded: 2026-10-18T04:57Z
Check the source to verify that this is the current version before use.

4.4.3 Hydrostatic test.-The body shall be hydrostatically tested using equipment capable of performing the test accurately and consistently. In performing the test, the pressure will be applied gradually until the required minimum pressure is reached, after which the pressure will be held for a minimum of 5 seconds. The equipment shall be calibrated prior to the start of each day's operation and at intervals of not over 2 hours of continuous operation. It shall also be calibrated prior to re-starting the operation after a layoff of one hour or more.

4.4.4 Air pressure test.-This test shall be made using equipment capable of performing the test accurately and consistently. Bodies shall be mounted in an approved fixture in such a manner that the body shall be completely submerged in water; the required air pressure shall be applied and held for a minimum of 15 seconds. The water in the tank shall be permitted to settle after immersion of the assemblies prior to the start of timing. Observation for evidence of leakage shall be made for the entire time the assembly is required to be pressurized. The equipment shall be calibrated at the start of each day's operation and at intervals of 4 hours and after a stoppage of 3 hours or more.

4.4.5 Radiographic inspection.-The procedures for performing radiographic inspection shall be as specified in MIL-R-11471 except for the following changes:

a. Delete references to MIL-R-11468 and MIL-R-11469.

b. Delete paragraphs 3.4.2, 3.4, 3.11.2, 4.2.1, 4.2.2, 4.2.3, 4.3.1, 4.4, 4.4.1 and 4.4.2.

c. Add to paragraph 4.2.4: Penetrameters shall be placed on each of two blocks of metal 3/4 x 1-1/2 (2 times the wall thickness of the shell of the section radiographed) of the same material or a material of similar density of the item being radiographed. The thickness of each block represents double the wall thickness at each of two sections as specified. Wall thickness shall be measured at approximately 1.7 inches and 3.8 inches from the nose end. The 3/4 inch x 1-1/2 inches faces shall be normal and be within the outer edge of the cone of radiation. The projectile bodies shall be radiographed at a zero degree position and rotated 90 degrees and radiographed again. Two penetrameters shall appear on each radiographic negative submitted. Prior to radiographic inspection, the blocks, penetrameters, equipment and radiographic inspection procedures shall be approved by the responsible Government procurement agency.

Source: https://assist.dla.mil -- Downloaded: 2026-10-18T04:57Z
Check the source to verify that this is the current version before use.

4.4.6 Protective coating.-The procedures for testing the cleaning and surface treatment methods for the components and assemblies, shall be in accordance with the methods and criteria for testing as specified in the applicable specifications. The salt spray test prescribed by the applicable drawing shall be performed utilizing the equipment and procedures specified by Federal Test Method Standard No. 141.

4.4.7 Proving ground functional tests.

4.4.7.1 Excess pressure.-The samples supplied in accordance with Tables I and II, inert loaded to the service weight and dummy fuzed will be assembled into complete rounds and fired for recovery in a mortar for which the round is standard. The propellant charge will be adjusted to produce 112 percent of the maximum rated pressure of the round in a new mortar.

4.4.7.2 Service pressure.-The samples supplied in accordance with Tables I and II, inert loaded and fuzed, will be assembled into complete rounds utilizing the service charge and fired in a mortar for which the round is standard, for comparison with an equal number of rounds from a reference lot. The sample round and reference rounds will be fired alternately. Horizontal and vertical distances will be recorded for each round fired for determination of horizontal and vertical probable error (PE) in mils to assess accuracy. Data obtained will be recorded for information only and forwarded to the cognizant technical agency.

5. PREPARATION FOR DELIVERY

5.1 Packing.

5.1.1 Level C.-Bodies shall be packed in accordance with the requirements of MIL-STD-1169.

5.2 Packaging, packing and marking.-Packaging, packing and marking shall be in accordance with MIL-STD-1169.

5.3 Data cards.-Data card information shall be as specified in MIL-STD-1167.

6. NOTES

6.1 Visual examination qualification.-When compliance with the applicable requirement is in doubt as a result of visual examination, this characteristic may be measured or gaged to determine acceptability.

Custodian:

Army - MU

Preparing activity:

Army - MU

Project No. 1310-A075

Source: https://assist.dla.mil -- Downloaded: 2026-10-18T04:57Z
Check the source to verify that this is the current version before use.

SPECIFICATION ANALYSIS SHEET

Form Approved
Budget Bureau No. 22-R255

INSTRUCTIONS: This sheet is to be filled out by personnel, either Government or contractor, involved in the use of the specification in procurement of products for ultimate use by the Department of Defense. This sheet is provided for obtaining information on the use of this specification which will insure that suitable products can be procured with a minimum amount of delay and at the least cost. Comments and the return of this form will be appreciated. Fold on lines on reverse side, staple in corner, and send to preparing activity. Comments and suggestions submitted on this form do not constitute or imply authorization to waive any portion of the referenced document(s) or serve to amend contractual requirements.

SPECIFICATION

ORGANIZATION

CITY AND STATE

CONTRACT NUMBER

MATERIAL PROCURED UNDER A

☐ DIRECT GOVERNMENT CONTRACT ☐ SUBCONTRACT

1. HAS ANY PART OF THE SPECIFICATION CREATED PROBLEMS OR REQUIRED INTERPRETATION IN PROCUREMENT USE?

A. GIVE PARAGRAPH NUMBER AND WORDING.

B. RECOMMENDATIONS FOR CORRECTING THE DEFICIENCIES

2. COMMENTS ON ANY SPECIFICATION REQUIREMENT CONSIDERED TOO RIGID

3. IS THE SPECIFICATION RESTRICTIVE?

[ ] YES [ ] NO *(If "yes", in what way?)*

4. REMARKS *(Attach any pertinent data which may be of use in improving this specification. If there are additional papers, attach to form and place both in an envelope addressed to preparing activity)*

SUBMITTED BY *(Printed or typed name and activity - Optional)*

DATE

DD FORM JAN 66 1426

REPLACES EDITION OF 1 OCT 64 WHICH MAY BE USED.

Source: https://assist.dla.mil -- Downloaded: 2026-10-18T04:57Z
Check the source to verify that this is the current version before use.

FOLD

Department of the Army

Frankford Arsenal
Philadelphia, Pa. 19137

OFFICIAL BUSINESS

POSTAGE AND FEES PAID
Department of the Army

Commanding Officer
Frankford Arsenal
ATTN: SMUFA-N1100
Philadelphia, Pa. 19137

FOLD

Source: https://assist.dla.mil -- Downloaded: 2026-10-18T04:57Z
Check the source to verify that this is the current version before use.