MIL-R-46762(MO)
AMENDMENT 2
6 March 1970
SUPERSEDING
AMENDMENT I
5 August 1965

MILITARY SPECIFICATION

RUBBER STOCK, UNVULCANIZED:
TRACK SHOES, PADS, AND PIN BUSHINGS

This amendment forms a part of Military Specification MIL-R-46762(MO) 17 May 1963.

Paragraph 2.1, under "SPECIFICATIONS, Military" delete "JAN-P-100" and "MIL-V-45349" with their respective titles.

Paragraph 2.1, under "STANDARDS, Military" add: "MIL-STD-1186- Cushioning, Anchoring, Bracing, Blocking, and Waterproofing; with appropriate Test Methods."

Paragraph 3.1, delete in its entirety and substitute:

"3.1 First Article. A first article of the unvulcanized rubber stock to be furnished under this specification shall be produced prior to the manufacture of this item in production quantities. The first article shall be submitted to the Government for first article inspection to determine conformance to the quality assurance provisions of this specification (see 4.3). The first article submitted by a contractor shall be fully representative of the unvulcanized rubber stock to be supplied from production facilities and tooling."

Page 3, Table II, line 12. Delete "Before aging at 300 percent elongation, psi, min.....2000."

Page 3, Table II, line 11. Add "2000" under "shoes and pads" column for 400 percent elongation, psi, min.

Paragraph 3.12, delete in its entirety and substitute:

"3.12 Workmanship. Workmanship shall be such as to produce track shoes and pads free from blisters, cracks, folds, back grinding, flash, cuts, and non-fill (aircheck) (see 6.3)."

Paragraph 4.1, delete in its entirety and substitute:

"4.1 Responsibility for inspection. Unless otherwise specified in the contract or purchase order, the supplier is responsible for the performance of all inspection requirements as specified herein. Except as otherwise

FSC-2530

Source: https://assist.dla.mil -- Downloaded: 202610-22T06:52Z
Check the source to verify that this is the current version before use.

specified in the contract or order, the supplier may use his own or any other facilities suitable for the performance of the inspection requirements specified herein, unless disapproved by the Government. The Government reserves the right to perform any of the inspections set forth in the specification where such inspections are deemed necessary to assure supplies and services conform to prescribed requirements."

Paragraph 4.2, line 4, delete "Qualification" and substitute "First Article" line 5, delete "Acceptance" and substitute "Quality Conformance"

Paragraph 4.3, delete in its entirety and substitute:

"4.3 First article inspection. A first article sample consisting of the following shall be submitted for first article inspection:

a. Five (5) pounds of unvulcanized bushing stock and five (5) pounds of unvulcanized block stock. This material should be in mill sheet form and between .250" and .375" thick.
b. One (1) shoe assembly consisting of blocks, pins and bushings already assembled to shoe.
c. Two (2) rubberized block (unassembled) for double pin track and/or one (1) rubberized shoe for single pin track.
d. One (1) pin with bushing assembled.
e. Six (6) test slabs, 6 x 6 x 0.080 ± .005 inch.
f. Six (6) bushing specimens, 0.250 ± .005 thick and 0.700 ± .005 inch in diameter.

The samples shall be representative of the units proposed to be furnished under the contract. First article inspection shall be conducted by the Government, at a place designated by the procuring activity (see 6.2). The first article inspection shall consist of first article tests specified in Table IV, examination for the defects specified in paragraph 4.4.2.2 and shall include the road test if specified (see 6.2). When the road test is specified unvulcanized rubber stock extruded to conform to specified drawings (see 6.2) as applicable will be required in the following amounts:

110 pieces - Track block, ground side.
110 pieces - Track block, wheel side.
440 pieces - Pin bushing.

The samples shall be examined for defects specified in 4.4 and after vulcanization to their intended use, subjected to the applicable tests specified in table IV.

Processing instructions. The instructions shall include the curing temperature and curing time within the limits as specified in 3.2."

Source: https://assist.dla.mil -- Downloaded: 202640-22T06:52Z
Check the source to verify that this is the current version before use.

Paragraph 4.3.1, - Delete in its entirety and substitute:

"4.3.1 Failure. Failure of a first article to pass any examination or test specified herein may be cause, at the option of the Government, for refusal to conduct additional testing until the faults revealed by the test have been corrected."

Paragraph 4.4, delete "Acceptance" and substitute "Quality conformance"

Paragraph 4.4.1.2, lines 1 and 2, Delete "acceptance" and substitute "quality conformance."

Paragraph 4.4.1.3, lines 1 and 2, Delete "acceptance" and substitute "quality conformance."

Page 5, Table IV, Column 4, Delete "Qualification" and substitute "First article."

Column 6, Delete "Acceptance" and substitute "Quality conformance."

Paragraph 4.4.2, Delete "Examination inspection" and substitute "Quality conformance examination."

Paragraph 4.4.3, Delete "Testing inspection" and substitute "Quality conformance tests."

Paragraph 4.4.3.1, line 1, Delete "Acceptance."

Paragraph 4.4.4.2, lines 1 and 2, Delete "acceptance" and substitute "quality conformance."

Paragraph 4.4.4.3, lines 1, 2 and 3, Delete "acceptance" and substitute "quality conformance."

Paragraph 4.4.6.1, Delete "Acceptance" and substitute "Quality conformance."

Paragraph 4.5, last four lines, Delete "Headquarters," "Center, Detroit Arsenal, Centerline, Mich., ATTN: SMOTA-RCM." and substitute "Command, ATTN: AMSTA-BMR, Warren, Michigan 48090."

Paragraph 4.7.3, lines 3 and 4, Delete "Specification JAN-P-100" and substitute "MIL-STD-1186."

Paragraph 6.2, and "(g) If road test is to be run (see 4.3)."

Add (h) "where first article inspection will be conducted (see 6.6)."

Paragraph 6.6, delete in its entirety and substitute:

Source: https://assist.dla.mil -- Downloaded: 202640-22T06:52Z
Check the source to verify that this is the currentversion before use.

"6.6 First Article Inspection. Unless otherwise specified (see 6.2), first article inspection will be conducted by U.S. Army Tank-Automotive Command, ATTN: AMSTA-BMR, Warren, Michigan 48090."

NOTICE, page 10, Delete in its entirety.

Custodian:
Army - AT

Preparing activity:
Army - AT
Project No. 2530-A0183

Source: https://assist.dla.mil -- Downloaded: 202640-22T06:52Z
Check the source to verify that this is the currentversion before use.