6 August 1959

MILITARY SPECIFICATION
TELESCOPE MARK 116 Mod 0

1. SCOPE

1.1 This specification covers the requirements for procurement of the Telescope Mark 116 Mod 0.

2. APPLICABLE DOCUMENTS

2.1 The following documents of the issue in effect on date of invitation for bids form a part of this specification.

SPECIFICATIONS

FEDERAL

PPP-B-585 - Boxes; Wood, Wirebound.
PPP-B-601 - Boxes; Wood, Cleated Plywood.
PPP-B-621 - Boxes; Wood, Nailed and Lock-Corner.

MILITARY

MIL-L-10547 - Liners, Case, Waterproof
MIL-S-18727 - Synchro Control (for Telescope Mark 102 Mod 2).

STANDARDS

MILITARY

MIL-STD-108 - Definitions of and Basic Requirements for Enclosures for Electronic Equipment.
MIL-STD-129 - Marking for Shipment and Storage.
MIL-STD-167 - Mechanical Vibrations of Shipboard Equipment

DRAWINGS

BUREAU OF ORDNANCE

DR. 181117 - Shock Test Stand for Circuit Breakers and Control Equipment.
LD 412561 - Telescope Mark 116 Mod 0 (Assembled Unit) List of Drawings, Subassemblies, Connecting Parts, etc.

FCS 6650

Source: https://assist.dla.mil -- Downloaded: 2026-10-19T11:11Z
Check the source to verify that this is the current version before use.

PUBLICATIONS

BUREAU OF ORDNANCE

OP 400 - General Instructions for the Design, Manufacture, and Inspection of Naval Ordnance Equipment.
NAVORD OD 16421 - Factory Acceptance Test for Telescope Mark 116 Mod 0

(Copies of specifications, standards, drawings, and publications required by contractors in connection with specific procurement functions should be obtained from the procuring activity or as directed by the contracting officer).

3. REQUIREMENTS

3.1 General requirements. - Requirements for manufacture shall be in accordance with Publication OP 400. The telescope shall conform to LD 412561 and all documents listed thereon, this specification, and the contract or order.

3.2 Preproduction sample. - Unless otherwise specified in the contract or order (see 6.2), a preproduction sample is required (see 4.3.1) for each such contract or order. Samples shall be manufactured using the methods, procedures, and plant location proposed for the production lot. Samples shall be inspected as specified under 4.4, such inspection being for the purpose of determining that the manufacturer's production process will produce telescopes that will meet the requirements of this specification.

3.3 Optical and mechanical requirements. -

3.3.1 Internal cleanness. - The optical components shall be carefully cleaned before being assembled into the telescope to ensure freedom from dust, dirt, moisture, fingerprints, and other foreign matter. Telescope compartments shall be clean and dust free before optical components are assembled therein. The assembled telescope shall be internally clean.

3.3.2 Filter knob. - The filter knob shall operate freely and smoothly to position either the filter or the compensating glass in the line of sight. The filter, or compensating glass, shall be positively held when in the line of sight position.

3.3.3 Eyepiece focus. - The eyepiece focusing knob shall operate freely and smoothly over the full movement of the eyepiece mount (plus 1 to minus 3 diopters). The diopter scale shall read 0 $\pm$ 1/4 diopter when the eyepiece is at infinity focus.

3.3.4 Optical cementing. - The cement film binding optical elements together shall be free from foreign particles, bubbles, cement starts, milkiness, and other defects that might reduce the effectiveness of the telescope. Excess cement shall be removed from the exterior of cemented parts. No reagent shall be used that could be absorbed into the cement film and cause subsequent deterioration of the cement film or cement starts. All cemented optical elements shall be marked with symbol "CC" indicating cellulose caprate cement. Marking shall be on the edge of lenses.

Source: https://assist.dla.mil -- Downloaded: 2026-10-19T11:11Z
Check the source to verify that this is the current version before use.

3.3.5 Parallax. - There shall be no apparent parallax greater than the thickness of the reticle lines when sighting on a collimated target. This requirement shall also be met with the variable density filter, set for any value of transmission in the telescope field of view.

3.3.6 Reticle. - The lines of the reticle shall be distinct, sharp, and clean cut and shall not appear broken because of improper filling or other causes.

3.3.7 Reticle illumination. - The illuminated reticle shall be of substantially uniform brightness throughout. There shall be no bright or otherwise objectionable reflection or stray light in or surrounding the field.

3.3.8 Stray light. - No stray light shall be visible in or surrounding the field of view, nor shall there be any false pupils or other concentrations of stray light in or adjacent to the exit pupil. No paint, enamel, lacquer, or other material which may become detached from the surfaces to which applied may be used in the interior of the telescope.

3.3.9 Image quality and definition. - The image of a round bright star shall appear round with a sharply defined edge under the conditions indicated in Publication NAVORD OD 16421. The image shall be free from points, flares, rays, fog, haze, or halos other than the normal diffraction rings. No difference in coloration between one side of the star and the other shall be seen. A slightly defocused image shall remain round. The difference in ocular setting between the three stars shall not exceed 0.1 diopter. There shall be no difference in ocular setting between the red and the blue stars.

3.3.10 Resolution. - The limit of resolution shall not exceed 5 seconds of arc simultaneously in both horizontal and vertical directions. With due allowance for the effects of brightness levels, use of the variable density filter shall not adversely affect resolution.

3.4 Performance. -

3.4.1 Reference surfaces. - The horizontal mounting surface shall be the primary reference plane for the telescope. The angular relationship between the plane of the horizontal mounting surface and the plane of the vertical mounting surface shall be within the tolerances specified on the applicable drawing. Machining of the mounting surfaces of the telescope after assembly of the optical parts therein, in order to secure proper alignment or for any other reason, is forbidden.

3.4.2 Movement of the line of sight. -

3.4.2.1 Limits of motion. - The limits of motion of the line of sight shall be 85 degrees above the horizontal (elevation) and 20 degrees below the horizontal (depression). The line of sight shall also have lateral (traverse) movement 30 degrees to the right and 30 degrees to the left of a plane that is mutually perpendicular to the planes of the horizontal and vertical mounting surfaces and contains the intersecting lines of the optical axis common to the objective lens, reticle, and eyepiece of the system.

Source: https://assist.dla.mil -- Downloaded: 2026-10-19T11:11Z
Check the source to verify that this is the current version before use.

3.4.2.2 Limit stops. - The positive mechanical limit stops, with adjusting arrangement for overtravel, on the elevation mirror and traverse prism mounts shall operate at the limits specified on the applicable drawings. The buffer type limit stops provided on the elevation and traverse servo mechanisms shall operate smoothly at the angles specified on the applicable drawings both in stopping the excursion of the line of sight and permitting a smooth and free withdrawal from the limits.

3.4.2.3 Accuracy of axes. - The positions of the axes of rotation of the elevation mirror and traverse prism mount shall be positively fixed to permit movement of the line of sight within the following limits of accuracy:

(a) As the line of sight is moved in elevation between the limits of minus 20 degrees and plus 85 degrees, the line of sight shall not deviate more than 2 minutes of arc from a plane which is mutually perpendicular to the planes of the horizontal and vertical mounting surfaces.

(b) As the line of sight is moved in traverse between the limits specified, 30 degrees left and 30 degrees right, the line of sight shall not deviate more than 2 minutes of arc from a line which is perpendicular to the horizontal mounting surface.

The above requirements shall be met with the variable density filter set for any value of transmission in the telescope field of view and with the filter removed and replaced by the clear compensating glass in the telescope field of view.

3.4.3 Servo performance. - The performance of the elevation and traverse servos shall be in accordance with 3.4.3.1 through 3.4.3.5.

3.4.3.1 Frequency response. - The servo shall have a frequency response which exhibits no resonance below 6 cycles per second and shall not produce a control ratio (output/input) greater than 1.3. The phase shift (for the servo) shall be less than 10 degrees under 3 cycles per second and less than 30 degrees between 3 and 6 cycles per second.

3.4.3.2 Velocity and velocity error. - The elevation and traverse servos shall each be capable of maximum velocities of 60 degrees per second and the velocity error of the servo shall not exceed 1/1000 degree per degree per second in this velocity range.

3.4.3.3 Acceleration and acceleration error. - The elevation and traverse servos shall each be capable of accelerations of 120 degrees per second per second and the acceleration error in this range shall not exceed 1/200 degree per degree per second squared.

3.4.3.4 Oscillations. - In moving from an initial point to a point designated by the external synchro transmitter, the telescope line of sight may be subject to angular perturbations, called "jitter", along or perpendicular to the direction of motion. The servos shall be so damped that jitter of the optical line of sight will not exceed 30 seconds of arc (true field) peak-to-peak jitter at line of sight velocities up to and including 30 degrees per second. There shall be no visibly perceptible oscillation of the line of sight, called "buzz", when holding a given transmitted position. Particular attention shall be paid to compliance with this requirement at zero degrees elevation and traverse.

Source: https://assist.dla.mil -- Downloaded: 2026-10-19T11:11Z
Check the source to verify that this is the current version before use.

3.4.3.5 Static accuracy. - Static accuracy is the correctness with which the telescope line of sight is positioned in response to synchro transmitted signals and includes receiving synchro errors, servo errors, and gear inaccuracies but does not include transmitting synchro errors. Static accuracy is largely determined by the accuracy of the gearing to each driven shaft and is governed by Specification MIL-S-18727. The telescope performance requirement is that the average error in positioning the line of sight within the specified limits of motion shall not exceed 2 minutes of arc (true field). A total spread (algebraic difference) of 4 minutes of arc between the highest single error and the lowest single error is allowable.

3.4.3.5.1 Precautions. - Each telescope shall be shipped with the line of sight adjusted at zero degrees elevation and traverse within 1 minute of the true position. Particular attention shall be paid to behavior and possible shifts of the zero position as a result of the environmental tests in order to insure maximum accuracy in alignment with the rest of a weapon control system.

3.4.4 External power fluctuations. - Telescope performance shall be satisfactory under the following conditions in the 400 cycle supply:

(a) Variations in voltage between the limits of 103.5 volts and 126.5 volts.

(b) Variations in frequency between the limits of 380 cycles and 420 cycles per second.

(c) Simultaneous variations of voltage and frequency between the above specified limits.

3.5 Watertightness. - The electrical compartment of the telescope shall be watertight when tested in accordance with Publication NAVORD OD 16421.

3.6 Internal pressure drop. - The internal pressure drop in the telescope shall not exceed 1/4 pound per square inch (psi) during a period of not less than 24 hours when tested in accordance with Publication NAVORD OD 16421.

3.7 Environmental requirements. -

3.7.1 Shock. - The telescope shall be capable of withstanding six 150 foot-pound blows.

3.7.2 Vibration. - The telescope shall be capable of withstanding Type I environmental vibration as defined in Standard MIL-STD-167 at frequencies between 200 and 1500 cycles per minute at an amplitude of plus or minus 0.030 inch.

3.7.3 Pressure-temperature. - The corrected internal pressure drop in the telescope shall not exceed 1 psi from an initial internal pressure of 4 psi during a period of not less than 72 hours. There shall be no condensation or moisture on the internal surfaces of the telescope and on the surfaces of optical components when the telescope is cooled from an ambient temperature of approximately 72°F to minus 20°F.

Source: https://assist.dla.mil -- Downloaded: 2026-10-19T11:11Z
Check the source to verify that this is the current version before use.

3.7.4 Temperature extremes. - Telescope optical and mechanical requirements and performance shall be as specified herein when the temperature of the telescope is stabilized at plus 155°F and also at minus 20°F. The change in temperature between these extremes shall cause no structural change in the telescope.

3.7.5 Watertightness. - The electrical compartment of the telescope shall be watertight when tested in accordance with 4.4.3.4.5.

3.8 Lubrication. - Lubrication of the telescope shall be in accordance with the applicable drawings. Lubricants shall be applied sparingly so as to avoid contamination of the optical elements.

3.9 Materials. - Materials used in the manufacture of the telescope shall be as specified on the applicable drawings. Within the limits of the referenced glass specifications, minor surfaces of optical elements are not sufficient cause for rejection unless such defects are evident to the unaided eye when looking directly through the telescope against a background having the brightness of the sky in average daylight.

3.10 Corrosion protection. - During the course of manufacture the surfaces of all parts and assembled units shall be protected against corrosion prior to and after assembly.

3.11 Workmanship. - Workmanship shall be of such quality as to produce material of uniform high quality and as to meet all requirements of the applicable drawings and of this specification.

4. QUALITY ASSURANCE PROVISIONS AND TEST REQUIREMENTS

4.1 Unless otherwise specified herein the supplier is responsible for the performance of all inspection requirements prior to submission for Government inspection and acceptance. Except as otherwise specified, the supplier may utilize his own facilities or any commercial laboratory acceptable to the Government. Inspection records of the examinations and tests shall be kept complete and available to the Government as specified in the contract or order.

4.2 Lot. - For purposes of sampling a lot shall consist of all the telescopes manufactured by the same process and at the same plant location and submitted for Government acceptance at any one time.

4.3 Sampling. -

4.3.1 For preproduction inspection. - Unless otherwise specified (see 4.3.1.1), one preproduction sample telescope shall be supplied by the contractor as specified in 3.2. The sample shall be submitted to the Government inspector for preproduction inspection (see 4.4.3.2) at an activity designated in the contract or order (see 6.2) or by the Bureau of Ordnance. Further production of the telescopes by the contractor prior to the approval of the procuring activity or completion of inspection of the preproduction sample shall be at the contractor's risk.

Source: https://assist.dla.mil -- Downloaded: 2026-10-19T11:11Z
Check the source to verify that this is the current version before use.

4.3.1.1 Preparation sample and inspection for a subsequent contract. - If a contractor has previously delivered telescopes in accordance with the requirements of this specification and his product has been found to be satisfactory, the preproduction sample and inspection for any subsequent contract or order may be waived at the discretion of the procuring activity (see 6.2).

4.3.2 Sampling for periodic tests. - Unless otherwise specified by the procuring activity, sample telescopes shall be randomly selected by the Government inspector, as indicated below, for periodic testing (see 4.4.3.3). The Government inspector shall forward the sample to a testing activity designated in the contract or order (see 6.2) or by the Bureau of Ordnance. The sampling procedure shall be as follows:

(a) One telescope from the first 25 telescopes or less.
(b) One telescope from the next 50 telescopes or less.
(c) One telescope from the next 75 telescopes or less.
(d) One telescope from each succeeding quantity of 100 telescopes or less.

If a sample from any of the above quantities fails the periodic tests, sampling shall be repeated starting with (a) above.

4.3.3 Sampling for lot acceptance. - No provisions are made for sampling for lot acceptance because each telescope shall be inspected (visually and dimensionally examined and tested) in accordance with 4.4.1, 4.4.2, and Publication NAVORD OD 16421.

4.4 Inspection. -

4.4.1 General procedure. - General inspection and test procedures shall be in accordance with Publication OP 400. Lot acceptance inspection shall be conducted at the contractor's plant. Inspection shall be performed at the state of assembly best suited for performing the examinations and tests specified herein.

4.4.2 Visual and dimensional examination. - Each telescope shall be visually examined for completeness of manufacture, freedom from defects, proper identification, and workmanship. Dimensional and other non-destructive inspections shall be made in accordance with the acceptance inspection instructions provided by the procuring activity.

4.4.2.1 Packaging, packing and marking. - Telescope containers shall be examined to determine whether or not packaging, packing, and marking are in accordance with Section 5.

4.4.3 Tests and test procedures. -

4.4.3.1 Filter and clear compensating glass. - All optical tests shall be conducted with the filter positioned in the telescope line of sight and also with the clear compensating glass positioned in the telescope line of sight.

Source: https://assist.dla.mil -- Downloaded: 2026-10-19T11:11Z
Check the source to verify that this is the current version before use.

4.4.3.2 Preproduction tests. - Preproduction telescopes (see 4.3.1) shall be subjected to the environmental tests of 4.4.3.4.1 through 4.4.3.4.5 and the lot acceptance tests as specified in 4.4.3.5. Preproduction telescopes that pass the required tests and meet the requirements specified herein shall be included in the quantity called for in the contract or order.

4.4.3.3 Periodic tests. - Periodic tests (see 4.3.2) shall consist of the environmental tests of 4.4.3.4.1 through 4.4.3.4.5 and shall be performed on telescopes that have previously passed the lot acceptance tests of 4.4.3.5.

4.4.3.3.1 Failures during periodic tests. - In the event of failure of any telescope during periodic testing, inspection and acceptance of subsequent telescopes shall be suspended until the reasons for failure and consequent rejection have been determined and the cause of failure corrected by the contractor to the satisfaction of the procuring activity. The contractor shall furnish the procuring activity with a written statement properly endorsed by the Government inspector indicating the reasons for failure and the corrective action taken.

4.4.3.4 Environmental tests. -

4.4.3.4.1 Shock. - The telescope shall be secured to the shock test stand shown on Drawing 181117 and tested to determine conformance to 3.7.1. The blows shall be struck, two in each of the three mutually perpendicular directions.

4.4.3.4.2 Vibration. - The telescope shall be tested to determine conformance to 3.7.2. The vibrations shall be applied separately in each of the three mutually perpendicular directions. Each test in each direction shall be of at least 15 minutes duration.

4.4.3.4.3 Pressure-temperature. - The telescope shall be tested for pressure-temperature to determine conformance to 3.7.3.

4.4.3.4.3.1 Test procedure. - The telescope shall be charged with dry air to a pressure of 4 psi. The exact internal air pressure, ambient temperature, and barometric pressure shall be simultaneously recorded. The air inlet valve shall then be closed to seal the telescope and the time recorded. The telescope shall then be subjected to the following temperatures in the order listed.

(a) Room temperature (approximately 72°F until stabilized).
(b) Ambient temperature of plus 155°F for at least 5 hours.
(c) Room temperature (approximately 72°F) for at least 2 hours.
(d) Ambient temperature of minus 20°F for at least 16 hours.
(e) Room temperature (approximately 72°F) for approximately 24 hours.

During and at the end of the minus 20°F temperature run of (d) above the telescope shall be examined to determine that no condensation or moisture has collected on the internal surfaces of the telescope and on the surface of optical components. At the end of the temperature run of (e) above the telescope internal air pressure, ambient temperature, and barometric pressure shall be simultaneously recorded and the internal air pressure corrected for any change between the ambient temperature and barometric pressure at the end of the test and the ambient temperature and barometric pressure at the beginning of the test.

Source: https://assist.dla.mil -- Downloaded: 2026-10-19T11:11Z
Check the source to verify that this is the current version before use.

4.4.3.4.3.2 Corrected and interpolated internal pressure. - A check shall be made to determine that the corrected final internal air pressure, as determined in 4.4.3.4.3.1, is not less than the interpolated internal air pressure, computed on the basis of 1 psi loss in 72 hours. The interpolated air pressure shall be computed from the formula:

$$P_t = P_o e^{-.004t}$$

Where: P_t = Interpolated pressure in psi at time t.

P_o = Initial pressure in psi.

e = Base of natural logarithms.

t = Time in hours between initial and final readings of internal air pressure in psi.

4.4.3.4.4 Temperature extremes. - The telescope shall be tested at extremes of temperature to determine conformance to 3.7.4. The tests of Publication NAVORD OD 16421 shall be conducted during the hot run of 4.4.3.4.3.1(b) and during the cold run of 4.4.3.4.3.1(d) as considered necessary by the Government inspector to determine conformance of the telescope to 3.7.4.

4.4.3.4.5 Watertightness. - The telescope shall be tested for watertightness to determine conformance to 3.7.5. This test shall consist of subjecting the fully machined telescope housing casting, without any electrical or electronic components mounted therein, to the submergence hermetic enclosure test in Standard MIL-STD-108. Immediately following the test, examination shall be made for the entrance of water into the housing, disassembly being made as necessary.

4.4.3.4.6 Examination and retests following environmental tests. - Following the environmental tests of 4.4.3.4.1 through 4.4.3.4.5 telescopes shall be examined for breakage, loose parts, and other defects. Telescopes that pass the environmental tests shall be returned to the contractor for repair and reconditioning if such repair and reconditioning are necessary as a result of environmental testing. The lot acceptance tests of 4.4.3.5 shall be repeated as necessary to determine that no changes in mechanical, electrical, and optical performance have taken place as a result of the environmental tests.

4.4.3.5 Lot acceptance tests. - Lot acceptance tests in accordance with Publication NAVORD OD 16421 shall be performed on each telescope to determine conformance to the requirements of 3.3.1 through 3.6.

4.5 Resubmission. - Telescopes that fail to pass any lot acceptance test shall be rejected. Rejected telescopes may be resubmitted for retests in accordance with the procedures of Publication OP 400.

5. PREPARATION FOR DELIVERY

Source: https://assist.dla.mil -- Downloaded: 2026-10-19T11:11Z
Check the source to verify that this is the current version before use.

5.1 Levels of packaging and packing. - Telescopes shall be packaged and packed in accordance with one of the following levels as specified in the contract or order (see 6.2).

5.2 Packaging. -

5.2.1 Level A. - Each telescope shall be placed and secured in the packing case conforming to LD 412555 listed on LD 412561.

5.2.2 Level B and level C. - Not applicable.

5.3 Packing. -

5.3.1 Level A. - Telescopes packaged as specified in 5.2.1 shall be packed in an overseas type box conforming to Specification PPP-B-585, PPP-B-601, or PPP-B-621. Boxes shall be lined with a waterproof case liner conforming to Specification MIL-L-10547, and sealed in accordance with the appendix thereto. Seams and closures shall have a water resistance equal to or better than that of the body material. The interior of each container shall be provided with suitable blocking, partitioning, and cushioning so as to prevent shifting of and damage to items contained therein.

5.3.2 Level B. - Telescopes packaged as specified in 5.2.1 shall be packed in a domestic type box conforming to Specification PPP-B-585, PPP-B-601, or PPP-B-621. The interior of each container shall be provided with suitable blocking, partitioning, and cushioning so as to prevent shifting of and damage to items contained therein.

5.3.3 Level C. - Telescopes packaged as specified in 5.2.1 shall be packed or otherwise prepared for shipment to insure carrier acceptance and to insure safe delivery to destination at the lowest applicable rate. Containers shall comply with the Consolidated Freight Classification Rules or other carrier regulations applicable to the mode of transportation.

5.4 Marking of shipping containers. -

5.4.1 For production telescopes. - In addition to any special marking required by the contract or order (see 6.2), shipping containers shall be marked in accordance with Standard MIL-STD-129.

5.4.2 For preproduction telescopes. - Shipping containers shall be marked as specified in 5.4.1 and with the following information:

Title, number, and date of this specification
Mark and Mod and LD number
Sample for preproduction inspection
Name of manufacturer
Manufacturer's plant address
Reference (contract number)

5.4.3 For telescopes for periodic testing. - Shipping containers shall be marked as specified in 5.4.2 except that containers shall be marked "Sample for periodic tests" instead of "Sample for preproduction inspection". In addition, containers shall be marked with the identification of the lot or quantity from which the sample was taken.

Source: https://assist.dla.mil -- Downloaded: 2026-10-19T11:11Z
Check the source to verify that this is the current version before use.

6. NOTES

6.1 Intended use. - The telescope Mark 116 Mod 0 is intended for use with the following items:

Gunar System Mark 1 Mod 0 (3-inch/50 caliber).
Gunar System Mark 2 Mod 0 (3-inch/70 caliber).
Gunar System Mark 3 Mod 0 (5-inch/54 caliber).
5-inch/54 caliber Mount Mark 42 and Mods.
3-inch/70 caliber Mount Mark 37 and Mods.
Gun Fire Control System Mark 69 and Mods.

6.2 Ordering data. - Procurement documents should specify the following:

(a) Title, number, and date of this specification.
(b) Whether preproduction samples and inspection are required (see 3.2 and 4.3.1.1).
(c) Testing activity for preproduction samples or samples for periodic tests if the activity is not designated by the Bureau of Ordnance (see 4.3.1 or 4.3.2).
(d) Levels required in preparation for delivery (see 5.1).
(e) Special marking when required (see 5.4.1).

6.3 Preparation for delivery criteria. - Criteria for use of the proper level of preservation, packaging, and packing are indicated below in 6.3.1 through 6.3.3.

6.3.1 Level A. - This level shall be used to afford adequate protection of items during multiple domestic shipment and handling, indeterminate storage, and world-wide redistribution.

6.3.2 Level B. - This level shall be used for protection of items during multiple domestic shipment and handling and covered storage. Six month cyclic inspection and any necessary represervation and repackaging is required when this level is used.

6.3.3 Level C. - This level shall be used only when it is definitely known that items are to be shipped to domestic installations for immediate use at the first receiving activity.

Notice. - When Government drawings, specifications, or other data are used for any purpose other than in connection with a definitely related Government procurement operation, the United States Government thereby incurs no responsibility nor any obligation whatsoever; and the fact that the Government may have formulated, furnished, or in any way supplied the said drawings, specifications, or other data is not to be regarded by implication or otherwise as in any manner licensing the holder or any other person or corporation, or conveying any rights or permission to manufacture, use, or sell any patented invention that may in any way be related thereto.

Preparing Activity
Navy - Bureau of Ordnance

Source: https://assist.dla.mil -- Downloaded: 2026-10-19T11:11Z
Check the source to verify that this is the current version before use.