MIL-F-12639B (MU)
28 February 1964
SUPERSEDING
MIL-F-12639A (Ord)
9 October 1961

MILITARY SPECIFICATION

FUZE, POINT DETONATING M508A1 LOADING, ASSEMBLING AND PACKING

1. SCOPE

1.1 This specification covers the loading, assembling and packing for one type of fuze designated as Fuze, Point Detonating, M508A1.

2. APPLICABLE DOCUMENTS

2.1 The following documents of the issue in effect on date of invitation for bids or request for proposals, form a part of this specification to the extent specified herein.

SPECIFICATIONS

MILITARY

MIL-A-2550 - Ammunition and Special Weapons, General Specification for
MIL-I-45208 - Inspection Requirements, General Specification for
MIL-I-45607 - Inspection Equipment, Supply and Maintenance of

STANDARDS

MILITARY

MIL-STD-105D - Sampling Procedures and Tables for Inspection by Attributes
MIL-STD-109 - Quality Assurance Terms and Definitions
MIL-STD-350 - Jolt Test for use in Production of Fuzes.
MIL-STD-1235 - Single and Multilevel Continuous Sampling Procedures and Tables for Inspection by Attributes.

FSC 1390

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T23:08Z
Check the source to verify that this is the current version before use.

DRAWINGS

ORDNANCE CORPS

7548400 - Box, Packing, Ammunition, for Standard Contour Fuzes w/Booster in Fiber Container, M43A2, Assembly, Details and Packing.
7548401 - Container, Ammunition, Fiber, M43A2, for Standard Contour Fuzes w/Booster. Assembly, Details and Packing.
7549041 - Fuze, PD, M508A1, Assembly.
8864492 - Box, Ammunition, Metal, For Artillery Type Fuzes.
8861213 - Box, Wirebound, Packing, Ammunition, For Artillery Type Fuzes.

PUBLICATIONS

IEL-7549041 - Index of Inspection Equipment Lists.

(Copies of specifications, standards, drawings, and publications required by contractors in connection with specific procurement functions should be obtained from the procuring activity or as directed by the contracting officer).

3. REQUIREMENTS

3.1 Material.-Materials and parts shall be in accordance with applicable drawings and specifications.

3.2 Fuzes.-The loaded fuzes shall comply with all requirements specified on Drawing (dwg.) 7549047, and with all requirements specified in applicable specifications.

3.3 Head assembly torque.-The head assembly shall withstand subsequent application of the minimum assembly torque specified on the applicable drawing, without moving.

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T23:08Z
Check the source to verify that this is the current version before use.

3.4 Jolt and jumble.-The loaded fuze assemblies shall have no explosive elements explode, shall have its interrupter remain in the un-armed position (completely obstruct flash hole), shall not come apart, and shall have no parts broken, deformed or displaced in such a manner as to render the fuze unsafe to handle or dangerous to fire when subjected to the jolt test specified in Standard MIL-STD-350 and a jumble test of 3600 revolutions. These tests shall be performed as specified in 4.3.1.

3.5 Proving ground.-The fuzes shall comply with the following requirements when tested as specified in 4.3.2.

3.5.1 Premature burst.-No fuze shall show evidence of premature burst (see 6.4).

3.5.2 Functioning.-No fuze shall fail to cause the projectile to function high order upon impact.

3.6 Workmanship

3.6.1 Finishes.-Moving parts, and surfaces contacting moving parts, shall be free of burrs, slivers, raised metal, cuts, nicks, pits, and scratches.

3.6.2 Foreign matter.-All parts shall be free of chips, cracks, scale, dirt, grease, rust, salt deposits, and other foreign material. The cleaning method shall not be injurious to any of the parts nor shall the parts be contaminated by the cleaning agents.

4. QUALITY ASSURANCE PROVISIONS

4.1 General quality assurance provisions.-Unless otherwise specified in the contract or purchase order the supplier is responsible for the performance of all inspection requirements specified herein. Except as otherwise specified, the supplier may utilize his own or any other inspection facilities and services acceptable to the Government. Inspection records of the examinations and tests shall be kept complete and available to the Government as specified in the contract or order. The Government reserves the right to perform any of the inspections

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T23:08Z
Check the source to verify that this is the current version before use.

set forth in the specification where such inspections are deemed necessary to assure that supplies and services conform to prescribed requirements. Reference shall be made to Standard MIL-STD-109 in order to define terms used herein. The provisions of Specification MIL-A-2550 shall apply.

4.1.1 Contractor quality assurance system.-The contractor shall provide and maintain an effective quality assurance system in compliance with the requirements of Specification MIL-I-45208. The contractor's quality assurance system shall contain a procedure for the reporting of critical defectives found during the course of his inspection and during inspection by the Government. Any critical defect encountered, unless annotated by an asterisk (*) to the right of the characteristic code number (see 6.2), will be reported within 48 hours. A monthly summary report covering those critical defects annotated by an asterisk will be furnished. The agencies to whom the reports will be furnished are identified in paragraph 6.6. The reports shall contain, as a minimum, the following information:

a. Contractor and contract number.
b. Number and revision date of specification.
c. Characteristic code number.
d. Lot or serial number.
e. Number of defectives found.
f. Assignable cause or analysis of occurrence.
g. Corrective action taken or recommended. When the corrective action is beyond the control of the contractor or the scope of the contract, the report shall contain the contractor's recommendation to the Government.

4.1.2 Submission of product.-At the time the completed lot of product is submitted to the Government for acceptance the contractor shall supply the following information accompanied by a certificate which attests that the information provided is correct and applicable to the product being submitted:

a. A statement that the lot complies with all quality assurance provisions of the approved current written description of the system.
b. Number of units of product inspected.
c. Results obtained for all inspection performed.

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T23:08Z
Check the source to verify that this is the current version before use.

d. Drawing, specification number and date, together with an identification and date of changes.

e. Certificates of analysis on all material purchased by the contractor when such material is controlled by Government specifications referenced in any of the contractual documents.

f. Number of items in the lot.

g. Date submitted.

The certificate shall be signed by a responsible agent of the certifying organization. The initial certificate submitted shall be substantiated by evidence of the agent's authority to bind his principal. Substantiation of the agent's authority will not be required with subsequent certificates unless, during the course of the contract, this authority is vested in another agent of the certifying organization.

4.1.3 Government verification.-Using the contractor's written quality assurance procedure, this detail specification, the applicable drawings and other contractual documents as a guide, the Government inspector shall verify at unscheduled intervals all quality assurance operations performed by the contractor. Verification will be in accordance with Specification MIL-I-45208 and will be performed to the extent necessary to assure compliance with the contractual requirements. Severity of Government inspection of individual characteristics will be directly related to the seriousness of the classification assigned. In no instance will a characteristic classified "critical" be accepted solely on the basis of the contractor's records.

4.2 Inspection provisions for production

4.2.1 Lot formation.-A lot shall consist of fuzes loaded and assembled by one manufacturer in one unchanged process, in accordance with the same drawing, same drawing revision, same specification, and same specification revision. Drawing, specification, and process changes not affecting safety, performance, or fit, as determined by the Government, shall not necessitate changing the lot number. Product shall be submitted for inspection in accordance with Standard MIL-STD-105D (or Standard MIL-STD-1235, when applicable). Each lot shall contain:

a. Parts and parts assemblies of one lot interfix number from one manufacturer.

b. Booster assemblies of one lot interfix number from one manufacturer.

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T23:08Z
Check the source to verify that this is the current version before use.

c. Detonator assemblies of one lot interfix number from one manufacturer.

4.2.2 Examination.-Inspection for Critical defects and Major defects, when so specified, shall be 100 percent. Sampling plans and procedures for Major and Minor defects shall be in accordance with Standard MIL-STD-105D except that continuous sampling plans in accordance with Standard MIL-STD-1235, may be used if approved by the procuring activity. Also, at the option of the procuring activity, AQL's and sampling plans may be applied to the individual characteristics listed using an AQL of 0.40 percent for each minor defect, and an AQL of 0.25 percent for each major defect except when 100 percent inspection is specified. Equipment necessary for the performance of the inspections listed shall be in accordance with 4.3.4.

4.2.2.1 Head assembly (see dwg. 7549043 covering a detail of dwg. 7549041).

Categories	Defects	Method of Inspection	Code No. (see 6.2)
Critical:	None defined		
Major:	AQL 0.25 percent		
101.	Detonator missing or inverted (when viewed through detonator retaining screw)	Visual	01001
102.	Detonator cushion missing or not compressed (indicating loose detonator) (when viewed through detonator retaining screw)	Visual	01002
Minor:	AQL 1.5 percent		
201.	Detonator retaining screw stake missing or inadequate	Visual	01003
202.	Detonator retaining screw not fully seated	Visual	01004
203.	Foreign matter on detonator or in any cavity or other evidence of poor workmanship (see 3.6)	Visual	01005

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T23:08Z
Check the source to verify that this is the current version before use.

4.2.2.2 Assembly, prior to assembling flash tube and booster assembly (see dwg. 7549041).

Categories	Defects	Method of Inspection	Code No.
Critical: None defined			
Major:	AQL 0.25 percent		
101.	Foreign matter in flash hole.....	Visual	02001
Minor: None defined			

4.2.2.3 Assembly, prior to assembly of head assembly (see dwg. 7549041).

Categories	Defects	Method of Inspection	Code No.
Critical:			
1.	Interrupter does not completely obstruct flash hole.....	Visual	03001*
Major:	AQL 0.25 percent		
101.	Flash tube stake missing, inadequate or not coated.....	Visual	03002
102.	Foreign matter in flash tube cavity or other evidence of poor workmanship (see 3.6).....	Visual	03003
Minor: None defined			

4.2.2.4 Assembly (see dwg. 7549041).

Categories	Defects	Method of Inspection	Code No.
Critical: None defined			
Major:	AQL 0.65 percent		
101.	Total length, maximum, (max.).....	Gage	04001

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T23:08Z
Check the source to verify that this is the current version before use.

102.	Length to shoulder above thread, max	Gage	04002
103.	Body thread damaged	Visual	04003
104.	Booster cup cracked or split	Visual	04004
105.	Firing pin closing disc missing or damaged (punctured, cracked or dented)	Visual	04005
Minor:	AQL 4.0 percent		
201.	Head assembly fails to withstand assembly torque (see 3.3 and 4.4.3)	Test	04006
202.	Booster assembly fails to withstand disassembly torque (see 4.4.4)	Test	04007
203.	Crack or puncture at ogive head, stake or dimples	Visual	04008
204.	Ogive cracked, dented or deformed	Visual	04009
205.	Protective paint missing from stakes	Visual	04010
206.	Ogive head stake or booster assembly stake missing or inadequate	Visual	04011
207.	Marking misleading or unidentifiable	Visual	04012
208.	Wrench slots damaged to extent they will not receive a wrench	Visual	04013
209.	Protective coating damaged (ignoring slight scratches)	Visual	04014
210.	Evidence of poor workmanship (see 3.6)	Visual	04015

4.2.2.5 Container (sealed) (see dwg. 7548401).

Categories	Defects	Method of Inspection	Code No.
Critical:	None defined		

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T23:08Z
Check the source to verify that this is the current version before use.

Categories	Defects	Method of Inspection	Code No.
Major:	AQL 0.25 percent		
101.	Assembly damaged so that contents are exposed or liable to become exposed	Visual	05001
102.	Sealing strip incomplete, badly wrinkled, or not in contact with surface for at least 1/2 inch around entire container	Visual	05002
Minor:	AQL 1.0 percent		
201.	Contents move when carton is shaken	Manual	05003
202.	Marking misleading or unidentifiable	Visual	05004

4.2.2.6 Box, metal, closed (see dwg. 8864492), when applicable (see 5.1.1).

Categories	Defects	Method of Inspection	Code No.
Critical:	None defined		
Major:	AQL 0.40 percent		
101.	Box not securely closed	Visual-Manual	06001
102.	Contents loose	Manual	06002
103.	Hardware missing, broken or loose	Visual-Manual	06003
Minor:	AQL 1.00 percent		
201.	Damage not affecting closure or air-tightness	Visual	06004
202.	Marking misleading or unidentifiable	Visual	06005

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T23:08Z
Check the source to verify that this is the current version before use.

4.2.2.7 Box, packing (sealed) (see dwg. 8861213 or 7548400, as applicable).

Categories	Defects	Method of Inspection	Code No.
Critical: None defined			
Major:	AQL 0.65 percent		
101.	Hardware missing, broken or loose	Visual-Manual	07001
102.	Strapping or wire missing, broken or loose	Visual-Manual	07002
103.	Contents exposed	Visual	07003
104.	Board broken or split	Visual	07004
105.	DOD symbol misleading or unidentifiable	Visual	07005
Minor:	AQL 2.5 percent		
201.	Hardware improperly engaged (when applicable	Visual-Manual	07006
202.	Handle missing or insecure (when applicable	Visual-Manual	07007
203.	Contents loose (when box is tilted)	Manual	07008
204.	Strapping or wire improperly assembled	Visual	07009
205.	Marking misleading or unidentifiable	Visual	07010
206.	Car seal missing, unsealed or improperly positioned	Visual	07011

4.2.3 Testing

4.2.3.1 Check test for deterioration of detonators - Code No. 01006, Major defect.-If the total time between original acceptance of any detonator lot and the assembly of that lot

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T23:08Z
Check the source to verify that this is the current version before use.

into the fuzes exceeds two years, or if the detonators have been subjected to adverse conditions, however brief, at any time since previous tests, the detonator lot shall be subjected to and must satisfactorily pass, the check test for deterioration specified in the applicable specification immediately before the detonator lot is assembled into the fuzes. This test shall be performed by the contractor on detonators selected by the Government inspector at the facility assembling the detonators into the fuzes (see 6.5).

4.2.3.2 Jolt and jumble (see 3.4) Critical defect, Code No. 04016.-The tests shall be performed as specified in 4.3.1 using equipment in accordance with 4.2.4.

4.2.3.2.1 Beginning with the first lot produced and continuing until three consecutive lots have complied with the acceptance criteria specified herein, 36 fuze assemblies shall be selected from each lot for these tests. If one or more fuze assemblies fail to comply with the requirements specified, the lot shall be rejected.

4.2.3.2.2 After 3 consecutive lots have complied with the criteria of 4.2.3.2.1, twelve assemblies shall be selected for these tests. If any assembly fails to comply with the requirements specified, the lot shall be rejected.

4.2.3.3 Proving ground (see 3.5) Premature burst, Critical defect, Code No. 04017; Failure to function, Major defect, Code No. 04018.-If a premature burst occurs the lot under test shall be rejected. The test shall be performed as specified in 4.3.2.

4.2.3.3.1 Beginning with the first lot produced and continuing until three consecutive lots have complied with the applicable criteria, the samples shall be selected in accordance with column I of Table I. If two or more fuzes fail to comply with the applicable functioning requirements the lot shall be rejected.

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T23:08Z
Check the source to verify that this is the current version before use.

4.2.3.3.2 After three consecutive lots have complied with the criteria of 4.2.3.3.1 the sampling plan shall be in accordance with Column II of Table I. If two or more assemblies fail to comply with the requirement specified, the lot shall be rejected. If there is only one functioning failure an additional sample shall be selected in accordance with Column I of Table I. If the combined number of failures from both the first and second sample is two or more the lot shall be rejected.

TABLE I

Sample Size I	Sample Size II	Projectile	Zone	Approx Elev Mils
12	6	105MM HE M1	VII	660
12	6	155MM HE M107	II	750
16	8	155MM HE M101	Normal	540
40	20 - Total			

4.2.4 Inspection Equipment.-Index of Inspection Equipment Lists Number IEL 7549041 identifies the inspection equipment required to perform the examinations and tests prescribed in this section. The contractor shall design inspection equipment in accordance with the instructions in paragraph 6.3.

4.2.4.1 Government rights to documentation.-Inspection equipment drawings and lists provided and revised in accordance with the requirements of the IEL may be used by DOD activities for design, procurement, manufacture, testing, evaluation, production and receiving inspection, overhaul, shipping, storage, identification of stock, ordering and storage of replacement parts, inspection of items at overhaul, general maintenance of equipment, construction, survey and whenever inspection equipment drawings are needed.

4.2.4.2 Supply and maintenance.-Supply and maintenance of the equipment listed on the IEL shall be in accordance with Specification MIL-I-45607.

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T23:08Z
Check the source to verify that this is the current version before use.

4.2.4.3 Government use of contractor's inspection and test equipment.-The contractor shall make available to the Government all inspection and test equipment necessary for determining conformance with contract requirements. Personnel for operating the equipment, and verification of its accuracy, shall be supplied by the contractor for the performance of examination or test by the Government.

4.3 Test methods and procedures

4.3.1 Jolt and jumble.-The loaded fuze assmblies shall be subjected to the jolt test in accordance with Standard MIL-STD-350. After completion of the jolt test, the fuzes subjected to the jolt test shall not be disassembled but shall be subjected to 3600 complete revolutions in a specified jumble machine at a speed of 30 plus or minus 2 revolutions per minute. Disassembly and examination of the fuzes shall be accomplished after both jolt and jumble tests have been completed. Examinations shall be made to determine compliance with 3.4.

4.3.2 Proving ground.-The fuzes shall be assembled into the specified number of projectile of each type and fired from the weapon for which they are standard (see Table I). Observation shall be made for compliance with the requirements of 3.5.

4.3.3 Head assembly torque.The torque shall be applied in a tightening direction prior to staking, while the thread sealing compound is wet. The joint at the forward and rearward end of the ogive shall be marked to provide a reference for determining movement between adjacent parts. Any discernible movement between adjacent parts shall be regarded as a torque test failure.

4.3.4 Booster disassembly torque.-The torque shall be applied in a loosening direction after staking. The joint between the booster assembly and fuze body assembly shall be marked to provide a reference for determining movement between adjacent parts. Any discernible movement between adjacent parts shall be regarded as a torque test failure.

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T23:08Z
Check the source to verify that this is the current version before use.

4.3.3.4 Air pressure test (see dwg. 8864492) Major defect.- The filled and closed boxes shall be sampled in accordance with MIL-STD-105D, Code letter G, AQL 0.40%. The test shall be performed as specified in 4.3.5. (Code number 06006).

4.3.5 Air pressure test.-Each box in the sample shall be tested by submerging in water and maintaining it for a minimum of 15 seconds at an air pressure differential of 3 pounds per square inch in excess of the outside pressure. Any box releaseing more than 4 bubbles of air shall be classified as defective.

5. PREPARATION FOR DELIVERY

5.1 Preservation and Packaging

5.1.1 Level A.-Packaging for Fuze, M508A1, shall be in accordance with dwg. 8864492.

5.1.2 Level C.-Packaging for Fuze, M508A1, shall be in accordance with dwg. 7548401.

5.2 Packing

5.2.1 Level A.-Packing for Fuze, M508A1, shall be in accordance with dwg. 8861213.

5.2.2 Level C.-Packing for Fuze, M508A1, shall be in accordance with dwg. 7548400.

5.3 Marking.-Marking shall be as specified on the applicable packing drawing.

5.4 Data cards.-Data card information for each lot shall be as specified in Specification-A-2550.

6. NOTES

6.1 Ordering data.-Procurement documents shall specify the following:

a. Title, number and date of this specification.

6.2 Inspection code numbers.-The five digit code numbers assigned to the inspections herein are to facilitate future data collection and analysis by the Government.

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T23:08Z
Check the source to verify that this is the current version before use.

6.3 Inspection equipment.-The contractor shall design inspection equipment as required by the referenced Inspection Equipment Lists (IEL) in accordance with the instructions of 6.3.1 through 6.3.7.

6.3.1 Inspection Equipment Lists.-Inspection Equipment Lists indicate the availability of inspection equipment designs by showing in the "number" column of the list of inspection equipment (OO Form 1242-3) the numbers of drawings of existing equipment designs or codes as indicated in 6.3.2. Design action required of the contractor with respect to the different types of drawings that may be listed is described in 6.3.3 and 6.3.4. Action required by the contractor with respect to commercial inspection equipment is described in 6.3.5. The contractor will be required to prepare detailed drawings in accordance with 6.3.6 for all the equipment coded as "contractor design" in the number column. These contractor designs must be approved by the Government prior to fabrication or procuring of the equipment. Designs shall be submitted for approval as specified in 6.3.7.

6.3.2 Inspection Equipment List codes.-The inspection equipment as defined in 6.3.3, 6.3.4, 6.3.5, and 6.3.6 will be designated in the Inspection Equipment List by the following codes:

CDOF - Contractor's design responsibility on Ordnance format; ORDM-608-12.
CDCF - Contractor's design responsibility on contractor format.
OD - Ordnance design.
ODMU - Ordnance design, mandatory for use.
CE - Commercial equipment.
SCD - Specification control Drawing.

6.3.3 Ordnance designs.-Ordnance designs are reflected on detailed drawings which completely depict all the information necessary for the fabrication of the item of inspection equipment. The contractor need provide no design when an Ordnance design is listed for an item of inspection equipment. Ordnance designs fall into two basic classifications; mandatory and non-mandatory. When an Inspection Equipment List references mandatory Ordnance designs, the contractor shall comply with, and use these designs accordingly. The contractor may, however, in connection with non-mandatory designs and with the approval of the Government,

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T23:08Z
Check the source to verify that this is the current version before use.

design alternate inspection equipment or use comparable commercial equipment to facilitate his operations. Such contractor prepared designs or commercial equipment selections must be approved by the Government prior to fabrication or procuring of the equipment. Designs shall be submitted for approval as specified in 6.3.7.

6.3.4 Specification control drawings.-Specification control drawings depict the minimum equipment requirements in outline, descriptive, diagrammatic, or pictorial form only and specify the required performance or other characteristics. Contractors must prepare detailed drawings (see 6.3.6) of their designs in support of specification control drawings. These contractor prepared designs must be approved by the Government prior to the fabrication or procuring of the equipment. Commercial equipment meeting the requirements of specification control drawings may be approved if described in sufficient detail to permit identification and evaluation by the Government. Designs shall be submitted for approval as specified in 6.3.7.

6.3.5 Commercial equipment.-Commercial equipment is inspection equipment that has universal application for a specific function. It is comprised of items commonly used by industry and government. Contractors are not required to furnish drawings of commercial inspection equipment but a list of such equipment must be approved by the Government. Lists shall be submitted for approval to the inspection element of the agency administering the contract.

6.3.6 Contractor designs.-Contractor designs are designs of inspection equipment for which the Government has assigned design responsibility to the contractor. Contractor designs shall be supported by detailed drawings which depict all information necessary to completely fabricate, calibrate and operate an item of inspection equipment. This requires that the necessary views, dimensions, materials, finish, notes, operating and calibration instructions be properly depicted in accordance with approved practices to the extent that further calculation or clarification will not be required. Contractor designs identified as CDCF may be developed on the format the contractor normally employs in his

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T23:08Z
Check the source to verify that this is the current version before use.

equipment design procedure provided such format reflects the detail and information specified above. Contractor designs identified as CDOF shall comply with the format and requirements of ORDM 608-12, and, in addition, contain the detail and information specified above.

6.3.7 Submission of contractor designs.-Designs shall be submitted for approval to the Commanding Officer, Picatinny Arsenal, ATTN: SMUPA-ND. Design review will normally be accomplished within one month after receipt by Picatinny Arsenal. Partial submission of inspection equipment designs is permissible and encouraged. However, the Arsenal completion date for design review will be based on the date of the final submission of designs.

6.4 Premature bursts.-Premature burst is defined as the functioning of the fuze in the weapon bore or in flight before impact.

6.5 Check test.-The contracting officer will arrange for the contractor to be reimbursed for the expense incurred in the performance of the detonator assembly check test. The test shall be conducted at Government expense without cost to the contractor who loaded the detonators or the contractor assembling the detonators into the fuzes, and shall not constitute a basis for rejection against either contractor except where deterioration has occurred as a direct result of carelessness in handling, storage, etc. permitted while the detonator lot was under their jurisdiction.

6.6 Critical defect report

6.6.1 Submission of critical defect reports.-For U. S. Army Munitions Command procurements, one copy of each critical defect report will be furnished the cognizant Government inspection agency; the Army Ammunition Procurement and Supply Agency, Attn: SMUAP-RO; Picatinny Arsenal, Attn: SMUPA-ND.

6.6.2 Reporting to other services.-For other than U. S. Army Munitions Command procurements, critical defect reporting shall be as prescribed by the contracting officer.

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T23:08Z
Check the source to verify that this is the current version before use.

6.7 Submission of test data.-In addition to the normal distribution of records, when the cartridge is procured by the U. S. Army Munitions Command, one copy of all ballistic test data shall be forwarded to each of the following:

Commanding Officer
Picatinny Arsenal
ATTN: SMUPA-ND2 and SMUPA-DC8
Dover, New Jersey

Custodian:
Army-MU

Preparing Activity:
Army-MU

Project No. 1390-A363

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T23:08Z
Check the source to verify that this is the current version before use.