MIL-F-12639B(MU)
AMENDMENT 3
28 OCTOBER 1965

SUPERSEDING
AMENDMENT 2
23 JANUARY 1965

MILITARY SPECIFICATION

FUZE, POINT DETONATING M508A1

LOADING, ASSEMBLING AND PACKING

This amendment forms a part of Military Specification MIL-F-12639B (MU), dated 28 February 1964.

* *Page 1,* paragraph 2.1, Specifications, Military: Delete "MIL-I-45208 Inspection . . . for."

Page 1, paragraph 2.1, Standards, Military: Delete "D" after "MIL-STD-105." After "Attributes" add "(ABC-STD-105)."

Page 2, paragraph 3.2, line 2: Delete "7549047" and substitute "7549041."

* *Page 4:* Delete paragraph 4.1.1 in its entirety.

Page 5, paragraph 4.2.1, line 8: Delete "D" after "MIL-STD-105."

Page 6, paragraph 4.2.2, line 4: Delete "D" after "MIL-STD-105."

Line 8: Delete "0.40" and substitute "0.65."

Line 9: Delete "0.25" and substitute "0.40."

Paragraph 4.2.2.1, Major: Delete "AQL 0.25" and substitute "AQL 0.40."

Page 7, paragraph 4.2.2.2, Major: Delete "AQL 0.25" and substitute "AQL 0.40."

Paragraph 4.2.2.3, Major: Delete "AQL 0.25" and substitute "AQL 0.40."

Paragraph 4.2.2.4, Major: Delete "AQL 0.65" and substitute "AQL 1.0."

Page 9, paragraph 4.2.2.5, Major: Delete "AQL 0.25" and substitute "AQL 0.40."

Paragraph 4.2.2.6, Major: Delete "AQL 0.40" and substitute "AQL 0.65."

Page 10, paragraph 4.2.2.7, Major: Delete "AQL 0.65" and substitute "AQL 1.0."

Page 12: Add new paragraph 4.2.3.4 as follows:

"4.2.3.4 *Air pressure test (see dwg. 8864492) Major defect.* The sampling plan for this test shall be in accordance with Standard MIL-STD-105, Code Letter G and AQL 0.40 percent. The test shall be performed as specified in 4.3.5 using equipment in accordance with 4.2.4."

Page 14: Delete paragraph 4.3.3.4 in its entirety.

Delete paragraph 4.3.5 and substitute:

FSC 1390

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T23:08Z
Check the source to verify that this is the current version before use.

"4.3.5 *Air pressure test.* Each box in the sample shall be placed in an air tight test chamber and an air pressure of 3 pounds per square inch introduced into the chamber. Pressure shall be maintained for 15 seconds in accordance with the operating procedure on the applicable drawing specified in the IEL and observation made to determine if a drop in pressure occurs."

* Delete paragraph 5.4 in its entirety.

* Paragraph 6.1: Add

"(b) Data card information shall be prepared for each lot in accordance with Standard MIL–STD–1167.

Page 15: Delete paragraph 6.3 through 6.3.7 and substitute:

"**6.3 Inspection equipment.** The contractor shall design inspection equipment as required by the reference Inspection Equipment Lists (IEL) in accordance with the instructions of paragraphs 6.3.1 through 6.3.7.

6.3.1 *Inspection equipment lists.* Inspection equipment lists indicate the availability of inspection equipment designs by showing in the "number" column of the list of inspection equipment (00 Form 1242–3) the numbers of drawings of existing equipment designs or codes as indicated in paragraph 6.3.2. Design action required of the contractor with respect to the different types of drawings that may be listed is described in paragraphs 6.3.3 and 6.3.4. Action required by the contractor with respect to commercial inspection equipment is described in 6.3.5. The contractor will be required to prepare detailed drawings in accordance with 6.3.6 for all the equipment coded as "Contractor Design" in the number column. These contractor designs must be approved by the Government prior to fabrication or procuring of the equipment. Designs shall be submitted for approval as specified in 6.3.7.

6.3.2 *Inspection equipment list codes.* The inspection equipment as defined in 6.3.3, 6.3.4, 6.3.5, and 6.3.6 will be designated in the IEL by the following codes:

CDAF — Contractor's design responsibility on Army format in accordance with MIL–D–45608.

CDCF — Contractor's design responsibility on contractor format.

AD — Army design.

ADMU — Army design, mandatory for use.

CE — Commercial equipment.

SCD — Specification control drawing.

6.3.3 *Army designs.* Army designs are reflected on detailed drawings which completely depict all the information necessary for the fabrication of the item of inspection equipment. The contractor need provide no design when an Army design is listed for an item of inspection equipment. Army designs fall into two basic classifications, mandatory and nonmandatory. When an inspection equipment list references mandatory Army designs, the contractor shall comply with, and use these designs accordingly. The contractor may, however, in connection with nonmandatory designs and with the approval of the Government, design alternative inspection equipment or use comparable commercial equipment to facilitate his operations. Such contractor prepared designs or commercial equipment selections must be approved by the Government prior to fabrication or procuring of the equipment. Designs shall be submitted for approval as specified in 6.3.7.

6.3.4 *Specification control drawing.* Specification control drawings depict the minimum equipment requirements in outline, descriptive, diagrammatic or pictorial form only and specify the required performance or other characteristics. Contractors must

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T23:08Z
Check the source to verify that this is the current version before use.

prepare detailed drawings (see 6.3.6) of their designs in support of specification control drawings. These contractor prepared designs must be approved by the Government prior to the fabrication or procuring of the equipment. Commercial equipment meeting the requirements of specification control drawings may be approved if described in sufficient detail to permit identification and evaluation by the Government. Designs shall be submitted for approval as specified in 6.3.7.

6.3.5 *Commercial equipment.* Commercial equipment is inspection equipment that has universal application for a specific function. It is comprised of items commonly used by industry and Government. Contractors are not required to furnish drawings of commercial inspection equipment, but a list of such equipment must be approved by the Government. Lists shall be submitted for approval to the inspection element of the agency administering the contract.

6.3.6 *Contractor designs.* Contractor designs are designs of inspection equipment for which the Government has assigned design responsibility to the contractor. Contractor designs shall be supported by detailed drawings which depict all information necessary to completely fabricate, calibrate, and operate an item of inspection equipment. This requires that the necessary views, dimensions, materials, finish, notes, operating and calibration instructions be properly depicted in accordance with approved practices to the extent that further calculation or clarification will not be required. Contractor designs identified as CDCF may be developed on the format the contractor normally employs in his equipment design procedure provided such format reflects the detail and information specified above. Contractor designs identified as CDAF shall comply with the format and requirements of MIL–D–45608, and in addition, contain the detail and information specified above. Final approved contractor designs identified as CDCF shall be suitable for microfilming. They must be nonreproducible diazo or electrostatic prints of top quality full size with black line on white background and shall provide a legible print produced via the 35-MM microfilm process. Contractor shall submit one copy of the final design as a rolled set or flat set.

6.3.7 *Submission of contractor designs.* Designs shall be submitted for approval to the Commanding Officer, Picatinny Arsenal, ATTN: SMUPA–ND. Design review will normally be accomplished within 1 month after receipt by Picatinny Arsenal. Partial submission of inspection equipment designs is permissible and encouraged. However, the Arsenal completion date for design review will be based on the date of the final submission of designs."

* *Page 17:* Delete paragraphs 6.6, 6.6.1, and 6.6.2 in their entirety.

*Asterisks indicate changes in addition to or differing from those of Amendment 2.

Custodian:

Army—MU

Project Number: 1390–A533

Preparing activity:

Army—MU

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T23:08Z
Check the source to verify that this is the current version before use.