MILITARY
SPECIFICATION

MIL-L-12626(SigC)
7 April 1953
Superseding U. S. Army
Specification 75-102-A
22 October 1945

LIGHT, SIGNAL
(SIGNAL LAMP EQUIPMENT SE-11-( ))

1. SCOPE

1.1 This specification covers a light, portable field equipment for transmitting messages by means of white or red flashes of light designated as Signal Lamp Equipment SE-11( ) (See 6.4).

2. APPLICABLE SPECIFICATIONS, STANDARDS, AND DRAWINGS.

2.1 The following specifications, standards, and drawings of the issue in effect on date of invitation for bids form a part of this specification:

SPECIFICATIONS

FEDERAL

NN-B-591	Boxes, Fiberboard, Wood Cleated (For Domestic Shipment).
NN-B-601	Boxes, Wood-Cleated-Plywood, for Domestic Shipment.
NN-B-621	Boxes, Wood, Nailed and Lock-Corner.
UU-T-111	Tape; Paper, Gummed (Sealing and Securing).
LLL-B-631	Boxes; Fiber Corrugated (For Domestic Shipment).

MILITARY

*JAN-B-18	Batteries, Dry
JAN-P-105	Packaging and Packing for Overseas Shipment - Boxes; Wood, Cleated, Plywood.
JAN-P-106	Packaging and Packing for Overseas Shipment - Boxes; Wood, Nailed.
MIL-B-107	Boxes, Wood, Wirebound (Overseas Type).
JAN-P-108	Packaging and Packing for Overseas Shipment - Boxes, Fiberboard (V-Board and W-Board), Exterior and Interior.
MIL-P-116	Preservation, Methods of.
JAN-P-117	Packaging and Packing for Overseas Shipment - Bags, Interior Packaging.
JAN-P-127	Packaging and Packing for Overseas Shipment - Tape, Adhesive, Pressure-Sensitive, Water Resistant.
MIL-B-131	Barrier-Material; Water-Vaporproof, Flexible
MIL-P-11268	Parts, Materials, and Processes used in Signal Corps Equipment; General Specification.

*For informational purposes.

Source: https://assist.dla.mil -- Downloaded: 2026-01-17T22:06Z
Check the source to verify that this is the current version before use.

U. S. ARMY

19-10	Filler, Interior Packing, Fiberboard, Corrugated, Signal and Double Faced, for General Packing Purposes.

STANDARDS

MILITARY

JAN-STD-15	Electrical and Electronic Symbols.
MIL-STD-105	Sampling Procedures and Tables for Inspection by Attributes.
MIL-STD-129	Marking of Shipments.

DRAWINGS

SIGNAL CORPS

460-12	Group B-2 Sampling Plans.
SC-D-6615	Goggles M-172
SC-D-15800	Oscilloscope BC-000, Circuit Label.
SC-D-15801	Junction Box JB-00, Circuit Label, Wiring.
SC-D-15914	Moisture Resistance Test Cycle for Ground Signal Equipment.
SC-D-19999	Standard Extreme Temperature Cycle.
SC-DL-29893	Cord CD-701
SC-DL-86486	Signal Lamp M-438( ).
SC-DL-86487	Bag BG-194
SC-DL-86488	Gun Stock M-437( ).
SC-DL-86489	Tripod M-21( )
SC-DL-86490	Key J-51
SC-DL-86494	Filter MC-430

(Copies of specifications, standards and drawings required by contractors in connection with specific procurement functions should be obtained from or as directed by the contracting officer. Both the title and identifying number or symbol should be stipulated when requesting copies.)

Source: https://assist.dla.mil -- Downloaded: 202610-17T23:06Z
Check the source to verify that this is the current version before use.

3. REQUIREMENTS

3.1 Description.- Signal Lamp Equipment SE-11( ) shall be a light portable field equipment for transmitting messages by means of white or red flashes of light in International Morse Code. The equipment shall operate on five each Battery BA-30 in accordance with Military Specification JAN-B-18 and shall have collapsible sights, similar to those of a rifle, for training the light beam from Lamp LM-61 on the target, and shall be provided with a pistol-type grip and removable gun-stock for hand held operation. The lamp shall be capable of being mounted on a swivel-head tripod for remote operation.

3.2 Preproduction samples.-

3.2.1 Quantities.- After award of contract, preproduction samples shall be furnished as listed in table I (See 6.3.2).

Table I - Preproduction samples

Sample	Quantity
Complete equipment for performance test - - - - - - - - - - - - - - -	2
Telephone-type keys of each type - - - - - - - - - - - - - - - - - -	4
Insulated hookup wire of each type used for special specifications	35 feet

3.2.2 Compliance with specified requirements.-

3.2.2.1 Preproduction samples shall meet specified requirements, shall be made and assembled by tools and methods that will be used for quantity production, and shall be accompanied by a statement to that effect. (See 3.2.2.3 for exception)

3.2.2.2 Approval of preproduction samples shall not be construed as a waiver of any specified requirement. After being released to the contractor (See 3.2.4) preproduction samples to be offered as units on contract shall be refabricated by the contractor if necessary to meet specified requirements.

3.2.2.3 When deviation from 3.2.2.1 is unavoidable, the preproduction samples may be submitted for approval provided that the accompanying statement describes in detail each nonconforming feature, reason therefor, and manner in which it will be corrected in production of equipment on contract.

3.2.3 Test data.- The preproduction samples shall be accompanied by test data showing compliance with specified performance. The test data shall comprise an engineering report giving test procedure, observations and other data, calculations, test results, and essential details of the testing equipment (manufacturer's model, serial number, date of calibration, and the like).

Source: https://assist.dla.mil -- Downloaded: 202610-17T23:06Z
Check the source to verify that this is the current version before use.

3.2.4 Reference standards.- After preproduction samples have been approved and returned to the contractor's plant, they shall be kept intact in custody of the Government inspector until released by him. They shall be used as reference standards to resolve any differences of opinion regarding interpretation of requirements.

3.2.5 Preproduction inspection.- Preproduction samples may be submitted by the Government to the group A inspection and non-destructive group B inspection specified in table IV, and V, respectively, and to the preproduction inspection specified in table II. Unlisted non-destructive inspection on preproduction samples of equipment and unlisted and non-destructive inspection on separate preproduction samples of parts or materials may be performed to determine compliance with specified requirements. Preproduction inspection will normally be performed in this order: (1) vibration, (2) bounce, (3) immersion; other preproduction inspection may precede, follow, or be interspersed between the foregoing.

Table II

Inspection	Requirements paragraph	Test paragraph
Bounce test	3.4	4.2
Drop test	3.4	4.3
Vibration test	3.4	4.4
Moisture resistance	3.3	4.5
Temperature test	3.3	4.6
Immersion test	3.3	4.8.1

3.3 Service conditions.- The equipment shall meet the following service conditions:

3.3.1 Equipment operating.- The equipment shall meet the requirements of this specification under any probable combination of the following:

a. Operation. Continuous operation in any specified manner, for a period of 1 year, alternating 6 hours on with 2 hours off, except for battery replacement.

b. Temperature. Any ambient temperature in the range of -40 to 150° F., including sun load.

c. Elevation. Any elevation up to 10,000 feet above sea level.

d. Relative humidity.- Any relative humidity up to 95 percent.

e. Dust. Dust as encountered during heavy traffic over dry clay roads.

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T23:06Z
Check the source to verify that this is the current version before use.

3.3.2 Equipment non-operating.- The equipment shall meet the requirements of 3.3.1 after subjection to any one or more of the following non-operating conditions:

a. Temperature. Continuous exposure for 72 hours at 160° F. and 72 hours at -80° F., at any orientation.

b. Elevation. Elevations up to 50,000 feet above sea level.

c. Relative humidity. Relative humidity up to 100 percent, including condensation caused by temperature changes.

d. Immersion. See 4.8.

e. Orientation. Indefinite storage in any orientation.

f. Vibration, bounce, and drop. See 3.4.

3.4 Vibration, bounce and shock.-

3.4.1 Vibration.- Except for internal resonance of parts and subassemblies specified herein, the equipment shall have no mechanical resonance below 55 cycles per second.

3.4.2 Bounce and shock.- The equipment shall meet the tests of table III.

Table III- Bounce and shock test

Test	Test paragraph	Requirements after test
Bounce, 3-hour	4.2	Full specification performance. No physical damage except surface abrasion
Drop	4.3	Equipment shall be operable. No physical damage except surface abrasion.

Source: https://assist.dla.mil -- Downloaded: 20261O-17T23:06Z
Check the source to verify that this is the current version before use.

3.5 Detail requirements.- Unless otherwise specified components of Signal Lamp Equipment SE-11( ) shall be constructed in accordance with the following drawings:

Goggles M-172( )	SC-D-6615
Gun Stock M-437( )	SC-DL-86488
Tripod LG-21( )	SC-DL-86489
Key J-51( )	SC-DL-86490
Filter MC-430( )	SC-DL-86494
Bag BG-194( )	SC-DL-86487
Cord CD-701( )	SC-DL-29893
Signal Lamp M-438( ) (3.5.1)	SC-DL-86486

3.5.1 Signal Lamp M-438( ).- Signal Lamp M-438( ) shall be constructed in accordance with Drawing SC-DL-86486. The contour of the reflector shall be essentially parabolic reflecting a beam of light conforming to 3.5.1.1. The reflecting surface shall be adequately plated and polished to assure a coefficient of reflection of at least 75 when tested as specified, in 4.9.1. The reflecting surface shall be smooth and free from bubbles or pits. The reflector shall be lacquered on the inside surface only. The lacquer shall not react chemically with either the gaskets or the reflector.

3.5.1.1 Light projection.- Signal Lamp M-438( ) shall project a concentrated, nearly parallel, beam of light such that the projected spot of light showing on a screen normal to the axis of the projected light at a distance of thirty feet from the lens shall fill a circle whose diameter is 4.2 feet ± 6 inches. The beam spread shall be 8° ± 1°. The width of the beam is defined as the angle throughout which the intensity of light is equal to or greater than 10 percent of the maximum intensity.

3.5.1.2 Light intensity.- The Signal Lamp M-438( ) shall have a minimum intensity of illumination of 4000 beam candles when using the specified batteries, reflector, and Lamp bulb. (See 4.9.2)

3.5.1.3 Waterproofing.- The assembled Signal Lamp M-438( ) shall be completely waterproof. All gaskets, or other devices used for waterproofing, shall provide a seal which will prevent leakage of water or moisture into the signal lamp or onto electrical contacts of the trigger switch.

3.6 Circuit diagrams.- Circuit diagrams (schematic, wiring, and cabling) shall be furnished as required to facilitate installation, operation, and maintenance of the equipment. The diagrams shall be in the form of labels meeting the general requirements of Specification MIL-P-11268.

Source: https://assist.dla.mil -- Downloaded: 20261O-17T23:06Z
Check the source to verify that this is the current version before use.

3.6.1 Schematic and wiring diagrams.- Schematic and wiring diagrams shall be suitable for use by maintenance personnel, and shall be mounted so far as practicable on inside surfaces where they will not be exposed to abrasion or the elements but will be readily accessible to maintenance personnel. Graphical symbols on schematic diagrams shall conform to Standard JAN-STD-15. Schematic and wiring diagrams shall conform to the following sample drawings:

a. Schematic diagram of electronic component	SC-D-15800
b. Wiring diagram of an electrical component	SC-D-15801

3.7 Technical literature, tools, and running spare parts.- Technical literature, tools and running spare parts shall be furnished as specified by the contract. Running spare parts shall be identical to corresponding parts in the equipment furnished on the order. (See 6.1)

3.8 Facsimiles.- In addition to any facsimiles specified by applicable documents, the specified number of facsimile copies of the following shall be submitted for approval to the contracting officer:

	Number of copies required
a. Circuit Diagram	4 each
b. Wiring Diagram	4 each

3.9 Workmanship.- Components, subassemblies, and part shall be manufactured and assembled in a thoroughly workmanlike manner.

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T23:06Z
Check the source to verify that this is the current version before use.

4. SAMPLING, INSPECTION, AND TEST PROCEDURES

4.1 Inspection, general.- Government inspection shall consist of group A and group B inspection as specified in 4.1.1 through 4.1.2.3. (See 6.3.1). Group B inspection shall normally be performed on lots that have passed group A inspection and on samples selected from units that have been subjected to and met the group A inspection. However the order may be varied when the Government considers it more practical to select separate samples for group B inspection.

4.1.1 Group A inspection.- Group A inspection shall be in accordance with Table IV and Standard MIL-STD-105. Group A inspection shall be performed in any order which is satisfactory to the Government inspector, except that the operational examination shall be last.

Table IV - Government group A inspection

Inspection	Requirement Paragraph	Test Paragraph	AQL	
			Major	Minor
Visual and mechanical (Equipment and operational accessories)		4.7	1%	4%
Visual and mechanical (Bag BG-194)		4.7	1%	4%
Light projection test	3.5.1.1	4.9.1	}	
Intensity test	3.5.1.2	4.9.2	}1%	
Reflection test	3.5.1.3	4.9.3	}	
Operational test		4.10	1%	

4.1.2 Group B inspection.- Group B inspection shall be in accordance with Table V.

4.1.2.1 Sampling procedure.- Samples shall be selected in an unbiased manner by the Government inspector. Unless otherwise specified, inspection shall be started using level II of the applicable drawing listed in table V. If the number of defective sample units from a lot exceeds the acceptance number specified on the drawing, the lot shall be rejected. Disposition of rejected product (sample units and lots) shall be in accordance with Standard MIL-STD-105 and 4.1.4.

4.1.2.2 Procedure in case of failure.- When a lot is rejected, the contractor shall immediately investigate the cause of failure and shall report to the Government inspector the results thereof and proposed corrective action. If the contractor and Government inspector cannot agree on the corrective action to be taken, the matter shall be referred to the contracting officer for resolution.

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T23:06Z
Check the source to verify that this is the current version before use.

Table V - Government group B inspection

Inspection	Requirement Paragraph	Test Paragraph	Group B Plans	Drawings
Immersion test	3.3.2 3.5.1.3	4.8	B-2	460-12

4.1.3 Reinspection of conforming group B.- Unless otherwise specified sample units which have been subjected to and passed group B inspection may be accepted on contract, provided that all visible damage incurred during group B inspection is repaired and the units are then subjected to and pass group A inspection.

4.1.4 Disposition of nonconforming product.- When defective sample units, rejected lots, are submitted for acceptance, such items shall be suitably tagged or identified by equivalent means to indicate the cause of failure and means employed to correct the fault. The record shall be presented to the Government when the product is submitted and shall become the property of the Government.

4.2 Bounce test.- The equipment, in its shipping case shall be placed on the table of the Package Tester as made by the L.A.B. Corporation, Summit, New Jersey, or equal, and shall be constrained from horizontal motion of more than 2 inches by suitable wooden fences. The package tester, shafts in phase, shall be operated at a speed of 285 r.p.m. ± 1 percent, for a total of 3 hours. During each 1/2-hour period of the test, the transit case (with contained equipment) shall rest on a different face.

4.3 Drop test.- The equipment, in its shipping case shall be dropped a distance of 6 feet on each corner, edge, and face (total of 26 drops). Drops shall be made from a quick-release hook; an Acme Drop Tester, or equal; a Conbur Tester (10-degree inclined plane), or equal; or a basket-type pendulum tester. The floor or barrier receiving the impact shall be 2-inch fir, backed by concrete or a rigid steel frame.

4.4 Vibration test.- The equipment shall be tested for resonant frequencies below 55 cycles per second, to determine compliance with 3.3.2, as follows:

(a) The equipment shall be fastened in its normal mounting position on a vibration table that can be controlled within 10 percent of the specified amplitude. The vibration table shall provide approximately sinusoidal vibration. (See 4.4(d).)

(b) The equipment shall be vibrated successively in three mutually perpendicular directions that are parallel respectively to the edges of the equipment, over a frequency range of 10 to 55 cycles per second, in 1-cycle-per-second steps. The total excursion shall be constant at 1/64 inch.

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T23:06Z
Check the source to verify that this is the current version before use.

4.4 (Contd)

(c) Mechanical resonance, if any, of the complete structure, of sub-assemblies, and of component parts shall be determined visually by means of a Strobotac, as made by the General Radio Corporation, Cambridge, Massachusetts, or equal, or by energizing the equipment and detecting mechanical vibration through electrical output indications.

4.5 Moisture-resistance test for equipment.-

4.5.1 Test conditions.-

(a) Do not move components from the humidity chamber for measurements.

(b) Start measurements not more than 5 minutes after power is applied to the components. Complete measurements as rapidly as possible. Do not leave power on after measurements have been completed.

(c) Test sealed components with the seal intact except during last two cycles. Bring out leads for electrical measurements through a hole in the case and seal against entrance of moisture. Perform last two cycles with sealed case removed.

4.5.2 Test procedure.- The components will be tested as follows:

(a) Dry at 130° ±5° F. for 24 hours.

(b) Condition at 77° ±5° F. and 40 to 50 percent relative humidity for 24 hours.

(c) Take measurements as specified in 4.5.3, and readjust or realine as necessary to meet full specification requirements.

(d) Subject to continuous cycling for five 48-hour cycles. Temperature, relative humidity, and period of time for each portion of the cycle shall conform to Drawing SC-D-15914. The measurements specified in 4.5.3 shall be made during the periods shown on the drawing and shall comply with 4.5.3.

(e) After cycling has been completed, condition the components for 24 hours at 77° ±5°F. and 40 to 60 percent relative humidity. Then adjust for optimum performance, using only those means provided by the components. No repair or replacement of parts shall be made. After adjustment, the components shall meet full specification requirements for those measurements specified in 4.5.3.

4.5.3 Performance.- Measurements made during test, and specified performance during cycling, shall insure meeting full specification requirements.

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T23:06Z
Check the source to verify that this is the current version before use.

4.5.4 Failure.- If any component fails to meet the performance specified in 4.5.3 during cycling, it shall be realined or readjusted once. If the component then fails to meet 4.5.3 or fails subsequently during cycling, it does not pass the test. In addition, if the component fails to meet full specification requirements as specified in 4.5.2(e), it does not pass the test.

4.6 Temperature test for equipment.- The equipment shall be subjected to the temperature cycle shown on Drawing SC-D-19999. Measurements shall be taken at steps 1, 3, 5, 8, and 10 to insure meeting full specification requirements.

4.7 Visual and mechanical inspection.- Parts and equipment shall be inspected for workmanship, mechanical fit, loose nuts and screws, application of specified tropicalization treatments, and miscellaneous defects. Controls and fastening devices shall be inspected for mechanical operation. Wiring, soldered connections, ground connections, welds, finishes, etc. shall be inspected for workmanship. Clearances, dimensions, and mechanical adjustments shall be measured. Labels and markings shall be inspected for conformance with approved facsimiles, when facsimiles are required. Examination also may be made for other visual or mechanical defects, similar to those described above, that are contrary to specified requirements for the equipment. Visual and mechanical defects shall be classified by the Government as major or minor in accordance with the definitions of Standard MIL-STD-105.

4.8 Immersion test.-

4.8.1 Preproduction test.- Signal Lamp M-438, charged with dummy batteries, shall be immersed to a minimum depth of 3-feet of fresh water for 2-hours. Immediately prior to immersion, the temperature of the equipment shall be approximately 40°F above the temperature of the water. The tank in which the equipment is immersed shall be of sufficient capacity to maintain the water at approximately its initial temperature, or the temperature of the water shall be maintained constant by other means. After completion of the 2-hour period of immersion, the equipment shall be removed from the water and wiped dry on exterior surfaces. There shall be no evidence of leakage.

4.8.2 Acceptance test.- Signal Lamp M-438, charged with dummy batteries, shall be immersed to a minimum depth of 2-feet of fresh water for a period of 1-hour. Immediately prior to immersion the temperature of the equipment shall be approximately 40°F above the temperature of the water. The tank in which the equipment is immersed shall be of sufficient capacity to maintain the water at approximately its initial temperature or the temperature of the water shall be maintained constant by other means.

4.8.2.1 Upon removal from the water, the signal lamp shall be charged with live batteries and then operated. There shall be no shorting of electrical contacts, or leakage of water in the trigger-switch, barrel assembly or reflector assembly. The signal lamp shall operate normally by means of either the trigger-switch or Key J-51.

Source: https://assist.dla.mil -- Downloaded: 202610-17T23:06Z
Check the source to verify that this is the current version before use.

4.9 Performance testing.-

4.9.1 Light projection test.- The signal lamp shall be tested for compliance with 3.5.1.1 by projecting the light from the signal lamp onto a screen as described in 3.5.1.1.

4.9.2 Intensity test.- The signal lamp shall be tested for intensity of illumination, using the specified batteries, reflector and lamp bulb. A minimum bean candle power of 4000 beam candles shall be obtained at the center of the beam approximately 1 feet from the lens.

4.9.3 Reflector test.- The reflector of the signal lamp shall be tested as follows: A small piece of absorbent cotton shall be saturated with concentrated nitric acid and the reflector surface swabbed with the saturated cotton. The surface shall give no indication of discontinuity of finish when the acid is applied.

4.10 Operation test.- Signal Lamp Equipment SE-11( ) assembled for field use shall be tested to insure proper operation and fit of all components. Signal Lamp M-438 shall be mounted on Tripod LG-21( ) to ascertain proper fit and freedom of rotation, the signal lamp shall operate normally by means of either the trigger-switch or Key J-51( ). Gun Stock M-437( ) shall be attached to the signal lamp, inspected for proper fit and normal operation using trigger-switch.

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T23:06Z
Check the source to verify that this is the current version before use.

5. PREPARATION FOR DELIVERY

5.1 Preservation and packaging.-

5.1.1 For domestic shipment.- Signal Lamp Equipment SE-11-( ) shall be preserved and packaged in accordance with Method III of Specification MIL-P-116.

5.1.2 For export shipment.- Preserve and package Signal Lamp Equipment SE-11-( ) in accordance with procedures specified for the designated methods as prescribed in Specification MIL-P-116, and further described in the following paragraphs.

5.1.2.1 Technical manual.- Package each technical manual Method 1C-3, as follows: Inclose each technical manual within a close-fitting Type II Class b bag, conforming to Specification JAN-P-117. Properly seal closure.

5.1.2.2 Signal Lamp Equipment SE-11-( ) within bag.- Package each lamp equipment within bag Method IIb, as follows: As required cushion each component of signal lamp equipment, determined in quantity and number from the bid request or contract, by wrapping in flexible corrugated paper, secure cushioning with gummed Kraft tape. Place and secure each cushioned item within designated bag. Fill all voids with flexible corrugated paper to prevent movement. Close cover and secure fastenings. Cushion each bag on all surfaces with cells or pads or both fabricated of corrugated fiberboard, conforming to Specification 19-10 and designed to absorb the shock of impact normally encountered in handling and transit. Place each cushioned bag together with the required amount of desiccant as prescribed in Specification MIL-P-116, within a close-fitting suitable style and grade corrugated fiberboard box. Seal entire closure with gummed Kraft tape conforming to Specification UU-T-111. Blunt all corners of the box. Place the boxed bag within a water-vapor-proof barrier, qualified for Class 2 application in accordance with the requirements of Specification MIL-B-131. Heat seal closure. Place the water-vapor-proofed bag within a close-fitting suitable style and grade fiberboard box conforming to Specification JAN-P-108. Seal entire box closure, corners and joints with water-resistant pressure-sensitive tape, conforming to Specification JAN-P-127. Place and secure technical manual packaged as specified in 5.1.2.1 to packaged item with water-resistant tape.

5.2 Packing.-

5.2.1 For domestic shipment.- Signal Lamp Equipment SE-11( ) shall be packed in wood-cleated fiberboard, wood-cleated plywood, nailed wood, or corrugated fiberboard boxes conforming to specification NN-B-595, NN-B-601, NN-B-621, and LLL-B-631, respectively. Closures shall be made in accordance with the applicable box specification.

5.2.2 For export shipment.- Place a quantity of Signal Lamp Equipment SE-11-( ) within bag, packaged as specified in 5.1.2.2, together within a wood cleated plywood nailed wood or wire bound wood box conforming to the requirements of Specification JAN-P-105, JAN-P-106 and MIL-B-107 respectively. Fabricate the boxes to fit contents snugly. The approximate gross weight of any exterior shipping container shall not exceed 150 pounds. Close the shipping container as specified in the appendix of the applicable box specification.

Source: https://assist.dla.mil -- Downloaded: 202640-17T23:06Z
Check the source to verify that this is the current version before use.

5.2.2.1 Shipping containers shall be strapped in conformance with the requirements of the appendix of the applicable container specification only for direct shipment to ports.

5.3 Marking for shipment.- Interior packaged and exterior shipping containers shall be marked in accordance with applicable provisions of MIL-STD-129.

6. NOTES

6.1 Ordering data.- Procurement documents should specify the following:

(a) Title, number, and date of this specification.
(b) Type required.
(c) Whether domestic or overseas shipment is required.
(d) Samples required. (See 3.2)
(e) Marking and shipping of samples.
(f) Place of final inspection. (See 4.1)
(g) Acceptable quality level. (See 4.1)
(h) Facsimiles required. (See 3.8)
(i) Technical literature required. (See 3.7)
(j) Quantity of tools and running spare parts required. (See 3.7)

6.2 Color of textiles.- Standard samples of Olive Drab No. 7 may be obtained from Specifications and Quality Control Branch, Philadelphia Quartermaster Depot, 2800 South Twentieth Street, Philadelphia 45, Pennsylvania. When requesting samples, indication should be given as to type of material concerned.

6.3 Contractual requirements.- It is recommended that the following be included in the contract.

6.3.1 Additional testing.- It should be understood that additional inspection and nondestructive testing of equipment may be performed by the Government inspector when considered necessary to determine compliance with this specification and other applicable documents. The government inspector, therefore, may withdraw materials, parts, sub-assemblies, or components temporarily from production for such inspection and testing, performed either at a Government laboratory or the contractor's plant.

6.3.2 Waiver of preproduction samples.- When items for which preproduction samples are required are currently in production on a Government order, the contractor may apply to the contracting officer for waiver of preproduction samples on the new order. Any request for waiver should include a statement indicating that the specified samples have been submitted and approved on the current contract; production of the item under the new order will be concurrent with, or follow without interruption, production on the current order; and current production is in strict compliance with specified requirements for the new equipment, or describing any deviations authorized on the current order. Waiver of preproduction samples may be contingent on renegotiation of the contract to reflect the saving in cost to the contractor.

Source: https://assist.dla.mil -- Downloaded: 202610-17T23:06Z
Check the source to verify that this is.the currenversion before use.

6.4 Nomenclature.- The parentheses in the nomenclature will be deleted or replaced by a letter identifying the particular design, for example SE-11W. As soon as possible after the award of the contract, the contractor should apply to the contracting officer for such information. (See 1.1)

NOTICE: When Government drawings, specifications, or other data are used for any purpose other than in connection with a definitely related Government procurement operation, the United States Government thereby incurs no responsibility nor any obligation whatsoever; and the fact that the Government may have formulated, furnished, or in any way supplied the said drawings, specifications, or other data is not to be regarded by implication or otherwise as in any manner licensing the holder or any other person or corporation, or conveying any rights or permission to manufacture, use or sell any patented invention that may in any way be related thereto.

Source: https://assist.dla.mil -- Downloaded: 202610-17T23:06Z
Check the source to verify that this is the current version before use.