MILITARY SPECIFICATION

CHARGE ASSEMBLY, DEMOLITION KIT, M37 FOR BLOCK DEMOLITION, M5A1, PARTS FOR LOADING, ASSEMBLY AND PACKING

1. SCOPE

1.1 This specification covers special requirements not covered by the drawings and provides quality assurance provisions for the fabrication of parts, loading, assembling and packing for one type of demolition item, designated as Charge Assembly, Demolition, M37 for Block Demolition M5A1.

2. APPLICABLE DOCUMENTS

2.1 The following documents of the issue in effect on date of invitation for bids or request for proposal, form a part of this specification to the extent specified herein.

SPECIFICATIONS

MILITARY

MIL-A-2550 —General Specification for Ammunition Except Small Arms Ammunition.

MIL-I-45208 —Inspection Requirements, General Specification for.

MIL-I-45607 —Inspection Equipment, Supply and Maintenance of.

STANDARDS

MILITARY

MIL-STD-105D —Sampling Procedures and Tables for Inspection by Attributes.

MIL-STD-109 —Quality Assurance Terms and Definitions.

MIL-STD-1235 —Single and Multilevel Continuous Sampling Procedures and Table for Inspection by Attributes.

DRAWINGS

ORDNANCE CORPS

8861107—Charge Assembly, Demolition, M37 for Block Demolition, M5A1, Assembly.

8883618—Box, Packing, Ammunition, for Charge Assembly, Demolition, M37.

8796522—Marking Diagram and Sealing.

PUBLICATIONS

ORDNANCE CORPS

IEL-8861107—Index of Inspection Equipment Lists.

(Copies of specifications, standards, drawings and publications required by contractors in connection with specific procurement functions should be obtained from the procuring activity or as directed by the Contracting Officer.)

2.2 **Other publications.** The following document forms a part of this specification to the extent specified herein. Unless otherwise indicated, the issue in effect on date of invitation for bids shall apply.

FSC 1375

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T00:05Z
Check the source to verify that this is the current version before use.

CODE OF FEDERAL REGULATIONS

49 CFR 71–90 —Interstate Commerce Commission Rules and Regulations for the Transportation of Explosives and Other Dangerous Articles.

(The Interstate Commerce Commission Regulations are now a part of the Code of Federal Regulations (1949 Edition and revisions) available from the Superintendent of Documents, Government Printing Office, Washington 25, D.C. Orders for the above publication should cite "49 CFR 71–90 (latest revisions)".)

3. REQUIREMENTS

3.1 Material. Materials and parts shall be in accordance with applicable drawings and specifications.

3.2 The Charge Assembly, Demolition, M37, shall comply with all the requirements specified on Drawing (dwg.) 8861107 and all drawings referenced thereon, and with all requirements specified in applicable specifications.

3.3 Workmanship. All parts and assemblies shall be fabricated and loaded in a thorough, workmanlike manner. They shall be free of burrs, sharp edges, cracks, dirt, grease, and other foreign matter. Charges shall be free of breaks, cracks and other defects which could prohibit proper functioning. Colors shall be uniform. All required markings shall be neat and sharply defined.

4. QUALITY ASSURANCE PROVISIONS

4.1 General quality assurance provisions. The supplier is responsible for the performance of all inspection requirements specified herein. Except as otherwise specified, the supplier may utilize his own or any other inspection facilities and services acceptable to the Government. Inspection records of the examinations and tests shall be kept complete and available to the Government as specified in the contract or order. The Government reserves the right to perform any of the inspections set forth in the specification where such inspections are deemed necessary to assure that supplies and services conform to prescribed requirements. Reference shall be made to Standard MIL–STD–109 in order to define terms used herein. The provisions of Specification MIL–A–2550 shall apply.

4.1.1. *Contractor quality assurance system.* The contractor shall provide and maintain an effective quality assurance system in compliance with the requirements of Specification MIL–I–45208.

4.1.2 *Submission of product.* At the time the completed lot of product is submitted to the Government for acceptance the contractor shall supply the following information accompanied by a certificate which attests that the information provided is correct and applicable to the product being submitted:

(a) A statement that the lot complies with all quality assurance provisions of the approved current written description of the system.
(b) Number of units of product inspected.
(c) Results obtained for all inspection performed.
(d) Drawing, specification number and date, together with an identification and date of changes.
(e) Certificates of analyses on all material procured directly by the contractor when such material is controlled by Government specifications referenced in any of the contractual documents.
(f) Number of items in the lot.
(g) Date submitted.

The certificate shall be signed by a responsible agent of the certifying organization. The initial certificate submitted shall be substantiated by evidence of the agent's authority to bind his principal. Substantiation of the agent's authority will not be required with subsequent certificates unless, during the course of the contract, this authority is vested in another agent of the certifying organization.

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T00:05Z
Check the source to verify that this is the current version before use.

4.1.3 *Government verification.* Using the contractor's written quality assurance procedure, this detail specification, the applicable drawings and other contractual documents as a guide, the Government inspector shall verify at unscheduled intervals all quality assurance operations performed by the contractor. Verification will be in accordance with Specification MIL–I–45208 and will be performed to the extent necessary to assure compliance with the contractual requirements. Severity of Government inspection of individual characteristics will be directly related to the seriousness of the classification assigned. In no instance will a characteristic classified "critical" be accepted solely on the basis of the contractor's records.

4.2 Inspection provisions.

4.2.1 *Lot formation.* A lot shall consist of Charge Assemblies, Demolition, M37, for Block Demolition M5A1 produced by one manufacturer in one unchanged process, in accordance with the same drawing, same drawing revision, same specification, and same specification revision. Drawing, specification, and process changes not affecting safety, performance, or fit, as determined by the Government, shall not necessitate changing the lot interfix number. Lots shall be submitted for inspection in accordance with Standard MIL–STD–105D (or Standard MIL–STD–1235 when applicable).

Each lot shall contain:

(a) Parts or parts assemblies having the same interfix number from one manufacturer.
(b) Bag assemblies of one lot interfix number from one manufacturer.
(c) Demolition blocks of one lot interfix number from one manufacturer.
(d) Priming assemblies of one lot interfix number from one manufacturer.
(e) Carrying case assemblies of one lot interfix number from one manufacturer.

4.2.2 *Examination.* Sampling plans and procedures for the following classifications of defects shall be in accordance with Standard MIL–STD–105D except that inspection for critical defects, when listed, shall be 100 percent. Continuous sampling plans in accordance with Standard MIL–STD–1235 may be used if approved by the procuring activity. Also, at the option of the procuring activity, AQL's and sampling plans may be applied to the individual characteristics listed using an AQL of 0.25 percent for each major defect and an AQL of 0.40 percent for each minor defect. Equipment necessary for the performance of the inspections listed shall be in accordance with 4.2.4.

4.2.2.1 Loading assembly (see dwg. 8833395, covering a detail of dwg. 8861113).

Categories	*Defects*	*Method of inspection*	*Code No. (see 6.2)*
Critical:	None defined.		
Major:	None defined.		
Minor:	AQL 1.5 percent		
201.	Sides warped or wrinkled	Visual	01001
202.	Cut, puncture, tear or burn through	Visual	01002
203.	Marking missing, incomplete, improper or unidentifiable	Visual	01003
204.	Cracks in body	Visual	01004

4.2.2.2 Bag assembly (see dwg. 8861111 covering a detail of dwg. 8861113).

Categories	*Defects*	*Method of inspection*	*Code No.*
Critical:	None defined.		
Major:	None defined.		
Minor:	AQL 1.5 percent		
201.	Cut, puncture or tear	Visual	02001
202.	Stitch or seam loose or open	Visual	02002
203.	Assembly of any component damaged, missing or mislocated	Visual	02003

4.2.2.3 Envelope (see dwg. 8861307 covering a detail of dwg. 886117).

Categories	*Defects*	*Method of inspection*	*Code No.*
Critical:	None defined.		
Major:	None defined.		
Minor:	AQL 1.0 percent		
201.	Glue, missing or inadequate	Visual-Manual	03001

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T00:05Z
Check the source to verify that this is the current version before use.

4.2.2.4 Hook (see dwg. 8861114 covering a detail of dwg. 8861118).

Categories	Defects	Method of inspection	Code No.
Critical:	None defined.		
Major:	None defined.		
Minor:	AQL 2.5 percent		
201.	Diameter of hole	Gage	04001
202.	Overall length	Gage	04002
203.	Overall width	Gage	04003
204.	Thickness, min.	Gage	04004
205.	Hole improperly located	Gage	04005
206.	Hole missing	Visual	04006
207.	Evidence of poor workmanship (see 3.3)	Visual	04007

4.2.2.5 Demolition block hook assembly (see dwg. 8861118 covering a detail of dwg. 8861117).

Categories	Defects	Method of inspection	Code No.
Critical:	None defined.		
Major:	None defined.		
Minor:	AQL 1.5 percent		
201.	Knots improperly tied	Visual	05001
202.	Insufficient number of knots, min.	Visual	05002
203.	Length of cord inadequate	Visual	05003
204.	Cord improperly affixed to hook	Visual	05004

4.2.2.6 Envelope assembly (see dwg. 8861117 covering a detail of dwg. 8861113).

Categories	Defects	Method of inspection	Code No.
Critical:	None defined.		
Major:	None defined.		
Minor:	AQL 1.5 percent		
201.	Overall length	Gage	06001
202.	Overall width	Gage	06002
203.	Cord not wrapped around hooks	Visual	06003
204.	Envelope improperly folded	Visual	06004

4.2.2.7 Demolition block bag assembly (see dwg. 8861113).

Categories	Defects	Method of inspection	Code No.
Critical:	None defined.		
Major:	AQL 0.65 percent		
101.	Filler missing or improperly assembled in bag	Visual	07001
102.	Separator missing or improperly assembled in bag	Visual	07002
103.	Incorrect quantity envelope assemblies	Visual	07003
104.	Incorrect quantity of demolition blocks	Visual	07004
105.	Envelope improperly assembled in bag	Visual	07005
106.	Cord untied or improperly tied	Visual	07006
Minor:	None defined.		

4.2.2.8 Charge assembly, demolition, M37 for block, demolition M5A1, assembly (see dwg. 8861107).

Categories	Defects	Method of inspection	Code No.
Critical:	None defined.		
Major:	AQL 0.40 percent		
101.	Priming assembly missing	Visual	08001
102.	Demolition block bag assembly missing	Visual	08002
103.	Tight coils or kinks in priming assembly	Visual	08003
Minor:	AQL 4.0 percent		
201.	Marking missing, incomplete, improper or unidentifiable	Visual	08004
202.	Cut, puncture or tear	Visual	08005
203.	Trace assembled improperly	Visual	08006
204.	Strap improperly tied	Visual	08007
205.	Components loose in carrying case	Visual-Manual	08008
206.	Loaders lot number missing	Visual	08009
207.	Date of loading missing or improper	Visual	08010
208.	Evidence of poor workmanship (see 3.3)	Visual	08011

4.2.2.9 Box, packing (see dwg. 8883618).

Categories	Defects	Method of inspection	Code No.
Critical:	None defined.		
Major:	AQL 0.40 percent		
101.	Incorrect number of assemblies	Visual	09001
102.	Assembly or component improperly inserted	Visual	09002
103.	Assembly or component improper type	Visual	09003
Minor:	AQL 0.40 percent		
201.	Filler missing or improperly assembled	Visual	09004

4.2.2.10 Box, packing, marking, closing, sealing and strapping (see dwgs. 8796522 and 8883618).

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T00:05Z
Check the source to verify that this is the current version before use.

Categories	*Defects*	*Method of inspection*	*Code No.*
Critical: None defined.			
Major:	AQL 0.65 percent		
101.	I.C.C. marking missing, incorrect, improper or illegible	Visual	10001
102.	Descriptive nomenclature missing, incorrect, improper or illegible	Visual	10002
103.	Strapping improper	Visual	10003
104.	Car seal, missing or improperly positioned or sealed	Visual	10004
105.	Contents loose when box is tilted	Visual-Manual	10005
106.	Board, broken or split	Visual	10006
107.	Box damaged, so that its contents are exposed or liable to become exposed	Visual	10007
Minor: None defined.			

4.2.3 *Inspection equipment.* Index of Inspection Equipment Number IEL–8861107 identifies the inspection equipment required to perform the examinations and tests prescribed in this section. The contractor shall design inspection equipment in accordance with the instructions in paragraph 6.3.

4.2.3.1 *Government rights to documentation.* Inspection equipment drawings and lists provided and revised in accordance with the requirements of the IEL may be used by DOD activities for design, procurement, manufacture, testing, evaluation, production and receiving inspection, overhaul, shipping, storage, identification of stock, ordering and storage of replacement of parts, inspection of items at overhaul, general maintenance of equipment, construction, survey and wherever inspection equipment drawings are needed.

4.2.3.2 *Supply and maintenance.* Supply and maintenance of the equipment listed on the IEL shall be in accordance with Specification MIL–I–45607.

4.2.3.3 *Government use of contractor's inspection and test equipment.* The contractor shall make available to the Government all inspection and test equipment necessary for determining conformance with contract requirements. Personnel for operating the equipment, and verification of its accuracy, shall be supplied by the contractor for the performance of examination or test by the Government.

5. PREPARATION FOR DELIVERY

5.1 Preservation and packing.

5.1.1 Packing and preservation for levels A, B and C shall be as specified in drawings 8883618 and 8796522.

5.2 Marking. Marking of all packaging and packing shall comply with dwg. 8796522.

5.3 Data cards. Data cards shall be prepared for each lot in accordance with the information specified in Specification MIL–A–2550.

6. NOTES

6.1 Ordering data. Procurement documents shall specify the following:

(a) Title, number and date of this specification.

6.2 Inspection code numbers. The five digit code numbers assigned to the inspections herein are to facilitate future data collection and analysis by the Government.

6.3 Inspection equipment. The contractor shall design inspection equipment as required by the referenced Inspection Equipment Lists (IEL) in accordance with the instructions of 6.3.1 through 6.3.7.

6.3.1 *Inspection equipment lists.* Inspection equipment lists indicate the availability of inspection equipment designs by showing in the "number" column of the list of inspection equipment (OO Form 1242–3) the numbers of drawings of existing equipment designs or codes as indicated in 6.3.2. Design action required of the contractor with respect to the different types of drawings that may be listed is described in 6.3.3 and 6.3.4. Action required by the contractor with respect to commercial inspection equipment is described in 6.3.5. The contractor will be required to prepare detailed drawings in ac-

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T00:05Z
Check the source to verify that this is the current version before use.

cordance with 6.3.6 for all the equipment coded as "contractor design" in the number column. These contractor designs must be approved by the Government prior to fabrication or procuring of the equipment. Designs shall be submitted for approval as specified in 6.3.7.

6.3.2 *Inspection equipment list codes.* The inspection equipment as defined in 6.3.3, 6.3.4, 6.3.5, and 6.3.6 will be designated in the inspection equipment list by the following codes:

CDOF —Contractor's design responsibility on Ordnance format; ORDM–608–12.
CDCF —Contractor's design responsibility on contractor format.
OD —Ordnance design.
ODMU —Ordnance design, mandatory for use.
CE —Commercial equipment.
SCD —Specification Control Drawing.

6.3.3. *Ordnance designs.* Ordnance designs are reflected on detailed drawings which completely depict all the information necessary for the fabrication of the item of inspection equipment. The contractor need provide no design when an Ordnance design is listed for an item of inspection equipment. Ordnance designs fall into two basic classifications; mandatory and nonmandatory. When an Inspection Equipment List references mandatory Ordnance designs, the contractor shall comply with, and use these designs accordingly. The contractor may, however, in connection with nonmandatory designs and with the approval of the Government, design alternate inspection equipment or use comparable commercial equipment to facilitate his operations. Such contractor prepared designs or comercial equipment selections must be approved by the Government prior to fabrication or procuring of the equipment. Designs shall be submitted for approval as specified in 6.3.7.

6.3.4 *Specification control drawings.* Specification control drawings depict the minimum equipment requirements in outline, descriptive, diagrammatic, or pictorial form only and specify the required performance or other characteristics. Contractors must prepare detailed drawings (see 6.3.6) of their designs in support of specification control drawings. These contractor prepared designs must be approved by the Government prior to the fabrication or procuring of the equipment. Commercial equipment meeting the requirements of specification control drawings may be approved if described in sufficient detail to permit identification and evaluation by the Government. Designs shall be submitted for approval as specified in 6.3.7.

6.3.5 *Commercial equipment.* Commercial equipment is inspection equipment that has universal application for a specific function. It is comprised of items commonly used by industry and government. Contractors are not required to furnish drawings of commercial inspection equipment but a list of such equipment must be approved by the Government. Lists shall be submitted for approval to the inspection element of the agency administering the contract.

6.3.6 *Contractor designs.* Contractor designs are designs of inspection equipment for which the Government has assigned design responsibility to the contractor. Contractor designs shall be supported by detailed drawings which depict all information necessary to completely fabricate, calibrate and operate an item of inspection equipment. This requires that the necessary views, dimensions, materials, finish, notes, operating and calibration instructions be properly depicted in accordance with approved practices to the extent that further calculation or clarification will not be required. Contractor designs identified as CDCF may be developed on the format the contractor normally employs in his equipment design procedure provided such format reflects the detail and information specified above. Contractor designs identified as CDOF shall comply with the format and requirements of ORDM 608–12, and, in addition, contain the detail and information specified above.

6.3.7 *Submission of contractor designs.*

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T00:05Z
Check the source to verify that this is the current version before use.

Designs shall be submitted for approval to the Commanding Officer, Picatinny Arsenal, ATTN: SMUPA–ND. Design review will normally be accomplished within one month after receipt by Picatinny Arsenal. Partial submission of inspection equipment designs is permissible and encouraged. However, the Arsenal completion date for design review will be based on the date of the final submission of designs.

Custodian:
Army—MU

Preparing activity:
Army—MU
Project No. 1375–A703

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T00:05Z
Check the source to verify that this is the current version before use.

SPECIFICATION ANALYSIS SHEET

Form Approved
Budget Bureau No. 119-R004

INSTRUCTIONS

This sheet is to be filled out by personnel either Government or contractor, involved in the use of the specification in procurement of products for ultimate use by the Department of Defense. This sheet is provided for obtaining information on the use of this specification which will insure that suitable products can be procured with a minimum amount of delay and at the least cost. Comments and the return of this form will be appreciated. Fold on lines on reverse side, staple in corner, and send to preparing activity *(as indicated on reverse hereof)*.

SPECIFICATION

ORGANIZATION *(Of submitter)* | CITY AND STATE

CONTRACT NO. | QUANTITY OF ITEMS PROCURED | DOLLAR AMOUNT $

MATERIAL PROCURED UNDER A

☐ DIRECT GOVERNMENT CONTRACT ☐ SUBCONTRACT

1. HAS ANY PART OF THE SPECIFICATION CREATED PROBLEMS OR REQUIRED INTERPRETATION IN PROCUREMENT USE?

A. GIVE PARAGRAPH NUMBER AND WORDING.

B. RECOMMENDATIONS FOR CORRECTING THE DEFICIENCIES.

2. COMMENTS ON ANY SPECIFICATION REQUIREMENT CONSIDERED TOO RIGID

3. IS THE SPECIFICATION RESTRICTIVE?

☐ YES ☐ NO IF "YES", IN WHAT WAY?

4. REMARKS *(Attach any pertinent data which may be of use in improving this specification. If there are additional papers, attach to form and place both in an envelope addressed to preparing activity)*

SUBMITTED BY *(Printed or typed name and activity)* | DATE

DD FORM 1 APR 63 1426 REPLACES NAVSHIPS FORM 4863, WHICH IS OBSOLETE PLATE NO. 15419

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T00:05Z
Check the source to verify that this is the current version before use.

FOLD

DEPARTMENT OF THE NAVY

POSTAGE AND FEES
NAVY DEPARTME

OFFICIAL BUSINESS

FOLD

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T00:05Z
Check the source to verify that this is the current version before use.

PLATE NO. 154