INCH-POUND

MIL-T-52150E
26 July 1991
SUPERSEDING
MIL-T-52150D
3 February 1983

MILITARY SPECIFICATION

TRESTLE ASSEMBLY: UNIVERSAL TRANSOM, 60-TON, FOR FLOATING AND FIXED BRIDGES

This specification is approved for use within the USA Belvoir Research, Development, and Engineering Center, Department of the Army, and is available for use by all Departments and Agencies of the Department of Defense.

1. SCOPE

1.1 Scope. This specification covers a 60-ton trestle with universal transom for deck-balk-type superstructure of class 60 treadway-superstructure floating and fixed bridges.

2. APPLICABLE DOCUMENTS

2.1 Government documents.

2.1.1 Specifications and standards. Unless otherwise specified, the following specifications and standards of the issue listed in that issue of the Department of Defense Index of Specifications and Standards (DODISS) specified in the solicitation form a part of this specification to the extent specified herein.

Beneficial comments (recommendations, additions, deletions) and any pertinent data which may be of use in improving this document should be addressed to: USA Belvoir Research, Development, and Engineering Center, ATTN: STRBE-TSE, Fort Belvoir, VA 22060-5606 by using the Standardization Document Improvement Proposal (DD Form 1426) appearing at the end of this document or by letter.

AMSC N/A FSC 5420

DISTRIBUTION STATEMENT A. Approved for public release, distribution is unlimited.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T21:08Z
Check the source to verify that this is the current version before use.

SPECIFICATIONS

MILITARY

MIL-T-704	-	Treatment and Painting of Materiel.
MIL-P-23377	-	Primer Coating, Epoxy Polyamide, Chemical and Solvent Resistant.
MIL-I-24391	-	Insulation Tape, Electrical, Plastic, Pressure Sensitive.
MIL-S-81733	-	Sealing and Coating Compound, Corrosion Inhibitive.

STANDARDS

MILITARY

MIL-STD-105	-	Sampling Procedures and Tables for Inspection by Attributes.
MIL-STD-129	-	Marking for Shipment and Storage.
MIL-STD-889	-	Dissimilar Metals.

(Unless otherwise indicated, copies of federal and military specifications, standards, and handbooks are available from the Standardization Document Order Desk, Building 4D, 700 Robbins Avenue, Philadelphia, PA 19111-5094.)

2.1.2 Other Government drawings. The following other Government drawings form a part of this specification to the extent specified herein. Unless otherwise specified, the issues are those in effect on the date of the solicitation.

DRAWINGS

ME

TA13207E9700	-	Trestle Assembly: Universal Transom, 60-Ton, for Floating and Fixed Bridges, General Assembly.
13216E9141	-	Loading Plan and Skid Detail Trestle Assembly, 2 Per Pack.

(Copies of drawings required by contractors in connection with specific acquisition functions should be obtained from the USA Belvoir Research, Development, and Engineering Center, ATTN: STRBE-JBS, Fort Belvoir, VA 22060-5606.)

2.2 Non-Government publications. The following document(s) form a part of this document to the extent specified herein. Unless otherwise specified, the issues of the documents which are DoD adopted are those listed in the issue of the DODISS cited in the solicitation. Unless otherwise specified, the issues

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T21:08Z
Check the source to verify that this is the current version before use.

of documents not listed in the DODISS are the issues of the documents cited in the solicitation (see 6.2).

NATIONAL MOTOR FREIGHT TRAFFIC ASSOCIATION, INC. (NMFTA)

National Motor Freight Classification Rules

(Application for copies should be addressed to the American Trucking Associations, Inc., ATTN: Traffic Department, 2200 Mill Road, Alexandria, VA 22314-4677.)

UNIFORM CLASSIFICATION COMMITTEE (UCC)

Uniform Freight Classification Rules

(Application for copies should be addressed to the Uniform Classification Committee, ATTN: Tariff Publishing Officer, Room 1106, 222 South Riverside Plaza, Chicago, Illinois 60606.)

(Non-Government standards and other publications are normally available from the organizations which prepare or which distribute the documents. These documents also may be available in or through libraries or other informational services.)

2.3 Order of precedence. In the event of a conflict between the text of this document and the references cited herein, the text of this document takes precedence. Nothing in this document, however, supersedes applicable laws and regulations unless a specific exemption has been obtained.

3. REQUIREMENTS

3.1 Description. The trestle assembly shall be in accordance with Top Assembly TA13207E9700 and as specified herein.

3.1.1 Drawings. The drawings forming a part of this specification are end product drawings. No deviation from the prescribed dimensions or tolerance is permissible without prior approval of the contracting officer. Where tolerances could cumulatively result in incorrect fits, the contractor shall provide tolerances within those prescribed on the drawings to insure correct fit, assembly, and operation of the trestle assembly. Any data (e.g. shop drawings, layouts, flow sheets, processing procedures, etc.) prepared by the contractor or obtained from a vendor to support fabrication and manufacture of the production item shall be made available, upon request, for inspection by the contracting officer or his designated representative.

3.2 First article. When specified (see 6.2), a sample shall be subjected to first article inspection (see 6.3) in accordance with 4.3.

3.3 Materials. Materials shall be as specified herein and on the drawings. Materials not specified shall be selected by the contractor and shall be subject to all provisions of this specification.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T21:08Z
Check the source to verify that this is the current version before use.

3.3.1 Material deterioration prevention and control. The trestle assembly shall be fabricated from compatible materials, inherently corrosion resistant or treated to provide protection against the various forms of corrosion and deterioration that may be encountered in any of the applicable operating and storage environment to which the item may be exposed.

3.3.1.1 Dissimilar metals. Dissimilar metals shall not be used in intimate contact with each other unless protected against galvanic corrosion. Dissimilar metals and methods of protection are defined and detailed in MIL-STD-889. Insulation shall be provided by an insulating barrier such as a coat of epoxy primer conforming to MIL-P-23377, or corrosion inhibiting sealant conforming to MIL-S-81733 or chromate tape conforming to MIL-I-24391. Protection against any galvanic corrosion could also be obtained by exclusion of the electrolyte if feasible.

3.3.1.2 Identification of materials and finishes. The contractor shall identify the specific material, material finish or treatment for use with component and subcomponent, and shall make information available upon request to the contracting officer or designated representative.

3.4 Recovered materials. For the purpose of this requirement, recovered materials are those materials which have been collected from solid waste and reprocessed to become a source of raw materials, as distinguished from virgin raw materials. The components, pieces and parts incorporated in the trestle assembly may be newly fabricated from recovered materials to the maximum extent practicable, provided the item produced meets all other requirements of this specification. Used, rebuilt or remanufactured components, pieces and parts shall not be incorporated in the item.

3.5 Treatment and painting. Unless otherwise specified (see 6.2), the portions of the trestle assembly normally painted shall be cleaned, treated, primed and painted in accordance with MIL-T-704, type F or G, as applicable, with the exterior topcoat color Camouflage Green 383. If required, the trestle assembly shall then be overcoated in accordance with the Government-furnished camouflage patterns with the colors specified therein. Surfaces to be painted shall be cleaned and dried to insure that they are free from contaminants such as oil, grease, welding slag and spatter, loose mill scale, water, dirt, corrosion product, or any other contaminating substances. As soon as practicable after cleaning, and before any corrosion product or other contamination can result, the surfaces shall be prepared or treated to insure the adhesion of the coating system. The painting shall consist of at least one coat of primer and one finish coat. The primer shall be applied to a clean, dry surface as soon as practicable after cleaning and treating. Painting shall be with manufacturer's current materials according to manufacturer's current process and the total dry film thickness shall be not less than 2.8 mils over the entire surface. The paint shall be free from runs, sags, orange peel, or other finishing defects.

3.6 Workmanship. When the trestle is assembled, the transom shall be capable of being moved up and down along the columns and there shall be no

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T21:08Z
Check the source to verify that this is the current version before use.

misfits or interference of mating parts. It shall be free of defects that could impair its operation or serviceability.

4. QUALITY ASSURANCE PROVISIONS

4.1 Responsibility for inspection. Unless otherwise specified in the contract or purchase order, the contractor is responsible for the performance of all inspection requirements as specified herein. Except as otherwise specified in the contract or purchase order, the contractor may use his own or any other facilities suitable for the performance of the inspection requirements specified herein, unless disapproved by the Government. The Government reserves the right to perform any of the inspections set forth in the specification where such inspections are deemed necessary to assure supplies and services conform to prescribed requirements.

4.1.1 Responsibility for compliance. All items must meet all requirements of sections 3 and 5. The inspection set forth in this specification shall become a part of the contractor's overall inspection system or quality program. The absence of any inspection requirements in the specification shall not relieve the contractor of the responsibility of assuring that all products or supplies submitted to the Government for acceptance comply with all requirements of the contract. Sampling in quality conformance does not authorize submission of known defective material, either indicated or actual, nor does it commit the Government to acceptance of defective material.

4.1.2 Parts and components. Parts and components detailed on the drawings shall be inspected in accordance with the quality assurance provisions (QAP) shown on the drawings. The drawings specify the characteristics requiring inspection, the sampling plan, and the basis for acceptance and rejection (see 6.5 and 6.6).

4.2 Classification of inspection. The inspection requirements specified herein are classified as follows:

a. First article inspection (see 4.3).
b. Quality conformance inspection (see 4.4).
c. Inspection of packaging (see 4.6).

4.3 First article inspection.

4.3.1 Examination. The first article trestle assembly shall be examined for the defects specified in 4.5.1. One or more defects shall be cause for rejection.

4.3.2 Test. The first article trestle assembly shall be tested as specified in 4.5.2. Failure of this test shall be cause for rejection.

4.4 Quality conformance inspection.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T21:08Z
Check the source to verify that this is the current version before use.

4.4.1 Sampling. Sampling for examination shall be in accordance with MIL-STD-105, table I and table IIa. A lot shall be accepted when zero defects are found and rejected when one or more defects are found.

4.4.2 Examination.

4.4.2.1 Individual. Each trestle assembly shall be examined for conformance to the individual examination shown on the component specification, as applicable. Presence of one or more defects shall be cause for rejection.

4.4.2.2 Samples. Samples selected in accordance with 4.4.1 shall be examined as specified in 4.5.1. Presence of one or more defects shall be cause for rejection.

4.5 Inspection procedure.

4.5.1 Examination. The trestle assembly shall be examined as specified herein for the following defects:

101. Materials not as specified (see 3.3)
102. Material not resistant to corrosion and deterioration, or treated to be resistant to corrosion and deterioration for the applicable storage and operating environments (see 3.3.1).
103. Dissimilar metals as defined in MIL-STD-889 are not effectively insulated from each other (see 3.3.1.1).
104. Contractor does not have documentation available for identification of material, material finishes or treatment (see 3.3.1.2).
105. Used, rebuilt or remanufactured components, pieces, or parts incorporated in the trestle assembly (see 3.4).
106. Treatment and painting not as specified (see 3.5).
107. Color not as specified (see 3.5).
108. Workmanship not as specified (see 3.6).

4.5.2 Assembly test. Assemble the trestle and brace it using the applicable trestle components. After assembly, move and pin the transom in three positions along the columns at the quarter points. Move the transom by using chain hoists or by any other lifting means. Any misfits, interference of mating parts, or inability to move the transom shall constitute failure of this test.

4.6 Inspection of packaging.

4.6.1 First article.

4.6.1.1 Examination. The first article shall be examined to determine compliance with section 5 of this specification. Any packing for level A that is not in accordance with the drawing or any marking for level A or C that is missing, illegible, incorrect, or incomplete shall constitute failure and shall be cause for rejection.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T21:08Z
Check the source to verify that this is the current version before use.

5. PACKAGING

5.1 First article. The contractor shall furnish a first article for examination within the time frame specified (see 6.2), to prove prior to starting production packaging that the applied packing and marking comply with the packaging requirements of this specification. Examination shall be as specified in section 4 and shall be subject to surveillance and approval by the Government (see 6.4). The first article examination may be accomplished utilizing either the first article trestle assembly or a production trestle assembly. If the first article trestle assembly is utilized, and packing shall be removed by the contractor at no expense to the Government, when requested by the Government to facilitate comparison between the first article trestle assembly and production trestle assembly.

5.2 Packing. Packing shall be level A or C as specified (see 6.2).

5.2.1 Level A. The components comprising two complete trestle assemblies shall be packed in accordance with drawing 13216E9141.

5.2.2 Level C. The trestle assembly components shall be packed to assure carrier acceptance and safe delivery to destination at lowest ratings in wood crates, boxes, loose components, or secured lifts as applicable, in compliance with Uniform Freight Classification rules or National Motor Freight Classification rules.

5.3 Marking. Loose components, secured lifts and shipping containers shall be marked in accordance with MIL-STD-129 (see 6.7).

6. NOTES

(This section contains information of a general or explanatory nature that may be helpful, but is not mandatory.)

6.1 Intended use. The trestle assembly is intended for use as an intermediate support in fixed spans and as a means for providing water level accommodation at the end of floating bridges. This item is a component of the following Supply Catalogs (SC); SC 5420-97-CL-E03, E35 and E36.

6.2 Acquisition requirements. Acquisition documents should specify the following:

a. Title, number, and date of this specification.
b. Issue of DODISS to be cited in the solicitation, and if required, the specific issue of individual documents referenced (see 2.1.1 and 2.2).
c. When a first article is required for inspection and approval and number of units required (see 3.2, 4.3, 4.6.1 and 6.3).
d. Time frame required for submission of the first article (see 5.1).
e. Level of packing required (see 5.2).
f. Color if not as specified (see 3.5).

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T21:08Z
Check the source to verify that this is the current version before use.

6.3 First article. When a first article inspection is required, the item(s) should be a preproduction model. The first article should consist of one or more units. The contracting officer should include specific instructions in acquisition documents regarding arrangements for examinations, approval of the first article test results and disposition of the first articles. Invitation for bids should provide that the Government reserves the right to waive the requirement for samples for first article inspection to those bidders offering a product which has been previously acquired or tested by the Government, and that bidders offering such products, who wish to rely on such production or test, must furnish evidence with the bid that prior Government approval is presently appropriate for the pending contract. Bidders should not submit alternate bids unless specifically requested to do so in the solicitation.

6.4 First article pack. Any changes or deviations of production packs from the approved first article will be subject to the approval of the contracting officer. Approval of the first article will not relieve the contractor of this obligation to pack and mark the trestle assemblies in accordance with this specification.

6.5 Quality assurance provisions (QAP). The contracting officer should require the contractor to maintain records of all QAP inspections. A suggested paragraph is as follows:

> "The contractor shall maintain complete records of all examinations and tests performed to verify the requirements of classified QAP characteristics. The records shall include as a minimum, lot size, sample size, drawing requirement, actual measurement, number and type of deficiencies found, quantity approved, quantity rejected, corrected action taken when applicable".

6.6 Definitions.

6.6.1 Quality assurance provisions (QAP). A QAP is a contractual requirement that supplements section 4 of this specification. QAP indicates the minimum requirements which must be inspected on the product drawings to verify the design objectives of the product and assure interchangeability of repair parts.

6.7 Levels of preservation. Levels of preservation have not been included as the components do not require preservation. For purposes of preservation/packing level marking the preservation should be considered level A.

6.8 Changes from previous issue. Marginal notations are not used in this revision to identify changes which respect to the previous issue due to the extensiveness of the changes.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T21:08Z
Check the source to verify that this is the current version before use.

6.9 Subject term (key word) listings.

Bridge
Transom
Trestle

Custodian:
Army - ME

Review activity:
Navy - MC
DLA - CS

Preparing activity:
Army - ME

Project 5420-0175

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T21:08Z
Check the source to verify that this is the current version before use.

STANDARDIZATION DOCUMENT IMPROVEMENT PROPOSAL

INSTRUCTIONS

1. The preparing activity must complete blocks 1, 2, 3, and 8. In block 1, both the document number and revision letter should be given.
2. The submitter of this form must complete blocks 4, 5, 6, and 7.
3. The preparing activity must provide a reply within 30 days from receipt of the form.

NOTE: This form may not be used to request copies of documents, nor to request waivers, or clarification of requirements on current contracts. Comments submitted on this form do not constitute or imply authorization to waive any portion of the referenced document(s) or to amend contractual requirements.

I RECOMMEND A CHANGE:	1. DOCUMENT NUMBER	2. DOCUMENT DATE (YYMMDD)
	MIL-T-52 50E	910726

3. DOCUMENT TITLE
Trestle Assembly: Universal Transom, 60-Ton, for Floating and Fixed Bridges

4. NATURE OF CHANGE (Identify paragraph number and include proposed rewrite, if possible. Attach extra sheets as needed.)

5. REASON FOR RECOMMENDATION

6. SUBMITTER

a. NAME (Last, First, Middle Initial)	b. ORGANIZATION
c. ADDRESS (Include Zip Code)	d. TELEPHONE (Include Area Code) (1) Commercial (2) AUTOVON (If applicable)
	7. DATE SUBMITTED (YYMMDD)

8. PREPARING ACTIVITY

a. NAME	b. TELEPHONE (Include Area Code) (1) Commercial (703) 664-5717	(2) AUTOVON 354-5717
c. ADDRESS (Include Zip Code) US Army Belvoir RDE Center ATTN: STRBE-TSE Ft. Belvoir, VA 22060-5606	IF YOU DO NOT RECEIVE A REPLY WITHIN 45 DAYS, CONTACT: Defense Quality and Standardization Office 5203 Leesburg Pike, Suite 1403, Falls Church, VA 22041-3466 Telephone (703) 756-2340	AUTOVON 289-2340

Source: https://assist.dla.mil -- Downloaded: 2026-10-22121-08z
Check this source to verify that this is the current version before use.