MIL-C-55449 B(EL)
26 June 1969
SUPERSEDING
MIL-C-55449 A. (EL)
24 June 1967

MILITARY SPECIFICATION

CONNECTOR, PLUG, ELECTRICAL U-237( )/G
CONNECTOR, RECEPTACLE, ELECTRICAL U-238( )/G

1. SCOPE

1.1 Scope.- This document covers two types of electrical power connectors, designated as Connector, Plug, Electrical U-237( )/G and Connector, Receptacle, Electrical U-238( )/G. (See 6.3).

2. APPLICABLE DOCUMENTS

2.1 Documents.- The following documents, of the issue in effect on date of invitation for bids or request for proposal, form a part of this specification to the extent specified herein.

SPECIFICATIONS

FEDERAL

PPP-B-566	Boxes, Folding Paperboard.
PPP-B-636	Boxes, Fiberboard.
PPP-B-676	Boxes, Set-up.
PPP-P-291	Paperboard, Wrapping, Cushioning.
PPP-T-45	Tape, Gummed, Paper, Reinforced and Plain, for Sealing and Securing.
PPP-T-97	Tape, Pressure-Sensitive Adhesive, Filament Reinforced.

MILITARY

MIL-P-116	Preservation, Methods of.
MIL-M-13231	Marking of Electronic Items.
MIL-F-14072	Finishes for Ground Signal Equipment.

FSC 5935

Source: https://assist.dla.mil -- Downloaded: 202610-22T23:22Z
Check the source to verify that this is the current version before use.

STANDARDS

MILITARY

MIL-STD-105	Sampling Procedures and Tables for Inspection by Attributes.
MIL-STD-129	Marking for Shipment and Storage.
MIL-STD-169	Extreme-Temperature Cycle.
MIL-STD-170	Moisture Resistance Test Cycle.
MIL-STD-202	Test Methods for Electronic and Electric Component Parts.

DRAWINGS

ELECTRONICS COMMAND

SC-DL-162362	Connector, Plug, Electrical U-237( )/G.
SC-DL-162391	Connector, Receptacle, Electrical U-238( )/G.
SC-GL-323058	Connector, Plug, Electrical U-237( )/G.
SC-GL-323121	Connector, Receptacle, Electrical U-238( )/G.
SM-D-352157	Cable Assembly, Power, Electrical CX-7705( )/U.

(Copies of specifications, standards, and drawings, required by suppliers in connection with specific procurement functions, should be obtained from the procuring activity or as directed by the contracting officer. Both the title and number or symbol should be stipulated when requesting copies.)

3. REQUIREMENTS

3.1 Description.- The connectors, which this specification covers, are four (4) contact hermaphroditic, waterproof, power connectors U-237( )/G and U-238( )/G used to supply electrical power to area-type communication system.

3.2 Construction.- The connectors shall be constructed in accordance with the requirements of this specification and the following Drawing and Data Lists:

Connector, Plug, Electrical U-237( )/G, SC-DL-162362.
Connector, Receptacle, Electrical U-238( )/G, SC-DL-162391.

3.3 Cast and molded parts.-

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T23:22Z
Check the source to verify that this is the current version before use.

3.3.1 Casting.- Castings shall be of uniform quality and condition, and free from cracks, harmful shrinkage, porosity, gas holes, foreign matter, and other injurious defects. The surface of the castings shall be free from pits, parting lines, porous areas, fins, ridges, modules, raised metal, and scale. All castings shall be completely cleaned prior to presentation for inspection. Castings shall not be plugged or welded, nor shall imperfections be filled in.

3.3.2 Molded parts.- Molded parts shall be uniform in quality, condition, and color. The molded parts shall be clean, smooth, free from porous areas, foreign materials, weak sections, bubbles, flash and any other injurious defects.

3.4 Cleaning.- After assembly, the equipment shall be cleaned thoroughly and shall be free from foreign material.

3.5 Finish, protective.- Equipment shall be given protective finish in accordance with MIL-F-14072 and the equipment drawings. (See 4.3).

3.6 Marking.- Marking shall conform to MIL-M-13231. (See 4.3).

3.7 Electrical requirements.-

3.7.1 Continuity.- The path between each male contact and its corresponding female contact in the connector shall be continuous electrically. In addition, the resistance between each male contact and the corresponding female contact of mated connectors shall not exceed 0.01 ohm. (See 4.7.1).

3.7.2 Dielectric strength.- There shall be no evidence of a voltage drop when tested in accordance with 4.7.2.

3.7.3 Insulation resistance.- When tested in accordance with 4.7.3, the insulation resistance shall be not less than 5,000 megohms except that it shall be not less than 1,000 megohms during the Moisture resistance test 4.9.4 and the High humidity and high temperature test 4.9.5.

3.7.4 Contact resistance.- When tested in accordance with 4.7.4, the voltage drop across each mated pair of contacts shall not exceed 1.8 millivolts.

3.8 Mechanical requirements.-

3.8.1 Immersion.- After being subjected to the tests specified in 4.8.1, the connector shall meet the requirements of Dielectric strength 3.7.2 and Insulation resistance 3.7.3, and there shall be no evidence of water in the connector housings or test fixture.

Source: https://assist.dla.mil -- Downloaded: 202610-22T23:22Z
Check the source to verify that this is the current version before use.

3.8.2 Air leakage.- There shall be no evidence of air leakage when tested in accordance with 4.8.2.

3.8.3 Durability.- Following the durability test of 4.8.3, contact resistance measurements shall be within 10% of the measurements taken prior to durability. The connector shall meet the electrical requirements of 3.7 and Air leakage 3.8.2. There shall be no distorted or broken components or binding of the coupler on Connector U-237( )/G.

3.8.4 Pull.- While being subjected to the test specified in 4.8.4, the assemblies shall show no straining of individual conductors or penetration of the grip through the cable jacket and shall meet the requirements of Continuity 3.7.1, Dielectric strength 3.7.2 and Insulation resistance 3.7.3. Upon completion of the pull test, the equipment shall be subjected to the Immersion test specified in 4.8.1 and meet the requirements of 3.8.1.

3.8.5 Interchangeability.- Like units, assemblies and sub-assemblies shall be physically and functionally interchangeable, without modification of such items or of the connector. (See 4.8.5). Individual items shall not be hand-picked for fit. Reliance shall not be placed on any unspecified dimension, characteristic, etc.

3.9 Service conditions.-

3.9.1 Shock drop.- After being subjected to the test specified in 4.9.1, the connectors shall be mechanically operable and any physical damage shall be minor. The equipment shall meet the electrical requirements of 3.7 and Air leakage 3.8.2.

3.9.2 Temperature cycling.- During the test specified in 4.9.2, the connector shall meet the requirements of Continuity 3.7.1, Dielectric strength 3.7.2 and Insulation resistance 3.7.3 and shall show no evidence of deterioration.

3.9.3 Mating at high and low temperature extremes.- The connector shall be capable of being mated and unmated without difficulty when tested in accordance with 4.9.3.

3.9.4 Moisture resistance.- When subjected to the test specified in 4.9.4, the connector shall meet the requirements of Insulation resistance 3.7.3, and there shall be no evidence of deterioration.

Source: https://assist.dla.mil -- Downloaded: 202610-22T23:22Z
Check the source to verify that this is the currentversion before use.

3.9.5 *High humidity and high temperature*.- When subjected to the test specified in 4.9.5, the connector shall meet the requirements of Insulation resistance 3.7.3, and there shall be no evidence of deterioration.

3.10 Workmanship.- The connector shall be manufactured and assembled in accordance with the applicable portions of the following paragraphs herein: (See 4.10).

3.3 Cast and molded parts.
3.4 Cleaning.

4. QUALITY ASSURANCE PROVISIONS

4.1 *Responsibility for inspection*.- Unless otherwise specified in the contract or purchase order, the supplier is responsible for the performance of all inspection requirements as specified herein. Except as otherwise specified, the supplier may utilize his own facilities or any commercial laboratory acceptable to the Government. The Government reserves the right to perform any of the inspections set forth in the specification where such inspections are deemed necessary to assure that supplies and services conform to prescribed requirements.

4.2 Classification of inspection.- Inspection shall be classified as follows:

(a) Inspection covered by subsidiary documents. (See 4.3).

(b) Quality conformance inspection.

(1) Quality conformance inspection of equipment before preparation for delivery. (See 4.4).

(2) Quality conformance inspection of preparation for delivery. (See 4.11).

4.3 Inspection covered by subsidiary documents.- The following shall be inspected under the applicable subsidiary documents as part of the inspection before preparation for delivery:

Item	Where required
Finish	3.5
Marking	3.6

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T23:22Z
Check the source to verify that this is the current version before use.

4.4 Quality conformance inspection of equipment before preparation for delivery.- The contractor, to demonstrate compliance with specified requirements, shall perform the inspection specified in 4.3 and 4.4.1 through 4.4.4. This does not relieve the contractor of his responsibility for performing any additional inspection which is necessary to control the quality of the product and to assure compliance with all specification requirements. The Government will review and evaluate the contractor's inspection procedures and examine the contractor's inspection records. In addition, the Government--at its discretion--may perform all or any part of the specified inspection to verify the contractor's compliance with specified requirements. Test equipment for Government verification inspection shall be made available by the contractor.

4.4.1 Group A inspection.- Each unit (100%) of each lot of equipment shall be inspected for conformance to all the inspection and test requirements of table I. Each lot will be subject to verification, utilizing the procedures of MIL-STD-105 using the general inspection levels and the AQLs indicated in table I. Group A inspection shall be performed in any order which is satisfactory to the Government.

Table I - Group A inspection

Inspection	Req. Para.	Insp. Para.	AQL Major	AQL Minor
Visual and mechanical	3.10	4.10	1.0%	4.0%
Electrical				
Continuity	3.7.1	4.7.1	1.0% for the group	
Dielectric strength	3.7.2	4.7.2		
Insulation resistance	3.7.3	4.7.3		
Air leakage	3.8.2	4.8.2	1.0%	

4.4.2 Group B inspection.- This inspection, including sampling, shall conform to table II and to the special procedures for small-sample inspection of MIL-STD-105. The inspection level shall be S-3 for normal, tightened and reduced inspection. Group B inspection shall normally be performed on inspection lots that have passed group A inspection and on samples selected from units that have been subjected to and met the group A inspection. The AQL shall be as shown below.

Source: https://assist.dla.mil -- Downloaded: 202610-22T23:22Z
Check the source to verify that this is the current version before use.

Table II - Group B inspection

Inspection	Req. Para.	Insp. Para.	AQL
Immersion	3.8.1	4.8.1	1.5 percent defective
Interchangeability	3.8.5	4.8.5	4.0 percent defective

4.4.3 Group C inspection.- This inspection shall consist of the tests specified in tables III, IV and V and shall be performed on samples that have been subjected to and met group A and group B inspection. Sample units shall be selected at random without regard to their quality except that the samples selected at the start of production shall be selected from the first units produced.

4.4.3.1 Group C-1 inspection.- This inspection shall consist of the tests specified in table III and shall be performed every month or every 1,000 units, whichever comes first.

Table III - Group C-1 inspection

Inspection	Req. Para.	Insp. Para.	Sampling
Contact resistance	3.7.4	4.7.4	2 units
Durability *	3.8.3	4.8.3	2 units
Pull	3.8.4	4.8.4	2 units

* Sample units subjected to this inspection shall not be furnished on contract.

4.4.3.2 Group C-2 inspection.- This inspection shall consist of the tests specified in table IV and shall be performed every 3 months or every 3,000 units, whichever comes first.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T23:22Z
Check the source to verify that this is the current version before use.

Table IV - Group C-2 inspection

Inspection	Req. Para.	Insp. Para.	Sampling
Shock drop	3.9.1	4.9.1	3 units
High humidity and high temperature	3.9.5	4.9.5	4 units

4.4.3.3 Group C-3 inspection.- This inspection shall consist of the tests specified in table V and shall be performed once each year or every 12,000 units, whichever comes first. The 4 units shall be subjected to all of the tests listed and in the order stated below.

Table V - Group C-3 inspection

Inspection	Req. Para.	Insp. Para.	Sample
Temperature cycling	3.9.2	4.9.2	4 units
Mating at high and low temperature extremes	3.9.3	4.9.3	4 units
Moisture resistance	3.9.4	4.9.4	4 units

4.4.3.4 Noncompliance.- The contractor shall immediately report, in writing, each group C failure occurrence, including details of the failure and characteristics affected. The contractor shall immediately investigate the cause of failure and further report the results of investigation and details of the proposed corrective action on (i) the process and materials, as applicable, and (ii) all units of product which were manufactured under the same conditions and which the Government considers subject to the same failure. Reports shall be forwarded to the responsible technical activity designated in the contract through the Quality Assurance Representative. After corrective action has been taken, additional sample units shall be subjected to group C inspection (all inspections, or the inspections which the sample failed, at the option of the Government) and groups A and B inspection may be reinstituted; however, final acceptance and shipment will be withheld until the group C reinspection results have shown that the corrective action was effective.

Source: https://assist.dla.mil -- Downloaded: 202610-22T23:22Z
Check the source to verify that this is the current version before use.

4.4.4 Reinspection of conforming group B and group C sample units.- Unless otherwise specified, sample units which have been subjected to and passed group B or group C inspection, or both, may be accepted on contract, provided that they are resubjected to and pass group A inspection after repair of all visible damage.

4.5 Test conditions.-

4.5.1 Procurement of Connector U-238( )/G.- When Connector, Receptacle U-238( )/G is being procured separately, the contractor will furnish sufficient Connector, Plug U-237( )/G housings to accomplish the tests where mating of connectors is required. (See 4.7.1, 4.7.4, 4.8.1, 4.8.3, 4.9.2, 4.9.3, 4.9.4 and 4.9.5). The contact assembly, including contacts (male and female), spacers, O-rings, insert, back plate and gasket assembled within the contractor-furnished U-237( )/G housing(s) shall be from the production of U-238( )/G being tested. The connector(s) shall be wired as indicated in 4.5.2(a).

4.5.2 Preparation of samples.- The contractor shall prepare samples of each connector on contract for quality conformance inspection in the following manner:

(a) Connector U-237( )/G.

(1) Samples selected for Immersion 4.8.1 and Pull 4.8.4 shall be wired to Cable WT-26( )/U in accordance with SM-D-352157.

(2) Samples selected for Temperature cycling 4.9.2, Moisture resistance 4.9.4 and High humidity and high temperature 4.9.5 shall be wired to a four conductor cable which is capable of withstanding the conditions of the required tests.

(3) Samples selected for Air leakage 4.8.2 shall have air injected through a plug which is inserted into the cable entrance of the connector. The plug shall have a major maximum diameter of 0.980 and a minor maximum diameter of 0.530.

(b) Connector U-238( )/G.

(1) Samples selected for Immersion 4.8.1, Air leakage 4.8.2, Temperature cycling 4.9.2, Moisture resistance 4.9.4 and High humidity and high temperature 4.9.5 shall be mounted on a sealed metal box(s). The metal box(s) shall have a valve through which air is injected and in addition provisions for a four conductor cable to be wired to the terminals of the connectors under test. The cable shall be capable of withstanding the conditions of the required tests.

(2) Samples selected for Durability 4.8.3 shall be mated with Connector U-237( )/G.

Source: https://assist.dla.mil -- Downloaded: 202640-22T23:22Z
Check the source to verify that this is the currentversion before use.

4.5.3 Contractor-furnished supplies.- Contractor shall furnish supplies as required in paragraphs 4.5.1 and 4.5.2 and in sufficient quantity to accomplish the tests required.

4.6 Preconditioning.- The contractor shall be permitted to precondition the equipments prior to performing any electrical tests. The preconditioning shall consist of removing surface moisture from the equipment by wiping, drying, or blowing. The application heat shall be limited to 3 minutes or less. For those equipments subjected to tests specified in Immersion 4.8.1, Moisture resistance 4.9.4 and High humidity and high temperature 4.9.5, unmated and without protective covers, a 24 hour waiting period in an ambient room temperature is permitted. However, if the contractor exercises this option of preconditioning, the contractor shall precondition all samples selected by Quality Assurance Representatives immediately prior to testing.

4.7 Electrical tests.-

4.7.1 Continuity.- The connector shall be tested to determine compliance with the requirements specified in 3.7.1. (See 4.5).

4.7.2 Dielectric strength.- The connector shall be tested in accordance with Method 301 of MIL-STD-202 to determine compliance with the requirements of 3.7.2. The potential, 3,500 volts rms (4,950 volts dc) shall be applied between each terminal in turn and the remaining terminals connected together to the housing ground.

4.7.3 Insulation resistance.- The connector shall be tested in accordance with Method 302, Condition B of MIL-STD-202 to determine compliance with the requirements of 3.7.3. The insulation resistance shall be measured between each terminal in turn and the remaining terminals connected together to the housing ground. The measurement shall be made after 1 minute electrification.

4.7.4 Contact resistance.- Connectors shall be mated and the voltage drop between each terminal and its corresponding terminal shall be measured to determine compliance with the requirements of 3.7.4. The test current shall be 3 ampere dc. (See 4.5).

4.8 Mechanical tests.-

4.8.1 Immersion.- The connector prepared in accordance with 4.5 shall be immersed to a depth of 3 feet of water for 16 hours to determine compliance with 3.8.1. Fifty percent shall be mated, twenty-five percent shall be with protective cover in place and the remainder shall be without protective covers. (Minimum 4 connectors).

Source: https://assist.dla.mil -- Downloaded: 202640-22T23:22Z
Check the source to verify that this is the current version before use.

4.8.2 Air leakage.- The connector prepared in accordance with 4.5 shall be submerged in water not deeper than 6 inches. Air at 2.5 psi shall then be applied internally to the equipment. After stabilization, the equipment shall be observed for a minimum of 30 seconds and meet the requirements of 3.8.2. This test shall then be repeated using air at 15 psi.

NOTE: Air leakage performed in any other manner must have Government approval.

4.8.3 Durability.- Two connectors shall be tested for compliance with 4.7.4. Contact resistance measurements shall be recorded. The connectors shall then be subjected to 200 cycles of mating and unmating. A cycle shall consist of mating, locking and unlcoking of the couplers and a complete separation of the connectors. The equipment shall meet the requirements of 3.8.3. (See 4.5).

4.9.4 Pull.- Two mated Connectors, Plug, Electrical U-237( )/G assembled as specified in 4.5 shall be subjected to a static load of 425 pounds for a sufficient duration to permit electrical measurements specified in 3.8.4. A minimum of 2-1/2 feet of Cable WT-26( )/U connected to each connector shall be subjected to the load.

4.8.5 Inspection for interchangeability.- The connector shall be gaged, using the appropriate gages listed below, to determine conformance to the physical and functional interchangeability requirement of 3.8.5. When a mechanical value is not within specified or design limits, it shall be considered a major defect.

Gage List	Connector
SC-GL-323058	Connector, Plug, Electrical U-237( )/G.
SC-GL-323121	Connector, Receptacle, Electrical U-238( )/G.

4.9 Service tests.-

4.9.1 Shock drop.- One connector shall be dropped a distance of 36 inches at random for a total of 12 drops. Six drops shall be made with the protective cover on, the remaining 6 drops shall be made with the protective cover off. In addition, when Connectors U-237( )/G are being procured, a pair of mated connectors shall be dropped at random 12 times from a distance of 36 inches. The floor or barrier receiving the impact shall be 2 inch fir backed by concrete or a rigid steel frame. Connectors shall meet the requirements of 3.9.1.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T23:22Z
Check the source to verify that this is the current version before use.

4.9.2 Temperature cycling.- Four connectors, mated, unmated with protective cover in place and unmated without protective cover assembled as specified in 4.5 shall be subjected to the temperature cycle shown on MIL-STD-169. Measurements shall be taken on the steps 1, 5 and 10, and shall meet the requirements of 3.9.2.

4.9.3 Mating at high and low temperatures extremes.- Four connectors, 2 mated and 2 unmated, shall be placed in a temperature chamber and conditioned at -65°F ± 2° for 24 hours. While still at -65°F ± 2°, the connectors shall be tested to determine compliance with the requirements of 3.9.3. The above shall be repeated at +150°F ± 2°.

4.9.4 Moisture resistance.- Four connectors assembled as specified in 4.5, mated, unmated with protective cover in place and unmated without protective cover shall be subjected to 15 continuous 48-hour cycles. Temperature, relative humidity, and period of time for each portion of the cycle shall conform to MIL-STD-170. Insulation resistance measurements shall be made during the periods shown on the Standard, using Method 302, Condition A, of MIL-STD-202. The connectors shall meet the requirements of 3.9.4.

4.9.5 High humidity and high temperature.- Four connectors assembled as specified in 4.5, mated, unmated with protective cover in place and unmated without protective cover shall be placed in a chamber at 86°F ± 5° and a relative humidity of 92 to 98 percent. The temperature and humidity shall be maintained continuously for 5 days. While still at these conditions, the insulation resistance shall be measured using Method 302, Condition A, of MIL-STD-202. The connectors shall meet the requirements of 3.9.5.

4.10 Visual and mechanical inspection.- The connectors shall be examined for the defects listed in table VI. (See 3.10).

4.11 Quality conformance inspection of preparation for delivery.- Preparation for delivery shall be inspected in accordance with MIL-P-116 to determine conformance to the requirements of section 5.

Source: https://assist.dla.mil -- Downloaded: 202640-22T23:22Z
Check the source to verify that this is the currentversion before use.

Table VI - Classification of visual and mechanical defects

Classification	Defect
Major	Locking threads chipped or broken.
	Threads stripped.
	Sharp edges on metal parts.
	Coupler not operating freely.
	Metal parts chipped or broken.
	Contacts missing, broken or bent.
	Contact assembly parts chipped or broken.
	Any foreign objects or material preventing the mating of connectors.
	Cuts or abrasions or rubber parts.
	Scratches, cuts, abrasions, etc., with exposure of bare metal.
Minor	Screws missing.
	Finish not as specified.
	Marking incorrect.
	Scratches, cuts, abrasions, etc., without exposure of bare metal.
	Finish adhesion-flaking, peeling or chipping.
	Wire grip missing.
	Scratches, cuts, abrasions, etc., of contact assembly.
	Gasket not properly bonded to contact assembly.

5. PREPARATION FOR DELIVERY

5.1 Preservation and packaging.- Preservation and packaging shall be Level A or C, as specified. (See 6.2).

5.1.1 Level A.-

5.1.1.1 Cleaning.- Connector, Plug, Electrical U-237( )/G and Connector, Receptacle, Electrical U-238( )/G shall be cleaned in accordance with process C-1 of MIL-P-116.

5.1.1.2 Drying.- Connector, Plug, Electrical U-237( )/G and Connector, Receptacle, Electrical U-238( )/G shall be dried in accordance with MIL-P-116.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T23:22Z
Check the source to verify that this is the current version before use.

5.1.1.3 Unit packaging.- Connector, Plug, Electrical U-237( )/G and Connector, Receptacle, Electrical U-238( )/G shall be packaged Method III in accordance with MIL-P-116. Cushion each connector by wrapping in paperboard cushioning conforming to PPP-P-291. Secure cushioning with tape conforming to PPP-T-45. Place each cushioned connector within a close-fitting paperboard box, variety 1, style II, type A, class a, conforming to PPP-B-566. Closure shall be made in accordance with the appendix to the box specification.

5.1.1.3.1 Intermediate packaging.- Connectors, packaged as specified in 5.1.1.3 bearing like stock numbers shall be placed in intermediate containers conforming to PPP-B-566, variety 1 or PPP-B-676. Intermediate containers shall be uniform in size and shape, shall be minimum cube and tare, and shall contain multiples of 5 unit packages not to exceed 10 pounds.

5.1.2 Level C.- Connector, Plug, Electrical U-237( )/G and Connector, Receptacle, Electrical U-238( )/G shall be preserved and packaged in a manner that will afford adequate protection against corrosion, deterioration and damage during shipment from the supply source to the first receiving activity.

5.2 Packing.- Packing shall be Level A, B or C as specified. (See 6.2).

5.2.1 Level A.- A quantity of Connector, Plug, Electrical U-237( )/G, and Connector, Receptacle, Electrical U-238( )/G packaged as specified in 5.1, bearing like stock numbers shall be packed in a close-fitting fiberboard box conforming to PPP-B-636, W5c. Shipping containers shall not exceed the gross weight limitation of the box specification for special requirements use. Closure shall be in accordance with the appendix to the box specification.

5.2.1.1 Reinforcing.- Shipping containers shall be reinforced in accordance with the appendix to the box specification, using tape conforming to PPP-T-97.

5.2.2 Level B.- A quantity of connectors packaged as specified in 5.1 shall be packed in accordance with paragraph 5.2.1.

5.2.3 Level C.- Connector, Plug, Electrical U-237( )/G and Connector, Receptacle, Electrical U-238( )/G packaged as specified in 5.1, bearing like stock numbers, shall be packed in shipping containers in a manner that will afford adequate protection against damage to the package and its contents during shipment from the supply source to the first receiving activity. Shipping containers shall comply with the rules and regulations of the common carrier as applicable to the mode of transportation.

5.3 Marking.- In addition to any special marking required by the contract or order, interior packages and exterior shipping containers shall be marked in accordance with MIL-STD-129. (See 6.2).

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T23:22Z
Check the source to verify that this is the current version before use.

6. NOTES

6.1 Intended use.- The connectors covered by this specification are used to supply electrical power to communication systems. They are quick connect and disconnect hermaphrodite waterproof power connectors. (See 1.1).

6.2 Ordering data.- Procurement documents should specify the following:

(a) Title, number, and date of this specification and any amendment thereto.

(b) Type required.

(c) Level of packaging and level of packing required for shipment. (Level A, level B or level C).

(d) The specific paragraphs of section 5 which are applicable to the particular procurement.

(e) When rough handling and functional tests are required.

6.3 Nomenclature.- The parentheses in the nomenclature will be deleted or replaced by a letter identifying the particular design; for example, Connector, Plug, Electrical U-237E/G. As soon as possible after the award of the contract, the contractor should apply for nomenclature in accordance with the applicable clause in the contract. (See 1.1).

CUSTODIAN

ARMY-EL

Preparing Activity

ARMY -EL

Project No. 5935-A592

Source: https://assist.dla.mil -- Downloaded: 202640-22T23:22Z
Check the source to verify that this is the current version before use.

FOLD

Department of the Army
Headquarters
U.S.Army Electronics Command
Fort Monmouth, New Jersey 07703

POSTAGE AND FEES PAID

OFFICIAL BUSINESS

Commanding General
U.S.Army Electronics Command
ATTN: AMSEL-TD-SS
Fort Monmouth, New Jersey 07703

FOLD

To detach this form, cut along this line

Source: https://assist.dla.mil -- Downloaded: 202640-22T23:22Z
Check the source to verify that this is the current version before use.

SPECIFICATION ANALYSIS SHEET

Form Approved
Budget Bureau No. 22-R255

INSTRUCTIONS: This sheet is to be filled out by personnel, either Government or contractor, involved in the use of the specification in procurement of products for ultimate use by the Department of Defense. This sheet is provided for obtaining information on the use of this specification which will insure that suitable products can be procured with a minimum amount of delay and at the least cost. Comments and the return of this form will be appreciated. Fold on lines on reverse side, staple in corner, and send to preparing activity. Comments and suggestions submitted on this form do not constitute or imply authorization to waive any portion of the referenced document(s) or serve to amend contractual requirements.

SPECIFICATION

ORGANIZATION

CITY AND STATE

CONTRACT NUMBER

MATERIAL PROCURED UNDER A

☐ DIRECT GOVERNMENT CONTRACT ☐ SUBCONTRACT

1. HAS ANY PART OF THE SPECIFICATION CREATED PROBLEMS OR REQUIRED INTERPRETATION IN PROCUREMENT USE?

A. GIVE PARAGRAPH NUMBER AND WORDING.

B. RECOMMENDATIONS FOR CORRECTING THE DEFICIENCIES

2. COMMENTS ON ANY SPECIFICATION REQUIREMENT CONSIDERED TOO RIGID

3. IS THE SPECIFICATION RESTRICTIVE?

☐ YES ☐ NO *(If "yes", in what way?)*

4. REMARKS *(Attach any pertinent data which may be of use in improving this specification. If there are additional papers, attach to form and place both in an envelope addressed to preparing activity)*

SUBMITTED BY *(Printed or typed name and activity - Optional)*

DATE

DD FORM 1 JAN 68 1426

REPLACES EDITION OF 1 OCT 64 WHICH MAY BE USED.

ESC-FM 1068-68

To detach this fo , cut along this line

Source: https://assist.dla.mil -- Downloaded: 202640-22T23:22Z
Check the source to verify that this is the current version before use.