MILITARY SPECIFICATION

CONTAINER, SHIPPING AND STORAGE BOMB DISPENSER: CNU-79/E

This specification is approved for use by Picatinny Arsenal, Department of the Army and is available for use by all Departments and Agencies of the Department of Defense.

1. SCOPE

1.1 This Specification covers one type of container designated as Container, Shipping and Storage, Dispenser, Bomb CNU-79/E.

2. APPLICABLE DOCUMENTS

2.1 The following documents of the issue in effect on date of invitation for bids or requests for proposals, form a part of this specification to the extent specified herein.

SPECIFICATIONS

MILITARY

MIL-T-5021 - Tests; Aircraft Welding Operator's Certification
MIL-A-48078 - Ammunition, Standard Quality Assurance Provisions, General Specification for

STANDARDS

FEDERAL

FED-STD-151 - Metals, Test Methods

MILITARY

MIL-STD-105 - Sampling Procedures and Tables for Inspection by Attributes (ABC-STD-105)

FSC: 8140

Beneficial comments (recommendations, additions, deletions) and any pertinent data which may be of use in improving this document should be addressed to: Commander, Picatinny Arsenal, Dover, New Jersey 07801 by using the self-addressed Standardization Document Improvement Proposal (DD Form 1426) appearing at the end of this document or by letter.

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T02:08Z
Check the source to verify that this is the current version before use.

MIL-STD-129 - Marking for Shipment and Storage

DRAWINGS

U.S. ARMY PICATINNY ARSENAL

8887105	- Container, Shipping and Storage, Bomb Dispenser: CNU-79/E
9298881	- Container, Shipping and Storage, Bomb Dispenser: CNU-79/E.

(Copies of specifications, standards, drawings, required by suppliers in connection with specific procurement functions should be obtained from the procuring activity or as directed by the Contracting Officer.)

3. REQUIREMENTS

3.1 Material. - Materials shall be in accordance with the applicable drawings and specifications.

3.2 Parts. - The container parts shall comply with all requirements specified on Drawing (Dwg) 8887105 or 9298881, as applicable, all associated drawings and with all requirements specified in applicable specification.

3.3 Welding. - All welding shall be in accordance with applicable specifications. All welding shall be performed by operators who are currently certified as Class B Operators in accordance with MIL-T-5021.

3.4 Assembly and disassembly. - The container shall accept the dispenser or fixture without evidence of excessive effort, in assembly or disassembly, or closing and securing the cover (see 4.5.1).

3.5 Performance characteristics. - The container shall comply with all the requirements specified on drawing 8887105 or 9298881, as applicable, and with all requirements specified in this specification, when loaded with a dispenser, without evidence of loose parts, or broken or permanently set structural members which render the container unusable. Minor dents or creases in nonstructural members, bent rings or eyes, and cracking of the wooden skids shall not be considered objectionable. The dispenser shall be operable after completion of the below listed tests. All tests shall be conducted at a temperature of plus (+) 80 degrees Fahrenheit (F°) plus or minus (±) 20°F.

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T02:08Z
Check the source to verify that this is the current version before use.

3.5.1 Fork lifting. - The loaded container shall be capable of being lifted by a suitable fork lift truck without evidence of puncture, and broken or bent frame structure (see 4.5.3.6).

3.5.2 Stacking. - The loaded container shall be capable of supporting a simulated stacking load equal to five (5) times the weight of a loaded container without evidence of permanent set or breakage of structural members (see 4.5.3.7).

3.5.3 Hoisting. - The loaded container shall be capable of carrying an additional load equal to two (2) times the weight of another loaded container without evidence of permanent set or breakage when suspended by the lift rings provided (see 4.5.3.8).

3.5.4 Pushing. - The loaded container shall withstand pushing without damage to skids or structure that would render the container unserviceable (see 4.5.3.9).

3.5.5 Edgewise drop. - The loaded container shall withstand dropping and meet the requirements of 3.5 (see 4.5.3.2).

3.5.6 Cornerwise drop. - The loaded container shall withstand cornerwise dropping and meet the requirements of 3.5 (see 4.5.3.3).

3.5.7 End impact. - The loaded container shall withstand end impacts and meet the requirements of 3.5 (see 4.5.3.4).

3.5.8 Roll-over. - The loaded container shall withstand roll-over and meet the requirements of 3.5 (see 4.5.3.5).

3.5.9 Vibration. - The loaded container, shall withstand vibrations as specified in Table I without evidence of loose parts or fasteners and breakage or cracks in the container structure, and resilient mounts. The vibration shall be applied in the vertical axis and, as specified (see 4.5.3.1).

TABLE I

Test	Freq of Forcing Function - Hz	Double Amplitude Inches	Test Duration Minutes Ambient
Transmissibility	2 — 10	.13	SUFFICIENT

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T02:08Z
Check the source to verify that this is the current version before use.

Test	10 — 20 20 — 60	.09 .06	TO DETERMINE RESONANT POINT
Fatigue Test	Natural Frequency Determine by Transmissibility	Same as above	30

3.5.10 Pressure retention. - The container shall withstand pressure retention tests when tested as specified, except that a pressure loss of 0.1 psig or less over a 30 minute period shall not be cause for rejection. (See 4.5.2).

3.6 Workmanship. - All parts and assemblies shall be fabricated and finished in a thorough workmanlike manner. They shall be free of burrs, chips, sharp edges, cracks, unblended radii, surface defects, dirt, grease, rust, corrosion products and other foreign matter. The cleaning method used shall not be injurious to any of the parts nor shall the parts be contaminated by the cleaning agent.

3.7 First article testing. - This specification contains technical provisions for first article inspection. Requirements for the submission of first article samples by the contractor shall be as specified in the contract.

4. QUALITY ASSURANCE PROVISIONS

4.1 Responsibility for inspection and standard quality assurance provisions. - Unless otherwise specified herein or in the contract, the provisions of MIL-A-48078 shall apply and are hereby made a part of this detail specification.

4.2 Classification of inspections. - The following types of inspection shall be conducted on this item.

a. First Article Inspection

b. Quality Conformance Inspection

4.3 First Article Inspection

4.3.1 Submission. - The contractor shall submit a first article sample as designated by the Contracting Officer for evaluation in accordance with provisions of 4.3.2 and 4.3.3. The first article sample shall consist of one (1) container assembly (DWG. 8887105 or 9298881, as applicable).

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T02:08Z
Check the source to verify that this is the current version before use.

4.3.2 Inspections to be performed. - See MIL-A-48078, and Table II specified herein.

4.3.3 Rejection. - See MIL-A-48078.

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T02:08Z
Check the source to verify that this is the current version before use.

TABLE II - FIRST ARTICLE INSPECTION

CLASSIFICATION OF DEFECTS & TESTS MIL-C-63064 (PA)

PARAGRAPH	TITLE		SHEET 1 OF 1		DRAWING NUMBER SEE BELOW
					NEXT HIGHER ASSEMBLY
CATEGORY	EXAMINATION OR TEST	NO. OF SAMPLE UNITS	AQL OR 100%	REQUIREMENT PARAGRAPH	PARAGRAPH REFERENCE /INSPECTION METHOD
	Base Assembly (Dwg 9204053 or 9298882 as applicable) Examination for Defects	1	100%	3.2	4.4.2.1
	Frame Assembly (Dwg 9204054) Examination for Defects	1	100%	3.2	4.4.2.2
	Shipping and Storage Container (Dwg 8887105 or 9298881 as applicable) Examination for Defects	1	100%	3.2	4.4.2.3
	Tests (a)				
	Assembly and Disassembly	1	100%	3.4	4.5.1
	Pressure Retention	1	100%	3.5.10	4.5.2
	Vibration	1	100%	3.5.9	4.5.3.1
	Edgewise Drop	1	100%	3.5.5	4.5.3.2
	Cornerwise Drop	1	100%	3.5.6	4.5.3.3
	End Impact	1	100%	3.5.7	4.5.3.4
	Roll Over	1	100%	3.5.8	4.5.3.5
	Fork-Lifting	1	100%	3.5.1	4.5.3.6
	Stacking	1	100%	3.5.2	4.5.3.7
	Hoisting	1	100%	3.5.3	4.5.3.8
	Pushing	1	100%	3.5.4	4.5.3.9
	Pressure Retention	1	100%	3.5.10	4.5.2

NOTES:
(a) The tests shall be performed in the sequence listed.
(b) All first article examinations and tests shall be performed on the one sample specified in Para 4.3.1.

SARPA-QA FORM 2567 FEB 74 4010

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T02:08Z
Check the source to verify that this is the current version before use.

4.4 Quality conformance inspection.

4.4.1 Inspection lot formation. - Inspection lots shall comply with the lot formation provisions of MIL-A-48078.

4.4.2 Examination. - (See MIL-A-48078). Unless otherwise specified in the classification of defects and test tables, sampling plans for major and minor defects shall be in accordance with MIL-STD-105, Inspection Level II. Equipment necessary for the performance of the inspections listed shall be in accordance with 4.4.4.

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T02:08Z
Check the source to verify that this is the current version before use.

CLASSIFICATION OF DEFECTS & TESTS

PARAGRAPH	TITLE	SHEET	OF	DRAWING NUMBER
4.4.2.1	Base Assembly	1	1	9204053 or 9298882 as applicable
				NEXT HIGHER ASSEMBLY 8887105 or 9298881 as applicable

CATEGORY	EXAMINATION OR TEST	NO. OF SAMPLE UNITS	AQL OR 100%	REQUIREMENT PARAGRAPH	PARAGRAPH REFERENCE /INSPECTION METHOD
Critical	None defined				
Major					
101	Mislocation of mounting plates		0.40%	3.2	Gage
Minor					
201	Any component missing or damaged		0.65%	3.2	Visual
202	Evidence of poor workmanship		1.00%	3.6	Visual

NOTES:

SARPA-QA FORM 2567 FEB 74 4810

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T02:08Z
Check the source to verify that this is the current version before use.

QUALITY CONFORMANCE INSPECTION

CLASSIFICATION OF DEFECTS & TESTS

MIL-C-63064 (PA)

PARAGRAPH	TITLE		SHEET 1 OF 1		DRAWING NUMBER
4.4.2.2	Frame assembly prior to installation of lower cushion				9204054
					NEXT HIGHER ASSEMBLY 8887105 or 9298881 as applicable
CATEGORY	EXAMINATION OR TEST	NO. OF SAMPLE UNITS	AQL OR 100%	REQUIREMENT PARAGRAPH	PARAGRAPH REFERENCE /INSPECTION METHOD
Critical	None defined				
Major					
101	Distance between end supports, max		0.40%	3.2	Gage
102	Improper inside dimension		0.40%	3.2	Gage
103	Misalignment of middle support with respect to end supports		0.40%	3.2	Gage
Minor					
201	Evidence of poor workmanship		1.00%	3.6	Visual

NOTES:

SARPA-QA FORM 2567 FEB 74 4B10

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T02:08Z
Check the source to verify that this is the current version before use.

QUALITY CONFORMANCE INSPECTION

CLASSIFICATION OF DEFECTS & TESTS

MIL-C-63064 (PA)

PARAGRAPH	TITLE	SHEET	DRAWING NUMBER
4.4.2.3	Shipping and storage container	1 OF 1	8887105 or 9298881 as applicable
			NEXT HIGHER ASSEMBLY

CATEGORY	EXAMINATION OR TEST	NO. OF SAMPLE UNITS	AQL OR 100%	REQUIREMENT PARAGRAPH	PARAGRAPH REFERENCE /INSPECTION METHOD
Critical	None defined				
Major					
101	T-Bolts missing or damaged		0.40%	3.2	Visual
102	Metal identification plate missing		0.40%	3.2	Visual
103	Any component missing or damaged		0.40%	3.2	Visual
104	Incorrect torque of bolts on resilient mounts		0.40%	3.2	Gage
Minor					
201	Holes for lead seal missing		0.65%	3.2	Visual
202	Marking misleading or unidentifiable		0.65%	3.2	Visual
203	Evidence of poor workmanship		1.00%	3.6	Visual

NOTES:

SARPA-QA FORM 2567 FEB 74 4810

10

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T02:08Z
Check the source to verify that this is the current version before use.

4.4.3 Testing. -

4.4.3.1 Assembly and disassembly. - (see 3.4) Major Defect. - Each container shall be subjected to the test of 4.5.1. If any container fails to comply with the applicable requirement, it shall be classified defective and removed from the lot. (Non-destructive)

4.4.3.2 Pressure retention (See 3.5.10) Major Defect. - Each container shall be subjected to the test of 4.5.2. If any container fails to comply with the applicable requirement, it shall be classified defective and removed from the lot. (Non-destructive)

4.4.4 Inspection Equipment. - The inspection equipment required to perform the inspections and tests prescribed in this specification is identified in the "Paragraph Reference/Inspection Method' column in the tables starting with paragraph 4.4.2.1. The contractor shall submit for approval, inspection equipment designs in accordance with the terms of the contract. See Section 6 of MIL-A-48078, and 6.2 herein.

4.5 Test method and procedures. -

4.5.1 Assembly and disassembly. - The T-Bolts shall be released and the cover assembly removed, utilizing the lifting provisions. The dispenser or fixture shall be loaded, and the container components reassembled to the torque specified on the applicable drawings. There shall be no excess effort required to load the dispenser or to reassemble the container components, other than the torque requirements specified on Drawing 8887105 or 9298881 as applicable.

4.5.2 Pressure retention test. - A fixture as shown on the Equipment List shall be assembled to the container. The vent assembly shall be blocked and the container shall be filled with air pressure equal to 3.5 $\pm$ .5 psig. The pressure loss shall not exceed 0.1 psig during a 30 minute period.

In lieu of the above test, the container may be assembled and closed, then tested by filling with dry air to a minimum pressure of 4 psig, and immersing all exterior surfaces in water to a depth of 2 inches, not necessarily simultaneously while maintaining 4 psig. After a 10 minute period of immersion, presence or emissions of air bubbles other than normal trapped air around the hardware or closure flange, shall be cause for rejection.

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T02:08Z
Check the source to verify that this is the current version before use.

4.5.3 Performance characteristics testing. - Only the First Article Sample shall be subjected to the following tests.

4.5.3.1 Vibration. - The loaded container shall withstand the vibrations specified in Table 1. The container shall be assembled to a suitable fixture with cover closed and latches fastened in a normal manner. Adequate safety precautions shall be observed to preclude endangering personnel and equipment.

4.5.3.2 Edgewise drop. - The container, with load assembled, shall be supported at one end of its base on a sill approximately five (5) inches in height and placed at right angled to the skids. The other end of the container shall be raised and allowed to fall freely from an eighteen inch height to a concrete or similarly hard surface. This test shall be applied to both ends of the container.

4.5.3.3 Cornerwise drop. - The container with load assembled, shall be supported at one corner of its base on a block approximately five (5) inches in height and with a block approximately twelve (12) inches high placed under the other corner of the same end of the container. The opposite end of the container shall be raised and allowed to fall freely from a eighteen inch height, measured from the lower of the two (2) corners, to a concrete or similarly hard surface. This test shall be applied to one corner of each end of the container.

4.5.3.4 End impact. - The container with load assembled shall be suspended as a pendulum at the end of four (4) cables, one (1) through each hoisting provision. The container shall be permitted to swing, with a velocity of 10 ± 1.5 feet per second, into a hard, flat, vertical surface. The impact shall be applied to both ends of the container, parallel to the longitudinal axis. Observation shall be made for evidence of external damage. Damage to wooden skids shall be disregarded.

4.5.3.5 Roll-over. - The loaded container, erect on it's skids on a hard, level floor, shall be tipped slowly sideways until it falls freely by its own weight to the floor. This process shall be repeated for one (1) revolution with falls from side to top, top to opposite side, and from that side to base.

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T02:08Z
Check the source to verify that this is the current version before use.

4.5.3.6 Fork lifting. - The container shall be lifted clear of another container (or equipment) when stacked, lowered to the floor by a fork-lift truck having forks forty (40) inches minimum in length. The truck shall be cleared of the container, reassume lifting position and restack. This procedure shall be followed in lifting once from each side. The container shall be examined for punctures or broken or bent frame structures.

4.5.3.7 Stacking. - The required load shall be placed on top of the container in such a manner as to simulate stacking of five (5) additional loaded containers therein. The containers shall be examined for permanent set and breakage of structural members.

4.5.3.8 Hoisting. - The loaded container shall be lifted free of any support by means of the lifting eyes or rings.

4.5.3.9 Pushing. - The loaded container shall be pushed across at least five (5) feet of rough concrete in the direction parallel to the axis of the container with the ends of fork truck blades in contact with skids. The test shall be repeated in a direction normal to the axis of the container with the ends of fork truck blades in contact with the skids.

5. PREPARATION FOR DELIVERY

5.1 Marking. - Marking shall be in accordance with Standard MIL-STD-129.

5.2 Shipping. - When shipments from more than one lot are shipped as a carload, each lot shall be kept separate, and the division between lots clearly indicated to prevent mixing of the lots in transit.

6. NOTES

6.1 Ordering data. - Procurement documents shall specify the following:

a. Title, number and date of this specification.
b. Ammunition data cards shall be prepared for each lot in accordance with Standard MIL-STD-1167.
c. Provisions of MIL-A-48078.

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T02:08Z
Check the source to verify that this is the current version before use.

6.2 Submission of inspection equipment designs for approval (See MIL-A-48078). - Submit equipment designs as required to Commander: Picatinny Arsenal, ATTN: SARPA-QA-T-T, Dover, New Jersey 07801.

6.3 Distribution of ammunition data cards. - Distribution of data cards shall include the following: Commander, Picatinny Arsenal, ATTN: SARPA-QA-A-M and SARPA-AD-D-P Dover, New Jersey 07801.

Custodian:
Army-PA

Preparing Activity:
Army-PA

Project Number: 8140-A-158

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T02:08Z
Check the source to verify that this is the current version before use.