MILITARY SPECIFICATION

POLARITY TEST PLUG

This specification is approved for use by all Departments and Agencies of the Department of Defense.

1. SCOPE

1.1 This specification covers the inspection and test of one type of polarity test plug used in the M56 Aircraft Sub-system.

2. APPLICABLE DOCUMENTS

2.1 The following documents of the issue in effect on date of invitation for bids or request for proposal form a part of this specification to the extent specified herein.

SPECIFICATIONS

MILITARY

MIL-A-2550	- Ammunition and Special Weapons; General Specification For.

STANDARDS

MILITARY

MIL-STD-105	- Sampling Procedures and Tables For Inspection by Attributes
MIL-STD-109	- Quality Assurance Terms and Definitions
MIL-STD-750	- Test Methods and Procedures for Microelectronics
MIL-STD-1168	- Lot Numbering of Ammunition
MIL-STD-1169	- Packaging, Packing and Marking for Shipment of Inert Ammunition Components
MIL-STD-1235	- Single and Multilevel Continuous Sampling Procedures and Tables for Inspection by Attributes

FSC: 1345

Source: https://assist.dla.mil -- Downloaded: 202640-22T19:20Z
Check the source to verify that this is the currentversion before use.

DRAWINGS

U.S. ARMY PICATINNY ARSENAL

PRODUCT DRAWING

9280147 - Polarity Test Plug.

(Copies of specifications, standards, drawings and publications listed above required by suppliers in connection with specific procurement functions should be obtained from the procuring activity or as directed by the Contracting Officer).

3. REQUIREMENTS

3.1 Material. - Materials shall be in accordance with applicable specifications and drawings.

3.2 Assembly. - The assembly shall comply with all requirements specified on drawing (dwg.) 9280147 and with all requirements specified in applicable specifications.

3.3 Indicator Lamp Operation. - The lamp shall light when a voltage of twenty four minus one (24.0-1.0) volts direct current is applied to the connector with the indicated polarity.

3.4 Workmanship. - All parts and assemblies shall be fabricated and finished in a thorough workmanlike manner. They shall be free of burrs, chips, sharp edges, cracks, unblended radii, surface defects, dirt, grease, rust, corrosive products, loose wire strands, exposed leads and other foreign matter. The cleaning agent or method used shall not be injurious to any part, nor shall the part be contaminated by the cleaning agents. All markings and stampings shall be neat and clearly defined.

3.5 Submission of Results of Contractor Conducted Examinations and Tests. - The contractor shall forward copies of the results of any of his examinations or tests to the designated address as required by the contract. Results shall be submitted within thirty (30) days at the completion of each lot tested (see 6.4).

3.6 First Article Inspection. - This specification makes provision for First Article Inspection. Requirements for the

Source: https://assist.dla.mil -- Downloaded: 202640-22T19:20Z
Check the source to verify that this is the currentversion before use.

submission of the first article samples by the contractor shall be as specified in the contract.

4. QUALITY ASSURANCE PROVISIONS

4.1 Responsibility for Inspection.-Unless otherwise specified in the contract or purchase order, the supplier is responsible for the performance of all inspection requirements as specified herein. Except as otherwise specified in the contract or order, the supplier may use his own or any other facilities suitable for the performance of the inspection requirements specified herein, unless disapproved by the Government. The Government reserves the right to perform any of the inspections set forth in the specification where such inspections are deemed necessary to assure supplies and services conform to prescribed requirements. Reference shall be made to MIL-STD-109 to define terms used herein. The provisions of MIL-A-2550 shall apply.

4.1.1 Submission of Product. -At the time each completed lot of items deliverable under the contract is submitted to the Government for acceptance, the contractor shall supply the following information accompanied by a certificate which attests that the information provided is correct and applicable to the product being submitted.

a. A statement that the lot complies with all of the quality assurance provisions specified in this specification.
b. Drawing and specification number and date, together with identification and date of changes thereto.
c. A statement that all material purchased by the contractor meets requirements, when such material is controlled by Government or commercial specifications referenced in any of the contractual documents, and that certificates of conformance are on file and available for review.
d. Number of items in the lot.
e. Date submitted.

The certificate shall be signed by a responsible agent of the certifying organization. The initial certificate submitted shall be substantiated by evidence of the agent's authority to bind his principal. Substantiation of the agents authority will not be required with subsequent certificates unless, during the course of the contract, this authority is vested in another agent of the certifying organization.

Source: https://assist.dla.mil -- Downloaded: 202610-22T19:20Z
Check the source to verify that this is the current version before use.

4.2 First Article Inspection

4.2.1 Submission. -Prior to the start of regular production the contractor shall submit a first article sample (see 6.1c) to a Government approved facility as designated by the contracting officer for evaluation in accordance with the provisions of 4,2.2 and 4.2.3. The first article sample shall consist of ten (10) sets of sub-assemblies and ten(10) assembled polarity test plugs which have been produced by the contractor or furnished by a supplier and which have been manufactured using the same production processes, procedures and equipment which will be used in fulfilling the contract. All parts and materials including packaging and packing shall be obtained from the same source of supply as will be used in regular production. Prior to submission the contractor shall inspect the sample to the degree necessary to assure that it conforms to the requirements of the contract and submit a record of this inspection with the sample, including a certificate of conformance for materials. A sample containing known defects will not be submitted unless specifically authorized by the Contracting Officer. A first article sample, or portion thereof, as directed by the Contracting Officer, shall also be submitted whenever there is a lapse in production for a period in excess of 90 days or whenever a change occurs in manufacturing process, material used, drawings or specification such as to significantly affect product uniformity as determined by the Government.

4.2.2 Inspections to be performed. Sub-assemblies and assemblies will be subjected by the Government to any or all of the examinations and tests specified in this specification and any or all requirements of the applicable drawings.

4.2.3 Rejection.- If any sub-assembly or assembly fails to comply with any of the applicable requirements, the first article sample shall be rejected. The Government reserves the right to term.irlate its inspection upon any failure of a sub-assembly or assembly to comply with any of the applicable requirements.

4.3 Inspection provisions

4.3.1 Lot formation. -The term "inspection lot" as used in this specification is defined as an essentially homogeneous collection of units of product from which a representative sample is drawn and inspected to determine conformance with applicable

Source: https://assist.dla.mil -- Downloaded: 202610-22T19:20Z
Check the source to verify that this is the currentversion before use.

requirements . The sample selected shall represent only that quantity of units from which the sample was drawn and shall not be construed to represent any prior or subsequent quantities presented for inspection. Homogeneity shall be considered to exist provided the inspection lot has been produced by one manufacturer in one unchanged process using the same materials and methods in accordance with the same drawings, same drawing revisions, same specifications and same specification revisions and complies with the provisions for submission of product as specified in MIL-STD-105. Changes to the process, specifications, or drawings not affecting safety, performance, interchangeability, or storage, as determined by the Government, shall not be deemed to alter the homogeneity of an inspection lot. All material submitted for inspection in accordance with this specification shall comply with the homogeneity criteria specified herein regardless of the type of sampling procedure which is being applied to determine conformance with requirements. Lot numbering, as required, shall be in accordance with MIL-STD-1168.

4.3.2 Examination.- The examinations listed in the following subparagraphs shall be performed on inspection lots (see 4.3.1) of the components or assemblies designated in the applicable paragraph headings. Inspection for critical defects (and major defects, when so specified) shall be 100 percent. Sampling plans for major and minor defects shall be in accordance with MIL-STD-105 except that continuous sampling plans in accordance with MIL-STD-1235 may be used if approved by the Government. Instead of applying the AQL's designated herein to the groups of major and minor defects listed, the contractor may elect to apply an AQL of .40 percent for each major defect and an AQL of 0.65 percent for each minor defect. When this method is elected, it shall be applied to all of the major and minor defects listed in the applicable sub-paragraph of this section, except where 100 percent inspection is specified, and be documented as part of the contractor's inspection system. Equipment necessary for the performance of the inspections listed shall be in accordance with 4.3.4.

4.2.3.1 Polarity Test Plug prior to sealing (see dwg. 9280147).

Categories	Defects	Method of Inspection	Code No. (see 6.2)
Critical:	None defined		

Source: https://assist.dla.mil -- Downloaded: 202610-22T19:20Z
Check the source to verify that this is the current version before use.

Major:	AQL 0.40 percent		
101.	Sleeving on leads and diode missing or incomplete	Visual	01001
Minor:	AQL 0.65 percent		
201.	Evidence of poor workmanship (see 3.4)	Visual	01002

4.3.2.2 Polarity Test Plug (see dwg. 9280147).

Categories	Defects	Method of Inspection	Code No.
Critical:	None defined		
Major:	AQL 0.40 percent		
101.	Strap(s) not secure	Manual	02001
102.	Polarity Marking missing	Visual	02002
Minor:	AQL 1.0 percent		
201.	Any component missing	Visual	02003
202.	Evidence of poor workmanship (see 3.4)	Visual	02004

4.3.3 TESTING

4.3.3.1 Indicator Lamp Operation (see 3.3) Major Defect, Code No. 02005, - Each lot of polarity test plugs shall be tested 100 percent for the specified requirements in accordance with the procedure specified in 4.4.1. Any plug failing to comply with all of the specified requirements shall be classed defective and removed from the lot. Testing is non-destructive and only accepted plugs shall be returned to the lot.

4.3.3.2 Diodes Forward Voltage Drop (see dwg. 9280147) Major Defect, Code No. 02006. - Each lot of polarity test plugs shall be testes 100 percent for the specified requirement in accordance with the procedure specified in 4.4.2. Any plug failing to comply with all of the specified requirements shall be classed defective and removed from the lot. Testing is non-destructive and only accepted plugs shall be returned to the lot.

4.3.4 Inspection Equipment. - Inspection equipment required to perform the inspections prescribed in this specification is identified in the Examination (4.3.2) and Test Method (4.4) paragraphs herein. See 6.3 for details concerning responsibilities for inspection design and approval.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T19:20Z
Check the source to verify that this is the current version before use.

4.4 TEST METHODS AND Procedures

4.4.1 Indicator Lamp Operation. - The polarity test plug shall be tested for the specified requirements of 3.4 using a government approved fixture, test equipment and operating procedures. Any plug failing to comply with the requirements shall be classed defective.

4.4.2 Diodes Forward Voltage Drop. - A shorting plug shall be substituted for the No. 327 lamp for this test only. The polarity test plug shall be driven at the plus (+) terminal with a current of one (1) ampere plus or minus five percent (+ 5%) when tested in accordance with Test Method 4011 of MIL-STD-750 to determine the forward voltage drop of both 1 N 4003 diodes in the device. Test Methods and Procedures shall be approved by the Government. Any device failing to comply with specified requirements shall be classed defective.

5. PREPARATION FOR DELIVERY

5.1 Preservation and Packaging

5.1.1 Level C. - Each polarity test plug shall be preserved and packaged in accordance with MIL-STD-1169.

5.2 Packing

5.2.1 Level C. - The polarity test plug, preserved and packaged in 5.1.1, shall be packed for shipment in accordance with MIL-STD-1169.

5.3 Marking. - Marking of the carton shall comply with MIL-STD-1169.

5.4 Shipping. - When polarity test plugs of more than one lot are shipped together, each lot shall be kept separate and the division between lots clearly indicated to prevent mixing of the lots in transit.

6. NOTES

6.1 Ordering data. -Procurement documents shall specify the following:

a. Title, number and date of this specification.

Source: https://assist.dla.mil -- Downloaded: 202610-22T19:20Z
Check the source to verify that this is the currentversion before use.

b. Data cards. - Data cards shall be prepared for each lot in accordance with the information specified in Standard MIL-STD-1167.

c. Provisions for submission of first article samples.

6.2 Inspection code numbers. -The five digit code numbers assigned to the inspections herein are to facilitate future data collection and analysis by the Government. They should be cited as references on drawings of equipment designs submitted by the contractor to the Government for approval (see 6.3.3).

6.3 Inspection Equipment Designs .-Inspection equipment designs are of two types - Government Special Inspection Equipment (SIE) designs and contractor designs. SIE designs are designated by drawing numbers under the "Method of Inspection" headings in Section 4. Design responsibility for all other inspection equipment is assigned to the contractor. The contractor need not furnish any design when a complete Government SIE design is provided. Unless otherwise specified, however, the contractor may submit alternate or modified contractor designs of SIE in accordance with 6.3.2 and 6.3.3 should he elect to do so.

6.3.1 SIE designs. -SIE designs may consist of any of the following:

a. Detailed drawings which completely depict all information necessary for the fabrication and use of the item of inspection equipment.

b. A source control drawing or a specification control drawing as defined in MIL-STD-100.

c. An envelope drawings, as defined in MIL-STD-100, which establishes the criteria which a detailed design shall meet. When envelope drawings are specified, the contractor shall prepare designs which comply with the criteria therein.

6.3.2 Contractor designs.-Contractor designs are required for all inspection equipment for which SIE designs are not specified and may include commercial equipment which the contractor proposes to use. (Commercial equipment is defined as unmodified equipment which is cataloged and available for purchase by the general public.) Contractor designs shall include appropriate operating instructions, calibration procedures and maintenance procedures. Commercial equipment shall be fully described by

Source: https://assist.dla.mil -- Downloaded: 202610-22T19:20Z
Check the source to verify that this is the currentversion before use.

catalog listings or other means which provide sufficient information to permit identification and evaluation by the Government and may include illustrations and engineering data. Designs shall be prepared for any special fixture(s) required to be used with commercial equipment, or with SIE designs if not otherwise covered thereby (see 6.3.1c). Designs shall be of the category and form (per MIL-D-1000) specified in the Contract Data Requirements Lists (DD Form 1423). The contractor is referred to MIL-HDBK-204, "Inspection Equipment Design" for guidance. The specification number and the applicable five digit defect code number (or other specific identifying information) from Section 4 of this specification shall be referenced on each contractor design together with the component or assembly drawing number and revision letter to which the specific design applies.

6.3.3 Submission of Designs for Approval.-Contractor designs shall be approved by the Government prior to fabricating or procuring the equipment. Designs shall be submitted for approval to Picatinny Arsenal, ATTN: SARPA-QA-A-M, Dover, New Jersey 07801 in accordance with the stipulations, time frame and distribution specified in the Contract Data Requirements List (DD Form 1423) or in the contract. The contractor must include in his submission of designs a listing of any and all Government SIE designs which will be utilized. Partial submission of inspection designs is permissible and encouraged. However, the completion date for design review will be based on the date of the final submission of designs. Picatinny Arsenal design review will normally be accomplished within one month after receipt.

6.4 Submission of results of contractor conducted examinations and tests (see 3.5). - The contractor shall send his results to:

Commander
Picatinny Arsenal
ATTN: SARPA-QA-A-M
Dover, New Jersey 07801

Custodian:
Army-PA

Preparing Activity:
Army-PA

Project Number: 1345-A-034

Source: https://assist.dla.mil -- Downloaded: 202610-22T19:20Z
Check the source to verify that this is the current version before use.