MILITARY SPECIFICATION

RELAY, EXPLOSIVE, XM11

1. SCOPE

1.1 This specification covers one type of explosive relay designated as Relay, Explosive, XM11.

2. APPLICABLE DOCUMENTS

2.1 The following documents of the issue in effect on date of invitation for bids or request for proposal, form a part of this specification to the extent specified herein.

SPECIFICATIONS

MILITARY

MIL-P-116 — Preservation, Methods of.

MIL-A-2550 — Ammunition and Special Weapons, General Specification for.

MIL-I-45607 — Inspection Equipment, Supply and Maintenance of.

STANDARDS

MILITARY

MIL-STD-105 — Sampling Procedures and Tables for Inspection by Attributes (ABC-STD-105).

MIL-STD-109 — Quality Assurance Terms and Definitions.

MIL-STD-1168 — Lot Numbering of Ammunition.

MIL-STD-1235 — Single and Multi-level Continuous. Sampling Procedures and Tables for Inspection by Attributes.

DRAWINGS

U. S. ARMY MUNITIONS COMMAND

7548347 — Box, Set-up, Packing, Ammunition, for Relays and Primers.

7548388 — Box, Packing, Ammunition, for Relays M4, M5, M7, XM10 or Primer, XM42.

7548389 — Box, Set-up, Packing, Ammunition Inner for Relays or Primers.

8886996 — Relay, Explosive: XM11

FSC 1375

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T00:36Z
Check the source to verify that this is the current version before use.

PUBLICATIONS

ARMY

ET-8886996 — Equipment Tabulation.

(Copies of specifications, standards, drawings, and publications required by suppliers in connection with specific procurement functions should be obtained from the procuring activity or as directed by the Contracting Officer.)

2.2 Other publications. The following documents form a part of this specification to the extent specified herein. Unless otherwise indicated, the issue in effect on the date of invitation for bids or request for proposal, shall apply.

CODE OF FEDERAL REGULATIONS

49 CFR 71-78 — Interstate Commerce Commission Rules and Regulations for the Transportation of Explosives and Other Dangerous Articles.

(The Interstate Commerce Commission Regulations are now a part of the Code of Federal Regulations (1949 Edition and revisions) available from the Superintendent of Documents, U.S. Government Printing Office, Washington, D.C. 20402. Orders for the above publication should cite, "49 CFR 71-78, (latest revision)."

3. REQUIREMENTS

3.1 Material. Materials and parts shall be in accordance with the applicable drawings and specifications.

3.2 Relay assembly. The relay assembly shall comply with all requirements specified on Drawing (dwg) 8886996, and with all requirements specified in applicable specifications.

3.3 Moisture content of lead azide. The moisture content of the lead azide at the time and place of loading shall not exceed 0.50 percent when determined as specified in 4.4.1.

3.4 Functioning. The relay assembly shall function and shall initiate a specified detonator when tested as specified in 4.4.2.

3.5 Workmanship. All parts and assemblies shall be fabricated, loaded and assembled in a thorough, workmanlike manner. They shall be free of burrs, sharp edges, cracks, chips, dirt, grease and other foreign matter. The cleaning method used shall not be injurious to any part, nor shall the parts be contaminated by the cleaning agents. Exterior surface coatings shall be continuous except for a few light scratches not exposing base material. All required markings shall be neat and sharply defined.

3.6 First article testing. This specification makes provisions for first article testing. Submission of the first article quantity by the contractor shall be as specified in the contract.

3.7 Submission of results of contractor-conducted examinations and tests. The contractor shall forward copies of the results of any of his examinations or tests to the designated address as required by the contract, the specification, or as requested by the Contracting Officer (see 6.6).

4. QUALITY ASSURANCE PROVISIONS

4.1 General quality assurance provisions. Unless otherwise specified in the contract or purchase order, the supplier is responsible for the performance of all inspection requirements as specified herein. Except as otherwise specified, the supplier may utilize his own facilities or any commercial laboratory acceptable to the Government. The Government reserves the right to perform any of the inspections set forth in the specification where such inspections are deemed necessary to assure supplies and services conform to prescribed requirements. Reference shall be

Source: https://assist.dla.mil -- Downloaded: 202610-23T00:36Z
Check the source to verify that this is the current version before use.

made to MIL-STD-109 in order to define terms used herein. The provisions of MIL-A-2550 shall apply.

4.1.1 *Submission of product.* At the time the completed lot of product is submitted to the Government for acceptance, the contractor shall supply the following information accompanied by a certificate which attests that the information provided is correct and applicable to the product being submitted:

(a) A statement that the lot complies with all the quality assurance provisions specified within this specification.

(b) Number of units of product inspected.

(c) Results obtained, by defect code, for all inspections performed.

(d) Drawing, specification number and date, together with an identification and date of changes.

(e) Certificates of conformance on all material purchased by the contractor when such material is controlled by Government or commercial specifications referenced in any of the contractual documents.

(f) Number of items in the lot.

(g) Date submitted

The certificate shall be signed by a responsible agent of the certifying organization. The initial certificate submitted shall be substantiated by evidence of the agent's authority to bind his principal. Substantiation of the agent's authority will not be required with subsequent certificates unless, during the course of the contract, this authority is vested in another agent of the certifying organization.

4.1.2 *Government verification.* Using the contractor's written quality assurance procedure, this detailed specification, the applicable drawings, and other contractual documents as a guide, the Government inspector shall verify, at unscheduled intervals, all quality assurance operations performed by the contractor. Verification will be performed to the extent necessary to assure compliance with the contractual requirements. Severity of Government inspection of individual characteristics will be directly related to the seriousness of the classification assigned. In no instance will a characteristic classified "Critical" be accepted solely on the basis of the contractor's records.

4.2 First article inspection.

4.2.1 *Submission.* The contractor shall submit a first article quantity to a Government-approved facility as designated by the Contracting Officer (see 6.1) for evaluation in accordance with provisions of 4.2.2. The first article sample shall consist of the following:

a. Twenty-five (25) of each component.

b. Two hundred (200) loaded assemblies.

All components and completed assemblies shall have been produced by the contractor or furnished by a supplier and which have been manufactured using the same production processes, procedures and equipment as will be used in fulfilling the contract. All parts and materials, including packaging and packing, shall be obtained from the same sources of supply as will be used in regular production. The sample shall be accompanied by certificates of conformance for materials. A first article sample, or portion thereof, as directed by the Contracting Officer, shall also be submitted whenever there is a lapse in production for a period in excess of 90 days or whenever a change occurs in manufacturing process, material used, drawing, specification, or source of supply as to significantly affect product uniformity as determined by the Government. Prior to submission, the contractor shall inspect the sample to the

Source: https://assist.dla.mil -- Downloaded: 202640-23T00:36Z
Check the source to verify that this is the current version before use.

degree necessary to assure that it conforms to the requirements of the contract and submit a record of this inspection with the sample. A sample containing known defects will not be submitted unless specifically authorized by the Contracting Officer.

4.2.2 *Inspections to be performed.* Components and completed assemblies will be subjected by the Government to all the examinations or tests specified in 4.3.2 and 4.3.3 of this specification, and any or all requirements of the applicable drawings. In addition, the following test shall be performed. Thereafter, testing shall be as specified in 4.3.2 and 4.3.3.

4.2.2.1 *Functioning (see 3.4).* The two hundred (200) loaded relay assemblies shall be subjected to the functioning test as specified in 4.4.2 using equipment in accordance with 4.3.4.

4.2.3 *Rejection.* If any component or relay assembly fails to comply with any of the applicable requirements, the first article sample shall be rejected. The Government reserves the right to terminate its inspection upon any failure of a component or relay assembly in the sample to comply with any of the stated requirements. In the event of rejection, the Government reserves the right to require the contractor to take corrective action and submit a new first article sample or portion thereof. Until a first article sample is accepted, the contractor is in no way authorized by the Government to resume regular production unless otherwise directed by the Contracting Officer.

4.3 Inspection provisions.

4.3.1 *Lot formation.* The term "Lot" as used throughout this specification refers to an inspection lot, which is defined as an essentially homogeneous collection of units of product from which a representative sample is drawn and inspected to determine conformance of the lot with applicable requirements. The sample selected shall represent only that quantity of units from which the sample was drawn and shall not be construed to represent any prior or subsequent quantities presented for inspection. Homogeneity shall be considered to exist provided the lot has been produced by one manufacturer, in one unchanged process, in accordance with the same drawing, same drawing revision, same specification and same specification revision. Changes to the process, specification or drawing not affecting safety, performance, interchangeability, or storage, as determined by the Government, shall not be deemed to alter the homogeneity of the lot. The lot shall contain

(a) Parts of one lot interfix number from manufacturer.

(b) Lead azide from not more than one lot.

The inspection lot shall comply with MIL-STD-105 and shall be numbered in accordance with MIL-STD-1168. Unless otherwise approved by the Contracting Officer, the inspection lot size of end items deliverable under the contract shall be not less than the smallest weekly estimate of quantities contractually scheduled for production during the contract period, nor more than the largest monthly quantity contractually scheduled for delivery during the contract period. Inspection lots for components of subassemblies, other than the items of delivery, shall be homogeneous and of a size mutually convenient to both the contractor and the Government inspector.

4.3.2 *Examination.* Sampling plans and procedures for the following classifications of defects shall be in accordance with MIL-STD-105 (ABC-STD-105), except that, inspection for Critical defects shall be 100 percent. Contractor's sampling plans, if used, shall be approved by the Government, and shall provide, as a minimum, the protection afforded the Government by the sampling plans in MIL-STD-105 (ABC-STD-105). Continuous sampling plans in accordance with MIL-STD-1235 may be used if ap-

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T00:36Z
Check the source to verify that this is the current version before use.

proved by the procuring activity. Also, at the option of the procuring activity, AQL's and sampling plans may be applied to the individual characteristics listed using an AQL of 0.40 percent for each major defect and an AQL of 0.65 percent for each minor defect. In addition, at the option of the procuring activity, defect characteristics of the same classification which have been separated into two (2) groups to specifically allow the optional method of inspection in accordance with 4.3.3.2, may be combined into one (1) group when the option of 4.3.3.2 is not exercised. The AQL for the combined grouping shall be as indicated in the applicable classification of defects paragraph. Equipment necessary for the performance of the inspection listed shall be in accordance with 4.3.4.

4.3.2.1 *Cup, flat bottom relay (see dwg 8840625 covering a detail of dwg 8886996).*

Categories	Defects	Method of inspection	Defect code (See 6.2)
Critical:	None defined.		
Major:	AQL 0.65 percent		
101.	Outside diameter, maximum (max)	Gage	(01002)
102.	Inside diameter, minimum	Gage	(01003)
103.	Thickness of bottom, max	Gage	(01004)
Minor:	AQL 1.50 percent		
201.	Total length	Gage	(01005)
202.	Radius missing	Visual	(01006)
203.	Evidence of poor workmanship (see 3.5)	Visual	(01007)

4.3.2.2 *Washer, relay (see dwg 8844437 covering a detail of dwg 8886996).*

Categories	Defects	Method of inspection	Defect code
Critical:	None defined.		
Major:	AQL 0.65 percent (see 4.3.3.1)		
101.	Thickness	Gage	(02001)
102.	Inside diameter	Gage	(02002)
103.	Outside diameter	Gage	(02003)
Minor:	AQL 0.65 percent		
201.	Evidence of poor workmanship (see 3.5)	Visual	(02004)

4.3.2.3 *Relay assembly (see dwg 8886996).*

Categories	Defects	Method of inspection	Defect code
Critical:			
1.	Onion skin disc missing, mutilated or punctured	Visual	(03001)
2.	Cup cracked or split	Visual	(03002)
Major:	AQL 0.40 percent (see 4.3.3.2)*		
101.	Weight of charge	Balance	(03003)
Major:	AQL 1.00 percent		
102.	Outside diameter, max	Gage	(03004)
103.	Length	Gage	(03005)
104.	Underside of cup fails to contact washer for full 360 degrees	Visual	(03006)
105.	Cup damaged (excluding No. 2 above)	Visual	(03007)
106.	Charge missing	Visual	(03008)
107.	Component missing	Visual	(03009)
Minor:	AQL 0.65 percent		
201.	Evidence of poor workmanship (see 3.5)	Visual	(03010)

* Combined AQL for major defects 101–107, inclusive, is as follows: AQL 1.00 percent (see 4.3.2).

4.3.2.4 *Box, set-up, inner (see dwg 7548389).*

Categories	Defects	Method of inspection	Defect code
Critical:	None defined.		
Major:	AQL 0.40 percent		
101.	Contents loose	Manual	(04001)
102.	Box damaged to the extent that contents are exposed	Visual	(04002)
Minor:	AQL 1.00 percent		
201.	Label missing or peeling	Visual	(04003)
202.	Marking misleading or unidentifiable, including incorrect color code	Visual	(04004)

4.3.2.5 *Box, set-up, packing, ammunition, outer (see dwg 7548347).*

Categories	Defects	Method of inspection	Defect code
Critical:	None defined.		
Major:	AQL 0.65 percent		
101.	Contents loose	Manual	(05001)

Source: https://assist.dla.mil -- Downloaded: 202610-23T00:36Z
Check the source to verify that this is the current version before use.

Categories	Defects	Method of inspection	Defect code
	102. Sealing compound incomplete or inadequate	Visual	(05002)
	103. Waterproof seal broken	Visual	(05003)
Minor:	AQL 1.00 percent		
	201. Label missing or peeling	Visual	(05004)
	202. Marking misleading or unidentifiable, including incorrect color code	Visual	(05005)

4.3.2.6 *Sealed Barrier Bag (see dwg 7548347).*

Categories	Defects	Method of inspection	Defect code
Critical:	None defined.		
Major:	AQL 0.40 percent		
	101. Heat seal improper or incomplete	Visual	(09001)
	102. Bag punctured, torn, or cut	Visual	(09002)
Minor:	AQL 0.65 percent		
	201. Marking misleading or unidentifiable	Visual	(09003)

4.3.2.7 *Box, packing (see dwg 7548388).*

Categories	Defects	Method of inspection	Defect code
Critical:	None defined.		
Major:	AQL 0.40 percent		
	101. Strapping missing, broken or loose	Visual-manual	(06001)
	102. Box damaged to the extent that contents are exposed or liable to become exposed	Visual	(06002)
Minor:	AQL 1.50 percent		
	201. Contents loose	Manual	(06003)
	202. Strapping improperly assembled	Visual	(06004)
	203. Marking misleading or unidentifiable, including incorrect color code	Visual	(06005)

4.3.3 *Testing.*

4.3.3.1 *Dimensional control of stamped parts.* In place of the normal sampling associated with the classification of defects, and with the approval of the Contracting Officer, a sample of at least ten (10) parts may be dimensionally inspected to qualify the tool used in the stamping process for use in production. In addition, a random sample of five (5) parts shall be selected from the last portion of each hour's production for dimensional inspection as a control of the tool during production. If any defective parts are found during qualification of the tool, the tool producing the defective parts shall not be used in production. If any defective parts are found when inspection is performed for control of the tool, the tool producing the defective part shall be removed from production. Further, that portion of production since the last tool control check, shall be returned to the contractor for corrective action. All tools removed from production because of some fault, may, after reworking, be returned to production, providing they pass the qualification test above. The contractor may request a change of inspection frequency, providing he presents objective evidence to the Contracting Officer to substantiate the request.

4.3.3.2 *Weight of charge (see dwg 8886996) major defect (defect code 03003).* In place of the normal sampling associated with the classification of defects, and with the approval of the Contracting Officer, the following inspection procedure may be employed: Fifty (50) unloaded cups shall be selected from each lot and shall be weighed separately. A sample of eighty (80) loaded units shall be selected from each lot and shall be weighed separately. The sum of the lightest weight of an empty cup and the minimum specified charge weight shall be used as the minimum acceptable weight for loaded units. Failure of (2) or more units in meeting the minimum acceptable weight requirement shall reject the lot.

4.3.3.3 *Moisture content of lead azide (see 3.3) major defect (defect code 07001).* A sample of two (2) grams of lead azide shall be selected for the moisture content determin-

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T00:36Z
Check the source to verify that this is the current version before use.

ation from that quantity of lead azide to be used in each day's production of relays. This determination shall be made at the site of, and immediately before loading the cups. The determination shall be performed as specified in 4.4.1. If the moisture content exceeds the percentage specified, and loading has not begun, the lot of lead azide shall be rejected until proper corrective action has been accomplished as verified by repeating the moisture content test specified in 4.4.1. If loading has begun, action on the unloaded lead azide shall be as specified above and all relays loaded with the questionable lead azide shall be rejected.

4.3.3.4 *Functioning (see 3.4) major defect (defect code 08001).* After all first article testing (see 4.2), this test shall be performed on every fifth lot. The sampling plan for this test shall be in accordance with MIL–STD–105 using code letter L and AQL of 0.25 percent. The test shall be performed as specified in 4.4.2. Any relay assembly which fails to comply with the specified requirement shall be classed defective. If any lot is rejected, this test shall be performed on every lot until three consecutive lots have been accepted. Thereafter, sampling will be on every fifth lot.

4.3.3.5 *Heat seal (quick leak) test of sealed barrier bag (as applicable) (see dwg 7548347 and MIL–P–116) major defect (defect code 09001).* The sampling and acceptance criteria shall be in accordance with MIL–STD–105, Inspection Level S–4. The test shall be performed as specified in 4.4.3 using equipment in accordance with 4.3.4. Any bag failing to comply with the requirements specified in MIL–P–116 shall be classed defective.

4.3.4 *Inspection equipment.* Equipment tabulation (ET) number 8886996 and equipment lists (ELs) referenced thereon identify the inspection equipment required to perform the examinations and test prescribed in this section. The contractor shall design inspection equipment in accordance with the instructions in 6.3.

4.3.4.1 *Government rights to documentation.* Inspection equipment drawings and lists provided and revised in accordance with the requirements of this specification may be used by DOD activities for design, procurement, manufacture, testing, evaluation, production and receiving inspection, overhaul, shipping, storage, identification of stock, ordering and storage of replacement parts, inspection or items at overhaul, general maintenance of equipment, construction, survey, and whenever inspection equipment drawings are needed.

4.3.4.2 *Supply and maintenance.* Supply and maintenance of the equipment listed on the ELs shall be in accordance with MIL–I–45607.

4.3.4.3 *Government use of contractor's inspection and test equipment.* The contractor shall, when required by the Government, make available all inspection and test equipment necessary for determining conformance with the contract requirements. Personnel for operating the equipment, and verification of its accuracy shall be supplied by the contractor for the performance of examination or test by the Government.

4.4 Test Methods and procedures.

4.4.1 *Moisture content of lead azide.* A tared, dried aluminum dish, 2 inches in diameter, shall be covered with a sheet of teflon, 2½ inches square, and sufficiently flat to form a tight cover and the tare weight determined. An accurately weighed portion of approximately two grams of the sample shall be transferred to the moisture dish while both the cover and dish are on the balance pan. The dish and contents shall be transferred to an oven and dried at 90° C. plus or minus (±) 2° C. for 2 hours. The cover shall be placed in a sulfuric acid desiccator during the drying period. After drying, the dish shall be quickly transferred to the desiccator and allowed to cool to room temperature. The teflon cover shall be placed on the dish and assembly weighed. The loss in

Source: https://assist.dla.mil -- Downloaded: 202640-23T00:36Z
Check the source to verify that this is the current version before use.

weight shall be used to calculate the percentage of moisture in the lead azide as follows:

$$\text{Percentage of moisture} = \frac{(A - B) \times 100}{A}$$

where

A = The weight of the sample before drying.

B = The weight of the sample after drying.

4.4.2 *Functioning.* The relay assembly shall be assembled in the fixture specified on the EL, or an approved equal. The test shall be performed as follows: A weight of 3.0 ± 0.25 ounces shall fall a distance of six to seven inches to strike the firing pin which will initiate an M47 detonator. The relay assembly under test shall, thereupon, function and initiate an M49 detonator. Examination shall be made to determine compliance with 3.4. Should the M49 detonator fail to function, a second relay shall be tested. If the detonator functions, it will be assumed that the relay previously tested was defective. If the second relay fails to function the detonator, the detonator will be considered defective and will be replaced by another detonator.

Note. Should the XM11 relay fail to function, it should be determined if any obstruction is present in the closing plug flash hole. Should evidence of obstruction be present, the test shall be declared invalid and the test repeated using another closing plug, a new XM11 relay and the same M49 detonator.

4.4.3 *Heat seal (quick leak) test of sealed barrier bag.* The quick leak test shall be performed as specified in MIL–P–116 with a static load of 50 ounces. Observation shall be made to determine compliance with MIL–P–116. Seals so tested shall not be returned to the lot.

5. PREPARATION FOR DELIVERY

5.1 Preservation and packaging.

5.1.1 *Level B (see 6.4) and level C (see 6.1).* The relays shall be preserved and packaged in accordance with dwgs 7548347 and 7548389.

5.2 Packing.

5.2.1 *Level B (see 6.4) and level C (see 6.1).* The relays shall be packed in accordance with dwg 7548388.

5.3 Marking. Marking shall be in accordance with dwgs 7548347, 7548388, 7548389, and Interstate Commerce Commission Code of Federal Regulations 49 CFR 71–78.

5.4 Shipping. When shipments of more than one lot are made as a carload, each lot shall be kept separate, and the division between lots clearly indicated to prevent mixing in transit.

6. NOTES

6.1 Ordering data. Procurement documents shall specify the following:

a. Title, number and date of this specification.

b. Data cards shall be prepared for each lot in accordance with the information specified in MIL–STD–1167.

c. Provisions for submission of first article samples.

d. Level of packaging and packing required.

6.2 Inspection code numbers. The five-digit code numbers assigned to the inspections herein are to facilitate future data collection and analysis by the Government.

6.3 Inspection equipment. The contractor shall design inspection equipment as required by the referenced equipment lists (EL) in accordance with the instructions of paragraphs 6.3.1 through 6.3.5.

Source: https://assist.dla.mil -- Downloaded: 202610-23T00:36Z
Check the source to verify that this is the current version before use.

6.3.1 *Equipment lists.* Equipment lists indicate the availability of inspection equipment designs by showing in the "Part number" column of the list of inspection equipment (Form SMUPA 1010) the numbers of drawings or federal stock numbers of existing equipment designs, or codes as indicated in paragraph 6.3.2. Design action required of the contractor is described in paragraphs 6.3.3 and 6.3.4. The contractor will be required to prepare detailed drawings in accordance with 6.3.4 for all the equipment coded as "Contractor design" in the "Part number" column. These contractor designs must be approved by the Government prior to fabrication or procuring of the equipment. Designs shall be submitted for approval as specified in 6.3.5.

6.3.2 *Equipment list codes.* The inspection equipment as defined in 6.3.3 and 6.3.4 will be designated in the EL by the following codes:

CD — Contractor design on controlled contractor format and/or commercial equipment.

MU — Army design, mandatory for use.

6.3.3 *Army designs.* Army designs are reflected on detailed drawings which completely depict all the information necessary for the fabrication of the item of inspection equipment. The contractor need provide no design when an Army design is listed for an item of inspection equipment. Army designs fall into two basic classifications; mandatory (designated "MU") and nonmandatory (indicated by drawing or federal stock number). When an equipment list references mandatory Army designs, the contractor shall comply with, and use these designs accordingly. The contractor may, however, in connection with nonmandatory designs, and with the approval of the Government, design alternate inspection equipment or use comparable commercial equipment to facilitate his operations. Such contractor-prepared designs or commercial equipment selections must be approved by the Government prior to fabrication or procuring of the equipment. Designs shall be submitted for approval as specified in 6.3.5.

6.3.4 *Contractor designs.* Contractor designs are designs of inspection equipment for which the Government has assigned design responsibility to the contractor. Contractor designs shall be supported by detailed drawings which depict all information necessary to completely fabricate, calibrate and operate an item of inspection equipment. This requires that the necessary views, dimensions, materials, finishes, notes, and operating and calibration instructions be properly depicted in accordance with approved practices to the extent that further calculation or clarification will not be required. Unless otherwise specified, contractor designs may be developed on the format the contractor normally employs in his equipment design procedure provided such format reflects the detail and information specified above, subject to the following controls: All submitted contractor designs shall conform to MIL–D–1000, Category E, Form 2. Legibility and reproducibility shall permit conventional making of clearly understandable, high contrast reproductions. Contractors shall submit one copy of final designs as a rolled set. Designs shall be submitted for approval as specified in 6.3.5.

6.3.5 *Submission of contractor designs.* Unless otherwise specified on the EL, all designs of equipment for inspection of defects classified as critical and major shall be submitted for approval to the Commanding Officer, Picatinny Arsenal, ATTN: SMUPA–NDIC. All other designs of inspection equipment shall be approved by the inspection element of the agency administering the contract. Submission shall be as directed by the contracting officer. Partial submission of inspection equipment designs is permissible and encouraged. However, the Arsenal completion date for design review will be based on the date of the final submission of designs. Picatinny Arsenal design review will be ac-

Source: https://assist.dla.mil -- Downloaded: 202610-23T00:36Z
Check the source to verify that this is the current version before use.

complished, normally, within one month after receipt. All submitted designs shall reference the applicable five-digit code number contained in section 4 of this specification.

6.4 **Level B packaging and packing.** In the event the expected storage time of the relays is in excess of 180 days, the barrier bag shall be used as specified on the applicable drawing. Expected storage time shall be determined by the procuring agency.

6.5 **Check test for deterioration of relays (not applicable to new production).** The following test (see 6.5.1) is designed to prevent the loading of relays which have deteriorated, into a major ammunition item. The test shall be performed on relays from each lot which have been stored under normal conditions for more than two years, or under adverse conditions for any period of time. If the specification for the ammunition item into which the relays are loaded does not require that the check test be performed, the Contracting Officer should insert a provision for the performance of the check test in that contract. The Contracting Officer will arrange for the contractor to be reimbursed for expenses incurred in the performance of the check test for possible deterioration of the relays.

6.5.1 *Functioning.* The sampling plan for the test shall be in accordance with MIL–STD–105, using code letter L and an AQL of 0.40 percent. The test shall be performed in accordance with 4.4.2.

6.6 **Submission of results of contractor-conducted examinations and tests.** Unless otherwise specified by the Contracting Officer, the contractor shall forward requested records of examinations or tests to Commanding Officer, Picatinny Arsenal, ATTN: SMUPA–ND3.

Custodian:

Army—MU

Preparing activity:

Army—MU

Project No. 1375–A1056

Source: https://assist.dla.mil -- Downloaded: 202640-23T00:36Z
Check the source to verify that this is the current version before use.