INCH-POUND
MIL-R-87989
05 SEPTEMBER 1989

MILITARY SPECIFICATION

REVETMENT KIT, PREFABRICATED PIN TYPE. CORRUGATED STEEL PANELS

This specification is approved for use within the Department of the Air Force and is available for use by all Departments and Agencies of the Department of Defense.

1. SCOPE.

1.1 Scope. This specification defines two types of revetment kits consisting of prefabricated corrugated panel, connector pins, special tools, and sealing materials.

1.2 Classification. Revetment kits shall be of the following types:

Type A-1	Nominal Dimension 12' high x 7' wide x 252' long
Type B-1	Nominal Dimension 16' high x 7' wide x 252' long

2. APPLICABLE DOCUMENTS.

2.1 Government documents.

2.1.1 Standards. The following standards form a part of this specification to the extent specified herein. Unless otherwise specified, the issues of these documents shall be those listed in the issue of the Department of Defense Index of Specifications and Standards (DODISS) and supplement thereto, cited in the solicitation (see 6.2).

STANDARDS

Military

MIL-STD-129	Marking for Shipment and Storage
MIL-STD-130	Identification Marking of U.S. Military Property

(Unless otherwise indicated, copies of federal and military specifications, standards, and handbooks are available from the Naval Publications and Forms Center, (ATTN: NPODS), 5801 Tabor Avenue, Philadelphia, PA 19120-5099.)

2.2 Non-Government publications. The following document(s) form a part of this document to the extent specified herein. Unless otherwise specified, the issues of the documents which are DoD adopted are

Beneficial comments (recommendations, additions, deletions) and any pertinent data which may be of use in improving this document should be addressed to: WR-ALC/MMVRG, Robins AFB, GA 31098-5609 by using the self-addressed Standardization Document Improvement Proposal (DD Form 1426) appearing at the end of this document or by letter.

AMSC N/A

FSC 5410

DISTRIBUTION STATEMENT A: Approved for public release; distribution is unlimited.

Source: https://assist.dla.mil -- Downloaded: 202610-23T12:29Z
Check the source to verify that this is the current version before use.

those listed in the issue of the DODISS cited in the solicitation. Unless otherwise specified, the issues of documents not listed in the DODISS are the issues of the documents cited in the solicitation (see 6.2).

American Society for Testing and Materials (ASTM)

A27	Coatings, Carbon Steel Mild to Medium Strength General Application.
A108	Steel Bars, Carbon, Cold Finished, Standard Quality.
A153	Zinc Coating (Hot Dip) on Iron and Steel Hardware.
A525	Sheet, Steel, Zinc Coated (Galvanized) by the Hot Dip Process General Requirements.
A446	Sheet, Steel, Zinc Coated (Galvanized) by the Hot Dip Process Structural Quality.
D2103	Polyethylene Film and Sheeting.

(Application for copies should be addressed to the American Society for Testing and Materials, 1916 Race Street, Philadelphia PA 19103.)

2.3 Drawings.

Marwais Steel Company (Code Identification 27444)

1201A	16' High A/C Revetment Kit Type B-1

(Non-Government standards and other publications are normally available from the organizations that prepare or distribute the documents. These documents also may be available in or through libraries or other informational services.)

2.4 Order of precedence. In the event of a conflict between the text of this specification and the references cited herein (except for associated detail specifications, specification sheets or MS standards), the text of this specification shall take precedence. Nothing in this specification, however, shall supersede applicable laws and regulations unless a specific exemption has been obtained.

3.0 REQUIREMENTS.

3.1 Description. The revetment kits shall consist of the parts listed below. All parts shall be manufactured in accordance with Marwais Steel Company (Code Identification 27444) Drawing Number 1201A (three sheets).

3.1.1 Type A-1. The type A-1 kits shall consist of the following parts:

Item	Drawing/Part No.	Quantity
Side Panel	1201A/SP-123	168
Cross Panel	1201A/CP-73	216
End Cross Panel	1201A/CP-73E	48
End Brace Panel	1201A/BP-43	24
Connecting Pin	1201A/CP-3	634 *
Flaring Tool	1201A/FT	3
Polyethylene Film	1201A/No Number	300
Galv Stl Screen Wire Std Mesh	1201A/No Number	300

* Includes 10 percent excess quantity.

Source: https://assist.dla.mil -- Downloaded: 202610-23T12:29Z
Check the source to verify that this is the currentversion before use.

3.1.2 Type B-1. The Type B-1 kit shall consist of the following parts:

Item	Drawing/Part No.	Quantity
Side Panel	1201A/SP-123	168
Side Panel	1201A/SP-122	84
Cross Panel	1201A/CP-73	216
Cross Panel	1201A/CP-72	108
End Cross Panel	1201A/CP-73E	48
End Cross Panel	1201A/CP-72E	24
End Brace Panel	1201A/CP-43	24
End Brace Panel	1201A/CP-42	12
Connecting Pin	1201A/CP-3	643 *
Connecting Pin	1201A/CP-2	317 *
Flaring Tool	1201A/FT	3
Polyethylene Film	1201A/No Number	300
Galv Stl Screen Wire Std Mesh	1201A/No Number	300

* Includes 10 percent excess quantity.

3.1.3 Flaring Tool. Flaring tools are to be provided to reshape notches in cross and end brace panels that have been compressed by nesting in shipment. The tool head shall meet the dimensional requirements of the drawings and shall be made from either cast steel or formed and welded from 1/4" thick steel plate. The handle shall be either steel rod or 3/4" OD steel pipe.

3.1.4 Nonglare Treatment. (Reference General Note 4 drawing 1201A.) All galvanized steel parts shall be chemically treated to provide a phosphate coating that will result in a nonglare surface and permit field painting without additional surface treatment. Results shall be equal to Armco "paintgrip", Republic "paintloc", bonderizing or any commercial equivalent.

3.2 First Article. When specified in the contract or purchase order, a sample shall be subjected to first article inspection (see 4.2.1 and 6.3).

3.3 Recycled virgin and reclaimed materials. No recycled or reclaimed material shall be used in the manufacture of the revetment kits. As applicable, all material will meet the requirements of ASTM A27, A108, A153, A525, A446, and D2103.

3.4 Workmanship. The finished parts of the revetment kit will reflect the quality imparted by craftsmen in the process of manufacture. The overall degree of workmanship shall be determined by implementation of paragraph 4.5, Examination.

4.0 QUALITY ASSURANCE PROVISIONS.

4.1 Responsibility for inspection. Unless otherwise specified in the contract or purchase order, the contractor is responsible for the performance of all inspection requirements as specified herein. Except as otherwise specified in the contract or purchase order, the contractor may use his own or any other facilities suitable for the performance of the inspection requirements specified herein, unless disapproved by the Government. The Government reserves the right to perform any of the inspections set forth in the specification where such inspections are deemed necessary to assure supplies and services conform to prescribed requirements.

4.1.1 Responsibility for compliance. All items must meet all requirements of sections 3 and 5. The inspection set forth in this specification shall become a part of the contractor's overall inspection system or quality program. The absence of any inspection requirements in the specification shall not relieve the

Source: https://assist.dla.mil -- Downloaded: 202610-23T12:29Z
Check the source to verify that this is the current version before use.

contractor of the responsibility of assuring that all products or supplies submitted to the Government for acceptance comply with all requirements of the contract. Sampling in quality conformance does not authorize submission of known defective material, either indicated or actual, nor does it commit the Government to acceptance of defective material.

4.2 Classification of Inspection. The inspection requirements specified herein are classified as follows:

a. First Article inspection (see 4.2.1).
b. Production inspection (see 4.2.2).

4.2.1 First Article Test. The contractor shall present the materials for two 12 foot end section lengths of revetment of the appropriate height. Material certificates shall be presented to verify material content, galvanizing, and phosphate coating. The parts shall be measured to verify compliance with the drawings. These two 12 foot lengths shall then be erected to verify proper fit. These sections shall then be filled with available dirt, sand or gravel. Large chunks or stones shall not be used. The contractor shall be responsible for providing all material equipment and personnel to accomplish this task (Reference para 4.1). The revetment shall then be inspected for bulges, splits or deformation, and such occurrence shall be ground for rejection of the First Article. These sections may at the contractor's option be disassembled, cleaned and refurbished as necessary and delivered as part of a production lot.

4.2.2 Production Inspection. Production inspection shall be performed on the sample structural elements selected in accordance with 4.4. This inspection shall include the examination in 4.5.

4.3 Inspection Lot. A quantity of twenty-five or less of the same item listed in 3.1.1 or 3.1.2 shall be designated as an inspection lot.

4.4 Inspection Sample. In inspection lots of twenty-five or less, five items shall be selected at random for inspection in accordance with 4.5.

4.5 Examination. Each sample selected in accordance with 4.4 shall be examined for compliance with Section 3 of this Military Specification. Examination shall be conducted as specified in Table I.

TABLE I

CLASSIFICATION OF DEFECTS

Category	Major Defects
101	Design and construction not as specified, dimensions not as shown on drawings.
102	Material not as specified or damaged or defective, affecting serviceability and reliability.
103	Elements not free from kinks or sharp bends, holes not accurately punched or drilled or free from burrs, components missing.
104	Items not finished as specified.
105	Marking not as specified per MIL-STD-129.
106	Phosphate coating not as specified.
107	Parts identification not as specified per MIL-STD-130.
	Minor Defects
108	Other visual defects.

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T12:29Z
Check the source to verify that this is the current version before use.

4.6 Production Inspection Item Failure. Failure of one selected production test item shall immediately stop any further production quantities. Production quantities shall not be produced until the failure deficiency is identified and corrected, and additional preproduction inspection performed to verify the correction. Corrected deficiencies shall be reviewed and approved by the procuring activity. All production items in an inspection lot that experiences the failure of one selected test item shall be subjected to production inspection.

4.7 Packing Inspection. The preservation, packing and marking of the revetment kit shall be inspected to determine compliance with the requirements of Section 5 of this purchase description.

5.0 PACKAGING.

5.1 Preservation and Packaging. Preservation and packaging shall be in accordance with the terms of the contract.

6.0 NOTES.

(This section contains information of a general or explanatory nature that may be helpful, but is not mandatory.)

6.1 Intended Use. Modular type corrugated steel bin revetments kits provide a means of constructing vertical walls of earth to the desired height and thickness for protection of personnel and combat equipment from enemy attack. The galvanized screen wire is a backup material to the polyethylene film in those instances where jet engine exhaust destroys or severely damages the film.

6.2 Ordering data.

a. Title, number and date of this specification.
b. Level of preservation and packaging, and level of packing required (see 5.1).
c. Specify type A-1 or Type B-1 revetment kit.

6.3 Inspection of First Article. First article inspection shall be performed as stated in paragraph 4.2.1.

6.4 Drawing changes. In the event it becomes necessary to change the drawings (see 3.1.1) in order to achieve the performance requirements of this specification, the contractor will immediately notify the contracting officer with recommendations for drawing changes to obtain the required performance. Extensive or detailed drawing changes are preferred in supplemental drawing form. The extent approved, such changes shall be processed in accordance with the provisions of the changes clause of the contractor.

6.5 Consideration of data requirements. The following data requirements should be considered when this specification is applied on a contract. The applicable Data Item Descriptions (DID's) should be reviewed in conjunction with the specific acquisition to ensure that only essential data are requested/provided and that the DID's are tailored to reflect the requirements of the specific acquisition. To ensure correct contractual application of the data requirements, a Contract Data Requirements List (DD Form 1423) must be prepared to obtain the data, except where DOD FAR Supplement 27.475-1 exempts the requirement for a DD Form 1423.

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T12:29Z
Check the source to verify that this is the current version before use.

6.6 Subject term (key word) listing.

Corrugated steel
Prefabricated
Revetment kit

Custodian:
Air Force - 99

Preparing Activity:
Air Force - 84

Project Number:
5410-F327

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T12:29Z
Check the source to verify that this is the current version before use.

(TO DETACH THIS FORM, CUT ALONG THIS LINE.)

STANDARDIZATION DOCUMENT IMPROVEMENT PROPOSAL

(See Instructions – Reverse Side)

1. DOCUMENT NUMBER	2. DOCUMENT TITLE

3a. NAME OF SUBMITTING ORGANIZATION	4. TYPE OF ORGANIZATION *(Mark one)*
	☐ VENDOR
b. ADDRESS *(Street, City, State, ZIP Code)*	☐ USER
	☐ MANUFACTURER
	☐ OTHER *(Specify)*: _____

5. PROBLEM AREAS

a. Paragraph Number and Wording:

b. Recommended Wording:

c. Reason/Rationale for Recommendation:

6. REMARKS

7a. NAME OF SUBMITTER *(Last, First, MI)* – Optional	b. WORK TELEPHONE NUMBER *(Include Area Code)* – Optional
c. MAILING ADDRESS *(Street, City, State, ZIP Code)* – Optional	8. DATE OF SUBMISSION *(YYMMDD)*

DD FORM 82 MAR 1426

PREVIOUS EDITION IS OBSOLETE.

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T12:29Z
Check the source to verify that this is the current version before use.

INSTRUCTIONS: In a continuing effort to make our standardization documents better, the DoD provides this form for use in submitting comments and suggestions for improvements. All users of military standardization documents are invited to provide suggestions. This form may be detached, folded along the lines indicated, taped along the loose edge *(DO NOT STAPLE)*, and mailed. In block 5, be as specific as possible about particular problem areas such as wording which required interpretation, was too rigid, restrictive, loose, ambiguous, or was incompatible, and give proposed wording changes which would alleviate the problems. Enter in block 6 any remarks not related to a specific paragraph of the document. If block 7 is filled out, an acknowledgement will be mailed to you within 30 days to let you know that your comments were received and are being considered.

NOTE: This form may not be used to request copies of documents, nor to request waivers, deviations, or clarification of specification requirements on current contracts. Comments submitted on this form do not constitute or imply authorization to waive any portion of the referenced document*(s)* or to amend contractual requirements.

☆ U.S. Government Printing Office: 1987—386-870/8894

(Fold along this line)

(Fold along this line)

NO POSTAGE NECESSARY IF MAILED IN THE UNITED STATES

OFFICIAL BUSINESS
PENALTY FOR PRIVATE USE $300

BUSINESS REPLY MAIL
FIRST CLASS PERMIT NO. 72236 WASH DC

POSTAGE WILL BE PAID BY HQ U.S. AIR FORCE

WR_ALC/MMVRG
ROBINS AFB GA 31098-5609

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T12:29Z
Check the source to verify that this is the current version before use.