NOT MEASUREMENT SENSITIVE

NOTICE OF CHANGE

MIL-STD-1465A (AR)
NOTICE 1
5 December 1988

MILITARY STANDARD
CONFIGURATION MANAGEMENT OF ARMAMENTS, MUNITIONS AND CHEMICAL PRODUCTION BASE MODERNIZATION

TO ALL HOLDERS OF MIL-STD-1465A (AR):

1. THE FOLLOWING PAGES OF MIL-STD-1465A (AR) HAVE BEEN REVISED AND SUPERSEDE THE PAGES LISTED:

NEW PAGE	DATE	SUPERSEDED PAGE	DATE
7	4 AUGUST 1987	7	REPRINTED WITHOUT CHANGE
8	5 DECEMBER 1988	8	4 AUGUST 1987
9	5 DECEMBER 1988	9	4 AUGUST 1987
10	5 DECEMBER 1988	10	4 AUGUST 1987
11	5 DECEMBER 1988	11	4 AUGUST 1987
12	5 DECEMBER 1988	12	4 AUGUST 1987
19	4 AUGUST 1987	19	REPRINTED WITHOUT CHANGE
20	5 DECEMBER 1988	20	4 AUGUST 1987

2. RETAIN THIS NOTICE AND INSERT BEFORE TABLE OF CONTENTS:

3. Holders of MIL-STD-1465A (AR) will verify that page changes and additions indicated above have been entered. This notice page will be retained as a check sheet. This issuance, together with appended pages, is a separate publication. Each notice is to be retained by stocking points until the military standard is completely revised or cancelled.

Custodian:
Army - AR

Preparing Activity:
Army - AR

Review Activities:
Army - Al, CE

(Project CMAN-A005)

AMSC A4161

AREA CMAN

DISTRIBUTION STATEMENT A. Approved for public release; distribution is unlimited.

Source: https://assist.dla.mil -- Downloaded: 2026-10-24T00:26Z
Check the source to verify that this is the current version before use.

c. Expeditious decision by the CCB or appropriate management level where necessary.

d. Timely incorporation of approved change.

e. Timely visibility of change status of management at all levels.

f. Timely revision of affected documentation to reflect current configuration.

4.2.5 Changes. Changes to the baseline configuration, once established, will be minimized and will generally be made only in the interest of:

a. Correction of deficiencies or resolution of conflicts as required to achieve operational requirements

b. Significant improvement in operation or performance

c. Incorporation of advances in the state-of-the-art

d. Compliance with revisions in environmental standards (OSHA)

e. Safety

f. VE

g. Cost Reduction/Cost Avoidance

5: DETAILED REQUIREMENTS

5.1 Configuration Identification.

5.1.1 General

5.1.1.1 Project Development. In order to determine the necessary reference points for configuration identification during the life cycle of a project, it is necessary to understand the overall development phases of a standard project. Figure 1 depicts the development for a typical project which contains both equipment and facilities construction work. Each of these phases will be further defined and amplified in this section.

5.1.1.2 Project Baselines. Configuration identification will be established by formal project baselines representing significant points in project development. These baselines are identified below as to specific equipment and facilities application. A sequential flow of project baselines is outlined in Figure 2.

5.1.1.3 Facility Identification. Configuration identification for facilities will consist of the facility design criteria documentation for each project, concept design, final design, and the operational data to be incorporated into the operational data package. The funding program documents will not be controlled by formal configuration management. The early preparation of comprehensive design criteria documentation to identify the requirements of the using agency is one of the primary objectives of this MIL-STD. The CE will assist and participate in design criteria preparation to the extent authorized by the PBMA.

Source: https://assist.dla.mil -- Downloaded: 2026-10-24T00:26Z
Check the source to verify that this is the current version before use.

5.1.1.4 Equipment Identification. Configuration identification for equipment will consist of the equipment pilot line or prototype documentation for each project, as applicable, the equipment functional criteria, the equipment TDP, and the operational data to be incorporated into the operational data package. The early preparation of complete and comprehensive functional criteria documentation is essential for defining performance requirements, describing processes, and establishing design requirements of the using agency. It is highly desirable that the design of process equipment be accomplished well in advance of the development of facilities design criteria; however, it is usually only possible in those cases where the equipment has been developed and proven under a MMTE program and drawings and specifications suitable for procurement are available. In those cases where the suitable drawings, and specifications are not available, the design effort for development of functional criteria must be limited to a definition of characteristics, e.g., equipment dimensions, RAM characteristics, nominal weight, clear aisle and overhead, type and capacity of utilities available or to be furnished, etc. This definition of characteristics is necessary to permit development of facility design criteria, at the least possible cost, by avoiding under or over-design of building and utilities.

5.1.2 Procedures for Facility Identification.

5.1.2.1 Criteria Baseline. The Project Development Brochure, constituting the Criteria Baseline, will normally be prepared in response to direction from the PBMA. The procedures and format will follow the guidance contained in TM 5-800-3. Interface requirements of the using agency such as clear height, aisle width, utility services required, and mounting details for equipment to be installed will be clearly identified. For utility services to equipment, the locations of the interface points are to be identified as well as the character and quantity of the services. Interfaces not identified in the design criteria document but to be furnished with the equipment vendor data shall be stated. Because the Project Development Brochure contains the actual requirements of the using agency, it will be controlled and maintained until project completion. The Project Development Brochure will be the point of reference in the evaluation of criteria change ECP when established requirements are affected (see 6.2).

5.1.2.2 Concept Baseline. The concept design for facilities will be prepared by the CE upon receipt of a directive from OCE. The procedures and format will follow normal CE practice for preparation of concept documents. Concept design will be prepared in sufficient detail to permit adequate review by the using agency to verify the design approach and to permit the preparation of a firm cost estimate by the CE to be utilized by AMCCOM for programming the cost of the project. The concept baseline is superseded upon approval of the design baseline. Data for the Concept Baseline will be obtained by CE utilizing their procedures. CE data acquisition procedures are not addressed in this MIL-STD.

5.1.2.3 Design Baseline. The final design for facilities will be prepared by the CE upon receipt of a directive from OCE. The procedures and format will follow normal CE practice. The design baseline is automatically established upon award of the construction contract. For configuration management record purposes, a baseline ECP will be prepared by USAEDH indicating that the design has been baselined as of the last amendment to the construction bid documents. Participating agencies who maintain a set of the design documentation will be on the distribution list for the IFB and amendments

Source: https://assist.dla.mil -- Downloaded: 2026-10-24T00:26Z
Check the source to verify that this is the current version before use.

as they are issued to the bidders; therefore, the design documentation will not be reproduced and distributed again with the baseline ECP. Data for the Design Baseline will be obtained by CE utilizing their procedures. CE data acquisition procedures are not addressed in this MIL-STD.

5.1.2.4 Exception to Standard Facility Identification. Separate instructions will be individually issued by PBMA for projects which, because of contract applications, are not covered by standard identification provisions as outlined in this standard. These would include "two-step", and "cost-plus-fixed-fee" type contracts administered by the CE.

5.1.3 Procedures for Process Equipment Identification.

5.1.3.1 Process Baseline. The TDP for a pilot line or equipment prototype normally will be developed by ARDEC or another engineering activity as a result of a MMTE project. The process baseline will be established only for those projects for which a pilot line or equipment prototype has been developed. The data for a process baseline is obtained by ARDEC or another engineering activity as part of the MMTE effort and is not a data requirement to be obtained under provisions of this standard.

5.1.3.2 Functional Baseline. The equipment functional criteria specification, constituting the Functional Baseline, will be prepared in response to direction from the PBMA. When the project also involves a facility effort, the functional baseline will be established as early as possible, but not later than the approval of the criteria baseline. The equipment functional criteria specification for a project will consist of a functional layout of the process system describing the physical and functional interface, a narrative description of the processes, a list of equipment CIs, and a complete list of references to descriptive technical documentation. The CIs will be identified as separate entities, each physically separable from the system and capable of being procured and installed as a separate CI. The equipment functional criteria)specification preparation will be based on knowledge of production requirements and of present and newly available process machinery designs. The equipment functional criteria specification will define the necessary design and performance of the process equipment. Preparation of the equipment functional criteria specification is covered in Appendix A. The PBMA will prepare a functional baseline ECP for submittal to the PBMA CCB for approval when criteria are complete. The equipment functional criteria specification will be maintained in a current status by ECP action until procurement and acceptance of the equipment have been completed (see 6.2).

5.1.3.3 Technical Baseline. The equipment TDP specification, constituting the Technical Baseline, will be prepared in response to direction from the PBMA. The Technical Baseline will be comprised of a complete equipment TDP (see direction for TDP). Preparation of the equipment TDP specification for individual CIs is covered in Appendix B. The complete TDP specification for a project will consist of a cover sheet as shown in Figure 8; a TDP Listing (TDPL), to include title, specification number, and date for each CI; and the individual TDP specifications for each listed CI. In exception cases, a non specification type TDP may be prepared in contractor or other acceptable format to comprise the Technical Baseline. The PBMA will prepare a Technical Baseline ECP for submittal to the PBMA CCB. The Technical Baseline will be established as a prerequisite

Source: https://assist.dla.mil -- Downloaded: 2026-10-24T00:26Z
Check the source to verify that this is the current version before use.

to preparation of the equipment procurement documentation. When the project also involves a facility effort, the Technical Baseline will be established prior to the CE 90 Percent Design Review Conference. The Technical Baseline will be maintained in a current status by ECP action until project completion (see 6.2).

5.1.4 Procedures for Project Documentation.

5.1.4.1 Operational Baseline. The Operational Baseline listing, constituting the operational baseline, identifies the documentation procured/developed during project execution that provided the user with the information necessary for identification and effective O&M capability. Typical examples of data items that may be listed are provided below for information only (see 6.2).

a. "As built" facility drawings

b. Equipment drawings (production and facility)

c. TDP

d. Specifications

e. Installation drawings

f. Line layout drawings

g. Manuals (operational, maintenance, training, layaway, reactivation, trouble shooting, supply, safety)

h. Equipment operating procedures

i. Overall operating procedures

j. Test procedures

k. Tooling lists

l. Spare/repair parts lists

m. Provisioning guides

n. Description of manufacture (DOM)

o. Critical process description

p. Master equipment list

Supersedes page 10 dated 4 August 1987

Source: https://assist.dla.mil -- Downloaded: 2026-10-24T00:26Z
Check the source to verify that this is the current version before use.

5.2 Configuration Control.

5.2.1 General.

5.2.1.1 Configuration Control Boards. Configuration control of established baselines will be exercised through formally established CCBs. The PBMA CCB will control changes to projects for both facilities and equipment. Field level CCBs (FCCBs) will be established at designated locations by direction of the PBMA Commander only.

5.2.1.2 Pre-CCB Coordination. Pre-CCB coordination of ECPs is encouraged, particularly where the impact is major or the proposed solution to the problem is in doubt. The use of preliminary ECPS for coordination is encouraged where preparation of the formal ECP is being delayed for some valid reason. Urgent ECPs with less than normal review periods may also be utilized where the reduction in processing time is required to minimize schedule impact. If necessary and with the consent of the CCB Chairman, urgent ECPs may be approved by the CCB prior to preparation of the formal impact sheet. The objective in all cases is to allow adequate time to review the ECP and to obtain the CCB decision in a timely manner as required to minimize schedule impact. Pre-CCB coordination of simple ECPs is not mandatory and in many cases would only delay the final CCB decision. Lower level working groups will not be established on a permanent basis for pre-CCB coordination. Where possible, objections or planned nonconcurrences by CCB members shall be resolved prior to the CCB meeting. A reasonable amount of across-the-table discussion at the CCB meeting is encouraged; however, the CCB member representing each agency must be prepared to discuss each ECP and must have sufficient authority to commit his agency in such discussions. Any agency planning to concur in an ECP shall advise the originator of the ECP and the Executive Secretary of the CCB at least five working days prior to the meeting. All nonconcurrences by members at a CCB meeting must be supported in writing to assist in evaluation and decision by the PBMA Commander in the event of a split board.

5.2.1.3 ECP Preparation and Submissions. ECPs may be prepared by any participating agency desiring a change to baselined documentation. ECPs will not be prepared to document no-cost editorial type corrections. ECPs initiated by commercial contractors should be submitted through the PCO to the Executive Secretary of the PBMA CCB. GOCO contractors shall prepare ECPs for submission and signature by the COR staff. The desired change is to be shown in general form allowing final design latitude. IF the ECP is approved, the final design to implement it is the responsibility of the design agency which will design directly against the approved ECP, without the necessity of preparing another ECP as authority to revise the design (see 6.2).

5.2.1.4 Classified Enclosures. Classified information will not be included in an ECP. Classified documents will be transmitted separately through normal security channels and referenced in the ECP.

5.2.2 PBM CCB.

5.2.2.1 CCB Board Members. The PBMA CCB will be located at PBMA, Picatinny Arsenal, NJ and will provide the Executive Secretary to perform the staff work associated with the CCB and a nonvoting Chairman to conduct the meetings. The PBMA CCB shall be comprised of members from the following agencies:

Source: https://assist.dla.mil -- Downloaded: 2026-10-24T00:26Z
Check the source to verify that this is the current version before use.

a. PBMA

b. ARDEC

c. IPIPMO

d. I&SA

e. USAEDH

f. Other participating agencies identified by the PBMA

The above list is general in scope and this standard will not be revised to maintain a specific list. Ad hoc members may be appointed by the Chairman to review any ECP and each will have a vote concerning those ECPs for which they have been designated to participate at the meeting. Technical advisors may accompany any board member and may be called upon for advice and information, but will not have a vote concerning any ECP.

5.2.2.2 Delegation of Authority. The Chairman, acting with the authority of the PBMA Commander, may approve individual ECPs with estimated dollar impact not to exceed an increase of $500,000, provided that all members are in agreement and that this dollar impact does not exceed the available funding for the individual project during the execution phase. ECPs will not be divided to circumvent ceiling restrictions and, the Chairman shall consolidate related ECPs, if appropriate, to insure that the CCB's authority is not exceeded. No dollar limitation will be placed upon changes to be made prior to the execution phase nor to cost decreases during any phase of the project.

5.2.2.3 Resolution. ECPs will be referred to the PBMA Commander for resolution when:

a. The estimated dollar impact exceeds the PBMA CCB authority.

b. The vote results in a split board. The board is considered to be split when an unanimous decision is not reached.

5.2.3 Other CCBs. FCCBs or special CCBs will be the only subordinate CCBs established. An FCCB or a special CCB may be established at the discretion of the PBMA Commander. A charter will be issued to each CCB when it is established.

5.2.4 ECP Preparation.

5.2.4.1 Examples. DA Form 5198-R (Production Base Engineering Change Proposal) (ECP) will be utilized as the ECP form for both baselining and controlling changes to equipment and facilities. DA Form 5198-R, DA Form 5199-R (Production Base Modernization Program Engineering Change Proposal (ECP) Continuation Sheet), DA Form 5201-R (Configuration Control Board Engineering Change Proposal (ECP) Concurrence Sheet) may all be locally reproduced on 8 1/2 by 11 inch paper (see 6.2).

5.2.4.2 ECP Numbering System.

Source: https://assist.dla.mil -- Downloaded: 2026-10-24T00:26Z
Check the source to verify that this is the current version before use.

5.2.4.3.14 Block 5a - Document Number and Title. Enter the number of each document affected by the proposed ECP. Facility drawings will be listed by file number. Enter NA for baseline ECP.

5.2.4.3.15 Block 5b - Current Revision. Insert the current revision symbol of the documentation to be changed.

5.2.4.3.16 Block 5c - Sheet/Page Numbers. Insert the sheet or page numbers primarily affected by the ECP.

5.2.4.3.17 Block 6a - Related ECP. Enter all ECPs (approved/pending) which relate to the proposed ECP.

5.2.4.3.18 Block 6b. Enter budget code.

5.2.4.3.19 Block 7a - Originator/Design Engineer. Enter the name, organization and the phone number of the individual who will be prepared to answer questions concerning the ECP.

5.2.4.3.20 Block 7b - Submitted By. The signature of an authorized representative of the agency initiating the ECP. All ECPs originated by the PBMA will be submitted by the Executive Secretary of the CCB.

5.2.5 ECP Processing Prior to CCB Action.

5.2.5.1 Distribution of ECPs. See Figure for flow diagram of a typical ECP. ECPs will be prepared on standard size formats utilizing black ink on white papre. They must be legible and capable of being satisfactorily microfilmed and reproduced. Attachments to ECPs must also be of the same quality, and sizes over 8 1/2" X 14" may be prepared on translucent reproducible stock. To reduce processing time, the originating agency makes the initial direct distribution of the original and one copy to the Executive Secretary and two copies to each participating agency. Participating agencies will normally include all board members, the affected ammunition plant, and CE district as applicable. A sample transmittal form, no letter required, will be used to distribute ECPs. The transmittal must, however, indicate the entire distribution that has been made other than in-house copies in the originating agency. The distribution list for each CCB will be controlled by the Executive Secretary of that CCB.

5.2.5.2 ECP Review Board. The review period for each change ECP will depend upon the complexity of the proposed change and whether the ECP has been assigned a routine or an urgent priority. In general, a maximum of five working days review period after receipt of the ECP shall be allowed for urgent ECPs. Approximately 14 calendar days shall be allowed for routine ECPs. This may be varied as directed by the CCB Chairman.

5.2.5.3 ECP Review and Coordination. See paragraph 5.2.1 for discussion of ECP review and coordination.

Source: https://assist.dla.mil -- Downloaded: 2026-10-24T00:26Z
Check the source to verify that this is the current version before use.

5.2.5.4 Changes to ECPs. Any changes to an ECP after it has once been distributed outside the originating agency requires a revision or a correction to the ECP. Where the revision or correction is identified during the CCB meeting and noted in Block 4 of the concurrence sheet, it is not necessary to rewrite the ECP itself.

5.2.6 ECP Impact Sheet.

5.2.6.1 Impact Sheet Form. DA Form 5200-R (Production Base Engineering Change Proposal, Impact Sheet) will be prepared during the review period by each agency impacted by a proposed change ECP. DA Form 5200-R will be locally reproduced on 8 1/2" X 11" paper. Impact sheets will conform to the same quality requirements as ECPs. Completed impact sheets for routine ECPs shall be furnished to the Executive Secretary prior to the CCB meeting. If unable to complete the impact sheet for urgent changes prior to the meeting, the CCB member representing the impact agency shall be prepared to furnish a ROM estimate so that the members will know the general magnitude of the impact which they are considering. In this case, the impact sheet will be furnished at a subsequent meeting. If the impact is substantially above the ROM estimate, the Chairman may elect to reconsider the ECP if it has not already been implemented. Addition of the impact sheet does not in itself require a change in the revision or the correction block of the ECP Form.

5.2.6.2 Preparation of ECP Impact Sheet. The following instructions are keyed to the block number on the form:

a. Block 1a - ECP Number

b. Block 1b - Revision

c. Blcok 1c - Correction

d. Block 1d - Title

e. Block 2a - Project Number and site affected

f. Block 2b - SP (Subproject)

The instructions for completion of these blocks are the same as those for the ECP Form.

5.2.6.2.1 Block 2c - Design Cost. Enter estimated cost of design effort required to incorporate change in design documentation.

5.2.6.2.2 Block 2d - Contract Cost. Enter estimated modification cost for projects under contract or which will be under contract when the ECP is implemented. Enter estimated change to the bid for projects where the ECP can be incorporated prior to contract award.

5.2.6.2.3 Block 2e - Othe Cost. Enter estimated cost, excluding design, for reproduction, negotiation, inspection, and overhead associated with incorporating the approved ECP into the contract.

Supersedes page 20 dated 4 August 1987

Source: https://assist.dla.mil -- Downloaded: 2026-10-24T00:26Z
Check the source to verify that this is the current version before use.