MILITARY SPECIFICATION
SHOP EQUIPMENT, CONTACT MAINTENANCE TRUCK-MOUNTED

This limited coordination Military Specification has been prepared by the US Army Armament, Munitions and Chemical Command based upon currently available technical information but it has not been approved for promulgation as a coordinated revision of MIL-S-45855. It is subject to modification. However, pending its promulgation as a coordinated military specification, it may be used in procurement.

1 SCOPE

* 1.1 Scope. This specification covers three types of truck-mounted, contact maintenance shops.

* 1.2 Classification. This specification covers truck-mounted, contact maintenance shops of the following types.

Type I - Consist of Truck chassis and body per drawing TA13217E8300.

Type II - Consist of Type I loaded with tools and equipment per Set Components List SC4940-95-CL-XXX.

Type III - Consist of Type I loaded with tools and equipment per Set Components List SC4940-95-CL-YYY.

2 APPLICABLE DOCUMENTS

* 2.1 Government documents.

* 2.1.1 Specifications, standards, and handbooks. Unless otherwise specified, the following specifications, standards, and handbooks of the issue listed in that issue of the Department of Defense Index of Specifications and Standards (DoDISS) specified in the solicitation form a part of this specification to the extent specified herein.

Beneficial comments (recommendations, additions, deletions) and any pertinent data which may be of use in improving this document should be addressed to: Commander, US Army Armament, Munitions and Chemical Command, ATTN: DRSMC-LEE-S (R), Rock Island, IL 61299-6000 by using the self-addressed Standardization Document Improvement Proposal (DD Form 1426) appearing at the end of this document or by letter.

AMSC N/A FSC 4940

DISTRIBUTION STATEMENT A. Approved for public release; distribution is unlimited.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T04:00Z
Check the source to verify that this is the current version before use.

SPECIFICATIONS

FEDERAL

O-A-548 - Antifreeze, Ethylene Gylcol, Inhibited
W-C-375 - Circuit Breaker, Molded Case; Branch-Circuit and Service
TT-P-664 - Primer Coating, Synthetic, Rust-Inhibiting, Lacquer-Resisting
VV-B-680 - Brake Fluid, Automotive
PPP-B-566 - Boxes, Folding, Paperboard
PPP-B-636 - Boxes, Shipping, Fiberboard
PPP-P-40 - Packaging and Packing of Hand Tools
PPP-T-60 - Tape, Preservation and Sealing

MILITARY

MIL-P-116 - Preservation-Packaging, Methods of
MIL-B-121 - Barrier Material, Greaseproofed, Waterproofed, Flexible
MIL-T-152 - Treatment, Moisture- and Fungus-Resistant of Communications, Electronic, and Associated Electrical Equipment
MIL-P-514 - Plates, Identification, Instruction and Marking, Blank
MIL-L-2104 - Lubricating Oil, Internal Combustion Engine, Tactical Service
MIL-L-2105 - Lubricating Oil, Gear, Multipurpose
MIL-G-10924 - Grease, Automotive and Artillery
MIL-A-11755 - Antifreeze, Arctic-Type
MIL-E-16298 - Electric Machines Having Rotating Parts and Associated Repair Parts: Packaging of
MIL-E-17555 - Electronic and Electrical Equipment, Accessories and Repair Parts: Packaging and Packing of
MIL-G-23827 - Grease, Aircraft and Instrument, Gear and Actuator Screw
MIL-T-45542 - Tool Sets, Shop Sets and Kits (Hardware, Installation, Modification and Tool) Both Common and Special: Packaging and Packing of
MIL-L-46167 - Lubricating Oil, Internal Combustion Engine, Arctic
MIL-W-45562 - Welding and Soldering Equipment, Supplies and Accessories, Packaging of

STANDARDS

MILITARY

MIL-STD-129 - Marking for Shipment and Storage
MIL-STD-130 - Identification Marking of US Military Property
MIL-STD-209 - Lifting and tiedown provisions
MIL-STD-281 - Automobiles, Trucks, Truck-Tractors, Trailers and Trailer Dollies; Preservation and Packaging of
MIL-STD-1474 - Noise Limits for Army Materiel

* 2.1.2 Other Government documents, drawings, and publications. The following other Government documents, drawings, and publications form a part of this specification to the extent specified herein.

PURCHASE DESCRIPTIONS

AT

ATPD 2074 Performance Specification - Military Commercial Truck

DRAWINGS

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T04:00Z
Check the source to verify that this is the current version before use.

AL

11021251 - Finish Methods
TA13217E8300 - Shop Equipment, Contact Maintenance, Truck-Mounted

(Copies of specifications, standards, handbooks, drawings, and publications required by manufacturers in connection with specific acquisition functions should be obtained from the contracting activity or as directed by the contracting officer.)

* 2.2 Other publications. The following document(s) form a part of this specification to the extent specified herein. The issues of the documents which are indicated as DoD adopted shall be the issue listed in the current DoDISS and the supplement thereto if applicable.

AMERICAN NATIONAL STANDARDS INSTITUTE (ANSI)

ANSI C73 - Dimensions of Attachments Plugs and Receptacles

(Application for copies should be addressed to the American National Standards Institute, 1430 Broadway, New York, NY 10018.)

AMERICAN SOCIETY FOR TESTING AND MATERIALS (ASTM)

ASTM D3951-82 - Standard Practice for Commercial Packaging

(Application for copies should be addressed to the American Society for Testing and Materials, 1916 Race Street, Philadelphia, PA 19103.)

(Industry association specifications and standards are generally available for reference from libraries. They are also distributed among technical groups and using Federal agencies.)

* 2.3 Order of precedence. In the event of a conflict between the text of this specification and the references cited herein, the text of this specification shall take precedence.

3 REQUIREMENTS

* 3.1 First article. When specified (see 6.2), the contractor shall furnish one complete shop for first article inspection. The first article may be either a preproduction model or an initial production item which conforms to the requirements of this specification. In either case, the approved first article and the production items shall be identical and in accordance with the terms of the contract. Approval of the first article shall not relieve the contractor of the responsibility to furnish equipment in accordance with the requirements of this specification. Any changes or deviations by the contractor of the production shop from the approved first article during production shall be subject to the approval of the contracting officer.

3.2 Description. This specification covers three types of Shop Equipment Contact Maintenance vehicles identified as follows:

3.2.1 Type I. The Type I Shop Equipment Contact Maintenance Vehicle Truck Mounted shall be as specified herein and shall be in accordance with TA13217E8300 equipped with a power take off (PTO) which drives an ac brushless alternator having a maximum output of 15KW thru a control panel for providing 230 VAC 3 phase and 115 VAC single phase 60 Hz power to appropriate installed outlets/receptacles.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T04:00Z
Check the source to verify that this is the current version before use.

3.2.2 Type II. The Type II Shop Equipment Contact Maintenance Vehicle Truck Mounted shall consist of the Type I vehicle loaded with tools and equipment specified in the Set Components List compiled from SC4940-95-CL-XXX.

3.2.3 Type III. The Type III Shop Equipment Contact Maintenance Vehicle Truck Mounted shall consist of the Type I vehicle loaded with tools and equipment specified in the Set Components List compiled from SC4940-95-CL-YYY.

3.2.4 Drawings. The drawings forming a part of this specification are end product drawings. No deviation from the prescribed dimensions or tolerances is permissible without prior approval of the contracting officer. Where tolerances could cumulatively result in incorrect fits, the supplier shall provide tolerances within those prescribed on the drawings to insure correct fit, assembly, and operation of the shop equipment. Any data (e.g., shop drawings, layouts, flow sheets, processing procedures, etc.) prepared by the supplier or obtained from a vendor to support fabrication and manufacture of the production item shall be made available, upon request, for inspection by the contracting officer or his designated representative.

3.3 Initial production. When specified (see 6.2), the supplier shall furnish to the Government one or more shops for inspection as specified in 4.4.

3.4 Material. Material shall be as specified herein and as shown on the applicable drawings. Materials not specified shall be selected by the supplier and shall be subject to all provisions of this specification.

3.5 Safety. All exposed parts which are subject to high oeprating temperatures or which are energized electrically shall be insulated, fully enclosed, or guarded. All moving parts which are hazardous to operating or maintenance personnel shall be fully enclosed or guarded. Protective devices shall not impair the operating functions.

3.6 Roadability. When loaded with the tools and equipment specified herein, the Type II/Type III loaded to 9,000 pounds gross vehicle weight (GVW), the shop shall withstand driving on paved roads, unimproved roads, cross-country trails, a chatter course and a diagonal ditch course. During or following driving, there shall be no damage to or displacement of any component, accessory, part, or tool installed in or on the shop and no evidence of defective welded, bolted, or riveted connections on the shop.

3.7 Truck Chassis. The Government-furnished 1 1/4 ton, 4 X 4 truck chassis shall be per ATPD 2074 (see 6.2) and shall be modified by the supplier in accordance with Top Assembly TA13217E8300 and as specified herein.

3.7.1 Shop weight. Unless otherwise specified (see 6.2), the GVW of the loaded shop with all tools and equipment shall not be greater than 9,000 pounds, nominal.

3.7.2 Air transportability. The fully loaded shop set (Type II/Type III) shall be capable of being loaded aboard and transported in a C-130 aircraft.

3.7.3 Lifting and tie down provisions. Lifting and tie down provisions for the fully loaded shop set (Type II/Type III) are required in accordance with MIL-STD-209.

3.8 Body. The supplier shall fabricate and install the body on the chassis in accordance with the applicable drawings. The supplier shall furnish all items of equipment including the tools and equipment specified for Type II and III Shops.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T04:00Z
Check the source to verify that this is the current version before use.

3.8.1 Electrical power system. The supplier shall furnish and install the entire ac electrical power system. The system shall be module configured consisting of control panel and related controls. The module(s) shall be so designed as to provide accessibility for scheduled routine and minor unscheduled maintenance without complete removal. Capability of complete removal and replacement of module shall be provided.

3.8.1.1 Control panel. The control panel shall be of a modular design and contain all controls and instruments (voltmeter, ammeter, frequency meter) necessary for the operation of the system. Controls shall be identified and functions indicated by silk screening on the control panel or by use of plates. The back of the control panel shall be accessible for circuit checks and component repair. A method of ventilation shall be provided to permit rapid dissipation of heat generated in the electrical circuitry.

3.8.1.2 Receptables. Four 15 ampere, 120 volt 2 poles, 3 wire receptacles conforming to the American National Standards Institute (ANSI) Standard C73 shall be furnished and installed in the control panel. The receptacles shall be wired in pairs and each pair shall be protected with a circuit breaker. One pair of receptacles shall conform to ANSI Designation C73.11 and one pair shall conform to C73.42. The receptacles shall be identified to indicate the voltage supplied.

3.8.1.3 Circuit breakers. Three circuit breakers of 15 ampere capacity, one circuit breaker of 30 ampere capacity and one circuit breaker of 40 ampere capacity shall be provided. The circuit breakers shall conform to W-C-375, Class 1a, single unit construction. Two 15 ampere circuit breakers shall be wired to protect the control panel receptacles as specified in 3.8.1.2 and one 15 ampere and the 30 ampere circuit breaker shall be wired to a terminal strip on the rear of the control panel. The 40 amp circuit breaker shall be wired to protect the maximum capacity of the ac generator.

3.8.1.4 Grounding. A 1/4-20 threaded ground stud shall be provided on the front of the control panel as a terminal for ground leads from the control panel mounted equipment. An 8 foot ground rod shall be provided with all Type I vehicles.

3.8.2 Electrical system. The 12 volt dc electrical system shall be in accordance with the applicable drawings and as specified herein for all vehicular lighting and towed load interconnections.

3.9 Tools and equipment. The tools and equipment for the Type II and III shops shall be located as specified, anchored or stored to prevent movement during transit. Tie down devices shall be designed for a general tool or equipment configuration to allow interchange of like items from different manufacturing sources. Wherever possible, items shall be grouped together by function.

3.10 Rough handling. The shop(s) (Type II and III) shall withstand stresses without damage to or displacement of any component when exposed to shock and vibration such as ocurring in rail transportation with humping at 10 mph.

3.11 Environmental. The shop(s) (Type II and III) including tools and equipment, shall withstand without damage, storage in a temperature of minus 50 degrees F for 72 hours and a 24 hour cycle in temperatures from plus 80 degrees F to plus 150 degrees F. The shop(s) shall be capable of operation in ambient temperature from minus 25 degrees F to plus 105 degrees F.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T04:00Z
Check the source to verify that this is the current version before use.

3.12 Sound level. The sound level of the shop(s) (Type II and III) shall be in accordance with MIL-STD-1474, Category D, for steady-state noise when tested in accordance with 4.6.2.5. Hearing protectors need not be supplied with the shop equipment. Hazard signs, if required, shall state: "Caution, Hearing Protection Required" when (name of tool or equipment) is operating.

3.13 Fuels, lubricants, and coolants. The shop(s) shall be assembled and tested with the products of the type and grade specified in Table I for the applicable ambient air temperature. The shops shall operate as specified herein when furnished with these products (see 6.5).

3.13.1 Oil lubrication. Unless otherwise specified herein, all components shall be filled to the operating level with military oils designated for use in the temperature range at the shipping destination. A tag shall be attached in a conspicuous place to indicate the temperature range and grade of lubricant used.

3.14 Fungus control. Unless otherwise specified (see 6.2), electrical components and circuit elements shall be treated for fungus resistance in accordance with the Type II requirements of MIL-T-152.

3.15 Identification Marking and Instruction Plates.

3.15.1 Identification marking. The unit shall be identified in accordance with MIL-STD-130..

3.15.2 Instruction plates. Instruction plates shall conform to MIL-P-514, Type III, Composition C, or Type I, Style 1, Composition A, Class 2.

3.16 Treatment and painting. The portions of the shop normally painted shall be cleaned, treated, and painted in accordance with drawing #11021251.

3.17 Maintainability. The Type I, II, and III shop equipment shall require a minimum of operational and in-storage maintenance. Replacement components will be used to the maximum extent possible. The shop equipment shall require a minimum of man-hours and skill to accomplish maintenance. Ease of maintenance and restricted use of components requiring special skills or tools for maintenance will be stressed. The maintenance ratio shall be no greater than 0.12 (see 6.7.1).

3.18 Reliability. The specified mean-time-between-failure shall be 75 hours when tested as specified in 4.6.2.7.

3.19 Workmanship. Standards of workmanship shall be such that the shop shall have the safety, stability, and operating characteristics specified herein and shall be free of defects that could adversely affect its intended use.

4 QUALITY ASSURANCE PROVISIONS

4.1 Responsibility for inspection. Unless otherwise specified in the contract, the contractor is responsible for the performance of all inspection requirements as specified herein. Except as otherwise specified in the contract, the contractor may use his own or any other facilities suitable for the performance of the inspection requirements specified herein, unless disapproved by the Government. The Government reserves the right to perform any of the inspections set forth in the specification where such inspections are deemed necessary to assure supplies and services conform to prescribed requirements.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T04:00Z
Check the source to verify that this is the current version before use.

4.1.1 Component and material inspection. The contractor is responsible for insuring that components and materials used are manufactured, tested, and inspected in accordance with referenced specifications and standards.

4.1.2 Disassembly inspection. The first article shop failing a performance test shall be disassembled in the presence of a Government representative to the extent necessary to determine the cause of the failure. Each disassembled part shall be inspected in detail for compliance with this specification and referenced drawings in regard to materials, dimensions, and tolerances. Parts not complying with such requirements shall be rejected. Reassembly with accepted parts and retesting shall be the responsibility of the contractor.

4.2 Classification of inspection. Inspection shall be classified as follows:

a. First article inspection (see 4.3).

b. Initial production inspection (see 4.4).

c. Quality conformance inspection (see 4.5).

d. Inspection comparison (see 4.7).

e. Packaging inspection (see 4.8).

4.3 First article inspection.

4.3.1 Examination. Each shop shall be examined for the defects marked "X" in Column 1 of Table II. Presence of one or more defects shall be cause for rejection.

4.3.2 Tests. Each shop shall be tested as specified in Column 1 of Table III. Failure of any test shall be cause for performing the inspection specified in 4.1.2.

* 4.3.3 Application of fuels, lubricants and coolants. Prior to any examination of test the first article shop shall be serviced and prepared in accordance with 3.13.1 and Table I. Oils shall be those designated for use in the ambient temperature at which the test is being performed.

4.4 Initial production inspection. When specified (see 3.3), one or more initial production shops shall be selected at random by the Government from shops being produced from production tooling. The shop(s) shall be examined for the defects marked "X" in Column 2 of Table II and subjected to the tests marked "X" in Column 2 of Table III to determine conformance to the requirements of this specification. The inspection shall be performed by the Government at a site selected by the Government. Acceptance of an initial production shop shall not exclude the remaining shops from the quality conformance inspection and acceptance provisions specified herein. In addition to any test specified as part of the initial production test, the Government reserves the right to conduct any and all other tests contained in this specification as part of the initial production test. Failure of such additional tests shall have the same effect as failure of those tests specified as initial production tests.

4.4.1 Inspection failure. Failure of an initial production shop to meet any requirement specified herein during the examination and tests specified in 4.4 shall be cause for rejection of the initial production shop and shall be cause for refusal by the Government to continue acceptance of production shops until evidence has been provided by the contractor that corrective action has been taken to eliminate the deficiencies. Correction of such deficiencies shall be accomplished by the contractor at no cost to the Government on shops previously accepted and produced under the contract. Any deficiencies found as a result of the initial production inspection will be considered prima facie evidence that all shops accepted prior to the completion of initial production inspection are similarly deficient, unless evidence

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T04:00Z
Check the source to verify that this is the current version before use.

to the contrary is furnished by the supplier and such evidence is acceptable to contracting officer.

4.4.2 Weight. The complete welding shop shall be weighed using a scale. Weight shall be as specified in 3.7.1.

4.4.3 Lifting loading (wet weight). Using a scale, the lifting loading shall be as specified in 3.7.3.

4.5 Quality conformance inspection.

4.5.1 Examination. Each shop shall be examined for the defects marked "X" in Column 3 of Table II. Presence of one or more defects shall be cause for rejection.

4.5.2 Tests. Each shop shall be subjected to the tests marked "X" in Column 3 of Table III. Failure of any test shall be cause for rejection.

4.6 Inspection schedule.

4.6.1 Examination. Examination shall be in accordance with Table II.

4.6.2 Tests.

4.6.2.1 Test schedule. Tests shall be in accordance with Table III. Sequence of the test at the option of the test facility except as required in test paragraphs.

* 4.6.2.2 Road. Install all the tools and equipment specified herein in the transport position and perform the following tests. Both prior to and after the road test, perform the installed equipment and power tool test specified in 4.6.2.3:

4.6.2.3 Road tests. Load the shop with the tools and equipment specified herein and perform the following tests:

a. Unimproved roads. Drive the shop 350 miles on unimproved roads at maximum safe speeds. The course shall consist of poorly maintained gravel and dirt roads with moderate washboarding and rutting and occasional potholes.

b. Cross-country trails. Drive the shop 150 miles on cross-country trails at maximum safe speeds. The course shall consist of maintain passability. Surface conditions shall range from smooth to rough with washboarding, rutting, potholes and depressed areas.

c. Chatter course. Drive the shop over a chatter course until at least 2,600 either upward or downward accelerations of magnitudes specified herein have been applied to a rear wheel center. The course shall be of construction that the acceleration magnitudes specified below can be obtained by adjusting the vehicle speed without the frequency of the accelerations exceeding 15 cycles per second (cps) or becoming less than 3 cps. The maximum acceleration magnitude specified below shall not be exceeded. Accelerations having magnitudes less than the minimum shall be disregarded. The course shall be of such length that a wheel center receives in one pass over the course at least 50 consecutive vertical acceleration cycles. The magnitude of an acceleration cycle shall not be less than five G's nor more than eight G's. Measure the accelerations by a trial test to establish the required vehicle test speed. Then disconnect the recording instruments and complete the test at established speed. The acceleration values used shall be those of the wheel center receiving the highest accelerations. Means for assuring that the vehicle test speed is held constant throughout the test shall be provided. Accelerations shall be measured on a running-gear member, usually an axle or spindle, that has a motion identical to that of the wheel center.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T04:00Z
Check the source to verify that this is the current version before use.

d. Diagonal ditch course. Drive the shop over a series of ditches until 600 reversal torsional frame stresses have been applied. The ditch profile shall be such as to allow vertical wheel travel of 18 inches from crest to root. The ditches shall be at 45 degrees to the centerline of the course and spaced a sufficient distance apart to allow only one rear wheel and one front wheel of opposite sides in the ditches at any one time.

Examine the shop at the completion of each phase of the road test. Damage to or displacement (see 6.7.2) of any component, accessory, part or tool; evidence of defective welded, bolted, or riveted connections shall constitute failure of these road tests.

4.6.2.4 Impact testing.

a. Test equipment. The following equipment is required:

(1) Five railroad cars and one flatcar equipped with standard draft gear couplings.

(2) Some means of moving the cars.

(3) Some means to determine accurately within plus or minus 5 percent the speed at the time of impact.

b. Procedure. Mount the shop in direct contact with the car floor with the front toward the impact end of the flatcar. Block and secure the shop to prevent any longitudinal, vertical, or side movement. Hump the loaded flatcar at a speed of not less than 10 mph against the five cars with their draft gear extended and brakes set. Examine the shop for physical damage. Record on data sheet all readings taken during test and condition of shop after test. Reverse the direction of impact and repeat the test. Evidence of any damage or permanent deformation of any part or component of the shop, excluding the Government-furnished chassis, shall constitute failure of this test.

4.6.2.5 Sound level measurement. Operate the shop at governed speed with the welder-generator and air compressor operating. Measure the sound level at the tailgate work station while operating each of the power tools. Sound level in excess of Category D of MIL-STD-1474 shall require the installation of hazard signs as specified in 3.12.

4.6.2.6 Environmental.

4.6.2.6.1 Low temperature storage. Place the shop in an ambient air temperature of minus 50 degrees F to minus 55 degrees F for a period of 72 hours. At the end of 72 hours, remove the shop from the low ambient temperature and stabilize at an air temperature of plus 80 degrees F plus or minus 10 degrees F. Start and operate the shop, including the welder-generator for 15 minutes. Operate each of the power tools 2 minutes. Inability of the shop, the tools and equipment to start and operate, or damage or deformation of any component, accessory, part or tool shall constitute failure of this test (see 6.8).

4.6.2.6.2 High temperature storage. Place the shop in an ambient air temperature of plus 90 degrees F to plus 95 degrees F for a period of 10 hours. Follow with 5 hours of steady increase to plus 150 degrees F to plus 155 degrees F, 4 hours at plus 150 degrees F to plus 155 degrees F and 5 hours of steady decrease to plus 80 degrees F plus or minus 10 degrees F. Operate the shop, tools and equipment in accordance with 4.6.2.6.1. Inability of the shop, tools and equipment to start and operate or damage or deformation of any component, accessory, part, or tool shall

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T04:00Z
Check the source to verify that this is the current version before use.

constitute failure of this test (see 6.8).

4.6.2.6.3 High temperature operation. Place the shop in ambient controlled air temperature and increase to stabilize at 105 degrees F plus or minus 5 degrees F and perform paragraph 4.6.2.2.2 maximum power operation test. Failure to perform for a one-hour period shall constitute failure of this test. This test when specified (see 6.2.1) is performed in lieu of paragraph 4.6.2.2.2.

4.6.2.7 Reliability. The shop equipment shall be tested for a total of (10) ten each missions to determine conformance to the requirements specified in 3.18. The shop equipment shall be considered to have demonstrated the required reliability if one or less chargeable reliability failure occur. A mission shall consist of the following:

a. Driving the fully loaded shop at maximum safe speeds for (10) ten miles on unimproved roads and (10) ten miles on cross-country trails.

b. Using the instructions furnished with the shop, set up the shop for operation.

c. Operating each installed equipment and power tool for a period of (10) ten minutes minimum, one time per mission.

d. Preparing the shop for movement to another location, to begin next mission.

A chargeable reliability failure is defined as any malfunction which cannot be corrected by an organization repair unit within five minutes by adjustment, repair, or replacement action (using controls on equipment, tools or parts) and which causes or may cause:

a. Failure to commence operation, cessation of operation, or degradation for performance below specified levels.

b. Damage to the shop by continued operation.

c. Safety hazards to personnel.

4.6.2.8 Maintenance evaluation. Maintenance operations required during first article and initial production tests shall be accomplished as specified in 3.17. Any support elements such as technical manuals, repair parts, special tools, etc., provided under the contract for assisting or conducting maintenance will be evaluated. Failure of the shop equipment to be maintained as specified shall constitute failure of this test.

4.7 Inspection comparison. The Government may select shops at any time during the contract production period and subject these shops to the examination specified in Column 2 of Table II and the tests specified in Column 2 of Table III to determine conformance to the requirements of this specification. The inspection will be performed by the Government at a site selected by the Government. Shops will be selected at random from those which have been accepted by the Government and will not include the previously inspected first article model or initial poduction model. In addition to any test specified as part of the inspection comparison, the Government reserves the right to conduct any and all other tests contained in this specification as part of the inspection comparison and failure of such additional tests shall have the same effect as failure of those tests specified as inspection comparison.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T04:00Z
Check the source to verify that this is the current version before use.

4.7.1 Inspection failure. Failure of an inspection comparison shop to meet any requirement specified herein during and as a result of the examination and test specified in 4.7 shall be cause for rejection of the inspection comparison shop and shall be cause for refusal by the Government to continue acceptance of production shops until evidence has been provided by the supplier that corrective action has been taken to eliminate the deficiencies. Correction of such deficiencies shall be accomplished by the supplier at no cost to the Government on shops previously produced and accepted under the contract. Any deficiencies found as a result of inspection comparison inspection will be considered prima facie evidence that all shops accepted after approval of the initial production shop are similarly deficient unless evidence to the contrary is furnished by the contractor and such evidence is acceptable to the contracting officer.

4.8 Packaging inspection. Preservation, packaging, packing, and marking for shipment and storage shall be examined to determine compliance with the requirements of Section 5.

5 PACKAGING

5.1 Preservation. Preservation shall be Level A, Level B, or Industrial, as specified (see 6.2.1).

5.1.1 Level A.

5.1.1.1 Preservatives. Preservatives specified herein shall conform to MIL-P-116.

5.1.1.2 Methods. Methods of preservation specified herein shall conform to MIL-P-116.

5.1.1.3 Sets or kits. When items are furnished in sets or kits with a carrying case, the items shall be preserved as specified herein and, when possible, replaced in the case.

5.1.1.4 Items having mounting brackets or holders. Items furnished with mounting brackets or holders shall be preserved as specified herein and, when possible, replaced in the bracket or holder and secured to prevent movement and damage.

5.1.1.5 Unprotected surfaces. Unprotected exterior metal surfaces of the components, not specifically specified herein, requiring the application of a contact preservative in accordance with MIL-P-116 shall be preserved as follows.

5.1.1.5.1 Unfinished surfaces. Unfinished surfaces shall be coated with Type P-1 preservative.

5.1.1.5.2 Machined surfaces. Exposed exterior machined surfaces shall be coated with Type P-2, P-6 or P-11 preservative. The coated surfaces shall be wrapped or covered with barrier material conforming to MIL-B-121, Type I, Grade A, Class 2 and secured in place with tape conforming to PPP-T-60, Type IV.

5.1.1.6 Truck chassis. The truck chassis with mounted body shall be preserved in accordance with the Level A (mobile) preservation and packaging requirements of MIL-STD-281.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T04:00Z
Check the source to verify that this is the current version before use.

5.1.1.7 Generator-welder. The generator-welder shall be preserved in accordance with MIL-E-16298, Level A, using the alternate method as specified for assembled machines.

5.1.1.8 Handtools and tool sets. Handtools and tool sets shall be preserved in accordance with the Level A requirements of PPP-P-40.

5.1.1.9 Belts and pulleys. All drive belts shall be released from tension or removed. Unpainted, unplated ferrous metal surfaces of the pulley shall be coated with primer conforming to TT-P-664. Removed belts shall be secured convenient to the pulley for which intended.

5.1.1.10 Chain hoist. The chain and any other unpainted metal surface of the hoist shall be coated with Type P-2 preservative. The hoist shall be wrapped in paper conforming to MIL-B-121, Type I, Grade A, Class 2, and packaged in a close-fitting box conforming to PPP-B-636, Domestic Type.

5.1.1.11 Items furnished in commercial containers. Items which are commercially packaged in sealed cans, pails, drums, jars or tubes shall not require preservation.

5.1.1.12 Method III. Straight adapters, electrical and ground clamps, fitting kits, insert and tool assortment kits, rubber hose, and brass nipples shall be individually preserved Method III.

5.1.1.13 Method IC-2. The first aid kit, floodlight, and moisture stabilizer shall be preserved method IC-2. The container shall be the contractor's commercial container or a close-fitting box conforming to PPP-B-566 or PPP-B-636, Class Domestic.

5.1.1.14 Locks and keys. The interior of locks shall be coated with powdered graphite and the locks operated to assure penetration of the graphite.

The keys shall be preserved Method III and forwarded to destination separately by registered mail. A cloth or paper shipping tag containing the shop equipment identification number and the trailer registration number shall be attached to the related padlock keys for future positive identification.

5.1.1.15 Fire extinguisher. Unpainted exterior metal surfaces of the fire extinguisher requiring the application of a contact preservative in accordance with MIL-P-116 shall be coated with Type P-1 preservative. The extinguisher shall be placed in the mounting bracket and secured.

5.1.1.16 Electronic and electrical equipment. Electronic and electrical equipment and accessories, shall be preserved and packaged in accordance with MIL-E-17555, level A.

5.1.1.17 Other tools and equipment. Tool and equipment items which are not specifically covered by the packaging requirements of this specification shall be preserved and unit packaged in accordance with Level A requirements of the applicable commodity specification of MIL-T-45542. Unit containers shall be non-weather-resistant grade.

5.1.1.18 Technical publications. Technical publications shall be preserved in accordance with MIL-P-116, Method IC-1 or IC-3.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T04:00Z
Check the source to verify that this is the current version before use.

5.1.1.19 Welding and soldering equipment. Welding and soldering equipment shall be preserved in accordance with Level A preservation and packaging requirements of MIL-W-45562.

5.1.1.20 Miscellaneous supplies and equipment. Items, equipment, and components not specifically identified herein, shall be preserved as specified for supplies and equipment of similar design and construction.

5.1.1.21 Consolidation. Components that cannot be placed in the drawer, toolboxes, or compartments, or secured by the mounting brackets or holders provided, shall be consolidated together in close-fitting boxes conforming to PPP-B-566 or PPP-B-636 Domestic Type. The boxes shall be of a size to fit into the available space within the body. The contents shall be blocked, braced, and cushioned as applicable to prevent movement and damage to the contents within the box.

5.1.2 Level B. Preservation shall be as specified for Level A with the following exceptions.

5.1.2.1 Truck chassis. The truck chassis with mounted body shall be preserved in accordance with the Level B (mobile) preservation and packaging requirements of MIL-STD-281.

5.1.2.2 Handtools and tool sets. Handtools and tool sets shall be preserved in accordance with the Level B requirements of PPP-P-40.

5.1.2.3 Welding and soldering equipment. Welding and soldering equipment shall be preserved in accordance with Level B preservation and packaging requirements of MIL-W-45562.

5.1.3 Industrial. Industrial preservation of the truck chassis with mounted body and all shop equipment shall be in accordance with ASTM D3951-82 and as specified herein. Components shall be placed and secured in the compartment provided. Toolboxes, drawers, mounting brackets, and holders shall be utilized to the greatest extent possible.

5.2 Packing (see 6.11). The truck mounted shop, with equipment enclosed, shall be prepared for shipment mobile in a manner to assure carrier acceptance and safe delivery to destination at lowest ratings. Items and equipment, installed in the shop body, and any other movable equipment or items, shall be cushioned, blocked, braced, and anchored to prevent damage to the equipment or to the body. All doors and drawers shall be secured to prevent accidental opening and in a manner to prevent pilferage of contents.

5.3 Marking.

5.3.1 Military. Marking for military levels of protection shall be in accordance with MIL-STD-129.

5.3.2 Industrial. Marking for industrial packaging shall be in accordance with ASTM D3951-82.

6 NOTES

6.1 Intended use. The contact maintenance shop is intended for use by personnel engaged in the maintenance of military mechanical equipment.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T04:00Z
Check the source to verify that this is the current version before use.

6.2 Ordering data.

6.2.1 Acquisition requirements. Acquisition documents should specify the following:

a. Title, number and date of this specification.

b. First article, when required (see 3.1).

c. When initial production inspection is required and number of shops to be furnished (see 3.3).

d. Special safety devices, when required (see 3.5 and 6.14).

e. Gross vehicle weight, if different (see 3.7.1).

f. Fungus control, if required (see 3.14).

g. Government-furnished property, if different (see 3.7).

h. Level of preservation and packaging required (see 5.1).

6.3 The contracting officer should arrange to furnish information concerning items specified in set SC-4940-95-CL-XXX or SC-4940-95-CL-YYY (see 3.1).

6.4 Technical interface data. The contracting officer should arrange to provide information concerning technical interface for the government furnished truck chassis specified in 3.7.

6.5 Lubricants. When requested by the contractor, the contracting officer should obtain a list of military lubricants applicable to the shop covered by this specification.

6.6 Government-furnished property. The contracting officer should arrange to furnish the supplier the property specified in 3.7.

6.7 Definitions.

6.7.1 Maintenance ratio. The ratio of the number of maintenance man-hours required for both scheduled maintenance and unscheduled repairs, to the number of hours of operation (see 3.17).

6.7.2 Displacement. Displacement is defined as dislodgement of any tool or item of equipment from its designated position. Movement of a tool or item of equipment within its designated position without any dislodgement is permitted (see 3.9 and 3.10).

6.8 Environment testing. In lieu of requiring the supplier to perform the tests specified in 4.6.2.6.1 and 4.6.2.6.2 the contracting officer may accept certification that the equipment furnished with the shop will withstand storage in the high and low temperatures specified, without malfunction, damage, or degradation of performance.

6.9 Packing (see 5.2). Levels of packing have not been included for the truck mounted shop equipment as the nature of the item is such that only mobile packing is appropriate. For purposes of preservation and packing level markings, the level of packing should be considered Level A and should be marked A/A.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T04:00Z
Check the source to verify that this is the current version before use.

6.10 Contract data requirements. Required technical data such as operator's manuals, parts lists, and other instructions for operation and maintenance, as identified on a numbered DD Form 1664, should be specified on a DD Form 1423 incorporated in the contract.

6.11 Provisions. The contracting officer should include provisioning requirements for repair parts and maintenance tools as necessary (including any special tools), and instructions on shipment as shops.

6.12 Ear protection. When the noise level exceeds Category D of MIL-STD-1474, the operator's manual for the shop should include appropriate instructions for use of hearing protection when using equipment that produces noise above 85db(A) inside and outside of the shop.

6.13 Safety and health determination. In order that equipment integrated into the user's operational environment will comply with OSHA limitation and control of noise levels, radiations, electromagnetic emission, noxious vapors, heat, etc. as applicable, specific requirements concerning guarding the point(s) of operation, and other safety and health requirements should be specified by the user (see 6.2.1).

6.14 Changes from previous issue. The margins of this specification are marked with an asterisk to indicate where changes (addition, modifications, corrections, deletions) from the previous issue were made. This was done as a convenience only and the Government assumes no liability whatsoever for any inaccuracies in these notations. Bidders and suppliers are cautioned to evaluate the requirements of this document based on the entire content irrespective of the marginal notations and relationship to the last previous issue.

Custodian:
Army - AL

Preparing Activity:
Army - AL

Project No. 4940-A484

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T04:00Z
Check the source to verify that this is the current version before use.

Table I. Service products.

Item	Application	Specification	Type and Grade
1	Engine:		
	a. Heavy Duty	MIL-L-2104	10, 30
	b. Arctic	MIL-L-46167	One Grade
2	Grease:		
	a. Automotive	MIL-G-10924	One Grade
	b. High Temperature	MIL-G-23827	One Grade
3	Hydraulic-system Oil:		
	a. Oil	MIL-L-2104	10
	b. Oil (low temperature)	MIL-L-46167	One Grade
4	Lubricating Oils:		
	Universal	MIL-L-2105	80, 90, 140
5	Antifreeze:		
	a. Ethylene glycol	O-A-548	One Grade
	b. Arctic	MIL-A-11755	One Grade
6	Brake Fluid:	VV-B-680	One Grade

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T04:00Z
Check the source to verify that this is the current version before use.

Table II. Examination schedule.

First Article	Initial Production	Quality Conformance	Defect	Requirement Paragraph
1	2	3	4	5
X	-	-	Dimensions not as specified.	3.2.4
X	X	-	Storage or tiedowns not as specified.	3.9
X	X	X	Assembly incomplete or incorrect.	3.2.1, 3.2.2, and 3.2.3
X	X	X	Parts, components, tools, or equipment missing, or not functioning as specified.	3.7, 3.8 and 3.9
X	X	X	Safety devices and guards missing or not as specified	3.5
X	-	X	Material not as specified.	3.4
X	X	X	Lubrication not as specified.	3.13
X	X	X	Workmanship not as specified.	3.19
X	-	X	Treatment or painting not as specified.	3.16
X	X	X	Accessories, identification or other marking, operating and safety instructions, or manuals missing.	3.15
X	-	X	Fungus and moisture not as specified.	3.14

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T04:00Z
Check the source to verify that this is the current version before use.

Table III. Test schedule.

First Article	Initial Production	Quality Conformance	Test	Test Paragraph	Requirement Paragraph
1	2	3	4	5	6
X	X	-	Roadability.	4.6.2.3	3.6
X	X	-	Impact testing.	4.6.2.4	3.10
X	X	-	Environmental.	4.6.2.6	3.11
X	-	-	Sound level.	4.6.2.5	3.12

U.S. GOVERNMENT PRINTING OFFICE: 1984 - 605-036/41968

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T04:00Z
Check the source to verify that this is the current version before use.

(TO DETACH THIS FORM, CUT ALONG THIS LINE.)

STANDARDIZATION DOCUMENT IMPROVEMENT PROPOSAL

(See Instructions – Reverse Side)

1. DOCUMENT NUMBER	2. DOCUMENT TITLE

3a. NAME OF SUBMITTING ORGANIZATION	4. TYPE OF ORGANIZATION *(Mark one)*
	☐ VENDOR
b. ADDRESS *(Street, City, State, ZIP Code)*	☐ USER
	☐ MANUFACTURER
	☐ OTHER *(Specify)*:

5. PROBLEM AREAS

a. Paragraph Number and Wording:

b. Recommended Wording:

c. Reason/Rationale for Recommendation:

6. REMARKS

7a. NAME OF SUBMITTER *(Last, First, MI)* – Optional	b. WORK TELEPHONE NUMBER *(Include Area Code)* – Optional
c. MAILING ADDRESS *(Street, City, State, ZIP Code)* – Optional	8. DATE OF SUBMISSION *(YYMMDD)*

DD FORM 82 MAR 1426 PREVIOUS EDITION IS OBSOLETE.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T04:00Z
Check the source to verify that this is the current version before use.