MIL-S-45855E(AL)
14 March 1988
SUPERSEDING
MIL-S-0045855D(AL)
7 November 1984
MIL-S-45855C(AL)
12 November 1980

MILITARY SPECIFICATION

SHOP EQUIPMENT, CONTACT MAINTENANCE

TRUCK-MOUNTED

This specification is approved for use by the Armament research and Development Engineering Center (Tool and Equipment Engineering Division, Standardization and Specification Engineering Branch), Department of the Army and is available for usage by all Departments and Agencies of the Department of Defense.

1. SCOPE

1.1 Scope. This specification covers three types of truck-mounted, contact maintenance shops.

1.2 Classification. This specification covers truck-mounted, contact maintenance shop of the following types.

Type I - Consist of Truck chassis and body per drawing TA13217E8300.

Type II - Consist of Type I loaded with tools and equipment per Set Components List SC4940-95-CL-B21.

Type III - Consist of Type I loaded with tools and equipment per Set Components List SC4940-95-CL-B22.

2. APPLICABLE DOCUMENTS

2.1 Government documents.

2.1.1 Specifications and standards. The following specifications and standards form a part of this specification to the extent specified herein. Unless otherwise specified, the issue of these documents shall be those listed in the issue of the Department of Defense Index of Specifications and Standards (DoDISS) and supplement thereto, cited in the solicitation.

SPECIFICATIONS

Beneficial comments (recommendations, additions, deletions) and any pertinent data which may be of use in improving this document should be addressed to: Commander, US Army Armament Research, Development and Engineering Center, ATTN: SMCAR-EST-S, Rock Island, IL 61299-7300 by using the self-addressed Standardization Document Improvement Proposal (DD Form 1426) appearing at the end of this document or by letter.

AMSC N/A FSC 4940
DISTRIBUTION STATEMENT A. Approved for public release; distribution is unlimited.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T04:00Z
Check the source to verify that this is the current version before use.

FEDERAL

O-A-548 - Antifreeze/Coolant, Engine, Ethylene Glycol, Inhibited, Concentrated
TT-P-664 - Primer Coating, Synthetic, Rust-Inhibiting, Lacquer-Resisting
VV-B-680 - Brake fluid, Automotive
PPP-B-566 - Boxes, Folding, Paperboard
PPP-B-636 - Boxes, Shipping, Fiberboard
PPP-P-40 - Packaging and Packing of Hand Tools
PPP-T-60 - Tape, Preservation and Sealing

MILITARY

MIL-P-116 - Preservation-Packaging, Methods of
MIL-B-121 - Barrier Material, Greaseproofed, Waterproofed, Flexible
MIL-T-152 - Treatment, Moisture- and Fungus-Resistant of Communications, Electronic, and Associated Electrical Equipment
MIL-V-173 - Varnish, Moisture- and Fungus-Resistant (For Treatment of Communications, Electronic, and Associated Electrical Equipment)
MIL-P-514 - Plates, Identification, Instruction and Marking, Blank
MIL-L-2104 - Lubricating Oil, Internal Combustion Engine, Tactical Service
MIL-L-2105 - Lubricating Oil, Gear, Multipurpose
MIL-G-10924 - Grease, Automotive and Artillery
MIL-A-11755 - Antifreeze, Arctic-Type
MIL-E-17555 - Electronic and Electrical Equipment, Accessories and Repair Parts: Packaging and Packing of
MIL-G-23827 - Grease, Aircraft and Instrument, gear and Actuator Screw
MIL-T-45542 - Tool Sets, Shop Sets and Kits (Hardware, Installation, Modification and Tool) Both Common and Special: Packaging and Packing of
MIL-L-46167 - Lubricating Oil, Internal Combustion Engine, Arctic
MIL-W-45562 - Welding and Soldering Equipment, Supplies and Accessories, Packaging of

STANDARDS

MILITARY

MIL-STD-129 - Marking for Shipment and Storage
MIL-STD-130 - Identification Marking of US Military Property
MIL-STD-171 - Finishing of Metal and Wood Surfaces
MIL-STD-209 - Lifting and Tiedown Provisions
MIL-STD-281 - Automobiles, Trucks, Truck-Tractors, Trailers and Trailer Dollies; Preservation and Packaging of
MIL-STD-454 - Standard General Requirements for Electronic Equipment
MIL-STD-889 - Dissimilar Metals
MIL-STD-1190 - Minimum Guidelines for Level C Preservation, Packing and Marking
MIL-STD-1474 - Noise Limits for Army Materiel

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T04:00Z
Check the source to verify that this is the current version before use.

2.1.2 Other Government documents, drawings, and publications. The following other Government documents, drawings, and publications form a part of this specification to the extent specified herein. Unless otherwise specified, the issues shall be those in effect on the date of the solicitation.

DEPARTMENT OF ARMY

LIST OF COMPONENTS

SC 4940-95-CL-B21 Sets, Kits and Outfits, Components List
SC 4940-95-CL-B22 Sets, Kits and Outfits, Components List

DRAWINGS

TA13217E8300 - Shop Equipment, Contact Maintenance, Truck-Mounted
13226E7548 - US/GE Standardized Camouflage Pattern Painting

(Copies of specifications, standards, handbooks, drawings, and publications required by contractors in connection with specific acquisition functions should be obtained from the contracting activity or as directed by the contracting officer.)

2.2 Other publications. The following documents form a part of this specification to the extent specified herein. Unless otherwise specified, the issues of the documents which are DoD adopted shall be those listed in the issue of the DoDISS specified in the the solicitation. Unless otherwise specified, the issues of documents not listed in the DoDISS shall be the issue of the nongovernment document which is current on the date of the specification.

NATIONAL ELECTRIC MANUFACTURERS ASSOCIATION (NEMA)

NEMA MG1 - Motors and Generators

(Applications for copies should be addressed to the National Electrical Manufacturers Association, 2101 L Street N.W., Washington, DC 20037.)

(Nongovernment standards and other publications are normally available from the organizations which prepare or which distribute the documents. These documents also may be available in or through libraries or other informational services.)

2.3 Order of precedence. In the event of a conflict between the text of this specification and the references cited herein (except for associated detail specification, specification sheets or MS standards), the text of this specification shall take precedence. Nothing in this specification, however, shall supersede applicable laws and regulations unless a specific exemption has been obtained.

3. REQUIREMENTS

3.1 First article. When specified (see 6.2.1), the contractor shall furnish one complete shop for first article inspection. The first article may be either a preproduction model or an initial production item which conforms to the requirements of this specification.

3.2 Description. This specification covers three types of Shop Equipment Contact Maintenance vehicles identified as follows:

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T04:00Z
Check the source to verify that this is the current version before use.

3.2.1 Type I. The Type I Shop Equipment, Contact Maintenance Vehicle, Truck Mounted, shall be as specified herein and shall be in accordance with TA 13217E8300. The Type I vehicle shall be equipped with a power take-off (pto) which drives an Alternate Current (AC) brushless alternator (see 3.6.2.1). The Type I vehicle shall also be equipped with an air compressor and storage reservoir (see 3.6.1).

3.2.2 Type II. The Type II Shop Equipment Contact Maintenance Vehicle Truck Mounted shall consist of the Type I vehicle loaded with tools and equipment specified in the Set Components List compiled from SC4940-95-CL-B21.

3.2.3 Type III. The Type III Shop Equipment Contact Maintenance Vehicle Truck Mounted shall consist of the Type I vehicle loaded with tools and equipment specified in the Set Components List compiled from SC4940-95-CL-B22.

3.2.4 Drawings. The drawings forming a part of this specification are end product drawings. No deviation from the prescribed dimensions or tolerances is permissible without prior approval of the contracting officer. Where tolerances could cumulatively result in incorrect fits, the supplier shall provide tolerances within those prescribed on the drawings to ensure correct fit, assembly, and operation of the shop equipment. Any data, e.g., shop drawings, layouts, flow sheets, processing procedures, etc., prepared by the supplier or obtained from a vendor to support fabrication and manufacture of the production item shall be made available, upon request, for inspection by the contracting officer or his designated representative.

3.3 Initial production. When specified (see 6.2.1), the supplier shall furnish to the Government one or more shops for inspection.

3.4 Material. Material shall be as specified herein and as shown on the applicable drawings. Materials not specified shall be selected by the contractor and shall be subject to all provisions of this specification. Materials shall be free from defects which would adversely affect the performance or maintainability of the individual components or overall assembly. When dissimilar metals are used in contact with each other, suitable protection against galvanic corrosion shall be applied in accordance with MIL-STD-889.

3.5 Shop dimensions, weight, and lifting.

3.5.1 Dimensions. Dimensions of all types of the shop sets shall be as shown on the applicable drawings (see 3.2.4). All types shall be capable of being transported in a C-130/C-141 Aircraft.

3.5.2 Weight. Unless otherwise specified (see 6.2.1), the GVW of the Type II and Type III shops shall not be greater than 9000 pounds.

3.5.3 Lifting and tiedown provisions. Multipurpose slinging and tiedown provisions for all shop sets (Type I, II, and III are required in accordance with MIL-STD-209, Class 3 (Multipurpose), Type II, (Tactical/Support Vehicles). Spreader bars shall be used in sling lifting of the vehicles. Stowage of the spreader bars on the venicle is not required. The Types I, II, and III vehicles are not intended to be helicopter transported.

3.6 Body. The supplier shall fabricate and install the body on the chassis in accordance with the applicable drawings (see 3.2.4).

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T04:00Z
Check the source to verify that this is the current version before use.

3.6.1 Air compressor. The electric motor driven air compressor with storage reservoir shall be furnished and installed by the contractor in accordance with the aplicable drawings (see 3.2.4). The air compressor shall deliver no less than 3.0 cubic feet per minute (cfm) of free air at 100 pounds per square inch gage (psig) and operate on 208 volts alternating current (VAC), 3 phase, 60 Hertz (HZ) power. The reservoir capacity shall be no less than 1200 cubic inches.

3.6.2 Electrical system. This specification covers the AC and DC electrical systems of the Type I vehicle. The electrical systems shall be designed and constructed in accordance with MIL-STD-454.

3.6.2.1 AC electrical power system. The pto driven alternator shall be furnished and installed by the contractor in accordance with the applicable drawings (see 3.2.4). The AC brushless alternator shall have a minimum output of 15 kilowatts (KW), 208 volts (V), 3 phase, 60 HZ power. The alternator output performance and design criteria shall be in accordance with NEMA MG1-78, Part 22.10 - Part 22.84.

3.6.2.2 DC electrical power system. The 12 volt Direct Current (DC) electrical system shall be in accordance with the applicable drawings as specified herein for all vehicular lighting and towed load interconnections.

3.6.2.3 Grounding. A 1/4-20 threaded ground stud shall be provided on the front of the control panel as a terminal for ground leads from the control panel mounted equipment. An 8 foot ground rod shall be provided with all Type I vehicles.

3.7 Fire extinguisher. The fire extinguisher shall be mounted in the Type II and III shop sets in accordance with the applicable drawings.

3.8 Tools and equipment. The tools and equipment for the Type II and III shops shall be located as specified, anchored or stored to prevent movement during transit. Tiedown devices shall be designed for a general tool or equipment configuration to allow interchange of like items from different manufacturing sources. Wherever possible, items shall be grouped together by function.

3.9 Safety. All exposed parts which are subject to high operating temperatures or which are energized electrically shall be insulated, fully enclosed, or guarded. All moving/rotating parts which are hazardous to operating or maintenance personnel shall be fully enclosed or guarded. Protective devices shall not impair the operating functions.

3.10 Performance.

3.10.1 Maximum power operation. When unit is operating at 208 volt, three phase and loaded to 15 Kw, there shall be no damage, deterioration, malfunction, or failure of electrical components, or failure of belts or other mechanical components as specified in 3.6.2.

3.10.2 Installed equipment and power tools operation. On Type II and Type III shops, using both external and shop generated power, operate all installed equipment and power tools.

3.10.3 Roadability. When loaded with the tools and equipment specified herein, the Type II/Type III Shops loaded to 9000 pounds Gross Vehicle Weight (GVW) while pulling a 3000 pound towed load shall withstand driving on unimproved roads (350 miles), cross-country/trails (150 miles), and without the towed load a chatter course and a diagonal ditch course. During or following driving, there shall be no damage to

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T04:00Z
Check the source to verify that this is the current version before use.

or displacement (see 6.7.2) of any component, accessory, part, or tool installed in or on the shop and no evidence of defective welded, bolted, or riveted connections on the shop.

3.10.4 Rough handling. The shop(s) (Type II and III) shall withstand stresses without damage to or displacement of any component when exposed to shock and vibration such as occurring in rail transportation with humping at 10 miles per hour (mph), minimum.

3.11 Environmental conditions.

3.11.1 Precipitation. The shop shall withstand accumulation of water to the interior of the shop or damage to components when exposed to natural or simulated rain fall, that which would inhibit shop operations.

3.11.2 Temperature(s) (storage and operating).

3.11.2.1 Storage. The shop(s) (Type II and III) with all equipment shall be capable of withstanding an ambient temperature range of -50 ±5 degrees Fahrenheit (F) in storage without encountering any adverse effects or damage. The complete shop(s) shall be operated when returned and stabilized to ambient temperature.

3.11.2.2 Operational temperature(s). The shop(s) (Type II and III) shall perform as specified below in any ambient temperature between -25 ±2 degrees F and +120 ±5 degrees F:

(a) Following a 24 hour soak period at -25 ±2 degrees F and while at that temperature operate all portable electric power tools flood lights, trouble lights and electric welder (Type II) from the shop installed power source. Slave starting of the government furnished vehicle may be attempted if starting difficulties are encountered (see 6.7.8). When returned to ambient temperature the complete shop shall be operated.

(b) Following a 24 hour soak period at +120 ±5 degrees F and while at that temperature, operate all shop equipment from the shop installed power source.

3.11.3 Sound level. The sound level of the shop(s) (Type I, II and III) shall be in accordance with MIL-STD-1474, Category D, for steady-state noise. Hearing protectors need not be supplied with the shop equipment. Hazard signs, if required, shall state: "Caution, Hearing Protection Required" when (name of tool or equipment) is operating.

3.12 Reliability. The shop equipment (Types I, II, and III) shall demonstrate a mission reliability of at least 0.90 when measured with mean time between failures (MTBF).

3.13. Availability. The shop equipment availability shall be not less than 95 percent.

3.14 Maintainability. The shop equipment (Type I, II and III) shall require a minimum of operational and in-storage maintenance. Replacement components will be used to the maximum extent possible. The shop equipment shall require a minimum of man-hours and skill to accomplish maintenance. Ease of maintenance and restricted use of components requiring special skills or tools for maintenance will be stressed. The maintenance ratio shall be no greater than 0.12 (see 6.7.1).

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T04:00Z
Check the source to verify that this is the current version before use.

3.15 Fuels, lubricants, and coolants. The shop(s) shall be assembled and tested with the products of the type and grade specified in table I for the applicable ambient air temperature. The shops shall operate as specified herein when furnished with these products (see 6.5).

TABLE I. Service products

Item	Application	Specification	Type and Grade
1	Engine:		
	a. Heavy Duty	MIL-L-2104	10, 30
	b. Arctic	MIL-L-46167	One Grade
2	Grease:		
	a. Automotive	MIL-G-10924	One Grade
	b. High Temperature	MIL-G-23827	One Grade
3	Hydraulic-system Oil:		
	a. Oil	MIL-L-2104	10
	b. Oil (low temperature)	MIL-L-46167	One Grade
4	Lubricating Oils:		
	Universal	MIL-L-2105	80, 90, 140
5	Antifreeze:		
	a. Ethylene glycol	O-A-548	One Grade
	b. Arctic	MIL-A-11755	One Grade
6	Brake Fluid:	VV-B-680	One grade

3.15.1 Oil lubrication. Unless otherwise specified herein, all components shall be filled to the operating level with military oils designated for use in the temperature range at the shipping destination. A tag shall be attached in a conspicuous place to indicate the temperature range and grade of lubricant used.

3.16 Fungus control. Components of electrical circuitry that are hermetically sealed or inherently resistant to fungus growth and moisture need not be treated. Components of electrical circuitry that are not inherently resistant to fungus growth or moisture shall be treated in accordance with MIL-T-152 and MIL-V-173.

3.17 Identification marking and instruction plates.

3.17.1 Identification marking. The unit shall be identified in accordance with MIL-STD-130.

3.17.2 Instruction plates. Instruction plates shall conform to MIL-P-514, Type III, Composition C, or Type I, Style 1, Composition A, Class 2.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T04:00Z
Check the source to verify that this is the current version before use.

3.18 Treatment and painting. The shop body and all other items requiring paint shall be cleaned, treated, and painted with a chemical agent resistant coating in accordance with finish 7.3.1 plus 20.2401, color Green 383, of MIL-STD-171 for aluminum alloys or finish 5.1.1 plus 20.24.1, color Green 383, of MIL-STD-171 for ferrous alloys. The external areas of the body shall be painted in a camouflage pattern in accordance with drawing 13226E7548.

3.19 Government-furnished property. Unless otherwise specified (see 6.2.1), the Government shall furnish the 1 1/4 ton, 4x4, M1031 truck chassis.

The truck chassis shall be modified by the supplier in accordance with TA13217E8300 and as specified herein.

3.20 Workmanship. Standards of workmanship shall be such that the shop shall have the safety, stability, and operating characteristics specified herein and shall be free of defects that could adversely affect its intended use.

4. QUALITY ASSURANCE PROVISIONS

4.1 Responsibility for inspection. Unless otherwise specified in the contract, the contractor is responsible for the performance of all inspection requirements as specified herein. Except as otherwise specified in the contract, the contractor may use his own or any other facilities suitable for the performance of the inspection requirements specified herein, unless disapproved by the Government. The Government reserves the right to perform any of the inspections set forth in the specification where such inspections are deemed necessary to assure supplies and services conform to prescribed requirements.

4.1.1 Responsibility for compliance. All items must meet all requirements of sections 3 and 5. The inspection set forth in this specification shall become a part of the contractor's overall inspection system or quality program. The absence of any inspection requirements in the specification shall not relieve the contractor of the responsibility of assuring that all products or supplies submitted to the Government for acceptance comply with all requirements of the contract. Sampling in quality conformance does not authorize submission of known defective material either indicated or actual, nor does it commit the Government to acceptance of defective material.

4.1.2 Component and material inspection. The contractor is responsible for ensuring that components and materials used are manufactured, tested, and inspected in accordance with referenced specifications and standards.

4.1.3 Preparation for examination and tests. Prior to examination and test, the shop shall be lubricated with oils and greases specified in 3.15, table I. Oils shall be those designated for use in the ambient temperature at which the examinations and tests are being performed.

4.2 Classification of inspection. Inspection shall be classified as follows:

a. First article inspection (see 4.3).

b. Initial production test (see 4.4).

c. Quality conformance inspection (see 4.5).

d. Inspection comparison (see 4.7).

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T04:00Z
Check the source to verify that this is the current version before use.

e. Packaging inspection (see 4.8).

4.3 First article inspection. When procurement is for more than one configuration of shop equipment first article inspection is applicable to each configuration (see 3.2 thru 3.2.3).

4.3.1 Examination. Each shop shall be examined for the defects marked "X" in Column 3 of table II. Presence of one or more defects shall be cause for rejection.

4.3.2 Tests. Each shop shall be tested as specified in Column 4 of table III. Failure of any test shall be cause for performing the inspection specified in 4.3.3.

4.3.3 Disassembly inspection. The first article shop failing a performance test shall be disassembled in the presence of a Government representative to the extent necessary to determine the cause of the failure. Each disassembled part shall be inspected in detail for compliance with this specification and referenced drawings in regard to materials, dimensions, and tolerances. Parts not complying with such requirements shall be rejected. Reassembly with accepted parts and retesting shall be the responsibility of the contractor.

4.4 Initial production test. When procurement is for more than one configuration of shop equipment initial production test is applicable to each configuration (see 3.2 thru 3.2.3). When specified (see 3.3), one or more initial production shops shall be selected at random by the Government from shops being produced from "X" in Column 4 of table II and subjected to the tests marked "X" in Column 5 of table III to determine conformance to the requirements of this specification. The inspection will be performed by the Government at a site selected by the Government. Acceptance of an initial production shop shall not exclude the remaining shops from the quality conformance inspection and acceptance provisions specified in section 4. In addition to any test specified as part of the initial production test, the Government reserves the right to conduct any and all other tests contained in this specification as part of the initial production test and failure of such additional tests shall have the same effect as failure of those tests specified as initial production tests.

4.4.1 Inspection failure. Failure of an initial production shop to meet any requirement specified herein during and as a result of the examination and tests specified in 4.4 shall be cause for rejection of the initial production shop and shall be cause for refusal by the Government to continue acceptance of production shops until evidence has been provided by the contractor that corrective action has been taken to eliminate the deficiencies. Correction of such deficiencies shall be accomplished by the contractor at no cost to the Government on shops previously produced and accepted under the contract. Any deficiencies found as a result of the initial production inspection will be considered prima facie evidence that all shops accepted prior to the completion of initial production inspection are similarly deficient, unless evidence to the contrary is furnished by the supplier and such evidence is acceptable to contracting officer.

4.5 Quality conformance inspection.

4.5.1 Examination. Each shop shall be examined for the defects marked "X" in Column 5 of table II. Presence of one or more defects shall be cause for rejection.

4.5.2 Tests. Each shop shall be subjected to the tests marked "X" in Column 6 of table III. Failure of any test shall be cause for rejection.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T04:00Z
Check the source to verify that this is the current version before use.

4.6 Inspection schedule.

4.6.1 Examination. Examination shall be in accordance with table II.

4.6.2 Tests.

4.6.2.1 Test. Tests shall be in accordance with table III. Sequence of the testing shall be at the option of the test facility, except as specified in the paragraphs herein.

4.6.2.2 Electric power system.

4.6.2.2.1 Maximum power operation. Operate the alternator at 208 volts, 3 phase, 4 wire, AC power with a resistive load of 4.6 KW line to ground on each of the three phases for 2 hours in 10 minute cycles of continuous load for 6 minutes followed by 4 minutes of no load. Nonconformance of the electrical components to 3.2.1 and 3.6.2.1, failure of other mechanical components, or failure to provide maximum power, shall constitute failure of this test.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T04:00Z
Check the source to verify that this is the current version before use.

TABLE II. Examination schedule.

Defect	Requirement Paragraph	First Article	Initial Production	Quality Conformance
1	2	3	4	5
Dimensions not as specified	3.2 and 3.5.1	X	---	---
Parts, Components, Tools, or equipment missing, or not functioning as specified.	3.2 and 3.7	X	X	X
Material not as specified	3.4	X	---	X
Stowage or tiedowns not as specified	3.8	X	X	X
Lifting and tiedown not as specified	3.5.3	X	X	---
Safety devices and guards missing or not as specified	3.9	X	X	X
Lubrication not as specified.	3.15	X	X	X
Fungus and moisture resistance not as specified	3.16	X	---	X
Accessories, identification or other marking, operating and safety instructions, or manuals missing.	3.17	X	X	X
Treatment or painting not as specified	3.18	X	---	X
Workmanship not as specified	3.20	X	X	X

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T04:00Z
Check the source to verify that this is the current version before use.

TABLE III. Test schedule.

Test	Test Paragraph	Requirement Paragraph	First Article	Initial Production	Quality Conformance
1	2	3	4	5	6
Power Tools	4.6.2.2.2.1	3.2 and 3.6.2.1	X	X	X
Welding	4.6.2.2.2.2	3.2.2	X	X	---
Air Transportability	4.6.2.4	3.5.1	X	X	---
Shop weight	4.6.2.3	3.5.2	X	X	---
Load Test Multpurpose Eyes	4.6.2.5.1	3.5.3	X	X	---
Air Compressor	4.6.2.2.2.3	3.6.1	X	X	X
Maximum Power Operation	4.6.2.2.1	3.6.2.1	X	X	---
Roadability	4.6.2.6	3.10.3	X	X	---
Impact Testing	4.6.2.7	3.10.4	X	X	---
Environmental	4.6.2.9	3.11	X	X	---
Sound Level	4.6.2.8	3.11.2	X	---	---
Reliability	4.6.2.10	3.12	---	X	---
Availability	4.6.2.11	3.13	---	X	---
Maintainability	4.6.2.12	3.14	---	X	---
Protective Finish	4.6.2.13	3.18	X	X	X

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T04:00Z
Check the source to verify that this is the current version before use.

4.6.2.2.2 Equipment and power tools.

4.6.2.2.2.1 Power tools. In all Type II and Type III contact maintenance units, operate the alternator at 208V, 3 phase, 60 HZ or 120 V, single phase, 60 HZ to operate each of the power tools. Operate each of the power tools for 2 minutes using the correct power requirement for each tool. Inability of the alternator to produce maximum power, or malfunction of any component or tool, shall constitute failure of this test.

4.6.2.2.2.2 Welding. Only Type II contact maintenance vehicles will contain welding units. Conduct a test on the welding unit as follows. Operate the alternator on 208 V, 3 phase 60 HZ power. Using straight polarity, a qualified arc welding operator shall deposit 3 linear feet of weld at the minimum output, 3 linear feet at intermediate output, and 3 linear feet at a maximum output. Repeat the test using reverse polarity. Inability of the alternator to produce maximum power, or failure to maintain a steady arc at any output and at either polarity, shall constitute failure of this test (see 3.2.2).

4.6.2.2.2.3 Air compressor. To the output side of the air storage tank install a pressure gage, pressure control valve and flow meter. With the compressor operating, adjust the output pressure to 100 ±2 psig using the pressure control valve. Flow shall be no less than 3.0 cfm. Failure to produce 3.0 cfm shall be cause for rejection (see 3.6.1).

4.6.2.3 Shop weight. Load the Type I, II and III vehicles with a full supply of fuel and lubricating fluids up to their specified levels and weigh the vehicles on a scale with a ±1 percent accuracy (see 3.5.2).

4.6.2.4 Air transportability. Inspect all outside dimensions given on TA13217E8300 of the Shop Equipment Contact Maintenance Vehicle, Types I, II and III. Outside dimension shall not exceed those given on TA13217E8300 (see 3.5.1).

4.6.2.5 Lifting and tiedown provisions. Slinging and tiedown provisions on Type I, Type II and Type III on Contact Maintenance Shop Equipment vehicles shall be per MIL-STD-209 (see 3.5.3). The following paragraphs in this specification apply for inspection.

a. Paragraph 4.1.1 Number. The number of lifting and tiedown eyes are as specified.

b. Paragraph 4.1.2 Location. The location of the eyes are as specified.

c. Paragraph 4.1.4 Multipurpose, slinging and tiedown provision finish. The material finish shall be as specified.

d. Paragraph 4.1.5 Marking. The shipping data plate and stenciled identification of lifting, tiedown, or multipurpose provisions shall be as specified. The allowable load of each lifting, tiedown, or multipurpose provision shall be stamped or etched on the provision.

e. Paragraph 5.2 Eye and provision dimensions. The slinging and tiedown eyes shall conform to applicable class and associated figures for dimensions, clearances and requirements.

4.6.2.5.1 Load test of multipurpose eyes. Lifting and tiedown provisions shall be tested in accordance with 5.1.3 of MIL-STD-209.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T04:00Z
Check the source to verify that this is the current version before use.

4.6.2.6 Road tests. Load the shop with the tools and equipment specified herein plus additional weight to 9000 pound GVW (see 3.10.3) and perform tests (a) thru (d). For test in (a), (b), and (c), attach a 3000 pound towed load. For tests in (c) and (d) there shall be no towed load.

a. Unimproved roads. Drive the shop 350 miles on unimproved roads at maximum safe speeds. The course shall consist of poorly maintained gravel and dirt roads with rutting and occasional potholes.

b. Cross-country/trails. Drive the shop 150 miles on cross-country/trails at maximum safe speeds. The course shall consist of native soil with rock added as required to maintain passability. Surface conditions shall range from smooth to rough with rutting, potholes and depressed areas.

c. Chatter course. Drive the shop over a chatter course until at least 2600 either upward or downward accelerations of magnitudes specified herein have been applied to a rear wheel center. The course shall be of construction that the acceleration magnitudes specified below can be obtained by adjusting the vehicle speed without the frequency of the accelerations exceeding 15 cycles per second (cps) or becoming less than 3 cps. The maximum acceleration magnitude indicated below shall not be exceeded, and accelerations having magnitudes less than the minimum shall be disregarded. The course shall be of such length that a wheel center receives in one pass over the course at least 50 consecutive vertical acceleration cycles of any magnitude less than the maximum specified herein. Measure the accelerations by a trial test to establish the required vehicle test speed. Then disconnect the recording instruments and complete the test at established speed. The acceleration values used shall be those of the wheel center receiving the highest accelerations. Means for assuring that the vehicle test speed is held constant throughout the test shall be provided. Accelerations shall be measured on a running-gear member, usually an axle or spindle, that has a motion identical to that of the wheel center. The magnitude of the acceleration shall be not less than 4 Gravity (G's) nor more than 7 G's.

d. Diagonal ditch course. Drive the shop over a series of ditches until 600 reversal torsional frame stresses have been applied. The ditch profile shall be such as to allow vertical wheel travel of 18 inches from crest to root. The ditches shall be at 45 degrees to the centerline of the course and spaced a sufficient distance apart to allow only one rear wheel and one front wheel of opposite sides in the ditches at any one time.

Examine the shop at the completion of each phase of the road test. Damage to or displacement (see 6.7.2) of any component, accessory, part or tool; evidence of defective welded, bolted, or riveted connections excluding the Government furnished chassis shall constitute failure of these road tests.

4.6.2.7 Impact testing. (see 3.10.4).

a. Test equipment. The following equipment is required:

(1) Five railroad cars and one flatcar equipped with standard gear couplings.

(2) Some means of moving the cars.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T04:00Z
Check the source to verify that this is the current version before use.

(3) Some means to determine accurately within plus or minus 5 percent the speed at the time of impact.

b. Procedure. Mount the shop in direct contact with the car floor with the front toward the impact end of the flatcar. Block and secure the shop to prevent any longitudinal, vertical, or side movement. Hump the loaded flatcar at a speed of not less than 10 mph against the five cars with their draft gear extended and brakes set. Examine the shop for physical damage. Record on data sheet all readings taken during test and condition of shop after test. Reverse the direction of impact and repeat the test. Evidence of any damage or permanent deformation of any part or component of the shop, excluding the Government-furnished chassis, shall constitute failure of this test.

4.6.2.8 Sound level measurement. Operate the shop at governed speed with the alternator and air compressor operating. Measure the sound level at the tailgate work station while operating each of the power tools. Sound level in excess of Category D of MIL-STD-1474 shall require the installation of hazard signs as specified in 3.11.3.

4.6.2.9 Environmental.

4.6.2.9.1 Rain test. Put the shop on a horizontal surface and expose the shop to natural or simulated rain falling toward the shop at an angle of approximately 45 degrees to the horizontal. The volume of rain impinging on the surface shall be not less than two inches in a five minute period. Simulated rain shall originate from a source which produces droplets of uniform distribution and velocity similar to natural rain at the point of contact with the shop. Conduct the test as follows:

a. Expose the top and left side to the rain as described above for a period of five minutes.

b. Repeat step "a" with the top and front exposed.

c. Repeat step "a" with the top and right side exposed.

d. Repeat step "a" with the top and rear exposed.

Nonconformance to 3.11.1 shall constitute failure of this test.

4.6.2.9.2 Temperature (storage and operation)tests. Place the shop(s) (Type II and III) in an ambient temperature of -50 $\pm$5 degrees F for a period not less than 72 hours (see 3.11.2.1). At the end of this period raise the temperature to -25 $\pm$2 degrees F for a period not less than 12 hours. At the end of this time period the temperature at -25 $\pm$2 degrees F, the following operational tests shall be performed (see 3.11.2.2):

a. Inspect the entire unit for any damage which may have resulted from exposure to temperature extreme.

b. Start and operate the alternator. It shall provide electrical power to both the 120/208 volt system.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T04:00Z
Check the source to verify that this is the current version before use.

c. Start and operate individually all portable electric power tools, flood lights and trouble lights from the shop installed power source for a minimum of 2 minutes.

d. Operate the electric welder (Type II) in straight polarity and deposit two 6 inch beads at near minimum and at near maximum output. Repeat the test using reverse polarity.

After the conclusion of the operating test at -25 ±2 degrees F, stop all equipment, close up the unit, and raise the ambient temperature to +70 ±5 degrees F. When stabilized at +70 ±5 degrees F, start and operate individually all installed equipment and power tools from the shop installed power source for a minimum of 5 minutes. After the conclusion of the operating test at +70 ±5 degrees F, stop all equipment, close up the unit, and raise the ambient temperature to +120 ±5 degrees F for a period of 24 hours. After the 24 hours, soak at +120 ±5 degrees F, start and operate individually all installed equipment and power tools from the shop installed power source for a minimum of 2 minutes. Nonconformance to 3.11 shall be cause for rejection of the unit.

4.6.2.10 Reliability. The initial production shop shall be tested for a total of ten missions to determine conformance to the requirements of 3.12. Data shall be gathered to evaluate the system reliability. Reliability is to be evaluated from MTBF and mission operating time (see 6.7.4 and 6.7.5).

$$\text{Reliability} = e^{-t/u}$$

where,

t = mission operating time, hour
u = mean time between failures (MTBF), hour
e = 2.718

The shop shall be considered to have demonstrated the required reliability if zero chargeable reliability failures occur (see 6.7.3).

4.6.2.10.1 Mission operation and test. A mission shall consist of the following:

a. Drive the fully loaded shop set at maximum safe speeds for ten miles on unimproved roads and ten miles on cross-country trails.

b. Using the instructions furnished with the shop, set up the shop for operation.

c. Operate each installed equipment and power tool for a period not less than 5 minutes one time per mission, except as noted.

d. Prepare the shop for movement to another location, to begin the next mission.

Nonconformance with 3.12 shall constitute failure of this test.

4.6.2.11 Availability. During the performance of the reliability test as specified in 4.6.2.10, data shall be gathered to evaluate the system availability. Availability is to be evaluated with respect to operating time and corrective maintenance (see 6.7.5 and 6.7.6).

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T04:00Z
Check the source to verify that this is the current version before use.

$$\text{Availability} = \frac{(\ \text{MTBUMA}\ )}{(\text{MTBUMA} + \text{MTTR})}\ (100 \text{ percent})$$

where,

MTBUMA = Mean time between unscheduled maintenance actions (unscheduled means corrective maintenance actions).

MTTR = Mean time to repair (use only times associated with corrective maintenance) (see 6.8.7).

The system availability requirement shall conform to 3.13. Nonconformance with 3.13 shall constitute failure to meet the availability requirement.

4.6.2.12 Maintainability. Maintenance operations required during first article and initial production tests shall be gathered to evaluate the system maintainability. Maintainability is to be evaluated with respect to total maintenance man-hours and total operating time during testing.

$$\text{Maintenance Ratio} = \frac{\text{TNMMT}}{\text{TOT}}$$

where,

TNMMT = Total number of man-hours of maintenance (scheduled maintenance and unscheduled repairs) during testing.

TOT = Total operating time (see 6.7.5).

Any support elements, i.e., technical publications, repair parts, special tools, etc., provided under the contract for assisting or conducting maintenance shall be evaluated. The system maintenance ratio shall conform to 3.14. Nonconformance with 3.14 shall constitute failure of this test.

4.6.2.13 Protective finish test. The hardness adhesion and thickness of the paint used on the Type I vehicle shall be determined (see 3.18) as follows:

a. The graphite point of a sharpened HB lead pencil shall be pressed at a right angle into a painted area of the vehicle until the graphite crumbles. Failure of the surface to withstand the test, as evidenced by a pitting of the paint, shall be cause for rejection.

b. A test sample of the same metal, painted with the same process and at the same time as the vehicle, shall have a sharpened H lead pencil pressed into the paint as on "a". Failure of the surface to pit (paint too hard) shall be cause for rejection.

c. Two two-inch intersecting lines shall be cut through the paint to the base metal of the test sample. A strip of 1/2 inch wide fiberglass tape shall be firmly pressed over the intersection and then pulled from the surface. Adhesion of any paint to the tape shall be cause for rejection.

d. Using a paint thickness measuring instrument, or by masking a portion of the test sample during painting, measure the thickness of the paint. Failure of the paint to be at lease the thickness specified on the applicable drawings shall be cause for rejection.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T04:00Z
Check the source to verify that this is the current version before use.

4.7 Inspection comparison. The Government may select shops at any time during the contract production period and subject these shops to the examination specified in Column 4 of table II and the tests specified in Column 5 of table III to determine conformance to the requirements of this specification. The inspection will be performed by the Government at a site selected by the Government. Shops will be selected at random from those which have been accepted by the Government and will not include the previously inspected first article model or initial production model. In addition to any test specified as part of the inspection comparison, the Government reserves the right to conduct any and all other tests contained in this specification as part of the inspection comparison and failure of such additional tests shall have the same effect as failure of those tests specified as inspection comparison.

4.7.1 Inspection failure. Failure of an inspection comparison shop to meet any requirement specified herein during and as a result of the examination and test specified in 4.7 shall be cause for rejection of the inspection comparison shop and shall be cause for refusal by the Government to continue acceptance of production shops until evidence has been provided by the supplier that corrective action has been taken to eliminate the deficiencies. Correction of such deficiencies shall be accomplished by the supplier at no cost to the Government on shops previously produced and accepted under the contract. Any deficiencies found as a result of inspection comparison inspection will be considered prima facie evidence that all shops accepted after approval of the initial production shop are similarly deficient unless evidence to the contrary is furnished by the contractor and such evidence is acceptable to the contracting officer.

4.8 Packaging inspection. The items shall be inspected before and after packaging to determine compliance with the preservation, packaging, packing and marking requirements specified in Section 5.

5 PACKAGING

5.1 Preservation. Preservation shall be Level A, Level B, or Level C, as specified (see 6.2.1).

5.1.1 Level A.

5.1.1.1 Preservatives. Preservatives specified herein shall conform to MIL-P-116.

5.1.1.2 Methods. Methods of preservation specified herein shall conform to MIL-P-116.

5.1.1.3 Sets or kits. When items are furnished in sets of kits with a carrying case, the items shall be preserved as specified herein and, when possible, replaced in the case.

5.1.1.4 Items having mounting brackets or holders. Items furnished with mounting brackets or holders shall be preserved a specified herein and, when possible, replaced in the bracket or holder and secured to prevent movement and damage.

5.1.1.5 Unprotected surfaces. Unprotected exterior metal surfaces of the components, not specifically specified herein, requiring the application of a contact preservative in accordance with MIL-P-116 shall be preserved as follows.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T04:00Z
Check the source to verify that this is the current version before use.

5.1.1.5.1 Machined surfaces. Exposed exterior machined surfaces shall be coated with Type P-2, P-6 or P-11 preservative. The coated surfaces shall be wrapped or covered with barrier material conforming to MIL-B-121, Type I, Grade A, Class 2 and secured in place with tape conforming to PPP-T-60, Type IV.

5.1.1.5.2 Unfinished surfaces. Unfinished surfaces shall be coated with Type P-1 preservative.

5.1.1.6 Truck chassis. The truck chassis with mounted body shall be preserved in accordance with the Level A (mobile) preservation and packaging requirements of MIL-STD-281.

5.1.1.7 Alternator.

5.1.1.8 Handtools and tool sets. Handtools and tool sets shall be preserved in accordance with the Level A requirements of PPP-P-40.

5.1.1.9 Belts and pulleys. All drive belts shall be released from tension or removed. Unpainted, unplated ferrous metal surfaces of the pulley shall be coated with primer conforming to TT-P-664. Removed belts shall be secured convenient to the pulley for which intended.

5.1.1.10 Chain hoist. The chain and any other unpainted metal surface of the hoist shall be coated with Type P-2 preservative. The hoist shall be wrapped in paper conforming to MIL-B-121, Type I, Grade A, Class 2, and packaged in a close-fitting box conforming to PPP-B-636, Domestic Type.

5.1.1.11 Items furnished in commercial containers. Items which are commercially packaged in sealed cans, pails, drums, jars or tubes shall not require preservation.

5.1.1.12 Method III. Straight adapters, electrical and ground clamps, fitting kits, insert and tool assortment kits, rubber hose, and brass nipples shall be individually preserved Method III.

5.1.1.13 Method IC-2. The first aid kit, floodlight, and moisture stabilizer shall be preserved Method IC-2. The container shall be the contractor's commercial container or a close-fitting box conforming to PPP-B-566 or PPP-B-636, Class Domestic.

5.1.1.14 Locks and keys. The interior of locks shall be coated with powdered graphite and the locks operated to assure penetration of the graphite.

The keys shall be preserved Method III and forwarded to destination separately by registered mail. A cloth or paper shipping tag containing the shop equipment identification number and the registration number shall be attached to the related keys for future positive identification.

5.1.1.15 Fire extinguisher. Unpainted exterior metal surfaces of the fire extinguisher requiring the application of a contact preservative in accordance with MIL-P-116 shall be coated with Type P-1 preservative. The extinguisher shall be placed in the mounting bracket and secured.

5.1.1.16 Electronic and electrical equipment. Electronic and electrical equipment and accessories, shall be preserved and packaged in accordance with MIL-E-17555, Level A.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T04:00Z
Check the source to verify that this is the current version before use.

5.1.1.17 Other tools and equipment. Tool and equipment items which are not specifically covered by the packaging requirements of this specification shall be preserved and unit packaged in accordance with Level A requirements of the applicable commodity specification of MIL-T-45542. Unit containers shall be non-weather-resistant grade.

5.1.1.18 Technical publications. Technical publications shall be preserved in accordance with MIL-P-116, Method IC-1 or IC-3.

5.1.1.19 Welding and soldering equipment. Welding and soldering equipment shall be preserved in accordance with Level A preservation and packaging requirements of MIL-W-45562.

5.1.1.20 Miscellaneous supplies and equipment. Items, equipment, and components not specifically identified herein, shall be preserved as specified for supplies and equipment of similar design and construction.

5.1.1.21 Consolidation. Components that cannot be placed in the drawer, toolboxes, or compartments, or secured by the mounting brackets or holders provided, shall be consolidated together in close-fitting boxes conforming to PPP-B-566 or PPP-B-636 Domestic Type. The boxes shall be of a size to fit into the available space within the body. The contents shall be blocked, braced, and cushioned as applicable to prevent movement and damage to the contents within the box.

5.1.2 Level B. Preservation shall be as specified for Level A with the following exceptions.

5.1.2.1 Truck chassis. The truck chassis with mounted body shall be preserved in accordance with the Level B (mobile) preservation and packaging requirements of MIL-STD-281.

5.1.2.2 Handtools and tool sets. Handtools and tool sets shall be preserved in accordance with the Level B requirements of PPP-P-40.

5.1.2.3 Welding and soldering equipment. Welding and soldering equipment shall be preserved in accordance with Level B preservation and packaging requirements of MIL-W-45562.

5.1.3 Level C. Level C preservation of the truck chassis with mounted body and all shop equipment shall be in accordance with MIL-STD-1190 and as specified herein. Components shall be placed and secured in the compartment provided. Toolboxes, drawers, mounting brackets, and holders shall be utilized to the greatest extent possible.

5.2 Packing (see 6.8). The truck mounted shop, with equipment enclosed, shall be prepared for shipment mobile in a manner to assure carrier acceptance and safe delivery to destination at lowest ratings. Items and equipment, installed in the shop body, and any other movable equipment or items, shall be cushioned, blocked, braced, and anchored to prevent damage to the equipment or to the body. All doors and drawers shall be secured to prevent accidental opening and in a manner to prevent pilferage of contents.

5.3 Marking.

5.3.1 Military. Marking for military levels of protection shall be in accordance with MIL-STD-129.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T04:00Z
Check the source to verify that this is the current version before use.

6 NOTES

6.1 Intended use. The contact maintenance shop is intended for use by personnel engaged in the maintenance of military mechanical equipment.

6.2 Ordering data.

6.2.1 Acquisition requirements. Acquisition documents should specify the following:

a. Title, number, and date of this specification.

b. First article when required (see 3.1).

c. When initial production inspection is required and number of shops to be furnished (see 3.3).

d. Gross vehicle weight, if different (see 3.5.2).

e. Government-furnished property, if different (see 3.19).

f. Level of preservation and packaging required (see 5.1).

6.3 The contracting officer should arrange to furnish information concerning items specified in set SC-4940-95-C1-B21 or SC-4940-95-CL-B22 (see 3.1).

6.4 Technical interface data. The contracting officer should arrange to provide information concerning technical interface for the government furnished truck chassis specified in 3.19.

6.5 Lubricants. When requested by the contractor, the contracting officer should obtain a list of military lubricants applicable to the shop covered by this specification as contained in the Federal Supply Catalog, Department of Defense Section, Identification List C9100-IL, for FSC Group 91 (see 3.15).

6.6 Government-furnished property. The contracting officer should arrange to furnish the supplier the property specified in 3.19.

6.7 Definitions.

6.7.1 Maintenance ratio. The ratio of the number of maintenance man-hours required for both scheduled maintenance and unscheduled repairs, to the number of hours of operation (see 3.14).

6.7.2 Displacement. Displacement is defined as dislodgment of any tool or item of equipment from its designated position. Movement of a tool or item of equipment within its designated position without any dislodgment is permitted (see 3.13 and 3.10.3.

6.7.3 Chargeable reliability failure. A chargeable reliability failure is defined as any malfunction:

a. Which cannot be corrected by organizational repair or replacement action using the controls on equipment tools or parts.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T04:00Z
Check the source to verify that this is the current version before use.

b. Which causes or may cause:

(1) Failure to start operation.

(2) Cessation of operation.

(3) Degradation of performance below specified levels.

(4) Damage to the shop by continued operation.

(5) Safety hazards to personnel.

6.7.4 Mean-time-between-failure (MTBF). For a particular interval, the total functioning life of a population of an item divided by the total number of failures within the population during the measurement interval. The definition holds for time, cycle, miles, events, or other measure of life units (see 4.6.2.10).

6.7.5 Operating time (OT). Defined to be an 8-hour period per mission. This time does not include scheduled maintenance or unscheduled repair time. If the mission profile is completed in less than 8 hours, the balance is considered to be standby time (see 4.6.2.10 and 4.6.2.12).

6.7.6 Corrective maintenance action. Any test incident that requires unscheduled maintenance time and includes both reliability chargeable failures and nonchargeable incidents (see 4.6.2.11).

6.7.7 Mean time to repair (MTTR). The total corrective maintenance time in clock hours divided by the total number of corrective maintenance actions (see 4.6.2.11).

6.7.8 Slave starting. External electrical power applied to a vehicle whose batteries have become discharged/depleted which may receive electrical battery voltage from an outside source through a slave cable plugged into the slave receptacle (see 3.11.2.2a).

6.8 Packing (see 5.2). Levels of packing have not been included for the truck mounted shop equipment as the nature of the item is such that only mobile packing is appropriate. For purposes of preservation and packing level markings, the level of packing should be considered Level A and should be marked A/A.

6.9 Contract data requirements. Required technical data such as operator's manuals, parts lists, and other instructions for operation and maintenance, as identified on a numbered DD Form 1664, should be specified on a DD Form 1423 incorporated in the contract.

6.10 Provisions. The contracting officer should include provisioning requirements for repair parts and maintenance tools as necessary (including any special tools), and instructions on shipment as shops.

6.11 Ear protection. When the noise level exceeds Category D of MIL-STD-1474, the operator's manual for the shop should include appropriate instructions for use of hearing protection when using equipment that produces noise above 85 decibel (dB)(A) inside and outside of the shop, and within a distance from the shop at which 85 dB(A) will be met.

6.12 Subject term (key word) listing.

Source: https://assist.dla.mil - Downloaded: 2026-10-22T04:00Z
Check the source to verify that this is the current version before use.

Alternator
Environmental
Roadability
Tools and equipment
Truck chassis
Maintainability
Mission
Reliability

6.13 Changes from previous issue. Asterisks are not used in this revision to identify changes with respect to the previous issue due to extensiveness of the changes

Custodian:
Army - AL

Preparing activity:
Army - AL

Project No. 4940-A517

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T04:00Z
Check the source to verify that this is the current version before use.

INSTRUCTIONS: In a continuing effort to make our standardization documents better, the DoD provides this form for use in submitting comments and suggestions for improvements. All users of military standardization documents are invited to provide suggestions. This form may be detached, folded along the lines indicated, taped along the loose edge *(DO NOT STAPLE)*, and mailed. In block 5, be as specific as possible about particular problem areas such as wording which required interpretation, was too rigid, restrictive, loose, ambiguous, or was incompatible, and give proposed wording changes which would alleviate the problems. Enter in block 6 any remarks not related to a specific paragraph of the document. If block 7 is filled out, an acknowledgement will be mailed to you within 30 days to let you know that your comments were received and are being considered.

NOTE: This form may not be used to request copies of documents, nor to request waivers, deviations, or clarification of specification requirements on current contracts. Comments submitted on this form do not constitute or imply authorization to waive any portion of the referenced document*(s)* or to amend contractual requirements.

(Fold along this line)

(Fold along this line)

DEPARTMENT OF THE ARMY

NO POSTAGE NECESSARY IF MAILED IN THE UNITED STATES

OFFICIAL BUSINESS
PENALTY FOR PRIVATE USE $300

BUSINESS REPLY MAIL
FIRST CLASS PERMIT NO. 12062 WASHINGTON D. C.

POSTAGE WILL BE PAID BY THE DEPARTMENT OF THE ARMY

Commander
US Army Armamrnt ,Munitions & Chemical
Command Armament Research and Development
CEnter (ARDC)
ATTN: SMCAR-EST-S
Rock Island, O; 61299-7300

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T04:00Z
Check the source to verify that this is the current version before use.

STANDARDIZATION DOCUMENT IMPROVEMENT PROPOSAL

(See Instructions – Reverse Side)

1. DOCUMENT NUMBER	2. DOCUMENT TITLE

3a. NAME OF SUBMITTING ORGANIZATION	4. TYPE OF ORGANIZATION *(Mark one)*
	☐ VENDOR
b. ADDRESS *(Street, City, State, ZIP Code)*	☐ USER
	☐ MANUFACTURER
	☐ OTHER *(Specify)*: _____

5. PROBLEM AREAS

a. Paragraph Number and Wording:

b. Recommended Wording:

c. Reason/Rationale for Recommendation:

6. REMARKS

7a. NAME OF SUBMITTER *(Last, First, MI)* – Optional	b. WORK TELEPHONE NUMBER *(Include Area Code)* – Optional
c. MAILING ADDRESS *(Street, City, State, ZIP Code)* – Optional	8. DATE OF SUBMISSION *(YYMMDD)*

DD FORM 82 MAR 1426 PREVIOUS EDITION IS OBSOLETE.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T04:00Z
Check the source to verify that this is the current version before use.