A-A-50689
28 May 1990

COMMERCIAL ITEM DESCRIPTION

CRANE, RAILWAY, DIESEL, 25-TON CAPACITY

The General Service Administration has authorized the use of this commercial item description.

1. ABSTRACT.

1.1 This commercial item description covers the requirements for a diesel-engine-driven, self-propelled, standard gage railway crane, with a lifting capacity of 25 tons that is capable of using a 1.5 cubic yard clamshell bucket.

2. SALIENT CHARACTERISTICS.

2. 1 Components.

2.1.1 A railway car body, including Components. and steel plate deck, equipped with two 4-wheel swivel trucks for travel on a standard gage railroad track, and the necessary draft and brake gear shall be provided. Four hydraulically controlled outriggers, two on each side of the car, shall be fitted to the car body. Couplers shall be provided. The design and construction of the above components shall conform to all applicable sections of the AAR Manual of Standards and Recommended Practices.

2.1.2 A full revolving hydraulic superstructure with diesel engine powerplant and crane equipment mounted thereon shall be provided. All crane superstructure (including safety features) shall be in accordance with SAE 1063, SAE 765, ANSI B30.5, PCSA Standard Number 4 and the AAR Manual of Standards and Recommended Practices. The power transmission system used to rotate the superstructure shall be a hydraulic mechanical arrangement with a continuous rotation angle of not less than 360°. A load moment indicator (LMI) including a digital indicator of the boom angle, length of boom in feet (if applicable), drum rotation, radius, boom head height, safe working load, actual load and the load on hook shall be provided and shall conform to SAE J375, J376, J159 and J1180. An anti-two block indicator with visual warning and lockout shall be provided. The LMI shall lockout the controls to prevent the operator from going beyond the crane capacity limits. The minimum boom length shall be 60 feet. Wire rope shall be 6 x 19 class, improved plow steel with design factors complying with ANSI B30.5. The rope length shall be sufficient to lower the hook 25 feet below the top of the the rail with the boom at minimum radius and the hook block reeved with the maximum parts of line. The main hook block shall have adequate weight to insure payout of the cable without load on the hook when the hook is in any position. The hook shall be a swivel type and shall be designed to handle at least four times the maximum safe load based on ultimate tensile strength of the material. The hook shall be certified by ferromagnetic wet particle inspection. When specified, a hydraulically operated clamshell bucket with teeth shall be provided. Bucket size shall be 1.5 cubic yard minimum. A combination hose reel and tagline reel shall be attached to control and actuate the bucket. The crane, with outriggers, shall be capable of lifting 50,000 pounds at a minimum radius of 10 feet.

2.2 Operating temperature. The rail crane shall be capable of operating at temperatures from -20°F to +120°F.

Beneficial comments, recommendations, additions, deletions, clarifications, etc., and any other data which may improve this document should be sent by letter to: WR-ALC/MMVRS, Robins AFB, GA 31098

FSC 2230

DISTRIBUTION STATEMENT A - Approved for public release; distribution is unlimited.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T08:45Z
Check the source to verify that this is the current version before use.

3. CONTRACTOR CERTIFICATION.

3.1 The contractor shall certify and maintain substantiating evidence that the product offered meets the salient characteristics of this commercial item description, and that the product conforms to the producer own drawings, specifications, standards and quality assurance practices and is the same product offered for sale in the commercial marketplace. Small businesses that cannot offer products with established commercial market acceptability may compete by submission of bid samples. The government reserves the right to require proof or to inspect for such conformance before first delivery and thereafter as may be otherwise provided for under the provisions of the contract.

4. PACKAGING.

4.1 Unless otherwise specified in the contract, each rail crane shall be preserved and packed in accordance with AAR requirements for interchange service to a degree of protection to preclude damage to the rail crane under normal shipping conditions to the DoD consignee within CONUS.

5. NOTES.

5.1 Applicable documents. The following documents form a part of this commercial item description to the extent specified herein. Unless otherwise specified, the issues of the documents which are Department of Defense (DoD) adopted shall be those listed in the issue of the DoDISS specified, the issues of the documents not listed in the DoDISS shall be those in effect on the date specified in the solicitation.

Association of American Railroads (AAR)

(Application for copies should be addressed to the Association of American Railroads, Mechanical Division, 50 F Street N.W., Washington D.C. 20001.)

Society of Automotive Engineers (SAE) Standards and Recommended Practices

(Application for copies should be addressed to the Society of Automotive Engineers, 400 Commonwealth Drive, Warrendale, PA 15096.)

Power Crane and Shovel Association (PCSA)

(Application for copies should be addressed to Construction Industry Manufacturers Association, Marine Plaza, Suite 1700,111 E. Wisconsin Avenue, Milwaukee, Wisconsin 53202.)

American National Standards Institute (ANSI)

(Application for copies should be addressed to the American National Standard Institute, 1430 Broadway, New York, NY 10017.)

5.2 Ordering data.

a. When a clamshell is required (see paragraph 2.1.2).

5.3 Intended use. Cranes covered by this specification are intended for wrecking service, heavy lifting and clamshell (where applicable).

Military Interests:

Civil agency coordinating activity:
GSA-FSS

Preparing activity:
Air Force - 84

CUSTODIANS:
Air Force - 99

Project number:
2230-0069

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T08:45Z
Check the source to verify that this is the current version before use.