MILITARY SPECIFICATION

LIGHTING SYSTEM, AIRPORT APPROACH, CONDENSER DISCHARGE SEQUENCE FLASHING, GENERAL REQUIREMENTS FOR

This amendment forms a part of Military Specification MIL-L-26311B(ASG), 10 August 1959, and has been approved by the Department of the Air Force and by the Bureau of Naval Weapons.

Page 1, paragraph 2.1: Delete the colon and add "to the extent specified herein:"

Page 1, under SPECIFICATIONS, Federal, delete the title of PPP-B-636 and substitute "Box, Fiberboard".

Page 2, under STANDARDS, Military, add: "MIL-STD-143 Specifications and Standards, Order of Precedence for the Selection of".

Page 2, paragraph 2.2:

(a) Delete the first sentence and substitute: "The following document forms a part of this specification to the extent specified herein."

(b) Delete "Drawings" and references thereunder and substitute:

"Specification

FAA-1106 Condenser-Discharge Sequenced Flashing Light System"

Page 3, paragraph 3.1: Add the following at end of paragraph: ", and has been listed on or approved for listing on the applicable Qualified Products List."

Page 3, paragraph 3.2.2, line 8: Delete: "Remote control monitor panel 1".

Page 5, paragraph 3.4, line 3: Delete "Specification MIL-D-70327" and substitute "Standard MIL-STD-143".

Page 5, paragraph 3.5.1, line 2: Delete "CAA-1106" and substitute "FAA-1106".

Page 6, paragraph 3.6.1, line 2: Delete "4.3.6" and substitute "4.5.6".

Page 6, paragraph 3.7.1, line 2: Delete "CAA-1106" and substitute "FAA-1106".

FSC 6210

Source: https://assist.dla.mil -- Downloaded: 2026-10-20T09:26Z
Check the source to verify that this is the current version before use.

Page 6, paragraph 3.7.1.1, lines 1 and 2: Delete the first sentence and substitute: "To assure proper venting, each of two sides of the elevated light housing shall be equipped with a 3/4-inch standard conduit elbow. The elbows shall be installed with the open ends downward to prevent rain from entering the vents. The open ends of the conduit elbows shall be provided with screens to prevent the entrance of insects. As an alternate and in lieu of conduit elbows, two rainproof louvers may be used. Openings in the louvers shall be provided with screens. With all housing openings temporarily sealed, the housing shall meet the water immersion test specified in 4.5.4."

Page 7, paragraph 3.7.2.4: Add "The type of flash tube used is optional, provided all applicable requirements are met."

Page 7, paragraph 3.7.2.5: Delete, and substitute:

"3.7.2.5 Containers.- The components of each flush light shall be housed in a single watertight container. The container shall be sufficiently watertight to pass a 2-psi internal air pressure test. The container shall be equipped with a readily removable cover to permit lamp and tube replacement and provide easy access to all components. Provisions shall be incorporated to permit the escape of moisture that may collect between the light window and the top assembly."

Pages 7 and 8, paragraphs 3.7.2.5.1.1 and 3.7.2.5.1.2: Delete.

Page 8, paragraph 3.7.2.5.2, second sentence: Delete.

Page 9, paragraph 3.7.8, lines 1 and 2: Delete "Elevated lights and the single or power pack containers" and substitute "Elevated and flush fixtures".

Pages 9 and 10, paragraphs 3.7.9 through 3.7.9.3: Delete.

Page 10, paragraph 3.7.10: Delete and substitute:

"3.7.10 Grounding.- The ground conductor in the input cable shall be positively connected to the containers of the elevated and flush light units."

Page 10, paragraph 3.8, line 2: Delete "CAA-1106" and substitute "FAA-1106".

Page 11, paragraph 3.13: Delete, and substitute:

"3.13 Monitoring equipment.- Necessary monitoring equipment shall be provided with each system. The monitoring equipment and circuitry shall be essentially in accordance with that specified in Specification FAA-1106, except that the remote control monitor circuit shall be altered to make use of an existing on-off switch on the type MA-1 control panel in the tower.

Source: https://assist.dla.mil -- Downloaded: 2026-10-20T09:26Z
Check the source to verify that this is the current version before use.

Dual green indicator lights conforming to MS25256-3A shall be located on the type MA-1 panel and shall operate whenever the on-off switch is ON unless the monitor system senses that three or more flashers are malfunctioning. Other circuitry or components required for the monitoring equipment shall not be permitted in the tower but may be housed in a box and located in the airfield lighting vault. The flasher and monitor sectionalizer specified in Specification FAA-1106 shall not be provided."

Page 12, paragraph 4.1: Delete, and substitute:

"4.1 Inspection responsibility.- The supplier is responsible for the performance of all inspection requirements as specified herein. Except as otherwise specified, the supplier may utilize his own or any other inspection facilities and services acceptable to the Government. Inspection records of the examination and tests shall be kept complete and available to the Government as specified in the contract or order. The Government reserves the right to perform any of the inspections set forth in the specification where such inspections are deemed necessary to assure supplies and services conform to prescribed requirements."

Page 12, paragraph 4.4.1, line 4: Delete "CAA-1106" and substitute "FAA-1106".

Page 12, paragraph 4.5.2, line 1: Delete "CAA-1106" and substitute "FAA-1106".

Page 13, paragraph 4.5.4, line 1: At the beginning of first sentence add "With vents sealed,".

Page 13, paragraph 4.5.5, line 1: Delete "CAA-1106" and substitute "FAA-1106".

Page 15, paragraph 6.2: Delete subparagraph (c).

Page 15, paragraph 6.3, line 9: Delete "Wright Air Development Center" and substitute "Aeronautical Systems Division (ASD)".

Custodians:

Navy - Wep
Air Force - AFSC

Preparing activity:

Air Force - AFSC

Source: https://assist.dla.mil -- Downloaded: 2026-10-20T09:26Z
Check the source to verify that this is the current version before use.