MILITARY SPECIFICATION

FUZE, GRENADE: HAND, PRACTICE M228 PARTS FOR, AND LOADING ASSEMBLING AND PACKING

This amendment forms a part of Military Specification MIL-F-14943D(AR), dated 7 December 1982, and is approved for use within the US Army Armament Munitions and Chemical Command and is available for use by all Departments and Agencies of the Department of Defense.

PAGE 2

Add the following immediately preceding 2.2 ("Order of precedence"):

"PUBLICATIONS

U. S. ARMY MATERIEL DEVELOPMENT AND READINESS COMMAND

AR 385-11	-	Ionizing Radiation protection.
DARCOM R 385-25	-	Radiation Protection.

(Application for copies of these regulations should be addressed to Commander, U. S. Army Materiel Development and Readiness Command, 5001 Eisenhower Ave., ATTN: DRCSF-P, Alexandria, VA 22333.)"

PAGE 3

* 3.3.1: Delete "less than three (3.0) seconds" and substitute less than four (4.0) seconds.

* 3.3.2: Delete "more than five (5) seconds and substitute "more than five and one tenth (5.1) seconds".

DISTRIBUTION STATEMENT A. Approved for public release; distribution is unlimited.

Source: https://assist.dla.mil -- Downloaded: 2026-10-18T05:10Z
Check the source to verify that this is the current version before use.

* 3.3.4: Add new paragraph:

"3.3.4 Long delay. Fuzes that function in more than five and one tenth (5.1) seconds but less than 10.0 seconds shall be noted as long delay devices."

PAGE 4

* 3.10: Add new paragrahph:

"3.10 Delay column process inspection. The contractor shall assure adequate process control exists at the delay column assembly be testing samples in accordance with the sampling plan and procedures noted in 4.4.3.11."

* 3.11: Add new paragraph:

"3.11 Critical or special major defects material handling. An analysis of critical defect material handling shall be made in accordance with MIL-A-48078 and 4.4.3.12."

* 3.12: Add new paragraph:

"3.12 Adhesives, sealants and lubricants. If adhesives, sealants or lubricants are required or permitted by the drawings, a process control drawing is required in accordance with MIL-A-48078 and 4.4.3.13."

PAGE 7

* TABLE I, First article inspection. Add to the Fuze Assembly Inspection:

"Adhesives, sealants and lubricants tear down, 10 samples, 3.12, 4.4.3.12".

PAGE 25

* 4.4.3.1: Delete in its entirety and substitute:

"4.4.3.1 Functioning (see 3.3). The fuze shall be observed for any failure to comply with the requirements as classed in Table II when tested as specified in 4.5.1.

Source: https://assist.dla.mil -- Downloaded: 2026-10-18T05:10Z
Check the source to verify that this is the current version before use.

TABLE II. Functional requirements

Defect		Classification
Premature delay failure	(see 3.3.1)	Special Major
Excessive delay failure	(see 3.3.3)	Special Major
"Hung" striker failure	(see 3.3)	Special Major
Normal delay failure	(see 3.3.2)	Major
Dud	(see 3.3)	Major
Long delay failure	(see 3.3.4)	Major

A sample of 800 fuze assemblies shall be taken from each lot and divided into two equally sized groups. One group shall be subjected to the static functioning test as specified in 4.5.1.1 and the other group to the dynamic functioning test as specified in 4.5.1.2. The lot shall be rejected if any of the following test results occur:

a. A Special Major defective is found (see Table II).

b. If four (4) or more fuzes dud or function low order (see 6.8).

c. If six (6) or more long delay failures occur in either group, or if the combined numbver of long delay failures in both groups equals or exceeds ten (10)."

4.4.3.1.2: Delete in its entirety.

PAGE 29

* 4.4.3.11: Add new paragraph:

"4.4.3.11 Delay column process inspection. The contractor shall randomly select nine (9) samples from each hour's production quantity that has undergone delay column consolidation. In addition, the contractor shall add to his sample the last unit produced during that hour's production. These ten (10) samples shall be statically fired for determination of that hour's production to comply with the requirements of 3.3. The production quantity shall be classed defective as noted by:

Source: https://assist.dla.mil -- Downloaded: 2026-10-18T05:10Z
Check the source to verify that this is the current version before use.

a. If one (1) or more samples fail to comply with the premature delay requirements of 3.3.1 - Special major defect.

b. If two (2) or more samples fail to comply with the long delay requirements of 3.3.4 - Major defect.

c. If one (1) or more samples fail to comply with the excessive delay requirement of 3.3.3 - Special major defect.

Testing shall be in accordance with 4.5.9."

* 4.4.3.12: Add new paragraph:

"4.4.3.12 Critical or special major defect material handling (see 3.11). The contractor shall maintain controls for all critical or special major defects as specified in paragraph 3.2, Amendment 4 to MIL-A-48078."

* 4.4.3.13: Add new paragraph:

"4.4.3.13 Adhesives, sealants and lubricants (see 3.12). The contractor shall maintain documents and controls as specified in paragraph 3.3, Amendment 4 of MIL-A-48078."

PAGE 30

4.4.4.1 and 4.4.4.2: The following paragraphs shall be added to follow 4.4.4:

"4.4.4.1 Automatic inspection equipment. All automatic test and inspection equipment, when utilized by the Contractor, shall be subjected to periodic verification and calibration check during production. All standards or test samples required for such calibration/verification shall be furnished by the equipment manufacturer as part of the equipment. Procedures for verification shall include, as a minimum: frequency, method of verification, and the method of retrieval of item produced between verification/calibration. These procedures shall be included in the operation/calibration procedures as required by the above paragraph. In addition, the equipment shall be subjected to periodic maintenance by the manufacturer or other qualified personnel as approved by the Contracting Officer and in accordance with approved maintenance procedures."

Source: https://assist.dla.mil -- Downloaded: 2026-10-18T05:10Z
Check the source to verify that this is the current version before use.

"4.4.4.2 Radiation-emitting equipment. Inspection equipment employing x-rays or containing radioisotopic material, when utilized by the contractor, shall comply with all safety requlations as specififed in AR 385-11 and DARCOM R 385-25 and display the required safety tag. The equipment shall be tamperproof, completely self-contained, with all controls locked to production personnel and accessible only to supervisory personnel. Unless otherwise specified, preventive maintenance and verification shall be performed not less than once every six (6) months. Maintenance and verification shall be performed only by the equipment manufacturer or other qualified personnel, as approved by the Contracting Officer. Records shall be kept of all maintenance performed. In addition, maintenance information shall be affixed to the inspection equipment. (label or tag)."

PAGE 32

* 4.5.9: Add new paragraph:

"4.5.9 Delay column process inspection static firing. The delay column assembly after consolidation shall be placed in a fixture and tested for delay time as specified in 3.3. The firing times shall be recorded for review by the Government and inclusion into the contractor's process control."

The margins of this amendment are marked with an asterisk or vertical line to indicate where changes (additions, modifications, corrections, deletions) from the previous amendment were made. This was done as a convenience only and the Government assumes no liability whatsoever for any inaccuracies in these notations. Bidders and contractors are cautioned to evaluate the requirements of this document based on the entire content irrespective of the marginal notations and relationship to the last previous amendment.

Custodian:
Army-AR

Preparing activity:
Army-AR

(Project 1330-A311)

Source: https://assist.dla.mil -- Downloaded: 2026-10-18T05:10Z
Check the source to verify that this is the current version before use.