MILITARY SPECIFICATION

CENTER, MESSAGE AN/GSQ-80( )

This amendment forms a part of Specification MIL-C-55412(EL) dated 18 Feb 1965.

Page 1, Para. 2.1 Specification Military.- Delete "MIL-M-13787 Motors, Alternating current, Fractional Horsepower, Squirrel Cage." Add "MIL-P-55505 Shelter, Electrical Equipment (containing equipment) Packaging and Packing of."

Page 2, Para. 2.2 Other Publications.- Delete the entire paragraph.

Page 3, Para. 3.2 Preproduction samples.- Replace the entire paragraph with the following: "3.2 Preproduction Inspection.- The contractor shall subject the first article to the preproduction tests specified and shall submit the test results, in the form of a report, for approval if required by the invitation for bids and contract. (See 4.3 and 6.1)."

Page 6, Para. 3.16 Motors, fractional horsepower.- Delete the entire paragraph.

Page 7, Para. 3.17 Exhaust blowers.- Delete the entire paragraph.

Page 8, Para. 3.24 Bounce.- Delete the entire paragraph.

Page 8, Para. 3.26 Power and Signal wiring.- Replace the entire paragraph with the following:

"3.26 Electrical installation Message Center AN/GSQ-80( )

3.26.1 Power wiring, message center.- The message cneter shall be wired in accordance with the drawings listed on SC-DL-512000 and shall comply with the requirements of this specification.

3.26.1.1 Operation of distribution panel circuits.- All components on all circuits of the distribution panel shall meet the continuity and operational tests described in 4.11.3 through 4.11.7.

FSC 9999

Source: https://assist.dla.mil -- Downloaded: 202610-22T23:19Z
Check the source to verify that this is the currentversion before use.

3.26.1.2 Dielectric Breakdown and Insulation Resistance, Power wiring.- All A.C. power wiring shall have an insulation resistance of not less than 100 megohms when measured between

(a) "Hot line" and "Neutral"
(b) "Neutral" and "Ground"
(c) "Hot line" and "Ground"

Insulation resistance shall be measured at least 10 seconds after an instantaneous potential of 500 volts D.C. is applied (4.11.2).

3.26.1.3 Overload, circuit breakers.- All circuit breakers shall be tested in accordance with 4.11.8 and shall comply with the requirements of Table A.

Table A Drop out time

Size	Overload (Percent)		
	200	300	1000
15-20 amp	—	5-9 sec	less than .02 sec
50 amp	20-30 sec	—	less than .01 sec

3.26.2 Audio Signal wiring, shelter facility.- The message center shall be wired in accordance with the drawings listed on SC-DL-512000 and shall comply with the requirements of this specification.

3.26.2.1 Distribution and continuity, Audio Signal Wiring.- There shall be electrical continuity between each terminal shown on the drawings.

3.26.2.2 Dielectric Breakdown and Insulation Resistance, Audio Signal wiring.- All audio signal wiring shall have an insulation resistance of not less than 100 megohms when measured between each conductor and the remaining conductors, conduit,wireduct, and shelter ground. Insulation resistance shall be measured at least 10 seconds after an instantaneous potential of 500 volts D.C. is applied (See 4.12)".

Page 9, Para. 4.3 Preproduction inspection.- Replace the first sentence with "This inspection shall be performed by the contractor on the first article unless otherwise specified in the contract." Delete in second paragraph "(h) Bounce".

Source: https://assist.dla.mil -- Downloaded: 202610-22T23:19Z
Check the source to verify that this is the current version before use.

Page 9, Table I - Preproduction inspection.- Delete the following tests "Flat drop", "Rotational drop", "Exhaust blower", and "Bounce".

Page 11, Para. 4.5.3 Group C inspection.- Replace the entire paragraph with the following:

"This inspection shall consist of the tests specified in Table IV and shall be performed on sample units that have been subjected to and met groups A and B inspection. Sample units shall be selected in accordance with paragraph 4.5.3.3".

Page 11, Table IV.- Group C inspection.- Add the following:

"Group I		
Flat drop	3.21	4.8.1
Rotational drop	3.21	4.8.2 "

Page 12, Para. 4.5.3.2 Noncompliance.- Replace the entire paragraph with the following:

"The contractor shall immediately report in writing each Group C failure occurence, including details of the failure and characteristics affected. The contractor shall immediately investigate the cause of failure and further report the results of investigation and details of the proposed corrective action on (i) the process and materials, as applicable, and, (ii) all units of product which were manufactured under the same conditions and which the Government considers subject to the same failure. Reports shall be forwarded to the responsible technical activity designated in the contract, through the Quality Assurance Representative. After corrective action has been taken, additional sample units shall be subjected to Group C inspection (all inspections, or the inspections which the sample failed, at the option of the Government) and Groups A and B inspection may be reinstated, however, final acceptance and shipment will be withheld until the Group C reinspection results have shown that the corrective action was effective."

Page 12, Para. 4.5.3.3 Add the following new paragraph:

"4.5.3.3 Sampling for inspection.- One sample shall be selected at random for each group of inspection in Table IV from the first 50 units, or fraction thereof, produced and one sample from each additional 150 units and fraction thereof produced. The first sample selected shall not be from the first items produced".

Source: https://assist.dla.mil -- Downloaded: 202610-22T23:19Z
Check the source to verify that this is the current version before use.

Page 12, Para. 4.5.3 Reinspection of conforming Group B and Group C sample units.- Replace the entire paragraph with the following:

"4.5.4 Reinspection of conforming Group B and Group C sample units.- Unless otherwise specified, sample units which have been subjected to and passed both Group B and Group C inspection may be accepted on contract or order provided all damage is repaired and the sample units are resubjected to and pass Group A inspection".

Page 12, Para. 4.6 Military Truck transport.- In the first sentence delete "(a) on any convenient hard surfaced road and subjected to 60 abrupt stops from 30 miles per hour and (b)", and in the last sentence delete "of both the (a) and (b) portion"

Page 14, Figure 1.- Replace the description of Item 10 with "No. 8 wire, 8 strands (4 loops), Hard, 2000 lb test"

Page 16, Para. 4.11.2 Insulation and continuity testing of power wiring circuits.- Replace the entire paragraph with the following:

"4.11.2 Dielectric Breakdown and Insulation Resistance, Power wiring.- The dielectric breakdown and insulation resistance of the power wiring shall be tested for conformance with 3.26.1.2 as described below.

(a) Remove all fluorescent lamps from their fixtures.
(b) Remove all starters from fluorescent fixtures.
(c) Remove cover from the power distribution box. Disconnect voltmeter from neutral bus bar. Switch on all circuit breakers.
(d) Remove all incandescent and neon lamps.
(e) Unplug all power cords from receptacles in wire-duct.
(f) Apply an instaneous voltage of 500 volts D.C. between terminal 1 of Power Receptacle U-238( )/G and terminal 2 of the same receptacle. After 10 seconds, measure the resistance between terminal 1 and terminal 2. Resistance shall not be less than 100 megohms. (Caution: After each test, discharge the conductor under test to ground to eliminate dange of shock.)
(g) Repeat (f) replacing terminal 2 (2 places) with terminal 4.
(h) Repeat (f) replacing terminal 1 (2 places) with terminal 4.
(i) Restore shelter facility to original condition, that is replace all lamps, cover, wires, etc."

Source: https://assist.dla.mil -- Downloaded: 202610-22T23:19Z
Check the source to verify that this is the currentversion before use.

Page 18, Para. 4.11.8 Test of circuit breakers and ammeter.- Replace entire paragraph with the following:

"4.11.8 Overload test of circuit breakers.- Circuit breakers shall be tested to determine that the drop out time for each overload condition is in accordance with paragraph 3.26.1.3. Circuit breakers under test shall be maintained at test ambient conditions for at least 1 hour prior to the application of overload current. Overload current shall be applied instantaneously. Drop out time shall be determined by use of a suitable Timer-Relay or oscilloscope."

Page 19, Para. 4.12 Bounce test.- Replace entire paragraph with the following:

"4.12 Dielectric Breakdown and Insulation resistance, Audio signal Wiring.- The dielectric breakdown and insulation resistance of the audio signal wiring shall be tested for conformance with 3.26.2.2 (with either manual on automatic testing equipment) as described below:

(a) Remove all telephone and intercom plugs from jacks in wireduct.

(b) Connect (3) binding posts 1B through 2B directly to shelter ground. Apply an instantaneous voltage of 500 volts D.C. between binding post 1A and shelter ground. After 10 seconds measure the resistance between binding post 1A and shelter ground. Resistance shall not be less than 100 megohms. (Caution: After each test, discharge the conductor under test to ground to eliminate danger of shock).

(c) Repeat (b) for each of the remaining three audio signal lines; that is, the 500V potential shall be applied in turn between binding posts 1B through 2B and shelter ground while the remaining 3 binding posts are connected directly to shelter ground, (for a total of 4 tests)."

Page 20, Para. 4.14 Exhaust blower.- Delete entire paragraph.

Page 21, Table VII.- Classification of visual and mechanical defects.- Under the classification "Major", replace item 6 with "Blower inoperative or rotating in wrong direction" Add as item 11 "Burrs and sharp edges in wire duct not removed". Under the classification "Minor", add as item 5 "Burrs and sharp edges on brackets not removed".

Source: https://assist.dla.mil -- Downloaded: 202610-22T23:19Z
Check the source to verify that this is the current version before use.

Page 22, Section 5 Preparation for delivery.- Replace the entire section with the following:

"5.1 Preservation, packaging and packing of the Message Center AN/GSQ-80 shall be in accordance with the applicable requirements of Specification MIL-S-55505".

Custodian:
Army (EL)

Preparing Activity
Army (EL)

Project Number 9999-A004

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T23:19Z
Check the source to verify that this is the current version before use.

SPECIFICATION ANALYSIS SHEET

Form Approved
Budget Bureau No. 119-R004

INSTRUCTIONS

This sheet is to be filled out by personnel either Government or contractor, involved in the use of the specification in procurement of products for ultimate use by the Department of Defense. This sheet is provided for obtaining information on the use of this specification which will insure that suitable products can be procured with a minimum amount of delay and at the least cost. Comments and the return of this form will be appreciated. Fold on lines on reverse side, staple in corner, and send to preparing activity.

SPECIFICATION

ORGANIZATION	CITY AND STATE

CONTRACT NO.	QUANTITY OF ITEMS PROCURED	DOLLAR AMOUNT
		$

MATERIAL PROCURED UNDER A

☐ DIRECT GOVERNMENT CONTRACT ☐ SUBCONTRACT

1. HAS ANY PART OF THE SPECIFICATION CREATED PROBLEMS OR REQUIRED INTERPRETATION IN PROCUREMENT USE?

A. GIVE PARAGRAPH NUMBER AND WORDING.

B. RECOMMENDATIONS FOR CORRECTING THE DEFICIENCIES

2. COMMENTS ON ANY SPECIFICATION REQUIREMENT CONSIDERED TOO RIGID

3. IS THE SPECIFICATION RESTRICTIVE?

☐ YES ☐ NO IF "YES", IN WHAT WAY?

4. REMARKS *(Attach any pertinent data which may be of use in improving this specification. If there are additional papers, attach to form and place both in an envelope addressed to preparing activity)*

SUBMITTED BY *(Printed or typed name and activity)*	DATE

DD FORM 1 OCT 64 1426

ESC-FM 2011-66

To detach this form, cut along this line

Source: https://assist.dla.mil -- Downloaded: 202610-22T23:19Z
Check the source to verify that this is the current version before use.

FOLD

DEPARTMENT OF THE ARMY
HEADQUARTERS
U.S.ARMY ELECTRONICS COMMAND
FORT MONMOUTH, NEW JERSEY 07703

OFFICIAL BUSINESS

POSTAGE AND FEES PAID
DEPARTMENT OF THE ARMY

Commanding General
U. S. Army Electronics Command
ATTN: AMSEL-PP-
Fort Monmouth, New Jersey 07703

FOLD

To detach this form, cut along this line

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T23:19Z
Check the source to verify that this is the current version before use.