MILITARY SPECIFICATION

DISPENSER AND MINE, AIRCRAFT: CBU-42/A

LOADING, ASSEMBLING AND PACKING

1. SCOPE

OR: 1.1 This specification covers the loading, assembling and packing for one type of Dispenser designated as Dispenser and Mine, Aircraft: CBU-42/A

2. APPLICABLE DOCUMENTS

2.1 The following documents of the issue in effect on date of invitation for bids or request for proposal, form a part of this specification to the extent specified herein:

SPECIFICATIONS

FEDERAL

MILITARY

MIL-A-2550	-	Ammunition and Special Weapons, General Specification for
MIL-I-45607	-	Inspection Equipment, Supply and Maintenance of

STANDARDS

MILITARY

FSC 1345

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T20:18Z
Check the source to verify that this is the current version before use.

MIL-STD-105 - Sampling Procedures and Tables for Inspection by Attributes (ABC-STD-105)

MIL-STD-109 - Quality Assurance Terms and Definitions

MIL-STD-1168 - Lot Numbering of Ammunition

MIL-STD-1235 - Single and Multilevel Continuous Sampling Procedures and Tables for Inspection by Attributes

DRAWINGS

U.S. AIR FORCE

68F10445 - Dispenser and Mine, Aircraft CBU-42/A

67F9688 - Shipping and Storage Container for Dispenser CNU-104/E Packing and Marking

PUBLICATIONS

ARMY

ET-68F10445 - Equipment Tabulation

(Copies of specifications, standards, drawings and publications required by suppliers in connection with specific procurement functions should be obtained from the procuring activity or as directed by the Contracting Officer.)

2.2 Other publications.-The following documents form a part of this specification to the extent specified herein. Unless otherwise indicated, the issue in effect on the date of invitation for bids or request for proposal shall apply.

CODE OF FEDERAL REGULATIONS

Title 49 - Transportation, Parts 171-179

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T20:18Z
Check the source to verify that this is the current version before use.

(The Code of Federal Regulations is available from the Superintendent of Documents, U.S. Government Printing Office, Washington, D.C. 20402. Orders should specify 49 CFR 171-179 (latest revision).)

3. REQUIREMENTS

3.1 Material.-Materials shall be in accordance with the applicable drawings and specifications.

3.2 Dispensers.-Dispensers shall comply with all requirements specified on Drawing (Dwg.) X68F10445, all associated drawings, and with all requirements specified in applicable specifications.

3.3 Workmanship.-All parts and assemblies shall be fabricated, loaded and assembled in a thorough, workmanlike manner. They shall be free of burrs, cracks, dirt, grease, rust, and other foreign matter. The cleaning method used shall not be injurious to any part, nor shall the parts be contaminated by the cleaning agents. Exterior surface coatings shall be continuous except for a few light scratches not exposing base material. All required marking and stamping shall be neat and sharply defined.

3.4 Submission of results of contractor-conducted examinations and tests.-The contractor shall forward copies of the results of any of his examinations or tests to the designated addresss as required by the contract. (see 6.4).

4. QUALITY ASSURANCE PROVISIONS

4.1 Responsibility for inspection.-Unless otherwise specified in the contract or purchase order, the supplier is responsible for the performance of all inspection requirements as specified herein. Except as otherwise specified in the contract or order, the supplier may use his own or any other facilities suitable for the performance of the inspection requirements specified herein, unless disapproved by the Government. The Government reserves the right to perform any of the inspections set forth in the specification where such inspections are deemed necessary to assure supplies and services conform to prescribed requirements.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T20:18Z
Check the source to verify that this is the current version before use.

Reference shall be made to MIL-STD-109 to define terms used herein. The provisions of MIL-A-2550 shall apply.

4.1.1 Submission of product.-At the time the completed lot of items deliverable under the contract is submitted to the Government for acceptance, the contractor shall supply the following information accompanied by a certificate which attests that the information provided is correct and applicable to the product being submitted:

a. A statement that the lot complies with all the quality assurance provisions specified in this specification.
b. Drawing and specification number and date, together with identification and date of changes thereto.
c. A statement that all material purchased by the contractor meets requirements, when such material is controlled by Government or commercial specifications referenced in any of the contractual documents, and that certificates of conformance are on file and available for review.
d. Number of items in the lot.
e. Date submitted.

The certificate shall be signed by a responsible agent of the certifying organization. The initial certificate submitted shall be substantiated by evidence of the agent's authority to bind his principal. Substantiation of the agent's authority will not be required with subsequent certificates unless, during the course of the contract, this authority is vested in another agent of the certifying organization.

4.2 Inspection provisions

4.2.1 Lot formation.-The term "inspection lot" as used in this specification is defined as an essentially homogeneous collection of units of product from which a representative sample is drawn and inspected to determine conformance with applicable requirements. The sample selected shall represent only that quantity of units from which the sample was drawn

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T20:18Z
Check the source to verify that this is the current version before use.

and shall not be construed to represent any prior or subsequent quantities presented for inspection. Homogeneity shall be considered to exist provided the inspection lot has been produced by one manufacturer, in one unchanged process, in accordance with the same drawing, same drawing revision, same specification and same specification revision and complies with the provisions for submission of product as specified in MIL-STD-105. Changes to process, specification, or drawing not affecting safety, performance, interchangeability, or storage, as determined by the Government, shall not be deemed to alter the homogeneity of an inspection lot. All material submitted for inspection in accordance with this specification shall comply with the homogeneity criteria specified herein regardless of the type of sampling procedure which is being applied to determine conformance with requirements. Lot numbering, as required, shall be in accordance with MIL-STD-1168. Each inspection lot of loaded dispensers shall contain:

a. CDU assemblies of one lot interfix number from one manufacturer.
b. Dispenser metal parts of one lot interfix number from one manufacturer.
c. Ejection cartridge of one lot interfix number from one manufacturer.

4.2.2 Examination.-The examinations listed in the following subparagraphs shall be performed on inspection lots (see 4.2.1) of the components or assemblies designated in the applicable paragraph headings. Inspection for critical defects (and major defects, when so specified) shall be 100 percent. Sampling plans for major and minor defects shall be in accordance with MIL-STD-105 except that continuous sampling plans in accordance with MIL-STD-1235 may be used if approved by the Government. Instead of applying the AQL's designated herein to the groups of major and minor defects listed, the contractor may elect to apply AQL's to individual defects using an AQL of 0.40 percent for each major defect and an AQL of 0.65 percent for each minor defect. When this method is elected, it shall be applied to all of the major and minor defects listed in the applicable subparagraph of this section, except where 100 percent inspection is specified, and be documented as part of the contractor's inspection system. Equipment necessary for the performance of the inspections listed shall be in accordance with 4.2.4.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T20:18Z
Check the source to verify that this is the current version before use.

4.2.2.1 Dispenser and Mine, Aircraft CBU-42/A, (See Dwg. 68F10445).-

Categories	Defects	Method of Inspection	Code No (See 6.2)
Critical			
1.	Safety Pin Missing	Visual	01001
Major	100% Percent		
101	Wiring harness not connected to intervalometer	Visual	01002
102	Any wires missing, damaged or improperly positioned	Visual	01003
103	Any part damaged, missing or improperly assembled	Visual	01004
104	Squib connectors not secure	Visual Manual	01005
Minor	AQL 1.00 Percent		
201	Marking incorrect, incomplete or missing	Visual	01006
202	Evidence of poor workmanship (See 3.3)	Visual	01007

4.2.2.2 Shipping and storage container, prior to assembling cover (See Dwg. 67F9688).

Categories	Defects	Method of Inspection	Code No.
Critical:	None Defined		
Major	AQL 0.40 Percent		
101	Desiccant missing	Visual	02001
102	Suspension lugs missing	Visual	02002
Minor	AQL 0.65 Percent		
201	Evidence of poor workmanship (See 3.3)	Visual	02003

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T20:18Z
Check the source to verify that this is the current version before use.

4.2.2.3 Shipping and storage container (See dwg 67F9688)

Categories	Defects	Method of Inspection	Code No.
Critical:	None Defined		
Major	AQL 0.65 Percent		
101.	Cover gasket damaged or missing	Visual	03001
102.	Any strap missing	Visual	03002
103.	Humidity reading too high	Visual	03003
104.	Any metallic seal missing	Visual	03004
Minor	AQL 1.00 Percent		
201.	Marking incorrect, incomplete or missing	Visual	03005
202.	Evidence of poor workmanship (See 3.3)	Visual	03006

4.2.3 Testing.-

4.2.3.1 Squib resistance check (See dwg 68F10445), Major Defect, Code No. 04001.-Each squib circuit of each dispenser shall be subjected to this test, as specified in paragraph 4.3.1. If any squib circuit fails to comply with the requirement of drawing, the dispenser shall be classified defective and removed from the lot.

4.2.3.2 Insulation Resistance (See Dwg. 68F10445), Major Defect, Code No. 05001.-Each dispenser shall be subjected to this test as specified in paragraph 4.3.2. If any dispenser fails to comply with requirement of the drawing, the dispenser shall be classified defective and removed from the lot.

4.2.3.3 Continuity test (See Dwg 68F10445), Major Defect, Code No. 06001.-Each dispenser shall be subjected to this test as specified in paragraph 4.3.3. If any dispenser fails to exhibit continuity as specified on the drawing, the dispenser shall be classified defective and removed from the lot.

4.2.4 Inspection equipment.-Equipment Tabulation (ET) number 68F10445 and Equipment Lists (EL's) referenced thereon identify the prescribed in this section. The contractor shall design inspection equipment in accordance with instructions in 6.3. Supply and maintenance of the equipment listed on the EL's shall be in accordance with MIL-I-45607.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T20:18Z
Check the source to verify that this is the current version before use.

4.2.4.1 Government rights to documentation.-Inspection equipment drawings and lists provided and revised in accordance with the requirements of this specification may be used by DOD activities for design, procurement, manufacture, testing, evaluation, production and receiving inspection, overhaul, shipping, storage, indentification of stock, ordering and storage of replacement parts, inspection of itmes at overhaul, general maintenance of equipment, construction, survey, and whenever inspection equipment drawings are needed.

4.3 TEST METHODS AND PROCEDURES

4.3.1 Squib resistance check.-The squib circuit shall be tested for resistance for conformance to the drawing requirements using equipments as specified in 4.2.4. This is a non-destructive test. Parts so tested may be returned to the lot.

4.3.2 Insulation resistance.-The dispenser shall be tested for insulation resistance for conformance to the drawing requirements using equipment as specified in 4.2.4. This is a non-destructive test. Parts so tested may be returned to the lot.

4.3.3 Continuity.-The dispenser shall be tested for continuity for conformance to the drawing requirements using equipment as specified in 4.2.4. This is a non-destructive test. Parts so tested may be returned to the lot.

5. PREPARATION FOR DELIVERY

5.1 Packing.-

5.1.1 Level A.-The loaded dispenser, preserved and packaged as specified in 5.1.1, shall be packed in accordance with Dwg. 67F9688.

5.2 Marking.-Marking shall be in accordance with Dwgs 67F9688 and Code of Federal Regulations, Title 49, Parts 171-179.

5.3 Shipping.-When shipments from more than one lot are shipped as a carload, each lot shall be kept separate, and the division between lots clearly indicated to prevent mixing of the lots in transit.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T20:18Z
Check the source to verify that this is the current version before use.

6. NOTES

6.1 Ordering data.-Procurement documents shall specify the following:

a. Title, number and date of this specification.
b. Data cards shall be prepared for each lot in accordance with the information specified in Standard MIL-STD-1167.

6.2 Inspection code numbers.-The five-digit code numbers assigned to the inspections herein are to facilitate future data collection and analysis by the Government. These code numbers are also used to correlate the characteristics cited on Equipment Lists with the inspections listed in this specification. These code numbers shall be listed on drawings of equipment designs submitted by the contractor (see 6.3.5).

6.3 Inspection equipment.-The contractor shall design inspection equipment as required by the referenced Equipment Lists (EL) in accordance with the instructions of paragraphs 6.3.1 through 6.3.5.

6.3.1 Equipment lists.-Equipment lists indicate the availability of inspection equipment designs by showing in the "Part Number" column of the list of inspection equipment (Form SMUPA 1010) the numbers of drawings of Federal Stock numbers of existing equipment designs, or codes as indicated in paragraph 6.3.2. Design action required of the contractor is described in paragraphs 6.3.3 and 6.3.4. The contractor will be required to prepare detailed drawings in accordance with 6.3.4 for all the equipment coded as "Contractor Design" in the "Part Number" column. These contractor designs must be approved by the Government prior to fabrication or procuring of the equipment. Designs shall be submitted for approval as specified in 6.3.5.

6.3.2 Equipment list codes.-The inspection equipment as defined in 6.3.3 and 6.3.4 will be designated in the EL by the following codes:

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T20:18Z
Check the source to verify that this is the current version before use.

CD - Contractor design on controlled contractor format and/or commerical equipment.
MU - Army design, mandatory for use.

6.3.3 Army designs.-Army designs are reflected on detailed drawings which completely depict all the information necessary for the fabrication of the item of inspection equipment. The contractor need provide no design when an Army design is listed for an item of inspection equipment. Army design fall into two basic classifications: Mandatory (designated "MU") and non-mandatory (indicated by drawing or Federal Stock Number). When an equipment list references mandatory Army Designs, the contractor shall comply with, and use these designs accordingly. The contractor may, however, in connection with non-mandatory designs, with the approval of the Government, design alternate inspection equipment to facilitate his operations. Such contractor-prepared designs (see 6.3.4) or commercial equipment selections must be approved by the Government prior to fabrication or procuring of the equipment. Designs shall be submitted for approval as specified in 6.3.5.

6.3.4 Contractor designs.-Contractor designs are designs of inspection equipment for which the Government has assigned design responsibility to the contractor. Contractor designs shall be supported by detailed drawings, which depict all information necessary to completely fabricate, calibrate and operate an item of inspection equipment. This requires that the necessary views, dimensions, materials, finishes, notes and operating and calibration instructions be properly depicted in accordance with approved practices to the extent that further calculation or clarification will not be required. Unless otherwise specified, contractor designs may be developed on the format the contractor normally employs in his equipment design procedure provided such format reflects the detail and information specified above, subject to the following controls: All submitted contractor designs shall conform to Specification MIL-D-1000, Category E, Form 2. Legibility and reproducibility shall permit conventional making of clearly understandable, high-contrast reproductions. Contractors shall submit three copies of final designs as a flat set. Designs shall be submitted for approval as specified in 6.3.5.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T20:18Z
Check the source to verify that this is the current version before use.

6.3.5 Submission of contractor design.-All submitted designs shall contain a reference to the applicable 5-digit code number contained in Section 4 of this specification and the appropriate component or assembly drawing number and revision letter to which the specific design applies. Unless otherwise specified on the EL, all designs of equipment for inspection of defects classified as critical and major shall be submitted for approval to the Commanding Officer, Picatinny Arsenal, ATTN: SMUPA-ND13. All other designs of inspection equipment shall be approved by the inspection element of the agency administering the contract. Submission shall be as directed to the contracting officer. Partial submission of inspection equipment designs is permissible and encouraged. However, the Arsenal completion date for design review will be based on the date of the final submission of designs. Picatinny Arsenal design review will be accomplished, normally, within one month after receipt.

6.4 Submission of results of contractor-conducted examinations and tests.-Unless otherwise specified by the Contracting Officer, the contractor shall forward requested records of examinations or tests to Commanding Officer, Picatinny Arsenal, ATTN: SMUPA-ND3.

Custodian:
Army-MU

Preparing activity:
Army-MU

Project Number:1345-A-286

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T20:18Z
Check the source to verify that this is the current version before use.