MIL-A-27670C(USAF)
AMENDMENT 3
1 DECEMBER 1986
SUPERSEDING
AMENDMENT 2
1 June 1979

MILITARY SPECIFICATION

AMPLIFIER-INDICATOR GROUP, INDICATED AIRSPEED A/A24G-10

This amendment forms a part of MIL-A-27670C(USAF), dated 16 Aug 65, and is approved for use within the Department of the Air Force and is available for use by all Departments and Agencies of the Department of Defense.

PAGE 1

* Delete "2.1" and add: "2.1 Government documents."

* Add: "2.1.1 Specification standards and handbooks. The following specifications, standards, and handbooks form a part of this specification to the extent specified herein. Unless otherwise specified, the issues of these documents shall be those listed in the issue of the Department of Defense Index of Specifications and Standards (DODISS) and supplement thereto, cited in the solicitation.

* Under SPECFICATION, Federal, delete "QQ-P-416" and add:
"PPP-B-601 Boxes, Wood Cleated, Plywood"
"PPP-B-636 Box, Shipping, Fiberboard".

* Under SPECIFICATION, Military, delete "MIL-E-5272" "MIL-P-7936", "MIL-M-26512", "MIL-R-26667" and "MIL-D-70327". Add: "MIL-B-27497 Bearing, Jewel, Sapphire or Ruby, Synthetic", "MIL-C-83488 Coatinig, Aluminum ION Vapor Deposited" and "MIL-M-7793/6 Meter, Time Totalizing, Miniature, Digital, 115 Volts, 400 Hz".

Add boxed paragraph to bottom center of page.

Beneficial comments (recommendations, additions, deletions) and any pertinent data which may be of use in improving this document should be addressed to: Oklahoma City Air Logistics Center/MMEDO, Tinker AFB OK 73145-5990 by using the self-addressed Standardization Document Improvement Proposal (DD Form 1426) appearing at the end of this document or by letter.

PAGE 2

Under STANDARDS, Military, delete "MS17322", "MS33586" and add:
"DOD-STD-100 Engineering Drawing Practices
MIL-STD-470 Maintainability Program Requirements (for Systems and Equipments)
MIL-STD-471 Maintability Demonstration
MIL-STD-781 Reliability Tests Exponential Distribution
MIL-STD-794 Part and Equipment, Procedures for Packaging and Packing of
* MIL-STD-810C Environmental Test Methods
MIL-STD-889 Dissimilar Metals"

DISTRIBUTION STATEMENT A. Approved for public release; distribution is unlimited.

Source: https://assist.dla.mil -- Downloaded: 2026-10-20T12:38Z
Check the source to verify that this is the current version before use.

* Delete "2.2" and add:

"2.2 Other publications. The following document(s) form a part of this specification to the extent specified herein. Unless otherwise specified, the issues of the documents which are DOD adopted shall be those listed in the issue of the DODISS specified in the solicitation. Unless otherwise specified, the issues of documents not listed in the DODISS shall be the issue of the nongovernment documents which is current on the date of the solicitation.

ASTM D3951 Packaging, Commercial

(Application for copies should be addressed to: ASTM, 1916 Race St Philadelphia PA 19103.)

(Nongovernment standards and other publications are normally available from the organization which prepare or which distribute the documents. These documents also may be available in or through libraries or other information services.)

* 3.1 First article. When specified in the contract or purchase order, a sample shall be subjected to first article inspection (see 4.2 and 6.2).

PAGE 3

3.4.2.1 Last line delete "MS33586" and add: "MIL-STD-889".

* Add:
"3.4.3.1 Recovered materials. Recovered materials shall be used to the maximum extent possible without jeopardizing the end use of the item.

PAGE 18

3.5.4 Line 5: Delete "requirements shall be in accordance with MIL-M-26512" and substitute "program requirements shall be in accordance with MIL-STD-470."

3.5.5 Delete and add:
"3.5.5 Mean-time-between-failures (MTBF). The equipment shall have an MTBF of 600 hours based on a 90% confidence factor."

Add new paragraph 3.5.7:
"3.5.7 Jewel bearings. Jewel bearings shall be in accordance with MIL-B-27497."

3.6, Step d, number (1): Delete and add: "In accordance with Method 514.2 of MIL-STD--810C." Step d, number (2): Delete and add: "In accordance with Method 514.2 of MIL-STD-810C.". Step h: Delete and add: "In accordance with Method 513.2 of MIL-STD-810C.". Step i: Delete and add: "In accordance with method 516.2 of MIL-STD-810C.". Step l: Delete existing title "Salt spray" and add: "Salt fog". Step m: Delete existing title "Sand and dust" and add: "Sand (fine dust)".

PAGE 23

* 3.7 Delete "MIL-D-70327" and add: "DOD-STD-100."

PAGE 25

Source: https://assist.dla.mil -- Downloaded: 2026-10-20T12:38Z
Check the source to verify that this is the current version before use.

3.8.2.5.1 In line 1 delete "3.8.2.1" and add: "3.8.1.1". Delete the second sentence.

* 3.8.2.8 Line 2 delete "MS17322" and add: "MIL-M-7793/6".

PAGE 27

* 3.8.3.1 Lines 4, 5 and 7: Under Bandwidth delete "cps" and add: "Hz".

* 3.9 Line 2 delete "and ARING 545". Lines 8 and 9: Delete "cps" and add: "Hz".

* 3.10.2 Line 1: Delete "cps" and add "Hz".

PAGE 29

* 3.20.2 Delete entirely and add: "3.20.2 Steel Parts. Steel parts shall be coated with ion vapor deposited aluminum where practical, in accordance with MIL-C-83488, Type I or II as applicable and of a class that is adequate to achieve the degree of protection required. Other protective coating, in lieu of MIL-C-83488 may be used if demonstrated to be satisfactory by cognizant engineering activity. Cadium plating must be avoided when satisfactory alternate processes can be used."

PAGE 30

* Add:
"4.1.1 Responsibility for compliance. All items must meet all requirements of sections 3 and 5. The inspection set forth in this specification shall become a part of the contractor's overall inspection system or quality program. The absence of any inspection requirements in the specification shall not relieve the contractor of the responsibility of assuring that all products or supplies submitted to the Government for acceptance comply with all requirements of the contract. Sampling in quality conformance does not authorize submission of known defective material, either indicated or actual, nor does it commit the Government to acceptance of defective material."

4.2a Change "Preproduction" tests to "First Article Inspection" tests. Change all references to "preproduction" in section 4 to "First Article".

PAGE 31

Table V: In column headed "Indicator Reading With Transmitter Set at E.Z.", opposite "Angle of attack", delete "0'∝" and add: "Midpoint of stall warning band."

PAGE 32

* 4.3.9.3 Line 3: Delete "Cps" and add: "Hz".

PAGE 36

* 4.5.2.2 Step g: Delete "Salt spray" and add: "Salt fog".
4.5.2.2 Delete "J. Reliability".

Source: https://assist.dla.mil -- Downloaded: 2026-10-20T12:38Z
Check the source to verify that this is the current version before use.

* 4.5.2.2.1 Step i: Delete "Salt spray" and add: "Salt fog".
4.5.2.2.1: Delete "L. Reliability".

PAGE 37

Add:

"4.5.2.4 Sampling plan C. Unless otherwise specified (see 6.2), 2 systems (indicators and amplifiers) shall be selected at random from the first 10 produced and subjected to the test specified in 4.6.42.1. Accept/reject criteria shall be as specified therein".

4.5.2.5 Sampling plan D. Unless otherwise specified (see 6.2), 4 systems (indicators and amplifiers) shall be selected at random from the first 10 of each production quantity of 150 or fraction thereof and subjected to the test specified in 4.6.42.2. Accept/reject criteria shall be as specified therein".

PAGE 43

4.6.15.2 Line 1: Delete "cps" and add: "Hz".

4.6.15.5 Line 1 and 2: Delete "cps" and add: "Hz".

PAGE 45

* 4.6.23 Delete "procedure IV of MIL-E-5272 at amplitudes of 0.009 to 0.011 inch" and add: "Method 514.2, procedure I, part 1 (curve c), category b.1 equipment of MIL-STD-810C, except as follows: Cycling time shall be the time of one sweep time. A range for curve c of 5 to 50 Hz and an acceleration level of + 1g from 23 to 50 Hz. Also, only the sinusoidal cycling portion will be required."

* 4.6.24 Delete sentences 1 and 2 and add: "The unit shall be subjected to a vibration test in accordance with Method 514.2, procedure I, part 2, category b.1 equipment of MIL-STD-810C, except as follows: 'A .4 inch double amplitude from 5 to 10 Hz and maximum of + 1g acceleration from 10 to 500 Hz, in lieu of Figure 514.2-2 and a given curve. Also, only the sinusoidal cycling portion will be required.".

* 4.6.27 Delete existing paragraph and add: The indicator shall be subjected to a vibration test in accordance with Method 514.2, procedure I, part 1 (curve c), category b.1 equipment of MIL-STD-810C. The frequency of vibration shall be varied uniformly at a sweep time of 1 hr. Curve c shall be modified as follows: 'A range for curve c of 5 to 50 Hz and an acceleration level of + 1 g from 23 o 50 Hz."

4.6.28 Delete existing pargraph and add: "The indicator shall be subjected to a acceleration test in accordance with Method 513.2, procedure II of MIL-STD-810C. The forward acceleration (A) level shall be 1.5g and produced by means of a centrifuge facility.

PAGE 46

* 4.6.29 Delete first sentence and add: "The unit shall be subjected to a

Source: https://assist.dla.mil -- Downloaded: 2026-10-20T12:38Z
Check the source to verify that this is the current version before use.

acceleration test in accordance with Method 513.2, procedure II of MIL-STD-810C. The forward acceleration level (A) shall be 2g and produced by means of a centrifuge facility.

* 4.6.30 Line 2 and 3 delete "procedure I of MIL-E-5272" and add "Method 507.1, procedure I of MIL-STD-810C.".

4.6.31 Line 2 delete "procedure I of MIL-E-5272" and add: Method 509.1, procedure I of MIL-STD-810C".

* 4.6.33 Delete "procedure I of MIL-E-5272." and add "Method 507.1, procedure I of MIL-STD-810C.".

* 4.6.34 Delete this portion of title "Salt spray" and add "Salt fog". Delete on line 3 "salt spray test in accordance with procedure I of MIL-E-5272." and add: "salt fog test in accordance with Method 509.1, procedure I of MIL-STD-810C.".

* 4.6.35 Delete this portion of title "Salt spray" and add "Salt fog". Delete on line 1 and 2 "salt spray test as specified in procedure I of MIL-F-5272." and add: "salt fog test in accordance with Method 509.1, procedure I of MIL-STD-810C.".

PAGE 47

* 4.6.39 Delete "procedure V of MIL-E-5272." and add: "Method 516.2, procedure I and III of MIL-STD-810C. Shock pulse shape shall be in accordance with figure 516.2-2 (amplitude a and time duration c) for both procedures. The amplifier shall be operated during procedure I.".

Delete "4.6.42 and Table VI" in its entirety.

Add: "4.6.42 Reliability".

PAGE 48

Change Table number identifier VII to VI.

* Add new paragraph: 4.6.42.1 Preproduction. The two systems specified in 4.5.2.4 shall be subjected to a preproduction reliability test in accordance with MIL-STD-781, test plan I, except as modified herein, which shall demonstrate a contractual MTBF of 600 hours. Each of the two indicators and amplifiers shall be tested in a minimum of 1,320 hours of actual electrical operation. The cycling time of 5 to 6 minutes per cycle for each indicator function display, with a minimum of 13,200 cycles per function, shall include monitor test, self test, and operation of all slew switches. A cycle shall consist of the excursion from the function minimum value to maximum and return to minimum. The test shall begin when rated power is applied to the system. After 4 hours of rated power on, the power shall be turned off for a period of 2 hours. This procedure of rated power-on, power-off shall be repeated until the test is completed. Only the power-on portion of the test shall be used in calculating the total test time required by test plan I. The system shall be tested at room temperature for approximately 64 percent of the test time, at -10° C for approximately 14 percent of the test time, and at + to 50°C for approximately 22 percent of the test time

Source: https://assist.dla.mil -- Downloaded: 2026-10-20T12:38Z
Check the source to verify that this is the current version before use.

shown in table VI. During the fifth cycle, the system shall be vibrated in accordance with paragraph 4.6.23 of this specification except as follows: 'The indicator shall be vibrated at a frequency of 35 Hz and a double amplitude of 0.036 inch in lieu of curve C.' The transition from the fourth to the fifth cycling period shall be completed in the shortest possible time to allow the vibration test to be conducted during a temperature change from -10° + 25°C. After each cycling period of electrical operation shown in table VI, the system shall be subjected to a scale error test of at least three stations per function. Any malfunction, including failure to meet the scale error test, shall be recorded, the test interrupted while repairs are made, and the test then continued from the point of interruption. Upon completion of the reliability test, the system shall again be tested for scale error with a 50 percent increase in tolerances. Failure to meet the increased-tolerance scale error test shall be considered malfunction. This test may be interrupted for normal weekend shutdown. If a reject decision is reached in accordance with test plan I of MIL-STD-781, or 13 or more failures occur in 3,660 hours of testing, delivery of production units shall be stopped and within 10 days the proposed corrective action shall be submitted to the contracting activity for approval. The equipment under test shall be modified to the approved configuration and the test rerun or continued until an accept or reject decision in accordance with test plan I (except as modified herein) is reached. At the conclusion of the redemonstration test, all equipment produced to date and all equipment subsequently produced shall be modified to the approved configuration (see 6.2). In the event a continue-test decision is reached at the end of 3,600 hours of testing, the test shall be continued until an accept or reject decision in accordance with test plan I (except as modified herein) is reached. If two or less failures occur in 3,600 hours of testing, the test samples and the first production quantity of 150 systems shall be accepted. Between 3,600 and 6,060 hours of testing, the equipment shall be accepted if the accept conditions of test plan I are met, or 6,060 hours of testing with 12 failures will constitute acceptance; 13 failures will constitute rejection. Failure to reach an accept decision in accordance with the criteria specified shall stop all deliveries until an accept decision is reached. Pattern failures, as defined in MIL-STD-781, shall require corrective action for all equipment produced to date and produced subsequently regardless of an accept or reject decision. Reporting shall be in accordance with MIL-STD-781.

* Add new paragraph: 4.6.42.2 Production. The four systems specified in 4.5.2.5 shall be subjected to a production reliability test in accordance with MIL-STD-781, test plan I, except as modified herein, which shall demonstrate a contractual MTBF of 600 hours. Each of the four indicators and amplifiers shall be tested a minimum of 900 hours of actual electrical operation. The cycling time of 5 to 6 minutes per cycle for each indicator function display, with a minimum of 13,200 cycles per function, shall include monitor test, self test, and operation of all slew switches. A cycle shall consist of the excursion from the function minimum value to maximum and return to minimum. The test shall begin when rated power is applied to the system. After 4 hours of rated power on, the power shall be turned off for a period of 2 hours. This procedure of power-on, power-off shall be repeated until the test is completed. Only the power-on portion of the test shall be used in calculating the total test time required by test plan I. The system shall be tested at room temperature for approximately 64 percent of the test time, at -10°C for approximately 14 percent of the test time, and at + 50°C for approximately 22 percent of the test time shown in table VI. During the fifth cycle, the indicator shall be vibrated in accordance with Method 514.2,

Source: https://assist.dla.mil -- Downloaded: 2026-10-20T12:38Z
Check the source to verify that this is the current version before use.

procedure 1, part 1 (curve c), category b.1 equipment of MIL-STD-810C, except as follows: 'Cycling time shall be the time of one sweep time. A range for curve c of 5 to 50 Hz and an acceleration level of + 1g from 23 to 50 Hz. Also, only the sinusoidal cycling portion will be required.". The transition from the fourth to the fifth cycling period shall be completed in the shortest possible time to allow the vibration test to be conducted during the temperture change from -10°C to +25°C. After each cycle period of electrical operation shown in table VI, the system shall be subjected to a scale error test of at least three stations per function. Any malfunction, including failure to meet the scale error test, shall be recorded, the test interrupted while repairs are made, and the test then continued from the point of interruption. Upon completion of the reliability test, the system shall again be tested for scale error with a 50 percent increase in tolerances. Failure to meet the increased-tolerances scale error test shall be considered a malfunction. This test may be interrupted for normal weekend shutdown. If a reject decision is reached in accordance with test plan I of MIL-STD-781, or 13 or more failures occur in 3,660 hours of testing, delivery of production units shall be stopped and within 10 days the proposed corrective action shall be submitted to the contracting activity for approval. The equipment under test shall be modified to the approved configuration and the test rerun or continued until an accept or reject decision in accordance with test plan I (except as modified herein) is reached. At the conclusion of the redemonstration test, all equipment produced in the particular production quantity and all equipment subsequently produced shall be modified to the approved configuration (see 6.2). In the event a continue-test decision is reached at the end of 3,600 hours of testing, the test shall be continued until an accept or reject decision is reached in accordance with test plan I (except as modified herein). If two or less failures occur in 3,600 hours of testing, the particular production quantity of 150 systems shall be accepted. Failure to reach an acceptance decision in accordance with the criteria specified shall stop deliveries of production equipment until an accept decision is reached. Pattern failures as defined in MIL-STD-781 shall require corrective action to all equipment produced in the particular production quantity and all equipment subsequently produced regardless of an accept or reject decision. This test shall be repeated for each 150 units or fraction thereof produced. Reporting shall be in accordance with MIL-STD-781."

* 4.6.43 Delete existing title "Sand and dust." and add "DUST (fine sand).". Delete "sand and dust test in accordance with MIL-E-5272, procedure I." and add dust (fine sand) test in accordance with Method 510.1, procedure I of MIL-STD-810C.".

PAGE 49

4.6.47: Delete and add:

"4.6.47 Maintainability demonstration. Maintainability demonstration shall be in accordance with MIL-STD-471, appendix B, method 2."

* Delete "4.7" and add: "4.7 Inspection of packaging. The inspection of the preservation-packaging and interior package marking shall be in accordance with Group A and B quality conformance inspection requirements, Section 4 of MIL-P-116. The sampling and inspection of the packing and marking for shipment and storage shall be in accordance with the quality assurance provisions of applicable container specification and the marking requirements of MIL-STD-129.

Source: https://assist.dla.mil -- Downloaded: 2026-10-20T12:38Z
Check the source to verify that this is the current version before use.

* Delete Section 5 in its entirety and add:

"5. PACKAGING

5.1 Preservation-Packaging: Preservation-packaging shall be level A, C or industrial as specified. (see 6.2)

5.1.1 Level A

5.1.1.1 Cleaning. Amplifier-Indicator shall be cleaned in accordance with process C-1 of MIL-P-116.

5.1.1.2 Drying. Amplifier-Indicator shall be dried in accordance with process D-4 of MIL-P-116.

5.1.1.3 Preservation Application. Not applicable.

5.1.1.4 Unit Packaging. Unless otherwise specified by the contracting activity, each amplifier-indicator shall be packaged in quantity unit packs of one each in accordance with Method 1C1 of MIL-P-116. Overbox completed pack in PPP-B-636 container. Apply sufficient cushioning material between bag and unit container of a type, density, and thickness to insure shock transmission does not exceed peak values in G's established for the amplifier-indicator when completed packs are subjected to the rough handling drop tests of MIL-P-116.

5.1.2 Level C. Amplifier-Indicator shall be clean, dry, and individual packaged in a manner that will afford adequate protection against corrosion, deterioration, and physical damage during shipment from supply source to the first receiving activity.

5.1.2 Industrial. The industrial preservation of amplifier-indicator shall be in accordance with ASTM D3951.

5.2 Packing. Packing shall be level A, B, C, or Industrial as specified (see 6.2).

5.2.1 Level A. Amplifier-Indicator packaged as specfied in 5.1.1 shall be packed in shipping containers conforming to PPP-B-601, Styles A or B Class overseas, unless otherwise specified by the contracting activity. Insofar as practical, exterior shipping container shall be of uniform shape, size, minimum tare and cube consistent with the protection required.

5.2.2 Level B. Amplifier-Indicator packaged as specified in 5.1.1 shall be packed in shipping containers conforming to PPP-B-636 class weather-resistant, unless otherwise specified by the contracting activity. Other requirements as specified in 5.2.1 apply.

5.2.3 Level C. Packing shall be applied which affords adequate protection during domestic shipment from the supply source to the first receiving activity for immediate use. This level shall conform to applicable carrier rules and regulations.

5.2.3 Industrial. The packaged Amplifier-Indicator shall be packed in accordance with ASTM D3951.

Source: https://assist.dla.mil -- Downloaded: 2026-10-20T12:38Z
Check the source to verify that this is the current version before use.

5.3 Marking. In addition to any other markings required by the contract or order (see 6.2), interior and exterior containers shall be marked in accordance with MIL-STD-129.

PAGE 50

6.2 Add:

"g. When sampling plans C and D, tests will not be performed (see 4.5.2.4 and 4.5.2.5).

h. That systems modified to an approved configuration will be at no additional contract cost (see 4.6.42.1 and 4.6.42.2)."

* Delete "6.3" and add: "6.3 First article. When a first article inspection is required sample units shall be inspected as specified (see 3.1 and 4.2).

The margins of this amendment are marked with an asterisk to indicate where changes (additions, modifications, corrections, deletions) from the previous amendment were made. This was dones as a convenience only and the Government assumes no liability whatsoever for any inaccuracies in these notations. Bidders and contractors are cautioned to evaluate the requirements of this document based on the entire content irrespective of the marginal notations and relationship to the last previous amendment.

Custodian:
AIR FORCE-99

Preparing Activity:
AIR FORCE-71

Project No.
6610-F131

Source: https://assist.dla.mil -- Downloaded: 2026-10-20T12:38Z
Check the source to verify that this is the current version before use.