MIL-D-43149B(ME)
31 January 1979
SUPERSEDING
MIL-D-43149A(ME)
20 April 1973

MILITARY SPECIFICATION

DRUM AND PUMP UNITS, LIQUID DISPENSING, TRACKED CARRIER MOUNTING

This specification is approved for use by the Mobility Equipment Research and Development Command, Department of the Army, and is available for use by all Departments and Agencies of the Department of Defense.

1. SCOPE

1.1 Scope. This specification covers two types of liquid dispensing drum and pump units for mounting in a tracked cargo carrier, 6-ton capacity, M548 for refueling tactical equipment in the field.

1.2 Classification (see 6.3). Dispensing units covered by this specification shall be of the following types as specified (see 6.2).

Type I - Drum and Pump Unit Liquid Dispensing, with Fabric Drums.
Type II - Drum and Pump Unit Liquid Dispensing, with Metal Tanks.

FSC 4930

Beneficial comments (recommendations, additions, deletions) any any pertinent data which may be of use in improving this document should be addressed to: US Army Mobility Equipment Research and Development Command, ATTN: DRDME-DS, Fort Belvoir, VA 22060 by using the self-addressed Standardization Document Improvement Proposal (DD Form 1426) appearing at the end of this document or by letter.

Source: https://assist.dla.mil -- Downloaded: 20260-21T20:47Z
Check the source to verify that this is the current version before use.

2. APPLICABLE DOCUMENTS

2.1 Issues of documents. The following documents of the issue in effect on date of invitation for bids or request for proposal form a part of this specification to the extent specified herein:

SPECIFICATIONS

FEDERAL

O-E-915	- Extinguisher, Fire, Dry-Chemical (Hand-Portable).
PPP-B-601	- Boxes, Wood, Cleated-Plywood.
PPP-B-636	- Boxes, Shipping, Fiberboard.
PPP-P-40	- Packaging and Packing of Hand Tools.
PPP-T-60	- Tape: Packaging, Waterproof.

MILITARY

MIL-P-116	- Preservation-Packaging, Methods of.
MIL-T-704	- Treatment and Painting of Materiel.
MIL-E-16298	- Electric Machines Having Rotating Parts and Associated Repair Parts: Packaging of.
MIL-L-21260	- Lubricating Oil, Internal Combustion Engine, Preservative and Break-In.
MIL-T-22238	- Tank, Liquid Storage, Metal for Petroleum Products, Horizontal with Skids, 600-Gallon Capacity.
MIL-D-23119	- Drums, Fabric, Collapsible, Liquid Fuel, Cylindrical; 500-Gallon Capacity.
MIL-F-52667	- Filter-Separators, Liquid Fuel: 50 GPM Capacity.
MIL-C-62122	- Cable Assembly, Slave, Electrical Connectors, Plug and Receptacle.

STANDARDS

FEDERAL

FED. STD. No. 595	- Colors.

MILITARY

MIL-STD-105	- Sampling Procedures and Tables for Inspection by Attributes.
MIL-STD-129	- Marking for Shipment and Storage.

Source: https://assist.dla.mil -- Downloaded: 2026-10-21T20:47Z
Check the source to verify that this is the current version before use.

MIL-STD-130	- Identification Marking of US Military Property.
MIL-STD-209	- Slinging and Tiedown Provisions for Lifting and Tying Down Military Equipment.
MIL-STD-461	- Electromagnetic Interference Characteristics Requirements for Equipment.
MIL-STD-781	- Reliability Tests: Exponential Distribution.
MIL-STD-810	- Environmental Test Methods.
MIL-STD-882	- System Safety Program for Systems and Associated Subsystems and Equipment: Requirements for.
MIL-STD-1188	- Commercial Packaging of Supplies and Equipment.
MIL-STD-1472	- Human Engineering Design Criteria for Military Systems, Equipment and Facilities.
MIL-STD-1474	- Noise Limits for Army Materiel.
MS3102	- Connector, Receptacle, Electric, Box Mounting, Solder Contacts, AN Type.
MS25043	- Cover, Electrical Connector, Receptacle, AN Type.

DRAWINGS

ME

TA13217E2960	- Drum and Pump Unit Liquid Dispensing with Fabric Drums Type I.
TA13217E2970	- Drum and Pump Unit Liquid Dispensing with Metal Tanks Type II.

(Copies of specifications, standards, and drawings required by contractors in connection with specific procurement functions should be obtained from the procuring activity or as directed by the contracting officer.)

2.2 Other publications. The following documents form a part of this specification to the extent specified herein. Unless otherwise indicated, the issue in effect on date of invitation for bids or request for proposal shall apply.

NATIONAL BUREAU OF STANDARDS

Handbook H28 - Screw-Thread Standards for Federal Services.

Source: https://assist.dla.mil -- Downloaded: 2026-10-21T20:47Z
Check the source to verify that this is the current version before use.

(Application for copies should be addressed to the Superintendent of Documents, Government Printing Office, Washington, DC 20402.)

HYDRAULIC INSTITUTE

Hydraulic Institute Standards.

(Application for copies should be addressed to the Hydraulic Institute, 122 East 42nd Street, New York, NY 10017.)

SOCIETY OF AUTOMOTIVE ENGINEERS

SAE Handbook.

(Application for copies should be addressed to the Society of Automotive Engineers, 400 Commonwealth Drive, Warrendale, PA 15096.)

ASSOCIATION OF AMERICAN RAILROADS

Rules Governing the Loading of Department of Defense Materiel on Open Top Cars.

(Application for copies should be addressed to the Association of American Railroads, 59 East Van Buren Street, Chicago, IL 60605.)

AMERICAN WELDING SOCIETY

Standard Qualification Procedure.

(Application for copies should be addressed to the American Welding Society, 2501 N.W. 7th Street, Miami, FL 33125.)

AMERICAN SOCIETY OF MECHANICAL ENGINEERS

Boiler and Pressure Vessel Code, Section IX.

(Application for copies should be addressed to the American Society of Mechanical Engineers, 345 East 47th Street, New York, NY 10017.)

UNDERWRITERS' LABORATORIES, INC., (UL)

UL 674B - Electric Motors and Generators for Use in Hazardous Locations.

Source: https://assist.dla.mil -- Downloaded: 2026-10-21T20:47Z
Check the source to verify that this is the current version before use.

(Application for copies should be addressed to the Underwriters' Laboratories, Inc., 207 East Ohio Street, Chicago, IL 60611; 333 Pfingsten Road, Northbrook IL 60062; 1285 Walt Whitman Road, Melville L.I., NY 11746; or 1655 Scott Boulevard, Santa Clara, CA 95050.)

3. REQUIREMENTS

3.1 Description. The drum and pump units (hereinafter called "dispensing units") shall be in accordance with Top Assemblies TA13217E2960 for Type I and TA13217E2970 for Type II, and as specified herein.

3.1.1 Drawings. The drawings forming a part of this specification are end product drawings. No deviations from the prescribed dimensions or tolerances is permissible without prior approval of the contracting officer. Any data (e.g., shop drawings, layouts, flow sheets, processing procedures, etc.) prepared by the contractor or obtained from a vendor to support fabrication and manufacture of the production item shall be made available, upon request, for inspection by the contracting officer or his designated

3.1.2 Interchangeability. All parts having the same part number shall be functionally and dimensionally interchangeable. Interchangeable parts are defined as two or more parts possessing such functional and physical characteristics as to be equivalent in performance and durability and capable of being exchanged one for the other without alteration of the parts themselves or of adjoining parts except for adjustment, and without selection for fit or performance.

3.2 First article (preproduction model). The contractor shall furnish one or more dispensing units as specified (see 6.2), for examination and testing within the time frame specified (see 6.2), to prove prior to starting production that his production methods will produce dispensing units that comply with the requirements of this specification. Examination and tests shall be as specified in Section 4 and unless otherwise specified herein, all examination and tests shall be conducted by the contractor subject to surveillance and approval by the Government (see 6.4). When specified (see 6.2), the Government will conduct any or all of the preproduction examination and tests, as specified.

3.3 Initial production. When specified (see 6.2), the contractor shall furnish to the Government one or more dispensing units for inspection as specified in 4.4.

3.4 Material. Material shall be as specified herein and as shown on the applicable drawings. Materials not as specified shall be selected by the contractor and shall be subject to all provisions of this specification (see 6.12).

Source: https://assist.dla.mil -- Downloaded: 2026-10-21T20:47Z
Check the source to verify that this is the current version before use.

3.5 Environmental.

3.5.1 Operating temperature. The dispensing unit shall perform as specified in any ambient temperature from plus 125° F to minus 25° F.

3.5.2 Storage temperature. The dispensing unit shall not be damaged by storage in any ambient temperature from plus 160° F to minus 50° F.

3.6 Safety. Pumping assemblies shall incorporate the system safety criteria and considerations specified in MIL-STD-882.

3.7 Human factors. The dispensing unit shall conform to the human factors engineering criteria as specified in MIL-STD-1472. The noise level of the pumping assembly shall not exceed the level specified in MIL-STD-1474, Category D when tested as specified in 4.6.2.11.

3.8 Maintainability.

3.8.1 Maintenance support. Assemblages or support elements such as technical manuals, repair parts, special tools or lubrication charts as specified (see 6.10 and 6.11), shall be adequate to perform the intended function of assisting or conducting maintenance operations when tested as specified in 4.6.2.12.

3.8.2 Maintenance ratio. The dispensing unit shall have a maintenance ratio of no greater than 0.08. A maintenance schedule shall be furnished prior to the start of the preproduction test.

3.9 Reliability. The upper test Mean-Time-Between-Failure (MTBF) (θ_0) shall be 114 hours and the lower test MTBF (θ_1) shall be 72 hours when the dispensing unit is operated at rated capacity and tested as specified in 4.6.2.13.

3.10 Performance.

3.10.1 Motor. The motor shall be direct current, 24 volts, 1.5 horsepower (hp), 3450 revolutions per minute (rpm) 75° C rise over a 40° C ambient, 30 minute duty cycle, permanent magnet, totally enclosed, nonventilated and explosionproof. The motor shall be equipped with a thermal overload device located within the winding that will shut off the motor at a temperature of 20 Centigrade below the maximum operating temperature.

3.10.2 Power cable receptacle. The motor shall be equipped with a receptacle conforming to MIL-C-62122.

3.10.3 Control cable receptacle. The motor shall be equipped with a receptacle conforming to MS3102R16S-4S with cover conforming to MS25043-16D.

Source: https://assist.dla.mil -- Downloaded: 2026-10-21T20:47Z
Check the source to verify that this is the current version before use.

3.10.4 Explosionproof. The electric motor assembly complete with all receptacles and connectors shall be explosionproof in accordance with UL 674(B), Class I, Group D, Division I.

3.10.5 Pump. The pump shall be a centrifugal, self-priming, close coupled, volatile liquid handling pump.

3.10.6 Pump capacity. The pump shall have the capacity to deliver liquid hydrocarbon fuels having a specific gravity of 0.075 at not less than 50 GPM when tested as specified in 4.6.2.4. The required net positive suction head (NPSH) of the pump shall not exceed 8 feet at the required flow rate of 50 gpm and a head of 60 feet.

3.10.7 Pump efficiency. The pump shall develop an efficiency of not less than 50 percent when tested as specified in 4.6.2.4.

3.10.8 Pump priming. The pump shall prime in not more than 2 minutes when tested as specified in 4.6.2.3.

3.10.9 Hydrostatic strength. The pump shall be capable of withstanding a hydrostatic pressure of 100 psi without evidence of leakage, rupture or distortion when tested as specified in 4.6.2.2.

3.11 Transportability.

3.11.1 Lifting and tiedown attachments. Lifting and tiedown attachments shall be compatible with the transportation mode requirements and shall conform to MIL-STD-209 when tested as specified in 4.6.2.14.1.

3.11.2 Rail impact. The dispensing units shall be suitable for transport by rail, truck, and air. The dispensing units shall meet test requirements of the Association of American Railroads (AAR) recommended procedures for conducting field impact tests of loaded freight cars when tested as specified in 4.6.2.14.2.

3.11.3 Mobility. The dispensing unit when installed in the Carrier, Cargo, Tracked, 6-ton, M548 shall be capable of travel over roads as follows without malfunction, permanent deformation, or damage to the dispensing unit or components:

(a) Over hard-surfaced roads at an average speed of 40 mph.
(b) Over gravel roads at an average speed of 20 mph.
(c) Over cross-country terrain at an average speed of 15 mph.
(d) Over Belgian Block at an average speed of 15 mph.

Source: https://assist.dla.mil -- Downloaded: 2026-10-21T20:47Z
Check the source to verify that this is the current version before use.

3.11.4 Slope capability. The M548 mounted dispensing unit shall be capable of travel on side slopes of 20 percent and up-grade and down grade on slopes of 30 percent when tested as specified in 4.6.2.16.

3.11.5 Emergency stops. The M548 mounted dispensing unit shall be capable of withstanding emergency stops at forward speeds up to 40 mph and at reverse speeds up to 10 mph without permanent deformation, failure, or damage to the dispensing unit or components.

3.11.6 Amphibious capability. The M548 Cargo Carrier shall be capable or normal amphibious operation with the dispensing unit installed.

3.12 Electromagnetic interference. The electromagnetic interference emission characteristics of the dispensing unit shall conform to MIL-STD-461, Class IIC.

3.13 Lubrication. The dispensing unit shall operate as specified herein when lubricated with military lubricants (see 6.5).

3.14 Fire extinguisher. When specified (see 6.2), a fire extinguisher conforming to O-E-915, Type II, Class 2, Size 20, with vehicle mounting bracket will be furnished by the Government (see 6.6).

3.15 Identification marking. The dispensing units shall be identified in accordance with MIL-STD-130.

3.16 Treatment and painting. The portions of the dispensing unit normally painted shall be cleaned, treated, and painted in accordance with MIL-T-704, Type A, color olive drab number 24087 conforming to FED. STD. No. 595.

3.17 Workmanship.

3.17.1 Castings and forgings. All parts, components, and assemblies of the pumping assembly which include castings and forgings shall be clean of harmful extraneous material such as sand, dirt, pits, sprues, scale, and flux. Rework shall be limited to procedures which do not reduce strength or affect function.

3.17.2 Piping, fittings, hose, cables. All piping, fittings, hose, control cables, and electrical cables shall be supported to prevent damage due to vibration, chafing, or sharp bends.

3.17.3 Metal fabrication. Metal used in fabrication shall be free from kinks and sharp bends. The straightening of material shall be done by methods that will not cause injury to the material. Corners shall be square

Source: https://assist.dla.mil -- Downloaded: 2026-10-21T20:47Z
Check the source to verify that this is the current version before use.

and true. Flame cutting, using tips suitable for the thickness of the steel may be employed instead of shearing and sawing. All bends shall be made with controlled means to insure uniformity of size and shape. Precaution shall be taken to avoid overheating. Heated steel shall be allowed to cool slowly. External surfaces shall be free of burrs, sharp edges, and corners, except when sharp edges or corners are required or where they are not detrimental to safety.

3.17.4 Aluminum welding. The aluminum surfaces of parts to be welded shall be free from scale, paint, grease, oxide film, and other foreign matter. The welding shall be done by the inert gas (argon or helium) shielded-arc method. Welds may be ground, filed, buffed, or chipped but not hammered and shall be free from defects such as bass metal cracks adjacent to or behind welds, cracks in weld metal, undercutting of base metal, lack of fusion with parent metal or between parts, porosity, lack of penetration, lack of prescribed fit, slag inclusion or spatter.

3.17.5 Welding. The surfaces of parts to be welded shall be free from rust, scale, paint, grease, mill scale that can be removed by chipping and wire brushing and other foreign matter. Welds shall transmit stress without permanent deformation or failure when the parts connected by welds are subjected to proof service loading. Parent materials, weld filler metals, and fabrication techniques shall be as required to enable the pumping assembly to conform to the examination and test requirements specified in Section 4. Parts to be joined by fillet welds shall be brought into as close contact as possible and in no event shall be separated by more than 3/16-inch, unless appropriate bridging techniques are used. Unless otherwise specified herein, the welding process used in fabrication of the pumping assembly shall be at the option of the contractor.

3.17.6 Welders. Before assigning any welder to manual welding work covered by this specification, the contractor shall provide the contracting officer with certification that the welder has passed qualification tests as prescribed by either of the following listed codes for the type of welding operations to be performed and that such qualification is effective as defined by the particular code:

Standard Qualification Procedure of American Welding Society.
Welding Qualification of the ASME.

Contractors who only make horizontal welds need not qualify welders for "all position welding". Subject to approval by the Government, the contractor's standard welder qualification may be substituted in lieu of the above codes provided that the contractor's procedure is equivalent to the above codes. The contractor shall be responsible for determining that automatic welder equipment operators are capable of producing quality welds.

Source: https://assist.dla.mil -- Downloaded: 2026-10-21T20:47Z
Check the source to verify that this is the current version before use.

3.17.7 Welding practice.

(a) Preheat of materials be welded, and maximum interpass temperature during welding, shall be in accordance with the contractor's recommendations.
(b) Tack welds shall be subject to the same quality requirements as final welds.
(c) Work shall be positioned for flat welding whenever practicable.
(d) Procedures and sequences shall be such that distortion and shrinkage will be held to a minimum. When straightening is required, caution shall be exercised to insure that the straightening process does not weaken the part and pumping assembly.

3.17.8 Weld quality.

(a) The contractor shall be responsible for determining the inspections needed to insure that, when the welded parts are assembled together to make the dispensing unit, the dispensing unit shall conform to the inspection requirements specified in Section 4.
(b) All weldments shall be free of slag, flux, weld spatter, and other impurities detrimental to both the appearance and strength of the weldment.
(c) Undercut in weldments shall be held to a minimum but shall not be more than 1/32-inch deep.

3.17.9 Bolted connections. Boltholes shall be accurately formed and shall have the burrs removed. Washers or lockwashers shall be provided where necessary. Matching thread areas securing bolts conforming to SAE J429 or capscrews shall be of sufficient strength to withstand the tensile strength of the bolt. All fasteners shall be correctly torqued and shall have full thread engagements.

3.17.10 Machine work. Tolerances and gages for metal fits shall conform to the limits specified herein, and on applicable drawings and to the standards of the industry.

4. QUALITY ASSURANCE PROVISIONS

4.1 Responsibility for inspection. Unless otherwise specified in the contract, the contractor is responsible for the performance of all inspection requirements as specified herein. Except as otherwise specified in the contract, the contractor may use his own or any other facilities suitable for the performance of the inspection requirements specified herein, unless

Source: https://assist.dla.mil -- Downloaded: 2026-10-21T20:47Z
Check the source to verify that this is the current version before use.

disapproved by the Government. The Government reserves the right to perform any of the inspections set forth in the specification where such inspections are deemed necessary to assure supplies and services conform to prescribed requirements.

4.1.1 Acceptability criteria. Dispensing units which conform to all requirements in Sections 3 and 5 of this specification and pass all applicable examinations and tests in Section 4 of this specification will be considered acceptable by the Government.

4.1.2 Component and material inspection. The contractor is responsible for insuring that components and materials used are manufactured, examined, and tested in accordance with referenced specifications and standards.

4.1.3 Disassembly inspection. The preproduction dispensing unit failing a performance test shall be disassembled to the extent necessary to determine the cause in the presence of a Government representative. Each disassembled part shall be inspected in detail for compliance with this specification and referenced drawings in regard to materials, dimensions, and tolerances. Parts not complying with such requirements shall be rejected.

4.1.4 Parts and components. Parts and components detailed on the drawings shall be inspected in accordance with the Supplementary Quality Assurance Provisions (SQAP) shown on the drawings. The drawings specify the characteristics requiring SQAP inspection, the sampling plan, and the basis for acceptance and rejection (see 6.7 and 6.8).

4.2 Classification of inspections. The inspection requirements specified herein are classified as follows:

(a) Preproduction inspection (see 4.3).
(b) Initial production inspection (see 4.4).
(c) Quality conformance inspection (see 4.5)
(d) Inspection comparison (see 4.7).
(e) Inspection of packaging (see 4.8).

4.3 Preproduction inspection.

4.3.1 Examination. The preproduction dispensing unit(s) shall be examined as specified in 4.6.1. Presence of one or more defects shall be cause for rejection.

4.3.2 Tests. The preproduction dispensing unit(s) shall be subjected to the tests marked "X" in Column 1 of Table I. Failure of any test shall be cause for rejection, or for performing the inspection specified in 4.1.3.

Source: https://assist.dla.mil -- Downloaded: 2026-10-21T20:47Z
Check the source to verify that this is the current version before use.

4.4 Initial production inspection. When specified (see 3.3), one or more initial production dispensing units will be selected at random by the Government from units being produced from production tooling and will be examined as specified in 4.6.1 and subjected to the tests marked "X" in Column 2 of Table I, to determine conformance to the requirements of this specification. The inspection will be performed by the Government at a site selected by the Government. Acceptance of an initial production dispensing unit shall not exclude the remaining dispensing units from the quality conformance inspection and acceptance provisions specified in Section 4. In addition to any test specified as part of the initial production test, the Government reserves the right to conduct any and all other tests contained in this specification as part of the initial production test and failure of such additional tests shall have the same effect as failure of those tests specified as initial production tests.

4.4.1 Inspection failure. Failure of an initial production dispensing unit to meet any requirement specified herein during and as a result of the examination and tests specified in 4.4 shall be cause for rejection of the initial production dispensing unit(s) and shall be cause for refusal by the Government to continue acceptance of production dispensing units until evidence has been provided by the contractor that corrective action has been taken to eliminate the deficiencies. Correction of such deficiencies shall be accomplished by the contractor at no cost to the Government on dispensing units previously accepted and produced under the contract. Any deficiencies found as a result of the initial production inspection will be considered prima facie evidence that all dispensing units accepted prior to the completion of initial production inspection are similarly deficient unless evidence to the contrary is furnished by the contractor and such evidence is acceptable to the contracting officer.

4.5 Quality conformance inspection.

4.5.1 Sampling. Sampling for examination shall be in accordance with MIL-STD-105, Inspection Level III. A lot shall not exceed 25 dispensing units.

4.5.2 Examination. Samples selected in accordance with 4.5.1 shall be examined for the major and minor defects specified in 4.6.1. AQL shall be 0.4 percent defective for major defects and 1.0 percent defective for minor defects.

4.5.3 Tests.

4.5.3.1 Individual. Each pump-motor assembly shall be subjected to the tests marked "X" in Column 3 of Table I. Failure of any test shall be cause for rejection.

Source: https://assist.dla.mil -- Downloaded: 2026-10-21T20:47Z
Check the source to verify that this is the current version before use.

4.6 Inspection procedure.

4.6.1 Examination. The dispensing unit shall be examined as specified herein for the following defects:

Major

101. Not enameled (where required).
102. Rust on exposed area.
103. Rust or corrosion.
104. Loose metal chips, burrs, or slivers.
105. Blowholes in casting.
106. Casting miscast or pitted.
107. Weld (except spot weld) missing where required.
108. Weld completely broken or not fused.
109. Component deformed, buckled, warped, bent, broken, fractured, or cracked.
110. Nozzle provided not as specified.
111. Ground-wire assemblies missing.
112. Nozzles not equipped with a cap, chain, and spring.
113. Coupling half that does not fit intended mating component.
114. Less than two hose clamps at any end of hose.
115. Discharge hose or suction hose assemblies not as specified.
116. Cable not as specified.
117. Cable assembly not as specified.
118. Electrical connection wrong location.
119. Pump housing not provided with a clean-out drainplug.
120. Pump shaft seal not as specified.
121. Wrench not positioned and mounted as indicated.
122. Quick couplings in the discharge opening of 4-way valves not type specified.
123. Suction and discharge coupling halves not provided with dust caps or plugs, as applicable.
124. Pump not secured to base frame.
125. O-rings missing on 4-way valve.
126. Hooks missing.
127. Lever inoperative (when subject to manual movement).
128. Filter-separator not as indicated on drawing.
129. Sight gage cracked or broken.
130. Rubber gasket on cover damaged or missing.
131. Extinguisher and bracket not provided (when applicable).
132. Evidence of leakage.
133. Identification marking not as specified.
134. Identification or instruction plate not attached as specified.
135. Identification information illegible, incorrect, or incomplete.

Source: https://assist.dla.mil -- Downloaded: 2026-10-21T20:47Z
Check the source to verify that this is the current version before use.

136. Electromagnetic interference suppression components and network not identical with approved model.
137. Motor not identical to preproduction model motor.

Minor

201. Enamel blistered, peeling, or lifted.
202. Bolt, nut, screw, or washer missing (where required).
203. Type of bolt, nut, screw, cotter pin, or washer not as specified.
204. Any rivets missing where required.
205. Riveted not peened securely, i.e., loose where rigidity is required.
206. Type of rivet is not as specified.
207. Spot weld missing where required.
208. Spot welds (when applicable) not spaced as specified.
209. Fit of hose on fitting too loose or insecurely attached.
210. Hose clamp not type specified.
211. Differential pressure indicator damaged or broken.

Table I. Test Schedule

Pre-production Model	Initial Production	Quality Conformance	Test	Test Para	Requirement Para
1	2	3	4	5	6
X	X	X	Hydrostatic.	4.6.2.2	3.10.9
X	X	-	Priming.	4.6.2.3	3.10.8
X	X	-	Capacity.	4.6.2.4	3.10.6
X	X	-	Efficiency.	4.6.2.4	3.10.7
X	-	-	Motor.	4.6.2.5	3.10.1
X	X	-	Operational.	4.6.2.6	3.10.6
-	-	X	Production.	4.6.2.7	3.10.6
-	X	-	High Temperature.	4.6.2.8	3.5
-	X	-	Low Temperature.	4.6.2.9	3.5
-	X	-	Safety.	4.6.2.10	3.6
-	X	-	Human Factors.	4.6.2.11	3.7
-	X	-	Maintenance Support.	4.6.12.1	3.8.1
-	X	-	Maintenance Ratio.	4.6.12.2	3.8.2
-	X	-	Reliability.	4.6.2.13	3.9
X	X	-	Lifting and Tiedown Attachments.	4.6.2.14.1	3.11.1

Source: https://assist.dla.mil -- Downloaded: 202610-21T20:47Z
Check the source to verify that this is the currentversion before use.

Table I. Test Schedule (Cont'd)

1	2	3	4	5	6
-	X	-	Rail Impact.	4.6.2.14.2	3.11.2
-	X	-	Mobility.	4.6.2.15	3.11.3
-	X	-	Slope.	4.6.2.16	3.11.4
-	X	-	Emergency Stop.	4.6.2.17	3.11.5
-	X	-	Amphibious.	4.6.2.18	3.11.6
X	-	-	Electromagnetic Interference.	4.6.2.19	3.12

4.6.2 Tests.

4.6.2.1 Test conditions. Unless otherwise specified in a test, tests shall be performed in accordance with the applicable provisions of the test code for centrifugal pumps of the standards of the Hydraulic Institute. All performance data shall be corrected to standard sea level conditions of barometric pressure of 29.92 inches of mercury and liquid fuel at 60° F having a specific gravity of 0.75 and vapor pressure of 4.0 psi. Water at a temperature of between 60° F to 80° F may be used as the test fluid.

4.6.2.2 Hydrostatic. Subject the pump motor assembly to a hydrostatic pressure of 100 psi for a period of not less than 5 minutes. Nonconformance to 3.10.9 shall constitute failure of this test.

4.6.2.3 Priming. The suction and discharge hose assemblies shall be drained and connected to the four way valve. One end of the suction hose assembly shall be placed in water with the surface located a minimum of 8 feet below the center line of the pump impeller. The pump shall be initially primed with gasoline and operated. Repeat the above procedure except the discharge hose shall become the suction inlet by operating the four way valve. Nonconformance to 3.10.8 shall constitute failure of this test.

4.6.2.4 Pump capacity. Test the pump motor assembly in accordance with the applicable sections of the centrifugal pump test code of the Hydraulics Institute. The test liquid shall be clear fresh water within the temperature range of 60° F to 80° F. Characteristic curves shall be plotted from this test while operating from no flow to maximum flow, plotting dynamic head, efficiency, power input, and rpm versus capacity in gpm. The test data and characteristic curves shall include complete information for correlation of the test liquid to determine hydrocarbon fuel capacity specified in 3.10.6 and efficiency specified in 3.10.7. Nonconformance to 3.10.6 or 3.10.7 shall constitute failure of this test.

Source: https://assist.dla.mil -- Downloaded: 2026-10-21T20:47Z
Check the source to verify that this is the current version before use.

4.6.2.5 Motor. The motor to be installed in the preproduction model(s) shall be UL listed in accordance with UL 674B, Class I, Group D, Division I. Nonconformance to 3.10.4 shall constitute failure of this test.

4.6.2.6 Operational. Fill the pump case with either petroleum fuel or a suitable solvent having a specific gravity of 0.75 and prime the pumping assembly with a static suction lift equivalent to 8 feet of water at standard atmospheric conditions. Once the pump has primed, open the discharge and operate the pump at 50 gpm at 60 foot head for 100 hours. This test shall be performed by operating for not less than 12 continuous hours daily until the conclusion of the test. During operation, only minor adjustments to the engine and discharge valving may be performed. A maximum shutdown time of 15 minutes is allowable for motor maintenance and examination during each 12-hour period. During operation, determinations shall be made as to whether there is leakage through the pump case, piping, fittings, or at the pump shaft seal and whether there is malfunction of any component. Evidence of leakage, malfunction of any component, inability of the pumping assembly to prime in 1 minute and deliver the capacity specified or inability of the pumping assembly to operate continuously shall constitute failure of this test.

4.6.2.7 Production. Test the pumping assembly as specified in 4.6.2.6 except that the operating time shall be 15 minutes.

4.6.2.8 High temperature. The dispensing unit shall be tested as specified in MIL-STD-810, Method 501, Procedure I. The maximum ambient storage temperature shall be 160° F and the maximum ambient operating temperature shall be 125° F. The operating period of Procedure I shall be 2 hours. The dispensing unit shall be operated at rated capacity. Nonconformance to 3.5 shall constitute failure of this test.

4.6.2.9 Low temperature. The dispensing unit shall be tested as specified in MIL-STD-810, Method 502, Procedure I. The minimum ambient storage temperature shall be minus 50° F. The minimum ambient operating temperature shall be minus 25° F. The operating period of Procedure I shall be 2 hours. The dispensing unit shall be operated at rated capacity. Nonconformance to 3.5 shall constitute failure of this test.

4.6.2.10 Safety. The dispensing unit shall be evaluated throughout testing as specified in 4.6.2. Nonconformance to 3.6 shall constitute failure of this test.

4.6.2.11 Human factors. Noise level shall be determined by placing the dispensing unit in a test area which is free of any large reflecting surfaces, such as signs or hillsides, within 50 feet of the unit or sound-level

Source: https://assist.dla.mil -- Downloaded: 2026-10-21T20:47Z
Check the source to verify that this is the current version before use.

measuring equipment. With the dispensing unit operated at rated load, a sound level survey will be made around the dispensing unit to determine the direction in which the maximum sound levels are propagated so that the test equipment may be correctly oriented. The recording microphones shall be positioned at 5 and 25 feet from the unit at a height to simulate the ear positions of the operating personnel. The noise level shall be measured with the dispensing unit operated at rated output. Operating noise exceeding the allowable limits stated in MIL-STD-1474 shall constitute failure of this test.

4.6.2.12 Maintainability.

4.6.2.12.1 Maintenance support. Maintenance operations required during initial production testing shall be accomplished by operating personnel in accordance with the requirements of 3.8.1. Failure of the support elements to maintain the dispensing unit as specified shall constitute failure of this test.

4.6.2.12.2 Maintenance ratio. The maintenance ratio shall be computed during initial production testing to determine compliance with 3.8.2. The maintenance ratio is defined as the total active maintenance manhours (scheduled and unscheduled) required to the total operating time. Nonconformance to 3.8.2 shall constitute failure of this test.

4.6.2.13 Reliability. The initial production dispensing unit(s) shall be tested as specified in 4.6.2.6 with "accept" and "reject" criteria in accordance with MIL-STD-781, Test Plan IVC using the MTBF specified in 3.9. A failure is defined as any malfunction which cannot be corrected within 30 minutes by adjustment, repair, or replacement action using controls, on-equipment tools or parts and which causes or may cause:

(1) Failure to commence operation, cessation of operation or degradation of performance below specified levels.
(2) Serious damage to the dispensing unit by continued operation.
(3) Serious personnel safety hazards.

4.6.2.14 Transportability.

4.6.2.14.1 Lifting and tiedown attachments. Lifting and tiedown attachments shall be subjected to static pull tests equivalent to those specified in MIL-STD-209. Nonconformance to 3.11.1 shall constitute failure of this test.

4.6.2.14.2 Rail impact. Tests shall be conducted in accordance with the Association of American Railroads (AAR) recommended procedures for conducting field impact tests of loaded freight cars. The dispensing unit shall be

Source: https://assist.dla.mil -- Downloaded: 2026-10-21T20:47Z
Check the source to verify that this is the current version before use.

blocked, braced, and tied down in accordance with procedures contained in the technical manuals or as specified in AAR Rules Governing the Loading of Department of Defense Materiel on Open Top Cars. The dispensing unit prepared for shipment shall be loaded and tied down on an open top flat car. Instrumented tests shall be conducted at speeds of 4, 6, and 8 mph in one direction, and at 8 mph in the opposite direction. After each impact the load and the tiedowns shall be inspected to determine the amount of load shift, condition of blocking and bracing, or evidence of possible failure. Once the test has begun, there shall be no readjustment of load, nor any reconditioning of bracing and chock material or tiedowns. After completion of the rail impact testing, an operational check-out of the dispensing unit shall be conducted. Any failure of tiedown attachments, any damage or permanent deformation to the unit or failure of the dispensing unit to operate as specified after rail impact testing shall constitute failure of this test.

4.6.2.15 Mobility. The carrier-mounted dispensing unit shall be driven over a smooth, hard-surfaced road at an average speed of 40 mph for a total of 600 miles; over gravel road at an average speed of 20 mph for 100 miles; over cross-country terrain at an average speed of 15 mph for a total of 200 miles; over Belgium Block at an average speed of 15 mph for a total of 100 miles. The drums or tanks shall be full for 50 percent of the mileage of each type road surface, and half full and empty each for 25 percent of the mileage of each type surface. After each of the above segments of the test the unit shall be operated at rated capacity for one hour. Breakage, permanent deformation, damage to the dispensing unit, components, or failure of the dispensing unit to operate as specified shall constitute failure of this test.

4.6.2.16 Slope. The fully loaded carrier-mounted dispensing unit shall be moved along a side slope of 20 percent. The procedure shall be repeated in the opposite direction. The carrier shall be driven upgrade and downgrade on a ramp of 30 percent slope. After negotiating the ramps, the unit shall be operated at rated capacity for one hour. Inability of the dispensing unit to withstand travel on the slopes, damage to the dispensing unit or components, or failure of the dispensing unit to operate as specified shall constitute failure of this test.

4.6.2.17 Emergency stop. The carrier-mounted dispensing unit shall be subjected to a series of emergency stops while fully loaded. The carrier shall be stopped while moving forward at 10 mph five consecutive times. This procedure shall be repeated in reverse at 10 mph. The carrier shall then be subjected to five consecutive emergency stops at each of the following speeds: 20, 30, and 40 mph forward, and finally 10 mph reverse. The

Source: https://assist.dla.mil -- Downloaded: 202610-21T20:47Z
Check the source to verify that this is the current version before use.

mounting and tiedown systems shall be inspected throughout the test. The unit shall be operated for one hour on completing the emergency stop tests. Breakage, permanent deformation, or damage to the unit, or failure of the unit to operate as specified, shall constitute failure of this test.

4.6.2.18 Amphibious. The carrier-mounted dispensing unit containing full fuel load shall be operated in the amphibious mode. Normal maneuvers such as entering and leaving the water and making turns in water at normal speed shall be conducted. Inability of the M548 carrier to operate and maneuver in water or damage to the dispensing unit shall constitute failure of this test.

4.6.2.19 Electromagnetic interference. The pumping assembly shall be tested in accordance with CE03, 150 KHz electric field as shown in Table I of MIL-STD-461. The contractor shall furnish the contracting officer a test plan and test report as specified in MIL-STD-461. Disapproval of the test plan, test report or nonconformance to 3.12 shall constitute failure of this test.

4.7 Inspection comparison. The Government may select dispensing units at any time during the contract production period and subject these units to the examination specified in 4.6.1 and the tests marked "X" in Column 2 of Table I to determine conformance to the requirements of this specification. The inspection will be performed by the Government, at a site selected by the Government, on units selected at random from those which have been accepted by the Government and will not include the previously inspected preproduction model and initial production dispensing units. In addition to any test specified as part of the inspection comparison, the Government reserves the right to conduct any and all other tests contained in this specification as part of the inspection comparison and failure of such additional tests shall have the same effect as failure of those tests specified as inspection comparison.

4.7.1 Inspection failure. Failure of an inspection comparison dispensing unit to meet any requirements specified herein during and as a result of the examination and tests specified in 4.7 shall be cause for rejection of the inspection comparison dispensing unit(s) and shall be cause for refusal by the Government to continue acceptance of production dispensing units until evidence has been provided by the contractor that corrective action has been taken to eliminate the deficiencies. Correction of such deficiencies shall be accomplished by the contractor at no cost to the Government on dispensing units previously accepted and produced under the contract. Any deficiencies found as a result of the inspection comparison will be considered prima facie evidence that all dispensing units accepted prior to

Source: https://assist.dla.mil -- Downloaded: 20260-21T20:47Z
Check the source to verify that this is the current version before use.

. Enter in block 6 any remarks not related to a specific paragraph of the document. If block 7 is filled out, an problems

the completion of inspection comparison are similarly deficient unless evidence to the contrary is furnished by the contractor and such evidence is acceptable to the contracting officer.

4.8 Inspection of packaging.

4.8.1 Preproduction pack inspection.

4.8.1.1 Examination. Examine the preproduction pack for the defects specified in 4.8.2.4. Presence of one or more defects shall be cause for rejection.

4.8.2 Quality conformance inspection of pack.

4.8.2.1 Inspection stages. Inspection shall be in three stages as follows:

(a) The first stage shall include inspection of procedures, methods, interior packaging materials, and packaging marking.
(b) The second stage shall include inspection of arrangement, and the anchoring and blocking of the components in the shipping containers.
(c) The third stage shall include inspection of closure and strapping and marking of completed shipping containers as prepared for shipment.

4.8.2.2 Unit of product. For the purpose of inspection, dispensing unit components, prepared for any applicable inspection stage shall be considered a unit of product.

4.8.2.3 Sampling. Sampling for examination shall be in accordance with MIL-STD-105.

4.8.2.4 Examination. Samples selected in accordance with 4.8.2.3 shall be examined for the following defects. AQL shall be 2.5 percent defective.

138. Materials, methods, or containers not as specified. Each incorrect material, method, or container shall constitute one defect.
139. Unpainted and unprotected surfaces not coated with preservative as specified for Level A.
140. Interior surfaces of the pump not coated with preservative as specified for Level A.
141. Excess preservative not drained from pump for Level A.

Source: https://assist.dla.mil -- Downloaded: 2026-10-21T20:47Z
Check the source to verify that this is the current version before use.

142. Openings into pump not sealed with tape as specified for Level A.
143. Electric motor not preserved in accordance with the referenced documents for Level A.
144. Filter-separator and components not preserved in accordance with the referenced document for Level A.
145. Fabric drums and components not preserved in accordance with the referenced document for Level A.
146. Metal tanks and components not preserved in accordance with the referenced document for Level A.
147. Hose not coiled and secured as specified for Level A.
148. Tiedowns not coiled as specified for Level A.
149. Fiber boxes not closed Method V as specified for Level A.
150. Fire extinguisher not preserved as specified for Level A.
151. Consolidation not as specified for Level A.
152. Plywood box not of minimum cube for Level A.
153. Strapping not as specified for Level A.
154. Marking illegible, incomplete, incorrect, or missing for Level A or Commercial.

5. PACKAGING

5.1 Preproduction pack. The contractor shall furnish a preproduction pack for examination within the time frame specified (see 6.2) to prove prior to starting production packaging that the applied preservation, packing, and marking comply with the packaging requirements of this specification. Examination shall be as specified in Section 4 and shall be subject to surveillance and approval by the Government (see 6.9). The preproduction pack may be accomplished utilizing either the preproduction model of the dispensing unit or a production dispensing unit. If the preproduction dispensing unit is utilized, any preservation and packing shall be removed by the contractor at no expense to the Government, when requested by the Government to facilitate comparison between the preproduction dispensing unit and production dispensing units.

5.2 Preservation. Preservation shall be Level A or Commercial as specified (see 6.2).

5.2.1 Level A.

5.2.1.1 Unprotected metal surfaces. Unpainted and unprotected exterior metal surfaces of the pump unit and other components of the dispensing unit requiring the application of a contact preservative in accordance with MIL-P-116 shall be coated with Type P-1 preservative. The preservative shall conform to the applicable specification listed in and shall be applied in accordance with MIL-P-116.

Source: https://assist.dla.mil -- Downloaded: 202610-21T20:47Z
Check the source to verify that this is the current version before use.

5.2.1.2 Pump unit. Interior surfaces of the pump shall be coated with preservative lubricating oil conforming to MIL-L-21260, Type I, Grade 10, applied by introducing the preservative into the pump intake while the pump is being actuated. A sufficient amount of preservative shall be applied until the preservative is being discharged at the pump discharge opening. Excess preservative shall be allowed to drain. After the drainage ceases, all openings into the pump shall be sealed with tape conforming to PPP-T-60, Type IV.

5.2.1.2.1 Electric motor. The electric motor shall be preserved in accordance with MIL-E-16298, Level A, using the alternate method as specified for assembled machines.

5.2.1.3 Filter-separator and components. The filter-separator and components shall be preserved and consolidated in accordance with MIL-F-52667, Level A.

5.2.1.4 Fabric drums and components. The fabric drums and components shall be preserved in accordance with MIL-D-23119, Level A.

5.2.1.5 Metal tanks and components. The metal tanks and components shall be preserved and consolidated in accordance with MIL-T-22238, Level A.

5.2.1.6 Hoses. Each hose shall be coiled to the minimum diameter that will not cause damage to the hose. The coils shall be secured with cotton tape or twine.

5.2.1.7 Tiedowns. Each web tiedown shall be coiled to the minimum diameter coil and the coil secured. The coiled tiedowns for each unit shall then be preserved in close-fitting box conforming to PPP-B-636, W5c. Box closure shall be in accordance with the appendix to the box specification, Method V.

5.2.1.8 Fire extinguisher. The fire extinguisher shall be preserved in a close-fitting box conforming to PPP-B-636, W6c. Box closure shall be in accordance with the appendix to the box specification, Method V.

5.2.1.9 Repair parts. The preservative application criteria and applicable method(s) of preservation of MIL-P-116 shall be used to preserve the repair parts.

5.2.1.10 Maintenance tools. Maintenance tools shall be preserved in accordance with PPP-P-40, Level A.

Source: https://assist.dla.mil -- Downloaded: 2026-10-21T20:47Z
Check the source to verify that this is the current version before use.

5.2.1.11 Technical publications. Technical publications when applicable for each dispensing unit shall be preserved together in accordance with MIL-P-116, Method IC-1.

5.2.1.12 Consolidation. The repair parts, maintenance tools, and technical publications for each dispensing unit, including any other overpack kit items, requiring the protection of a container, shall be consolidated together in a box conforming to PPP-B-636, W5c, W6c, or V3c, as applicable, Style RSC. Box closure shall be in accordance with the appendix to the box specification, Method V.

5.2.2 Commercial. Each complete dispensing unit including the repair parts, tools, and technical publications shall be preserved in accordance with MIL-STD-1188.

5.3 Packing. Packing shall be Level A or Commercial as specified (see 6.2).

5.3.1 Level A.

5.3.1.1 Pump unit and other components. The pump unit, coiled hose, tiedowns, and the fire extinguisher, preserved as specified in 5.2, and the consolidated overpack kit items (see 5.2.1.12), shall be packed together in a box conforming to PPP-B-601, Overseas Type, Style I or J. The box shall be of minimum cube to contain the items. Arrangement shall be such as to afford maximum compactness, good balance, and low center of gravity in so far as possible. Blocking, bracing, anchoring, and cushioning shall be applied in accordance with MIL-STD-1186. Strapping shall conform to QQ-S-781, Class 1, Type I or IV, size as applicable. Unless otherwise specified (see 6.2), strapping shall be Finish B. When specified (see 6.2), strapping shall be Finish A.

5.3.1.2 Filter-separator unit and components. The filter-separator unit and components, preserved as specified in 5.2, shall be packed in accordance with MIL-F-52667, Level A.

5.3.1.3 Fabric drums and components. The fabric drums and components, preserved as specified in 5.2, shall be packed in accordance with MIL-D-23119, Level A.

5.3.1.4 Metal tanks and components. The metal tanks and components, preserved as specified in 5.2, shall be packed in accordance with MIL-T-22238, Level A.

Source: https://assist.dla.mil -- Downloaded: 202640-21T20:47Z
Check the source to verify that this is the currentversion before use.

5.3.2 Commercial. The components of the dispensing unit, preserved as specified in 5.2, shall be packed in accordance with MIL-STD-1188.

5.4 Marking.

5.4.1 Military packaging. Marking shall be in accordance with MIL-STD-129.

5.4.2 Commercial packaging. Marking shall be in accordance with MIL-STD-1188.

6. NOTES

6.1 Intended use. The dispensing units when installed in the M548 tracked cargo carrier will provide a tactical mobile fuel dispensing unit for other tracked carriers, combat vehicles, and support vehicles.

6.2 Ordering data. Procurement documents should specify the following:

(a) Title, number, and date of this specification.
(b) Type of dispensing unit required (see 1.2).
(c) Time frame required for submission of preproduction model and number of preproduction models required (see 3.2).
(d) When the Government will conduct any or all of the preproduction model examination and tests. When the Government will conduct some but not all of the preproduction examination and tests, the contracting officer should specify which examination and tests will be conducted by the Government and which examination and tests shall be conducted by the contractor (see 3.2).
(e) When initial production inspection is required and number of dispensing units to be furnished, when applicable (see 3.3).
(f) When Government-furnished property is required (see 3.14 and 6.6).
(g) Time frame required for submission of preproduction pack (see 5.1).
(h) Degree of preservation and degree of packing required (see 5.2 and 5.3).
(i) When Finish A strapping is required (see 5.3.1.1).

6.3 Classification. There is no direct cross-reference relationship between the two types of dispensing units covered by this revision of the specification and the one type covered by the previous edition.

6.4 Preproduction model. Any changes or deviations of production dispensing units from the approved preproduction model during production will be subject to the approval of the contracting officer. Approval of the preproduction model will not relieve the contractor of his obligation to furnish dispensing units conforming to this specification.

Source: https://assist.dla.mil -- Downloaded: 20261O-21T20:47Z
Check the source to verify that this is the currentversion before use.

6.5 Lubricants. The contracting officer should furnish a list of military lubricants applicable to the pumping assembly covered by this specification as contained in the Federal Supply Catalog, Department of Defense Section, Identification List C9100-IL, for FSC Group 91.

6.6 Government-furnished property. When specified, the contracting officer should arrange to furnish the property specified in 3.14.

6.7 Supplementary Quality Assurance Provisions (SQAP). The contracting officer should require the contractor to maintain records of all SQAP inspections. A suggested paragraph is as follows:

> "The contractor shall maintain complete records of all examinations and tests performed to verify the requirements of classified SQAP characteristics. The records shall include as a minimum, lot size, sample size, drawing requirement, actual measurement, number and type of deficiencies found, qualtity approved, quantity rejected, corrected action taken when applicable."

6.8 Definitions.

6.8.1 Supplementary Quality Assurance Provisions (SQAP). A SQAP is a contractual requirement that supplements Section 4 of the specification. SQAP indicates the minimum requirements which must be inspected on the product drawings to verify the design objectives of the product and assure interchangeability of repair parts.

6.9 Preproduction pack. Any changes or deviations of production packs from the approved preproduction pack will be subject to the approval of the contracting officer. Approval of the preproduction pack will not relieve the contractor of his obligation to preserve, pack, and mark the tank and pump units or tank units as applicable in accordance with this specification.

6.10 Data requirements. The contracting officer should include requirements for such data as technical publications, instructional materials, illustrated parts lists, and contractor's maintenance and operation manual to be furnished with each dispensing unit.

6.11 Provisioning. The contracting officer should include provisioning requirements for repair parts and maintenance tools as necessary (including any special tools), and instructions on shipment of dispensing units, A suggested paragraph is as follows:

> "Shipment of dispensing units shall include repair parts, maintenance tools, operational instructions, and accessories, unless exceptions are provided elsewhere in the contract."

Source: https://assist.dla.mil -- Downloaded: 202610-21T20:47Z
Check the source to verify that this is the current version before use.

6.12 Recycled material. It is encouraged that recycled material be used when practical as long as it meets the requirements of the specification (see 3.4).

Custodian:
Army - ME

Preparing activity:
Army - ME

Project 4930-A195

Source: https://assist.dla.mil -- Downloaded: 20261O-21T20:47Z
Check the source to verify that this is the current version before use.

special tools are not required for maintenance, assembly, and disassembly

STANDARDIZATION DOCUMENT IMPROVEMENT PROPOSAL

OMB Approval
No. 22-R255

INSTRUCTIONS: The purpose of this form is to solicit beneficial comments which will help achieve procurement of suitable products at reasonable cost and minimum delay, or will otherwise enhance use of the document. DoD contractors, government activities, or manufacturers/vendors who are prospective suppliers of the product are invited to submit comments to the government. Fold on lines on reverse side, staple in corner, and send to preparing activity. Comments submitted on this form do not constitute or imply authorization to waive any portion of the referenced document(s) or to amend contractual requirements. Attach any pertinent data which may be of use in improving this document. If there are additional papers, attach to form and place both in an envelope addressed to preparing activity.

DOCUMENT IDENTIFIER AND TITLE MIL-D-43149B(ME) Drum and Pump Units, Liquid Dispensing, Tracked Carrier Mounting

NAME OF ORGANIZATION AND ADDRESS

CONTRACT NUMBER

MATERIAL PROCURED UNDER A

☐ DIRECT GOVERNMENT CONTRACT ☐ SUBCONTRACT

1. HAS ANY PART OF THE DOCUMENT CREATED PROBLEMS OR REQUIRED INTERPRETATION IN PROCUREMENT USE?

A. GIVE PARAGRAPH NUMBER AND WORDING.

B. RECOMMENDATIONS FOR CORRECTING THE DEFICIENCIES

2. COMMENTS ON ANY DOCUMENT REQUIREMENT CONSIDERED TOO RIGID

3. IS THE DOCUMENT RESTRICTIVE?

☐ YES ☐ NO *(If "Yes", in what way?)*

4. REMARKS

SUBMITTED BY *(Printed or typed name and address - Optional)*

TELEPHONE NO.

DATE

DD FORM 1 JAN 72 1426

REPLACES EDITION OF 1 JAN 66 WHICH MAY BE USED

Source: https://assist.dla.mil -- Downloaded: 202610-21T20:47Z
Check the source to verify that this is the current version before use.

FOLD

POSTAGE AND FEES PAID
DEPARTMENT OF THE ARMY
DOD – 314



OFFICIAL BUSINESS
PENALTY FOR PRIVATE USE $300

Commander
US Army Mobility Equipment Research
and Development Command
ATTN: DRDME-DS
Ft. Belvoir, VA 22060

FOLD

Source: https://assist.dla.mil -- Downloaded: 2026-10-21T20:47Z
Check the source to verify that this is the current version before use.