MIL-P-43155F(GL)
30 March 1984
SUPERSEDING
MIL-P-43155E(GL)
13 May 1977

MILITARY SPECIFICATION

PRINTING PLANT, SPECIAL WARFARE,

TRANSPORTABLE, (LIGHTWEIGHT) MoDEL 800

This specification is approved for use by the Natick Research and Development Center, Department of the Army and is available for use by all Departments and Agencies of the Department of Defense,

1* SCOPE

1.1 Scope. This document covers a transportable printing plant (see 6.1).

2. APPLICABLE DOCUMENTS

2.1 Government documents. Unless otherwise specified, the following documents of the issue in effect on date of invitation for bids or request for proposal, form a part of this document to the extent specified herein.

SPECIFICATIONS

FEDERAL

AA-C-291	Chair, Folding (Steel)
AA-S-700	Stools, Filing and General Purpose, Steel
GG-M-95	Magnifier and Reducing Glass
GG-P-725	Psychrometers
QQ-A-200/9	Aluminum Alloy Bar, Rod, Shapes, Tube, and Wire, Extruded, 6063
QQ-A-225/8	Aluminum Alloy 6061, Bar, Rod, Wire and Special Shapes; Rolled, Drawn or Cold Finished
QQ-A-250/11	Aluminum Alloy 6061, Plate and Sheet

Beneficial comments (recommendations, additions, deletions) and any pertinent data which may be of use in improving this document should be addressed to: U.S. Army Natick Research and Development Center, Natick, MA 01760 by using the self-addressed Standardization Document Improvement Proposal (DD Form 1426) appearing at the end of this document or by letter.

FSC 3610

Source: https://assist.dla.mil -- Downloaded: 2026-10-21T20:49Z
Check the source to verify that this is the current version before use.

TT-C-490	Cleaning Methods and Pretreatment of Ferrous Surfaces for Organic Coatings
TT-E-529	Enamel, Alkyd, Semigloss

MILITARY

MIL-P-116	Preservation Methods of
MIL-P-514	Plates, Identification, Instruction and Marking, Blank
MIL-W-530	Webbing, Textile, Cotton, General Purpose, Natural or in Colors
MIL-C-3432	Cables, (Power and Special Purpose) and Wire, Electrical (300 and 600 Volts)
MIL-C-5541	Chemical Conversion Coatings or Aluminum and Aluminum Alloys
MIL-G-3859	Grease Gun, Hand Operated, Lever, Push and Screw Type
MIL-C-10578	Corrosion Removing and Metal Conditioning Compound (Phosphoric Acid Base)
MIL-C-40060/l–	Cabinet, Storage, Steel: Map Reproduction, Double Door

STANDARDS

MILITARY

MIL-STD-105	-	Sampling Procedures and Tables for Inspection by Attributes
MIL-STD-129	-	Marking for Shipment and Storage
MIL-STD-1474	-	Noise Limits for Army Material

DRAWINGS

U.S. ARMY NATICK RESEARCH AND DEVELOPMENT CENTER

6-1-5889	-	Two Color Test Target
6-1-7500	-	Printing Plant, Special Warefare, Transportable, (Lightweight) Model 800; Drawing List
6-1-7501	-	Partition Assembly Darkroom
6-1-7531	-	Press Shelter Assembly

(Copies of documents required by manufacturers in connection with specific acquisition functions should be obtained from the contracting activity or as directed by the contracting officer.)

Source: https://assist.dla.mil -- Downloaded: 202610-21T20:49Z
Check the source to verify that this is the current version before use.

OTHER GOVERNMENT DOCUMENTS

Laws and Regulations

49 CFR - Motor Carrier Safety Regulations

(The Code of Federal Regulations (CFR) and the Federal Register (FR) are for sale on a subscription basis by the Superintendent of Documents, U.S. Government Printing Office, Washington, DC 20402. When indicated, reprints of certain regulations may be obtained from the Federal agency responsible for issuance thereof.)

2.2 Other publications. Unless otherwise specified, the following documents of the issue on date of invitation for bids or request for proposal, form a part of this document to the extent specified herein.

AMERICAN SOCIETY FOR TESTING AND MATERIALS (ASTM)

A 108 - Steel, Bars, Carbon, Cold-Finished
A 109 - Steel, Carbon, Cold-Rolled Strip
A 167 - Stainless and Heat-Resisting Chromium-Nickel Steel, Plate, Sheet, and Strip
A 569 - Steel, Carbon, Hot-Rolled Sheet and Strip, Commercial Quality
D 3951 - Standard Practice for Commercial Packaging

(Application for copies should be addressed to the American Society for Testing and Materials, 1916 Race Street, Philadelphia, PA 19103.)

AMERICAN WELDING SOCIETY

Standard Qualification Procedure for the American Welding Society

(Application for copies should be addressed to the American Welding Society, 2501 Northwest 7th Street, Miami, FL 33125.)

AMERICAN SOCIETY OF MECHANICAL ENGINEERS

Welding Qualifications of the American Society of Mechanical Engineers

(Application for copies should be addressed to the American Society of Mechanical Engineers, 345 East 47th Street, New York, NY 10017.)

Source: https://assist.dla.mil -- Downloaded: 2026-10-21T20:49Z
Check the source to verify that this is the current version before use.

NATIONAL FIRE PROTECTION ASSOCIATION (NFPA)

NFPA No. 70 - National Electrical Code

(Application for copies should be addressed to the National Fire Protection Association, 60 Batterymarch Park, Quincy, MA 02169.)

ASSOCIATION OF AMERICAN RAILROADS

Rules Governing Commodities in Closed or Open Top Cars

(Application for copies should be addressed to the Association of American Railroads, 59 East Van Buren Street, Chicago, IL 60605,)

(Technical society and technical association documents are generally available for reference from libraries. They are also distributed among technical groups and using Federal agencies.)

2.3 Order of precedence. In the event of a conflict between the text of this document and the references cited herein, the text of this document shall take precedence.

3. REQUIREMENTS

3.1 Alternate components. Components offered as equivalent to components specified herein and on the referenced drawings as a specific manufacturer's equal shall be functionally equal with the manufacturer's part number identified. The incorporation of such a component in the design of the specified end product shall not require modification to any components, unless such modification is specifically approved by the contracting officer. Prior to commencing production, the contractor shall submit for the contracting officer's approval, a list identifying each alternate component, together with proof that each listed component complies with requirements specified herein. The contracting officer, at his option, may require a physical sample of the proposed substitution. Approval of the submitted listing, together with necessary supporting data does not relieve the contractor of the responsibility that these components perform in accordance with specified requirements when incorporated into' the end product.

3.2 Materials and components. The materials and components shall be as specified herein and on the applicable drawings. Materials and components not definitely specified shall be of the quality normally used by the manufacture provided the completed item complies with all the provisions of this document.

3.2.1 Aluminum. Aluminum alloy 6061-T6 shall conform to QQ-A-225/8 or QQ-A-250/11, as applicable. Aluminum alloy 6063-T5 shall conform to QQ-A-200/9.

3.2.2 Steel, carbon. Carbon steel bar shall conform to ASTM 108. Carbon steel or strip shall conform to ASTM A 109 or A 569.

Source: https://assist.dla.mil -- Downloaded: 202610-21T20:49Z
Check the source to verify that this is the current version before use.

3.2.3 Steel, stainless. Stainless steel sheets shall conform to ASTM A 167.

3.3 Design and construction. The design and construction for the printing plant shall be as specified herein, and as shown on the drawings listed on drawing 6-1-7500. Each shelter shall be equipped by the contractor with heating and cooling air conditioner system, forced feed water system and electric power distribution system for 120/220 volts, alternating current, single phase, 4 wire power source. All wiring shall be in accordance with the provisions of NFPA No. 70. The noise levels within the printing plant shall meet the limits specified in MIL-STD-1474 and where practical, shall not exceed 85 decibels A-weighted at personnel positions (see 4,3.6). If the noise level exceeds 85 decibels A and reducing the noise level is not practical, noise caution signs per MIL-STD-1474 shall be posted on equipment and at work stations that exceed 85 decibels A. The duplicating machine shall be modified to include the color press and shall produce network as Shown on drawing 6-1-5889 which is in register.

3,4 Performance.

3.4.1 Sight levels. The printing plant lateral and longitudinal sight levels mounted on the exterior of each shelter, shall be positioned and set parallel to the shelter floor surface in accordance with drawings 6-1-7501 and 7531. When tested as specified in 4.3.1, the position of the vial bubble of the test level shall correspond with the lateral and longitudinal sight levels.

3.4.2 Water tightness. The printing plant shall show no evidence of leakage when tested as specified in 4.3.2.

3.4.3 Printing plant operation. All electrically operated equipment, including switches, lights, telephone, binding posts, heating and air conditioning systems, and water supply and drainage system shall function as specified when tested for performance and roadability as specified in 4.3.3 and 4.3.4.

3.5 Finish. Finish requirements shall conform to the following except as otherwise specified on the drawings.

3.5.1 Shelters, interior. All surfaces of the interior of each shelter shall be cleaned and rehabilitated, when necessary to restore the original color and finish.

3.5.1.1 Contractor installed components. All surfaces of contractor installed components shall be prepared and primed (see 3.5.1.1,1 and 3.5,1.1.2) and enameled (see 3.5.1.1.3) on all surfaces visible after installation and during use, with exceptions as follows:

a. Components identified by brand name, or equal, shall not be further finished providing such components have received the manufacturer's final applied enamel or plated finish,

Source: https://assist.dla.mil -- Downloaded: 202640-21T20:49Z
Check the source to verify that this is the current version before use.

b. Surfaces of previously enameled electric lighting fixtures, and corrosion resisting steel shall not be primed or enameled.
c. Surfaces adversely affected by paint films shall not be primed or enameled.
d. Exterior surfaces of electrical circuit components shall be enameled to match the interior green enamel.
e. The fire extinguisher and first aid kit shall not be further primed or enameled to obscure the characteristic color associated with the items.

3,5.1.1.1 Surface preparation. All metal surfaces requiring paint shall be cleaned using compound, MIL-C-10578 (type i or II) or MIL-C-5541, class la for aluminum and TT-A-490, Method III for steel.

3.5. 1.1.2 Priming. After surface preparation (see 3.5.1.1,1), a primer designed for metal surfaces shall be applied to all metal surfaces prior to enameling.

3.5.1.1.3 Enameling, All metal and wood surfaces shall be given two coats of enamel in accordance with TT-E-519. The color shall match the-interior color of the Government furnished shelter except as noted on drawings. The first coat of enamel shall be thoroughly dry prior to application of the second coat. The finished enameled surfaces shall be uniformly coated, smooth, free from sags, excess buildup, orange peel, runs, and teardrops.

3.5.2 Shelters, exterior. Parts and equipment attached to exterior surfaces shall be cleaned, primed, and enameled in accordance with the manufacturer's regular commercial practice. The final applied finish shall match the color and gloss of the original finish of the Government furnished shelter. Exterior shelter surfaces shall be rehabilitated, when necessary, to restore the original color and finish to exterior surfaces which become scratched or abraded during progress of the work required by this document.

3,6 Marking. In addition to existing markings, each completed shelter shall be marked for identification in accordance with requirements herein specified, and as shown on applicable drawings.

3,6.1 Shelter, exterior.

3.6.1.1 End item identification plates. Identification plates, conforming to type I, style 3 of MIL-P-514, shall be attached to the upper left hand corner of the exterior door wall of each printing plant shelter. The required information shall be added in the spaces provided. Included as information, shall be the National Stock Number (NSN) and nomenclature of the 2-shelter printing plant, and the NSN and nomenclature of the shelters to which the plates are attached. Plate size may be expanded, if necessary, to receive the required information.

Source: https://assist.dla.mil -- Downloaded: 202610-21T20:49Z
Check the source to verify that this is the current version before use.

3.6.1.2 Gross weight. The gross weight, in pounds, of each completed shelter shall be noted on each side of the shelter by means of l-inch high, white painted numerals. Location shall be 6 to 8 inches from the top and 15 to 17 inches from the forward edge of each side of the shelter. The legend "GROSS WEIGHT LBS." shall be similarly painted in l-inch characters, adjacent to the weight marking.

3.6.1.3 Blackout buzzer. The blackout buzzer pushbutton adjacent to the entrance door shall be identified by means of an aluminum plate permanently attached directly above the blackout buzzer pushbutton. The plate size shall be as shown on the applicable drawing. The notation "BLACKOUT WARNING" shall be engraved or indented and the characters filled with red enamel.

3.6.1.4 Center of balance and sling points, Each exterior wall of the shelters shall have a white painted l-inch wide vertical line 3 inches long, located at the center of balance. At the door end, the line shall commence 14 inches above the skid bottom. The line shall commence 2 feet above the skid bottom on the remaining three sides. The legend "CENTER OF BALANCE, LOADED" shall be similarly painted immediately above the vertical line in l-inch letters. When tested as specified in 4.3.5, the actual balance point and the painted lines shall coincide.

3.6.1.5 Forklift warning. Forklift warning "DO NOT FORKLIFT", shall be indicated on all four sides of the shelter in the center near the base, using 2-inch white painted letters.

3.6.2 Circuit breakers, electric. Each circuit breaker within the load center assembly panel shall be identified by means of a plastic or metal plate permanently lettered to identify the circuit serviced. The lettered plate shall be mechanically secured within the circuit breaker panel box in a location clearly identifying each circuit breaker.

3.7 Operating supplies. Operating supplies shall be furnished by the contractor, when specified (see 6.2).

3.8 Government furnished property (GFP) and contractor furnished property. The GFP indicated in table I will be furnished to the contractor by the Government (see 6.2), and shall be a part of the printing plant. The contractor furnished property shall be in accordance with table II.

Source: https://assist.dla.mil -- Downloaded: 202610-21T20:49Z
Check the source to verify that this is the current version before use.

TABLE 1. Government furnished property

Item No.	Quantity	Nomenclature
1	2	Shelter, Electrical Equipment, S-280, B/G, MIL-S-55286.
2	2	Extinguisher, Fire, Vaporizing-Liquid, CF_3 BR, 2-3/4 pound, With Bracket, MIL-E-52031.
3	4	Air Conditioner, type II, size A, class 1, MIL-A-52767.
4	2	First Aid Kit, General Purpose NSN 6545-00-922-1200

TABLE II. Contractor furnished property

Item No.	Quantity	Nomenclature
1	2	Cable, power, assembly,portable cable, 600 volts, 3 copper conductors, w/ground wire (green) tinned, No. 6 AWG, Standard, 133 strands No. 27AWG, rubber insulated, covering in sequence from conductors, cotton and polychloroprene, MIL-C-3432
2	5	Cabinet, storage, metal, gray, 2 doors, 12 inch depth, 18 inch high, 30 inch width, 1 shelf, MIL-C-40060/1
3	1	Camera, still picture, self processing, 3/4 by 4-1/4 inches print size, 8 exposure film pack capacity, F 8.8 114 millimeter lens, electric eye automatic exposure with range view finder, Polaroid Model EE-100
4	1	Camera process vertical, 17-3/4 by 22-3/4 inches copying area with vacuum back, 19 by 26 inches copyboard, two lens (21 and 15 centimeter lens), 4 each 500 watt halogen lamps, 115V, 60 Hertz, AGFA-GEVAERT, Repromaster Mark 3 with vacuum pump and grid chart Graphic Systems Division
5	1	Chair, folding, front to back folding, metal seat back, gray, AA-C-291, type I, class 1 style 4
6	1	Cutter, paper, guillotine, electric motor driven, fully automatic 18-1/2 inches cutting width, floor mounted, 1 HP, 110 volts, 50 Hertz Michael Business Machine Corp., FSCM CODE (28098) Triumph Model
7	1	Dispenser, paper towel, for single fold towels, commercial

Source: https://assist.dla.mil -- Downloaded: 202610-21T20:49Z
Check the source to verify that this is the current version before use.

TABLE II. Contractor furnished property (cent'd)

Item No.	Quantity	Nomenclature
8	1	Drafting, instrument set, enclined case (Supply catalogue SC 6675-97-CL-E07)
9	1	Dryer, film, 14 inches maximum film width, 26 inches wide by 14 inches depth by 8 inches high, Decco Inc., FSCM CODE (07183) Model No. 1418
10	1	Duplicating machine, offset process, 10-1/2 inches by 16-1/2 inches image area, equipped with safeguard features, automatic vacuum feeder, precision register conveyor board, quick change components, chrome plated cylinder and single lever control, receding stacker, 115 volts, 60 Hertz, Addressograph - Multigraph Model FSCM CODE (00494) Model 1250 LNW
11	1	Filter, light photographic lens, yellow, medium, 0.1 millimeters thick, Wratten, FSCM CODE (19139), Model No. 81494061
12	1	Filter, light photographic lens, green, 0.01 millimeters thick, Wratten, FSCM CODE (19139), Model No. 581494442
13	1	Filter, light photographic lens, blue, 0.1 millimeters thick, Wratten, FSCM CODE (19139), Model No. 471494368
14	1	Filter, light photographic lens, red 0.1 millimeters thick,Wratten, FSCM CODE (19139), Model No. 251494178
15	2	Funnel, steel, rigid spout, 1 pint capacity, Vollrath Co., FSCM CODE (63277), Model No. 8476
16	1	Gage, brass, 12 inches length, graduations in points and inches, Polychrome Corp., Model No. 12
17	1	Hose, nonmetallic, 1 inch inside diameter, 250 pounds per square inch maximum pressure, inner tube material synthetic rubber, FSCM CODE (89470), Part No. H39-1.
18	1	Kit, rifle, FSCM CODE (19207) Part No. 11630529
19	1	Kit, photoscreen instant, for EE100 reporter camera, kit #4 w/65, 85 and 100 line screen, Fototype Inc., Chicago, IL

Source: https://assist.dla.mil -- Downloaded: 202610-21T20:49Z
Check the source to verify that this is the current version before use.

TABLE 11. Contractor furnished property (cont'd)

Item No.	Quantity	Nomenclature
20	2	Ladder, vehicle boarding, straight 63 inches long, aluminum side rail, 6 aluminum treads with attachment hooks, FSCM CODE (22585) Model No. MX3319G
21	1	Lamp duty control w/cabinet, housing power pack, switch and reset timer, 100 Watt, lamp Nuare Co. Inc., FSCM CODE (93791) Model CP25
22	1	Lubricating gun, hand lever operated, hand primed, 15 ounces, capacity , 5-1/2 to 7 inches long, hydraulic coupler with loader fitting, MIL-G-3859, size 1
23	1	Magnifier, single lens reading glass with 2X magnifying power, GG-M-95
24	1	Pitcher, solution, stainless, 2-quart capacity, MC Master-Carr, FSCM CODE (3A054) Model No. 4325T1
25	1	Phototypesetter, direct entry, language Model Comp/Set 3560W, with single diskette record/ playing option Model 504H and dry process option Model 20-1349-0 Addressograph Multigraph Varityper FSCM CODE (62812) Processor, Dry-X for 12 inch paper, table top mounted Varity per Addressograph Multigraph, FSCM CODE (62812) Model 712
26		Plunger can and holder, Addressograph Multigraph International Model No. A-120-6400-AS
27		Press color, with cylinder and roller components for Addressograph-Multigraph, Model 1250N Duplicating Machine, capable of simultaneous 2 color run, Townsend Industries, FSCM CODE (16159), Model No. T51LW
28		Processor, diffusion transfer, 14 inch capacity, stainless steel casing, Nuarc FSCM CODE (93791) Model No. P1400
29		Psychrometer, dry and wet bulb readings on metal plate, GG-P-725
30		Punch and repeat machine, with 12 brass register pins, Bychrome Inc.
31		Rack, photo tray, w/metal rack, 3 wire trays, plastic coated, 11 inches by 14 inches, Richards Co., FSCM CODE (10068) Model No. 1400

Source: https://assist.dla.mil -- Downloaded: 202610-21T20:49Z
Check the source to verify that this is the current version before use.

TABLE II. Contractor furnished property cont'd)

Item No.	Quantity	Nomenclature
32	1	Ruler steel, printer's 24 inch, Polychrone Corp., FSCM CODE (605), Model No. 605
33	2	Safelight, darkroom, fluorescent, 20 Watts, 24 inches long, photo red safety sleeve ARM-A-SAFELITE Corp., Model No. F-20-T12, with light fixture Lithonia (FSCM CODE 16543), P/N 5120-TS-120
34	1	Shears, straight trimmers, pointed blades, 14 inches long, commercial
35	4	Sling assembly, vehicle lifting, 15,000 pound capacity, 4 slings, 0.375 inches diameter wire rope, FSCM CODE 80063, Model No. SCD36423
36	2	Spatula, laboratory, steel blades, 6 inches long, 1 inch wide, wood handle, commercial
37	3	Stool, revolving, metal legs and wood seat, with seat raising mechanism, 5 inches raising adjustment, 30 inches distances from seat to floor at lowest adjustment, with footrest AA-S-700, type II, size 1
38	2	Table, light, table mounted, Nuarc FSCM CODE (93791), Model No. VLT 18T 18 by 20 inches glass area (FSCM CODE 93791)
39	2	T-Square, steel with cast aluminum head, 24 inches long, Arthur-Brown and Brothers, Inc., Catalogue No. 140871
40	2	Thermometer, standard bath thermometer temperature range 30° to 140°F, glass stem liquid container, commercial
41	1 set	Trays, photo, 11 by 14 inches with rack, Richards Model No. 1400
42	1	Vacuum frame, exposure, ultra violet, 21 by 16 inches maximum area, 8 lamps with exposure timer, vacuum pump 115 volts, 60 Hertz, Ionics Control Inc. FSCM CODE (6K938), Model No. BVL-1617
43	1	Varigraph production outfit with composing table complete, Varigraph Co., FSCM CODE (94747)
44	1	Viewing light, two way (ortho-safe/white), 18 by 20 inches size, wall mounted Nuarc, BCM Code (93791), Model No. DLV20 Modified

Source: https://assist.dla.mil -- Downloaded: 202610-21T20:49Z
Check the source to verify that this is the currentversion before use.

TABLE 11. Contractor furnished property (cent'd)

Item No.	Quantity	Nomenclature
45	1	Voltage regulator, lKVA capacity, rack mounted, 115 volts, General Radio, FSCM CODE (24655), Model No. 1591-9712
46	As required	Webbing, cotton, textile, type 111, class 4, 1 inch wide, olive drab 7 MIL-W-530

3.9 Workmanship. The finish shall be free of blisters, peel, chipped areas or areas of no film. The finish shall be free from smudges, poor touch up, scale, scratches, stain, overspray, sag, imprint or embedded foreign matter. Threaded fasteners shall not be broken, stripped or loose. Holes for rivets shall be accurately punched or drilled and any burrs that would prevent proper seating of the rivet shall be removed. Rivets shall completely fill the holes, with full size heads neatly finished and in full contact with the surface of the member and shall not be loose.

3.9.1 Welders. Unless otherwise specified (see 6.2), before assigning any welder to work, contractor shall provide the Government inspection service with the names of the welders to be employed in the work, together with certification that each of the welders has passed a qualification test as prescribed by either of the following listed codes for the type of welding operation to be performed, and that such qualification is effective as defined by that particular code as follows:

(a) Standard Qualification Procedure of the American Welding Society.

(b) Welding Qualification of the American Society of Mechanical Engineers.

3.9.2 Welding. The surface of parts to be welded shall be free from oxide, scale, paint, grease, and other foreign matter. Welds shall be continuous, sound, smooth, and free from porisity, cracks, incomplete fusion, and deformation of material. All scale and flux deposits (when flux is used) shall be removed from the finished welds, and rough edges and projections shall be dressed smooth.

3.9.3 Electrical wiring. Wiring shall not be cut, abraded, or have excessive insulation stripped, and shall be properly and tightly joined at terminals. Wiring shall have adequate slack to provide strain relief.

4. QUALITY ASSURANCE PROVISIONS

4.1 Responsibility for inspection. Unless otherwise specified in the contract or purchase order, the contractor is responsible for the performance of all inspection requirements as specified herein. Except as otherwise specified in the contract or purchase order, the contractor may use his own or any other facilities suitable for the performance of the inspection requirements specified herein, unless disapproved by the Government. The Government reserves the right to perform any of the inspections set forth in the document where such inspections are deemed necessary to assure supplies and services conform to prescribed requirements.

Source: https://assist.dla.mil -- Downloaded: 202610-21T20:49Z
Check the source to verify that this is the current version before use.

4.2 Quality conformance inspection. "Unless otherwise specified, sampling for inspection shall be performed in accordance with MIL-STD-105.

4.2.1 Component and material inspection. In accordance with 4.1, components and materials shall be inspected in accordance with all the requirements of referenced documents unless otherwise excluded, amended, modified, or qualified in this document or applicable purchase document.

4.2.2 Initial production item testing. The initial production item shall be tested as specified in 4.3 thru 4.3.6. Any failure of the initial product item shall be cause for rejection of the item. The testing process shall be repeated until an item successfully passes all the tests.

4.2.3 In-process inspection. Examination shall be made of the following fabrication process to establish conformance with specified requirements. Whenever nonconformance is noted, correction should be made to the applicable process and all items processed.

TABLE III. In-process examination

Requirement	Paragraph
Finish	3*5
Rivet holes are made to insure snug fit; rivet holes are drilled or peened at time of assembly; burrs at rivet holes are removed. Threaded fasteners are not broken, stripped or loose.	3.9
Surfaces of parts to be welded are free from oxide, scale, paint, grease, and other foreign matter.	3.9.2

4.2.4 End item inspection.

4.2.4.1 End item visual examination. The end item shall be examined for the defects listed in table IV. The lot size shall be expressed in units of completely assembled printing plants. The sample unit shall be one printing plant. The inspection level shall be II and the acceptable quality level (AQL), expressed in terms of defects per hundred units, shall be 2.5 for major defects and 6.5 for total (major and minor combined) defects.

TABLE IV. End item visual defects

Examine	Defect	Classification Major	Minor
Finish	Color not as specified		X
	Blistered, peeled, chipped, or area of no film		X
	Poor touch-up, orange peel, color separation, smudge, scale, scratched, stained, overspray, sag, imprint, or foreign matter imbedded		X

Source: https://assist.dla.mil -- Downloaded: 2026-10-21T20:49Z
Check the source to verify that this is the current version before use.

TABLE IV, End item visual defects (cont'd)

Examine	Defect	Classification Major	Minor
Design, construction and workmanship, general (applicable to all components and assemblies)	Any component or part missing or not specified type or size	X	
	Fractured, split, punctured, torn, dented, creased, deteriorated, or malformed	X	
	Component misplaced or not in proper alignment		X
	Component loose		X
	Sharp burr or edge or sliver		X
	Any operation omitted or not properly performed	X	
	Any functioning component that is inoperative or will not operate as intended	X	
	Any functioning component that requires abnormal force to be operated or not interchangeable		X
	Any adjustable assembly that cannot be adjusted		X
	Any assembly not properly adjusted		X
	Any component not readily accessible for servicing where required		X
Welding	Missing, incomplete, cracked, fractured, not fused	X	
	Undercut, not smooth and uniform, or scale or flux deposits not removed		X
Bolts, nuts, screws, studs and other types of threaded fasteners	Broken, stripped, fractured, or not tight		X
Rivets (when required)	Broken, not peened or insufficiently peened, or loose		X
Electrical assembly	Wiring cut, abraded, or not properly installed or joined	X	
	Adequate slack not provided for wiring to relieve strain		X

Source: https://assist.dla.mil -- Downloaded: 202610-21T20:49Z
Check the source to verify that this is the current version before use.

TABLE IV. End item visual defects (cent'd)

Examine	Defect	Classification Major	Classification Minor
Gauges, instruments, controls and thermometer	Not properly mounted or not specified type or capacity		x
	Not free of foreign matter		x
Marking	Missing, incomplete, not legible, not specified type or size, or not in proper location		x

4.2.4.2 End item dimensional examination. The end item shall be examined for conformance to the dimensions specified in this document and on the drawings. Any dimension not within the specified tolerance shall be classified as a defect. The lot size shall be expressed in unit of printing plants. The sample unit shall be one printing plant. The inspection level shall be S-2 and the AQL, expressed in terms of defects per hundred units, shall be 6.5.

4.2.4.3 End item testing. Each end item shall be tested as specified in 4.3.1, 4.3.2 and 4.3.3. Any test failure shall be cause for rejection of the end item.

4.2.5 Packaging inspection. Examination shall be made to determine that preservation, packing, and marking comply with section 5 requirements. Any deviation from specified requirements shall be cause for rejection.

4.3 Methods of inspection.

4.3.1 Sight levels. Settings of exterior lateral and longitudinal sight levels shall be checked for compliance with 3.4.1 using an ill-inch carpenter's level, with a properly set vial, as follows:

(a) The setting of the lateral exterior sight level shall be checked with the carpenter's level placed over the lateral centerline of the interior floor surface with the vial over the intersection of the lateral and longitudinal centerline.

(b) The setting of the longitudinal sight level shall be checked with the carpenter's level placed over the longitudinal centerline of the interior floor surface, with the vial of the level over the intersection of the longitudinal and lateral centerlines.

Any disagreement in the readings of the exterior lateral sight levels, exterior longitudinal sight levels and interior test levels shall constitute -failure of this test.

Source: https://assist.dla.mil -- Downloaded: 202610-21T20:49Z
Check the source to verify that this is the current version before use.

4.3.2 Rain test. The printing plant shall be exposed to simulated rainfall at the rate of 3 inches, plus or minus 1 inch per hour as measured at the surface of the equipment by a U.S. Weather Bureau type gauge. The rainfall shall be produced by means of a water spray nozzle of such design that the water is emitted in the form of droplets, The angle of rainfall shall be varied up to 45 degrees from vertical. The rainfall shall be dispersed uniformly over the test area within rainfall limits specified above. Each of the four sides including the air conditioner shall be exposed to the rainfall for not less than 15 minutes for total duration of not less than 1 hour. Each side exposure shall include exposure of the top. Any evidence of water or dampness within the shelter shall constitute failure of this test,

4.3.3 Performance test. Each completed shelter shall be connected to a suitable electric power source, the water storage system shall be filled to capacity and equipment operated as follows:

a. Vacuum Frame - Check vacuum for evenness of light distribution by means of gray scale and screens.
b. Contact Print Light - Check timer and light operation,
c. Water tank/drain system - Pump water from tank, 1 quart at a time, using electrical switch, Insure drain allows removal of water from basin without leaks.
d. Air conditioner - Operate each air conditioner, using all modes of operation cool, vent, low heat and high heat. Determine temperature change by observing thermostat 68°-70°F/45-50 percent psychrometer humidity.
e. Varigraph - Prepare test display lettering in accordance with test artwork.
f. Phototypesetter - Prepare text operating phototypesetter for 2 hours.
g. Light Tables - Turn lights on and check for illumination.
h. Viewing Light - Turn lights on and check for illumination.
i. Vertical Camera - Determine parallel alignment by using graph method. Optically check dimensional stability at 25, 50, 100, 200 and 400 percent.
j. PMT Processor - Operate using camera prepared test material.
k. Film Dryer - Process 12 wet ortho sheets.
1. Duplicator/Press w/colorhead - Produce 20 reams of printed material, at variable speeds. Run for at least 1 hour at 10,000 impressions per hour.
m. Paper Cutter - Cut 20 reams of 11 by 17 inches paper stock into 3 by 5 inches leaflets. Check for feathering and incomplete cuts.
n, Electrical system - Check on lights, switch, buttons and electrical outlets.
0. Doors/Drawers - Check on doors and drawers for smooth operation,

Any electrical or mechanical malfunction, leak in the water supply or drainage system or deviation in quality of duplicating machine output shall constitute failure of this test (see 3.4.2).

Source: https://assist.dla.mil -- Downloaded: 202610-21T20:49Z
Check the source to verify that this is the current version before use.

4.3.4 Roadability. Following successful completion of tests specified in 4.3.3, the complete printing plant, with all contents, shall be secured as specified in 5. 1.1.2.1 and mounted on Government furnished vehicle and subjected to a 100 mile road test. The vehicle shall be driven at top legal speed, or as road conditions permit, for this type equipment. Not less than 50 percent of the test course shall be unimproved roads such as earth or partially surfaced gravel, and the remainder shall be improved roads such as concrete, asphalt, or macadam. The test shall include not less than 20 quick starts and stops of the vehicle on grades of not less than 5 percent or greater than 10 percent. Fifty percent of the starts and stops shall be made on ascending grades and 50 percent on descending grades. This test need not be repeated during the life of the contract providing subsequent printing plates are identical to the units tested and accepted. At the completion of the test, the printing plant shall be reinspected in accordance with 4.2,3.1 and retested as specified in 4.3.2 and 4.3.3. Any nonconformance noted on completion of the road test shall constitute failure of the test.

4.3.5 Center of balance marking. The location of the center of balance marking shall be tested for compliance with 3.6.1.4 b placing the fully equipped shelter, with all supplies properly stored on a pipe roller. The shelter shall then be moved on the pipe roller to determine the relationship of the actual center of balance points and the center of balance markings. Two checks shall be made; one with the pipe roller parallel to the shelter skids and one 90 degrees to the skids, Failure of any actual center of balance to coincide with the applicable center of balance marking shall constitute failure of this test.

4.3.6 Noise test. The initial production unit shall be tested for conformance with the noise limits as specified in 3.3 and shall be in accordance with MIL-STD-1474.

5. PACKAGING

5.1 Preservation. Preservation shall be level A or Commercial, as specified (see 6.2).

5.1.1 Level A.

5.1.1.1 Preservation application. The contents of each shelter shall be preserved in accordance with the manufacturer's recommendations, using the preservative application criteria of MIL-P-116.

5.1.1.2 Securing of contents. The contents of each shelter shall be secured with means provided. Component parts that are free to move or rotate, and not provided with securing means, shall be secured or cushioned in such a manner as to prevent damage while in transit. Supplies, when furnished, shall be placed in appropriate drawers or cabinets. Supplies subject to damage shall be secured or cushioned in such a manner as to prevent damage while in transit. Special care shall be taken to insure that supplies unit packed in glass bottles are adequately cushioned. Supplies subject to damage due to extreme heat or cold shall be shipped separately.

Source: https://assist.dla.mil -- Downloaded: 2026-10-21T20:49Z
Check the source to verify that this is the current version before use.

5.1.1.3 Water system. All water shall be drained-or flushed from all units containing water.

5.1,1,4 Air conditioner. The refrigerant charge shall be pumped down, and the appropriate valves closed and capped.

5.1.1.5 External electrical power cable, The external electrical power cables shall be disassemblied from the shelters. Each cable shall be coiled, the coil secured, and placed within the appropriate shelter.

5.1.1.6 External drain hoses. The external drain hoses shall be disassembled from the shelters, the drain openings closed with dust caps where provided and the hoses placed within the shelters.

5.1.1,7 Door. The access door of each shelter shall be closed and secured with the padlocks provided. The padlock keys shall be placed in a cotton cloth draw-string bag, the bag securely tied, closed and secured to the door padlock loop, The bag shall be further secured to the door handle with a minimum 0.057 inch diameter annealed wire.

5.1.2 Commercial. Printing plants shall be preserved in accordance with ASTM D 3951.

5.2 Packing. Packing shall be level A.

5.2.1 Level A.

5.2.1.1 Railway shipment, Loading of the printing plant in railroad cars shall be in accordance with the rules governing the loading of commodities in closed cars or on open top cars of the Association of American Railroads.

5.2.1.2 Highway shipment, Shipment shall be in accordance with the Motor Carriers Safety Regulations of The Code of Federal Regulations 49 CFR.

5.3 Marking. In addition to any special marking required by the contract or purchase order, the printing plant shall be marked in accordance with MIL-STD-129 or ASTM D 3951 except marking shall be accomplished on plywood, lumber, or hardboard panels as specified herein for unpacked vehicles. In addition, the words "HANDLE WITH CARE" shall be marked on the panels. Two panels, marked as specified, shall be securely fastened to each shelter by wiring or bolting in such a manner as to prevent loss in transit or damage to the shelter,

5.3.1 Additional marking. Closed valves of the air conditioners shall be tagged or otherwise clearly marked with instructions for restoring to service. Warning tags shall be prominently affixed to the air conditioner controls, and shall caution against operating the unit without opening valves. Paper envelopes containing publications shall be appropriately marked.

Source: https://assist.dla.mil -- Downloaded: 202610-21T20:49Z
Check the source to verify that this is the current version before use.

5.3.2 Humping precautions. A large sign containing the words “DO NOT HUMP" shall be secured in a conspicuous place on each side of railroad cars used to ship the printing plant.

6. NOTES

6.1 Intended use. The printing plant is intended for use in the printing of leaflets in a tactical situation where early and rapid distribution is required by PSYOP units.

6.2 Ordering data. Acquisition documents should specify the following:

a. Title, number, and date of this document.
b. Source and delivery of Government furnished property as applicable (see 3.8 and 4.3.4).
c* When certificate of qualification test for welders is not required (see 3.9.1).
d. Selection of applicable level of preservation and packing (see 5.1 and 5.2).

6.3 Changes from previous issue. Asterisks are not used in this revision to identify changes with respect to the previous issue, due to the extensiveness of the changes.

Custodian:

Army - GL

Review activity:

Army - MD

Preparing activity:

Army - GL

Project No. 3610-A294

Source: https://assist.dla.mil -- Downloaded: 202610-21T20:49Z
Check the source to verify that this is the current version before use.

INSTRUCTIONS: In a continuing effort to make our standardization documents better, the DoD provides this form for use in submitting comments and suggestions for improvements. All users of military standardization documents are invited to provide suggestions. This form may be detached, folded along the lines indicated, taped along the loose edge *(DO NOT STAPLE)*, and mailed. In block 5, be as specific as possible about particular problem areas such as wording which required interpretation, was too rigid, restrictive, loose, ambiguous, or was incompatible, and give proposed wording changes which would alleviate the problems. Enter in block 6 any remarks not related to a specific paragraph of the document. If block 7 is filled out, an acknowledgement will be mailed to you within 30 days to let you know that your comments were received and are being considered.

NOTE: This form may not be used to request copies of documents, nor to request waivers, deviations, or clarification of specification requirements on current contracts. Comments submitted on this form do not constitute or imply authorization to waive any portion of the referenced document*(s)* or to amend contractual requirements.

(Fold along this line)

(Fold along this line)

DEPARTMENT OF THE ARMY
Army Natick Research and Development Center
Natick, Massachusetts 01760

NO POSTAGE NECESSARY IF MAILED IN THE UNITED STATES

OFFICIAL BUSINESS
PENALTY FOR PRIVATE USE $300
STRNC-ES

BUSINESS REPLY MAIL
FIRST CLASS PERMIT NO. 12062 WASHINGTON D. C.
POSTAGE WILL BE PAID BY THE DEPARTMENT OF THE ARMY

Commander
US Army Natick Research and Development Center
ATTN: STRNC-ES
Natick, MA 01760

Source: https://assist.dla.mil -- Downloaded: 202610-21T20:49Z
Check the source to verify that this is the current version before use.

STANDARDIZATION DOCUMENT IMPROVEMENT PROPOSAL

(See Instructions – Reverse Side)

1. DOCUMENT NUMBER	2. DOCUMENT TITLE
MIL-P-43155F(GL)	Printing Plant, Special Warfare, Transportable, (Lightweight) Model 800

3a. NAME OF SUBMITTING ORGANIZATION	4. TYPE OF ORGANIZATION *(Mark one)*
	☐ VENDOR
	☐ USER
b. ADDRESS *(Street, City, State, ZIP Code)*	☐ MANUFACTURER
	☐ OTHER *(Specify)*: _____

5. PROBLEM AREAS

a. Paragraph Number and Wording:

b. Recommended Wording:

c. Reason/Rationale for Recommendation:

6. REMARKS

7a. NAME OF SUBMITTER *(Last, First, MI)* – Optional	b. WORK TELEPHONE NUMBER *(Include Area Code)* – Optional
c. MAILING ADDRESS *(Street, City, State, ZIP Code)* – Optional	8. DATE OF SUBMISSION *(YYMMDD)*

DD FORM 82 MAR 1426 PREVIOUS EDITION IS OBSOLETE.

NATICK OP, 1 Apr 84

Source: https://assist.dla.mil -- Downloaded: 202610-21T20:49Z
Check the source to verify that this is the current version before use.