MILITARY SPECIFICATION

PLANT, ASPHALT MIXING, DRUM TYPE, ELECTRIC MOTOR DRIVEN, ROADABLE, AIR TRANSPORTABLE C-5A AIRCRAFT, 125 TONS PER HOUR CAPACITY

This specification is approved for use within the Department of the Air Force and is available for use by all Departments and Agencies of the Department of Defense.

1. SCOPE

1.1 Scope. This specification covers a complete asphalt mixing plant capable of producing various design mixes of asphaltic concrete either from virgin materials or from a mixture of virgin and recycled materials.

2. APPLICABLE DOCUMENTS.

2.1 Government documents.

2.1.1 Specifications, standards, and handbooks. The following specifications, standards, and handbooks form a part of this specification to the extent specified herein. Unless otherwise specified, the issues of these documents shall be those listed in the issue of the Department of Defense Index of Specifications and Standards (DODISS) and supplement thereto, cited in the solicitations (see 6.2).

SPECIFICATIONS

FEDERAL

VV-F-800	Fuel Oil, Diesel

MILITARY

MIL-T-5684	Turbine Fuel Aviation, Grades JP-4 and JP-5
MIL-A-8421	Air Transportability Requirements, General Specification for

Beneficial comments (recommendations, additions, deletions) and any pertinent data which may be of use in improving this document should be addressed to: WR-ALC/MMDETB, Robins AFB, GA 31098-5609 by using the Standardization Document Improvement Proposal (DD Form 1426) appearing at the end of this document or by letter.

AMSC N/A

FSC 3895

DISTRIBUTION STATEMENT A: Approved for public release; distribution is unlimited.

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T09:46Z
Check the source to verify that this is the current version before use.

STANDARDS

FEDERAL

FED-STD-595 Colors

MILITARY

MIL-STD-130 Identification Marking of US Military Property

(Unless otherwise indicated, copies of federal and military specifications, standards, and handbooks are available from the Naval Publications and Forms Center, (ATTN: NPODS), 5801 Tabor Avenue, Philadelphia, PA 19120-5099.)

2.2 Non-Government publications. The following document(s) form a part of this document to the extent specified herein. Unless otherwise specified, the issues of the documents which are DoD adopted are those listed in the issue of the DODISS cited in the solicitation. Unless otherwise specified, the issues of documents not listed in the DODISS are the issues of the documents cited in the solicitation (see 6.2).

SOCIETY OF AUTOMOTIVE ENGINEERS, INC (SAE)

SAE Handbook.

TIRE AND RIM ASSOCIATION, INC (TRA)

TRA Yearbook

(Non-Government standards and other publications are normally available from the organizations that prepare or distribute the documents. These documents also may be available in or through libraries or other informational services.)

2.3 Order of precedence. In the event of a conflict between the text of this specification and the references cited herein (except for associated detail specifications, specification sheets or MS standards), the text of this specification shall take precedence. Nothing in this specification, however, shall supersede applicable laws and regulations unless a specific exemption has been obtained.

3. REQUIREMENTS.

3.1 Preproduction. When specified (see 6.2), the supplier shall furnish a complete diesel-electric asphalt mixing plant for preproduction inspection in accordance with Sections 4 and 6.

3.2 Safety. Gears, sprockets, drives; drive, head, tail and takeup pulleys; flywheels; drive couplings; shafts; and similar exposed moving machine parts which may be contacted by attending persons and cause injury shall be guarded. All guards shall be designed to provide access to the guarded parts. Steps, ladders, grab rails, hand rails, grab irons, guardrails, walkways and platforms, when installed, shall be in accordance with SAE J185. Protective devices shall not impair the operational functions. All steps shall be located for easy access to destination. Drives located lower than 7-feet above grade shall be guarded .

3.3 Maintainability. Components of the plant shall be readily accessible for repair or replacement with minimum removal or disturbance of adjacent parts or components using general purpose tools. Operating parts, accessories and drain outlets shall be easily accessible for regular maintenance service.

Source: https://assist.dla.mil -- Downloaded: 20261O-23T09:46Z
Check the source to verify that this is the current version before use.

3.4 Painting. All components of the plant shall be treated and painted in accordance with the manufacturer's standard commercial practice, except that the finish color shall be chip number 24052 semigloss green in accordance with FED-STD-595.

3.5 Identification Marking. A corrosion resistant metal nameplate in accordance with MIL-STD-130 shall be permanently and legibly marked with the following information, and shall be attached to each asphalt plant:

a. Nomenclature.

b. Manufacturer's model number.

c. Manufacturer's serial number.

d. Manufacturer's name.

e. Contract number.

f. Date of manufacture.

g. Special characteristics, HP, RPM, etc.

h. Weight.

i. Cube and center of gravity of each component assemblage.

j. U.S.

3.6 Lubrication Plate. A lubrication plate or decal showing the following information shall be securely attached to each component of the plant assemblage requiring periodic servicing:

a. Point of application.

b. Service interval.

c. Type of lubricant.

d. Viscosity.

3.7 Description. The mixing plant shall be a drum mix type capable of being mobile by components since each component shall be on wheels or trailer mounted for road travel and shall fit on C-5A aircraft. The assembled plant and accessories shall be complete for producing a minimum of 125 tons per hour of hot mix asphaltic concrete with a 300 degree Fahrenheit mix temperature using material with an average removal of combined cold feed moisture of 7 percent, or 125 TPH at 280 degrees Fahrenheit at 8 percent combined cold feed moisture removal. The plant shall be portable component by component using pneumatic rubber tires and shall be capable of recycling asphalt.

3.8 Components. Components of the complete asphalt plant shall be, but are not limited to, the following:

a. Drum mixer unit, portable.

b. Cold feed bin, portable.

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T09:46Z
Check the source to verify that this is the current version before use.

c. Charging conveyor, portable.

d. Bitumen storage tanks, portable.

e. Heating fuel storage tank, portable.

f. Generator, portable.

g. Steel switchgear shed, portable.

h. Steel plant control house, portable.

i. Reclaimed material charging conveyor, portable.

j. Silo surge system, portable.

k. Power cables.

1. Fines feeder.

m. Hot oil heater assembly.

n. Jacketed piping system.

o. Control system/asphalt blending system.

p. Data.

q. Training/field representation.

3.8.1 Drum Mixer Unit. Design of the drum shall permit a synchronized virgin aggregate and recycling material mixing capability. There shall be an ignition/tile combustion chamberless automatic burner with remote ignition control to furnish heat to the drum. The burner shall have a minimum 50 HP blow and a minimum 1 1/2-HP fuel pump. The drum shall be fabricated of A441 Tri-Ten or equal 5/16 inch minimum thickness steel plate. Drum rotation shall be positive, using heavy industrial chain drive, having a power source of 50 HP minimum. The system air flow shall be variable throughout the minimum range of 11,000 CFM through 28,000 CFM. The drum shall have flighting, the position of which can be varied in the field, using common tools, to permit easy modification of material flow rates. Recycling entry system shall be mid-drum and shall possess a by-pass chute. The main frame of the drum mixer unit shall be all welded heavy structural steel with dual axle, dual 15-inch tires, kingpin, airbrakes, brake signals, turn signals and mudflaps. Tires, wheels, rims and tubes (when tires used are not tubeless) shall be in accordance with the recommendations of the TRA Yearbook. The drum unit shall be designed for easy erection and quick conversion to the portable mode. The use of a self-contained hydraulic erection system shall be permitted. Supports and blocking necessary to serve as a foundation for the operational drum shall be made of steel and shall be furnished with the plant. Supports or legs shall be adjustable, for example, screw jack type, and mechanical. Storing facilities on the drum unit shall be provided for foundation elements when in the portable mode. A slinger type, reversible, minimum 5HP-drive shall introduce the virgin aggregate into the drum mixer.

3.8.2 Cold Feed Bin Unit. The cold feed bin unit shall have four 25-ton capacity bins with a 30-inch wide belt gathering conveyor, electric SCR or accu-drive motors, vibrating device on the bin closest to the drum mixer unit, and a tachometer operated automatic cold feed system that monitors the tons per hour material from each feeder and displays this information at the control station. The

Source: https://assist.dla.mil -- Downloaded: 202640-23T09:46Z
Check the source to verify that this is the current version before use.

cold feed shall have a built-in bulkhead unit constructed of easily reparable material and of a configuration to allow maintenance on both sides of the feeder. All wiring shall be in a conduit to one end of the feed unit. The feed unit shall be portable. It shall have dual 15-inch tires, kingpin, airbrakes, brake signals, turn signals and mudflaps. Tires, wheels, rims and tubes (when used) shall be in accordance with the TRA Yearbook. This unit shall be designed for easy erection and rapid conversion to the portable mode. The use of a self-contained hydraulic erection system shall be permitted. Supports and blocking necessary to serve as a foundation for the operational cold feed bin unit shall be made of steel and shall be furnished by the contractor. Supports or legs shall be adjustable, mechanical screwjack type. Storing facilities shall be provided on the bin unit for foundation elements when in the transport mode. Additionally, the manufacturer shall furnish a portable two bin, 25-ton minimum capacity each, a minimum 5-HP direct current or accu-drive for each bin, 30-inch minimum width feeders and 30-inch minimum collecting belt. Both bins shall be equipped with a Block Buster model 416 or equal air cannon and shall be topped by a 4-inch flush mounted bar grizzly unit. This two bin unit shall include a bulkhead and means for self-erection. It shall be portable on pneumatic tires, and shall have a a kingpin, airbrakes, brake signals, turn signals and mudflaps. The mud flaps shall be of an all black or all white color.

3.8.3 Charging Conveyor Portable. A cold feed portable charging conveyor, with a 47-foot (minimum) length and 24-inch (minimum) width 4-ply rated belt electric motor 10-HP (minimum) driven, shall be furnished. The conveyor shall have a lagged head pulley, a self-cleaning tail pulley, 4-inch diameter 20 degree sealed for life idlers, a material receiving hopper, windguards, a dual idler belt scale complete with an electric recorder and diagnostic control box and cables, and a pneumatic calibration test weight assembly complete with solenoid valve. This unit shall include a 4-foot by 8-foot (minimum) single deck 2-inch scalping screen drive by a 5-HP electric motor complete with switch gear and cable. The scalping screen shall be mounted on a base that connects to the charging conveyor for travel and sits off in place during operations. The charging conveyor unit shall be portable. It shall have a kingpin attachment, 20 inch pneumatic tires, in accordance with TRA Yearbook recommendations, turn lights, stop lights, and mudflaps.

3.8.4 Bitumen Storage Tanks, Portable. Three each 10,000 gallon (minimum) asphalt storage/heater tanks, fully insulated and portable shall be furnished by the manufacturer. These three tanks shall be built onto one chassis and shall have separate hot oil heater built onto the gooseneck. This heater shall have sufficient capacity to heat the cone of the silo surge system (see 3.8.10) as well as heating each of the three storage tanks. The plant pump packing and unloading pump shall be mounted on the unit. The unit shall be portable with pneumatic tires in accordance with the TRA Yearbook, air brakes, brake lights, directional signal lights and mudflaps. Interconnect piping shall be jacketed except for flex sections.

3.8.5 Heating Fuel Storage Tank, Portable. A semi-trailer mount 5,000 gallon (minimum) fuel tank with a 1 1/2-HP (minimum) fuel pump and the beginning of the piping system to feed the burner on the drum mixer unit shall be furnished. Additional equipment which shall be mounted on this same trailer are the plant diesel electric generator, the switchgear shed, and the plant control house. The semitrailer's tires, wheels and rims shall be in accordance with the TRA Yearbook. The trailer shall have a kingpin, air brakes, brake lights and directional signal lights.

3.8.6 Generator, Portable. A diesel generator shall be furnished. The diesel generator shall, without exceeding the manufacturer's recommended operational RPM, produce sufficient current to operate the plant continuously at maximum production. The diesel generator unit shall be mounted on the same semi-trailer as the heating fuel storage tank. The diesel engine shall normally operate on Number 2 commercial grade diesel fuel IAW Federal Specification W-F-800 and shall be able to operate on aviation fuels JP-4 and JP-5 IAW Military Specification MIL-T-5684 in emergencies.

3.8.7 Steel Switchgear Shed. All switchgear for the mixing plant shall be located in one ventilated steel shed. Shed shall be designed such that air conditioning shall not be required below +125

Source: https://assist.dla.mil -- Downloaded: 202610-23T09:46Z
Check the source to verify that this is the currentversion before use.

degrees Fahrenheit. Switchgear shall be encased in cabinets designed for the purpose. This shed shall be mounted on the same semi-trailer carrying the diesel generator set.

3.8.8 Steel Plant Control House. The plant control house shall be fabricated of steel and shall be equipped for complete control of plant operation. This control house shall be hauled on the semi-trailer with items 3.8.5, 3.8.6, and 3.8.7, above. The control house shall have three sides windowed and tinted, shall be easily positioned or repositioned, and shall-afford a complete view of the operating plant.

3.8.9 Reclaimed Material Charging Conveyor, Portable. The reclaimed material charging conveyor, portable shall be identical to the charging conveyor portable specified herein 3.8.3 except for the 47-foot length. The length of this reclaimed material charging conveyor shall be compatible with the plant furnished.

3.8.10 Silo Surge System, Portable. A portable silo surge system of 65-tons minimum capacity shall be furnished. The system shall be complete with a drag flight conveyor, slug feeder and weight batcher. The silo shall have 3-inch, minimum thickness, insulation, metal skin, a hot oil heated cone, dual air gates and an air compressor.

3.8.11 Power Cables. All power cables, of the correct size and length necessary to set up and operate the plant, shall be furnished.

3.8.12 Fines Feeder. A feeder, mounted on a semi-trailer having air brakes, brake lights, directional signal lights and pneumatic tires per TRA Yearbook recommendations, shall be furnished to add fines to the drum mixer unit. The fines feeder shall be complete consisting of, but not limited to the following: one 40-cubic foot weighing vessel underneath a 350 barrel unpressurized silo having at least 12 aeration pads and piping from the blower, one rotary vane feeder 1 1/2-HP minimum, a low pressure rotary blower (Schnitzer Model 3006 or equal), 3 load cell suspension and electronic weighing control, and filler pipe in drum and connecting pipe.

3.8.13 Hot Oil Heater Assembly. The bitumen tank heating devices shall be of sufficient capacity to supply hot oil into all bitumen lines to the plant, to the pumping devices, to the interconnect piping using piping and transfer devices for this purpose, and if required to the silo surge cone.

3.8.14 Jacketed Piping System. The bitumen piping shall be heated by a system of steeljacketed piping having flexible line interconnects where necessary.

3.8.15 Control System/Asphalt Blending System. The control system shall completely control the plant operations with options for reclaimed aggregate, mineral filler, mix additives (anti-strip 0.5 percent normal), readout of feeder rates of cold feeds, individual dry aggregate belt scale flow rate in tons per hour and total mix including bitumen. The memory shall store a minimum of eight mix designs. When any one of the eight mix designs are called out, the controls will reset feeder rates to respond to the design of the mix called. Additional controls required are automatic burner control, automatic damper control, alarms for feeder/burner/or other component out of tolerance to the mix design, surge bin controls, drag conveyor controls, cold feed controls, asphalt metering controls, and start/stop stations with load meters for motors over 20-HP. The asphalt percentages shall be entered and the control system shall monitor both virgin material and reclaimed material weights passing over the dual idler belt scales, await the inputed delay and then direct the correct amount of asphalt to be pumped into the drum. A digital weight indicator and simple printer of delivery type tickets shall be included.

3.8.16 Data. A minimum of two each of the manufacturer's maintenance and operation instructions, parts book, drawings and plans for the complete setup of the plant, piping systems layout, electrical wiring diagrams, and fuel supply piping layout shall be sent with the plant to its contrac-

Source: https://assist.dla.mil -- Downloaded: 202640-23T09:46Z
Check the source to verify that this is the currentversion before use.

tual shipping point. The manufacturer shall take the necessary precautions to ensure the data shall be in usable condition and that it will arrive with the plant. The maintenance and operating instructions and the parts list shall cover all components of the entire plan, as well as a step by step procedure for setup and takedown for ready for calibration and transport modes.

3.8.17 Training/Field Representative. The successful bidder shall furnish a technical representative upon delivery of the plant for a minimum of 10 work days to assist with the initial plant setup, and provide training as required.

3.9 Environmental. The plant shall meet the United States clean air standards. It shall be the manufacturer's option to supply a wet type filter system or a dry collector. The type item selected shall fit into the C-5A aircraft and shall be completely portable. Wet systems shall include the washer, water pump, and necessary piping, fittings, and connectors. Dry collectors shall have a maximum air to cloth ratio of 6 to 1 and shall include the necessary duct work, air compressor(s), a pneumatic dust return system, over temperature shut down and isolation system.

3.10 Tools. Any tool, other than common hand tools, which is deemed to be special and is essential to the adjustment or correct operation of plant components shall be supplied by the contractor and shipped with the plant to initial destination.

3.11 Air Transportability. All separate components in the portable mode shall not exceed the maximum dimensional criteria, in accordance with MIL-A-8421, of length 1551 inches to ensure transportability on C-5A aircraft. Design of the components shall permit each to be restrained to withstand the following forces applied statically and independently:

Fore - 3-G
Aft- 1 1/2-G
Lateral- 1 1/2-G
Up - 2-G
Down - 41/2-G

"G" is the weight of the component. Thus 3-G would be a force three times the component's weight. Directions provided are relative to the aircraft. Additionally, each component shall be so configured that it will negotiate a 10-degree ramp to a flat plane and into an interior measuring not greater than 162 inches high and 228-inches wide without any interference with the interior ceiling, walls, the ramp or ramp crest.

3.12 Workmanship. Workmanship of the asphalt plant and accessories shall be of the quality prevailing among manufacturer's producing equipment of the type specified herein. Defective components or parts and assemblies which have been repaired to overcome deficiencies shall not be furnished. Welded, bolted and riveted construction shall be in accordance with the highest standards of industry.

4. QUALITY ASSURANCE PROVISIONS

4.1 Responsibility for inspection. Unless otherwise specified in the contract or purchase order, the contractor is responsible for the performance of all inspection requirements as specified herein. Except as otherwise specified in the contract or purchase order, the contractor may use his own or any other facilities suitable for the performance of the inspection requirements specified herein, unless disapproved by the Government. The Government reserves the right to perform any of the inspections set forth in the specification where such inspections are deemed necessary to assure supplies and services conform to prescribed requirements.

4.1.1 Responsibility for compliance. All items shall meet all requirements of sections 3 and 5. The inspection set forth in this specification shall become a part of the contractor's overall inspection

Source: https://assist.dla.mil -- Downloaded: 202610-23T09:46Z
Check the source to verify that this is the current version before use.

system or quality program. The absence of any inspection requirements in the specification shall not relieve the contractor of the responsibility of assuring that all products or supplies submitted to the Government for acceptance comply with all requirements of the contract. Sampling in quality conformance does not authorize submission of known defective material, either indicated or actual, nor does it commit the Government to accept defective material.

4.2 Classification of Inspection. Inspection shall be classified as follows:

a. Preproduction inspection.

b. Quality conformance inspection.

4.2.1 Preproduction Inspection. Preproduction inspection shall be applied to the preproduction sample submitted in accordance with 3.1. Preproduction inspection shall consist of the examination in 4.3 and all tests in 4.4. Failure of the preproduction sample to pass the examinations on one or more tests shall be cause for rejection.

4.2.2 Quality Conformance Inspection. Quality conformance inspection shall be applied to each item being offered for acceptance under the contract. Failure of the asphalt plant to pass the examination, tests or inspection shall be cause for rejection. Quality conformance shall consist of the following:

a. Examination (See 4.3)

b. Tests (See 4.4)

c. Inspection of preservation, packaging, packing and marking for shipment and storage (See 4.5)

4.3 Examination. Each complete asphalt plant shall be examined for compliance with the requirements specified in Section 3 of this Specification. Any redesign or modification of the supplier's standard product to comply with special requirements shall receive particular attention. This element of inspection shall encompass all visual examinations and dimensional measurements. Noncompliance with any specified requirements shall be cause for rejection.

4.4 Tests.

4.4.1 Road Test. With the components of the asphalt plant in transport mode, each separate unit shall be towed by a manufacturer's truck tractor over non-paved roads at speeds up to 25 miles per hour for a distance of not less than 5 miles. During the test run each towed unit shall be braked to a stop a minimum of 5 times and brake lights and directional signal lights shall be operated to ensure that they are working correctly. Failure of the trailorized units to track and operate correctly or support the loads without any sign of permanent deformation shall be cause for rejection.

4.4.2 Plant Set-Up Test. The transport mode units shall all be delivered to a site of the manufacturer's selection for assembly into the operational mode. The components shall then be assembled using common tools and a 40-ton (approximately) capacity crane having a minimum lift height of 60 feet under the hook. Setup of the plant shall be complete and ready for calibration in no more than 150 manhours. Failure to meet the setup time requirement as well as the proper fitting of components shall be cause for rejection.

4.4.3 Operational Test. The assembled asphalt plant shall be operated at no load for sufficient duration to ensure that all components operate as specified and without malfunction. Failure shall be cause for rejection.

Source: https://assist.dla.mil -- Downloaded: 202610-23T09:46Z
Check the source to verify that this is the currentversion before use.

4.4.4 Plant Disassembly Test. Using the crane (see 4.4.2) and common tools the operational plant shall be disassembled and converted to the transport mode in no more than 100 manhours. Failure to meet this time criteria shall be cause for rejection.

4.4.5 Production Tests. The manufacturer shall submit, to the quality assurance representative at the time of testing, a notorized certification that the asphalt plant he is supplying meets or exceeds all specified performance requirements of Section 3 of this purchase description. If first article test report is required, a copy of this certification shall be included in the report. Failure to comply shall be cause for rejection.

4.4.6 Air Transportability Test. To prove that each component of the asphalt plant, in the transport mode, will load and fit into the C-5A aircraft, the following test shall be conducted. An aircraft mockup of wood or other suitable material shall be furnished by the manufacturer. The mockup shall consist of a 10 degree ramp, sturdy enough to support each component, connecting two horizontal ramps. Ramps shall be a maximum of 228 inches wide. Over the top ramp, a frame work shall be constructed having inside dimensions of 162 inches high and 228 inches wide and 20 feet long from the inclined ramp crest toward the extended end of the upper ramp. The surface of the uppermost ramp represents the floor of the aircraft, the inside of the frame uprights depict the inner sides of the aircraft, and the ceiling of the framework the ceiling height of the aircraft. Each component of the asphalt plant shall be backed from the lower ramp, up the inclined ramp and onto the upper ramp. Interference of any component with the interior framework of the mockup, ramp or ramp crest shall be cause for rejection.

4.5 Inspection of Preservation Packaging, Packing and Marking for Shipment and Storage. Preservation, packaging, packing and marking for shipment and storage shall be inspected to verify conformance with the terms of the contract or order.

5. PACKAGING

5.1 Preservation, Packaging, Packing, Marking and Shipping. Preservation, packaging, packing, marking and method of shipping shall be in accordance with the provisions of the contract or order.

6. Notes.

(This section contains information of a general or explanatory nature that may be helpful, but is not mandatory.)

6.1 Intended Use. This asphalt plant is intended for the use of the Civil Engineer to produce hot mix asphaltic concrete from recycled materials and/or virgin materials for paving projects such as streets, highways and airfield pavements.

6.2 Ordering Data. Procurement documents should specify the following:

a. Title, number and date of this purchase description.

b. Preproduction sample, if required (see paragraph 3.1)

6.3 Preproduction Sample. The sample may be a production item or a preproduction item which meets the requirements of this specification. In either case, the sample shall be identical with the proposed item and shall be made or shall have been made by the methods that are to be used or were used in production of items to fulfill the terms of the contract. Approval of a preproduction sample shall not relieve the contractor of the responsibility to furnish equipment in accordance with the requirements of this specification. The preproduction sample may be shipped as part of the contract.

Source: https://assist.dla.mil -- Downloaded: 202610-23T09:46Z
Check the source to verify that this is the currentversion before use.

6.4 Subject Term (Key Word) Listing.

Bitumen Storage Tanks
Charging Conveyor
Cold Feed Bin Unit
Drum Mixer Unit
Jacketed Piping System
Silo Surge System

Custodian:
Air Force - 99

Preparing Activity:
Air Force - 84

Project Number: 3895-F276

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T09:46Z
Check the source to verify that this is the current version before use.

STANDARDIZATION DOCUMENT IMPROVEMENT PROPOSAL

INSTRUCTIONS

1. The preparing activity must complete blocks 1, 2, 3, and 8. In block 1, both the document number and revision letter should be given.
2. The submitter of this form must complete blocks 4, 5, 6, and 7.
3. The preparing activity must provide a reply within 30 days from receipt of the form.

NOTE: This form may not be used to request copies of documents, nor to request waivers, or clarification of requirements on current contracts. Comments submitted on this form do not constitute or imply authorization to waive any portion of the referenced document(s) or to amend contractual requirements.

I RECOMMEND A CHANGE:	1. DOCUMENT NUMBER	2. DOCUMENT DATE (YYMMDD)
	MIL-P83814	14 June 1990

3. DOCUMENT TITLE Plant,Asphalt Mixing,Drum Type,Electric Motor Dirven,Roadable, Air Transportable C-5A Aircraft, 125 Tons Per Hour Capacity

4. NATURE OF CHANGE *(Identify paragraph number and include proposed rewrite, if possible. Attach extra sheets as needed.)*

5. REASON FOR RECOMMENDATION

6. SUBMITTER

a. NAME (Last, First, Middle Initial)	b. ORGANIZATION	
c. ADDRESS (Include Zip Code)	d. TELEPHONE (Include Area Code) (1) Commercial (2) AUTOVON (If applicable)	7. DATE SUBMITTED (YYMMDD)

8. PREPARING ACTIVITY

a. NAME	b. TELEPHONE (Include Area Code) (1) Commercial 912-926-5616	(2) AUTOVON 468-5616
Michael A. Greene		
c. ADDRESS (Include Zip Code) WR-ALC/MMDETB Robins AFB GA 31098-5609	IF YOU DO NOT RECEIVE A REPLY WITHIN 45 DAYS, CONTACT: Defense Quality and Standardization Office 5203 Leesburg Pike, Suite 1403, Falls Church, VA 22041-3466 Telephone (703) 756-2340 AUTOVON 289-2340	

Source: https://assist.dla.mil -- 2026-01-28 14:03:47 EST
Check the source to verify that this is the current version before use.