FF-I-525A
June 22, 1970
SUPERSEDING
Int. Fed. Spec. FF-I-00525(GSA-FSS)
October 28, 1966

FEDERAL SPECIFICATION

INCINERATOR, PORTABLE, CLASSIFIED PAPER WASTE, SECURITY

This specification was approved by the Commissioner, Federal Supply Service, General Services Administration, for the use of all Federal agencies.

1. SCOPE AND CLASSIFICATION

1.1 Scope. This specification covers portable incinerators which are mounted on casters. The incinerators are designed to meet the document destruction criteria for classified material set forth in Executive Order 10501, as amended, "Safeguarding Official Information in the Interest of the Defense of the United States."

1.2 Classification. The incinerators shall be of but one type and size and shall be capable of the complete burning destruction of paper material at the burning rate of not less than 6 pounds an hour.

2. APPLICABLE DOCUMENTS

2.1 The following documents of the issues in effect on the date of invitation for bids or request for proposal, form a part of this specification to the extent specified herein.

Federal Specifications:

CC-M-636 - Motor, Alternating Current (Fractional Horsepower).
TT-C-490 - Cleaning Methods and Pretreatment of Ferrous Surfaces for Organic Coatings.
TT-E-489 - Enamel, Alkyd, Gloss (For Exterior and Interior Surfaces).
TT-P-28 - Paint, Aluminum, Heat Resisting.
TT-P-645 - Primer, Paint, Zinc Chromate, Alkyd type.
PPP-B-566 - Boxes, Folding, Paperboard.
PPP-B-601 - Boxes, Wood, Cleated-Plywood.
PPP-B-665 - Boxes, Paperboard, Metal Stayed (Including Stay Material).
PPP-B-676 - Boxes, Setup.
PPP-C-843 - Cushioning Material, Cellulosic.

Federal Standard:

Fed. Std. No. 123 - Marking for Domestic Shipment (Civilian Agencies).

(Activites outside the Federal Government may obtain copies of Federal Specifications, Standards, and Handbooks as outlined under General Information in the Index of Federal Specifications and Standards and at the prices indicated in the Index. The Index, which includes cumulative monthly supplements as issued, is for sale on a subscription basis by the Superintendent of Documents, U.S. Government Printing Office, Washington, D.C. 20402.

(Single copies of this specification and other Federal Specifications required by activities outside the Federal Government for bidding purposes are available without charge from Business Service Centers at the General Services Administration Regional Offices in Boston, New York, Washington, D.C., Atlanta, Chicago, Kansas City, Mo., Fort Worth, Denver, San Francisco, Los Angeles, and Seattle, Washington.

(Federal Government activities may obtain copies of Federal Specifications, Standards, and Handbooks and the Index of Federal Specifications and Standards from established distribution points in their agencies.)

Military Specifications:

MIL-B-121 - Barrier Material, Grease-Proofed, Water-Proofed, Flexible.
MIL-P-116 - Preservation, Methods of.
MIL-S-45180 - Sealing Compound, Gasket, Hydrocarbon, Fluid and Water Resistant.
MIL-T-22085 - Tape, Pressure-Sensitive Adhesive, Preservation and Sealing.

FSC 4540

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T11:47Z
Check the source to verify that this is the current version before use.

Military Standards:

MIL-STD-105 - Sampling Procedures and Tables for Inspection by Attributes.
MIL-STD-129 - Marking for Shipment and Storage.

(Copies of Military Specifications and Standards required by contractors in connection with specification procurement functions should be obtained from the procuring activity or as directed by the contracting officer.)

3. REQUIREMENTS.

3.1 Preproduction sample. Before production is commenced, a sample of the finished commodity shall be submitted or made ready for approval of the contracting officer or his authorized representative for inspection and tests to determine compliance with this specification. Approval of the preproduction sample authorizes the commencement of production, but does not relieve the contractor of responsibility for compliance with all provisions of this specification. Production units shall not vary from the approved preproduction sample in design or construction without written approval of the contracting officer.

3.2 Materials. Materials used in the incinerators shall be as indicated herein and in the specification drawings (see 6.3). Materials not definitely specified shall be of good commercial quality, suitable in every respect for the purpose intended.

3.2.1 Protective coating. Material used in the incinerator which may be subject to deterioration when exposed to climatic and environmental conditions likely to be encountered during service usage shall be protected against such deterioration in a manner which will in no way prevent compliance with the performance requirements of this specification. The use of any protective coating which will crack, chip, or scale with age or extremes of climate and environmental conditions shall be avoided.

3.3 Construction.

3.3.1 Fabrication and assembly. Component parts of the incinerator shall be fabricated and assembled in accordance with the specification drawings. The fabricator shall be responsible that the respective parts fit together properly for the intended use. Completely assembled incinerators shall comply with tests in 4.7.

3.3.2 Construction precautions. Particular attention shall be given to the following construction details in assembly of the incinerator:

(a) Care shall be taken not to warp or spatter weld metal on the machined mating surfaces of the Flanges when they are welded to the Ash Container and to the Hot Air Jacket Assembly.

(b) In welding the Cone to the flat disc of the Inner Cover, the disc shall be maintained flat within 1/64-inch to minimize air leakage in the finished unit. Welds shall not extend more than 1/16-inch beyond the 9-1/2-inch OD of the Cone.

(c) The Inner Cover, after assembly, shall move freely by hand against its spring tension and shall not bind when moved laterally in its slot.

(d) To minimize air leakage at the rectangular butt fitting, care shall be taken to position the Cyclone Assembly so that it lines up properly with the rectangular flue gas passage of the Inner Cover. Any welding burrs inside the lower part of the Cyclone Assembly shall be ground smooth to avoid poor dust collection efficiency of the Cyclone.

(e) Care shall be taken so that proper alignment is obtained in fitting the hinged cover on the unit and to assure that the cover seats adequately against the rubber "O" Ring Gasket under operating air pressure. The shims shown in the specification drawings, and the adjustment provided on the Latch makes it possible to obtain a leak-free seal at the cover.

(f) All welding of stainless steel parts shall be done by heliarc welding using stainless steel filler rod, if necessary.

3.4 Motor blower. The electric motor blower for the incinerator shall be a self-contained, fractional horsepower, two-stage, vacuum cleaner type. Unless otherwise specified (see 6.2), the blower motor shall be a single phase unit designed to operate from a 50/60 cycle, 110 volt source. The motor shall be in accordance with CC-M-636 and shall be capable of developing sufficient power to maintain continuous full load output without exceeding allowable temperature rises specified in CC-M-636.

3.4.1 Motor toggle switch. The toggle switch shall be suitable for starting and stopping the motor and its rating shall be not less than that of the motor blower.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T11:47Z
Check the source to verify that this is the current version before use.

3.5 Casters. The incinerator shall be mounted on casters as depicted in the specification drawings. The casters shall have nonmarking, natural, or synthetic rubber tires and ball, roller, or self-lubricating sleeve bearings.

3.6 Pretreatment. Prior to painting, the exterior surfaces of the incinerator shall be cleaned in accordance with any of the types in TT-C-490.

3.7 Color and finish. Painting of the exterior surfaces of the incinerator shall not be performed until all testing is completed. The inner body of the incinerator shall be painted inside and outside with a heat resistant aluminum paint conforming to TT-P-28. A primer coat of zinc chromate paint conforming to TT-P-645 shall be applied to the exterior surfaces. The exterior shall than be painted with a final coat of gray enamel conforming to TT-E-489.

3.8 Marking. In addition to the markings required in the specification drawings, each incinerator shall be plainly marked with an identifying serial number, the manufacturer's name or trade mark, and the date (year) of manufacture.

3.9 Workmanship. The incinerator, including all parts and accessories shall be fabricated and assembled in a workmanlike manner. The incinerator shall be free from blemishes, burrs, and unfinished surfaces. Soldering, welding, brazing, riveting, and wiring shall be neat and secure. Lock washers, cotter pins, clips, or other features shall be used to prevent the loosening of screws, nuts, bolts, and similar hardware.

3.10 Instruction manual. An instruction manual shall be furnished by the manufacturer to provide complete instructions necessary for the assembly, operation, and maintenance of the incinerator.

3.11 Spare parts. The spare parts listed in the specification drawings shall be packaged and furnished with each incinerator.

4. QUALITY ASSURANCE PROVISIONS

4.1 Inspection responsibility. Except as otherwise specified herein, the supplier is responsible for the performance of all inspection requirements as specified herein. Except as otherwise specified, the supplier may utilize his own or any other inspection facility or services acceptable to the Government. Inspection records of the examinations and tests shall be kept complete and available to the Government as specified in the contract or order. The Government reserves the right to perform any of the inspections set forth in this specification where such inspections are deemed necessary to assure that supplies and services conform to prescribed requirements.

4.2 Component and material inspection. In accordance with 4.1, the supplier is responsible for insuring that components and materials used are manufactured, tested, and inspected in accordance with the requirements of referenced subsidiary specifications and standards to the extent specified, or, if none, in accordance with this specification.

4.3 Approval of preproduction sample. In accordance with 3.1, inspections and tests specified in 4.7 shall be made by the Government inspector on a complete, working incinerator to determine compliance with specification requirements before regular production is started.

4.4 Inspection lot. A lot shall consist of all incinerators produced at one time by one manufacturer, from the same materials, under identical manufacturing conditions.

4.5 Inspection of preparation for delivery. An inspection shall be made to determine that the preservation, packaging, packing and marking comply with the requirements in section 5 of this specification. Defects shall be scored in accordance with table I. For examination of interior packaging the sample unit shall be one shipping container fully prepared for delivery, selected at random just prior to the closing operations. Sampling shall be in accordance with MIL-STD-105. Defects of closure listed shall be examined on shipping containers fully prepared for delivery. The lot size shall be the number of shipping containers in the end item inspection lot. The inspection level shall be S-2 with an AQL of 2.5 defects per hundred units.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T11:47Z
Check the source to verify that this is the current version before use.

TABLE I. Classification of preparation for delivery defects

Examine	Defects
Markings (exterior and interior)	Omitted; incorrect; illegible; improper size, location, sequence, or method of application.
Materials	Any component missing or damaged.
Workmanship	Inadequate application of components such as incomplete closure of container flaps, loose strapping, inadequate stapling. Distortion of container.

4.6 Testing. Each incinerator offered for acceptance under contract or order shall be tested in accordance with test methods in 4.7. Proper functioning of one incinerator shall not constitute the basis for acceptance of an entire lot. Rejection of an incinerator offered for acceptance shall not preclude the manufacturer from correcting the condition which forms tha basis for rejection, and from reworking a rejected part to remedy such defect for resubmission to inspection and test. All units and parts so reworked shall be indicated to the Government inspector.

4.7 Test methods.

4.7.1 Cold air flow test. Each incinerator shall be coneected to an appropriate electrical outlet and a manometer shall be connected to the incinerator Pressure Tap Fitting by means of a rubber tube not to exceed 36 inches in length. The cold air-flow tests shall be made while the incinerator assembly is empty, in order to check for leaks at the gasketed joints, and to measure the chamber pressure which is an indication of the overall satisfactory condition of the air flow passages.

To measure the chamber pressure all doors shall be closed and the motor turned on. Under these conditions, the internal air pressure in the chamber, as indicated by the Manometer, shall be between 8.0 to 9.0 inches of water. Any errors or defects stemming from the manufacture of the Incinerator Assembly that contributes to internal pressures outside the range of 8.0 to 9.0 inches of water shall be corrected by the manufacturer. The measurement of the chamber pressure shall then be re-run before proceeding with the remainder of the cold air-flow testing.

To check for leaks, the motor shall be running and the charging door and the door covering the motor closed. A check shall then be made for air leaks around the sight port, each of the screws in the cover plate, around the charging door and the clamp assembly in the back by the cyclone separator. Leakage thus detected shall be judged excessive if the flame from a lighted "paper book" match is extinguished when held within 1-inch distance of the source of leakage. Excessive leakage of air at any of the points shall be corrected by appropriate measures before the cold air-flow testing is completed and the paper-burning test conducted.

4.7.2 Paper-burning test. This test shall consist of burning 6 pounds of selected paper in a period of one hour. The paper shall be charged in 2 pound batches. A supply of reasonably dry paper shall be obtained and used for the burning test. Typical paper from dicarded office files, such as bond and onion-skin typing paper shall be considered suitable. Newspapers and glossy magazines are not acceptable.

During the burning test another check for air leaks shall be made. Particular attention shall be paid to the cover plate, the screws in the cover plate, the "V" closure around the ash receptable, and the microswitch along the side. If air leaks occur during the burning test the fabricator shall be responsible for stopping these leaks. If the microswitch disengages during the burning test the fabricator shall be responsible for correcting this malfunction.

Near the end of the burning test, the slow burning residue shall be stirred once by manual poking, to obtain complete burnout.

4.8 Test Results. Results of the tests shall be considered satisfactory if the following conditions are achieved:

(a) The incinerator meets the specified cold air-flow requirements.
(b) All air leaks are stopped for both the cold-air-flow tests and during the paper burning tests.
(c) Incineration of six (6) pounds of paper is completed in one (1) hour or less.
(d) All raw paper is destroyed to the point where no readable material remains.
(e) No accumulation of residue is exhausted from the cyclone separator.
(f) All associated equipment such as the dolly, stacks, poker, and microswitch are fabricated and attached correctly and function as intended.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T11:47Z
Check the source to verify that this is the current version before use.

5. PREPARATION FOR DELIVERY

5.1 Preservation and packing. Preservation and packaging shall be level A, B, or C as specified (see 6.2).

5.1.1 Level A.

5.1.1.1 Disassembly. Disassembly of the incinerator shall be the minimum necessary to safeguard parts vulnerable to damage, pilferage and loss. The blower unit, pyrometer unit, radiation shield, or protruding parts that increase cubage and that can be removed and reassembled without special tools shall be removed. All bolts, nuts and washers removed shall be attached to the mating parts and secured to prevent their loss.

5.1.1.2 Unprotected surfaces. Exterior unprotected metal surfaces requiring the application of a contact preservative shall be coated with type P-1 preservative in accordance with MIL-P-116.

5.1.1.3 Blower assembly. The power supply cables shall be coiled to the minimum safe diameter and secured in three places evenly spaced around the circumference of the coil. All openings in the electric motor shall be sealed with tape conforming to MIL-T-22085, type I.

5.1.1.4 Unit packaging.

5.1.1.4.1 Pyrometer. The pyrometer shall be packaged method IG-2 of MIL-P-116.

5.1.1.4.2 Technical manual. The technical manual shall be packaged method IC-1 of MIL-P-116.

5.1.1.4.3 Spare parts. The spare parts shall be wrapped with material conforming to MIL-B-121, type II and cushioned with material conforming to PPP-C-843, type II, class 2. The wrap shall be secured with tape.

5.1.2 Level B.

5.1.2.1 Disassembly. Disassembly of the incinerator shall be the minimum necessary to safeguard parts vulnerable to damage, pilferage and loss. The blower unit, pyrometer unit, radiation shield or protruding parts that increase cubage and that can be removed and reassembled without special tools shall be removed. All bolts, nuts, and washers removed shall be attached to the mating parts and secured to prevent their loss.

5.1.2.2 Blower assembly. Power supply cables shall be coiled to the minimum safe diameter and secured in three places evenly spaced around the circumference of the coil. All openings in the electric motor shall be covered with tape conforming to MIL-T-22085, type I.

5.1.2.3 Unit packaging.

5.1.2.3.1 Pyrometer. The pyrometer shall be packaged in a close-fitting box conforming to PPP-B-566, PPP-B-665, or PPP-B-676. Cushioning shall be provided.

5.1.2.3.2 Technical manual. The technical manual shall be packaged in a kraft paper bag and secured with tape.

5.1.2.3.3 Spare parts. The spare parts shall be wrapped with material conforming to MIL-B-121, type II, and cushioned with material conforming to PPP-C-843, type II, class 2. The wrap shall be secured with tape.

5.1.3 Level C. The incinerator components or spare parts shall be preserved and packaged to afford protection against corrosion, deterioration and damage from the supplier to the initial destination.

5.2 Packing. Packing shall be level A, B, or C, as specified (see 6.2).

5.2.1 Level A. The incinerator and components or spare parts shall be packed in a close-fitting box conforming to PPP-B-601, overseas type. Cushioning, blocking and bracing shall be provided. The box shall be closed and strapped in accordance with the appendix to the box specification.

5.2.2 Level B. The incinerator and components or spare parts shall be packed in a close-fitting box conforming to PPP-B-601, domestic type. Cushioning, blocking and bracing shall be provided. The box shall be closed in accordance with the appendix to the box specification.

5.2.3 Level C. The incinerator, components or spare parts shall be packed to insure carrier acceptance and safe delivery at destination in containers comply with the rules and regulations applicable to the mode of transportation.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T11:47Z
Check the source to verify that this is the current version before use.

6. NOTES

6.1 Intended use. The incinerator covered by this specification is 12 inches by 21 inches by 28 inches high and weighs approximately 85 pounds. It is intended for office use as determined by the responsible authority in the emergency destruction of classified documents and related paper products. The incinerator is not designed to burn wood, wood products, or refuse and such use will cause irreparable damage to the incinerator. The unit must be vented through a window or similar opening to the outside when in use.

6.2 Ordering data. Purchaser should exercise any desired options offered herein, and procurement documents should specify the following:

(a) Title, number, and date of this specification.
(b) Motor electrical characteristics, if other than specified (see 3.4).
(c) Levels of preservation, packaging, and packing required (see 5.1 and 5.2).

6.3 Specifications drawings. Specification drawings (No. 366) which form a part of this specification are available for examination, or will be furnished at a cost of $10.00 per set upon request addressed to the General Services Administration Business Service Center, Washington, D.C. 20407. Certified checks or postal money orders are to be made payable to "General Services Administration, Region 3".

Description	Drawing Number
Air-Fed Incinerator Assembly	366-100
Air-Fed Incinerator Detail	366-200
Air-Fed Incinerator Detail	366-201
Air-Fed Incinerator Detail	366-202
Air-Fed Incinerator Detail	366-203
Air-Fed Incinerator Detail	366-204
Air-Fed Incinerator Detail	366-205

Preparing activity:

GSA

Orders for this publication are to be placed with General Services Administration, acting as an agent for the Superintendent of Documents. See section 2 of this specification to obtain extra copies and other documents referenced herein. Price 10 cents each.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T11:47Z
Check the source to verify that this is the current version before use.