MIL-C-14024B(MU)
3 October 1967
SUPERSEDING
MIL-C-14024A(CmlC)
18 April 1960

MILITARY SPECIFICATION

CANISTER, SMOKE, WP, 5 INCH

PROJECTILE, M5; COMPONENTS FOR

1. SCOPE

1.1 Scope. This specification covers two types of components for a smoke canister.

1.2 Classification. Canister components shall be of the following types:

Type I	-	Canister body deep drawn.
Type II	-	Canister body longitudinally welded.

2. APPLICABLE DOCUMENTS

2.1 The following documents of the issue in effect on date of invitation for bids or request for proposal, form a part of this specification to the extent specified herein:

SPECIFICATIONS

FEDERAL

QQ-S-781	-	Steel, Strapping, Flat.
PPP-B-621	-	Boxes, Wood, Nailed and Lock-Corner.
PPP-F-320	-	Fiberboard; Corrugated and Solid Sheet Stock (Container Grade), and Cut Shapes.
PPP-P-291	-	Paperboard, Wrapping, Cushioning.
PPP-T-60	-	Tape: Pressure-Sensitive Adhesive, Waterproof for Packaging.
PPP-T-495	-	Tubes, Mailing, and Filing.

FSC 1320

Source: https://assist.dla.mil -- Downloaded: 2026-10-18T02:46Z
Check the source to verify that this is the current version before use.

STANDARDS

MILITARY

MIL-STD-105 - Sampling Procedures and Tables for Inspection by Attributes.

DRAWINGS

US ARMY MUNITIONS COMMAND

DL15-11-117 - Canister, Smoke, WP, 5 Inch Projectile, M5, Empty.

(All drawings referenced in this specification are listed on above Edgewood Arsenal drawing.)

(Copies of specifications, standards, drawings, and publications required by suppliers in connection with specific procurement functions should be obtained from the procuring activity or as directed by the contracting officer.)

3. REQUIREMENTS

3.1 Materials and components.

3.1.1 Materials. All materials cited on Drawing DL15-11-117 or on the subsidiary drawings shall conform to the specification listed thereon, or to the specific characteristics set forth on the drawings.

3.1.2 Components. All components of the canister shall conform to the Specifications and drawings listed on Drawing DL15-11-117 and to the subsidiary drawings.

3.2 Assembly. The components shall be assembled in accordance with Drawing D15-11-117.

3.3 Leakage. The canister shall not leak when subjected to an internal air pressure of $40 \begin{smallmatrix} +5 \\ -0 \end{smallmatrix}$ pounds per square inch gage (psig) and tested as specified in 4.3.4.

Source: https://assist.dla.mil -- Downloaded: 2026-10-18T02:46Z
Check the source to verify that this is the current version before use.

3.4 Preproduction. Prior to the start of regular production a preproduction sample of canister components shall be produced in accordance with this specification for examination and test (see 4.2).

3.5 Workmanship. The canister components shall be free from foreign matter (oil, grease, or flux) and damage such as cracks, dents or deformation which could affect their use.

4. QUALITY ASSURANCE PROVISIONS

4.1 Responsibility for inspection.

4.1.1 Supplier's responsibility. Unless otherwise specified in the contract or purchase order, the supplier is responsible for the performance of all inspection requirements as specified herein. Except as otherwise specified, the supplier may utilize his own facilities or any commercial laboratories acceptable to the Government. The Government reserves the right to perform any of the inspections set forth in the specification, where such inspections are deemed necessary to assure supplies and services conform to prescribed requirements.

4.1.2 Objective evidence. The supplier shall provide evidence acceptable to the contracting officer that the requirements of 3.1 and section 5 for which specific inspection has not been provided in this specification have been satisfied.

4.2 Preproduction.

4.2.1 Sample. A preproduction sample of 15 sets of canister components shall be manufactured using the same methods, materials, equipment and processes as will be used during regular production.

4.2.2 Inspection.

4.2.2.1 For examination. The sample sets of canister components shall be examined in accordance with the classification of defects (4.3.3.2).

4.2.2.2 For test. The sample sets of canister components shall be tested as specified in 4.3.4.

Source: https://assist.dla.mil -- Downloaded: 2026-10-18T02:46Z
Check the source to verify that this is the current version before use.

4.2.3 Acceptance/rejection criteria. The preproduction sample shall comply with the examinations and test specified in 4.2.2 to be acceptable. The supplier shall obtain written approval from the contracting officer prior to proceeding with regular production.

4.3 Regular production.

4.3.1 Lotting. A lot shall consist of the components produced by one manufacturer of one interfix number, at one plant, from the same materials, under essentially the same manufacturing conditions.

4.3.2 Sampling for examination and nondestructive test. Sampling shall be conducted in accordance with MIL-STD-105.

4.3.3 Inspection.

4.3.3.1 Examination and nondestructive test. Sample components and the level A preparation for delivery shall be examined and tested in accordance with the classification of defects and MIL-STD-105.

Source: https://assist.dla.mil -- Downloaded: 2026-10-18T02:46Z
Check the source to verify that this is the current version before use.

4.3.3.2 Classification of defects.

(a) Canister, smoke, WP, 5 inch projectile, M5, empty (Dwg D15-11-117).

Categories	Defects	Acceptance standards
Critical:		
1	Leakage	4.3.4
Major:	AQL 1.0 percent defective	
101	Component missing or incorrectly assembled	
102	Welding incorrect	
103	Soldering incorrect	
104	Overall lengths incorrect	
105	Outside diameter incorrect (after painting)	
106	Threads (1/2 - 14 NPTF) incorrect	
107	Protective finish missing or incorrect	
108	Threads (7/8-14 UNF 2B)	
109	Depth of thread .344 (Drawing B15-11-15)	
110	Incorrect diameter .90 + .02 (Drawing B15-11-15)	
111	Workmanship (3.5)	
Minor:	AQL 2.5 percent defective	
201	Plastic plug, size, type incorrect or missing	

Source: https://assist.dla.mil -- Downloaded: 2026-10-18T02:46Z
Check the source to verify that this is the current version before use.

4.3.3.2 Classification of defects. (Continued.)

(b) Body, Canister (Dwg C15-11-12 or C15-11-95).

Categories		Defects
Critical:		None defined
Major:	AQL	1.0 percent defective
101		Outside diameter incorrect
102		Welding incorrect (Dwg C15-11-12)
103		Overall length incorrect
104		Holes diameter incorrect
105		Holes location incorrect
106		Burrs not removed
107		Workmanship (3.5)

(c) Well, burster tube assembly (Dwg D15-11-11).

Categories		Defects
Critical:		None defined
Major:	AQL	1.0 percent defective
101		Overall length incorrect
102		Top plate diameter incorrect
103		Thread incorrect
104		Welding incorrect
105		Brazing incorrect
106		Tube not flush or below flush to undercut of adapter
107		Component missing or incorrectly assembled
108		Workmanship (3.5)

Source: https://assist.dla.mil -- Downloaded: 2026-10-18T02:46Z
Check the source to verify that this is the current version before use.

4.3.3.2 Classification of defects. (Continued.)

(d) Plug, pipe, headless (MS49005-8).

Categories	Defects
Critical:	None defined
Major:	AQL 1.0 percent defective
101	Thread incorrect
102	Length incorrect
103	Hexagon recess incorrect
104	Pitch diameter incorrect

(e) Collar, closure (Dwg B15-11-5).

Categories	Defects
Critical:	None defined
Major:	AQL 1.0 percent defective
101	Depth of basic pitch diameter incorrect
102	Thread incorrect
103	Thickness incorrect
104	Offset incorrect
105	Diameter (1.120-.010) incorrect
106	Workmanship (3.5)

(f) Preparation for delivery (section 5).

Categories	Defects
Critical:	None defined
Major:	AQL 1.0 percent defective
101	Incorrect quantities packaged or packed
102	Containers incorrect
103	Container damaged (broken, torn, crushed, punctured or wracked)
104	Marking missing, illegible or incorrect

Source: https://assist.dla.mil -- Downloaded: 2026-10-18T02:46Z
Check the source to verify that this is the current version before use.

4.3.4 Leakage test. The canister shall be subjected to the specified pressure and submerged in water containing a rust inhibitor and a wetting agent to prevent bubbles from clinging to the surface of the canister. The canister shall be submerged a minimum of 2 inches from the top of the canister to the surfaceof the water and held for 30 ± 2 seconds. Steady bubbling shall indicate leakage. The temperature of the water shall be approximately 10°F above ambient temperature.

5. PREPARATION FOR DELIVERY

5.1 Packing, level A. Six empty canisters shall be packed in a class 2, style optional nailed wood box, for a type 3 load, conforming to PPP-B-621. The internal box dimensions shall be 12-3/4 inches long by 8-5/8 inches wide by 13-3/8 inches high. The individual items shall be placed in a fiber tube 3-29/32 inches inside diameter by 13 inches long, conforming to type I, class 1 or 2, style A of PPP-T-495. As an alternate, the individual items may be placed in a full length open end, close fitting tube formed from paperboard conforming to type III, style 1 of PPP-P-291, with firmly taped seam using waterproof pressure sensitive tape conforming to class 3 of PPP-T-60. Filler pads fabricated from type CF or SF, weather resistant class fiberboard conforming to PPP-F-320 shall be placed between the sides, ends, top and bottom of the tubes and box. Additional filler pads shall be used as required to make a tight pack. The box shall be closed in conformance with the applicable requirements of PPP-B-621 using two flat steel straps 5/8 inch by 0.010 inch, type I, class C of QQ-S-781.

5.2 Marking. In addition to any special marking required by the contract or order, shipping containers shall be marked in accordance with Drawing D150-2-1.

6. NOTES

6.1 Intended use. The components covered by this specification are to be used in a projectile for spotting and as an antipersonnel weapon against enemy shore installations and targets.

6.2 Ordering data. Procurement documents should specify the following:

Source: https://assist.dla.mil -- Downloaded: 2026-10-18T02:46Z
Check the source to verify that this is the current version before use.

(a) The title, number and date of this specification.

(b) The type of canister required.

(c) Preproduction:

(1) Time allowed for supplier submission of samples for Government test and evaluation after award of contract.

(2) Name and address of test facilities and shipping instructions when testing is performed by the Government.

(3) Time required for the Government to notify the supplier whether or not to proceed with production.

Custodian:

Army - MU

Preparing activity:

Army - MU (EA)

Project No. 1320-A088

Source: https://assist.dla.mil -- Downloaded: 2026-10-18T02:46Z
Check the source to verify that this is the current version before use.