MILITARY SPECIFICATION

TELEPHONE CIRCUIT, LINE RELAY TA-452( )/GTA-14

This specification is approved for use by all Department and Agencies of the Department of Defense.

1. SCOPE

1.1 This specification covers one type of seize detector used between Common Battery (CB) or Local Battery (LB) subscribers and manual telephone switchboards; designated as Telephone Circuit, Line Relay TA-452( )/GTA-14.

2. APPLICABLE DOCUMENTS

2.1 The following documents, of the issue in effect on date of invitation for bids or request for proposal, form a part of this specification to the extent specified herein.

SPECIFICATIONS

FEDERAL

NN-P-71	Pallet, Material Handling, Wood, Stringer Construction
QQ-S-781	Strapping, Steel, Flat And Seals
PPP-B-585	Box, Wood, Wirebound
PPP-B-601	Box, Wood, Cleated Plywood
PPP-B-621	Box, Wood, Nailed And Lock Corner
PPP-B-636	Box, Shipping, Fiberboard
PPP-B-640	Box, Fiberboard, Corrugated, Triple-wall
PPP-F-320	Fiberboard, Corrugated And Solid, Sheet Stock, And Cut Shapes
PPP-P-291	Paperboard, Wrapping, Cushioning
PPP-S-760	Strapping, Nonmetalic
PPP-T-45	Tape, Gummed, Paper, Reinforced And Plan, For Sealing And Securing
PPP-T-76	Tape, Pressure-Sensitive Adhesive Paper, Water Resistant
PPP-T-97	Tape, Pressure-Sensitive Adhesive, Filament Reinforced

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T19:47Z
Check the source to verify that this is the current version before use.

SPECIFICATIONS (con't)

MILITARY

MIL-P-116	Preservation-packaging, Methods of
MIL-B-131	Barrier Materials, Water vaporproof, Flexible, Heat-sealable
MIL-D-3464	Dessicants, Activated, Bagged, Packaging Use And Static Dehumidification
MIL-P-11268	Parts, Materials, And Processes Used In Electronic Equipment
MIL-M-13231	Marking of Electronic Items
MIL-F-14072	Finish For Ground Signal Equipment
MIL-P-19644	Plastic Molding Material (Polystyrene Foam, Expanded Bead)
MIL-P-26514	Polyrethane Foam, Rigid or Plastic, For Packaging

STANDARDS

MILITARY

MIL-STD-105	Sampling Procedure And Tables For Inspection By Attributes
MIL-STD-129	Marking For Shipment And Storage
MIL-STD-202	Test Methods For Electronic And Electrical Component Parts
MIL-STD-252	Wired Equipment, Classification of Visual And Mechanical Defects
MIL-STD-454	Standard General Requirements for Electronic Equipment
MIL-STD-810	Environmental Test Methods

DRAWINGS

ELECTRONICS COMMAND

SC-A-46439	List of Accessories for Package Tester
SM-C-183246	Bell
DL-SM-B-444550	Telephone Circuit, Line Relay TA-452( )/GTA-14(V)
SM-D-444580	*Wiring Diagram* TA-452/GTA-14(V)

(Copies of documents required by contractors in connection with specific procurement functions should be obtained from the procurement activity or as directed by the contracting officer.)

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T19:47Z
Check the source to verify that this is the current version before use.

3. REQUIREMENTS

3.1 First Article. - When specified in the contract or purchase order, the contractor shall furnish First Article units in accordance with 4.3.

3.2 Construction. - The equipment shall be constructed in accordance with the requirements of this Specification and Drawing and Data List DL-SM-B-444550 (including the requirements for parts, materials and processes thereon) (See 4.4).

3.3 Parts, materials and processes; general. - In addition to the requirements of this specification, the requirements of MIL-P-11268, including the selection requirements therein, shall apply (See 4.4).

3.4 Finish. - The equipment shall be finished in accordance with MIL-F-14072 and the equipment drawings (See 4.4).

3.5 Marking. -

3.5.1 General. - Marking shall conform to MIL-M-13231. Front panel marking shall be Group I as described in that specification (See 4.4).

3.5.2 Visibility. - Wherever practicable, parts shall be so mounted that their identification markings will be readily visible with minimum disassembly of the equipment.

3.5.3 Serial numbers. - The equipment shall be serially numbered.

3.6 Interchangeability. - Like units, assemblies, subassemblies and replaceable parts shall conform to Requirement 7 of MIL-STD-454 (See 4.4).

3.7 Electrical. -

3.7.1 Insulation Resistance. - The resistance between circuits insulated from each other shall be 100 megohms minimum (See 4.6.1).

3.7.2 Relay Operation. - The equipment shall detect subscriber off-hook conditions on Common Battery (CB) lines with loop resistances of 0 to 1500 ohms with a leakage resistance from infinity to no less than 10,000 ohms. The equipment shall detect subscriber SEIZE signals of 90 v peak, 20 Hz square wave on Local Battery (LB) lines with loop resistances of 0 to 3500 ohms. Each circuit shall be selectable for operation in the CB and LB mode (See 4.6.2).

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T19:47Z
Check the source to verify that this is the current version before use.

3.7.3 Voltage.- The equipment shall operate with any supply voltage in the range of 44 to 58 volts direct current (DC) and meet the requirements of this specification (See 4.6.3).

3.8 Service Conditions. - The equipment shall meet the following service conditions and provide full specification performance during and after testing.

3.8.1 Temperature. -

3.8.1.1 Low. - When tested as specified in 4.7.1.1, the equipment shall meet the requirements of 3.7.2.

3.8.1.2 High. - When tested as specified in 4.7.1.2, the equipment shall meet the requirements of 3.7.2.

3.8.2 Humidity. - The equipment shall meet the requirements of 3.7.2 during the operating times specified in 4.7.2.

3.8.3 Bounce, vehicular. - When tested as specified in 4.7.3, the equipment shall meet the requirements of 3.7.2.

3.9 Workmanship. - The equipment shall be manufactured and assembled in accordance with Requirement 9 of MIL-STD-454 and the applicable portions of MIL-P-11268 (See 4.8).

4. QUALITY ASSURANCE PROVISIONS

4.1 Responsibility for Inspection. - Unless otherwise specified in the contract or purchase order, the contractor is responsible for the performance of all inspection requirements as specified herein. Except as otherwise specified in the contract or purchase order, the contractor may use his own or any other facilities suitable for the performance of the inspection requirements specified herein, unless disapproved by the Government. The Government reserves the right to perform any of the inspections set forth in the specification where such inspections are deemed necessary to assure supplies and services conform to prescribed requirements.

4.2 Classification of Inspections. - The inspection requirements specified herein are classified as follows:

a. First Article inspection. (See 4.3). Does not include preparation for delivery.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T19:47Z
Check the source to verify that this is the current version before use.

4.2 Classification of Inspections. (con't)

b. Inspections covered by subsidiary documents (See 4.4).

c. Quality conformance inspections.

(1) Quality conformance inspection of equipment before preparation for delivery (See 4.5).

(2) Quality conformance inspection of preparation for delivery (See 4.9).

4.3 First Article. - Unless otherwise specified in the contract or purchase order, the First Article inspection shall be performed by the contractor.

4.3.1 First Article units. - The contractor shall furnish two (2) First Article units of the complete Telephone Circuit, Line Relay TA-452( )/GTA-14.

4.3.2 First Article inspection. - The First Article inspection shall consist of the inspections specified in subsidiary documents covering the items listed in 4.4, and the inspections specified for Group A and Group C (See Tables II and III respectively). The inspection shall be performed in the following order: 4.4, Group A for all units; and Group C as specified in Table I. After completion of Group C environmental tests, conforming units shall be reinspected and shall pass all Group A inspection.

4.3.3 First Article data. - The First Article test plan and test report shall be as required in the contract or purchase order.

4.4 Inspections covered by subsidiary documents: The following shall be inspected under the applicable subsidiary documents as part of the inspection required by this specification, and the inspection requirement specified in the contract or purchase order.

Item	Where required
Construction	3.2
Parts, materials and processes-general	3.3
Finish	3.4
Marking	3.5
Interchangeability	3.6

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T19:47Z
Check the source to verify that this is the current version before use.

TABLE I

Order of Group C Tests

Inspection	Unit 1	Unit 2
Voltage		1
Temperature		
Low	1	
High	2	
Humidity	3	
Bounce, Vehicular		2

4.5 Quality conformance inspection of equipment before preparation for delivery - The contractor shall perform the inspection specified in 4.4, 4.5.1 through 4.5.4. This does not relieve the contractor of his responsibility for performing any additional inspection which is necessary to control the quality of the product and to assure compliance with all specification requirements.

4.5.1 Group A inspection. - Each unit on contract or purchase order shall be inspected for conformance to the inspections specified in Table II. Discrete lots shall be formed from units that pass this inspection. Factors of lot composition not defined herein or in the contract or purchase order, shall be in accordance with MIL-STD-105. Each lot shall be subject to sampling inspection, utilizing the procedures of MIL-STD-105, using the general inspection levels and AQLs indicated in Table II.

4.5.1.1 Order of inspection within Group A. - Group A inspection shall be performed in the order listed in Table II.

TABLE II

Group A Inspection

Inspection	Req Para	Test Para	AQL Major	AQL Minor
Visual-Mech	3.9	4.8	1%	4%
Insulation Res.	3.7.1	4.6.1	4.0 DPHU	
Relay Operation	3.7.2	4.6.2	4.0 DPHU	

NOTE: DPHU - Defects Per Hundred Units. Defects in all characteristics other than Visual and Mechanical are considered Major.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T19:47Z
Check the source to verify that this is the current version before use.

4.5.2 Group B inspection. - Not required.

4.5.3 Group C Inspection. - Group C inspection shall be performed on units that have passed Group A inspection. The inspection shall consist of the inspections specified in Table III. Samples shall be selected in accordance with 4.5.3.1.

4.5.3.1 Samples for Group C inspection. - Two units shall be selected at random for each inspection in Table III from every 100 units or fraction thereof produced. The first samples selected shall be at the start of the contract from the first quality conformance inspection production lot.

4.5.3.2 Order of inspection within Group C. - Group C inspection shall be performed in the order shown in Table I.

TABLE III

Group C Inspection

Inspection	Req Para	Test Para
Voltage	3.7.3	4.6.3
Temperature, Low	3.8.1.1	4.7.1.1
Temperature, High	3.8.1.2	4.7.1.2
Humidity	3.8.2	4.7.2
Bounce, Vehicular	3.8.3	4.7.3

4.5.3.3 Group C failures. - Actions required relative to Group C failures shall be as specified in the contract or purchase order.

4.5.4 Reinspection of Conforming Group C Sample Units. - Unless otherwise specified, sample units which have been subjected to and passed Group C inspection may be accepted on the contract provided all damage is repaired and the sample units are resubjected to and pass Group A and Group B inspection.

4.6 Electrical. -

4.6.1 Insulation Resistance. - Insulation resistance shall be measured in accordance with Method 302 of MIL-STD-202, Test potential of 200 vdc $\pm$ 10%, as follows.

a. No connection shall exist at the 48v power source receptacles during the test. Operate CB/LB switches to CB position.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T19:47Z
Check the source to verify that this is the current version before use.

4.6.1 Insulation Resistance. - (con't)

b. Apply test voltage between each pin of the 52 pin receptacle marked LINE 00-09 and chassis ground and measure insulation resistance for conformance to 3.7.1.

c. Pin numbers 1, 8, 11, 18, 22, 29, 32, 39, 43 and 50 will indicate a short. Manually operate relay CO and obtain reading.

d. Pin numbers 16 and 37 shall indicate short (normal).

e. Repeat for LINE receptacles 10-19, 20-29, 30-39, 40-49, 50-59, 60-69, 70-79, 80-89 and 90-99.

f. Apply test voltage between the Night Alarm (NA) terminal posts, with NA switch open, and measure insulation resistance for conformance to 3.7.1.

4.6.2. Relay operation. - Perform the following tests with 44 volts DC applied to the equipment power receptacle, the NA switch ON and a Bell (SM-C-183246) or equivalent device connected to the NA binding posts. Depress each fuse spring to make contact and verify that the alarm sounds.

4.6.2.1 Common Battery (CB) mode. - Operate all CB/LB switches to the CB position.

a. Terminate pins 1-2 of the MDF receptacle (circuit No. 00) with a 1500 ohm resistor. Relay LR shall operate, the NA shall sound and 44 volts DC shall appear across pins 4-16 of the LINE receptacle (circuit No. 00). Pin 3 of the LINE receptacle shall indicate open to ground. Operate NA switch off and on and verify operation of the switch.

b. Connect pin 5 of the LINE receptacle (circuit No. 00) to pin 16. Relay CO shall operate. Relay LR shall release, the NA shall cease and the 44 volts DC shall be removed from pin 4. The terminating resistor (1500 ohms) shall be measured across pins 1-2 of the LINE receptacle (circuit No. 00). Pin 3 of the LINE receptacle shall indicate a short to ground.

c. Repeat a and b above for circuits No. 01 to 99 (see Wiring Diagram SM-D-444580).

d. Repeat a above for circuits No. 00 to 99 except use a 10,000 ohm terminating resistor and a 58 VDC power supply voltage. Relay LR shall not operate.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T19:47Z
Check the source to verify that this is the current version before use.

4.6.2.1 Common Battery (CB) mode. (con't)

e. Repeat b above for circuits No. 00 to 99 except add a 2200 ohm series resistor (which will provide 20 ma to the coil of relay CO). Relay CO shall not operate.

4.6.2.2 Local Battery (LB). - Operate all CB/LB switches to the LB position.

a. Apply a 90 volt peak, 20 Hz square wave SEIZE signal with a 3500 ohm resistor in series to pins 1-2 of the MDF receptable (circuit No. 00) for two seconds. Relay LR shall operate and hold without chattering, the NA shall sound and 44 volts DC shall appear across pins 4-16 of the LINE receptacle (circuit No. 00). Pin 3 of the LINE receptacle shall indicate open to ground.

b. Connect pin 5 of the LINE receptacle (circuit No. 00) to pin 16. Relay CO shall operate. Relay LR shall release, the NA shall cease and the 44 volts DC shall be removed from pin 4. Pin 3 of the LINE receptacle shall indicate open to ground (no change).

c. Repeat a and b above for circuits No. 01 to 99.

d. Apply a short circuit to pins 1-2 of the MDF receptacle (circuit No. 00). Relay LR shall not operate. Repeat for circuits 01 to 99.

4.6.3 Voltage. - The tests of 4.6.2 shall be performed with a power supply voltage of 58 volts DC.

4.7 Service Conditions. -

4.7.1 Temperature. -

4.7.1.1 Low. - The equipment shall be tested in accordance with Method 502, Procedure I, of MIL-STD-810. The storage temperature shall be minus 80°F, maintained for four hours, and the operating temperature shall be plus 32°F. Prior to, during and following the test, the equipment shall meet the full specification performance of 3.7.2.

4.7.1.2 High. - The equipment shall be tested in accordance with Method 501, Procedure I, of MIL-STD-810. The storage temperature shall be 160°F, maintained for two hours, and the operating temperature shall be 125°F. Prior to, during and following the test, the equipment shall meet the full specification performance of 3.7.2.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T19:47Z
Check the source to verify that this is the current version before use.

4.7.2 Humidity. - The equipment shall be subjected to the humidity test specified in Method 507, Procedure II, of MIL-STD-810, with test measurements during Step 4 and the last 5-hour period of each 48-hour cycle in Step 6. Inability of the equipment to meet the requirements of 3.7.2 shall constitute failure of this test.

4.7.3 Bounce, vehicular. - The equipment shall be tested in accordance with Method 514, Procedure IX, Part 2, of MIL-STD-810. Prior to testing, the equipment shall meet full specification performance for the requirements of 3.7.1 and 3.7.2. When practicable, package tester accessories shall be selected from those listed on Drawing SC-A-46439. The adapter plate shall be free of cracks and broken welds, and all unused holes, except the 2-inch breather holes, shall be plugged. The equipment shall be braced from the top of the equipment to the adapter plate to maintain a 90° orientation with the adapter plate. No part of the mounted surface shall be less than 7 inches from the edge of the adapter plate. Neither the additional barriers used to safeguard personnel nor the braces shall restrain the fore-and-aft motion of the adapter plate against the backstop.

4.8 Visual and Mechanical. - The equipment shall be examined for conformance to Requirement 9 of MIL-STD-454 and applicable portions of MIL-P-11268 and for defects listed in MIL-STD-252.

4.9 Quality conformance inspection of preparation for delivery. - Preparation for delivery shall be inspected in accordance with MIL-P-116 to determine conformance to the requirements of Section 5.

4.10 Rough handling test (preparation for delivery). - When rough handling test in accordance with MIL-P-116 is required by the contract, the functional tests of 4.6.2.1 shall be conducted to determine freedom from operational malfunction caused by rough handling.

5. PREPARATION FOR DELIVERY

5.1 Preservation and packaging. Preservation and packaging shall be Level A or C, as specified (See (6.2.b).

5.1.1 Level A.

5.1.1.1 Cleaning. - Telephone Circuit, Line Relay TA-452/GTA-14 shall be cleaned in accordance with process C-1 of MIL-P-116.

5.1.1.2 Drying. - Telephone Circuit, Line Relay TA-452/GTA-14 shall be dried in accordance with the applicable procedure of MIL-P-116.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T19:47Z
Check the source to verify that this is the current version before use.

5.1.1.3 Preservation application. None required.

5.1.1.4 Unit packaging. - Unit packaging shall be in accordance with the methods prescribed in MIL-P-116 as specified herein.

5.1.1.4.1 *Technical literature.* - *Each technical literature shall be packaged* method IC-1.

5.1.1.4.2 Telephone Circuit, Line Relay TA-452/GTA-14. - Each Telephone Circuit shall be individually packaged method II-b as follows: Cushion the Telephone Circuit on all surfaces with cells or pads or both fabricated of fiberboard conforming to PPP-F-320, type CF, class domestic, variety SW, grade 200, designed to protect all projections and absorb the shock of impact in handling and transit. As an alternate, cushioning material may be fabricated of plastic molding material conforming to MIL-P-19644 or polyurethane foam conforming to MIL-P-26514. Place the cushioned unit within a close-fitting fiberboard box conforming to PPP-B-636, type CF, class domestic, variety SW, grade 275. Place dessicant conforming to MIL-D-3464, in the amount specified in MIL-P-116, but without direct contact with the Voltmeter, in the appropriate voids within the box. Fill balance of voids with paperboard conforming to PPP-P-291, type I, to prevent movement during handling and transit. Close the box with tape conforming to PPP-T-45, type III, grade A. Blunt all corners of the box and cover any exterior stapling or stitching with the same type tape. Place the closed box within a barrier bag fabricated of material conforming to MIL-B-131, class 1, with sufficient allowance in one direction to permit two subsequent resealings. Heat seal the closure, leaving a small opening for exhausting the air. Exhaust the entrapped air and complete the seal. Place the sealed bag with contents within a close-fitting fiberboard box conforming to PPP-B-636, W6c. Cover any interior stapling or stitching of the box with tape conforming to PPP-T-45, type III, grade A. Place the technical literature, packaged as specified in 5.1.1.4.1, on top of the contents, directly under the lid of the box. Close the box in accordance with the appendix of the box specification.

5.1.2 Level C. - Telephone Circuit, Line Relay TA-452/GTA-14 shall be preserved and packaged in a manner that will afford adequate protection against physical and environmental damage during shipment, handling and limited intransit storage.

5.2 Packing. - Packing shall be level A, B or C as specified. Shipping containers for all levels shall be capable of stacking and supporting superimposed loads during shipment and storage without damaging the container(s) or its contents.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T19:47Z
Check the source to verify that this is the current version before use.

5.2.1 Level A. - A quantity of Telephone Circuit, Line Relay TA-452/GTA-14, packaged as specified in 5.1 shall be packed within a close-fitting box conforming to PPP-B-601, overseas type; PPP-B-621, style 4, class 2; or PPP-B-585, style 2 or 3, class 3. Fiberboard boxes being placed directly in the shipping container shall be waterproofed with tape conforming to PPP-T-76, in accordance with the taping requirements of the appendix of the box specification. When the gross weight exceeds 200 pounds, or the container length and width is 48 x 24 inches or more and the weight exceeds 100 pounds, 3 x 4 inch skids, laid flat, shall be applied in accordance with the requirements of the container specification, or if not specified in the specification, in a manner which will adequately support the item and facilitate the use of material handling equipment. Closure and strapping shall be in accordance with the applicable container specification or appendix thereto except that metal strapping shall conform to QQ-S-781, type 1, Finish A.

5.2.2 Level B. - A quantity of Telephone Circuit, Line Relay TA-452/GTA-14, packaged as specified in 5.1, shall be packed within a close-fitting box conforming to PPP-B-601, domestic type; PPP-B-621, style 4, class 1; PPP-B-585, style 2 or 3, class 3; PPP-B-640, class 2, style E; or PPP-B-636, type CF, class weather-resistant. The gross weight of boxes conforming to PPP-B-640 shall not exceed 250 pounds. When the gross weight of wood boxes exceeds 200 pound, or the container length and width is 48 x 24 inches or more and the weight exceeds 100 pounds, 3x4 inch skids, laid flat, shall be applied in accordance with the requirements of the container specification, or if not specified in the specification, in a manner which will adequately support the item and facilitate the use of material handling equipment. When the gross weight of fiberfoard boxes exceeds 200 pounds, or the container length and width is 48 x 24 inches or more and the weight exceeds 100 pounds, containers will be pallet-mounted on pallets conforming to NN-P-71, type IV. Closure and strapping or reinforcing shall be in accordance with the applicable container specification or appendix thereto except that fiberboard shipping containers shall be reinforced by pressure-sensitive filament tape banding or nonmetallic strapping conforming to PPP-T-97, type IV and PPP-S-760, type II, respectively; selection of the material and application shall be in accordance with the appendix of the applicable box specification.

5.2.3 Level C. - Telephone Circuit, Line Relay TA-452/GTA-14, packaged as specified in 5.1, shall be packed in shipping containers that comply with Federal or Military specifications, in a manner that will afford adequate protection to the package and its contents against physical and environmental deterioration and damage, during limited shipment, handling and intransit storage.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T19:47Z
Check the source to verify that this is the current version before use.

5.3 Marking. - In addition to any special marking required by the contract or order, interior packages and exterior shipping containers shall be marked in accordance with MIL-STD-129.

6. NOTES

6.1 Intended use. - Telephone Circuit, Line Relay TA-452( )GTA-14 is part of Manual Telephone Central Office equipment installed in mobile shelter configurations. It provides SEIZE detection of up to 100 Common Battery (CB) or Local Battery (LB) subscriber circuits. It requires a nominal 48 vdc power source. It interfaces on the subscriber side with the Main Distributing Frame (MDF) through four 52-pin connectors and to the switchboard (LINE) side through ten 52-pin connectors. System considerations are described in Department of the Army Technical Manual TM 11-2146.

6.2 Ordering Data. - Procurement documents should specify the following:

a. Title, number, date of this specification and any amendment thereto.

b. Levels of preservation and packaging and packing (See section 5).

c. When rough handling test is required.

d. The number of First Article samples required.

e. Technical literature required.

f. Quantity of running spare parts.

6.3 Nomenclature. - The parentheses in the nomenclature will be deleted or replaced by a letter identifying the particular design; for example: TA-452W/GTA-14. The contractor should apply for nomenclature in accordance with the applicable clause in the contract.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T19:47Z
Check the source to verify that this is the current version before use.

6.4 Verification inspection. - Verification by the Government will be limited to amount deemed necessary to determine compliance with the contract and will be limited in severity to the definitive quality assurance provisions established in this specification and the contract. The amount of verification inspection by the Government will be adjusted to make maximum utilization of the contractor's quality control system and the quality history of the product.

Custodian:

Army - (EL)

Preparing Activity

Army - (EL)

Project No. 5805-A230

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T19:47Z
Check the source to verify that this is the current version before use.

FOLD

Department of the Army
Headquarters
U.S.Army Electronics Command
Fort Monmouth, New Jersey 07703

POSTAGE AND FEES PAID

OFFICIAL BUSINESS

Commanding General
U.S.Army Electronics Command
ATTN: AMSEL- RD-TS
Fort Monmouth, New Jersey 07703

FOLD

To detach this form, cut along this line

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T19:47Z
Check the source to verify that this is the current version before use.

SPECIFICATION ANALYSIS SHEET

Form Approved
Budget Bureau No. 22-R255

INSTRUCTIONS: This sheet is to be filled out by personnel, either Government or contractor, involved in the use of the specification in procurement of products for ultimate use by the Department of Defense. This sheet is provided for obtaining information on the use of this specification which will insure that suitable products can be procured with a minimum amount of delay and at the least cost. Comments and the return of this form will be appreciated. Fold on lines on reverse side, staple in corner, and send to preparing activity. Comments and suggestions submitted on this form do not constitute or imply authorization to waive any portion of the referenced document(s) or serve to amend contractual requirements.

SPECIFICATION MIL-T-49081(EL) TELEPHONE CIRCUIT, LINE RELAY TS-452()/GTS-14

ORGANIZATION

CITY AND STATE

CONTRACT NUMBER

MATERIAL PROCURED UNDER A

☐ DIRECT GOVERNMENT CONTRACT ☐ SUBCONTRACT

1. HAS ANY PART OF THE SPECIFICATION CREATED PROBLEMS OR REQUIRED INTERPRETATION IN PROCUREMENT USE?

A. GIVE PARAGRAPH NUMBER AND WORDING.

B. RECOMMENDATIONS FOR CORRECTING THE DEFICIENCIES

2. COMMENTS ON ANY SPECIFICATION REQUIREMENT CONSIDERED TOO RIGID

3. IS THE SPECIFICATION RESTRICTIVE?

☐ YES ☐ NO *(If "yes", in what way?)*

4. REMARKS *(Attach any pertinent data which may be of use in improving this specification. If there are additional papers, attach to form and place both in an envelope addressed to preparing activity)*

SUBMITTED BY *(Printed or typed name and activity - Optional)*

DATE

DD FORM 1 JAN 66 1426

REPLACES EDITION OF 1 OCT 64 WHICH MAY BE USED.

ESC-FM 1068-68

To detach this form, cut along this line

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T19:47Z
Check the source to verify that this is the current version before use.