MILITARY SPECIFICATION

TEST SET, ELECTRICAL CIRCUIT, M40E1 PARTS FOR, ASSEMBLING AND PACKING

1. SCOPE

1.1 This specification covers the parts, assembling and packing for one type of test set designated as Test Set, Electrical Circuit, M40E1.

2. APPLICABLE DOCUMENTS

2.1 The following documents of the issue in effect on date of invitation for bids or request for proposals, form a part of this specification to the extent specified herein.

SPECIFICATIONS

FEDERAL

PPP-B-636 - Boxes, Fiber

MILITARY

MIL-A-2550 - Ammunition and Special Weapons; General Specification for.

STANDARDS

MILITARY

MIL-STD-105 - Sampling Procedures and Tables for Inspection by Attributes (ABC-STD-105)
MIL-STD-109 - Quality Assurance Terms and Definitions
MIL-STD-1168 - Lot Numbering of Ammunition
MIL-STD-1169 - Packaging, Packing and Marking for Shipment of Inert Ammunition Components

Source: https://assist.dla.mil -- Downloaded: 202610-22T19:18Z
Check the source to verify that this is the current version before use.

MIL-STD-1235 - Single and Multilevel Continuous Sampling Procedures and Tables for Inspection by Attributes

DRAWINGS

U.S. ARMY MUNITIONS COMMAND

9272546 - Test Set, Electrical Circuit, M40E1

(Copies of specifications, standards and drawings required by suppliers in connection with specific procurement functions should be obtained from the procuring activity or as directed by the contracting officer).

3. REQUIREMENTS

3.1 Material.-Materials, parts and assemblies shall be in accordance with applicable drawings and specifications.

3.2 Test sets.-The test sets shall comply with all requirements specified on drawing 9272546 and with all requirements specified in applicable specifications.

3.3 Five foot drop.-Test sets shall show no evidence of cracking or separating after being subjected to the five foot drop test and shall function satisfactorily.

3.4 Wiring.-The distance between any portion of the bulb circuit and any portion of the resistor circuit shall be not less than 1/8 inch.

3.5 Functioning of Test Set.- The test set shall function satisfactorily as evidenced by a flash of the lamp with the output terminals connected to a dummy load, and by no flash of the lamp with the output terminals open.

3.6 Functioning of lamp.-The lamp (see dwg. 9275725) shall function satisfactorily and shall not blow out when connected in series with a fifteen (15) ohm resistor.

Source: https://assist.dla.mil -- Downloaded: 202610-22T19:18Z
Check the source to verify that this is the current version before use.

3.7 Workmanship.-All parts and assemblies shall be fabricated and finished in a thorough workmanlike manner. They shall be free of burrs, chips, sharp edges, cracks, crazes, unblended radii, porosity, warpage, burn marks, checks, chipped edges, blisters, excess flash, dirt, grease, rust, salt deposits, visible raised cement seams, solder splash, corrosion products, and other defects and foreign matter which would affect their serviceability. The cleaning method used shall not be injurious to any part nor shall the parts be contaminated by the cleaning agent. All required markings shall be neat and sharply defined.

3.8 First article inspection.-This specification makes provisions for first article inspection. Requirements for the submission of first article samples by the contractor shall be as specified In the contract.

4. QUALITY ASSURANCE PROVISIONS

4.1 Responsibility for Inspection.-Unless otherwise specified In the contract or purchase order, the supplier is responsible for the performance of all inspection requirements as specified herein. Except as otherwise specified in the contract or order, the supplier may use his own or any other facilities suitable for the performance of the inspection requirements specified herein, unless disapproved by the Government. The Government reserves the right to perform any of the inspections set forth in the specification where such inspections are deemed necessary to assure supplies and services conform to prescribed requirements. Reference shall be made to MIL-STD-109 to define terms used herein. The provisions of MIL-A-2550 shall apply.

4.1.1 Submission of Product.-At the time each completed lot of items deliverable under the contract is submitted to the Government for acceptance, the contractor shall supply the following information accompanied by a certificate which attests that the Information provided is correct and applicable to the product being submitted.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T19:18Z
Check the source to verify that this is the current version before use.

a. A statement that the lot complies with all of the quality assurance provisions specified in this specification.
b. Drawing and specification number and date, together with identification and date of changes thereto.
c. A statement that all material purchased by the contractor meets requirements, when such material is controlled by Government or commercial specifications referenced in any of the contractual documents, and that certificates of conformance are on file and available for review.
d. Number of items in the lot.
e. Date submitted.

The certificate shall be signed by a responsible agent of the certifying organization. The initial certificate submitted shall be substantiated by evidence of the agent's authority to bind his principal. Substantiation of the agents authority will not be required with subsequent certificates unless, during the course of the contract, this authority is vested in another agent of the certifying organization.

4.2 First Article Inspection

4.2.1 Submission.-Prior to the start of regular production the contractor shall submit a first article sample (see 6.1c) to a Government approved facility as designated by the contracting officer for evaluation in accordance with the provisions of 4.2.2 and 4.2.3. The first article sample shall consist of inert parts, sub-assemblies and assemblies, including at least three (3) items from each cavity used to produce plastic parts and be so identified as to permit tracing each item to the cavity in which it was molded) which have been produced by the contractor or furnished by a supplier and which have been manufactured using the same production processes, procedures and equipment which will be used in fulfilling the contract. All parts and materials including packaging and packing shall be obtained from the same source of supply as will be used in regular production. Prior to submission, the contractor shall inspect the sample to the degree necessary to assure that it conforms to the requirements of the contract and submit a record of this inspection with the sample, including a certificate of conformance for materials. A sample containing known defects will not be submitted unless specifically authorized by the Contracting Officer. A first article sample,

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T19:18Z
Check the source to verify that this is the current version before use.

or portion thereof, as directed by the Contracting Officer, shall also be submitted whenever there is a lapse in production for a period in excess of 90 days or whenever a change occurs in manufacturing process, material used, drawing or specification such as to significantly affect product uniformity as determined by the Government.

4.2.2 First article inspection provisions.

4.2.2.1 Component parts and subassemblies.-Twenty five (25) complete sets of parts (i.e. 25 each of every component parts and subassembly, including at least three (3) Items from each cavity used to produce plastic parts and so identified as to permit tracing each item to the cavity in which it was molded).

4.2.2.1.1 Inspections to be performed.-The parts and subassemblies will be subjected by the Government to any or all of the applicable examinations and tests specified in 4.3.2, 4.3.3 and 4.3.5 of this specification and any or all of the requirements of the applicable drawings.

4.2.2.1.2 Inspections to be performed.-The parts and subassemblies will be subjected by the Government to any or all of the applicable examinations and tests specified in 4.3.2, 4.3.3 and 4.3.5 of this specification and any or all of the requirements of the applicable drawings.

4.2.2.1.3 Rejection.-If any component or subassembly fails to comply with any of the applicable requirements, the first article sample shall be rejected. The Government reserves the right to terminate its inspection upon any failure of a component or subassembly to comply with any of the stated requirements.

4.2.2.2 Test set assemblies.-Thirty (30) test sets completely packaged and sealed as required by the applicable drawings.

4.2.2.2.1 Inspections to be performed.-The thirty (30) test sets shall be subjected to the following tests in the sequence indicated in addition to the inspections specified In 4.3.2.9:

a. Functioning (see 3.5) in accordance with 4.4.2.
b. Five foot drop test (see 3.3) in accordance with 4.4.3.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T19:18Z
Check the source to verify that this is the current version before use.

4.2.2.2.2 Rejection. -If any test set fails to comply with any of the applicable requirements, the first article sample shall be rejected. The Government reserves the right to terminate its inspection upon any failure of the test set to comply with any of the stated requirements.

4.3 Inspection provisions

4.3.1 Lot formation.-The term “inspection lot” as used in this specification is defined as an essentially homogeneous collection of units of product from which a representative sample is drawn and inspected to determine conformance with applicable requirements. The sample selected shall represent only that quantity of units from which the sample was drawn and shall not be construed to represent any prior or subsequent quantities presented for inspection. Homogeneity shall be considered to exist provided the inspection lot has been produced by one manufacturer in one unchanged process using the same materials and methods in accordance with the same drawings, same drawing revisions, same specifications and same specification revisions and complies with the provisions for submission of product as specified in MIL-STD-105. Changes to the process, specifications, or drawings not affecting safety, performance, interchangeability, or storage, as determined by the Government, shall not be deemed to alter the homogeneity of an inspection lot. All material submitted for inspection in accordance with this specification shall comply with the homogeneity criteria specified herein regardless of the type of sampling procedure which is being applied to determine conformance with requirements. Lot numbering, as required, shall be in accordance with MIL-STD-1168, Each inspection lot of test sets shall contain parts from not more than one lot interfix number from one manufacturer.

4.3.2 Examination.-The examinations listed in the following subparagraphs shall be performed on inspection lots (see 4.3.1) Of the components or assemblies designated in the applicable paragraph headings. Inspection for critical defects (and major defects, when so specified) shall be 100 percent. Sampling plans for major and minor defects shall be in accordance with MIL-STD-105 except that continuous sampling plans in accordance with MIL-STD-1235 may be used if approved by the Government. Instead of applying the AQL’s designated herein to the groups of major and minor defects listed, the contractor may elect to apply AQL’s to individual defects using an AQL of 0.40 percent for each major defect and an AQL of 0.65 percent for each minor. defect. When this method is elected, it shall be applied to all of the major and

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T19:18Z
Check the source to verify that this is the current version before use.

minor defects listed in the applicable subparagraphs of this section, except where 100 percent inspection is specified, and be documented as part of the contractor's inspection system. Equipment necessary for the performance of the inspections listed shall be in accordance with 4.3.4.

4.3.2.1 Connector assembly, male (see dwg. 9272095 covering a detail. of dwg. 9272546).

Categories	Defects	Method of Inspection	Code No.
Critical:	None defined		
Major:	AQL 0.65 percent		
101.	Component improperly assembled, damaged, loose or missing	Visual	01001
102.	Clip ends not secure	Manual	01002
103.	Clip base not flat or not seated	Visual	01003
104.	Presence of rubber or other foreign material on contacts	Visual	01004
Minor:	AQL 0.65 percent		
201.	Evidence of poor workmanship (see 3.7)	Visual	01005

4.3.2.2 Connector assembly, female (see dwg. 9272147 covering a detail of dwg. 9272546).

Categories	Defects	Method of Inspection	Code No.
Critical:	None defined		
Major:	AQL 0.40 percent		
101.	Component improperly assembled, damaged, loose or missing	Visual	02001
102.	Presence of rubber or other foreign material on contacts	Visual	02002

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T19:18Z
Check the source to verify that this is the current version before use.

Minor:	AQL 0.65 percent	
201.	Evidence of poor workmanship (see 3.7).....	Visual

4.3.2.3 Case (see dwg. 9270796 covering a detail of dwg. 9272546).

Categories	Defects	Method of Inspection	Code No.
Critical:	None defined		
Major:	AQL 0.40 percent		
101.	Crack or poor weld line.....	Visual	03001
102.	Alignment of mating surfaces over maximum (max).....	Visual	03002
Minor:	AQL 0.65 percent		
201.	Evidence of poor workmanship (see 3.7).....	Visual	03003

4.3.2.4 Prong (see dwg. 9268999 covering a detail of dwg. 9272095).

Categories	Defects	Method of Inspection	Code No.
Critical:	None defined		
Major:	AQL 1.0 percent		
101.	Length.....	Gage	04001
102.	Prong end length.....	Gage	04002
103.	Prong end diameter.....	Gage	04003
104.	Diameter "A".....	Gage	04004
105.	Knurl missing or inadequate.....	Visual	04005
Minor:	AQL 1.5 percent		
201.	Hole "A" depth.....	Gage	04006
202.	Body length.....	Gage	04007
203.	Diameter "B".....	Gage	04008
204.	Evidence of poor workmanship (see 3.7).....	Visual	04009

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T19:18Z
Check the source to verify that this is the current version before use.

4.3.2.5 Contact, female prior to pinch (see dwg. 9283958 covering a detail of dwg. 9272147).

Categories	Defects	Method of Inspection	Code No.
Critical:	None defined		
Major:	AQK 1.0 percent		
101.	Length	Gage	05001
102.	Front hole diameter	Gage	05002
103.	Diameter "A"	Gage	05003
104.	Slot length	Gage	05004
105.	Entrance radius missing	Visual	05005
106.	Knurl missing or inadequate	Visual	05006
Minor:	AQL 2.5 percent		
201.	Front hole depth	Gage	05007
202.	Hole "A" depth	Gage	05008
203.	Body length	Gage	05009
204.	Diameter "B"	Gage	05010
205.	Evidence of poor workmanship (see 3.7)	Visual	05011

4.3.2.6 Contact, female (see dwg. 9283958 covering a detail of dwg. 9272546).

Categories	Defects	Method of	Code No. Inspection
Critical:	None defined		
Major:	AQL 0.40 percent		
101.	Front hole diameter	Gage	06001
Minor:	AQL 0.65 percent		
201.	Evidence of poor workmanship (see 3.7)	Visual	06002

4.3.2.7 Case and connector assembly (see dwg. 9272547 covering a detail of dwg. 9272546).

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T19:18Z
Check the source to verify that this is the current version before use.

Categories	Defects	Method of Inspection	Code No.
Critical: None defined			
Major:	AQL 0.65 percent		
101.	Component improperly assembled, damaged, loose or missing.....	Visual	07001
102.	Wiring too close (see 3.4).....	Visual	07002
103.	Solder or crimp incorrect (as applicable).....	Visual	07003
104.	Adhesive on opening.....	Visual	07004
Minor:	AQL 0.65 percent		
201.	Evidence of poor workmanship (see 3.7).....	Visual	07005

4.3.2.8 Bulb and vial assembly (see dwg. 9272072 covering a detail of dwg. 9272546).

Categories	Defects	Method of Inspection	Code No.
Critical: None defined			
Major:	AQL 0.40 percent		
101.	Component improperly assembled, damaged, loose or missing.....	Visual	08001
Minor:	AQL 0.65 percent		
201.	Evidence of poor workmanship (see 3.7).....	Visual	08002

4.3.2.9 Test set, M40 (see dwg. 9272546).

Categories	Defects	Method of Inspection	Code No.
Critical: None defined.			
Major:	AQL 0.40 percent		
101.	Component improperly assembled, damaged, loose, or missing.....	Visual	09001
102.	Evidence of insufficient potting (not flush).....	Visual	09002

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T19:18Z
Check the source to verify that this is the current version before use.

Categories	Defects	Method of Inspection	Code No.
Minor:	AQL 1.5 percent		
201.	Marking misleading or unidentifiable.....	Visual	09003
202.	Gap greater than 0.015 inch, or foam does exude between case halves.....	Gage-Visual	09004
203.	Evidence of poor workmanship (see 3.7).....	Visual	09005

4.3.2.10 Carton, sealed (see section 5).

Categories	Defects	Method of Inspection	Code No.
Critical:	None defined.		
Major:	AQL 0.40 percent		
101.	Assembly damaged so that contents are exposed or liable to become exposed.....	Visual	10001
102.	Sealing strip incomplete, badly wrinkled, or not in full contact with surface around entire carton.....	Visual	10002
Minor:	AQL 1.0 percent		
201.	Contents move when carton is shaken.....	Manual	10003
202.	Marking misleading or unidentifiable.....	Visual	10004

4.3.3 Testing

4.3.3.1 Resistance of resistor - Major Defect - Code No. 11001 (see dwg. 9270785).-Fifty (50) resistors shall be selected from each lot for test. The lot shall be rejected if any resistor fails to comply with the requirements. The test shall be performed as specified In 4.4.1 using test equipment in accordance with 4.3.4. (non-destructive).

4.3.3.2 Functioning of test set - Major Defect - Code No. 11002.-This test shall be performed 100 percent. Any test set which fails to comply with the requirements shall be classed defective and removed from the lot. The test shall be performed as specified in 4.4.2 using test equipment in accordance with 4.3.4, and optional equipment of 6.4. (Non-Destructive).

Source: https://assist.dla.mil -- Downloaded: 202610-22T19:18Z
Check the source to verify that this is the current version before use.

4.3.3.3 Five foot drop - Major Defect - Code No. 11004 (see 3.3).-Fifty (50) test sets shall be selected from each lot for test. The lot shall be rejected if any test set fails to comply with the requirements. The test shall be performed as specified in 4.4.3 using test equipment in accordance with 4.3.4. (Non-destructive)

4.3.3.4 Load test - Major Defect - Code No. 01006 (male connector dwg. 9272095 - Code No. 02004 (female connector dwg. 9272147).-Fifty (50) connectors of each type shall be selected from each lot for test. The lot shall be rejected if any connector fails to comply with the requirements. The test shall be performed as specified in 4.4.4 using test equipment in accordance with 4.3.4. (Non-destructive)

4.3.3.5 Pull test of crimped prong and contact connections - Major Defect - Code No. 11005 (see dwg. 9272547).-A sample of at least 5 of each prong and each contact shall be crimped with a one-foot length of the appropriate gauge of solid copper wire and tested as specified in 4.4.5 to qualify new or adjusted crimping equipment for use in production or as a control of the equipment during production. Testing for control of crimping equipment during production shall be performed on the above quantity of samples from each crimping machine beginning with the samples crimped at the start of regular production and at the end of each continuous production run of four hours or less. If any defective crimp is found when testing is performed for control of the equipment, the equipment producing the defective crimp shall be removed from production. Further, that portion of production since the last control check shall be returned to the contractor for testing, according to MIL-STD-105, Code Letter G, AQL 1.5 percent. All equipment formerly removed from production because of some fault may, after correction, be returned to production providing they pass the qualification test

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T19:18Z
Check the source to verify that this is the current version before use.

above. The contractor may request a change of testing frequency providing he presents objective evidence to the Contracting Officer to substantiate the request. Test equipment shall be in accordance with 4.3.4. (Destructive Test)

4.3.3.6 Resistance of lamp - Major Defect - Code No. 11006 (see dwg. 9275725).-One hundred and twenty five (125) lamps shall be selected from each lot for test. The lot shall be rejected if two or more lamps fail to comply with the requirements. The test shall be performed as specified in 4.4.6 using test equipment in accordance with 4.3.4. (Non-destructive)

4.3.3.7 Functioning of lamp - Major Defect - Code No. 11007 (see 3.6).-Eighty (80) lamps shrill be selected at random from each lot of lamps for this test. The lot of lamps shall be rejected if one or more lamps fail to comply with the requirements. The test shall be performed as specified in 4.4.7 using test equipment in accordance with 4.3.4. (Destructive Test)

4.3.4 Inspection Equipment .-Inspection equipment required to perform the inspections prescribed in this specification is identified in the Examination (4.3.2) and Test Method (4.4) paragraphs herein. See 6.3 for details concerning responsibilities for inspection design and approval.

4.3.5 Dimensional control of molded parts.-In place of normal sampling and inspections associated with the Classification of Defects, and after a curing time for the parts has been approved (see Note 2) a sample of three (3) parts (as molded) from each cavity shall be fully inspected dimensionally to qualify a new or reworked cavity for use in production. The molded parts shall carry the individual cavity identification. As a control of' each cavity during production, the above quantity of parts from each cavity shall be inspected for at least the defects listed in paragraphs 4,3.5.1 through 4.3.5,3 after continuous production of each 5,000 parts or at the end of each week, whichever occurs first. Of the three (3) samples, one (1) sample shall be the last part produced. If any defective parts are found during qualification of the cavity, the cavity producing the defective part will not be used in production. If any defective parts are found when inspection is performed for the control of the cavity, the cavity producing the defective part

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T19:18Z
Check the source to verify that this is the current version before use.

shall be removed from production. Further, that portion of production since the last control check shall be returned to the contractor for inspection for each separate type of defect according to MIL-STD-105, using an AQL of 0.40 percent for each major defect and an AQL of 0.65 percent for each minor defect. All cavities removed from production because of some fault, may after reworking, be returned to production providing they pass the qualification test above. The contractor may request a change of inspection frequency providing he presents objective evidence to the contracting officer to substantiate the request. Contractor design of gages and test equipment required to perform the inspections listed herein shall be forwarded to Commander, Picatinny Arsenal, Dover, New Jersey 07801, ATTN: SARPA-QA-A-M for approval prior to manufacture of equipment. The noted subparagraphs identify those items and minimum inspections subject to the requirements of this paragraph.

NOTE 2. - In establishing a curing times, dimensionally check ten (10) parts from each cavity at periodic intervals (e.g. every 30, 60, etc. mins.) until dimensional stability is attained. The curing time will be from the time the part comes out of the mold until dimensional stability is attained. The inspection data used in determining the curing time shall be sent to Picatinny Arsenal, Dover, New Jersey 07801 ATTN: SARPA-QA-A-M. If any new change in material, cycle time, a reworked cavity, or a new cavity is used, a new curing time shall be established and approved.

4.3.5.1 Connector, male (see dwg. 9272095 covering a detail of dwg. 9272546).

Categories	Defects	Method of Inspection	Code No.
Critical:	**None defined**		
Major:			
101.	**Prong c-to-c distance.....**	**Gage**	**12001**
102.	**Cap does not fit securely.....**	**Manual**	**12002**
103.	**Depth to prong tips.....**	**Gage**	**12003**
Minor:	**None defined.**		

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T19:18Z
Check the source to verify that this is the current version before use.

4.3.5.2 Connector, female (see dwg. 9272147 covering a detail of dwg. 9272546).

Categories	Defects	Method of Inspection	Code No.
Critical: None defined			
Major:			
101.	Depth to contact tops.....	Gage	13004
102.	Contact c-to-c distance.....	Gage	13001
103.	Front hole entrance diameter of contacts.....	Gage	13002
104.	Cap does not fit securely.....	Manual	13003
Minor: None defined.			

4.3.5.3 Case (see dwg. 9270796 covering a detail of dwg. 9272546).

Categories	Defects	Method of Inspection	Code No.
Critical: None defined			
Major:			
101.	Evidence of mold wear or shifting.....	Visual	14001
102.	Counterbore diameter undersize.....	Gage	04002
103.	Marking missing or unidentifiable..	Visual	14003
Minor: None defined.			

4.4 Test methods and procedures

4.4.1 Resistance.-The resistance of the resistor shall be measured using an ohmeter. Observation shall be made for compliance with the applicable drawing requirements.

4.4.2 Functioning.-The test set shall be connected to a pulse generator and functioned at the twenty seven (27) milliwatt second energy position. The lamp shall be observed for compliance with the applicable requirement.

4.4.3 Five foot drop.-The test set shall be examined for any evidence of cracking or separation of parts after being

Source: https://assist.dla.mil -- Downloaded: 202610-22T19:18Z
Check the source to verify that this is the current version before use.

dropped from a height of 5 plus or minus 0.25 feet onto a 2 inch thick pine plank. The test set shall then be functioned in accordance with 4.4.2 and checked for compliance with the specified requirements.

4.4.4 Load test of male and female connectors.-With the connector held securely in a tensile testing machine, the required force shall be applied at the crimping end of each prong and contact separately with a speed of head travel of 1 inch per minute maximum. Observation shall be made for compliance with the specified requirements.

4.4.5 Pull test of crimped prong and contact connections.-The prong and contact connections shall be placed in a tensile testing machine and sufficient force applied to pull the wire out of the sample or break the wire. The test shall be conducted with a speed of head travel of 1 inch per minute maximum. Observation shall be made for compliance with the specified requirements.

4.4.6 Resistance of the lamp. -The resistance of the lamp shall be measured using an ohmeter. Observation shall be made for compliance with the applicable drawing requirement.

4.4.7 Functioning of lamps.-The lamps shall be tested prior to assembly in the test set. The lamp shall be connected in series to a fifteen (15) ohm resistor, plus or minus 10 percent, then connected to a pulse generator and functioned at the twenty seven (27) milliwatt second energy level for one hundred (100) consecutive pulses. The lamp shall be observed for compliance with the specified requirement. Lamps subjected to this test shall not be returned to the lot.

5. PREPARATION FOR DELIVERY

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T19:18Z
Check the source to verify that this is the current version before use.

5.1 Packing

5.1.1 Level C.-Two hundred (200) test sets shall be packed in a fiberboard box complete with plain fiberboard pads. A fiberboard pad shall be placed on the bottom of the box. The test sets shall be positioned in the box, flat side down, in a 2 by 10 pattern - 20 sets per layer; 10 layers per box. A plain pad shall be placed between each layer of sets and on the top layer. Additional pads shall be added as required for a tight pack. The box shall conform to PPP-B-636 for a Type CF, Class Domestic, Variety SW, Grade 200. The plain pads shall be constructed of the same test fiberboard as the box. Box size shall be approximately 10 by 9 3/4 by 17 3/4 inches In depth, inside dimensions. Pads shall be equal in size to the inside length and width of the box less 1/16 inch. Boxes shall be closed in conformance to the requirements of Rule 41 of the Uniform Freight Classification.

5.2 Palletization.-Boxes may be palletized at the shippers option. Palletization shall conform to MIL-STD-1169 instructions for Level C shipment.

5.3 Marking.-Marking of boxes and pallet loads shall comply with MIL-STD-1169 requirements.

5.4 Shipping.-When component parts from more than one lot are shipped as a carload, each lot shall be kept separate and the division between lots clearly indicated.

6. NOTES

6.1 Ordering data.-Procurement documents shall specify the following:

a. Title, number and date of this specification.
b. Data cards. - Data cards shall be prepared for each lot in accordance with the information specified in Standard MIL-STD-1167.
c. Provisions for submission of first article samples.

6.2 Inspection code numbers.-The five digit code numbers assigned to the inspections herein are to facilitate future data collection and analysis by the Government. They should

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T19:18Z
Check the source to verify that this is the current version before use.

be cited as references on drawings of equipment designs submitted by the contractor to the Government for approval (see 6.3.3).

6.3 Inspection Equipment Designs.-Inspection equipment designs are of two types - Government Special Inspection Equipment (SIE) designs and contractor designs. SIE designs are designated by drawing numbers under the "Method of Inspection" headings in Section 4. Design responsibility for all other inspection equipment is assigned to the contractor. The contractor need not furnish any design when a complete Government SIE design is provided. Unless otherwise specified, however, the contractor may submit alternate or modified contractor designs of SIE in accordance with 6.3.2 and 6.3.3 should he elect to do so.

6.3.1 SIE designs .-SIE designs may consist of any of the following:

a. Detailed drawings which completely depict all information necessary for the fabrication and use of the item of inspection equipment.

b. A source control drawing or a specification control drawing as defined in MIL-STD-100.

c. An envelope drawing, as defined in MIL-STD-100, which establishes the criteria which a detailed design shall meet. When envelope drawings are specified, the contractor shall prepare designs which comply with the criteria therein.

6.3.2 Contractor designs. -Contractor designs are required for all inspection equipment for which SIE designs are not specified and may include commercial equipment which the contractor proposes to use. (Commercial equipment is defined as unmodified equipment which is cataloged and available for purchase by the general public.) Contractor designs shall include appropriate operating instructions, calibration procedures and maintenance procedures. Commercial equipment shall be fully described by catalog listings or other means which provide sufficient information to permit identification and evaluation by the Government and may include illustrations and engineering data. Designs shall be prepared for any special fixture(s) required to be used with commercial equipment, or with SIE designs if not otherwise covered

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T19:18Z
Check the source to verify that this is the current version before use.

thereby (see 6.3.1c). Designs shall be of the category and form (per MIL-D-1000) specified in the Contract Data Requirements Lists (DD Form 1423). The contractor is referred to MIL-HDBK-204, "Inspection Equipment Design" for guidance. The specification number and the applicable five digit defect code number (or other specific identifying information) from Section 4 of this specification shall be referenced on each contractor design together with the component or assembly drawing number and revision letter to which the specific design applies.

6.3.3 Submission of Designs for Approval.-Contractor designs shall be approved by the Government prior to fabricating or procuring the equipment. Designs shall be submitted for approval to Picatinny Arsenal, ATTN: SARPA-QA-A-M, Dover, Neew Jersey 07801 in accordance with the stipulations, time frame and distribution specified in the Contract Data Requirements List (DD Form 1423) or in the contract. Partial submission of inspection equipment designs is permissible and encouraged. However, the completion date for design review will be based on the date of the final submission of designs. Picatinny Arsenal design review will normally be accomplished within one month after receipt.

6.4 Sinusoidal Pulser.- One design for a sinusoidal pulser is available under test equipment drawing 9201429. Operating and calibration procedures are available under drawings 9201431, and 9201434.

Custodian:
Army-MU

Preparing Activity:
Army-MU

Project Number: 1345-A-021

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T19:18Z
Check the source to verify that this is the current version before use.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T19:18Z
Check the source to verify that this is the current version before use.

SPECIFICATION ANALYSIS SHEET

Form Approved
Budget Bureau No. 22-R255

INSTRUCTIONS: This sheet is to be filled out by personnel, either Government or contractor, involved in the use of the specification in procurement of products for ultimate use by the Department of Defense. This sheet is provided for obtaining information on the use of this specification which will insure that suitable products can be procured with a minimum amount of delay and at the least cost. Comments and the return of this form will be appreciated. Fold on lines on reverse side, staple in corner, and send to preparing activity. Comments and suggestions submitted on this form do not constitute or imply authorization to waive any portion of the referenced document(s) or serve to amend contractual requirements

SPECIFICATION

ORGANIZATION

CITY AND STATE

CONTRACT NUMBER

MATERIAL PROCURED UNDER A

☐ DIRECT GOVERNMENT CONTRACT ☐ SUBCONTRACT

. HAS ANY PART OF THE SPECIFICATION CREATED PROBLEMS OR REQUIRED INTERPRETATION IN PROCUREMENT USE?

A. GIVE PARAGRAPH NUMBER AND WORDING.

B. RECOMMENDATIONS FOR CORRECTING THE DEFICIENCIES

. COMMENTS ON ANY SPECIFICATION REQUIREMENT CONSIDERED TOO RIGID

IS THE SPECIFICATION RESTRICTIVE?

☐ YES ☐ NO *(If "yes", in what way?)*

REMARKS *(Attach any pertinent data which may be of use in improving this specification. If there are additional papers, attach to form and place both in an envelope addressed to preparing activity)*

SUBMITTED BY *(Printed or typed name and activity - Optional)*

DATE

DD FORM 1 JAN 66 1426

REPLACES EDITION OF 1 OCT 64 WHICH MAY BE USED.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T19:18Z
Check the source to verify that this is the current version before use.

FOLD

Department of the Army
Picatinny Arsenal
Dover, New Jersey 07801

POSTAGE AND FEES PAID
DEPARTMENT OF THE ARMY
DOD 314

OFFICIAL BUSINESS

Commander
Picatinny Arsenal
ATTN: SMUPA-QA-A
Dover, New Jersey 07801

FOLD

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T19:18Z
Check the source to verify that this is the current version before use.