MILITARY SPECIFICATION
ANCHOR, UNDERWATER MINE, MARK 56 MOD 4 AND MOD 5

This amendment forms a part of Military Specification MIL-A-23773A (OS), dated 10 January 1967 and has been approved by the Naval Ordnance Systems Command, Department of the Navy.

Page 2
Paragraph 2.1, delete: CLASSIFICATION OF DEFECTS
CD 2421432 Anchor, Underwater Mine Mark 56 Mod 4
CD 2421477 Anchor, Underwater Mine Mark 56 Mod 5

Page 6
Paragraph 4.5.1, delete entire paragraph and insert new paragraph to read:

4.5.1 Examination. Each mine anchor shall be visually and dimensionally examined in accordance with Drawings 2421432 and 2421477 to determine compliance with this specification and LDs 549694 and 549718.

Page 8
Paragraph 4.5.2.1, on second line following (Sampling) add: (M101).

Paragraph 4.5.2.2.1, on first line following (Sampling) add: (M102).

Paragraph 4.5.2.2.2, on first line following (Sampling) add: (M103).

Page 9
Before Paragraph 4.5.2.3, insert new paragraph to read:

4.5.2.2.3 Assembly leakage test (Sampling)(M104). The Safety Device Assembly, Dwg. 1281099, assembled to a suitable test fixture, shall be subjected to an external pressure of 45 ± 5 psig for ten minutes. Upon application of the pressure, the piston shall move inward a minimum

Source: https://assist.dla.mil -- Downloaded: 2026-10-19T17:52Z
Check the source to verify that this is the current version before use.

of 0.531 inch. Any outward movement of the piston during the ten-minute period shall be regarded as evidence of leakage and the safety device shall be rejected.

Paragraph 4.5.2.3, on first line following (Sampling) add: (M105).

Paragraph 4.5.2.4, on first line following (Sampling) add: (M106).

Paragraph 4.5.2.5, on first line following (Sampling) add: (M107).

Paragraph 4.5.2.6, on first line following (Sampling) add: (M108).

Page 10

Paragraph 4.5.2.7, on first line following (Sampling) add: (M109).

Paragraph 4.5.2.8, on first line following (Sampling) add: (M110).

Paragraph 4.5.2.9, on first line following (Sampling) add: (M111).

Page 12

Add new paragraph to read:

6.3 This specification has been prepared for the Naval Ordnance Systems Command by the Naval Mine Engineering Facility, Yorktown, Virginia 23491.

Preparing Activity

Navy - OS

Project No. 1350-N019

☆ U. S. GOVERNMENT PRINTING OFFICE: 1971-714-158/2398

Source: https://assist.dla.mil -- Downloaded: 2026-10-19T17:52Z
Check the source to verify that this is the current version before use.