MIL-P-23810A(OS)
7 November 1967
Superseding
MIL-P-23810(Wep)
14 March 1963

MILITARY SPECIFICATION

PANEL, COMPONENT, RECORDING

(For Torpedo Exercise Section Mark 64 Mod 2)

This specification has been approved by the Naval Ordnance Systems Command, Department of the Navy

1. SCOPE

1.1 Scope. This specification describes the requirements for the procurement, inspection, and test of a recording panel, LD 613310.

2. APPLICABLE DOCUMENTS

2.1 The following documents of the issue in effect on the date of invitation for bids or request for proposal form a part of this specification to the extent specified herein.

SPECIFICATIONS

MILITARY

MIL-O-23560/4	Oscillograph

STANDARDS

MILITARY

MIL-STD-105	Sampling Procedures and Tables for Inspection by Attributes
MIL-STD-129	Marking for Shipment and Storage

DRAWINGS

NAVAL ORDNANCE SYSTEMS COMMAND

LD 162756	Shipping (Packing) Condition
LD 613310	Recording Component Panel Assembled
Drawing 2436236	Recording Component Panel Schematic Diagram

FSC 1355

Source: https://assist.dla.mil -- Downloaded: 2026-10-19T17:59Z
Check the source to verify that this is the current version before use.

PUBLICATIONS

NAVAL ORDNANCE SYSTEMS COMMAND

WR-43	Preparation of Quality Assurance Provisions (Including Classification of Characteristics)
OS 6341	Miscellaneous General Ordnance Design Requirements

(Copies of specifications, standards, drawings, and publications requested by contractors in connection with specific procurement functions should be obtained from the procuring activity or as directed by the contracting officer.)

2.2 Other publications. The following documents form a part of this specification to the extent specified herein. Unless otherwise indicated, the issue in effect on date of invitation for bids or request for proposal shall apply.

NATIONAL BUREAU OF STANDARDS PUBLICATIONS

Handbook H28	Screw-Thread Standards for Federal Services

(Application for copies should be addressed to the Superintendent of Documents, Government Printing Office, Washington, D. C. 20402.)

CONSOLIDATED CLASSIFICATION COMMITTEE PUBLICATION

Consolidated Freight Classification Rules

(Application for copies should be addressed to the Consolidated Classification Committee, 202 Chicago Union Station, Chicago, Illinois, 60606)

AMERICAN TRUCKING ASSOCIATION, INC., PUBLICATION

Motor Freight Classification Rules

(Application for copies should be addressed to the Issuing Offi er, American Trucking Association, Inc., 1424 16th St., N.W., Washington, D. C. 20036

3. REQUIREMENTS

3.1 Description. The recording component panel serves as a gathering and transforming center for all torpedo information obtained during an exercise run. It receives signal inputs from all the signal source points located throughout the torpedo, and transforms them into recordable signals. It then relays the transformed signals to a recording oscillograph,

Source: https://assist.dla.mil -- Downloaded: 2026-10-19T17:59Z
Check the source to verify that this is the current version before use.

MIL-O-23560/4, which records the information for later study of the torpedo's behavior during a run. The recording panel also contains a dc power supply which furnishes power to all the signal source points that are dc energized.

3.2 General requirements

3.2.1 Contractor-furnished data. Data required by this specification or by applicable documents referenced in Section 2 need not be furnished unless specified in the contract or order (see 6.2).

3.2.2 Preproduction samples. Unless otherwise specified in the contract or order, preproduction samples of the recording panel shall be manufactured using the methods and procedures proposed for the production lot. These samples will be tested as specified in Section 4 herein, and are for the purpose of determining that the production item meets the requirements of this specification and the design. Provisions of samples shall be in accordance with 4.2.1.

3.2.3 Materials. Unless otherwise specified in the contract, requisition, or order, all materials and purchased parts entering into the final assembly of the recording panel shall conform strictly to the detailed requirements indicated on the drawings and specifications listed in LD 613310.

3.2.4 Finishes, coatings, construction, and dimensions. Finishes, coatings, construction, and dimensions for the recording panel shall be strictly in accordance with the applicable drawings, specifications, and publications listed in LD 613310.

3.2.5 Moisture, fungus, and corrosion. The recording panel shall be rendered moisture, fungus, and corrosion resistant as required by OS 6341.

3.2.6 Marking. Marking of assemblies, subassemblies, and parts shall be in accordance with the applicable drawings listed in LD 613310.

3.2.7 Interchangeability. Component parts of the assembled units (unless otherwise specified on the applicable drawings) fabricated in strict accordance with their applicable drawings shall be interchangeable and shall assemble with mating components of the unit without selection or fitting. If, during assembly of the fabricated parts of a unit, selection or fitting is required, then changes in dimensions are necessary and revision and correction of the applicable drawings is required. See 3.2.10.

3.2.8 Gages. The contractor shall provide himself with whatever gages are necessary and adequate to ensure that the material to which this specification applies will meet the dimensional requirements shown on the applicable drawings. If so stipulated in the contract, order, or requisition, the Government will furnish drawings of

Source: https://assist.dla.mil -- Downloaded: 2026-10-19T17:59Z
Check the source to verify that this is the current version before use.

pertinent Navy Final Inspection Gages for guidance in the design of the contractor's inspection gages. However, such procedure shall not serve to relieve the contractor of his responsibility in the design and manufacture of such gages as may be required in the satisfactory fulfillment of the contract requirements, but is intended to facilitate acceptance of all components and assemblies by Navy Final Inspection Gages.

3.2.9 Threads. Unless otherwise specified, all threads shall be in accordance with National Bureau of Standards Handbook H28. The class or fit for threads shall be as specified on the applicable drawings.

3.2.10 Conflicting requirements. Conflicting requirements arising between this specification or any specifications, publications, or drawings listed herein shall be referred in writing to the procuring agency or appointed agent for interpretation, clarification, and resolution (or correction).

3.3 Performance requirements and product characteristics. The recording panel shall meet the following performance requirements and product characteristics:

3.3.1 The recording panel shall operate with an input power supply of 115 volts ac plus or minus 3 percent, 400 cps plus or minus 2 percent, single phase.

3.3.2 All pin, plug, and component numbers referred to herein are given in Drawing 2436236.

3.3.3 Interconnections between pins of P70 and S71 shall be as specified in Table I, given in 4.4.4.2.

3.3.4 With a load of 15 ohms plus or minus 5 percent connected across pins 5 and 6 of S71 and a 400 cps, ac input of 10 volts applied across terminals C and D of P70, the output signal developed across pins 5 and 6 of S71 shall be 0.004 volt plus or minus 25 percent, peak-to-peak.

3.3.5 With connections as specified in 3.3.4, connecting terminals D and E of P70 shall produce an additional output signal of 0.004 volt plus or minus 25 percent.

3.3.6 With connections as specified in 3.3.5, removal of the connection between terminals D and E of P70 and transfer of the ac input lead from terminal D of P70 to terminal E of P70 shall remove the ac output specified in 3.3.4 without affecting the dc output specified in 3.3.5.

3.3.7 With a 400 cps, ac input of 3 volts applied across terminals H and J of P70 and a resistive load of 15 ohms plus or minus 5 percent connected across pins 9 and 10 of S71, the output signal developed across pins 9 and 10 of S71 shall be 0.02 volt plus or minus 20 percent, peak-to-peak.

3.3.8 With connections as specified in 3.3.7, application of 115 volts 400 cps, ac across terminals CC and DD of P70 (with terminal CC having

Source: https://assist.dla.mil -- Downloaded: 2026-10-19T17:59Z
Check the source to verify that this is the current version before use.

the same polarity as terminal J of P70) shall reduce the output given in 3.3.7 to zero plus or minus 0.008 volt, peak-to-peak.

3.3.9 With 115 volts 400 cps, single phase ac connected as in 3.3.8, but with the ac input signal to terminals H and J of P70 180 degrees out of phase with that in 3.3.7, the output shall be 0.035 volt plus or minus 20 percent, peak-to-peak.

3.3.10 With a resistive load of 15 ohms plus or minus 5 percent connected across pins 15 and 16 of S71, and a 400 cps, ac input of 115 volts applied across terminals M and N of P70, a voltage shall be developed across pins 15 and 16 of S71 which may be adjusted over the range of 0.05 volt to 0.100 volt, peak-to-peak, by potentiometer R74.

3.3.11 With a resistive load of 15 ohms plus or minus 5 percent connected across pins 23 and 24 of S71 and a 400 cps, ac input of 3 volts applied across terminals U and V of P70, the output developed across pins 23 and 24 of S71 shall be 0.02 volt plus or minus 20 percent, peak-to-peak.

3.3.12 With the connections as specified in 3.3.11, application of 115 volts, 400 cps, ac across terminals CC and DD of P70 (with terminal CC of P70 having the same polarity as terminal V of P70), the output given in 3.3.11 shall be reduced to zero plus or minus 0.008 volt, peak-to-peak.

3.3.13 With 115 volts, 400 cps, single phase ac connected as in 3.3.12, but with the ac input signal to terminals U and V of P70 180 degrees out of phase with that in 3.3.11, the output shall be 0.035 volt plus or minus 20 percent, peak-to-peak.

3.3.14 With a resistive load of 150 ohms plus or minus 5 percent connected across terminals EE and FF of P70 and a 115 volt, 400 cps, ac input applied across terminals CC and DD of P70, the output developed across terminals EE and FF of P70 shall be 4.7 plus or minus 0.5 volts dc, terminal EE being negative.

3.3.15 The peak-to-peak ac ripple component of the dc output voltage specified in 3.3.14 shall not exceed 2 percent of the measured dc voltage.

3.3.16 With the 150 ohm load of 3.3.14 connected across terminals EE and FF of P70, the dc voltage across terminals EE and BB of P70 and across terminals FF and BB of P70 shall be half of that voltage measured in 3.3.14, plus or minus 1.0 volt.

3.3.17 With an open circuited phone plug inserted in phone jack J1, there shall be an open circuit between terminal BB of P70 and pin 32 of S71. The closed circuits from terminal BB of P70 to pins 1, 8, 12, 14, 20, and 22 of S71 (as given in Table I) shall not be affected.

3.3.18 The recording component panel shall have an operating life of 500 hours when tested as specified in 4.5.3.

Source: https://assist.dla.mil -- Downloaded: 2026-10-19T17:59Z
Check the source to verify that this is the current version before use.

3.3.19 With connections as in 3.3.14, a voltmeter connected between pin FF of P70 and pin 3 of S71, shall indicate a voltage which may be varied, by adjustment of R75, from 0 to 4.7 plus or minus 0.5 volts, less the voltage drop through 51,000 ohms due to meter current.

3.4 Environmental requirements

3.4.1 Vibration. The recording panel, less pack and packaging and mounted as specified in 4.5.1, shall be capable of withstanding vertical vibrations for a period of 3 hours at a frequency of 60 cycles per second and a double amplitude (peak-to-peak) of 0.016 plus or minus 0.002 inch. Thereafter the panel shall show no damage and shall meet the performance requirements and product characteristics of this specification.

3.4.2 Temperature and humidity. The recording panel, less pack and packaging, shall be capable of withstanding a temperature of plus 160 degrees F, plus or minus 5 degrees F, 90 to 95 percent relative humidity, for a period of 72 hours, in accordance with test procedures specified in 4.5.2. Thereafter the panel shall show no corrosion or damage and shall meet the performance requirements and product characteristics of this specification.

3.4.3 Storage life. When Level A preservation, packaging, and packing, as defined in 6.2, is specified, the recording panel shall show no damage and shall meet all the performance requirements and product characteristics of this specification after being stored for a period of five years, in the packaging and packing specified, under temperature and humidity conditions as follows:

3.4.3.1 Temperature: Minus 65 degrees F to plus 160 degrees F (minus 53 degrees C to plus 71 degrees C).

3.4.3.2 Humidity: Up to 90 to 95 percent relative.

3.5 Cleanup. Prior to and after final assembly, all parts, components, and the assembly shall be thoroughly cleaned of loose, spattered, or excess solder, metal chips, and other foreign matter. All burrs, sharp edges, and rosin flash shall be removed.

3.6 Workmanship. The recording panel, including all parts and accessories, shall be constructed and finished in a manner to ensure compliance with all the requirements of this specification. Particular attention shall be paid to neatness and thoroughness of soldering, wiring, marking of parts and assemblies, painting, machine screw assemblage, welding, brazing, and freedom of parts from burrs and sharp edges. The standards of workmanship exhibited in any approved preproduction sample, subject to any qualification stated in the Government's notice of approval, shall be determinative of the requirements of the contract relative to workmanship insofar as not specifically covered by applicable specifications.

Source: https://assist.dla.mil -- Downloaded: 2026-10-19T17:59Z
Check the source to verify that this is the current version before use.

4. QUALITY ASSURANCE PROVISIONS

4.1 Responsibility for inspection. Unless otherwise specified in the contract or purchase order, the supplier is responsible for the performance of all inspection requirements as specified herein. Except as otherwise specified, the supplier may utilize his own facilities or any commercial laboratory acceptable to the Government. The Government reserves the right to perform any of the inspections set forth in the specification where such inspections are deemed necessary to ensure that supplies and services conform to prescribed requirements.

4.1.1 Classification of characteristics. The characteristics verified by the tests and examinations herein are classified as Critical, Major, or Minor, in accordance with WR-43. Tests and examinations that verify critical characteristics are identified by the symbol (C) and those that verify major characteristics are identified by the symbol (M). The number following the classification symbol indicates the serial number of the test or examination. Tests and examinations that are not annotated with a classification code are classified minor.

4.2 Sampling

4.2.1 Preproduction sample. Unless otherwise specified for each contract or order, a representative sample of five recording panels shall be submitted to the Government inspector, preserved, packaged, and packed as specified in the contract or order, for production tests at an activity designated in the contract or by the Naval Ordnance Systems Command. Further production of the recording panels by the contractor prior to approval of the contracting activity of preproduction samples shall be at the contractor's risk. Preproduction samples accepted will be applied as part of the quantity specified in the contract or order.

4.2.2 Lot size. As applied to Government inspection of units of production, the term "lot" shall mean "inspection lot," that is, a collection of units of product submitted by a supplier for Government inspection. Unless otherwise specified, the number of units of product in inspection lots will be determined by the Government inspector and may differ from the quantity designated in the contract or order in a lot for production, shipment, or other purpose.

4.2.3 Periodic production samples

Step 1. Upon initiation of production the Government inspector shall randomly select one unit from each group of five units for submission to a Naval Ordnance Systems Command activity.

Step 2. Upon satisfactory compliance of each unit from three consecutively produced groups, select a sample in accordance with MIL-STD-105, Inspection Level L-4 (acceptance number zero), based on the remainder of the contract.

Source: https://assist.dla.mil -- Downloaded: 2026-10-19T17:59Z
Check the source to verify that this is the current version before use.

Step 3. When a defective unit is found while the L-4 level of inspection is in effect, shift to step 1 and proceed as indicated.

4.3 Classification of tests. The inspection and testing of the recording panels shall be classified as follows:

4.3.1 Quality conformance tests. Quality conformance tests are to be accomplished on each recording panel being submitted for acceptance under contract. These tests, detailed in 4.4, shall be performed by the manufacturer.

4.3.2 Preproduction and periodic production tests. Preproduction and periodic production tests are those which are accomplished on samples selected as specified in 4.2.1 and 4.2.3 which are representative of the recording panels after the award of the contract to determine that the lot and production meet the requirements of this specification.

4.4 Quality conformance tests

4.4.1 Test equipment. The following items of test equipment are required to perform the acceptance tests set forth in this specification:

4.4.1.1 Volt-ohm-milliammeter, capable of indicating resistances of 0-1000, 0-10,000, and 0-1,000,000 ohms and dc voltages of 0-1 and 0-10 volts. Voltmeter to have resistances of 20,000 ohms per volt.

4.4.1.2 Power source, 115 volt, 400 cps, ac single phase.

4.4.1.3 Transformer, 400 cps; Primary: 115 volts
Secondary: (a) 10 volts
(b) 6 volts (CT)

4.4.1.4 Resistor, 150 ohms plus or minus 5 percent, 1 watt.

4.4.1.5 Resistor, 15 ohms plus or minus 5 percent, 1 watt.

4.4.1.6 Calibrated oscilloscope, with a sensitivity of at least 0.02 volt per inch for both ac and dc inputs.

4.4.2 Test conditions. Unless otherwise specified, the recording panel shall be subjected to acceptance tests under the following conditions:

4.4.2.1 Temperature: 65 degrees F to 95 degrees F (18 degrees C to 35 degrees C).

4.4.2.2 Altitude: Normal ground.

4.4.2.3 Vibration: None.

4.4.2.4 Humidity: Room ambient to 95 percent relative maximum.

Source: https://assist.dla.mil -- Downloaded: 2026-10-19T17:59Z
Check the source to verify that this is the current version before use.

4.4.3 Test and inspection equipment and facilities. The manufacturer shall furnish and maintain all necessary test equipment and facilities and shall provide personnel for performing the quality conformance tests. The test equipment shall be adequate in quantity and, unless definite requirements are specified, shall be of sufficient accuracy and quality to permit performance of the required tests.

4.4.4 Test procedure

4.4.4.1 All components, pin, end plug numbers referred to herein are given on Drawing 2436236.

4.4.4.2 (M101) Measure the resistance between pins specified in Table I.

4.4.4.3 Connect the 15 ohm plus or minus 5 percent resistor and a calibrated oscilloscope across pins 5 and 6 of S71. Set the oscilloscope to indicate presence of both ac and dc current. Turn on the oscilloscope and allow it to warm up for five minutes.

4.4.4.3.1 (M102) Apply ten volts of 400 cps, ac across terminals C and D (from the secondary of the 400 cps, ac transformer given in 4.4.1.3). The oscilloscope shall show a 400 cps, ac signal which shall measure 0.004 volt plus or minus 25 percent, peak-to-peak. The ripple content shall be less than 0.5 mv peak-to-peak.

TABLE I

From Terminal of P70	To Pin of S71	Resistance
A	3	Closed circuit
B	4	Closed circuit
F	7	8200 ohms ± 5%
K	11	2700 ohms ± 5%
L	13	39,000 ohms ± 5%
P	17	Less Than 250 ohms clockwise to 20,000 ohms ± 5% counter-clockwise
R	18	Closed circuit
S	19	2700 ohms ± 5%
T	21	2700 ohms ± 5%
W	25	Closed circuit
X	26	Closed circuit
AA	30	Closed circuit
BB	8	Closed circuit
BB	14	Closed circuit
BB	12	Closed circuit
BB	20	Closed circuit
BB	22	Closed circuit
BB	32	Closed circuit
HH	13	68,000 ohms ± 5%
JJ	2	39,000 ohms ± 5%
BB	1	Closed circuit

Source: https://assist.dla.mil -- Downloaded: 2026-10-19T17:59Z
Check the source to verify that this is the current version before use.

NOTE: A reading of 0.2 ohm or less is necessary to constitute a closed circuit.

4.4.4.3.2 (M103) With connections as given in 4.4.4.3.1, jumper across terminals D and E of P70. The oscilloscope shall show a deflection indicating the presence of dc voltage (positive on terminal 5 of S71) of 0.004 volt plus or minus 25 percent.

4.4.4.3.3 (M104) With connections as given in 4.4.4.3.2, disconnect the ac input voltage lead from terminal D of P70, connect it to pin E, and remove the jumper between terminals D and E. The dc output of 4.4.4.3.2 shall remain, but the ac output of 4.4.4.3.1 shall be absent.

4.4.4.4 Remove the 15 ohm load resistor and the oscilloscope from pins 5 and 6 of S71 and connect them across pins 9 and 10 of S71.

4.4.4.4.1 (M105) Apply 3 volts of 400 cps, ac (as given in 4.4.1.3) across terminals H and J of P70. The output voltage as indicated on the oscilloscope shall be 0.02 volt plus or minus 20 percent, peak-to-peak.

4.4.4.4.2 (M106) Without altering the setup of 4.4.4.4.1, apply 115 volts 400 cps, ac (as given in 4.4.1.2) across terminals CC and DD of P70, with terminal CC having the same polarity as terminal J. The ac output voltage, as indicated on the oscilloscope, shall be reduced to zero plus or minus 0.008 volt, peak-to-peak.

4.4.4.4.3 (M107) Reverse the input leads to terminals H and J of P70, with the input to CC-DD remaining as in 4.4.4.4.2. The ac output voltage shall measure 0.035 volt plus or minus 20 percent, peak-to-peak.

4.4.4.5 (M108) Disconnect the ac inputs to terminals H and J, and terminals CC and DD. Move the oscilloscope and 15 ohm load resistor from pins 9 and 10 of S71 to pins 15 and 16 of S71, and apply 115 volts 400 cps, ac across terminals M and N of P70. The ac output voltage shall be capable of adjustment between 0.05 and 0.100 volt, peak-to-peak, by means of potentiometer R74.

4.4.4.6 Disconnect the ac input to terminals M and N of P70, and move the oscilloscope and 15 ohm load resistor from pins 15 and 16 of S71 to pins 23 and 24 of S71.

4.4.4.6.1 (M109) Apply 3 volts of 400 cps, ac across terminals U and V of P70. The ac voltage shall measure 0.02 volt plus or minus 20 percent, peak-to-peak.

4.4.4.6.2 (M110) Without altering the setup of 4.4.4.6.1, apply 115 volts 400 cps, ac across terminals CC and DD of P70, with terminal CC having the same polarity as pin V of P70. The ac voltage shall be reduced to no more than 0.008 volt.

4.4.4.6.3 (M111) Reverse the input leads to terminals U and V of P70, with the input to terminals CC and DD remaining as in 4.4.4.6.2. The ac output voltage shall measure 0.035 volt plus or minus 20 percent, peak-to-peak.

Source: https://assist.dla.mil -- Downloaded: 2026-10-19T17:59Z
Check the source to verify that this is the current version before use.

4.4.4.7 Remove the input leads to terminals U and V of P70, and remove the oscilloscope and load resistor from pins 23 and 24 of S71. Leave the input to terminals CC and DD in place, as in 4.4.4.6.2.

4.4.4.7.1 (M112) Connect a dc voltmeter and a 150 ohm plus or minus 5 percent load resistor across terminals EE and FF of P70. The dc output voltage, as indicated on the voltmeter, shall be 4.7 plus or minus 0.5 volt, with terminal EE being negative.

4.4.4.7.2 (M113) Connect an oscilloscope in parallel with the voltmeter of 4.4.4.7.1 and measure the ac ripple component of the voltage. The peak-to-peak ripple voltage shall not be greater than 2.0 percent of the measured dc voltage.

4.4.4.7.3 (M114) Measure the dc voltages from terminal EE to terminal BB, and from terminal FF to terminal BB. Each shall be one half of the voltage measured in 4.4.4.7.1, plus or minus 1.0 volt, with terminal EE negative and FF positive with respect to BB.

4.4.4.8 Insert an open circuited phone jack or some nonconducting object into phone jack J1 so as to deflect the moving contact of J1. The closed circuit between terminal BB of P70 and pin 32 of S71 shall open.

4.4.4.9 (M115) Holding the moving contact of J1 deflected as in 4.4.4.8, check the continuity from terminal BB of P70 to pins 1, 8, 12, 14, 20, and 22 of S71. All checks shall indicate a closed circuit, as in Table I.

4.4.4.10 (M116) With the input to terminals CC and DD in place and a 150 ohm plus or minus 5 percent load resistor across terminals EE and FF, as in 4.4.4.7.1, connect a 20,000 ohm per volt voltmeter with a 0-10 volt range between pin FF of P70 and pin 3 of S71. It should indicate a voltage which may be varied, by adjustment of potentiometer R75, from 0 to 3.7 plus or minus 0.5 volts.

4.5 Preproduction and periodic production inspection. The preproduction and periodic production samples, after satisfactorily passing the quality conformance tests of 4.4, shall be subjected to the following tests and examinations. Certified inspection data covering the results of preproduction and periodic production inspections shall be forwarded to the Naval Ordnance Systems Command. Failure to meet any requirement specified herein shall be cause for rejection of the lot represented and units tested.

4.5.1 Vibration (M117) The recording panel, less pack and packaging, shall be mounted rigidly, secured with the mounting base horizontal to a vibration device, utilizing the 4 mounting holes in the base. The recording panel shall be vibrated for a period of 3 hours at a frequency of 60 cycles per second and a double amplitude (peak-to-peak) of 0.016 plus or minus 0.002 inch. At the conclusion of this test, the recording panel shall meet the performance requirements and product characteristics of this specification.

Source: https://assist.dla.mil -- Downloaded: 2026-10-19T17:59Z
Check the source to verify that this is the current version before use.

4.5.2 Temperature and humidity (M118). The recording panel, less pack and packaging, shall be placed in a test chamber and subjected to a temperature of plus 160 degrees F plus or minus 5 degrees F, 90 to 95 percent relative humidity, for a period of 72 hours. Condensation from the test chamber shall not be allowed to drip onto the recording panel. At the conclusion of this test and after returning to room temperature, the recording panel shall meet the performance requirements and product characteristics of this specification. Prior to checkout, wiping or air hose drying may be performed, but no drying by heating or baking shall be done.

4.5.3 Operating life (M119)

4.5.3.1 Connect resistive loads of 15 ohms plus or minus 5 percent across pins 5 and 6, 9 and 10, 15 and 16, and 23 and 24 of S71. Connect a resistive load of 150 ohms plus or minus 5 percent across terminals EE and FF of P70.

4.5.3.2 Connect 3 volts of 400 cps, ac across terminals H and J, and U and V of P70. (The same source may be used for both inputs.)

4.5.3.3 Apply 10 volts of 400 cps, ac across terminals C and D, and M and N of P70. (The same source may be used for both inputs.)

4.5.3.4 Apply 115 volts 400 cps, ac across terminals CC and DD of P70.

4.5.3.5 Cycle the 115 volt ac input for periods of 59 minutes on, followed by 1 minute off, for a total of 500 complete cycles. At the completion of this cycling, the recording panel shall meet the performance requirements specified in 3.3.

4.6 Visual and dimensional examination. Each recording panel shall be examined to determine conformance with the requirements for workmanship and dimensions.

4.7 Preservation, packing, and packaging. The inspector shall ascertain that the preservation, packing, and packaging of the panel conforms to Section 5 of this specification.

4.8 Rejection. Failure of the recording panel to meet all the requirements and tests of this specification shall be considered cause for rejection of the unit, and in the case of periodic production tests, of the lot from which the sample was drawn.

5. PREPARATION FOR DELIVERY

5.1 Preservation and packaging (see 6.2)

5.1.1 Levels A and B. The recording panels shall be individually protected and unit packaged in accordance with LD 162756.

5.1.2 Level C. The recording panel shall be afforded preservation and packaging in accordance with the manufacturer's replacement parts practice.

Source: https://assist.dla.mil -- Downloaded: 2026-10-19T17:59Z
Check the source to verify that this is the current version before use.

5.2 Packing (see 6.2)

5.2.1 Levels A and B. The recording panel, packaged as specified in 5.1.1, shall be packed in accordance with LD 162756.

5.2.2 Level C. The recording panels, packaged as specified in 5.1.2, shall be packed to afford protection against damage during direct shipment from the supply source to the first receiving activity for immediate use. Containers shall comply with Consolidated Freight Classification Rules or other common carrier regulations applicable to the mode of transportation.

5.3 Marking

5.3.1 Normal markings. In addition to any special marking required by the contract or order, unit packages and exterior shipping containers shall be marked in accordance with MIL-STD-129.

5.3.2 Serial numbers. Unit packages and shipping containers shall be marked with the serial number of the unit contained within.

6. NOTES

6.1 Intended use. The recording panel is intended for use in Torpedo Exercise Head Mk 64 Mod 2.

6.2 Ordering data. Procurement documents should specify the following:

(a) Title, number, and date of this specification.
(b) Any exceptions to this specification.
(c) Required level of preservation and packaging.
(d) Required level of packing.
(e) Assigned activity for preproduction and periodic production tests.
(f) Data required.
(g) That all additional samples required shall be provided and inspected at the expense of the supplier, when such additional samples are required because of the failure of any sample(s) to pass the prescribed inspections.
(h) That certified inspection data covering the results of preproduction and periodic production inspections shall be forwarded to the Naval Ordnance Systems Command when testing is accomplished at other than a Government activity.

6.3 Criteria for use of proper level of preservation, packaging, and packing.

(a) Level A. This level shall be used for those items which are to be shipped to indeterminate destinations, or stored under indeterminate conditions for redistribution anywhere.

Source: https://assist.dla.mil -- Downloaded: 2026-10-19T17:59Z
Check the source to verify that this is the current version before use.

(b) Level B. This level shall be used only when it is definitely known that the item will be held in covered storage, either in domestic or overseas locations, for a period of six months or less.

(c) Level C. This level shall be used only when it is definitely known that the packaged item is to be shipped to domestic installations for immediate use at the first receiving activity.

Source: https://assist.dla.mil -- Downloaded: 2026-10-19T17:59Z
Check the source to verify that this is the current version before use.

SPECIFICATION ANALYSIS SHEET

Form Approved
Budget Bureau No. 119-R004

INSTRUCTIONS

This sheet is to be filled out by personnel either Government or contractor, involved in the use of the specification in procurement of products for ultimate use by the Department of Defense. This sheet is provided for obtaining information on the use of this specification which will insure that suitable products can be procured with a minimum amount of delay and at the least cost. Comments and the return of this form will be appreciated. Fold on lines on reverse side, staple in corner, and send to preparing activity *(as indicated on reverse hereof)*.

SPECIFICATION

MIL-P-23810A(OS) PANEL, COMPONENT, RECORDING (FOR TORPEDO EXERCISE SECTION MK 64 Mod 2)

ORGANIZATION *(Of submitter)*	CITY AND STATE

CONTRACT NO.	QUANTITY OF ITEMS PROCURED	DOLLAR AMOUNT
		$

MATERIAL PROCURED UNDER A

☐ DIRECT GOVERNMENT CONTRACT ☐ SUBCONTRACT

1. HAS ANY PART OF THE SPECIFICATION CREATED PROBLEMS OR REQUIRED INTERPRETATION IN PROCUREMENT USE?

A. GIVE PARAGRAPH NUMBER AND WORDING.

B. RECOMMENDATIONS FOR CORRECTING THE DEFICIENCIES.

2. COMMENTS ON ANY SPECIFICATION REQUIREMENT CONSIDERED TOO RIGID

3. IS THE SPECIFICATION RESTRICTIVE?

☐ YES ☐ NO IF "YES", IN WHAT WAY?

4. REMARKS *(Attach any pertinent data which may be of use in improving this specification. If there are additional papers, attach to form and place both in an envelope addressed to preparing activity)*

SUBMITTED BY *(Printed or typed name and activity)*	DATE

DD, FORM 1426 APR 62

C-6870

Source: https://assist.dla.mil -- Downloaded: 2026-10-19T17:59Z
Check the source to verify that this is the current version before use.