MIL-A-52568C(ME)
8 April 1982
SUPERSEDING
MIL-A-52568B(ME)
8 August 1973

MILITARY SPECIFICATION

AIR CONDITIONER, TRAILER MOUNTED, ELECTRIC-MOTOR DRIVEN, 18,000 BTU/HR

This specification is approved for use by the Mobility Equipment Research and Development Command, Department of the Army, and is available for use by all Departments and Agencies of the Department of Defense.

1. SCOPE

1.1 Scope. This specification covers a trailer-mounted air conditioner, with accessories, powered by a 5 kW DED Generator set.

2. APPLICABLE DOCUMENTS

2.1 Government documents.

2.1.1 Specifications and standards. Unless otherwise specified (see 6.2), the following specifications and standards of the issue listed in that issue of the Department of Defense Index of Specifications and Standards (DoDISS) specified in the solicitation, form a part of this specification to the extent specified herein.

SPECIFICATIONS

FEDERAL

QQ-S-781	- Strapping, Steel, Flat and Seals.
TT-I-1795	- Ink, Marking, Stencil, Opaque (Porous and Non-Porous Surfaces).
UU-T-81	- Tags, Shipping, and Stock.
PPP-B-601	- Boxes, Wood, Cleated-Plywood.
PPP-B-636	- Boxes, Shipping, Fiberboard.
PPP-C-843	- Cushioning Material, Cellulosic.
PPP-P-40	- Packaging and Packing of Hardware.
PPP-T-60	- Tape, Packaging, Waterproof.

Beneficial comments (recommendations, additions, deletions) and any pertinent data which may be of use in improving this document should be addressed to: US Army Mobility Equipment Research and Development Command, ATTN: DRDME-DS, Fort Belvoir, VA 22060 by using the self-addressed Standardization Document Improvement Proposal (DD Form 1426) appearing at the end of this document or by letter.

FSC 4120

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T21:25Z
Check the source to verify that this is the current version before use.

MIL-P-116	- Preservation, Methods of.
MIL-B-121	- Barrier Material, Greaseproofed, Waterproofed, Flexible.
MIL-T-704	- Treatment and Painting of Materiel.
MIL-E-10062	- Engines: Preparation for Shipment and Storage of.
MIL-C-12000	- Cable, Cord, and Wire, Packaging of.
MIL-E-16298	- Electric Machines having Rotating Parts and Associated Repair Parts: Packaging of.
MIL-L-21260	- Lubricating Oil, Internal Combustion Engine, Preservative and Break-in.
MIL-A-46153	- Antifreeze, Ethylene Glycol, Inhibited, Heavy Duty, Single Package.
MIL-C-52437	- Chassis, Trailer, Single-and-Multi-Axle.

STANDARDS

MILITARY

MIL-STD-105	- Sampling Procedures and Tables for Inspection by Attributes.
MIL-STD-129	- Marking for Shipment and Storage.
MIL-STD-281	- Automobiles, Trucks, Truck-Tractors, Trailers and Trailer Dollies.
MIL-STD-642	- Identification Marking of Combat and Tactical Transport Vehicles.
MIL-STD-1188	- Commercial Packaging of Supplies and Equipment.

2.1.2 Other Government documents, drawings, and publications. The following other Government documents, drawings, and publications form a part of this specification to the extent specified herein.

DRAWINGS

ME

TA13226E1370	- Air Conditioner - Trailer Mounted, Generator Set Powered, 18,000 Btu.

(Copies of specifications, standards, and drawings required by contractors in connection with specific procurement functions should be obtained from the procuring activity or as directed by the contracting officer.)

2.2 Other publications. The following document(s) form a part of this specification to the extent specified herein. The issues of the documents which are indicated as DoD adopted shall be the issue listed in the current DoDISS and the supplement thereto, if applicable.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T21:25Z
Check the source to verify that this is the current version before use.

AMERICAN SOCIETY OF MECHANICAL ENGINEERS

Boiler and Pressure Vessel Code, Welding Qualification, Section IX.

(Application for copies should be addressed to the American Society of Mechanical Engineers, 345 East 47th Street, New York, NY 10017.)

AMERICAN WELDING SOCIETY

B3.0 - Standard Qualification Procedure.

(Application for copies should be addressed to the American Welding Society, 2501 Northwest Seventh Street, Miami, FL 33125.)

SOCIETY OF AUTOMOTIVE ENGINEERS

SAE Handbook.

(Application for copies should be addressed to the Society of Automotive Engineers, Two Pennsylvania Plaza, New York 10001.)

(Industry association specifications and standards are generally available for reference from libraries. They are also distributed among technical groups and using Federal agencies.)

2.3 Order of precedence. In the event of a conflict between the text of this specification and the references cited herein, the text of this specification shall take precedence.

3. REQUIREMENTS

3.1 Description. The air conditioner (hereinafter called the "unit") shall be a Government-furnished air conditioner and generator set mounted on a Government-furnished trailer with accessories, and shall be assembled in accordance with Top Assembly, TA13226E1370 and as specified herein.

3.1.1 Drawings. The drawings forming a part of this specification are end product drawings. No deviation from the prescribed dimensions or tolerances is permissable without prior approval of the contracting officer. Where tolerances could cumulatively result in incorrect fits, the contractor shall provide tolerances within those prescribed on the drawings to insure correct fit, assembly, and operation of the air conditioners. Any data (e.g. shop drawings, layouts, flow sheets, processing procedures, etc.) prepared by the contractor or obtained from a vendor to support fabrication and manufacture of the production item shall be made available, upon request, for inspection by the contracting officer or his designated representative.

3.2 First article (preproduction model). The contractor shall furnish one or more units as specified (see 6.2), for examination and testing within the time frame specified (see 6.2), to prove that his production methods will produce units that comply with the requirements of this specification. Examination and

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T21:25Z
Check the source to verify that this is the current version before use.

tests shall be as specified in Section 4; and unless otherwise specified herein, all examination and tests shall be conducted by the contractor subject to surveillance and approval by the Government (see 6.3). When specified (see 6.2), the Government will conduct any or all of the preproduction examination and tests, as specified (see 6.2).

3.3 Initial production. When specified (see 6.2), the contractor shall furnish to the Government one or more units (see 6.2) for inspection as specified in 4.4.

3.4 Material. Material shall be as specified herein and on the applicable drawings. Materials not specified shall be selected by the contractor and shall be subject to all provisions of this specification (see 6.9).

3.5 Performance characteristics. When assembled in accordance with the drawings, the air conditioner shall be capable of being started and operated by the generator set, and shall provide cooled air through the evaporator discharge openings.

3.6 Safety. The air conditioner and generator set shall be effectively grounded prior to operation to protect all persons or objects from electrical shock hazard.

3.7 Vehicle markings. Registration numbers and other markings of the trailer shall be in accordance with MIL-STD-642 (see 6.7).

3.8 Government-furnished property. Unless otherwise specified (see 6.2), the following property in the quantities indicated will be furnished by the Government (see 6.4):

Item No.	Description	Identification	Qnty f/ea unit
1	1/ Air Conditioner, Multipackage, 18,000 Btu/hr (with operator and maintenance manual).	NSN4120-00-935-5342	1
2	1/ Generator Set, DED, 5kW, 60 Hz (with operator and maintenance manual).	NSN6115-00-465-1044	1
3	Chassis Trailer, Multi-Axle Size 6, Class CCE, w/spare tire, Air Suspension.	MIL-C-52437 and Drawing 13226E1371	1
4	Duct, Flexible, 15 Ft. Long by 12 In. Dia.	NSN4130-00-930-3474	2
5	Rack, Duct Retaining.	NSN4130-00-930-3476	2

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T21:25Z
Check the source to verify that this is the current version before use.

Item No. (Continued)	Description	Identification	Qnty f/ea unit
6	Rod Ground.	NSN5975-00-642-8937	1
7	Clamp, Ground Rod.	NSN5999-00-243-5861	1
8	Wire, Ground, 10 Ft.	NSN6145-00-189-6695	1
9	Case, Cotton Duct.	NSN7520-00-559-9618	1

1/ Prior to any operation and testing, the equipment shall be prepared for operation by the contractor in accordance with the operator and maintenance manuals furnished with the items, and as specified in 4.6.2.1.

3.9 Roadability. When tested as specified in 4.6.2.3, the unit shall withstand cross-country hauling without damage or failure and shall be operable.

3.10 Workmanship.

3.10.1 Metal fabrication. Metal used in fabrication shall be free from kinks and sharp bends. The straightening of material shall be done by methods that will not cause injury to the material. Corners shall be square and true. All bends shall be made with controlled means to insure uniformity of size and shape. Precaution shall be taken to avoid overheating. Heated steel shall be allowed to cool slowly. External surfaces shall be free of burrs, sharp edges and corners, except when sharp edges or corners are required or where they are not detrimental to safety.

3.10.2 Bolted connections. Boltholes shall be accurately formed and shall have the burrs removed. Washers or lockwashers shall be provided where necessary. Matching thread areas securing bolts conforming to SAE J429 or capscrews shall be of sufficient strength to withstand the tensile strength of the bolt. All fasteners shall be correctly torqued and shall have full thread engagement.

3.10.3 Riveted connections. Rivets shall fill the holes completely. The upset rivet heads shall be full, neatly made, concentric with the rivet holes, and in full contact with the surface of the member, and shall be in accordance with SAE J492.

3.10.4 Jigs and fixtures. Shop-fabricated components shall be assembled in steel jigs or frames and joined while held in position. Jigs and frames shall minimize distortion.

3.10.5 Welders. Before assigning any welder to manual welding work covered by this specification, the contractor shall provide the contracting officer with certification that the welder has passed qualification tests as prescribed by either of the following listed codes for the type of welding operations to be performed and that such qualification is effective as defined by the particular code:

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T21:25Z
Check the source to verify that this is the current version before use.

Standard Qualification Procedure of the American Welding Society.
Welding Qualifications of the ASME.

Contractors who only made horizontal welds need not qualify welders for "all position welding". Subject to approval by the Government, contractor's standard welder qualification may be substituted in lieu of the above codes provided that the contractor's procedure is equivalent to the above codes. The contractor shall be responsible for determing that automatic welder equipment operators are capable of producing quality welds.

3.10.6 Interchangeability. All parts having the same part number shall be functionally and dimensionally interchangeable. Interchangeable parts are defined as two or more parts possessing such functional and physical characteristics as to be equivalent in performance and durability and capable of being exchanged one for the other without alteration of the parts themselves or of adjoining parts except for adjustment, and without selection for fit or performance.

3.11 Treatment and painting. The unit shall be cleaned, treated and painted in accordance with MIL-T-704, color as specified per end item requirements (see 6.2), Government furnished property, if painted a different color than specified (see 6.2), shall receive a top coat of paint the color as specified in 6.2.

3.11.1 Repainting. If repainting of Government-furnished property is required to change the color or to touch-up the paint, all exterior surfaces exposed or visible during operation, except identification plates and markings shall be painted. These surfaces shall be solvent cleaned to remove oil, grease, or other contaminants. Then these surfaces shall be steam cleaned to remove dirt, dust, mud or any other materials that could contaminate the surface. These surfaces shall then be completely dried prior to painting.

3.11.2 Contractor furnished parts. Parts not supplied as Government furnished property shall be cleaned, treated and painted in accordance with applicable drawings, color as specified in 6.2.

4. QUALITY ASSURANCE PROVISIONS

4.1 Responsibility for inspection. Unless otherwise specified in the contract or purchase order, the contractor is responsible for the performance of all inspection requirements as specified herein. Except as otherwise specified in the contract or order, the contractor may use his own or any other facilities suitable for the performance of the inspection requirements specified herein, unless disapproved by the Government. The Government reserves the right to perform any of the inspections set forth in the specification where such inspections are deemed necessary to assure supplies and services conform to prescribed requirements.

4.1.1 Acceptability criteria. Units which conform to all requirements in Section 3 and 5 of this specification and pass all applicable examinations and tests in Section 4 of this specification will be considered acceptable by the Government.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T21:25Z
Check the source to verify that this is the current version before use.

4.1.2 Component and material inspection. The contractor is responsible for insuring that components and materials used are manufactured, examined, and tested in accordance with referenced specifications and standards.

4.1.3 Disassembly inspection. Failure of any test or examination of the preproduction model shall be cause for disassembly, in the presence of a Government representative, of the preproduction model to the extent necessary to determine the cause of the failure. Each disassembled part shall be examined in detail for compliance with this specification and referenced drawings in regard to materials, dimensions, tolerances, and workmanship. Parts not complying with such requirements shall be rejected and shall be cause for rejecting the preproduction model.

4.2 Classification of inspection. Inspection shall be classified as follows:

a. Preproduction unit (see 4.3).
b. Initial production inspection (see 4.4).
c. Quality conformance inspection (see 4.5).
d. Inspection comparison (see 4.7).
e. Inspection of packaging (see 4.8).

4.3 Preproduction unit.

4.3.1 Examination. The units shall be examined for the defects specified in 4.6.1. Presence of one or more defects shall be cause for rejection.

4.3.2 Test. The units shall be tested as specified in 4.6.2.1 and 4.6.2.2. Failure of any test shall be cause for performing the inspection specified in 4.1.3.

4.4 Initial production inspection. When specified (see 3.3), one or more initial production units will be selected at random by the Government from the units being produced by production tooling and will be examined as specified in 4.6.1 and tested as specified in 4.6.2 to determine conformance to the requirements of this specification. The inspection will be performed by the Government at a site selected by the Government. Acceptance of an initial production unit shall not exclude the remaining units from the quality conformance inspection and acceptance provisions specified in Section 4. In addition to any test specified as part of the initial production test, the Government reserves the right to conduct any and all other tests contained in this specification as part of the initial production test and failure of such additional tests shall have the same effect as failure of those tests specified as initial production tests.

4.4.1 Inspection failure. Failure of an initial production unit to meet any requirement specified herein during and as a result of the examination and tests specified in 4.4 shall be cause for rejection of the initial production unit(s) and shall be cause for refusal by the Government to continue acceptance of production units until evidence has been provided by the contractor that corrective action has been taken to eliminate the deficiencies. Correction of such deficiencies shall be accomplished by the contractor at no cost to the

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T21:25Z
Check the source to verify that this is the current version before use.

Government on units previously accepted and produced under the contract. Any deficiencies found as a result of the initial production inspection will be considered prima facie evidence that all units accepted prior to the completion of initial production inspection are similarly deficient unless evidence to the contrary is furnished by the contractor and such evidence is acceptable to the contracting officer.

4.5 Quality conformance inspection.

4.5.1 Examination. Each unit shall be examined for the defects specified in 4.6.1. Presence of one or more defects shall be cause for rejection.

4.5.2 Tests. Each unit shall be tested as specified in 4.6.2.1 and 4.6.2.2. Failure of the test shall be cause for rejection.

4.6 Inspection procedure.

4.6.1 Examination. The unit shall be examined for the following defects:

101. Nonconformance to drawing requirements.
102. Components missing or not as specified.
103. Fasteners missing or insecure.
104. Electrical connections insecure.
105. Identification marking missing or not as specified.
106. Items to be furnished with the air conditioner missing or not as specified.
107. Gasketing insecure.
108. Workmanship not as specified.
109. Duct and duct adapter not compatible.

4.6.2 Tests.

4.6.2.1 Test conditions. Prior to conducting the operational tests in 4.6.2.2 the following preparation shall be made:

a. The air conditioner, multipackage, 18,000 Btu/hr, and the generator set, DED, 5kW, 60Hz shall be prepared for operation in accordance with the operator and maintenance manuals furnished with these respective Government-furnished items (see 3.8) except that the battery furnished with the generator set shall not be activated nor used. Batteries for starting and operating the generator sets during test shall be furnished by the contractor.
b. Connect the electrical grounding stud of the trailer to an earth ground.
c. Assure that the generator voltage selector switch is set to "120/208 volt, 3 phase, 4 wire" position.
d. Assure that a correct electrical connection is made between the generator set and the 18,000 Btu/hr, multipackage air conditioner.
e. The flexible air ducts shall be installed on the duct adapters.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T21:25Z
Check the source to verify that this is the current version before use.

4.6.2.2 Operational. Place the unit in an ambient temperature between 75 degrees F and 120 degrees F. Set the air conditioner selector switch and the generator set selector switch in the "OFF" position. Start the generator set as described on the "Operating Instruction" plate. After any necessary adjustments to voltage and frequency have been made, place the generator set circuit breaker in the "ON" position. Move the air conditioner temperature control knob to the maximum "Cooler" position and move the air conditioner selector switch to the "Vent" position. Determine that only the evaporator blowers are operating and turning in the correct direction. Move the air conditioner selector switch to the "Cool" position. Determine that the compressor, evaporator blowers, and condenser blowers are operating and turning in the correct direction. After 5 minutes, determine that cool air is issuing from the evaporator discharge openings. Move the air conditioner selector switch to the "OFF" position. Determine that all air conditioner components have ceased operating. Place the generator set circuit breaker in the "OFF" position and stop the generator. Nonconformance to 3.5 shall constitute failure of this test.

4.6.2.3 Roadability. The units shall be subjected to a roadability test consisting of the following test phases for a total of 400 miles:

a. 200 miles primary roads.
b. 100 miles unpaved roads.
c. 100 miles off road terrain.

The speed at which the road test is conducted shall not exceed maximum safe speed. At the completion of each test phase the air conditioner shall be inspected for failure of equipment mountings, deformed and broken body members, defective welds, shifting, loosening, and displacement of panels; deformed and broken tubing and equipment. At the conclusion of all the road tests, the unit shall be operated for a period of 4 hours to insure that all controls and components function properly. Structural damage, misalignement or malfunction of components, leaks, abnormal vibration, or any other irregular operation shall constitute failure of this test.

4.7 Inspection comparison. The Government may select units at any time during the contract production period and subject these units to the examination specified in 4.6.1 and the tests specified in 4.6.2 to determine conformance to the requirements of this specification. The inspection will be performed by the Government at a site selected by the Government, on units selected at random from those which have been accepted by the Government and will not include the previously inspected preproduction model and initial production units. In addition to any test specified as part of the inspection comparison, the Government reserves the right to conduct any and all other tests contained in this specification as part of the inspection comparison and failure of such additional tests shall have the same effect as failure of those tests specified as inspection comparison.

4.7.1 Inspection failure. Failure of an inspection comparison unit to meet any requirement specified herein during and as a result of the examination and tests specified in 4.7 shall be cause for rejection of the inspection comparison unit(s) and shall be cause for refusal by the Government to continue acceptance

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T21:25Z
Check the source to verify that this is the current version before use.

of production units until evidence has been provided by the contractor that corrective action has been taken to eliminate the deficiencies. Correction of such deficiencies shall be accomplished by the contractor at no cost to the Government on units previously accepted and produced under contract. Any deficiencies found as a result of the inspection comparison will be considered prima facie evidence that all units accepted prior to the completion of inspection comparison are similarly deficient unless evidence to the contrary is furnished by the contractor and such evidence is acceptable to the contracting officer.

4.8 Inspection of packaging.

4.8.1 Preproduction pack inspection.

4.8.1.1 Examination. The preproduction pack shall be examined for the defects specified in 4.8.2.3. Presence of one or more defect shall be cause for rejection.

4.8.2 Quality conformance inspection of pack.

4.8.2.1 Unit of product. For the purpose of inspection, a completed pack prepared for shipment shall be considered a unit of product.

4.8.2.2 Sampling. Sampling for examination shall be in accordance with MIL-STD-105.

4.8.2.3 Examination. Samples selected in accordance with 4.8.2.2 shall be examined for the following defects. AQL shall be 2.5 percent defective.

110.	Materials, methods, and containers not as specified. Each incorrect material, method, or container shall be considered one defect.
111.	Disassembly not as specified for level A or B.
112.	Matchmarking not as specified for level A or B.
113.	Unprotected metal surfaces not preserved as specified for level A or B.
114.	Canvas cover for air conditioner not secured in place when furnished.
115.	Generator set not preserved as specified for level A or B.
116.	Engine not preserved as specified.
117.	Fuel can not preserved as specified for level A or B.
118.	Air conditioner refrigeration system not pumped down and tagged as specified.
119.	Ducts not placed in the storage compartment.
120.	Duct adapters not packed as specified for level A or B.
121.	Trailer chassis components not preserved as specified for level A or B.
122.	Ground rod clamp and wire not placed in the duct storage compartment for level A or B.
123.	Fire extinguisher not packed as specified for level A or B.
124.	Technical manuals not preserved as specified.
125.	Maintenance tools not preserved as specified for level A or B.
126.	Consolidation not as specified.
127.	Housing not constructed as specified for level A.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T21:25Z
Check the source to verify that this is the current version before use.

128. Securing of the housing not as specified for level A.
129. Strapping not as specified for level A.
130. Marking missing, illegible, incorrect or incomplete.
131. Depreservation guides not furnished and located as specified.

5. PACKAGING

5.1 Preproduction pack. The contractor shall furnish a preproduction pack for examination within the time frame specified (see 6.2) to prove, prior to starting production packaging, that the applied preservation, packing and marking comply with the packaging requirements of this specification. Examination shall be as specified in Section 4 and shall be subject to surveillance and approval by the Government (see 6.8). The preproduction pack may be accomplished utilizing either the preproduction unit or a production unit. If the preproduction unit is utilized, any preservation and packing shall be removed by the contractor at no expense to the Government when requested by the Government to facilitate comparison between the first produced unit and the production unit.

5.2 Preservation. Preservation shall be level A, level B, or Commercial as specified (see 6.2).

5.2.1 Level A.

5.2.1.1 Disassembly. The duct adapters shall be removed. The electric cable from the generator to the air conditioner and the ground cables shall be removed. Any parts vulnerable to damage and any protruding parts such as exhaust stacks, air cleaner, etc. that would interfere with or cause damage to the barrier wrap or wood cap shall be removed. The rear support legs shall be retracted and the crank handles removed. The front landing leg shall be retracted and the crank handle shall be stowed in its proper location. Removed parts other than those specified above shall be limited to those parts that can be removed and reinstalled without special tools. Removed bolts, nuts, pins, screws, and washers shall be reinstalled in mating parts and secured to prevent loss.

5.2.1.2 Matchmarking. Disassembled parts shall be matchmarked when necessary to facilitate reassembly. Removed parts and mating parts on the item shall be matchmarked by stenciling on the part or by the use of tags. Tags shall conform to UU-T-81, Type A or D. Stencil ink shall conform to TT-I-1795. Printing or typing on tags shall be with waterproof ink.

5.2.1.3 Unprotected surfaces. Unprotected metal surfaces, not otherwise provided for herein, requiring the application of a contact preservative in accordance with MIL-P-116 shall be coated with type P-1 preservative. On surfaces where the type P-1 preservative would have to be removed prior to placing the equipment in service, type P-6 or P-11 preservative shall be used. Surfaces coated with type P-6 or P-11 preservative shall be wrapped with barrier material conforming to MIL-B-121, type 1, grade A, class 2 and secured with tape conforming to PPP-T-60, Type IV.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T21:25Z
Check the source to verify that this is the current version before use.

5.2.1.4 Generator set. The generator set shall be preserved in accordance with MIL-P-116, Method IIa. The generator set shall be secured directly through the barrier material to the trailer using the generator mounting bolts. Before the generator set is enclosed in the method IIa barrier, the consolidated packaging specified in 5.2.1.15, and the provisions of 5.2.1.4.1 and 5.2.1.4.2 shall be accomplished.

5.2.1.4.1 Engine. The engine shall be preserved in accordance with MIL-E-10062, Level A, Type II, Method IIa.

5.2.1.4.2 Fuel can. The fuel can shall be flushed or fogged with preservative oil conforming to type I or II, grade 30 of MIL-L-21260. The can shall be secured in its mounting bracket if provided.

5.2.1.5 Air conditioner. The refrigeration system shall be pumped down and the valves shall be closed leaving the low-pressure side of the system with a positive pressure holding charge. A tag shall be attached to the electrical power connection indicating the valves are closed and must be opened before operating the air conditioner. The canvas cover shall be placed over the air conditioner and secured in place. The air conditioner shall then be preserved in accordance with MIL-P-116, Method IIa, securing the air conditioner directly through the barrier material to the trailer floor using the air conditioner mounting bolts.

5.2.1.6 Ducts. The ducts shall be wrapped with material conforming to PPP-C-843, Type II, Class optional and placed in the duct storage compartment.

5.2.1.7 Duct adapters. The removed duct adapters with filter in place shall be placed in a close fitting box conforming to PPP-B-601, Domestic type. The duct adapters shall be wrapped with material conforming to PPP-C-843, Type II, Class optional.

5.2.1.8 Ground rod, clamp, and wire. The ground rod, clamp, and wire shall be placed in the duct storage compartment.

5.2.1.9 Repair parts. Repair parts shall be preserved in accordance with the applicable criteria of MIL-P-116.

5.2.1.10 Maintenance tools. Maintenance tools shall be preserved in accordance with PPP-P-40, Level A.

5.2.1.11 Electric cable. Removed electric cable shall be preserved in accordance with MIL-C-12000, Level A.

5.2.1.12 Technical publications. Technical publications shall be preserved in accordance with MIL-P-116, Method IC-1, and placed in the cotton duck case.

5.2.1.13 Fire extinguisher. The fire extinguisher and mounting box shall be packed in a fiberboard box conforming to PPP-B-636, W5c.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T21:25Z
Check the source to verify that this is the current version before use.

5.2.1.14 Trailer chassis. The trailer chassis shall be preserved in accordance with the level A (mobile) requirements of MIL-STD-281.

5.2.1.15 Consolidation. Any disassembled items, repair parts, tools, publications and boxed fire extinguisher shall be consolidated in the toolbox, if provided, in the pockets of the canvas cover, in the duct storage compartment or in the duct adapter box (see 5.2.1.7) as space permits.

5.2.2 Level B. Preservation shall be as specified for level A with the following exceptions.

5.2.2.1 Generator set. The generator set shall be preserved in accordance with MIL-E-16298, Level A for assembled machines using the alternate method for electric machines attached to mechanical equipment.

5.2.2.1.1 Engine. The engine shall be preserved in accordance with MIL-E-10062, Level A, Type II, Method I.

5.2.2.2 Air conditioner. The air conditioner shall be pumped down and tagged as specified in 5.2.1.5. The canvas cover shall be installed and secured.

5.2.2.3 Trailer chassis. The trailer chassis shall be preserved in accordance with the level B (mobile) requirements of MIL-STD-281.

5.2.3 Commercial. The trailer mounted air conditioner shall be preserved in accordance with the criteria of MIL-STD-1188. In addition the engine crankcase shall be filled with the required amount of lubrication oil and the cooling system shall be filled with a fresh, clean solution of 50 percent water and 50 percent antifreeze conforming to MIL-A-46153. The air conditioner shall be pumped down and tagged as specified for level A (see 5.2.1.5). The canvas cover shall be secured in place on the air conditioner.

5.3 Packing. Packing shall be level A or Commercial as specified (see 6.2).

5.3.1 Level A. The trailer mounted air conditioner shall be prepared for mobile shipment. The consolidation box shall be positioned on the floor of the trailer and secured by strapping or bolting. Strapping shall conform to QQ-S-781, Class 1, Type 1 or IV, Finish A or B. A plywood housing consisting of two ends, two sides and a top shall be fabricated to completely enclose the air conditioner, generator set, and duct storage compartment, and rest on the trailer floor. The housing shall be constructed in accordance with the requirements of PPP-B-601, Overseas Type, Style 1, and shall be modified as required to fit the trailer configuration and to permit securing the trailer frame. The housing shall be secured in place by appropriate means to prevent movement of the cover, and with not less than four steel straps. The straps shall conform to QQ-S-781, Class 1, Type I or IV, size 3/4 inch. Unless otherwise specified (see 6.2) strapping shall be finish B. When specified, finish A strapping shall be used. The strapping shall be applied by not less than two straps going completely around the housing in the longitudinal direction under the trailer frame and not less than two straps going girthwise around the housing under the trailer frame.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T21:25Z
Check the source to verify that this is the current version before use.

5.3.2 Commercial. The trailer mounted air conditioner shall be prepared for mobile shipment in a manner to assure common carrier acceptance and provide safe delivery to destination at lowest rates.

5.4 Marking.

5.4.1 Military marking. Marking for military levels of protection shall be in accordance with MIL-STD-129.

5.4.2 Commercial marking. Marking for commercial packaging shall be in accordance with MIL-STD-1188.

5.5 Depreservation guide. Two depreservation guides, DA Form 2250, shall be furnished. One shall be preserved by method IC-1 in accordance with MIL-P-116 and the bag marked to indicate "DEPRESERVATION GUIDE". The preserved guide shall be secured in a conspicious location on the equipment. The other copy shall be placed in with the technical publications".

6. NOTES

6.1 Intended use. The unit is intended for use in providing cooled air for correct functioning of military van or shelter-housed equipment and for comfort of operating personnel in applications where electric power is not available or is inadequate.

6.2 Ordering data. Procurement documents should specify the following:

a. Title, number, and date of this specification.
b. Date of issue of DoDISS applicable to this contract and exceptions thereto (see 2.1.1).
c. Time frame required for submision of preproduction unit and number of units required (see 3.2).
d. When the Government will conduct any or all of the preproduction unit examination and tests. When the Government will conduct some but not all of the preproduction units examination and tests, the contracting officer should specify which examination and tests will be conducted by the Government and which examination and tests shall be conducted by the contractor (see 3.2).
e. When initial production inspection is required and number of units to be furnished, when applicable (see 3.3).
f. When the property will not be furnished by the Government (see 3.8).
g. Time frame required for submission of the preproduction pack (see 5.1).
h. Degree of preservation and packing required (see 5.2 and 5.3).
i. When other than finish B strapping is required (see 5.3.1).
j. Color shall be as specified by contracting officer to meet the end item user requirements.

6.3 Preproduction unit. Any changes or deviations of production units from the approved preproduction unit during production will be subject to the

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T21:25Z
Check the source to verify that this is the current version before use.

approval of the contracting officer. Approval of the preproduction unit will not relieve the contractor of his obligation to furnish units conforming to this specification.

6.4 Government-furnished property. The contracting officer should arrange to furnish the property specified in 3.8. The color of this property should be as specified in 6.2. If the Government-furnished property to be furnished to the contractor is not in accordance with the color specified, the contract or order should indicate what the existing color is. The contract or order should also indicate the packaging level of the Government-furnished equipment for depreservation purposes.

6.5 Data requirements. The contracting officer should include requirements for such data as technical publications, instructional materials, illustrated parts lists, and contractor's maintenance and operation manual to be furnished with each unit.

6.6 Provisioning. The contracting officer should include provisioning requirements for repair parts and maintenance tools as necessary (including any special tools), and instructions on shipment of units. A suggested paragraph is as follows:

> "Shipment of units shall include repair parts, maintenance tools, operational instructions, and accessories, unless exceptions are provided elsewhere in the contract."

6.7 Registration numbers. The contracting officer should arrange to furnish a list of registration numbers to be applied to the trailer (see 3.7).

6.8 Preproduction pack. Any changes or deviations of production packs from the approved preproduction pack will be subject to the approval of the contracting officer. Approval of the preproduction pack will not relieve the contractor of his obligation to preserve, package, pack, and mark the unit in accordance with this specification.

6.9 Recycled material. It is encouraged that recycled material be used when practicle as long as it meets the requirements of this specification (see 3.4).

Custodian:
Army - ME

Review activity:
DLA - GS

Preparing activity:
Army - ME

Project 4120-A028

☆U.S. GOVERNMENT PRINTING OFFICE: 1992—505-022/2310

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T21:25Z
Check the source to verify that this is the current version before use.

STANDARDIZATION DOCUMENT IMPROVEMENT PROPOSAL

INSTRUCTIONS: This form is provided to solicit beneficial comments which may improve this document and enhance its use. DoD contractors, government activities, manufacturers, vendors, or other prospective users of the document are invited to submit comments to the government. Fold on lines on reverse side, staple in corner, and send to preparing activity. Attach any pertinent data which may be of use in improving this document. If there are additional papers, attach to form and place both in an envelope addressed to preparing activity. A response will be provided to the submitter, when name and address is provided, within 30 days indicating that the 1426 was received and when any appropriate action on it will be completed.
NOTE: This form shall not be used to submit requests for waivers, deviations or clarification of specification requirements on current contracts. Comments submitted on this form do not constitute or imply authorization to waive any portion of the referenced document(s) or to amend contractual requirements.

DOCUMENT IDENTIFIER *(Number)* AND TITLE MIL-A-52568C(ME) Air Conditioner, Trailer Mounted, Electric-Motor Driven, 18,000 Btu/Hr

NAME OF ORGANIZATION AND ADDRESS OF SUBMITTER

☐ VENDOR ☐ USER ☐ MANUFACTURER

1. ☐ HAS ANY PART OF THE DOCUMENT CREATED PROBLEMS OR REQUIRED INTERPRETATION IN PROCUREMENT USE? ☐ IS ANY PART OF IT TOO RIGID, RESTRICTIVE, LOOSE OR AMBIGUOUS? PLEASE EXPLAIN BELOW.

A. GIVE PARAGRAPH NUMBER AND WORDING

B. RECOMMENDED WORDING CHANGE

C. REASON FOR RECOMMENDED CHANGE(S)

2. REMARKS

SUBMITTED BY *(Printed or typed name and address — Optional)*

TELEPHONE NO.

DATE

DD FORM 1 OCT 76 1426 EDITION OF 1 JAN 72 WILL BE USED UNTIL EXHAUSTED.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T21:25Z
Check the source to verify that this is the current version before use.