MILITARY SPECIFICATION

BODY, ANTIPERSONNEL MINE, PRACTICE, M33 PARTS FOR LOADING, ASSEMBLING, AND PACKING

1. SCOPE

1.1 This specification covers the parts for loading, assembling and packing for one type of mine designated as Body, Antipersonnel Mine, Practice, M33.

2. APPLICABLE DOCUMENTS

2.1 The following documents of the issue in effect on date of invitation for bids or request for proposal, form a part of this specification to the extent specified herein.

SPECIFICATIONS

FEDERAL

PPP-T-45 - Tape, Gummed, Paper, Reinforced and Plain, for Sealing and Securing
PPP-B-636 - Box, Fiberboard

MILITARY

MIL-A-2550 - Ammunition and Special Weapons; General Specification for

STANDARDS

MILITARY

MIL-STD-105 - Sampling Procedures and Tables for Inspection by Attributes
MIL-STD-109 - Inspection Terms and Definitions

FCS: 1345

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T20:27Z
Check the source to verify that this is the current version before use.

MIL-STD-1168 - Lot Numbering of Ammunition
MIL-STD-1169 - Packaging, Packing and Marking for Shipment of Inert Ammunition Components
MIL-STD-1235 - Single and Multilevel Continuous Sampling Procedures and Tables for Inspection by Attributes

DRAWINGS

U.S. ARMY MUNITIONS COMMAND

9251501 - Body, APERS, Mine, Practice, M33

PUBLICATIONS

U.S. ARMY MUNITIONS COMMAND

ET-9251501 - Equipment Tabulation

(Copies of specifications, standards, drawings and publications required by contractors in connection with specific procurement functions should be obtained from the procuring activity or as directed by the contracting officer.)

3. REQUIREMENTS

3.1 Material.-Material shall be in accordance with applicable drawings and specifications.

3.2 Body.-The practice mine body shall comply with all requirements specified on Drawing (dwg.) 9251501, and with all requirements specified in applicable specifications.

3.3 Susceptibility to cracking

3.3.1 Case assembly.-The case assembly, dwg. 9251502, shall not crack when subjected to a load of 175 pounds, plus or minus 5 pounds when tested as specified in 4.4.1.1.

3.3.2 Cover.-The cover, dwg. 8800916, shall not crack when subjected to a load of 60 pounds, plus or minus 5 pounds, when tested as specified in 4.4.1.2.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T20:27Z
Check the source to verify that this is the current version before use.

3.3.3 Low temperature.-The cover and case assembly shall not crack when subjected to temperature conditioning at minus 65 degrees Fahrenheit, plus or minus 5 degrees, for a period of 24 hours plus or minus 1/2 hour when tested as specified in 4.4.1.3.

3.4 Workmanship.-All parts and assemblies shall be fabricated and finished in a thorough, workmanlike manner. They shall be free of burrs, chips, sharp edges, surface cracks, crazes, porosity, warpage, burn marks, checks, blisters, excess flash, unblended radii, chipped edges, scratches, dirt, grease, rust, corrosion products and other defects and foreign matter which would affect appearance or serviceability. The cleaning method used shall not be injurious to any part nor shall the parts be contaminated by the cleaning agent. All required markings shall be neat, legible and sharply defined.

3.5 First article inspection.-This specification makes provisions for first article inspection. Requirements for the submission of first article samples by the contractor shall be as specified in the contract.

4. QUALITY ASSURANCE PROVISIONS

4.1 Responsibility for inspection.-Unless otherwise specified in the contract or purchase order, the supplier is responsible for the performance of all inspection requirements as specified herein. Except as otherwise specified in the contract or order, the supplier may use his own or any facilities suitable for the performance of the inspection requirements specified herein, unless disapproved by the Government. The Government reserves the right to perform any of the inspection set forth in the specification where such inspections are deemed necessary to assure supplies and services conform to prescribed requirements. Reference shall be made to MIL-STD-109 to define terms used herein. The provisions of MIL-A-2550 shall apply.

4.1.1 Submission of product.-At the time each completed lot of items deliverable under the contract is submitted to the Government for acceptance, the contractor shall supply the following information accompanied by a certificate which attests that the information provided is correct and applicable to the product being submitted:

a. A statement that the lot complies with all of the quality assurance provisions specified in this specification.
b. Drawing and specification number and date, together with identification and date of changes thereto.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T20:27Z
Check the source to verify that this is the current version before use.

c. A statement that all material purchased by the contractor meets requirements, when such material is controlled by the Government or commercial specifications referenced in any of the contractual documents, and that certificates of conformance are on file and available for review.

d. Number of items in the lot.

e. Date submitted.

The certificate shall be signed by a responsible agent of the certifying organization. The initial certificate submitted shall be substantiated by evidence of the agent's authority to bind his principal. Substantiation of the agent's authority will not be required with subsequent certificates unless, during the course of the contract, this authority is vested in another agent of the certifying organization.

4.2 First article inspection

4.2.1 Submission.-The contractor shall submit a first article sample as designated by the Contracting Officer for evaluation in accordance with the provisions of 4.2.2. The first article sample shall consist of 15 complete assemblies and 15 complete sets of parts (i.e., 15 each of every individual component and every subassembly, including at least three items from each cavity used to produce plastic parts and so identified as to permit tracing each item to the cavity in which it was molded) which have been produced by the contractor or furnished by a supplier and which have been manufactured using the same production processes, procedures and equipment which will be used in fulfilling the contract. All parts and materials, including packaging and packing shall be obtained from the same source of supply as will be used in regular production. Prior to submission, the contractor shall inspect the sample to the degree necessary to assure that it conforms to the requirements of the contract and he shall submit a record of this inspection with the sample, including certificates of conformance for materials. A sample containing known defects shall not be submitted unless specifically authorized by the contracting officer. A first article sample, or portion thereof, as directed by the contracting officer shall also be submitted whenever there is a lapse in production for a period in excess of 90 days, or whenever a change occurs in manufacturing process, material used, drawing or specification such as to significantly affect product uniformity as determined by the Government. In the event of rejection, the Government reserves the right to require the contractor to take corrective action and submit an additional sample or portion thereof of items for first article inspection. Until a first article sample is accepted, the contractor is, in no way, authorized by the Government to initiate regular production unless otherwise directed by the contracting officer.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T20:27Z
Check the source to verify that this is the current version before use.

4.2.2 Inspections to be performed.-Assemblies, sub assemblies and components shall be subjected by the Government to any or all of the examinations specified in 4.3 of this specification and any or all requirements of the applicable drawings. After classification of defects and other inspections have been performed as specified, the following components and subassemblies shall be subjected to test as indicated below:

a. Susceptability to cracks under loading (see 3.3.1 and 3.3.2) - 5 case assemblies, 5 covers.

b. Susceptability to cracks at low temperatures (see 3.3.3) - 5 case assemblies, 5 covers.

4.2.3 Rejection.-If any assembly, subassembly or component fails to comply with any of the applicable requirements, the first article sample shall be rejected. The Government reserves the right to terminate its inspection upon any failure of an assembly, subassembly or component to comply with any of the stated requirements.

4.3 Inspection provisions

4.3.1 Lot formation.-The term "inspection lot" as used in this specification is defined as an essentially homogeneous collection of units of product from which a representative sample is drawn and inspected to determine conformance with applicable requirements. The sample selected shall represent only that quantity of units from which the sample was drawn and shall not be construed to represent any prior or subsequent quantities presented for inspection. Homogeneity shall be considered to exist provided the inspection lot has been produced by one manufacturer, in one unchanged process, using the same materials and methods, in accordance with the same drawings, same drawing revisions, same specifications and same specification revisions and complies with the provisions for submission of product as specified in MIL-STD-105. Changes to the process, specifications, or drawings not affecting safety, performance, interchangeability, or storage as determined by the Government, shall not be deemed to alter the homogeneity of an inspection lot. All material submitted for inspection in accordance with this specification shall comply with the homogeneity criteria specified herein regardless of the type of sampling procedure which is being applied to determine conformance with requirements. Lot numbering, as required, shall be in accordance with MIL-STD-1168. Each inspection lot of complete practice body assemblies shall contain parts of one lot interfix number from one supplier.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T20:27Z
Check the source to verify that this is the current version before use.

4.3.1.1 Process specification.-A process specification specifying the time, temperature and pressure ranges which shall be maintained during production of the molded parts shall be kept on file and available for review.

4.3.2 Examination.-The examinations listed in the following subparagraphs shall be performed on inspection lots (see 4.3.1) of the components or assemblies designated in the applicable paragraph headings. Inspection for critical defects (and major defects, when so specified) shall be 100 percent. Sampling plans for major and minor defects shall be in accordance with MIL-STD-105 except that continuous sampling plans in accordance with MIL-STD-1235 may be used if approved by the Government. Instead of applying the AQL's designated herein to the groups of major and minor defects listed, the contractor may elect to apply AQL's to individual defects using an AQL of 0.40 percent for each major defect and an AQL of 0.65 percent for each minor defect. When this method is elected, it shall be applied to all of the major and minor defects listed in the applicable subparagraphs of this section, except where 100 percent inspection is specified, and be documented as part of the contractor's inspection system. Equipment necessary for the performance of the inspections listed shall be in accordance with 4.3.4.

4.3.2.1 Case (see dwg. 8800915 covering a detail of dwg. 9251501)

Categories	Defects	Method of Inspection	Code No. (see 6.2)
Critical:	None defined		
Major:	AQL 1.00 percent		
101.	Case split to extent that functioning may be impaired	Visual	01001
102.	Fillet to face of snap tabs improper	Visual	01002
103.	Start of perfect thread incorrectly located	Gage	01003
104.	Depth of thread cavity	Gage	01004
105.	Depth to bottom of undercut below threads, maximum (max.)	Gage	01005
106.	Location of well recesses	Gage	01006
107.	Height front to rear knife edge	Gage	01007
108.	Pitch diameter of threads	Gage	01008
Minor:	AQL 1.00 percent		
201.	Knife edges of sight have flash or nicks	Visual	01009

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T20:27Z
Check the source to verify that this is the current version before use.

202.	Evidence of poor workmanship (see 3.4)	Visual	01027

4.3.2.2 Cover (see dwg. 8800916 covering a detail of dwg. 9251501)

Categories	Defects	Method of Inspection	Code No.
Critical:	None defined		
Major:	AQL 0.40 percent		
101.	Cover split to extent that functioning may be impaired	Visual	02001
Minor:	AQL 0.65 percent		
201.	Evidence of poor workmanship (see 3.4)	Visual	02002

4.3.2.3 Case assembly (see dwg. 9251502 covering a detail of dwg. 9251501)

Categories	Defects	Method of Inspection	Code No.
Critical:	None defined		
Major:	AQL 0.65 percent		
101.	Length across snap tabs	Gage	03001
102.	Width across snap tabs	Gage	03002
103.	Outside length of mating lip section	Gage	03003
104.	Outside width of mating lip section	Gage	03004
Minor:	AQL 1.50 percent		
201.	Missing parts	Visual	03005
202.	Torque to move legs	Test	03006
203.	Torque to move brackets	Test	03007
204.	Evidence of poor workmanship (see 3.4)	Visual	03008

4.3.2.4 Cup, well (see dwg. 8837133 covering a detail of dwg. 9251501)

Categories	Defects	Method of Inspection	Code No.
Critical:	None defined		

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T20:27Z
Check the source to verify that this is the current version before use.

Major:	AQL 0.40 percent		
101.	Flange diameter	Gage	04001
Minor:	AQL 0.65 percent		
201.	Evidence of poor workmanship (see 3.4)	Visual	04002

4.3.2.5 Shipping plug - priming adapter (see dwg. 8857210 covering a detail of dwg. 9251501)

Categories	Defects	Method of Inspection	Code No.
Critical:	None defined		
Major:	AQL 0.65 percent		
101.	Start of perfect thread, plug end	Gage	05001
102.	Start of perfect thread, split end	Gage	05002
103.	Slot width, minimum (min.)	Gage	05003
Minor:	AQL 0.65 percent		
201.	Evidence of poor workmanship (see 3.4)	Visual	05004

4.3.2.6 Case assembly, loaded (see dwg. 9251502 covering a detail of dwg. 9251501)

Categories	Defects	Method of Inspection	Code No.
Critical:	None defined		
Major:	None defined		
Minor:	AQL 1.50 percent		
201.	Snap tab(s) missing or damaged	Visual	06001
202.	Marking misleading or unidentifiable	Visual	06002
203.	Evidence of poor workmanship (see 3.4)	Visual	06003

4.3.2.7 Assembly (see dwg. 9251501)

Categories	Defects	Method of Inspection	Code No.
Critical:	None defined		

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T20:27Z
Check the source to verify that this is the current version before use.

Major:	AQL 0.40 percent		
101.	Well cup or shipping plug missing, damaged or improperly assembled	Visual	07001
102.	Leg assembly damaged (bent or twisted)	Visual	07002
Minor:	AQL 2.50 percent		
201.	Excessive cement	Visual	07003
202.	Edges chipped or broken	Visual	07004
203.	Crack or split	Visual	07005
204.	Marking misleading or unidentifiable	Visual	07006
205.	Color incorrect	Visual	07007
206.	Evidence of poor workmanship (see 3.4)	Visual	07008

4.3.2.8 Carton sealed (see section 5)

Categories	Defects	Method of Inspection	Code No.
Critical:	None defined		
Major:	AQL 0.65 percent		
101.	Contents move when carton is shaken (insufficient filler material)	Manual	08001
102.	Carton damaged so that contents are exposed or liable to become exposed	Visual	08002
103.	Sealing strip incomplete, badly wrinkled, or not fully attached to surface around entire carton	Visual	08003
Minor:	AQL 0.65 percent		
201.	Marking misleading or unidentifiable	Visual	08004

4.3.3 Testing

4.3.3.1 Susceptability to cracking

4.3.3.1.1 Case assembly (see 3.3.1), Major Defect, Code No. 03009.-A sample of twenty case assemblies shall be selected from each lot for this test. If any assembly fails to comply with the specified requirement the lot shall be rejected. The test shall be performed as specified in 4.4.1.1. (Non-destructive test, samples may be returned to the lot)

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T20:27Z
Check the source to verify that this is the current version before use.

4.3.3.1.2 Cover (see 3.3.2), Major Defect, Code No. 02003.-A sample of twenty covers shall be selected from each lot for this test. If any cover fails to comply with the specified requirement, the lot shall be rejected. The test shall be performed as specified in 4.4.1.2. (Non-destructive test, samples may be returned to the lot).

4.3.3.1.3 Low temperature (see 3.3.3) Major Defects, Code No. 03010, Case assembly and Code No. 02016, Cover.-A sample of fifteen case assemblies and fifteen covers shall be selected from each lot for this test. If any case assembly or cover fails to comply with the specified requirement, the lot represented by the sample shall be rejected. The test shall be performed as specified in 4.4.1.3. (Non-destructive test, samples may be returned to the lot).

4.3.4 Inspection equipment.-Equipment Tabulation Number ET-9251501 identifies the inspection equipment required to perform the examinations and tests prescribed in this section. The contractor shall design inspection equipment in accordance with the instructions in paragraph 6.3.

4.3.4.1 Government rights to documentation.-Inspection equipment drawings and lists provided and revised in accordance with the requirements of the ET may be used by DOD activities for design, procurement, manufacture, testing, evaluation, production and receiving inspection, overhaul, shipping, storage, identification of stock, ordering and storage of replacement parts, inspection of items at overhaul, general maintenance of equipment, construction, survey and whenever inspection equipment drawings are needed.

4.3.5 Dimensional control of plastic parts.-In place of the normal sampling and inspections associated with the Classification of Defects, and after a curing time for the parts has been approved (see Note 1) a sample of three (3) parts (as molded) from each cavity shall be fully inspected dimensionally to qualify a new or reworked cavity for use in production. The molded parts shall carry the individual cavity identification. As a control of each cavity during production, the above quantity of parts from each cavity shall be inspected for at least the defects listed in paragraphs 4.3.5.1 through 4.3.5.3 after continuous production of each 5,000 parts or at the end of each week, whichever occurs first. Of the three (3) samples, one (1) sample shall be the last part produced. If any defective parts are found during qualification of the cavity, the cavity producing the defective part will not be used in production. If any defective parts are found when inspection is performed for the control of the cavity, the cavity producing the defective part shall be re-

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T20:27Z
Check the source to verify that this is the current version before use.

moved from production. Further, that portion of production since the last control check shall be returned to the contractor for inspection for each separate type of defect according to MIL-STD-105, using an AQL of 0.40 percent for each major defect and an AQL of 0.65 percent for each minor defect. All cavities removed from production because of some fault, may after re-working, be returned to production providing they pass the qualification test above. The contractor may request a change of inspection frequency providing he presents objective evidence to the contracting officer to substantiate the request. Contractor design of gages and test equipment required to perform the inspections listed herein shall be forwarded to Commanding Officer, Picatinny Arsenal, Dover, New Jersey 07801, ATTN: SMUPA-QA-A-M for approval prior to manufacture of equipment. The following subparagraphs identify those items and minimum inspections subject to the requirements of this paragraph. A defect classification of Minor is assigned to all defects listed herein.

NOTE 1.-In establishing a curing time, dimensionally check ten (10) parts from each cavity at periodic intervals (e.g. every 30, 60, etc. mins.) until dimensional stability is attained. The curing time will be from the time the part comes out of the mold until dimensional stability is attained. The inspection data used in determing the curing time shall be sent to Picatinny Arsenal, Dover, New Jersey 07801, ATTN: SMUPA-QA-A-M. If any new change in material, cycle time, a reworked cavity, or a new cavity is used, a new curing time shall be established and approved.

4.3.5.1 Case (see dwg. 8800915)

Defects	Method of Inspection	Code No.
1. Marking misleading or unidentifiable	Visual	01010
2. Radius of mating lip edge incorrect	Visual	01011
3. Radii and fillets incorrect	Visual	01012
4. Height of mating lip above peripheral band	Gage	01013
5. Outside corner radius (4) of lip	Gage	01014
6. Thickness of front face, in area of 4 corners	Gage	01015
7. Thickness of walls, 4 sides	Gage	01016
8. Thickness of 4 eyepiece stiffener webs	Gage	01017
9. Thickness of 2 knifedge sections	Gage	01018
10. Outside diameter of well bodies	Gage	01019
11. Width of (4) snap tabs	Gage	01020
12. Bracket hole locations front to rear	Gage	01021
13. Bracket hole diameters	Gage	01022
14. Diameter of undercut below threads	Gage	01023
15. Height of peripheral band, 4 sides	Gage	01024
16. Width of clearance slots behind wells	Gage	01025

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T20:27Z
Check the source to verify that this is the current version before use.

17. Height of clearance slots behind walls.	Gage	01026

4.3.5.2 Cover (see dwg. 8800916)

Defects	Method of Inspection	Code No.
1. Marking misleading or unidentifiable...	Visual	02004
2. Radii and fillets incorrect.....	Visual	02005
3. Lip thickness, 8 places.....	Gage	02006
4. Face thickness, 4 places.....	Gage	02007
5. Width of cutouts.....	Gage	02008
6. Height of lip above cutouts, 3 places..	Gage	02009
7. Height of top cutout tab.....	Gage	02010
8. Location of cutouts.....	Gage	02011
9. Inside lip height, 2 sides.....	Gage	02012
10. Inside width.....	Gage	02013
11. Inside length.....	Gage	02014
12. Lip contour out of drawing limits.....	Gage	02015

4.3.5.3 Shipping plug - priming adapter (see dwg. 8857210)

Defect	Method of Inspection	Code No.
1. Overall height of plug end.....	Gage	05005
2. Overall height of split end.....	Gage	05006
3. Height of plug boss.....	Gage	05007
4. Height of plug end threaded section....	Gage	05008
5. Height of slit end threaded section....	Gage	05009
6. Depth of counterbore.....	Gage	05010
7. Height to major diameter, 2 places.....	Gage	05011
8. Height to pitch diameter, 2 places.....	Gage	05012
9. Thread major diameter, 2 places.....	Gage	05013
10. Thread pitch diameter, 2 places.....	Gage	05014
11. Boss diameter incorrect, 2 places.....	Gage	05015
12. Counterbore diameter.....	Gage	05016
13. Optional hole diameter oversize.....	Gage	05017
14. Optional hole depth oversize.....	Gage	05018
15. Small adapter hole diameter.....	Gage	05019
16. Countersink missing or incorrect.....	Visual	05020

4.3.6 Dimensional control of stamped parts.-To qualify a new or reworked tool to be used in the stamping process for use in production, a sample of at least ten (10) parts shall be fully inspected dimensionally. As a control of each tool during production, the above quantity of parts from each tool shall be inspected for at least the defects specified in 4.3.6.1 through 4.3.6.3 after each hours production. If any defective parts are found during qualification of the tool it shall not be used in production. If any defective parts are found when inspection is performed for the control of the tool, the tool producing the defect shall be removed from production. Further, that portion

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T20:27Z
Check the source to verify that this is the current version before use.

of production since the last control check shall be returned to the contractor for inspection for each separate type of defect according to MIL-STD-105, using an AQL of 0.40 percent for each major defect and an AQL of 0.65 percent for each minor defect. All tools removed from production because of some fault, may after reworking, be returned to production providing they pass the qualification test above. The contractor may request a change of inspection frequency providing he presents objective evidence to the contracting officer to substantiate the request. Contractor designs of gages and test equipment required to perform the inspections liste/ herein shall be forwarded to Commanding Officer, Picatinny Arsenal, Dover, New Jersey 07801 ATTN: SMUPA-QA-A-M for approval prior to manufacture of equipment. The following subparagraphs identify those items and minimum inspections subject to the requirements of this paragraph. A defect classification of Minor is assigned to all defects listed herein.

4.3.6.1 Bracket, angle (see dwg. 8800907)

Defects	Method of Inspection	Code No.
1. Bend angle	Gage	09001
2. Hole location, 2 places	Gage	09002
3. Hole diameter, 2 places	Gage	09003
4. End radius, 2 places	Gage	09004
5. Evidence of poor workmanship (see 3.4)	Visual	09005

4.3.6.2 Leg (see dwg. 8800908)

Defects	Method of Inspection	Code No.
1. Offset depth	Gage	10001
2. Hub diameter	Gage	10002
3. Hole diameter	Gage	10003
4. Length hole to tip	Gage	10004
5. Evidence of poor workmanship (see 3.4)	Visual	10005

4.3.6.2 Cup, well (see dwg. 8837133)

Defects	Method of Inspection	Code No.
1. Length, min	Gage	04003
2. Inside diameter	Gage	04004
3. Wall thickness	Gage	04005
4. Bottom thickness	Gage	04006

4.4 Test Methods and Procedures

4.4.1 Susceptability to cracks under loading

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T20:27Z
Check the source to verify that this is the current version before use.

4.4.1.1 Case assembly.-The case assembly shall be placed on a flat dry steel surface of 60 microinch finish with the convex curved face facing upward. The sight area shall be allowed to overhang the side of the steel surface so that the sides of the case assembly lie flat on the testing surface. A load of 175 pounds plus or minus 5 pounds shall be applied with a flat plate, five inches square minimum, centered over the convex curved face. The load shall be applied and held for a period of 5 seconds minimum and care shall be taken to avoid a sudden application of the load with consequent risk of exceeding the requirement. Observation shall be made for evidence of cracks, including hairline cracks, as evidence of noncompliance with 3.3.1.

4.4.1.2 Cover.-The cover shall be placed on a flat dry steel surface of 60 microinch finish with the concave curved face facing downward. A load of 60 pounds plus or minus 5 pounds shall be applied with a flat plate, 3 3/4 inches square centered over the convex curved face. The load shall be applied and held for a period of 5 seconds minimum and care shall be taken to avoid a sudden application of the load with consequent risk of exceeding the requirement. Observation shall be made for evidence of cracks, including hairline cracks, as evidence of noncompliance with 3.3.2.

4.4.1.3 Low temperature.-The case assembly and the cover shall be placed in a cold temperature chamber in such a manner that no external mechanical stresses are applied. The case shall be maintained at a temperature of minus sixty-five degrees Fahrenheit plus or minus 5 degrees for a period of 24 hours, plus or minus 1/2 hour. Observation shall be made for evidence of cracks, including hairline cracks, as evidence of non-compliance with 3.3.3.

5. PREPARATION FOR DELIVERY

5.1 Preservation and packaging

5.1.1 Level C.-The Body, Antipersonnel, Mine, Practice, M33 shall be packaged in accordance with Standard MIL-STD-1169.

5.2 Packing

5.2.1 Level C.-The Body, Antipersonnel, Mine, Practice, M33 shall be packed in accordance with Standard MIL-STD-1169. The following additional packing requirements shall apply.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T20:27Z
Check the source to verify that this is the current version before use.

Thirty (30) mine bodies shall be packed leg-end down in a fiberboard box with interior half-slotted partitions assembled to form 30 individual cells in 3 by 5 arrangement. A filler pad shall be inserted in the bottom of the box, between layers, and on the top layer of cells. The inside dimension of each cell shall be 8 1/2 by 2 1/16 by 5 1/2 inches deep. The inside dimensions of the box shall be 25 13/16 by 10 7/8 by 11 3/8 inches deep. The filler pads shall be 25 3/4 by 10 3/4 inches. The box shall by Style RSC, conforming to Specification PPP-B-636, Type CF, Class Domestic, Variety SW, Grade 200. The partitions and filler pads shall be constructed of the same fiberboard as the box. Minor changes in dimensions to provide a tight pack are permissable.

Top and bottom flaps of the box shall be sealed by applying 2 inch wide gummed kraft tape conforming to Specification PPP-T-45, Type III, Grade B, over the entire length of all seams, with an extension of a minimum of 2 inches onto the end panels, and around all corners of the box.

6. NOTES

6.1 Ordering data.-Procurement documents shall specify the following:

a. Title, number and date of this specification.
b. Data cards.-Data cards shall be prepared for each lot in accordance with the information specified in Standard MIL-STD-1167.
c. Provisions for submission of first article samples.

6.2 Inspection code numbers.-The five digit code numbers assigned to the inspections herein are to facilitate future data collection and analysis by the Government. These code numbers are also used to correlate the characterisitics cited on Equipment Lists with the inspections listed in this specification. In addition, they should be cited as references on drawings of equipment designs submitted by the contractor to the Government for approval (see 6.3.5).

6.3 Inspection equipment.-The contractor shall design inspection equipment as required by the inspection Equipment Lists (EL) referenced on the applicable ET in accordance with the instructions of paragraphs 6.3.1 through 6.3.5.

6.3.1 Inspection equipment lists (EL).-Inspection equipment lists indicate the availability of inspection equipment designs by showing in the "number" column of the list of inspection

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T20:27Z
Check the source to verify that this is the current version before use.

equipment (Form SMUPA 1010) the numbers of drawings or Federal Stock numbers of existing equipment designs, or codes as indicated in paragraph 6.3.2. Design action required of the contractor is described in paragraphs 6.3.3 and 6.3.4. The contractor will be required to prepare detailed drawings in accordance with 6.3.4 for all the equipment coded as "Contractor Design" in the number column. These contractor designs must be approved by the Government prior to fabrication or procuring of the equipment. Designs shall be submitted for approval as specified in 6.3.5.

6.3.2 Inspection equipment list codes.-The inspection equipment as defined in 6.3.3 and 6.3.4 will be designated in the EL by the following codes:

CD = Contractor design on controlled contractor format and/or commercial equipment
MU = Army design, mandatory for use

6.3.3 Army designs.-Army designs are reflected on detailed drawings which completely depict all the information necessary for the fabrication of the item of inspection equipment. The contractor need provide no design when an Army design is listed for an item of inspection equipment. Army designs fall into two basic classifications; mandatory (designated "MU") and non-mandatory (indicated by drawing or Federal Stock Number). When an inspection equipment list references mandatory Army designs, the contractor shall comply with, and use these designs accordingly. The contractor may, however, in connection with non-mandatory designs, design alternate inspection equipment or use comparable commercial equipment to facilitate his operations. Such contractor prepared designs or commercial equipment selections must be approved by the Government prior to fabrication or procuring of the equipment. Designs shall be submitted for approval as specified in 6.3.5.

6.3.4 Contractor designs.-Contractor designs are designs of inspection equipment for which the Government has assigned design responsibility to the contractor. Contractor designs shall be supported by detailed drawings which depict all the information necessary to completely fabricate, calibrate and operate an item of inspection equipment. This requires that the necessary views, dimensions, materials, finishes, notes, operating and calibration instructions be properly depicted in accordance with approved practices to the extent that further calculation or clarification will not be required. Unless otherwise specified, contractor designs may be developed on the format the contractor normally employs in his equipment design procedure provided such format reflects the detail and information specified above, subject

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T20:27Z
Check the source to verify that this is the current version before use.

to the following controls: All submitted contractor designs shall conform to MIL-D-1000, Category A, form 2. Legibility and reproducibility shall permit conventional making of clearly understandable, high contrast reproductions. Contractors shall submit three copies of final designs as a flat set. Designs shall be submitted for approval as specified in 6.3.5.

6.3.5 Submission of contractor designs.-All submitted designs shall contain a reference to the applicable five digit code number contained in Section 4 of this specification and the appropriate component or assembly drawing number and revision letter to which the specific design applies. Unless otherwise specified on the EL, all designs of equipment for inspection of defects classified as critical and major shall be submitted for approval to the Commanding Officer, Picatinny Arsenal, ATTN: SMUPA-QA-A-M. All other designs of inspection equipment shall be approved by the inspection element of the agency administering the contract; submission shall be as directed by the contracting officer. Partial submission of inspection equipment designs is permissible and encouraged. However, The Arsenal completion date for design review will be based on the date of the final submission of designs. Picatinny Arsenal design review will be accomplished normally within one month after receipt.

Custodian:
Army-MU

Preparing activity:
Army-MU

Project Number: 1345-A-297

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T20:27Z
Check the source to verify that this is the current version before use.