MILITARY SPECIFICATION

# FUZE, MINE, AT, M608
# LOADING, ASSEMBLING AND PACKING

## 1. SCOPE

1.1 This specification covers the loading, assembling and packing for one type of fuze and arming cap assembly designated as Fuze, Mine, Antitank, M608.

## 2. APPLICABLE DOCUMENTS

2.1 The following documents, of the issue in effect on date of invitation for bids or request for proposal, form a part of this specification to the extent specified herein.

SPECIFICATIONS

MILITARY

MIL-A-2550 - Ammunition and Special Weapons; General Specification For

STANDARDS

MILITARY

MIL-STD-105 - Sampling Procedures and Tables For Inspection by Attributes (ABC-STD-105)
MIL-STD-109 - Quality Assurance Terms and Definitions
MIL-STD-331 - Fuze and Fuze Components, Environmental and Performance Tests For
MIL-STD-1168 - Lot Numbering of Ammunition
MIL-STD-1235 - Single and Multilevel Continuous Sampling Procedures and Tables For Inspection by Attributes

DRAWINGS

U.S. ARMY MUNITIONS COMMAND

8876062 - Carton, Packing, Ammunition, for Fuze, Mine, AT, M608
8876063 - Box, Wirebound, Packing, Ammunition, for Fuze, Mine, AT, M608
8889500 - Fuze Assembly



Source: https://assist.dla.mil -- Downloaded: 2026-10-22T20:18Z
Check the source to verify that this is the current version before use.

8889507 - Lead Assembly
9204009 - Fuze and Arming Cap Assembly, M608
9204010 - Knob Assembly, Arming
9204021 - Ring, Retaining
9204022 - Body, Arming Cap

PUBLICATIONS

U.S. ARMY MUNITIONS COMMAND

ET-9204009 - Equipment Tabulation

(Copies of specifications, standards, drawings and publications required by suppliers in connection with specific procurement functions should be obtained from the procuring activity or as directed by the contracting officer.)

3. REQUIREMENTS

3.1 Material.-The material shall be in accordance with applicable specifications and drawings.

3.2 Assembly.-The assembly shall comply with all requirements specified on Drawings (dwgs.) 8889500 and 9204009 and with all requirements specified in applicable specifications.

3.3 Waterproofness.-The fuze assembly (dwg. 8889500) shall withstand submersion in water as evidenced by satisfactory functioning when tested as specified in 4.4.4.

3.4 Transportation-vibration.-The fuze and arming cap assembly shall withstand the transportation-vibration test when tested as specified in 4.4.3.

3.5 Functioning.-The fuze and arming cap assembly shall function in the ARMED position at between 250 and 450 milliseconds when a load of 70 pounds, plus or minus 5 pounds, is applied to the top of the assembly. The test shall be performed as specified in 4.4.5.

3.6 Non-functioning.-The fuze and arming cap assembly shall not function in the SAFE position when a load of 75 pounds minimum (min.) is applied for 0.5 second, min., when tested as specified in 4.4.6.



Source: https://assist.dla.mil -- Downloaded: 2026-10-22T20:18Z
Check the source to verify that this is the current version before use.

3.7 Jolt.-The fuze and arming cap assembly shall not function during the test, and shall be safe to handle after the test specified in 4.4.7.

3.8 Jumble.-The fuze and arming cap assembly shall not function during the test, and shall be safe to handle after the test specified in 4.4.8.

3.9 Workmanship.-All parts and assemblies shall be fabricated and loaded in a thorough, workmanlike manner. They shall be free of burrs, sharp edges, cracks, chips, dirt, grease, rust, corrosion products and other foreign material. The cleaning method used shall not be injurious to any of the parts nor shall the parts be contaminated by the cleaning agent. Surface coatings shall be continuous except for a few slight scratches not exposing base material. All required markings shall be neat and sharply defined.

3.10 First article inspection.-This specifications makes provisions for first article inspection. Requirements for the submission of first article samples by the contractor shall be as specified in the contract.

## 4. QUALITY ASSURANCE PROVISIONS

4.1 Responsibility for inspection.-Unless otherwise specified in the contract or purchase order, the supplier is responsible for the performance of all inspection requirements as specified herein. Except as otherwise specified in the contract or order, the supplier may use his own or any other facilities suitable for the performance of the inspection requirements specified herein, unless disapproved by the Government. The Government reserves the right to perform any of the inspections set forth in the specification where such inspections are deemed necessary to assure supplies and services conform to prescribed requirements. Reference shall be made to MIL-STD-109 to define terms used herein. The provisions of MIL-A-2550 shall apply.

4.1.1 Submission of product.-At the time each completed lot of items deliverable under the contract is submitted to the Government for acceptance, the contractor shall supply the following information accompanied by a certificate which attests that the information provided is correct and applicable to the product being submitted:

a. A statement that the lot complies with all of the quality assurance provisions specified in this specification.



Source: https://assist.dla.mil -- Downloaded: 2026-10-22T20:18Z
Check the source to verify that this is the current version before use.

b. Drawing and specification number and date, together with identification and date of changes thereto.

c. A statement that all material purchased by the contractor meets requirements, when such material is controlled by Government or commercial specifications referenced in any of the contractual documents, and that certificates of conformance are on file and available for review.

d. Number of items in the lot.

e. Date submitted.

The certificate shall be signed by a responsible agent of the certifying organization. The initial certificate submitted shall be substantiated by evidence of the agent's authority to bind his principal. Substantiation of the agent's authority will not be required with subsequent certificates unless, during the course of the contract, this authority is vested in another agent of the certifying organization.

4.2 First article inspection

4.2.1 Submission.-Prior to the start of regular production, the contractor shall submit a first article sample (see 6.1c) to a Government approved facility as designated by the contracting officer for evaluation in accordance with the provisions of 4.2.2. The first article sample shall consist of eighty consecutively produced assemblies (thirty of which shall be inert loaded assemblies) which have been produced by the contractor and which have been manufactured using the same production processes, procedures and equipment which will be used in fulfilling the contract. All parts and materials, including packaging and packing, shall be obtained from the same source of supply as will be used in regular production. Prior to submission, the contractor shall inspect the sample to the degree necessary to assure that it conforms to the requirements of the contract and submit a record of this inspection with the sample, including certificates of conformance for materials. A sample containing known defects will not be submitted unless specifically authorized by the contracting officer. A first article sample, or portion thereof, as directed by the contracting officer, shall also be submitted whenever there is a lapse in production for a period in excess of 90 days or whenever a change occurs in manufacturing process, material used, drawing or specification such as to significantly affect product uniformity as determined by the Government.



Source: https://assist.dla.mil -- Downloaded: 2026-10-22T20:18Z
Check the source to verify that this is the current version before use.

4.2.2 Inspections to be performed.-Assemblies will be subjected by the Government to any or all of the examinations or tests specified in 4.3.2 and 4.3.3 of this specification and any or all requirements of the applicable drawings. In addition, the following testing will be performed.

4.2.2.1 Waterproofness (see 3.3).-Ten loaded assemblies shall be selected from the first article sample for this test. The test shall be performed as specified in 4.4.4.

4.2.2.2 Transportation-vibration (see 3.4).-Ten inert loaded assemblies and ten loaded assemblies other than those used for the waterproofness test shall be selected from the first article sample for this test. The test shall be performed as specified in 4.4.3.

4.2.2.3 Non-functioning (see 3.6).-Thirty loaded assemblies, consisting of the twenty assemblies from paragraphs 4.2.2.1 and 4.2.2.2, shall be tested for non-functioning as specified in 4.4.6. This test shall be performed after the waterproofness and transportation-vibration tests and prior to the functioning test.

4.2.2.4 Jolt (see 3.7).-Ten inert assemblies and ten loaded assemblies shall be selected from the first article sample for this test. The test shall be performed as specified in 4.4.7. These samples shall not be tested for functioning or non-functionings.

4.2.2.5 Jumble (see 3.8).-Ten inert assemblies and ten loaded assemblies shall be selected from the first article sample for this test. The test shall be performed as specified in 4.4.8. These samples shall not be tested for functioning or non-functioning.

4.2.3 Rejection.-If any assembly fails to comply with any of the applicable requirements, the first article sample shall be rejected. The Government reserves the right to terminate its inspection upon any failure of any assembly in the sample to comply with any of the stated requirements.

4.3 Inspection provisions

4.3.1 Lot formation.-The term "inspection lot" as used in this specification is defined as an essentially homogeneous collection of units of product from which a representative sample is drawn and inspected to determine conformance with applicable requirements. The sample selected shall represent only that quantity of units from which the sample was drawn and shall not be construed to represent any prior or subsequent quantities presented for inspection. Homogeneity shall be considered to



Source: https://assist.dla.mil -- Downloaded: 2026-10-22T20:18Z
Check the source to verify that this is the current version before use.

exist provided the inspection lot has been produced by one manufacturer in one unchanged process, using the same materials and methods in accordance with the same drawings, same drawing revisions, and same specifications and same specification revisions and complies with the provisions for submission of product as specified in MIL-STD-105. Changes to the process, specifications, or drawings not affecting safety, performance, interchangeability, or storage, as determined by the Government, shall not be deemed to alter the homogeneity of an inspection lot. All material submitted for inspection in accordance with this specification shall comply with the homogeneity criteria specified herein regardless of the type of sampling procedure which is being applied to determine conformance with requirements. Lot number, as required, shall be in accordance with MIL-STD-1168. Each inspection lot of loaded fuzes shall contain:

a. Parts of not more than one lot interfix number from one manufacturer.

b. Detonators from not more than one lot.

c. Lead assemblies containing RDX from not more than one lot and produced by one process which results in homogeneity of all lead assemblies used in loading the entire lot of fuzes.

4.3.2 Examination.-The examinations listed in the following subparagraphs shall be performed on inspection lots (see 4.3.1) of the components or assemblies designated in the applicable paragraph headings. Inspection for critical defects (and major defects, when so specified) shall be 100 percent. Sampling plans for major and minor defects shall be in accordance with MIL-STD-105 except that continuous sampling plans in accordance with MIL-STD-1235 may be used if approved by the Government. Instead of applying the AQL's designated herein to the groups of major and minor defects listed, the contractor may elect to apply AQL's to individual defects using an AQL of 0.40 percent for each major defect and an AQL of 0.65 percent for each minor defect. When this method is elected, it shall be applied to all of the major and minor defects listed in the applicable subparagraph of this section, except where 100 percent inspection is specified, and be documented as part of the contractor's inspection system. Equipment necessary for the performance of the inspections listed shall be in accordance with 4.3.4.

4.3.2.1 Lead assembly (see dwg. 8889507 covering a detail of dwg. 8889500).

| Categories | Defects | Method of Inspection | Code No. (see 6.2) |
|---|---|---|---|
| Critical: | | | |
| 1. | Cup cracked, split or cut | Visual | 01001 |
| 2. | Explosive exposed | Visual | 01002 |



Source: https://assist.dla.mil -- Downloaded: 2026-10-22T20:18Z
Check the source to verify that this is the current version before use.

| | | | |
|---|---|---|---|
| Major: | AQL 1.0 percent | | |
| 101. | Length | Gage | 01003 |
| 102. | Diameter, maximum (max.) | Gage | 01004 |
| 103. | Color of lacquer incorrect (either end) | Visual | 01005 |
| 104. | Crimp less than 360 degrees | Visual | 01006 |
| 105. | Disc punctured or torn | Visual | 01007 |
| 106. | Cup dented or distorted | Visual | 01008 |
| Minor: | AQL 0.65 percent | | |
| 201. | Evidence of poor workmanship (see 3.9) | Visual | 01009 |

4.3.2.2 Lead Housing assembly (see dwg. 8889506 covering a detail of dwg. 8889500).

| Categories | Defects | Method of Inspection | Code No. |
|---|---|---|---|
| Critical: | | | |
| 1. | Lead above flush | Gage | 02001 |
| Major: | AQL 0.65 percent | | |
| 101. | Lead assembly inverted or missing | Visual | 02002 |
| 102. | Sealing compound missing or improper | Visual | 02003 |
| 103. | Flash hole obstructed | Visual | 02004 |
| Minor: | AQL 0.65 percent | | |
| 201. | Evidence of poor workmanship (see 3.9) | Visual | 02005 |

4.3.2.3 Detonator housing assembly (see dwg. 8889509 covering a detail of dwg. 8889500).

| Categories | Defects | Method of Inspection | Code No. |
|---|---|---|---|
| Critical: | | | |
| 1. | Detonator above flush | Gage | 03001 |
| Major: | AQL 0.40 percent | | |
| 101. | Detonator inverted or missing | Visual | 03002 |
| 102. | Sealing compound excessive | Visual | 03003 |
| Minor: | AQL 0.65 percent | | |
| 201. | Evidence of poor workmanship (see 3.9) | Visual | 03004 |



Source: https://assist.dla.mil -- Downloaded: 2026-10-22T20:18Z
Check the source to verify that this is the current version before use.

4.3.2.4 Fuze assembly, after assembly of helical compression spring and output piston (see dwg. 8889500).

| Categories | Defects | Method of Inspection | Code No. |
|---|---|---|---|
| Critical: | | | |
| 1. | Helical compression spring missing, broken or distorted | Visual | 04001 |
| Major: | AQL 0.40 percent | | |
| 101. | Output piston inverted | Visual | 04003 |
| Minor: | AQL 0.65 percent | | |
| 201. | Evidence of poor workmanship (see 3.9) | Visual | 04002 |

4.3.2.5 Fuze assembly, after assembly of helical compression spring, output piston, special shaped diaphragm but just prior to insertion of out put piston cap and preformed packing and upsetting of body (see dwg. 8889500).

| Categories | Defects | Method of Inspection | Code No. |
|---|---|---|---|
| Critical: None defined. | | | |
| Major: | AQL 0.40 percent | | |
| 101. | Hole, cut or tear in diaphragm | Visual | 05001 |
| 102. | Special shaped diaphragm improperly seated against fuze body, or adhesive/sealant missing | Visual | 05002 |
| Minor: | AQL 0.65 percent | | |
| 201. | Evidence of poor workmanship (see 3.9) | Visual | 05005 |

4.3.2.6 Fuze assembly, after assembling parts specified in 4.3.2.5 and assembling output piston cap, preformed packing, and staking of body (see dwg. 8889500).

| Categories | Defects | Method of Inspection | Code No. |
|---|---|---|---|
| Critical: None defined. | | | |
| Major: | AQL 0.40 percent | | |
| 101. | Stake missing | Visual | 27001 |



Source: https://assist.dla.mil -- Downloaded: 2026-10-22T20:18Z
Check the source to verify that this is the current version before use.

| | | | |
|---|---|---|---|
| Minor: | AQL 0.65 percent | | |
| 201. | Evidence of poor workmanship (see 3.9) | Visual | 27002 |

4.3.2.7 Fuze assembly, after assembling parts specified in 4.3.2.6 and after assembling input mechanism gasket and orifice cup assembly but just prior to insertion of the input piston guide, special shaped diaphragm, and input piston (see dwg. 8889500).

| Categories | Defects | Method of Inspection | Code No. |
|---|---|---|---|
| Critical: | | | |
| 1. | Orifice cup assembly missing | Visual | 22003 |
| Major: | AQL 0.40 percent | | |
| 101. | Any component improperly assembled | Visual | 22001 |
| Minor: | AQL 0.65 percent | | |
| 201. | Evidence of poor workmanship (see 3.9) | Visual | 22002 |

4.3.2.8 Fuze assembly, after assembling parts specified in 4.3.2.7 and after subassembling input diaphragm, input piston guide, input piston, but just prior to insertion into fuze body and staking (see dwg. 8889500).

| Categories | Defects | Method of Inspection | Code No. |
|---|---|---|---|
| Critical: None defined. | | | |
| Major: | AQL 0.40 percent | | |
| 101. | Hole, cut or tear in diaphragm | Visual | 23001 |
| 102. | Any component improperly assembled | Visual | 23002 |
| Minor: | AQL 0.65 percent | | |
| 201. | Evidence of poor workmanship (see 3.9) | Visual | 23003 |

4.3.2.9 Fuze assembly, after assembling parts specified in 4.3.2.8 and assembling input diaphragm, input piston guide, input piston subassembly, and staking of fuze body (see dwg. 8889500).



Source: https://assist.dla.mil -- Downloaded: 2026-10-22T20:18Z
Check the source to verify that this is the current version before use.

| Categories | Defects | Method of Inspection | Code No. |
|---|---|---|---|
| Critical: | None defined. | | |
| Major: | AQL 0.40 percent | | |
| 101. | Stake missing | Visual | 24001 |
| Minor: | AQL 0.65 percent | | |
| 201. | Evidence of poor workmanship (see 3.9) | Visual | 24002 |

4.3.2.10 Fuze assembly, after assembling parts specified in 4.3.2.9 and after air evacuation, oil filling, and assembly of sealing screw (see dwg. 8889500).

| Categories | Defects | Method of Inspection | Code No. |
|---|---|---|---|
| Critical: | None defined. | | |
| Major: | AQL 0.65 percent | | |
| 101. | Torque of sealing screw | Test | 25001 |
| 102. | Input piston not in extreme uppermost position | Visual | 25002 |
| 103. | Oil leaking | Visual | 25003 |
| Minor: | AQL 0.65 percent | | |
| 201. | Evidence of poor workmanship (see 3.9) | Visual | 25004 |

4.3.2.11 Fuze assembly, after assembling parts specified in 4.3.2.10 and after assembling fuze safing pin, preformed packing, and spacer sleeve but prior to staking spacer sleeve (see dwg. 8889500).

| Categories | Defects | Method of Inspection | Code No. |
|---|---|---|---|
| Critical: | None defined. | | |
| Major: | AQL 0.40 percent | | |
| 101. | Preformed packing missing | Visual | 07001 |
| Minor: | AQL 0.65 percent | | |
| 201. | Evidence of poor workmanship (see 3.9) | Visual | 07002 |



Source: https://assist.dla.mil -- Downloaded: 2026-10-22T20:18Z
Check the source to verify that this is the current version before use.

4.3.2.12 Fuze assembly, after assembling parts specified in 4.3.2.11, and after staking spacer sleeve (see dwg. 8889500).

| Categories | Defects | Method of Inspection | Code No. |
|---|---|---|---|
| Critical: None defined. | | | |
| Major: | AQL 0.40 percent | | |
| 101. | Spacer sleeve stake missing..... | Visual | 08002 |
| Minor: | AQL 0.65 percent | | |
| 201. | Evidence of poor workmanship (see 3.9)..... | Visual | 08003 |

4.3.2.13 Fuze assembly, after assembling parts specified in 4.3.2.12, and assembling firing pin chamber, firing pin, firing pin spring, fuze safing arm, screw, balls, torsion spring, and steel spring pins, but prior to sealing and staking firing pin chamber (see dwg. 8889500).

| Categories | Defects | Method of Inspection | Code No. |
|---|---|---|---|
| Critical: | | | |
| 1. | Torque of fuze safing arm screw..... | Test | 09001 |
| 2. | Fuze safing arm missing, loose or incorrectly assembled..... | Visual-Manual | 09002 |
| 3. | Helical torsion spring missing, broken, or incorrectly assembled.... | Visual | 09003 |
| Major: | AQL 0.40 percent | | |
| 101. | Length of spring pin protrusion... | Gage | 09004 |
| 102. | Firing pin or restraining ball missing..... | Visual | 09008 |
| Minor: | AQL 0.65 percent | | |
| 201. | Evidence of poor workmanship (see 3.9)..... | Visual | 09009 |

4.3.2.14 Fuze assembly, after assembling parts specified in 4.3.2.13, and staking and sealing firing pin chamber (see dwg. 8889500).

| Categories | Defects | Method of Inspection | Code No. |
|---|---|---|---|
| Critical: None defined. | | | |



Source: https://assist.dla.mil -- Downloaded: 2026-10-22T20:18Z
Check the source to verify that this is the current version before use.

| | | | |
|---|---|---|---|
| Major: | AQL 0.65 percent | | |
| 101. | Perpendicularity of slot with flat on body | Gage | 26003 |
| 102. | Stake missing | Visual | 26001 |
| 103. | Sealing compound missing | Visual | 26002 |
| Minor: | AQL 0.65 percent | | |
| 201. | Evidence of poor workmanship (see 3.9) | Visual | 26004 |

4.3.2.15 Fuze assembly, after inserting detonator housing assembly in fuze body cavity (see dwg. 8889500).

| Categories | Defects | Method of Inspection | Code No. |
|---|---|---|---|
| Critical: | None defined. | | |
| Major: | AQL 0.40 percent | | |
| 101. | Detonator missing | Visual | 10001 |
| 102. | Spring tang does not engage housing | Visual | 10002 |
| Minor: | AQL 0.65 percent | | |
| 201. | Evidence of poor workmanship (see 3.9) | Visual | 10003 |

4.3.2.16 Fuze assembly (see dwg. 8889500).

| Categories | Defects | Method of Inspection | Code No. |
|---|---|---|---|
| Critical: | None defined. | | |
| Major: | AQL 0.65 percent | | |
| 101. | Lead missing | Visual | 11003 |
| 102. | Stake or crimp missing | Visual | 11004 |
| 103. | Sealing compound missing | Visual | 11005 |
| Minor: | AQL 0.65 percent | | |
| 201. | Evidence of poor workmanship (see 3.9) | Visual | 11006 |

4.3.2.17 Fuze and Arming Cap Assembly, M608, prior to assembly to Fuze Assembly (see dwg. 9204009).



Source: https://assist.dla.mil -- Downloaded: 2026-10-22T20:18Z
Check the source to verify that this is the current version before use.

| Categories | Defects | Method of Inspection | Code No. |
|---|---|---|---|
| Critical: | | | |
| | 1. Arming knob not in SAFE position.... | Visual | 12001 |
| | 2. Cotter pin missing or end not spread..... | Visual | 12002 |
| | 3. Headless groove pin missing from Arming Knob Assembly..... | Visual | 12003 |
| Major: | AQL 0.40 percent | | |
| | 101. Component missing other than cotter pin or headless groove pin. | Visual | 12004 |
| | 102. Stakes missing around guide pins in Arming Knob Assembly..... | Visual | 12006 |
| Minor: | AQL 0.65 percent | | |
| | 201. Evidence of poor workmanship (see 3.9)..... | Visual | 12005 |

4.3.2.18 Fuze and Arming Cap Assembly, M608 (see dwg. 9204009).

| Categories | Defects | Method of Inspection | Code NO. |
|---|---|---|---|
| Critical: | | | |
| | 1. Cotter pin missing or end not spread..... | Visual | 13001 |
| Major: | AQL 0.65 percent | | |
| | 101. Any component missing other than cotter pin..... | Visual | 13002 |
| | 102. Marking incorrect, misleading or unidentifiable..... | Visual | 13003 |
| | 103. Retaining ring not fully seated in groove..... | Visual | 13004 |
| Minor: | AQL 0.65 percent | | |
| | 201. Evidence of poor workmanship (see 3.9)..... | Visual | 13005 |

4.3.2.19 Carton, Packing (see dwg. 8876062).

| Categories | Defects | Method of Inspection | Code No. |
|---|---|---|---|
| Critical: None defined. | | | |



Source: https://assist.dla.mil -- Downloaded: 2026-10-22T20:18Z
Check the source to verify that this is the current version before use.

| | | | |
|---|---|---|---|
| Major: | AQL 0.40 percent | | |
| 101. | Carton torn, punctured or damaged | Visual | 14001 |
| Minor: | AQL 0.65 percent | | |
| 201. | Marking misleading or unidentifiable | Visual | 14002 |
| 202. | Contents loose | Visual | 14003 |

4.3.2.20 Sealed wood packing box (see dwg. 8876063).

| Categories | Defects | Method of Inspection | Code No. |
|---|---|---|---|
| Critical: | None defined. | | |
| Major: | AQL 0.40 percent | | |
| 101. | Box damaged | Visual | 15001 |
| 102. | Hardware or strapping missing, broken, or loose | Visual-Manual | 15002 |
| Minor: | AQL 1.5 percent | | |
| 201. | Contents loose | Manual | 15003 |
| 202. | Marking misleading or unidentifiable | Visual | 15004 |
| 203. | Car seal missing, unsealed or improperly positioned | Visual | 15005 |

4.3.3 Testing

4.3.3.1 Binder-lubricant content of lead charge - (see dwg. 8889507) - Major defect - Code No. 16001.-The binder-lubricant content of the lead charge shall be determined from a sample to be selected at the loading station at the time of loading the lead assemblies. A minimum of one five gram sample shall be selected from each eight hours of production and tested as specified in 4.4.1. If the total binder-lubricant content does not comply with the specified requirement, all lead charge composition represented by the sample, including any lead assemblies loaded with the non-conforming lead charge composition, shall be rejected. The contractor shall maintain adequate records to provide identification of the specific amount of lead charge composition and loaded items which are represented by the sample.



Source: https://assist.dla.mil -- Downloaded: 2026-10-22T20:18Z
Check the source to verify that this is the current version before use.

4.3.3.2 Torque test of arming knob - (see dwg. 9204009) - Major defect - Code No. 17001.-The sampling plan for this test shall be in accordance with MIL-STD-105 using Code Letter J and an AQL of 0.65 percent. Any assembly which fails to comply with the applicable drawing requirement shall be classed defective. The test shall be performed as specified in 4.4.2 using equipment in accordance with 4.3.4.

4.3.3.3 Waterproofness (see 3.3) - Major defect - Code No. 18001.-The sampling plan for this test shall be in accordance with MIL-STD-105 using Code Letter G and an AQL of 1.5 percent. Any assembly which fails to comply with the applicable requirement shall be classed defective. The test shall be performed as specified in 4.4.4 using equipment in accordance with 4.3.4.

4.3.3.4 Functioning (see 3.5) - Major defect - Code No. 19001.-Beginning with the first lot produced and continuing until three consecutive lots shave complied with the acceptance criteria specified, the sampling plan for this test shall be in accordance with MIL-STD-105 using Code Letter J and an AQL of 1.0 percent. Any fuze and arming cap assembly which fails to comply with the applicable requirement shall be classed defective. The test shall be performed as specified in 4.4.5 using equipment in accordance with 4.3.4.

4.3.3.4.1 After three (3) consecutive lots have met the acceptance criteria of 4.3.3.4 the sampling plan for this test shall be in accordance with MIL-STD-105 using Code Letter H and an AQL of 1.0 percent.

4.3.3.5 Non-functioning - (see 3.6) - Critical defect - Code No. 20001.-This test shall be conducted 100 percent. Any fuze and arming cap assembly which fails to comply with the applicable requirement shall be classed defective. The test shall be performed as specified in 4.4.6 using equipment in accordance with 4.3.4.

4.3.3.6 Check test for deterioration of detonators - (see MIL-D-14978) - Major defect - Code No. 21001.-If the total time between original acceptance of any detonator lot and the assembly of that lot into the fuzes exceeds two years, or if the detonators have been subjected to adverse conditions, however brief, at any time since previous tests, the detonator lot shall be subjected to, and must satisfactorily pass, the check test for deterioration specified in the applicable detonator specification immediately before the lot is assembled into the [illegible]. This test shall be performed by the contractor on detonators selected by the Government inspector at the facility assembling the detonators into the fuzes (see 6.5).



Source: https://assist.dla.mil -- Downloaded: 2026-10-22T20:18Z
Check the source to verify that this is the current version before use.

4.3.4 Inspection equipment.-Equipment Tabulation Number ET-9204009 identifies the inspection equipment required to perform the examinations and tests prescribed in this section. The contractor shall design inspection equipment in accordance with the instructions in 6.3.

4.3.4.1 Government rights to documentation.-Inspection equipment drawings and lists provided and revised in accordance with the requirements of the ET may be used by DOD activities for design, procurement, manufacture, testing, evaluation, production and receiving inspection, overhaul, shipping, storage, identification of stock, ordering and storage of replacement parts, inspection of items at overhaul, general maintenance of equipment, construction, survey and whenever inspection equipment drawings are needed.

4.4 Test methods and procedures

4.4.1 Determination of binder-lubricant content of RDX.-The calcium resinate, graphite, and total-binder-lubricant content shall be determined as follows:

4.4.1.1 Calcium resinate.-An accurately weighed portion of 5 grams of the sample shall be tranferred to a tared medium porosity sintered-glass crucible. The sample shall be extracted with three 20 milliliter (ml) portions of chloroform which have been previously saturated with RDX, maintaining each portion in contact with the residue for approximately 5 minutes before applying suction. Any lumps which may persist shall be broken up by stirring occasionally and the sides of the crucible washed down with each 20 ml. portion of chloroform to insure complete removal of the calcium resinate. The residue shall be aspirated until the odor of the chloroform is no longer detectable; the crucible and contents shall be placed in a drying oven at 100-105 degrees Centigrade (C.) for 1/2 hour, cooled in a desiccator and weighed. The above extraction shall be repeated, drying, and weighing with individual 20 ml. portions of chloroform until the loss in weight on subsequent extractions totals less than 0.003 grams. The loss in weight of the crucible plus contents shall be calculated to percent calcium resinate in the sample on a moisture-free basis as follows:

Percentage of Calcuim Resinate = 100A divided by W, where:
A = loss in weight of the crucible plus contents.
W = weight of the sample.



Source: https://assist.dla.mil -- Downloaded: 2026-10-22T20:18Z
Check the source to verify that this is the current version before use.

4.4.1.2 Graphite.-The residue remaining after the calcium resinate has been removed shall be extracted with two 20 ml. portions of dimethyl formamide, each portion maintained in contact with the residue for approximately 5 minutes with intermittent stirring before applying suction. The crucible and contents shall be washed with a minimum of 3 ml. portions of acetone, each portion maintained in contact with the residue for approximately 1 minute with continuous stirring before applying suction, until the following qualitative test for RDX in the acetone washings is negative. The acetone filtrate shall be transferred to a 25 ml. beaker, evaporated to dryness on a steam bath and several drops of a solution of chromotropic color, as compared to a pink color obtained by a blank prepared in an identifical manner indicates the presence of RDX. The residue shall be aspirated until the odor of acetone is no longer detectable; the crucible and contents shall be placed in a drying oven at 95 degrees C. plus or minus 2 degrees C. for 1/2 hour, cooled in a desiccator and weighed. The weight of the residue in the crucible shall be claculated to the percentage of graphite in the sample on a moisture-free basis as follows:

Percentage of Graphite = 100A divided by W, where:
A = increase of weight of filtering crucible.
W = weight of sample.

4.4.1.3 Total binder-lubricant.-The percentage of total binder-lubricant in the sample shall be calculated by adding the percentages of calcium resinate and graphite.

4.4.2 Torque test of arming knob.-The fuze and arming cap assembly shall be mounted in a test fixture and the cotter pin removed. The torque shall be applied to the arming knob and observation made to determine compliance with the applicable drawing requirement. At the end of this test, the pull ring and cotter pin shall be replaced with a new ring and pin, and the cotter pin shall be spread in accordance with the applicable drawing requirement. Test equipment shall be in accordance with 4.3.4.

4.4.3 Transportation-vibration.-The test shall be performed in accordance with MIL-STD-331, Test 104, Procedure II. The assemblies which are without loaded components shall be examined subsequent to the test for any evidence of looseness between the fuze safing arm and fuze safing pin and for any evidence of looseness of the safing arm screw. Loaded fuzes subjected to this test shall then be functioned in accordance with 4.4.5.



Source: https://assist.dla.mil -- Downloaded: 2026-10-22T20:18Z
Check the source to verify that this is the current version before use.

4.4.4 Waterproofness.-The fuze assembly (see 8889500) shall be submerged under water for 24 hours, minimum. The submersion conditions shall be such that the fuze assembly senses a three foot, min., head of water or its equivalent for the specified time. After removal from the water, the fuze assembly shall be placed in a fixture and tested for functioning using an Arming Knob Assembly (dwg. 9204010), Arming Cap Body (9204022), and a Retaining Ring (dwg. 9204021) which comply with all applicalbe drawing requirements. Observation shall be made for compliance with the applicable requirement. Test equipment shall be in accordance with 4.3.4.

4.4.5 Functioning.-The fuze and arming cap assembly shall be mounted in a test fixture and the specified load applied parallel to the center axis of the assembly with the arming knob set in the ARMED position. Observation shall be made for functioning within the specified time. The actual time required for each fuze to function shall be recorded. Test equipment shall be in accordance with 4.3.4.

4.4.6 Non-functioning.-The specified load shall be applied aprallel to the center axis of the fuze and arming cap assembly with the arming knob set in the SAFE position. Observation shall be made for compliance with the applicable requirement.

4.4.7 Jolt.-The test shall be performed as specified in Method 101 of MIL-STD-331. The fuze and arming cap assembly shall be examined after the test to determine compliance with the requirements.

4.4.8 Jumble.-The test shall be performed as specified in Method 102 of MIL-STD-331. The fuze and arming cap assembly shall be examined after the test to determine compliance with the requirements.

## 5. PREPARATION FOR DELIVERY

5.1 Preservation and packaging.

5.1.1 Level A.-The fuze and arming cap assembly shall be packaged in accordance with dwg. 8876062.



Source: https://assist.dla.mil -- Downloaded: 2026-10-22T20:18Z
Check the source to verify that this is the current version before use.

5.2 Packing

5.2.1 Level A.-The fuze and arming cap assemblies shall be packed in accordance with dwg. 8876063.

5.3 Marking.-Marking shall be in accordance with dwgs. 8876062 and 8876063.

6. NOTES

6.1 Ordering data.-Procurement documents shall specify the following:

a. Title, number and date of this specification.

b. Data cards.-Data cards shall be prepared for each lot in accordance with the information specified in MIL-STD-1167.

c. Provisions for submission of first article samples.

6.2 Inspection code numbers.-The five digit code numbers assigned to the inspections herein are to facilitate future data collection and analysis by the Government. These code numbers are also used to correlate the characteristics cited on Equipment Lists with the inspections listed in this specification. In addition, they should be cited as references on drawings of equipment designs submitted by the contractor to the Government for approval (see 6.3.5).

6.3 Inspection equipment.-The contractor shall design inspection equipment as required by the inspection Equipment Lists (EL) referenced on the applicable ET in accordance with the instructions of paragraphs 6.3.1 through 6.3.5.

6.3.1 Inspection equipment lists (EL).-Inspection equipment lists indicate the availability of inspection equipment designs by showing in the "number" column of the list of inspection equipment (Form SMUPA 1010) the numbers of drawings or Federal Stock numbers of existing equipment designs, or codes as indicated in paragraph 6.3.2. Design action required of the contractor is described in paragraphs 6.3.3 and 6.3.4. The contractor will be required to prepare detailed drawings in accordance with 6.3.4 for all the equipment coded as "Contractor Design" in the number column. These contractor designs must be approved by the Government prior to fabrication or procuring of the equipment. Designs shall be submitted for approval as specified in 6.3.5.



Source: https://assist.dla.mil -- Downloaded: 2026-10-22T20:18Z
Check the source to verify that this is the current version before use.

6.3.2 Inspection equipment list codes.-The inspection equipment as defined in 6.3.3 and 6.3.4 will be designated in the EL by the following codes:

CD - Contractor design on controlled contractor format and/or commercial equipment.
MU - Army design, mandatory for use.

6.3.3 Army designs.-Army designs are reflected on detailed drawings which completely depict all the information necessary for the fabrication of the item of inspection equipment. The contractor need provide no design when an Army design is listed for an item of inspection equipment. Army designs fall into two basic classification; mandatory (designated "MU") and non-mandatory (indicated by drawing or Federal Stock Number). When an inspection equipment list references mandatory Army designs, the contractor shall comply with, and use these designs accordingly. The contractor may, however, in connection with non-mandatory designs, design alternate inspection equipment or use comparable commercial equipment to facilitate his operations. Such contractor prepared designs or commercial equipment selections must be approved by the Government prior to fabrication or procuring of the equipment. Designs shall be submitted for approval as specified in 6.3.5.

6.3.4 Contractor designs.-Contractor designs are designs of inspection equipment for which the Government has assigned design responsibility to the contractor. Contractor designs shall be supported by detailed drawings which depict all information necessary to completely fabricate, calibrate and operate an item of inspection equipment. This requires that the necessary views, dimensions, materials, finish, notes, operating and calibration instructions be properly depicted in accordance with approved practices to the extent that further calculation or clarification will not be required. Unless otherwise specified, contractor designs may be developed on the format the contractor normally employs in his equipment design procedure provided such format reflects the detail and information specified above, subject to the following controls: All submitted contractor designs shall conform to MIL-D-1000, Category A, Form 2. Legibility and reproducibility shall permit conventional making of clearly understandable, high contrast reproductions. Contractors shall submit three copies of final designs as a flat set. Designs shall be submitted for approval as specified in 6.3.5.



Source: https://assist.dla.mil -- Downloaded: 2026-10-22T20:18Z
Check the source to verify that this is the current version before use.

6.3.5 Submission of contractor designs.-All submitted designs shall contain a reference to the applicable five digit Code Number contained in Section 4 of this specification and the appropriate component or assembly drawing number and revision letter to which the specific design applies. Unless otherwise specified on the EL, all designs of equipment for inspection of defects classified as critical and major shall be submitted for approval to the Commanding Officer, Picatinny Arsenal, ATTN: SMUPA-ND15. All other designs of inspection equipment shall be approved by the inspection element of the agency administering the contract; submission shall be as directed by the contracting officer. Partial submission of inspection equipment designs is permissible and encouraged. However, the Arsenal completion date for design review will be based on the date of the final submission of designs. Picatinny Arsenal design review will be accomplished normally within one month after receipt.

6.4 Submission of ammunition data cards.-In addition to the normal distribution of records, one copy of all ammunition data cards shall be forwarded to each of the following:

Commanding Officer
Picatinny Arsenal
ATTN: (1) SMUPA-ND5
(2) SMUPA-DC
Dover, New Jersey 07801

6.5 Cost of check test.-The contracting officer will arrange for the contractor to be reimbursed for the expense incurred in the performance of the check test for deterioration of the detonators. The test shall be conducted at Government expense without cost to the contractor who loaded the detonators into the fuzes, and shall not constitute a basis of rejection against either contractor except where deterioration has occurred as a direct result of carelessness in handling storage, etc., permitted while the detonator lot was under the jurisdiction of either contractor.

Custodian:
Army-MU

Preparing activity:
Army-MU

Project Number: 1345-A-291



Source: https://assist.dla.mil -- Downloaded: 2026-10-22T20:18Z
Check the source to verify that this is the current version before use.