MIL-P-52200B(ME)
7 January 1972
SUPERSEDING
MIL-P-52200A(MO)
26 August 1965

MILITARY SPECIFICATION

PONTON BOAT: HALF-SECTION, ALUMINUM HULL, SPOON BOW

1. SCOPE

1.1 This specification covers an aluminum, half-section, ponton boat with spoon-shaped bow for the raft section of the light tactical floating bridge.

2. APPLICABLE DOCUMENTS

2.1 The following documents of the issue in effect on date of invitation for bids or request for proposal form a part of this specification to the extent specified herein:

SPECIFICATIONS

Federal

QQ-S-781	- Strapping, Steel, Flat and Seals.
PPP-B-601	- Boxes, Wood, Cleated-Plywood.
PPP-B-621	- Boxes, Wood, Nailed and Lock-Corner.

Military

MIL-T-704	- Treatment and Painting of Materiel.
MIL-W-5044	- Walkway Compound, Nonslip, and Walkway Matting, Nonslip.
MIL-R-7885	- Rivets; Blind, Structural, Pull-Stem and Chemically Expanded.

STANDARDS

Federal

FED. STD. No. 595	- Colors.

Source: https://assist.dla.mil -- Downloaded: 202610-22T21:10Z
Check the source to verify that this is the current version before use.

Military

MIL-STD-105	- Sampling Procedures and Tables for Inspection by Attributes.
MIL-STD-129	- Marking for Shipment and Storage.

DRAWINGS

ME

DL13216E9807	- Ponton Boat: Half-Section; Aluminum Hull, Spoon Bow.
D13213E6596-1 and -2	- Level A Packing of Ponton Boat; Half-Section, Aluminum Hull, Spoon Bow.

(Copies of specifications, standards, and drawings required by suppliers in connection with specific procurement functions should be obtained from the procuring activity or as directed by the contracting officer.)

2.2 Other publications. The following documents form a part of this specification to the extent specified herein. Unless otherwise indicated, the issue in effect on date of invitation for bids or request for proposal shall apply.

AMERICAN SOCIETY OF MECHANICAL ENGINEERS

Boiler and Pressure Vessel Code

Welding Qualifications

(Application for copies should be addressed to the American Society of Mechanical Engineers, 345 East 47th Street, New York, N. Y. 10017.)

AMERICAN WELDING SOCIETY

Standard Qualification Procedure

(Application for copies should be addressed to the American Welding Society, 345 East 47th Street, New York, N. Y. 10017.)

3. REQUIREMENTS

3.1 Description. The half-section ponton boat shall be in accordance with Data List DL13216E9807 and as specified herein.

Source: https://assist.dla.mil -- Downloaded: 202610-22T21:10Z
Check the source to verify that this is the currentversion before use.

3.1.1 Drawings. The drawings forming a part of this specification are engineering design drawings. No deviation from the prescribed dimensions or tolerances is permissible without prior approval of the contracting officer. Any data (e.g. shop drawings, layouts, flow sheets, processing procedures, etc.) prepared by the supplier or obtained from a vendor to support fabrication and manufacture of the production item shall be made available, upon request, for inspection by the contracting officer or his designated representative.

3.2 First article (preproduction model). The supplier shall furnish two half-section ponton boats for examination and testing within the time frame specified to prove prior to starting production that his production methods will produce ponton boats that comply with the requirements of this specification. One half-section ponton boat shall be complete in every detail; the other shall be complete except the intermediate and finish coats of paint and marking shall not be applied. Examination and tests shall be as specified in section 4 and shall be subject to surveillance and approval by the Government (see 6.3).

3.3 Material. Material shall be as specified herein and as shown on the applicable drawings. Materials not specified shall be selected by the supplier and shall be subject to all provisions of this specification.

3.4 Hardware.

3.4.1 Aluminum alloy blind rivets. Aluminum alloy blind rivets shall conform to MIL-R-7885, type and class optional. Other types of blind rivets, such as those in which the expansion is accomplished by driving a spindle into the rivet shank, may be used if they meet all requirements of MIL-R-7885 except that requirements for expansion, dimensions, and tolerances shall not apply.

3.4.2 Steel blind rivets. Steel blind rivets shall be modified brazier or universal head and shall be cadmium or zinc plated.

3.5 Dimensions, measurements, and tolerances. Dimensions shown in the table of offsets or dimensions marked "REF" on the drawings are provided for informational purposes only and do not govern manufacturing or final acceptance operations in any way. Measurements shall be made under the same climatic conditions as for production. For measuring half-breadths, the centerline of the half-section ponton boat shall lie in a vertical plane passing through the straight line extending from the center point of the bow to the center point of the transom cap and passing through the centerline of the keel. The positioning of holes, size of material, and

Source: https://assist.dla.mil -- Downloaded: 202610-22T21:10Z
Check the source to verify that this is the current version before use.

length, width and depth of members shall be measured from one end or both, and tolerances shall not be cumulative. Frames shall be located within 1/8 inch of the dimensions shown. Frame locations shall be measured from the outside of the transom plate and tolerances on dimensions shall not be cumulative. The supplier shall use the necessary dies, tools, fixtures, jigs, templates, and quality control measures necessary to achieve the half-section ponton boat tolerances specified and alinement and location of hull components to insure interchangeability and nestability of the half-section ponton boats furnished under this specification. The half-section ponton boats shall nest within and couple to one another without binding or other interference. Unless otherwise specified on the drawings, tolerances for the half-section ponton boat shall be as follows:

(a) Half-breadths (gunwale and chine), plus or minus 1/4 inch.
(b) Heights above base line (gunwale and chine), plus or minus 1/4 inch.

3.6 Fabrication.

3.6.1 Hull details. Handrails, skids, stringers, midwales, and keel sections shall be of one-piece construction. Sealing tape shall be used between all metal surfaces which form external (wetted) joints or seams except the gunwale seam. Only one thickness of sealing tape shall be used and only one width of tape shall be used per seam except in cases where the seam width is more than 1-1/2 inches. The sealing tape shall be applied without stretching or tearing and shall cover the entire contact surface. Sealing compound shall be used only in the locations shown on the drawings. Where sealing tape or compound is to be applied, surfaces shall be cleaned, treated and primed (see 3.7) prior to application. Unless otherwise shown on the drawings for 6061-T6 aluminum alloy, forming radii (inside) for cold bending shall be 3/16 inch for sheets less than 0.125 inch thick and 1/4 inch for 0.125-inch-thick sheets. When aluminum sheet size permits, the following options are permissible in lieu of the joints shown on the drawings for assembly of the hull skin:

(a) Each longitudinal half of the bottom of the hull skin may be one continuous piece from transom to bow.
(b) Full width of the hull bottom may be one piece from transom to a butt joint located near frame 6.
(c) Each side of the hull skin may be one continuous piece from transom to bow. This option may be used with either (a) or (b).

Source: https://assist.dla.mil -- Downloaded: 202610-22T21:10Z
Check the source to verify that this is the currentversion before use.

3.6.2 Riveting. Rivets passing through the hull shall have the preformed (manufactured) heads located on the outside of the hull. Unless otherwise shown on the drawings, all rivets shall be standard brazier head with flat driven heads. Rivet holes shall be drilled or drilled-and-reamed to correct size except that holes may be punched in subassemblies when positive means are employed to prevent drifting. Rivet hole sizes shall be as follows: 0.191 inch for 3/16-inch-diameter rivet, 0.257 inch for 1/4-inch-diameter rivet, and 0.323 inch for 5/16-inch-diameter rivet. Depth of countersink for countersunk-head rivets in the member shall be equal to the depth of the countersunk part of the head. Countersinking shall be performed with positive-limit stops fitted to the countersinking tool. Burrs and chips shall be removed from all rivet joints and seams and from all outside surfaces before riveting. Automatic or squeeze-type riveters shall be permitted for driving rivets in subassemblies when pressure employed does not cause permanent distortion or damage of the material. Flat rivet heads (driven) shall have a diameter 1.75 times the nominal shank diameter and a height 0.50 times the nominal shank diameter. All formed rivet heads shall be concentric with the rivet shank and in full contact with the surface of the member. Rivets shall not be overdriven causing seam deformation with resulting separation of seam lap edges from the surface. Welding adjacent to riveting shall be done before the driving of rivets. Rivet tension shall not be created by rivets being driven in improperly-fitted members. Seams and rivet lines shall show no separations of contact surfaces. Unless otherwise shown on the drawings, rivet edge distances shall be 3/8 inch for 3/16-inch-diameter rivets, 7/16 inch for 1/4-inch-diameter rivets, and 1/2 inch for 5/16-inch-diameter rivets.

3.7 Treatment and painting. The half-section ponton boat shall be cleaned, treated, and painted in accordance with MIL-T-704, type B. Unless otherwise specified (see 3.2), intermediate and finish painting shall be accomplished after inspection. Following cleaning and priming, the floor plates, bow steps, and the interior of the bottom of the hull forward from frame 2 shall be given one coat of deck covering conforming to MIL-W-5044, type II, except that the color shall conform to color No. 34087 of FED. STD. No. 595. The shank of the coupling pin shall not be treated or painted.

3.8 Identification marking. The half-section ponton boat shall be identified in accordance with the applicable drawing of DL13216E9807.

3.9 Workmanship. The surfaces of all components shall be free from kinks, wrinkles, burrs, and scratches. Materials developing fractures or cracks from fabrication shall be discarded and not repaired by welding. Welds shall be free from cracks or other imperfections which may reduce

Source: https://assist.dla.mil -- Downloaded: 202640-22T21:10Z
Check the source to verify that this is the currentversion before use.

effectiveness of the welded parts. The half-section ponton boat shall be watertight. Threaded fasteners shall be screwed tight but shall not distort components being held. All half-section ponton boat components shall be present and clean prior to packing for shipment.

3.9.1 Welding. The surfaces of parts to be welded shall be free from corrosion, scale, paint, grease, and other foreign matter which affects weld quality. Aluminum welding shall be done by the inert gas (argon or helium), shielded-arc method, using 4043 aluminum alloy filler material. Welds shall be ground, filed, or buffed but shall not be hammered. During welding, components shall be held to insure alinement.

3.9.2 Welders. Welders shall be qualified in accordance with the Standard Qualification Procedure of the American Welding Society or the Welding Qualifications of the ASME.

4. QUALITY ASSURANCE PROVISIONS

4.1 Responsibility for inspection. Unless otherwise specified in the contract or purchase order, the supplier is responsible for the performance of all inspection requirements as specified herein. Except as otherwise specified in the contract or order, the supplier may use his own or any other facilities suitable for the performance of the inspection requirements specified herein, unless disapproved by the Government. The Government reserves the right to perform any of the inspections set forth in the specification where such inspections are deemed necessary to assure supplies and services conform to prescribed requirements.

4.1.1 Acceptability criteria. Half-section ponton boats which conform to all requirements in sections 3 and 5 of this specification and pass all applicable examinations and tests in section 4 of this specification will be considered acceptable by the Government.

4.1.2 Component and material inspection. The supplier is responsible for insuring that components and materials used are manufactured, examined, and tested in accordance with referenced specifications and standards.

4.1.3 Parts and components. Parts and components detailed on the drawings shall be inspected in accordance with the Supplementary Quality Assurance Provisions (SQAP) shown on the drawings. The drawings specify the characteristics requiring SQAP inspection, the sampling plan, and the basis for acceptance and rejection (see 6.4 and 6.5).

Source: https://assist.dla.mil -- Downloaded: 202610-22T21:10Z
Check the source to verify that this is the currentversion before use.

4.2 Classification of inspection. Inspection shall be classified as follows:

(a) Preproduction inspection (see 4.3).
(b) Quality conformance inspection (see 4.4).
(c) Inspection of preparation for delivery (see 4.6).

4.3 Preproduction inspection.

4.3.1 Examination. Each half-section ponton boat shall be examined as specified in 4.5.1. Presence of one or more defects shall be cause for rejection.

4.3.2 Tests. Each half-section ponton boat shall be tested as specified in 4.5.2. Failure of any test shall be cause for rejection.

4.4 Quality conformance inspection.

4.4.1 Examination. Each half-section ponton boat shall be examined as specified in 4.5.1. Presence of one or more defects shall be cause for rejection.

4.4.2 Tests. Each half-section ponton boat shall be tested as specified in 4.5.2.2. Failure of the test shall be cause for rejection.

4.5 Inspection procedure.

4.5.1 Examination. The half-section ponton boat shall be examined for the following defects prior to testing, final painting, and marking. Government-loaned property listed in DLI3216E9807 and described in pamphlet AMSME-FB-P715-100 shall be used for the examination where applicable (see 6.6).

101. Material not as specified.
102. Hardware not as specified.
103. Dimensions, measurements, and tolerances not as specified.
104. Sealing tape and sealing compound not applied as specified.
105. Rivets mislocated, overdriven, or not in full contact with members.
106. Separation of seam contact surfaces.
107. Weld defects.

The half-section ponton boat shall be examined for the following defects after testing and application of final paint and marking:

Source: https://assist.dla.mil -- Downloaded: 202610-22T21:10Z
Check the source to verify that this is the currentversion before use.

108. Treatment and painting not as specified.
109. Identification marking not as specified.
110. Components defective, loose, missing, or dirty.

4.5.2 Tests.

4.5.2.1 Coupling and nesting. The pair of half-section ponton boats shall be nested. The half-section ponton boats shall be interchanged and the test repeated. The two half-section ponton boats shall then be coupled at their transoms and the coupling pins shall be inserted. Inability of either half-section ponton boat to nest interchangeably or to connect with the other half-section ponton boat shall constitute failure of this test.

4.5.2.2 Watertightness. The leveled hull shall be submerged in water or filled with water to within 4-1/2 inches of the top of the aft gunwale. The hull shall remain submerged in or filled with water for 10 minutes. Evidence of leakage shall constitute failure of this test. Repairs to half-section ponton boats failing this test shall be accomplished by redriving (tightening) or replacing rivets and not by the addition of sealing compound. Replacement of rivets may be size-for-size when the rivet hole is not enlarged or damaged. When the rivet hole is enlarged, the next larger diameter rivet shall be used.

4.6 Inspection of preparation for delivery.

4.6.1 Preproduction pack inspection.

4.6.1.1 Examination. Examine the preproduction pack for the defects specified in 4.6.2.3. Presence of one or more defects shall be cause for rejection.

4.6.2 Quality conformance inspection of pack.

4.6.2.1 Unit of product. For the purpose of inspection, a completed pack prepared for shipment shall be considered a unit of product.

4.6.2.2 Sampling. Sampling for examination shall be in accordance with MIL-STD-105.

4.6.2.3 Examination. Samples selected in accordance with 4.6.2.2 shall be examined for the following defects. Acceptable Quality Level (AQL) shall be 2.5 percent defective.

Source: https://assist.dla.mil -- Downloaded: 20261O-22T21:10Z
Check the source to verify that this is the current version before use.

111. Materials and containers not as specified for level A. Each incorrect material or each incorrect container shall be considered one defect.
112. Coupling pin assemblies and pin retainers not packaged in the quantity specified for level A.
113. Ponton boat sections not packed and arranged in accordance with the referenced drawings for level A. Each deviation from the drawings shall be considered one defect.
114. Strapping and wire rope not tensioned and locked to prevent loosening for level A.
115. Marking illegible, incomplete, incorrect for level A or C.

5. PREPARATION FOR DELIVERY

5.1 Preproduction pack. The supplier shall furnish a preproduction pack for examination and test within the time frame specified, to prove prior to starting production packaging and packing that the applied preservation, packaging, packing, and marking comply with the preparation for delivery requirements of this specification. Examination and tests shall be those specified in section 4 and shall be subject to surveillance and approval by the Government (see 6.7). The preproduction pack may be accomplished utilizing either the preproduction model ponton boats or production ponton boats. If the preproduction model ponton boats are utilized, any preservation, packaging, and packing shall be removed by the supplier at no expense to the Government, when requested by the Government to facilitate comparison between the preproduction model ponton boats and production ponton boats.

5.2 Packaging. Packaging shall be level A or C, as specified.

5.2.1 Level A.

5.2.1.1 Coupling pin assemblies and pin retainers. The coupling pin assemblies and pin retainers for the superstructure connections in the quantities required for eight half-section ponton boats (see 5.3.1) shall be packaged together in a box conforming to PPP-B-621, class 1, style optional, or PPP-B-601, domestic type, style optional. The box shall be close-fitting. Strapping shall not be required.

5.2.2 Level C. The coupling pin assemblies and pin retainers for the superstructure connections shall be packaged to assure undamaged delivery from the supplier to the initial destination.

Source: https://assist.dla.mil -- Downloaded: 202610-22T21:10Z
Check the source to verify that this is the current version before use.

5.3 Packing. Packing shall be level A or C, as specified.

5.3.1 Level A. Unless otherwise specified, eight half-section ponton boats shall be inverted, nested, and packed as shown on Drawings D13213E6596-1 and -2. The package containing the coupling pin assemblies and pin retainers shall be secured to the crate base under the half-section ponton boats with flat steel strapping conforming to QQ-S-781, type I, class B, size as applicable. All strapping and wire rope shall be sufficiently tensioned and locked to prevent loosening or shifting of components during shipment.

5.3.2 Level C. The half-section ponton boats, coupling pin assemblies, and pin retainers shall be packed to assure undamaged delivery from the supplier to the initial destination.

5.4 Marking. Marking shall be in accordance with MIL-STD-129.

6. NOTES

6.1 Intended use. The aluminum half-section ponton boat is intended for use primarily as a bridging-equipment component.

6.2 Ordering data. Procurement documents should specify the following:

(a) Title, number, and date of this specification.
(b) Time frame required for submission of preproduction model (see 3.2).
(c) Time frame required for submission of preproduction pack (see 5.1).
(d) Level of packaging and level of packing required (see 5.2 and 5.3).
(e) Whether a quantity other than specified shall be inverted, nested, and packed on a crate base (see 5.3.1).

6.3 Preproduction model. Any changes or deviations of production ponton boats from the approved preproduction model during production will be subject to the approval of the contracting officer. Approval of the preproduction model will not relieve the supplier of his obligation to furnish ponton boats conforming to this specification.

6.4 Supplementary quality assurance provisions (SQAP). The contracting officer should require the supplier to maintain records of all SQAP inspections. A suggested paragraph is as follows:

Source: https://assist.dla.mil -- Downloaded: 20261O-22T21:10Z
Check the source to verify that this is the current version before use.

"The supplier shall maintain complete records of all examinations and tests performed to verify the requirements of classified SQAP characteristics. The records shall include as a minimum, lot size, sample size, drawing requirement, actual measurement, number and type of deficiencies found, quantity approved, quantity rejected, corrective action taken when applicable."

6.5 Definitions.

6.5.1 Supplementary quality assurance provisions (SQAP). A SQAP is a contractual requirement that supplements section 4 of the specification. SQAP indicates the minimum requirements which must be inspected on the product drawings to verify the design objectives of the product and assure interchangeability of repair parts.

6.6 Government-loaned property. The contracting officer should arrange to loan the property specified in 4.5.1.

6.6.1 Pamphlet. The contracting officer should arrange for the delivery of pamphlet AMSME-FB-P715-100 "Care, Operation and Maintenance of Inspection Equipment for Ponton Boat: Half-Section, Aluminum Hull, Spoon Bow, FSN 5420-542-4729", when requested.

6.7 Preproduction pack. Any changes or deviations of production packs from the approved preproduction pack will be subject to the approval of the contracting officer. Approval of the preproduction pack will not relieve the supplier of his obligation to package, pack, and mark the ponton boat sections in accordance with this specification.

Custodian:

Army - ME

Preparing activity:

Army - ME

Project No. 5420-A232

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T21:10Z
Check the source to verify that this is the current version before use.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T21:10Z
Check the source to verify that this is the current version before use.

SPECIFICATION ANALYSIS SHEET

Form Approved
Budget Bureau No 22-R255

INSTRUCTIONS: This sheet is to be filled out by personnel, either Government or contractor, involved in the use of the specification in procurement of products for ultimate use by the Department of Defense. This sheet is provided for obtaining information on the use of this specification which will insure that suitable products can be procured with a minimum amount of delay and at the least cost. Comments and the return of this form will be appreciated. Fold on lines on reverse side, staple in corner, and send to preparing activity. Comments and suggestions submitted on this form do not constitute or imply authorization to waive any portion of the referenced document(s) or serve to amend contractual requirements.

SPECIFICATION: MIL-P-52200B(ME) Ponton Boat: Half-Section, Aluminum Hull, Spoon Bow

ORGANIZATION

CITY AND STATE | CONTRACT NUMBER

MATERIAL PROCURED UNDER A

☐ DIRECT GOVERNMENT CONTRACT ☐ SUBCONTRACT

1. HAS ANY PART OF THE SPECIFICATION CREATED PROBLEMS OR REQUIRED INTERPRETATION IN PROCUREMENT USE?

A. GIVE PARAGRAPH NUMBER AND WORDING.

B. RECOMMENDATIONS FOR CORRECTING THE DEFICIENCIES

2. COMMENTS ON ANY SPECIFICATION REQUIREMENT CONSIDERED TOO RIGID

3. IS THE SPECIFICATION RESTRICTIVE?

☐ YES ☐ NO (If "yes", in what way?)

4. REMARKS (Attach any pertinent data which may be of use in improving this specification. If there are additional papers attach to form and place both in an envelope addressed to preparing activity.)

SUBMITTED BY (Printed or typed name and activity - Optional) | DATE

DD FORM 1426 REPLACES [illegible]

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T21:10Z
Check the source to verify that this is the current version before use.

FOLD

DEPARTMENT OF THE ARMY
U. A. ARMY MOBILITY EQUIPMENT COMMAND
RESEARCH, DEVELOPMENT AND ENGINEERING DIRECTORATE
ATTN: AMSME-RZG
FORT BELVOIR, VIRGINIA 22060

OFFICIAL BUSINESS

POSTAGE AND FEES PAID

DEPARTMENT OF THE ARMY
U. S. ARMY MOBILITY EQUIPMENT COMMAND
RESEARCH, DEVELOPMENT AND ENGINEERING DIRECTORATE
ATTN: AMSME-RZG
FORT BELVOIR, VIRGINIA 22060

FOLD

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T21:10Z
Check the source to verify that this is the current version before use.