INCH-POUND

MIL-T-52735B(ME)
21 August 1991
SUPERSEDING
MIL-T-52735A(ME)
18 November 1976

MILITARY SPECIFICATION

TRANSPORTER: M812 CHASSIS,

FOR

RIBBON FLOATING BRIDGE

This specification is approved for use within the USA Belvoir Research, Development and Engineering Center, Department of the Army, and is available for use by all Departments and Agencies of the Department of Defense.

1. SCOPE

1.1 Scope. This specification covers the ribbon bridge transporter assembly and the modifications to the M812 truck chassis necessary to accomplish installation of the assembly on the vehicle.

2. APPLICABLE DOCUMENTS

2.1 Government documents.

2.1.1 Specifications, standards, and handbooks. The following specifications, standards, and handbooks form a part of this document to the extent specified herein. Unless otherwise specified, the issues of these documents are those listed in the issue of the Department of Defense Index of Specifications and Standards (DODISS) and supplement thereto, cited in the solicitation (see 6.2).

Beneficial comments (recommendations, additions, deletions) and any pertinent data which may be of use in improving this document should be addressed to: USA Belvoir Research, Development and Engineering Center, ATTN: STRBE-TSE, Fort Belvoir, VA 22060-5606 by using the Standardization Document Improvement Proposal (DD Form 1426) appearing at the end of this document or by letter.

AMSC N/A FSC 5420

DISTRIBUTION STATEMENT A. Approved for public release; distribution is unlimited.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T21:31Z
Check the source to verify that this is the current version before use.

SPECIFICATIONS

FEDERAL

UU-T-81	- Tags, Shipping and Stock.
PPP-P-40	- Packaging and Packing of Hand Tools.

MILITARY

MIL-P-116	- Preservation, Methods of.
MIL-B-121	- Barrier Material, Greaseproofed, Waterproofed, Flexible.
MIL-S-196	- Support Items, Accessories, and Kits, Mechanical: Packaging of.
MIL-T-704	- Treatment and Painting of Materiel.
MIL-L-2104	- Lubricating Oil, Internal Combustion Engine, Tactical Service.
MIL-W-5044	- Walkway Compound, Nonslip and Walkway Matting, Nonslip.
MIL-E-10062	- Engines; Preparation for Shipment and Storage of.
MIL-L-21260	- Lubricating Oil, Internal Combustion Engine, Preservative and Break-In.
MIL-T-22085	- Tape, Pressure Sensitive, Adhesive, Preservation and Sealing.
MIL-C-24667	- Coating System, Nonskid, for Roll or Spray Application (Metric).
MIL-A-46153	- Antifreeze, Ethylene Glycol, Inhibited, Heavy Duty, Single Package.
MIL-C-46168	- Coating, Aliphatic Polyurethane, Chemical Agent Resistant.
MIL-C-53039	- Coating, Aliphatic, Polyurethane, Single Component, Chemical Agent Resistant (CARC), Lead and Chromate Free.
MIL-V-62038	- Vehicle, Wheeled, Preparation for Shipment and Storage of.

STANDARDS

MILITARY

MIL-STD-105	- Sampling Procedures and Tables for Inspection by Attributes.
MIL-STD-129	- Marking for Storage and Shipment.
MIL-STD-209	- Slinging and Tiedown Provisions for Lifting and Tying Down Military Equipment.
MIL-STD-810	- Environmental Test Methods and Engineering Guidelines.
MIL-STD-889	- Dissimilar Metals.
MIL-STD-1261	- Arc Welding Procedures for Constructional Steels.
MIL-STD-1791	- Design for Internal Aerial Delivery in Fixed Wing Aircraft.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T21:31Z
Check the source to verify that this is the current version before use.

(Unless otherwise indicated, copies of federal and military specifications, standards, and handbooks are available from the Standardization Documents Order Desk, Building 4D, 700 Robbins Avenue, Philadelphia, PA 19111-5094.)

2.1.2 Other Government documents, drawings, and publications. The following other Government documents, drawings, and publications form a part of this document to the extent specified herein. Unless otherwise specified, the issues are those in effect on the date of the solicitation.

DRAWINGS

ME

TA13219E4111 - Transporter, Tactical Floating Bridge.
13219E4150 - Chassis, Truck, M812.

(Copies of drawings required by contractors in connection with specific acquisition functions should be obtained from the USA Belvoir Research, Development and Engineering Center, ATTN: STRBE-JBS, Fort Belvoir, VA 22060-5606.)

MILITARY TRAFFIC MANAGEMENT COMMAND (MTMC/TEA)

Pamphlet 70-1 - Transportability for Better Strategic Mobility.

(Application for copies should be addressed to the Military Traffic Management Command/Transportation Engineering Agency (MTMC/TEA), ATTN: MTT-TR, P.O. Box 6276, Newport News, VA 23606-0276.)

2.2 Non-Government publications. The following document forms a part of this specification to the extent specified herein. Unless otherwise specified, the issues of the documents which are DoD adopted are those listed in the issue of the DODISS cited in the solicitation. Unless otherwise specified, the issues of documents not listed in the DODISS are the issues of the documents cited in the solicitation (see 6.2).

AMERICAN SOCIETY OF MECHANICAL ENGINEERS (ASME)

Boiler and Pressure Vessel Code, Section IX, Qualification Standard for Welding and Brazing Procedures, Welders, Brazers, Welding and Brazing Operators.

(Application for copies should be addressed to the American Society of Mechanical Engineers, 345 East 47th Street, New York, NY 10017.)

AMERICAN WELDING SOCIETY, INC. (AWS)

D1.1 Structural Welding Code - Steel.

(Application for copies should be addressed to the American Welding Society, Inc., 550 N.W. LeJeune Road, P.O. Box 351040, Miami, FL 33135.)

Source: https://assist.dla.mil -- Downloaded: 202640-22T21:31Z
Check the source to verify that this is the current version before use.

NATIONAL MOTOR FREIGHT TRAFFIC ASSOCIATION (NMFTA)

National Motor Freight Classification Rules.

(Application for copies should be addressed to the American Trucking Association, Inc., ATTN: Traffic Order Section, 2200 Mill Road, Alexandria, VA 22314.)

UNIFORM CLASSIFICATION COMMITTEE (UCC)

Uniform Freight Classification Rules.

(Application for copies should be addressed to Uniform Classification Committee, ATTN: Tariff Publishing Officer, Room 1106, 222 South Riverside Plaza, Chicago, IL 60606.)

(Non-Government standards and other publications are normally available from the organizations which prepare or which distribute the documents. These documents also may be available in or through libraries or other informational services.)

2.3 Order of precedence. In the event of a conflict between the text of this document and the references cited herein (except for related associated detail specifications, specification sheets or MS standards), the text of this document takes precedence. Nothing in this document, however, supersedes applicable laws and regulations unless a specific exemption has been obtained.

3. REQUIREMENTS

3.1 Description. The transporter, or separately procured component(s) thereof, shall be in accordance with top assembly TA13219E4111 and as specified herein. The transporter is a 10-wheeled, 5-ton capacity, diesel-powered truck designed to launch and retrieve ribbon bridge bays and to provide overland transportation. In addition to the M812 chassis, the assembly consists of a front support member upon which is mounted a receptacle for the boom tip, the locking pin hydraulic cylinder and the personnel guard with hydraulic control station and access ladder, the front bay support member complete with two roller assemblies, and, for lifting the bridge bays, a hydraulically actuated boom equipped with four rollers, two tiedown hooks and a hydraulic winch. The transporter hydraulic system is an open-centered circuit operating at 2500 pounds per square inch (psi). The pump is driven by a power take-off from the transmission and supplies oil from a reservoir to a filter, two 5-inch diameter cylinders for operation of the boom, a 3-inch cylinder for locking the bridge bay onto the truck, and an 11,000-pound line pull hydraulic winch. The transporter has lights on the boom and personnel guard for night operation and an electrically operated parking brake for use during launch or retrieval operations.

3.1.1 Drawings. The drawings forming a part of this specification are end product drawings. No deviation from the requirements shown on the drawings is permissible without prior approval of the contracting officer. Where tolerances could cumulatively result in incorrect fits, the contractor shall provide tolerances within those prescribed on the drawings to ensure correct

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T21:31Z
Check the source to verify that this is the current version before use.

fit, assembly and operation of the transporter. Any data (e.g. shop drawings, layouts, flow sheets, processing procedures, etc.) prepared by the contractor or obtained from a vendor to support fabrication and manufacture of the production item shall be made available, upon request, for inspection by the contracting officer or his designated representative. Dimensions shown on drawings shall be verified using parts at 68 degrees Fahrenheit (F) to 70 °F.

3.2 First article. Unless otherwise specified (see 6.2), a sample ribbon bridge transporter(s) or separately procured component(s) shall be subjected to first article inspection (see 6.3) in accordance with 4.3.

3.2.1 Hydraulic system components. In addition to the first article, and unless otherwise specified (see 6.2), a sample of the following hydraulic components shall be subjected to first article inspection (see 6.3) in accordance with 4.3 prior to the time the first article is furnished: One each of all pressure relief and check valves, flow regulators, quick disconnect couplings, and one valve control bank. The hydraulic components shall be identical to those furnished on the first article.

3.2.2 Transportation data. When specified (see 6.2), a first article transporter shall be weighed, measured, and the center of gravity located to provide the data required for the transportation data plate.

3.3 Material. Material shall be as specified herein and on the applicable drawings. Material not specified shall be selected by the contractor and shall be subject to all provisions of this specification. Copies of analyses and test reports for all materials shall be available for inspection. Chemical composition and mechanical properties of heat-treated materials shall be verified by chemical analysis and mechanical tests. Unless otherwise specified (see 6.2), the age of rubber products furnished shall not exceed 24 months from the date of issue to date of acceptance of the transporter or separately procured component(s) by the Government.

3.3.1 Material deterioration prevention and control. The transporter or separately procured components shall be fabricated from compatible materials, inherently corrosion resistant or treated to provide protection against the various forms of corrosion and deterioration that may be encountered in any of the applicable storage and operating environments to which the item may be exposed.

3.3.1.1 Dissimilar metals. Dissimilar metals shall not be used in intimate contact with each other unless protected against galvanic corrosion. Dissimilar metals and methods of protection are defined and detailed in MIL-STD-889.

3.3.1.2 Identification of materials and finishes. The contractor shall identify the specific material, material finish or treatment for use with components and subcomponents, and shall make information available, upon request, to the contracting officer or designated representative.

3.3.1.3 Recovered materials. For the purpose of this requirement, recovered materials are those materials which have been collected from solid waste and reprocessed to become a source of raw materials, as distinguished

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T21:31Z
Check the source to verify that this is the current version before use.

from virgin raw materials. The components, pieces and parts incorporated in the transporter may be newly fabricated from recovered materials to the maximum extent practicable, provided the transporter produced meets all other requirements of this specification. Used, rebuilt or remanufactured components, pieces and parts shall not be incorporated in the transporter.

3.4 Structural performance. The transporter shall perform all tests specified herein without structural failure or permanent deformation attributable to nonconforming materials, dimensions, incorrect assembly or adjustment, tolerances, or incorrect workmanship.

3.5 Fuel, coolant, lubricants, and hydraulic fluid. The transporter shall be serviced, tested and furnished with standard military service products of the types and grades as specified on the lubrication order (LO). The hydraulic system shall be filled and tested with oil conforming to MIL-L-2104, grade 10, and shall not show visual evidence of contamination when examined as specified herein.

3.6 Transporter assembly. The transporter shall be assembled utilizing the Government-furnished 5-ton, 6 x 6, M812 truck chassis conforming to 13219E4150 (see 6.4). All other items shall be fabricated and installed or procured and installed by the contractor.

3.6.1 Transporter and transporter systems assembly, installation and adjustments. The components of the various systems of the transporter shall be assembled, installed and adjusted to assure acceptable performance of the completed transporter as specified herein. All like components shall be interchangeable with respect to installation, performance and quality. All adjustments not requiring an operational transporter shall be completed prior to initial start-up. Care shall be exercised to assure that final adjustments which must be completed after the transporter is operational will not result in a safety hazard when the engine is started.

3.6.2 Initial start-up. Prior to starting the engine with power take-off engaged, the hydraulic system shall conform to the cleanliness requirements specified in 3.8.2.2, and the entire transporter shall be serviced in accordance with 3.5. The engine shall be prepared, started and operated in accordance with the engine manufacturer's run-in and operating procedures. Upon starting the engine, all final adjustments shall be performed and examined as specified in 4.5 to assure correct assembly and operation.

3.7 Electrical system. The electrical circuitry and connections shall be assembled and installed to assure conductance of the full electrical capacity of the components connected. The full electrical insulation qualities of all dielectric components shall not be reduced by assembly or installation. Electrical connection points shall be bare and clear of paint and other dielectric materials. All exposed parts which are electrically energized shall be insulated, fully enclosed or guarded. Electrical cables shall be installed without excess slack and secured to prevent slippage through the cable clamps. The electrical circuits shall operate their respective electrical functions when tested as specified in 4.5.2.2.

3.8 Hydraulic system.

Source: https://assist.dla.mil -- Downloaded: 202610-22T21:31Z
Check the source to verify that this is the currentversion before use.

3.8.1 Hydraulic system installation. Tubing and components shall be as specified herein and on the applicable drawings. The components and tubing shall be painted as specified in 3.9 prior to installation and shall be secured by brackets or clamps to prevent movement or chafing of the tubes. Connection points shall be bare and clear of paint, and special care shall be taken to prohibit the entrance of sealant into the system.

3.8.2 Hydraulic system cleanliness.

3.8.2.1 Hydraulic fluid filtration and sampling. Prior to first article approval, the contractor shall submit, for approval, a filtration procedure for the hydraulic system. Hydraulic fluid samples shall be taken between the exit side of the valve control, and the hydraulic reservoir.

3.8.2.2 Pre-operation cleanliness. The assembled hydraulic system, including all Government-furnished hydraulic components (see 3.6), shall be flushed and the hydraulic fluid cleanliness level shall be in conformance to table I.

TABLE I. Contamination limits (particles per milliliter).

Quantity (max)	Particle Size
1000	Greater than 10 microns
100	Greater than 20 microns
40	Greater than 30 microns
10	Greater than 40 microns

3.8.2.3 Post-operation cleanliness. After all operational testing, the hydraulic fluid cleanliness level shall be in conformance to table I.

3.8.3 System performance. The hydraulic system shall be filled with the specified fluid, bled of air, and adjusted to assure acceptable performance of each hydraulic function. The controls and components of the hydraulic circuitry shall start, correctly operate, and stop all hydraulic functions in a smooth controlled fashion without binding, chatter, erratic response, vibration, or abnormal noise. The hydraulic pump shall develop a minimum of 2400 pounds per square inch (psi) at 1000 engine revolutions per minute (rpm) when the hydraulic oil temperature is 180 °F, ±5 °F.

3.8.3.1 Lifting/loading. The assembled transporter shall be capable of lifting an interior bay assembly using the high-bank launch procedure as described in the approved technical manual (TM).

3.8.4 Cylinders. Cylinders shall be fully charged with hydraulic oil conforming to MIL-L-2104, which meets the contamination limits specified in table I. Ports shall be plugged with threaded steel plugs. Exposed piston rod threads shall be protected with threaded steel protectors (see 5.1.1.8).

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T21:31Z
Check the source to verify that this is the current version before use.

3.9 Treatment and painting. Cleaning, treatment and painting of components shall be in accordance with the applicable drawings and as specified herein. Where MIL-T-704, type F or G, paint is required (see 6.2), the finish coat shall conform to MIL-C-46168 or MIL-C-53039, camouflage green 383. Surfaces inaccessible for painting after installation shall be painted before installation. All surfaces, with the exception of the winch cable, glass, rubber, bearing surfaces, and the piston rod, shall be painted. Nonslip coating conforming to MIL-W-5044, type II or MIL-C-24667, type I, composition G, grade A, class 1 shall be applied to all walkway surfaces, the top surface of the front support, and the top surface of the boom assembly, as observed in the folded or down position. The sequence of application shall be MIL-T-704 primer, MIL-W-5044 or MIL-C-24667 nonslip coating, and MIL-C-46168 or MIL-C-53039 top coat.

3.10 Marking. Identification markings, level indications, jacking and lifting points, warnings, and all other marking shall be as specified on the applicable drawings.

3.11 Government-loaned property. When specified (see 6.2), any or all of the following property in the quantities indicated will be loaned by the Government (see 6.5):

Item	Identification	Description	Quantity
1	5420-00-071-5322, type I	Bay Assembly, Interior	1
2	5420-00-497-5276, type II	Bay Assembly, Ramp	1
3	3940-00-214-7493	Sling, Bay Lifting	1
4	3940-00-338-5653	Snatch Block	1
5	TM5-5420-209-12	Operator's Manual	1

3.12 Performance. The transporter shall perform as specified herein without evidence of any of the following defects:

a. Malfunctioning of components.
b. Binding of parts or improper fit during launching and retrieving of bridge bays.
c. Permanent distortions (other than normal wear).
d. Material defects such as cracks and open joints.
e. Failure of mechanical mechanisms to operate as required.
f. External hydraulic leakage.
g. Failure of hydraulic systems to operate as required.
h. Failure of winch to operate as required.

3.12.1 Operational characteristics. The transporter shall:

a. Be capable of launching a bridge bay within 5 minutes and retrieving it within 10 minutes.
b. Perform "high-bank" launches and retrievals as described in the approved technical manual (TM).

3.12.2 Equipment publications. Operating and maintenance functions of the transporter shall conform to applicable sections of the approved TM (see 3.11 and 6.6).

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T21:31Z
Check the source to verify that this is the current version before use.

3.13 Reliability. The transporter shall exceed acceptance criteria based on an upper test value of 50 mean missions between failure (MMBF) and a lower test value of 40 MMBF. A mission consists of the required transport distance and one launch/retrieve cycle (see 4.5.2.12.1).

3.14 Maintenance ratio. The transporters shall have a maintenance ratio of not more than 0.183. Maintenance ration (MR) is defined as the ratio of the total active maintenance man-hours required (scheduled and unscheduled) to the total operating time. Man-hours for repair of replaced components and scheduled before-and-after operation checks are excluded. A maintenance schedule shall be established prior to the start of any testing.

3.15 Interchangeability. All parts, components and assemblies having the same identification number shall be functionally and dimensionally interchangeable. Interchangeability is defined as two or more parts (components and assemblies) possessing such functional and physical characteristics as to be equivalent in performance and durability and capable of being exchanged one for the other without alteration of themselves or of adjoining parts (components and assemblies), except for built-in adjustment, and without selection for fit and performance.

3.16 Specification-control items and source-control items. Prior to using any specification-control item other than a suggested source item, the contractor shall furnish to the contracting officer evidence that the item conforms to all requirements on the applicable drawing. The contractor is responsible for performing all inspections and tests on specification or source control items if not performed by the vendor. No change shall be made to any source or specification control item after approval of the first article without prior approval by the contracting officer.

3.17 Workmanship.

3.17.1 Transporter assembly. The transporter shall be assembled in accordance with the requirements specified on the applicable drawings and specifications. All parts, components and assemblies containing moving parts shall be assembled free of harmful extraneous materials such as metallic particles, dirt, grit, or corrosion.

3.17.2 Castings and forgings. All parts, components, and assemblies of the transporter which include castings and forgings shall be clean of extraneous material such as sand, dirt, pits, sprues, scale, and flux. Rework shall be limited to procedures which do not reduce mechanical properties or affect function.

3.17.3 Metal fabrication. Metal used in fabrication shall be free from kinks and sharp bends. The straightening of material shall be done by methods that will not cause injury to the material. Corners shall be square and true. Flame-cutting, using tips suitable for the thickness of the steel, may be employed instead of shearing and sawing for steel only. All bends shall be made with controlled means to ensure uniformity of size and shape. Precaution shall be taken to avoid overheating. Heated steel shall be allowed to cool slowly. All parts shall be completely and accurately shaped to the drawing requirements prior to joining (welding). Joints, butts and splices shall be

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T21:31Z
Check the source to verify that this is the current version before use.

limited to those shown on the end product drawings. External surfaces shall be free of burrs, sharp edges and corners, except when sharp edges or corners are required or where they are not detrimental to safety.

3.17.4 Steel welds. The surfaces of parts to be welded shall be free from rust, scale, paint, grease, mill scale and other foreign matter. Parent materials, weld filler metals, and fabrication techniques shall be as required to enable the transporter to conform to the examination and test requirements specified in section 4. Parts to be joined by fillet welds shall be brought into as close contact as possible and in no event shall be separated by more that 0.188 inch unless appropriate bridging techniques are used. Procedures and sequences shall be such that distortion and shrinkage will be held to a minimum. When straightening is required, caution shall be exercised to ensure that the straightening process does not weaken the part and the complete item. Tack welds shall have the same quality requirements as the final weld. Weldments, weld beads, and tack welds shall be:

a. Homogenous in appearance.
b. Smoothly blended into the base metal without spattering or other irregularities.
c. Able to transmit stress without permanent deformation or failure when parts connected by welds are subjected to service loading.

Welding shall be in accordance with AWS D1.1. Prior to any welding, welding procedures shall be qualified for each joint as specified in AWS D1.1. Guided bend tests shall be used for procedure qualification. Welding procedures shall be available at each welding station for welder's or operator's reference. The welding procedure specifications and qualifications shall be made available for review by the contracting officer or his representative.

3.17.5 Care of welding electrodes. Care of welding electrodes specified for welding high-strength steel shall be as follows:

a. When a container of welding electrodes is opened, the entire contents shall be placed immediately in a baking oven, with electrodes placed not more than three layers deep on a tray, and baked either (1) for a minimum of 1 hour, but not more than 1-1/4 hours, at 800 °F; or (2) for a minimum of 4 hours at 400 °F.
b. The baked electrodes, while still warm, shall then be placed in a ventilated holding oven set at 250 °F to 300 °F.
c. Not more than a 1/2-hour supply of welding electrodes shall be taken from the holding oven at one time.
d. If electrodes are out of the holding oven in excess of 1/2 hour but less than 1 hour, they shall be returned to the holding oven for a period of not less than 1 hour.
e. If electrodes are out of the holding oven in excess of 1 hour, they shall be returned to the baking oven and rebaked as described under "a".
f. Electrodes removed for use shall not be allowed to come in contact with any moist or wet surfaces. Electrodes that have been in contact with water, grease or oil shall not be used.

Source: https://assist.dla.mil -- Downloaded: 202640-22T21:31Z
Check the source to verify that this is the current version before use.

3.17.6 Welders. Before assigning any welder or welding operator to welding work covered by this specification, the contractor shall provide the contracting officer with certification that the welder or welding operator has passed qualification tests as prescribed by either of the following listed codes for the type of welding operation to be performed and that such qualification is effective as defined by the particular code:

ASME Boiler and Pressure Vessel Code, Section IX
AWS D1.1 Structural Welding Code - Steel

Contractors who only make horizontal welds need not qualify welders for all position welding. In the event of evidence of poor welds, the Government reserves the right to require retesting of any welder or welding operator. The test results shall be made available for review by the contracting officer's representative.

3.17.7 Weld repairs. All areas of defective or unacceptable welds shall be repaired in accordance with the weld repair procedures specified in MIL-STD-1261 and shall be subject to prior approval of the contracting officer. Repair of any defective weld shall be limited to two rewelds.

3.17.8 Hoses and tubing. All hoses and tubing shall be installed without twists, kinks or collapsed sections. Tubing bends shall be in accordance with the drawing requirements. Tubing shall not be reformed. Tubing assemblies shall be correctly formed to prevent prestress at installation due to misalignment. Tubes, hoses or their connections shall not leak when tested as specified in 4.5.2.

3.17.9 Machine work. Tolerances and gauges for metal fits shall conform to the limits specified on the applicable end product drawings.

3.17.10 Jigs and fixtures. Fabrication, assembly and installation of all transporter components (except minor parts) shall be accomplished with production tooling, jigs or fixtures, and parts shall be joined while held in position. Jigs or fixtures shall be designed to minimize distortion of the parts being welded and to assure that the configuration, alignment and location of parts meet the specified requirements. Subsequent straightening and thermal stress relieving is permitted to relieve distortion, provided the straightening process does not damage the component.

3.17.11 Bolted connections. Bolt holes shall be accurately formed and shall have the burrs removed. Washers or lockwashers shall be provided where necessary. Matching thread areas securing bolts or capscrews shall be of sufficient strength to withstand the tensile strength of the bolt. All fasteners shall be correctly torqued and shall have full thread engagement. Bolts shall protrude not more that two full threads.

3.18 Transportability. The transporter shall be capable of being transported by military or commercial trailers, trains, marine vessels, aircraft and must be capable of withstanding the impact forces encountered in shipment without damage or permanent deformation. The transporter shall be equipped with tiedown or slinging provisions.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T21:31Z
Check the source to verify that this is the current version before use.

3.18.1 Tiedown provisions. The tiedown provisions shall conform to MIL-STD-209, class 2 or 3, type II equipment, and to MIL-STD-1791 for equipment restraint criteria. The tiedown provisions shall satisfactorily complete the pull testing as specified without weld failure, permanent deformation, cracking, loosening, or breaking of the provision or its connecting structural components.

3.18.2 Slinging provisions. The slinging provisions shall conform to MIL-STD-209, class 1 or 3, type II. The provisions shall enable the complete transporter to be lifted in the normal operating position. The provisions shall be located so that not less than one inch clearance is maintained between slings and all exterior parts and shall be fastened to members which will withstand stresses in the amount and direction of pull specified in the provisions without weld failure, permanent deformation, cracking, loosening, or breaking of the provision or its connecting structural components. Slinging provisions may also be used as tiedown provisions when such provisions meet the requirements specified in 3.18.1. All slinging/tiedown provisions shall be labeled "LIFT", "TIEDOWN" or "LIFT TIEDOWN", as appropriate, in 1-inch (2.54 cm) high letters.

3.18.3 Air transportability. The transporter shall meet the requirements of MIL-STD-1791 for air transport. When required (see 6.2), the contractor shall provide sufficient data to the Government in the transportability report to confirm that the transporter being supplied can be loaded and transported in the C-130, C-141 and C-5A aircraft and lifted by helicopters.

3.18.4 Rail transportability. The transporter shall be rail transportable in CONUS and NATO countries without restrictions. The transporter shall have a dimensional profile within the Gabarit International de Chargement (GIC) in accordance with MTMC/TEA pamphlet 70-1, outline diagram when loaded on a 50-inch (127 cm) high rail car. The transporter shall be capable of withstanding shock loads resulting from rail impact testing in accordance with 4.5.2.9 without failure, damage or permanent deformation.

3.18.5 Highway transportability. The transporter when loaded on a semitrailer/tractor, shall be within the highway permit limits of all states.

4. *QUALITY ASSURANCE PROVISIONS*

4.1 Responsibility for inspection. Unless otherwise specified in the contract or purchase order, the contractor is responsible for the performance of all inspection requirements (examinations and tests) as specified herein. Except as otherwise specified in the contract or purchase order, the contractor may use his own or any other facilities suitable for the performance of the inspection requirements specified herein, unless disapproved by the Government. The Government reserves the right to perform any of the inspections set forth in the specification where such inspections are deemed necessary to assure supplies and services conform to prescribed requirements.

4.1.1 Responsibility for compliance. All items must meet all requirements of sections 3 and 5. The inspection set forth in this specification shall become a part of the contractor's overall inspection system or quality

Source: https://assist.dla.mil -- Downloaded: 202640-22T21:31Z
Check the source to verify that this is the current version before use.

program. The absence of any inspection requirements in the specification shall not relieve the contractor of the responsibility of assuring that all products or supplies submitted to the Government for acceptance comply with all requirements of the contract. Sampling inspection, as part of manufacturing operations, is an acceptable practice to ascertain conformance to requirements, however, this does not authorize submission of known defective material, either indicated or actual, nor does it commit the Government to acceptance of defective material.

4.1.2 Component and material inspection. The contractor is responsible for ensuring that components and materials used are manufactured, examined, and tested in accordance with referenced specifications and standards, as applicable.

4.1.3 Parts and components. Parts and components detailed on the drawings shall be inspected in accordance with the quality assurance provisions (QAP) shown on the drawings. The drawings specify the characteristics requiring QAP inspection, the sampling plan, and the basis for acceptance and rejection (see 6.8 and 6.9.1).

4.2 Classification of inspections. The inspection requirements specified herein are classified as follows:

a. First article inspection (see 4.3).
b. Quality conformance inspection (see 4.4).
c. Inspection comparison (see 4.6).
d. Inspection of packaging (see 4.7).

4.3 First article inspection.

4.3.1 Examination. The first article transporter or separately procured component(s) shall be examined as specified in 4.5.1. Presence of one or more defects shall be cause for rejection.

4.3.2 Tests. The first article transporter shall be tested as specified in 4.5.2.1 through 4.5.2.6. Failure of any test shall be cause for performing the disassembly inspection specified in 4.1.3.

4.4 Quality conformance inspection.

4.4.1 Sampling. Sampling for examination and tests for separately procured transporter components shall be in accordance with MIL-STD-105.

4.4.2 Examination.

4.4.2.1 Individual. Each transporter shall be examined for the defects specified in 4.5.1. Presence of one or more defects shall be cause for rejection.

4.4.2.2 Samples. Samples of separately procured components selected in accordance with 4.4.1 shall be examined for the applicable defects specified in 4.5.1. A lot will be accepted when zero defects are found and rejected if one or more defects are found.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T21:31Z
Check the source to verify that this is the current version before use.

4.4.3 Tests.

4.4.3.1 Individual. Each transporter shall be tested as specified in 4.5.2.1 through 4.5.2.6. Failure of any test shall be cause for rejection.

4.4.3.2 Samples. Samples of separately procured components selected in accordance with 4.4.1 shall be subjected to the applicable test(s) specified in 4.5.2.1 through 4.5.2.6. A lot will be accepted when zero defects are found and rejected if one or more defects are found.

4.5 Inspection procedure.

4.5.1 Examination. The transporter(s) or separately procured components shall be examined as specified herein for the following defects, as applicable:

Major

101. Parts or components not in accordance with the QAP requirements as shown on the end product drawings (see 3.1.1).
102. Dimensions other than those identified on the QAP requirements shown on the drawings not as specified (see 3.1.1).
103. Transportation data not as specified, when required (see 3.2.2).
104. Materials not as specified (see 3.3).
105. Age of rubber products not within specified limits (see 3.3).
106. Materials not resistant to corrosion and deterioration, or treated to be resistant to corrosion and deterioration for the applicable storage and operating environments (see 3.3.1).
107. Dissimilar metals as defined in MIL-STD-889 are not effectively insulated from each other (see 3.3.1.1).
108. Contractor does not have documentation available for identification of material, material finishes or treatment (see 3.3.1.2).
109. Used, rebuilt or remanufactured components, pieces or parts incorporated in the transporter (see 3.3.1.3).
110. Structural performance not as specified (see 3.4).
111. Fuel, coolant, lubricants, and hydraulic fluid not as specified (see 3.5).
112. Lubrication fittings not as specified (see 3.5).
113. Transporter and transporter systems assembly, installation and adjustments not as specified (see 3.6.1).
114. Components missing or not as specified (see 3.6.1).
115. Electrical system performance and installation not as specified (see 3.7).
116. Hydraulic system performance and installation not as specified (see 3.8).
117. Cleaning, treatment and painting not as specified (see 3.9).
118. Nonskid compound missing or not as specified (see 3.9).
119. Identification marking missing or not as specified (see 3.10).
120. Transporter performance not as specified (see 3.12).
121. Operational characteristics not as specified (see 3.12.1).
122. Components not interchangeable as specified (see 3.15).
123. Specification and source control items not as specified (see 3.16).
124. Workmanship not as specified (see 3.17).

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T21:31Z
Check the source to verify that this is the current version before use.

125. Welding and welds not as specified (see 3.17.4).
126. Welder or welding operator qualification not as specified (see 3.17.6).
127. Torque of bolts not as specified (see 3.17.11).
128. Transportability provisions not as specified (see 3.18.1 through 3.18.5).

4.5.1.1 Welding examination. All areas of welded assemblies affected by the welding processes shall be examined prior to plating, painting, or installation for evidence of defects, including base metal cracks, weld cracks, undercutting, lack of fusion, porosity, lack of penetration, incorrect fit, incorrect preparation for welding, inclusions, incorrect weld size, and incorrect welding procedures. Weld quality shall be examined and compared against the approved welding specimens (see 3.17.4). All welds shall be visually examined with the aid of a 5X magnifying glass. Evidence of weld defects in excess of the soundness requirements shown on the applicable drawings shall constitute failure of this examination.

4.5.1.2 Weld repair examination. All weld repair areas shall be visually examined with the aid of a 5X magnifying glass. Weld repairs which evidence defects in excess of that exhibited by the weld specimens or soundness requirements specified in 3.17.7 shall constitute failure of this examination.

4.5.2 Tests.

4.5.2.1 Test conditions.

a. All test apparatus shall be accurate to within 3 percent of full scale reading. The transporter instruments may be used to the extent possible for test data readings. All pertinent test data shall be recorded and validated by the contractor and by the Government representative.
b. The transporter shall be serviced in accordance with the lubrication order (LO) as contained in the TM (see 3.12.2). Fuel and lubricants shall be those designated for use in the ambient temperature at the place of test.
c. Unless otherwise specified (see 6.2), the transporter shall be equipped with an interior bay (see 3.11), and all tests shall be performed at the climatic conditions existing at the place of test.
d. The transporter shall operate as specified herein without maintenance other than that established by the lubrication order contained in the approved TM.
e. During the test, all equipment shall be operated in accordance with the approved TM.
f. The sequence of testing shall be as follows:
   (1) Electrical system circuitry (sequence optional).
   (2) Hydraulic system pretest cleanliness.
   (3) Hydraulic system performance.
   (4) Lift and loading test.
   (5) Hydraulic system post-test cleanliness.
   (6) Reliability and maintainability.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T21:31Z
Check the source to verify that this is the current version before use.

4.5.2.2 Electrical circuitry. Actuate each electrical circuit of the transporter and observe the response of each respective electrical function. Nonconformance to any drawing requirement or to any specification referenced herein shall constitute failure of this test.

4.5.2.3 Pretest cleanliness.

a. The assembled hydraulic system shall be flushed as specified in 3.8.2.2. An oil sample shall be taken as specified in 3.8.2.1 and a particle count taken of the sample.
b. If the particle count exceeds the values shown in table I, continue flushing the system until contamination is reduced to the acceptable level.

4.5.2.3.1 Failure criteria. Nonconformance to 3.8.2.2 shall constitute failure of this test.

4.5.2.4 System performance and test procedure.

4.5.2.4.1 Hydraulic system.

a. Operate the hydraulic system for 10 minutes, actuating the boom and rear winch in both directions sufficiently to detect any chatter, vibration or erratic response.
b. At the end of this 10-minute period, set the engine at 1000 rpm and actuate the boom control valve by shifting the lever to the down position.
c. Record the relief valve setting for a sustained 3-minute period.
d. Continue to operate against the relief valve until the oil temperature reaches 180 °F, ±5 °F.
e. Verify that the pump will produce 2400 psi at 1000 engine rpm when the oil temperature is 180 °F, ±5 °F.
f. Record the maximum pressure developed when working against the relief valve at an engine speed of 1900 rpm.
g. Operate the front winch sufficiently to detect any chatter, vibration or erratic response.

4.5.2.4.2 Lifting/loading.

a. Remove the transporter pintle hook.
b. Place the bogie brackets in position and attach the boom cable to the lifting sling for a controlled high-bank launch (see approved TM).
c. Lift an interior bay assembly and hold approximately 1 foot high for 5 minutes.
d. Lower the load approximately 6 inches and hold for 3 minutes.
e. After a successful completion of this lift, lower the load, re-rig, remove bogie brackets, and load the bay on the transporter.
f. Verify that the travel restraints and loading brackets fit and function correctly.

4.5.2.4.3 Failure criteria. Nonconformance to 3.8.3 shall constitute failure of this test.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T21:31Z
Check the source to verify that this is the current version before use.

4.5.2.5 Post-test cleanliness.

a. Following completion of the tests specified in 4.5.2.4, an oil sample shall be taken as specified in 3.8.2.1 and a particle count taken of the sample.
b. If the particle count exceeds the values in table 1, continue flushing and sampling until contamination is reduced to the acceptable level.
c. After achieving the required cleanliness level, and prior to delivery to the Government, the alternate filter arrangement shall be removed and the specified filter element, as shown on the applicable drawings, shall be installed.

4.5.2.5.1 Failure criteria. Nonconformance to 3.8.2.3 shall constitute failure of the test.

4.5.2.6 Tiedown provisions test. The tiedown provisions shall be tested in accordance with MIL-STD-209 to prove conformance to 3.18.1. Inability to meet the requirements of 3.18.1 shall constitute failure of this test.

4.5.2.7 Slinging provisions test. The slinging provisions shall be tested in accordance with MIL-STD-209 to prove conformance to 3.18.2. Inability to meet the requirements of 3.18.2 shall constitute failure of this test.

4.5.2.8 Air transport test. The transporter shall be tested in accordance with MIL-STD-1791 to prove conformance to 3.18.3. Inability to meet the requirements of 3.18.3 shall constitute failure of this test.

4.5.2.9 Rail impact test. The first article transporter shall be tested in accordance with MIL-STD-810 to prove conformance to 3.18.4. Inability to meet the requirements of 3.18.4 shall constitute failure of this demonstration.

4.5.2.9.1 Failure criteria. Failure to meet the requirements of 3.18.4 and 4.5.2.9 rail impact test shall constitute failure of this test.

4.5.2.10 Highway transport test. Inability to meet the requirements of 3.18.5 shall constitute failure of this test.

4.5.2.11 Post-test hydraulic cleanliness. After completion of the above tests, the hydraulic system cleanliness shall be checked by taking a particle count. If the particle count exceeds the values in table I, the system shall be flushed until contamination is reduced to the acceptable level. Inability to conform to the cleanliness levels specified in table I shall constitute failure of this test. After achieving the required cleanliness, and prior to delivery to the Government, a new filter element shall be installed.

4.5.2.12 Reliability and maintainability. This test will be conducted by the Government at a site selected by the Government. The test will be conducted using a minimum of 16 transporters. Maintenance shall be performed in accordance with the technical manual, and at the end of each day's mission, any damage to the transporters will be repaired prior to the next day's mission. Failure to meet all performance requirements of this specification, when such failure is due to faulty material or workmanship, shall be cause for refusal by the Government to continue acceptance of production units until

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T21:31Z
Check the source to verify that this is the current version before use.

evidence has been provided by the contractor that corrective action has been taken to eliminate the deficiencies. Correction of such deficiencies shall be accomplished by the contractor at no cost to the Government on all units previously produced. Any such material or workmanship deficiencies will be considered prima facie evidence that all units accepted prior to the completion of this test are similarly deficient unless evidence to the contrary is furnished by the contractor and such evidence is acceptable to the contracting officer.

4.5.2.12.1 Reliability-maintainability test cycle. Reliability-maintainability testing shall be conducted for 100 bridge missions for each transporter. Each bridge mission for a transporter shall consist of the following:

a. One launch/retrieve cycle.
b. 20 miles of transporting.

4.5.2.12.2 Reliability. Test each transporter for 100 missions, for a total of 1600 overall missions. If 35 or fewer total failures out of 1600 missions occur, reliability is acceptable. If at any time during the test greater than 35 failures occur, reliability is not acceptable and the test is terminated. For the purpose of reliability computations a mission failure is defined as follows:

a. Any malfunction which would cause inability to complete a bridge mission specified in 4.5.2.12.1 and cannot be repaired by the crew or organizational maintenance within one hour. Any malfunction requiring repair at a higher maintenance level is considered a mission failure.
b. Any impending malfunction which would require maintenance that cannot be deferred until the end of the bridge mission which would create a safety hazard if the mission continued and cannot be repaired by the crew or organization maintenance within one hour.

Simultaneous related malfunctions are considered one failure.

4.5.2.12.3 Maintainability. The maintenance man-hours required to perform all corrective and preventive maintenance occurring during the reliability test (see 4.5.2.12.1) shall be recorded and classified as to whether it was scheduled or unscheduled. The MR requirement of 3.14 shall be assessed using the following formula:

$$MR = \frac{\text{Total Scheduled Maintenance Man-hrs} + \text{Total Unscheduled Maintenance Man-hrs}}{\text{Total Operating Time}}$$

Operator/crew checks and services are excluded from this ratio.

4.6 Inspection comparison. The Government may select transporters at any time during the contract production period and subject these transporters to the examination specified in 4.5.1 and the tests specified in 4.5.2 to determine conformance to the requirements of this specification. The inspection will be performed by the Government, at a site selected by the Government, on transporters selected at random from those which have been accepted by the Government and will not include the previously inspected first

Source: https://assist.dla.mil -- Downloaded: 202640-22T21:31Z
Check the source to verify that this is the currentversion before use.

article. In addition to any test specified as part of the inspection comparison, the Government reserves the right to conduct any and all other tests contained in this specification as part of the inspection comparison, and failure of such additional tests shall have the same effect as failure of those tests specified as inspection comparison.

4.6.1 Inspection failure. Failure of an inspection comparison transporter to meet any requirement specified herein during and as a result of the examination and tests specified in 4.6 shall be cause for rejection of the inspection comparison transporter and shall be cause for refusal by the Government to continue acceptance of production transporters until evidence has been provided by the contractor that corrective action has been taken to eliminate the deficiencies.

4.7 Inspection of packaging. The preservation and marking of each transporter as prepared for shipment shall be examined to assure conformance to the requirements of section 5 of this specification and the quality assurance provisions of MIL-E-10062 and MIL-V-62038.

5. PACKAGING

5.1 Preservation. Preservation shall be level A, B or C as specified (see 6.2).

5.1.1 Level A. Each complete transporter shall be preserved in accordance with the level A (mobile) requirements of MIL-V-62038, with the following exceptions and additional requirements. Materials and methods required for preservation specified herein shall conform to the applicable specifications listed in MIL-V-62038.

5.1.1.1 Preservative. Preservative oil specified in MIL-V-62038 shall conform to MIL-L-21260, grade 10 or 30, as applicable.

5.1.1.2 Engine. The transporter engine shall be preserved in accordance with the level A requirements of MIL-E-10062, type I.

5.1.1.3 Cooling system. The cooling system shall be preserved by the water and antifreeze procedures as specified in MIL-V-62038, except the antifreeze shall conform to MIL-A-46153.

5.1.1.4 Repair parts. Repair parts shall be preserved in accordance with the level A requirements of MIL-S-196. Parts not specifically covered in MIL-S-196 shall be preserved in accordance with the applicability, selection and application provisions of MIL-P-116.

5.1.1.5 Maintenance tools. Maintenance tools shall be preserved and packaged in accordance with the level A requirements of PPP-P-40.

5.1.1.6 Batteries. Batteries shall be secured in place in the battery carriers as specified in MIL-V-62038.

5.1.1.7 Windshield cover. The windshield shall be protected from breakage by covering each side with a fitted piece of 1/4 inch thick plywood or

Source: https://assist.dla.mil -- Downloaded: 202640-22T21:31Z
Check the source to verify that this is the current version before use.

hardboard allowing a minimum of 1 inch clearance between the glass and the cover. The cover shall be secured in place as specified in MIL-V-62038.

5.1.1.8 Hydraulic system (except hydraulic brake or steering systems). The hydraulic fluid supply tank shall be filled with the hydraulic fluid recommended for operation. Cylinders shall be fully charged with hydraulic fluid as specified in 3.8.4. Ports shall be plugged with threaded steel plugs. Exposed piston rod threads shall be protected with threaded steel protectors. The pistons shall be retracted as far as practicable into the cylinder and secured. When the pistons cannot be fully retracted, exposed portions of the piston rods (ramshafts) shall be coated with type P-6 or P-11 preservative and wrapped or covered with barrier material conforming to MIL-B-121, type I or II, grade A, class 2, extending the wrap approximately 2 inches on the ram cylinder, if possible. The wrap shall be secured in place with tape conforming to MIL-T-22085, type II. When the pistons can be fully retracted, any remaining uncoated surfaces of the piston rods shall be coated with type P-1 preservative, with no wrapping required. The hydraulic control valves shall be secured in the neutral position. A tag conforming to UU-T-81, type A, shall be attached in a conspicuous location indicating: "The hydraulic system is filled with the fluid specified for operation." The information shall be applied on the tag with waterproof ink.

5.1.1.9 Other components. Other components, such as the boat hook, tethering line, spanner wrench, wrecking bar, bay connecting wrench, and lanyard, shall be placed and secured as provided for on the transporter.

5.1.2 Level B. Each complete transporter shall be preserved in accordance with the level B (mobile) requirements of MIL-V-62038, with the exceptions and additional requirements specified in 5.1.1 for level A.

5.1.3 Level C. Each complete transporter, except for the engine and cooling system (see 5.1.3.1), shall be preserved in a manner to afford protection against deterioration and damage during shipment from the contractor to the initial destination.

5.1.3.1 Engine. The cooling system, fuel system, and combustion chambers and valves shall be preserved in accordance with MIL-E-10062, as specified for type I classification. The cooling system shall be preserved by the water and antifreeze procedure using antifreeze conforming to MIL-A-46153.

5.2 Packing. Each complete transporter, preserved as specified in 5.1, shall not require packing (see 6.10).

5.3 Marking (see 6.10). In addition to any special marking specified in the contract or purchase order (see 6.2), marking shall be in accordance with MIL-STD-129.

6. NOTES

(This section contains information of a general or explanatory nature which is helpful, but is not mandatory)

Source: https://assist.dla.mil -- Downloaded: 202610-22T21:31Z
Check the source to verify that this is the current version before use.

6.1 Intended use. The transporter is intended for use as an on-road or off-road overland carrier of ribbon bridge interior bays and ramp bays, the standard 27-foot bridge erection boat or ribbon bridge erection boat mounted on its boat cradle or cargo pallets. It is intended to operate with rear axles partially submerged in water while launching or retrieving the bridge bays or the boat.

6.2 Acquisition requirements. Acquisition documents should specify the following:

a. Title, number, and date of this specification.
b. Issue of DODISS to be cited in the solicitation, and if required, the specific issue of individual documents referenced (see 2.1.1 and 2.2).
c. When first article transporters or separately procured component(s) are required for inspection and approval and the number of transporters or components required (see 3.2).
d. When data for the transportation data plate is required (see 3.2.2).
e. Age of rubber products if other than as specified (see 3.3).
f. Color required when other than specified (see 3.9).
g. When air transportability data is required for the transportability report (see 3.18.3 and 6.12).
h. When Government-loaned property is required (see 3.11 and 6.5).
i. When an interior bay is not required for testing (see 4.5.2.1).
j. Level of preservation required (see 5.1).
k. Any special marking (see 5.3).

6.3 First article. When a first article inspection is required, the transporters or separately procured components may be either the first article or first-produced items. The first article should consist of one or more transporters or separately procured components. The contracting officer should include specific instructions in the acquisition documents regarding arrangements for examinations, approval of the first article test results and disposition of the first article. Invitation for bids should provide that the Government reserves the right to waive the requirement for samples for first article inspection to those bidders offering a product which has been previously acquired or tested by the Government, and that bidders offering such products, who wish to rely on such production or test, must furnish evidence with the bid that prior Government approval is presently appropriate for the pending contract. Bidders should not submit alternate bids unless specifically requested to do so in the solicitation.

6.4 Government-furnished property. The contracting officer should arrange to furnish the property specified in 3.6.

6.5 Government-loaned property. When required, the contracting officer should arrange to lend the property specified in 3.11 in the quantities required.

6.6 Data requirements. The contracting officer should include requirements for such data as technical publications, instructional materials, illustrated parts lists, and contractor's maintenance and operational manual to be furnished with each transporter.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T21:31Z
Check the source to verify that this is the current version before use.

6.7 Provisioning. The contracting officer should include provisioning requirements for repair parts and maintenance tools as necessary (including any special tools), and instructions on shipment of transporters.

6.8 Quality assurance provisions (QAP). The contracting officer should require that the contractor maintain records of all QAP inspections. A suggested paragraph is as follows:

"The contractor shall maintain complete records of all examinations and tests performed to verify the requirements of classified QAP characteristics. The records shall include, as a minimum, lot size, sample size, drawing requirement, actual measurement, number and type of deficiencies found, quantity approved, quantity rejected and corrective action taken when applicable."

6.9 Definitions.

6.9.1 Quality assurance provisions (QAP). A QAP is a contractual requirement that supplements section 4 of the specification. QAP indicates the minimum requirements which must be inspected on the product drawings to verify the design objectives of the product and assure interchangeability of repair parts.

6.10 Levels of packing. Levels of packing have not been included as only mobile shipment is appropriate. For the purpose of marking, the level of packing shall be considered level A.

6.11 Storage prior to delivery. The contracting officer should arrange for the necessary storage provisions for transporters awaiting delivery to prevent damage or deterioration.

6.12 Transportability report. When specified (see 6.2), the contracting officer should arrange for the contractor to furnish a transportability report in accordance with AR 70-47 and S.O.P. 70-38 for the transporter 95 days prior to delivery of the first article.

6.13 Subject term (key word) listing.

Bridge bay
M812 5-ton truck chassis
Ribbon bridge
Ribbon bridge transporter
Transporter
Transporter assembly

6.14 Changes from previous issue. Marginal notations are not used in this revision to identify changes with respect to the previous issue due to the extensiveness of the changes.

Source: https://assist.dla.mil -- Downloaded: 202610-22T21:31Z
Check the source to verify that this is the current version before use.

Custodian:

Army - ME

Preparing activity:

Army - ME

Project 5420-A370

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T21:31Z
Check the source to verify that this is the current version before use.

STANDARDIZATION DOCUMENT IMPROVEMENT PROPOSAL

INSTRUCTIONS

1. The preparing activity must complete blocks 1,2,3, and 8. In block 1, both the document number and revision letter should be given.
2. The submitter of this form must complete blocks 4,5,6, and 7.
3. The preparing activity must provide a reply within 30 days from receipt of this letter.

NOTE: This form may not be used to request copies of documents, nor to request waives requirements in current contracts. Comments submitted on this form do not constitute or imply authorization to waive any portion of the referenced document(s) or do amend contractual requirements.

RECOMMENDED CHANGE:	1. DOCUMENT NUMBER MIL-T-52735B(ME)	2. DOCUMENT DATE (YYMMDD) 910821

3. DOCUMENT TITLE
Transporter: M812 Chasis, for Ribbon Floating Bridge

4. NATURE OF CHANGE (identify paragraph number and include proposed if possible. Attach extra sheets as needed).

5. REASON FOR RECOMMENDATION

6. SUBMITTER

a. NAME (LAST,FIRST MIDDLE INITIAL)	b. ORGANIZATION	
c. ADDRESS (Include zip code)	d. TELEPHONE (Include Area Code) (1) Commercial (2) AUTOVON (if applicable)	7. DATE SUBMITTED (YYMMDD)

8. PREPARING ACTIVITY

a. Name Gerry Harlow	b. TELEPHONE (In lude Area Code) (1) Commercial (2) AUTOVON (703) 664-2071 354-2071
c. ADDRESS (Include zip code) Belvoir RDE Center ATTN: STRBE-TSE Fort Belvoir, VA 22060-5606	If you do not receive a reply with 45 days, contact: Defense Quality and Standardization Office 5203 Leesburg Pike, Suite 1403 Falls Church, VA 22041-3466 Telephone (703) 756-2340 AUTOVON 289-2340

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T21:31Z
Check the source to verify that this is the current version before use.