MIL-P-19380J
AMENDMENT-2
26 July 1982
SUPERSEDING
AMENDMENT 1
24 AUGUST 1981

MILITARY SPECIFICATION

PONTOONS, STEEL, SECTIONAL, P-SERIES: INCLUDING FITTINGS AND TOOLS (FOR COUPLING INTO FLOATING STRUCTURES), GENERAL SPECIFICATION FOR

This Amendment forms a part of Military Specification MIL-P-19380J, dated 28 March 1981, and is approved for use by all Departments and Agencies of the Department of Defense.

PAGE 4

2.1, DRAWINGS, NAVAL FACILITIES ENGINEERING COMMAND (NAVFAC), Insert after "6002567, Sheet 34...":

6028355 - Causeway Lifting Padeye (PH10).
6028362 - Flexor Assembly Instructions.

PAGE 5

2.1, CIVIL ENGINEERING LABORATORY (CEL), insert after 77-26-8F:

79-13-1F - Center Universal End Pontoon".

Delete:

CIVIL ENGINEER SUPPORT OFFICE (CESO)

Drawing No.	Description
SK9103	Pad, Lift/Launch, Pontoon Causeway Barge.
SK9114	Flexor Connector Assembly Instructions.

PAGE 8

3.8.2.1, line: 6 Change: "completed the same day as blast cleaning." to read: "completed within a maximum of 4 hours after blast cleaning."

Custodians:

Army - ME
Navy - YD

Preparing activity:

Navy - YD

Project No. 1945-0048

FSC 1945

Source: https://assist.dla.mil -- Downloaded: 2026-10-18T12:46Z
Check the source to verify that this is the current version before use.