MILITARY SPECIFICATION

SINK UNIT, SURGICAL SCRUB AND UTENSIL, HOSPITAL, FIELD

This specification is mandatory for use by all Departments and Agencies of the Department of Defense.

1. SCOPE

1.1 Scope. This specification covers a lightweight, self contained, unit assembly sink for performing surgical scrubbing, and washing of instruments and utensils in the field. The unit is capable of delivering either electrically heated water, or unheated water, as desired:

2. APPLICABLE DOCUMENTS

2.1 Specifications, standards, and drawings. The following documents, of the issue in effect on date of invitation for bids or request for proposals, form a part of this specification to the extent specified herein:

SPECIFICATIONS

Federal

QQ-A-200/8	Aluminum Alloy Bar, Rod Shapes, Tube and Wire, Extruded, and Structural Shapes, 6061
QQ-A-250/1	Aluminum Alloy 1100, Plate and Sheet
QQ-A-250/8	Aluminum Alloy 5052, Plate and Sheet
QQ-A-250/11	Aluminum Alloy 6061, Plate and Sheet
QQ-A-601	Aluminum Alloy Sand Castings
QQ-S-766	Steel Plate, Sheet, and Strip-Corrosion Resisting
TT-E-529	Enamel, Alkyd, Semi-gloss

Source: https://assist.dla.mil -- Downloaded: 202610-21T10:26Z
Check the source to verify that this is the current version before use.

SPECIFICATIONS (Cont'd)

Federal

TT-P-636	Primer Coating, Alkyd, Wood and Ferrous Metal
TT-P-1757	Primer Coating, Zinc Chromate, Low Moisture Sensitivity
TT-W-572	Wood-preservative, Water-repellent
WW-T-700/6	Tube, Aluminum Alloy, Drawn, Seamless, 6061
PPP-B-636	Boxes, Shipping, Fiberboard

Military

MIL-M-7298	Manual, Technical, Commercial Equipment
MIL-P-15328	Primer (Wash), Pretreatment, Blue (Formula No. 117-B For Metals)
MIL-P-19834	Plate, Identification, Metal Foil, Adhesive Backed

STANDARDS

Federal

FED-STD-151	Metal, Test Methods
FED-STD-595	Color

Military

MIL-STD-105	Sampling Procedures and Tables For Inspection by Attributes
MIL-STD-129	Marking For Shipment And Storage

Source: https://assist.dla.mil -- Downloaded: 20260-21T10:26Z
Check the source to verify that this is the current version before use.

DRAWING

Defense Personnel Support Center (DPSC)

25015 Sink Unit, Surgical Scrub and Utensil, Hospital, Field

(Copies of specifications, standards, and drawing required by suppliers in connection with specific procurement functions should be obtained from the procuring activity or as directed by the contracting officer.)

2.2 Other publications. The following documents form a part of this specification to the extent specified herein. Unless otherwise indicated, the issue in effect on date of invitation for bids or request for proposals shall apply.

UNDERWRITERS' LABORATORIES, INC. (UL)

Underwriters' Laboratories Standards

(Application for copies should be addressed to the Underwriters' Laboratories, Inc., 207 East Ohio Street, Chicago, Ill. 60611, or: 333 Pfingsten Road, Northbrook Ill. 60062, or: 1285 Walt Whitman Road, Melville, L. I., New York 11746.

NATIONAL FIRE PROTECTION ASSOCIATION

National Electrical Code

(NFPA Standards are available from the National Fire Protection Association, 60 Batterymarch Street, Boston, Massachusetts 02110.)

3. REQUIREMENTS

3.1 Fire and casualty hazards.

3.1.1 The contractor shall submit proof, prior to delivery, that the microswitch to be furnished under the contract conforms to the applicable requirements of UL. Proof shall consist of one of the following:

A. UL label or UL listing of the product, provided the contractor agrees to have Underwriters' Laboratories, Inc. forward a copy of the UL report directly to the Contracting Officer, upon the latter's request.

Source: https://assist.dla.mil -- Downloaded: 202610-21T10:26Z
Check the source to verify that this is the currentversion before use.

B. Laboratory report from a qualified independent laboratory. If an independent laboratory is used, it must be adequately equipped and competent to determine compliance with UL standards. The qualification of such laboratory shall be determined by the Government which reserves the right to require a facilities report and to conduct a facilities survey. Any laboratory report submitted shall include actual test methods, data taken, and results of tests. Detailed findings of examinations necessary to determine compliance shall also be included. The test report shall also have a section that describes the test sample in such a way that the report can be used to insure identity of production items with the test sample. This section shall be supplemented with construction information such as materials used, spacings between electrical components, types of bushings photographs, wiring diagrams, sketches, and parts list, all appropriately identified. Compliance with this paragraph does not excuse compliance with all other requirements of the contract and specifications.

3.2 Material. Except as specified herein, materials shall conform to the applicable portions of the specifications, standards, and drawing (with bill of materials) specified herein, and shall be capable of meeting the requirements specified therein. In addition, the metals shall conform to the chemical requirements of their applicable specifications when tested as specified in Section 4. When materials to be used are not specifically designated, those used shall be of the highest commercial quality, and entirely suitable for the purpose intended.

3.2.1 Government-furnished materials. The following component shall be furnished to the contractor by the Government:

NSN 6545-00-914-3480 - Chest, Medical Instrument and Supply Set, Field, No. 3, 30 inches Long by 18 inches Wide by 10 inches Deep.

3.3 Design and construction. The design and construction of the sink unit shall be in accordance with the referenced Drawing (and Bill of Materials) and as specified herein. The sink unit shall be operable on a 115 volt, 60 Hz, AC power supply, and shall be suitably insulated and grounded for safe operation under field conditions. The sink unit shall consist of a modified No. 3 medical field chest, a corrosion resisting steel sink basin, a self-priming water pump, a water heater, a water delivery and control system with fittings, a modified soap dispenser, and an aluminum stand. The water heater shall be the instantaneous type protected by an internal thermostat, and capable of delivering water at not less than 110° F at the rate of 1 quart per minute with an incoming water temperature of no higher than 70°F. The sink unit shall be capable of being easily assembled and disassembled without the use of special tools, and all components shall fit into the NSN 6545-00-914-3480 field chest for storage and transportation. The overall weight of the sink unit, including the field medical chest, shall not exceed 77 pounds. Neither the

Source: https://assist.dla.mil -- Downloaded: 202640-21T10:26Z
Check the source to verify that this is the currentversion before use.

sink unit nor any component of the sink unit shall fail when tested as specified in 4.3.

3.4 Major components. The sink unit shall include the following major components:

a. NSN 6545-00-914-3480 Chest, Medical Instrument and Supply Set, Field, No. 3. (Modified, see 3.4.1).

b. Support stand with knee lever valve.

c. Sink basin with trays.

d. Power unit containing pump and heater units.

e. Power unit extension rod assembly.

f. Hoses, modified detergent dispenser, and aspirator bulb.

3.4.1 Chest, Medical Instrument and Supply Set, Field, No. 3. The medical instrument and supply set field chest shall be modified by the contractor in accordance with the Drawing.

3.4.2 Support stand. Style, design, and construction of the support stand shall be as shown on the Drawing. Support stand shall be secured to the lid of the closed medical field chest by means of the mounting angles. Stand, when erected, shall provide for attachment of basin, water faucet, and detergent dispenser faucet, and provide for the reception of the power unit extension rods surmounted by the power control box. Knee lever, valve, and explosion-proof switch assembly, together with necessary electrical conducting cords, shall be assembled to shelf of supporting stand as shown on the Drawing. After wiring, the "Y" connector, P/N 135 on Sheet 7 of the Drawing, shall be completely filled with a magnesite base cement, Series SC sealing compound, manufactured by the Killark Electrical Manufacturing Company.

3.4.3 Sink basin. Sink basin and trays shall conform to the Drawing and shall be fabricated in accordance with the best accepted practices to produce an item suitable for the purpose intended. The basin shall be formed seamlessly from a single sheet of 0.050 inch thick corrosion-resisting steel conforming to QQ-S-766, class 302 or class 304. The metal sheet shall not be reduced below 0.040 inch thick at any point in the finished basin. The walls of the slots cut into the roll of the basin shall be free of pockets for potential bacterial growth.

Source: https://assist.dla.mil -- Downloaded: 20261O-21T10:26Z
Check the source to verify that this is the current version before use.

3.4.4 Power unit. The power unit shall be fabricated in accordance with the Drawing. Identification plates and wiring diagram shall be located as shown on the Drawing. All electrical components, mountings, electrical connections, and gravity-feed control valve, shall be properly secured and the entire unit shall be electrically and mechanically grounded. All electrical wiring shall be properly dressed and positioned within the unit, and meet the requirements of the National Electrical Code.

3.4.4.1 Power unit mounting brackets. The brackets shall be fabricated as shown on the Drawing. Material shall be Tenzaloy, temper T5, in accordance with Federal Specification QQ-A-601.

3.4.4.2 Spare fuse holder. Shall be fabricated of black, medium-density, polyurethane foam. The holder shall be securely bonded to the wall of the power unit as specified in the Drawing and Bill of Material.

3.4.4.3 Identification plates and wiring diagram. The identification plates (except Sink Unit Identification Plate, see 3.4.6.1, and Warning Plate, see 3.4.6.2) and Wiring Diagram shall be Type II in accordance with Military Specification MIL-P-19834, except that the dimensions of plates and lettering shall be as shown on the Drawing. These plates and wiring diagram shall have a black background with white legends.

3.4.5 Power unit extension rod assembly. Power unit extension rod assembly shall consist of 2 round, drawn aluminum tubes, alloy No. 6061-T6, WW-T-700/6, 7/8 inch outside diameter by 0.065 inch wall thickness by 19 3/16 inches long. The tubes shall be hard-coat anodized (black), except for the exterior surface of each end for a length of 1 inch. The 1-inch untreated sections may be accomplished by masking prior to, or grinding subsequent to, anodizing.

3.4.6 Identification plate, sink unit, and Warning plate.

3.4.6.1 Identification plate, sink unit. The sink unit identification plate (P/N 40) shall be fabricated in accordance with the Drawing. Characters shall be etched, engraved, or stamped to a minimum depth of .003 inch. All characters shall be filled with a hard paint, enamel, or lacquer. Face of plate shall be sprayed with a fungus and moisture-resistant varnish. Identification plate shall be secured at each of four corners by rivets, screws, bolts, or welds.

3.4.6.2 Warning plate. Warning plate, affixed to male service plug, as shown on the Drawing, shall be fabricated from Hermes Plastics, "Gravoply" No. 13, equal, (red surface, white lettering).

Source: https://assist.dla.mil -- Downloaded: 2026-10-21T10:26Z
Check the source to verify that this is the current version before use.

3.4.7 Surgical detergent dispenser. The surgical detergent dispenser shall be in accordance with the bill of material, except as modified by the Drawing.

3.5 Spare parts. Each unit shall be supplied with the following spare parts:

a. Fuse - 5 inserted in fuse holder, spare.

b. Hose washer - 6 washers mounted as shown on the Drawing.

3.6 Welding. Welding shall be durable, sound in every detail and in accordance with latest practices recommended by the American Welding Society. All welds shall be produced by qualified welding operators with satisfactory welding equipment using satisfactory filler metal or electrode where applicable to provide the best possible weld. Surfaces to be welded shall be free from grease, oil, oxides or any other foreign matter; any cleaning method which will remove these substances and leave the surface clean is satisfactory. All weld joints shall blend into the adjacent metal in gradual, smooth curves. Welds shall not be oxidized. All welds shall be continuous with no visible voids, pin holes, or cracks, and have more strength than required for purpose intended.

3.7 Finish.

3.7.1 Sink basin. The entire inside and outside surfaces shall be ground to a No. 4 finish after all surface imperfections have been removed by previous grinding. This last grinding shall produce a uniform, finished surface with all imperfections and marks of previous grinds removed. The thickness of the sheet forming the basin shall not be reduced below the thickness specified in 3.4.3 by grinding to remove surface imperfections. As an alternate, the interior of the basin may be finished by electropolishing. The electropolishing shall result in a uniform, bright, and shiny surface which may be easily cleaned. As a final operation, the basin shall be thoroughly cleaned to remove foreign particles such as dirt, grease, graphite, and metal.

3.7.2 Field chest. Interior of field chest, including cover, shall be sprayed with Pettit Paint Company's undercoat No. 4169, and finished with Pettit Paint Company's white gloss polypoxy No. 4170 spray.

3.7.3 Metal parts. Except for the exterior of the Government-furnished field chest (see 3.2.1), all exposed metal parts, including interior of power unit box and cover, shall be treated by prepriming with a wash-primer coat in accordance with MIL-P-15328, and then treated with a primer spray coat in accordance with Federal Specification TT-P-1757, color Y. Finish coat shall consist of two spray coats of baking-type synthetic, semi-

Source: https://assist.dla.mil -- Downloaded: 2026-10-21T10:26Z
Check the source to verify that this is the current version before use.

gloss, enamel in accordance with Federal Specification TT-E-529, class B. Color shall be 24241 conforming to FED-STD 595. The exterior surfaces of Government-furnished field chests shall be lightly sanded, scratches primed in accordance with TT-P-1757, and finished as specified above. The following parts shall not be painted:

a. Power unit extension rods.
b. Interior of chest and cover (except as specified in 3.7.2).
c. Turn-type, cadmium-plated, fasteners.
d. Hose lines.
e. Hose connections.
f. Heater, pump, and electrical components.
g. Sink basin, including feet and brackets.
h. Straps and fasteners.

3.7.4 Wood parts. Wood parts shall be dressed to the correct dimensions and then immersed in pentachlorophenol solution, in accordance with Federal Specification TT-W-572, composition A. Immersion shall be for a period of not less than 4 hours. Treated wood shall be thoroughly air-dried, or kiln-dried, prior to painting. Wood parts shall then be given a prime coat in accordance with Federal Specification TT-P-636, followed by 2 top coats of semi-gloss enamel in accordance with Federal Specification TT-E-529. Color shall be 24241 conforming to FED-STD-595.

3.8 Identification marking. One side of the exterior surface of the field chest (see 3.2.1) shall be permanently and legibly marked with black enamel paint. Markings shall be in accordance with the Drawing.

3.9 Service Data. The contractor shall furnish, with each unit, two copies each of a technical manual which contains complete instructions for installation, operation, and maintenance and lists of component parts. The manual shall comply with the requirements of MIL-M-7298 MANUAL, TECHNICAL, Commercial Equipment. The cover of the manual shall also include the information listed below. As soon as practicable after award of the contract or purchase order, the contractor shall furnish to the Contracting Officer, via the cognizant Government inspector, two preliminary copies of his proposed technical manual, for review and comment by the Directorate of Medical Materiel, Defense Personnel Support Center. The preliminary manuals shall be submitted sufficiently early to permit adequate review by the Directorate of Medical Materiel, Defense Personnel Support Center (based on a maximum period of 30 days for such review) and to allow incorporation by the contractor of any required revisions and corrections in the final manual without delaying delivery under the contract or purchase order. In addition, the Contractor shall furnish 15 copies of the approved technical manual to the Contracting Officer for distribution. Should the supplier have furnished acceptable manuals for the identical item within two years preceding the date of contract and proposes to furnish manuals identical with those previously accepted, then the requirements for review of drafts and submission of 15 additional copies may be waived upon

Source: https://assist.dla.mil -- Downloaded: 2026-10-21T10:26Z
Check the source to verify that this is the current version before use.

request to the contracting officer. Waiver of submission of 15 additional copies shall be at the option of the Government.

Information to be included on the manual cover:

NSN 6545-00-935-4056

SINK UNIT, SURGICAL SCRUB AND UTENSIL, HOSPITAL, FIELD, Hot and Cold Water Supply, 1 Sink, Electrically Heated, 115 volt, 60 Hz, AC

Contract No.
Name and address of contractor
Contractor's Model No.

3.10 Tests. The sink unit shall meet test requirements when tested as specified in 4.3.

3.11 Workmanship. Workmanship shall be first class throughout. Sink units shall be free from defects which detract from their appearance or may impair their serviceability, and shall be suitable in all respects for the purpose intended.

4. QUALITY ASSURANCE PROVISIONS

4.1 Responsibility for inspection. Unless otherwise specified in the contract or purchase order, the supplier is responsible for the performance of all inspection requirements as specified herein. Except as otherwise specified in the contract or order, the supplier may use his own or any other facilities suitable for the performance of the inspection requirements specified herein, unless disapproved by the Government. The Government reserves the right to perform any of the inspections set forth in the specification where such inspections are deemed necessary to assure supplies and services conform to prescribed requirements.

4.1.1 Records. Records of examinations and tests performed by or for the contractor shall be maintained by the contractor and made available to the Government, upon the Government's request, at any time, or from time to time, during the performance of the contract and for a period of 3 years after delivery of the supplies to which such records relate.

4.1.2 Inspection. Inspection, as used in this specification, is defined as both examination (such as visual or auditory investigation without the use of special laboratory appliances or procedures) and testing (determination by technical means of physical and chemical properties) of the item.

Source: https://assist.dla.mil -- Downloaded: 202610-21T10:26Z
Check the source to verify that this is the current version before use.

4.1.3 Certificates of quality. Certificates of quality, supplied by the manufacturers of the straps and aluminum casting, sheet, strip, and angles, and corrosion resisting steel sheet, may be furnished in lieu of actual performance of such testing by the contractor, provided lot identity has been maintained and can be demonstrated to the Government. The certificate shall include the name of the contractor, the contract number, the name of the manufacturer or supplier, the NSN, the item identification, the name of the component/material, the lot number, the lot size, the sample size, the date of testing, the test method, individual test results, and the specification requirements.

4.2 Quality conformance inspection. The examination and tests required to assure conformance of those items or lots of items to be offered for acceptance are classified as specified in tables I and II and IV (see 4.2.1 and 4.2.2) and 4.2.3 (see Table IV).

4.2.1 Sampling for examination. Sampling for examination shall be conducted in accordance with MIL-STD-105. The inspection levels and acceptable quality levels shall be as indicated in table I. Unit of product for examination purposes shall be one sink unit.

Table I. Inspection and Acceptable Quality Levels

Type Defect	Inspection level	AQL (percent defective)
Major A	II	1.0
Major B	S-1	2.5
Minor	II	2.5

4.2.2 Examination.

4.2.2.1 Sink unit. The sink unit shall be examined for defects including, but not limited to, those listed in table II.

Table II. Classification of Defects

Categories	Defects
Critical	None defined.
Major A	
101	Component missing.
102	Any component cracked, broken, dented or otherwise damaged.
103	Wiring not as specified.

Source: https://assist.dla.mil -- Downloaded: 2026-10-21T10:26Z
Check the source to verify that this is the current version before use.

Table II. Classification of Defects (Cont'd)

Categories	Defects
Major A	
104	Interior finish of sink basin not smooth, and free of scratches and grinding marks.
105	Any weld, not sound, or not free of spatter and porosity.
106	Any pocket in a slot in the basin.
107	Any rivet head in sink basin not flush with surface.
108	Identification marking missing.
109	Any identification plate not in accordance with drawing.
110	Any identification plate not located as per drawing.
111	Any exposed edge or corner not free of a burr, and sharp edge.
112	Any welds not finished smooth.
Major B	
151	Any latch that does not operate smoothly.
152	Any securing strap not capable of retaining component.
153	Any bypass-Return hose shorter than specified.
Minor	
201	Exterior surface of sink basin not free of scratches, grinding and trimming marks.
202	Any hose other than Bypass-Return not length specified.
203	Any screw or bolt not drawn up tight.
204	Paint finish not uniform.
205	Paint finish not free of runs and sags.
206	Paint finish not free of scratches.
207	Paint blisters evident.
208	Sink unit not free of dirt, grease, metallic particles, and other foreign substances.

Source: https://assist.dla.mil -- Downloaded: 2026-10-21T10:26Z
Check the source to verify that this is the current version before use.

4.2.3 Packaging inspection. The inspection of the preservation-packaging and interior package marking shall be in accordance with the group A and B quality conformance inspection requirements of MIL-P-116. The inspection of the packing and marking for shipment and storage shall be in accordance with the quality assurance provisions of the applicable container specification and the marking requirements of MIL-STD-129.

4.2.4 Sampling for tests. Sampling for tests shall be conducted in accordance with MIL-STD-105 and table IV, except that the acceptance number shall be zero for all sample sizes. Unit of product for test purposes shall be one fully assembled sink unit.

Table IV. Sampling and Quality Conformance Criteria for Testing

Characteristic	Requirement	Test Procedure	Inspection level
Dielectric strength	3.10	4.3.2	100 percent
Humidity resistance	3.10	4.3.3	1 First Article
Reliability	3.10	4.3.4	1 First Article
Performance			
Pump operation	3.10	4.3.5.1	100 percent
Heated water-pump	3.10	4.3.5.2	S-1*
Heated water-gravity	3.10	4.3.5.3	S-1*

* Minimum sample size 3 sink units.

4.2.4.1 Sampling for chemical testing of metals. A sufficient amount of each lot of each metal used in the construction of the structural components of the sink unit shall be selected for chemical analysis as specified in 4.3.1.

4.2.4.2 Where feasible, the same sample unit may be used for the determination of two or more test characteristics.

4.3 Tests. Tests shall be conducted to determine compliance with specification requirements.

Source: https://assist.dla.mil -- Downloaded: 2026-10-21T10:26Z
Check the source to verify that this is the current version before use.

4.3.1 Chemical analysis of metals. The samples selected in accordance with 4.2.3.1 shall be analyzed in conformance with methods 111 or 112 of FED-STD-151. In case of dispute, method 111 shall be used for referee analysis.

4.3.2 Dielectric strength test. With the pump and heater switches in the "ON" position, run the assembled unit for 5 minutes, disconnect from power supply, and while in the heated condition gradually apply a 900 volt alternating current potential between the current-carrying and the non-current-carrying parts and maintain at that value for a period of 1 minute. There shall be no evidence of dielectric breakdown or arc-over.

4.3.3 Humidity test. Place the power unit in a chamber at which the temperature and humidity are maintained at constant values of 95°F. and 85% respectively, for a period of 24 hours. Repeat the dielectric strength test described in 4.3.2 above. There shall be no dielectric breakdown or arc-over.

4.3.4 Reliability test. This test shall be performed as follows: Assembled unit, with heater and pump switches in the "On" position shall be operated cyclically 1000 times. In this test the heated waste water shall not be recycled but voided in a convenient manner. As necessary, test may be interrupted to refill reservoir with water at ambient temperature. One cycle shall consist of moving the knee switch from the "Off" position to "On" and back to "Off". During the test, when checked at equal increments of not more than 100 cycles, unit shall not exhibit any leakage, malfunctions, mechanical deficiencies, etc. It is to be noted that this test applies only to pump operation of the unit. At the option of the testing activity, the above test may be performed using mechanical means to simulate the actual use of the unit by personnel.

4.3.5 Performance tests. Performance tests shall be performed on completely assembled units.

4.3.5.1 Pump operation. With all switches in "Off" position, the service cord shall be connected to a properly grounded outlet. The pump switch shall be placed in "On" position and the knee lever switch then activated. Pump shall then deliver continuous flow of water within 1 minute after activation by knee lever switch.

Source: https://assist.dla.mil -- Downloaded: 2026-10-21T10:26Z
Check the source to verify that this is the current version before use.

4.3.5.2 Heated water - pump operation. The water reservoir shall contain water at 70° + 0, - 2°F. for this test. Place both the pump and heater switches in the "ON" position. The sink unit shall deliver water from the faucet to meet the requirements set forth in table V.

Table V. Heated Water - Pump Operation

Knee Lever Position Approx.	Flow Rate (Qt./Min.)	Temperature (°F.)
Left (Activated)	1.8 ± 0.1	95° + 5°, - 2°
Middle	1.2 ± 0.1	105° ± 3°
Right	0.8 ± 0.1	120° + 2°, - 5°

4.3.5.3 Heated water - gravity-feed operation. With the unit properly connected for gravity feed operation, and heater and pump switches "Off", knee lever shall be placed in the "half swing" position, and the suction end of the aspirator bulb shall be connected by tubing to the faucet opening. The lines shall then be evacuated with the aspirator to commence flow from an elevated container, approximately 3 feet above the faucet, containing water at a temperature of 70° + 0 - 2°F. Upon commencement of flow, knee lever valve shall be fully closed (extreme left position) The heater shall then be turned on and knee-lever valve opened to permit flow of water and activation of heater. The sink unit shall deliver water from the faucet to meet the requirements set forth in table VI.

Table VI. Heated Water - Gravity-Feed Operation

Flow Rate (Qt./Min.)	Temperature (°F.)
1.5 ± 0.1	98° ± 3°
2.2 ± 0.1	89° ± 3°

Source: https://assist.dla.mil -- Downloaded: 2026-10-21T10:26Z
Check the source to verify that this is the current version before use.

5. PACKAGING.

5.1 Preservation-packaging. Preservation packaging shall be level A or C as specified (see 6.1).

5.1.1 Level A.

5.1.1.1 Cleaning. Sinks shall be cleaned in accordance with MIL-P-116, method C-1.

5.1.1.2 Preservative application. Preservatives shall not be used.

5.1.1.3 Unit packaging. Each sink shall be disassembled, positioned and secured within a No. 3 Field Chest in such a manner so as to prevent shifting of or damage to the components. The lid shall be placed in position and latched.

5.1.2 Level C. Each sink shall be packaged as specified in 5.1.1.3.

5.2 Packing. Packing shall be level A or C as specified (see 6.1).

5.2.1 Level A. Each chest shall be packed in an exterior container designed for a type 1 load and constructed in accordance with PPP-B-636, class weather-resistant. Closure and strapping shall be as specified in the appendix of PPP-B-636.

5.2.2 Level C. The subject commodity shall be packed in substantial commercial containers of the type, size, and kind commonly used for the purpose, so constructed as to insure acceptance and safe delivery by common or other carriers, at the lowest rate, to point of delivery called for in the contract or purchase order.

5.3 Marking. Marking shall be as specified in MIL-STD-129.

6. NOTES

6.1 Ordering data. Procurement documents should specify the following:

(a) Title, number, and date of this specification.
(b) National Stock Number and Item Identification.
(c) Selection of applicable levels of packaging and packing (see 5.1 and 5.2).

Source: https://assist.dla.mil -- Downloaded: 2026-10-21T10:26Z
Check the source to verify that this is the current version before use.

6.2 Availability of color chips. Individual chips of the colors specified in 3.7.3 and 3.7.4 are available from:

Commissioner
Federal Supply Service
General Services Administration
Standardization Division, Paints Branch
Washington, DC 20406

6.3 The sink unit covered by this specification is listed in the Federal Supply Catalog as follows:

National Stock Number	Item Identification
6545-00-935-4056	Sink Unit, Surgical Scrub and Utensil Hospital, Field, Hot and Cold Water Supply, 1 Sink, Electrically Heated, 115 volt, 60 Hz, AC.

Custodians:
Army - MD
Navy - MS
Air Force - 03

Preparing Activity:
Defense Supply Agency - DM

Project Number - 6545-0028

Source: https://assist.dla.mil -- Downloaded: 2026-10-21T10:26Z
Check the source to verify that this is the current version before use.

STANDARDIZATION DOCUMENT IMPROVEMENT PROPOSAL

OMB Approval
No. 22-R255

INSTRUCTIONS: The purpose of this form is to solicit beneficial comments which will help achieve procurement of suitable products at reasonable cost and minimum delay, or will otherwise enhance use of the document. DoD contractors, government activities, or manufacturers/ vendors who are prospective suppliers of the product are invited to submit comments to the government. Fold on lines on reverse side, staple in corner, and send to preparing activity. Comments submitted on this form do not constitute or imply authorization to waive any portion of the referenced document(s) or to amend contractual requirements. Attach any pertinent data which may be of use in improving this document. If there are additional papers, attach to form and place both in an envelope addressed to preparing activity.

DOCUMENT IDENTIFIER AND TITLE

MIL-S-37321(DSA-DM) SINK UNIT, SURGICAL SCRUB AND UTENSIL, HOSPITAL, FIELD

NAME OF ORGANIZATION AND ADDRESS

CONTRACT NUMBER

MATERIAL PROCURED UNDER A

☐ DIRECT GOVERNMENT CONTRACT ☐ SUBCONTRACT

1. HAS ANY PART OF THE DOCUMENT CREATED PROBLEMS OR REQUIRED INTERPRETATION IN PROCUREMENT USE?

A. GIVE PARAGRAPH NUMBER AND WORDING.

B. RECOMMENDATIONS FOR CORRECTING THE DEFICIENCIES

2. COMMENTS ON ANY DOCUMENT REQUIREMENT CONSIDERED TOO RIGID

3. IS THE DOCUMENT RESTRICTIVE?

☐ YES ☐ NO *(If "Yes", in what way?)*

4. REMARKS

SUBMITTED BY *(Printed or typed name and address - Optional)*

TELEPHONE NO.

DATE

DD FORM 1 JAN 72 1426

REPLACES EDITION OF 1 JAN 66 WHICH MAY BE USED

Source: https://assist.dla.mil -- Downloaded: 2026-10-21T10:26Z
Check the source to verify that this is the current version before use.

FOLD

DEFENSE PERSONNEL SUPPORT CENTER
2800 South 20th Street
Philadelphia, PA 19101

POSTAGE AND FEES PAID
DEFENSE SUPPLY AGENCY
DoD - 304

OFFICIAL BUSINESS
PENALTY FOR PRIVATE USE $300

HEADQUARTERS, DEFENSE PERSONNEL SUPPORT CENTER
ATTN: DIRECTORATE OF MEDICAL MATERIEL, CODE ATT
2800 SOUTH 20TH STREET
PHILADELPHIA, PA 19101

FOLD

Source: https://assist.dla.mil -- Downloaded: 2026-10-21T10:26Z
Check the source to verify that this is the current version before use.