MILITARY SPECIFICATION

Test Set, Guided Missile A/E 24T-82

1. SCOPE

1.1 Scope. This specification covers a missile test set designated as Test Set, Guided Missile A/E 24T-82 hereinafter referred to as "Test Set" (for operational use reference Section 6 of this specification).

2. APPLICABLE DOCUMENTS.

2.1 The following documents, of the issue in effect on date of invitation for bids or request for proposal, form a part of the specification to the extent specified herein:

SPECIFICATIONS

Federal

PPP-B-591	Boxes, Fiberboard, Wood-Cleated
PPP-B-601	Boxes, Wood, Cleated-Plywood
PPP-B-621	Boxes, Wood, Nailed and Lock-Corner
PPP-B-636	Box, Fiberboard
PPP-B-640	Boxes, Fiberboard, Corrugated, Triple Wall

Military

MIL-P-116	Preservation, Methods of
MIL-M-4552	Multimeter AN/PSM-6B
MIL-L-10547	Liners, Case and Sheet, Overwrap; Water-Vaporproof or Water proof Flexible
MIL-T-21200	Test Equipment for Use with Electronic and Fire Control Systems, General Specification for
MIL-I-45208	Inspection System Requirements

STANDARDS

Military

MIL-STD-105	Sampling Procedures and Tables for Inspection by Attributes
MIL-STD-129	Marking for Shipment and Storage
MIL-STD-130	Identification Marking of US Military Property
MIL-STD-480	Configuration Control - Engineering Changes, Deviations and Waivers

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T09:54Z
Check the source to verify that this is the current version before use.

Drawings

AF Drawing 69F32621
AF Drawing 69B32697

(Copies of specifications, standards, drawings, and publications required by suppliers in connection with specific procurement functions should be obtained from the Procuring Activity or as directed by the Contracting Officer).

3. REQUIREMENTS

3.1 Qualification. First Article tests of three Test Sets shall be made in accordance with the provisions contained herein.

3.2 General Specification. The requirements of MIL-T-21200 for Class 2 equipment are applicable as requirements of this specification with the exceptions or additions called out herein.

3.2.1 Nameplate Identification. Test Set identification conforming to MIL-STD-130 shall be provided on the chassis. Approval of the drawing for the nameplate shall be by the Engineering Division of the Procuring Activity.

3.3 Service Conditions. The equipment shall operate with no degradation of performance under any combination of service conditions specified in MIL-STD-810, Table 1, Column E. The design criteria shall be those applicable to Ground Equipment and worldwide operation.

3.4 Design.

3.4.1 Configuration. The dimensions of the Test Set and cables shall be in accordance with AF Drawing No. 69F32621.

3.4.2 Design Reference. AF Drawing No. 69F32621 shall be used as a reference and guide for design of the Test Set.

3.4.3 Components. The Test Set shall comprise one complete unit which shall include the chassis with control panel, cable assembly and attaching provisions for an AN/PSM-6 Meter. Selection of components and design criteria shall be in accordance with the provisions of MIL-T-21200.

3.4.4 Attaching Provisions. Two catches shall be provided on the chassis bracket for physically attaching an AN/PSM-6 Meter. Two leads with connectors shall be provided for electrical connection to the AN/PSM-6 Meter.

3.4.5 Electrical Requirements. The Test Set shall be designated for use with voltages up to 115 Volts Alternating Current (VAC).

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T09:54Z
Check the source to verify that this is the current version before use.

3.4.6 Control Panel. The Control Panel shall be marked as shown on AF Drawing No. 69B32697 and in accordance with MIL-T-21200.

3.3.7 Sealing Gaskets. A gasket shall be provided between the chassis and the control panel and between the chassis and the bottom panel. The gasket shall be fungus resistant.

3.5 Engineering Changes. Engineering changes to the requirements of this specification or to design and manufacturing drawings and contractor's control specifications after approval of first article Test Sets shall conform to the requirements of MIL-STD-480.

3.6 Government Loaned Property. When specified in the contract, the Government will loan the following to the contractor upon his request.

ITEM NO.	STOCK NO.	PART NO.	ITEM DESCRIPTION	QUANTITY
1	6625-643-1686 or equal	MIL-M-4552 Type AN/PSM-6B	Multimeter with Accessories	1

4. QUALITY ASSURANCE PROVISIONS

4.1 Responsibility for Inspection. Unless otherwise specified in the contract or Purchase Order, the supplier is responsible for the performance of all inspection and test requirements as specified herein. Except as otherwise specified, the supplier may utilize his own facilities or any commercial laboratory acceptable to the Government. The Government reserves the right to perform any of the inspections or tests set forth in this specification where such inspections or tests are deemed necessary to assure supplies and services conform to prescribed requirements.

4.1.1 Test Procedures. Detailed Test Procedures shall be prepared by the contractor for each classification of tests and inspections.

4.2 Classification of Tests. The inspection and testing of the Test Sets shall be in accordance with MIL-I-4508 and be classified as follows:

a. First Article Tests (4.3)

b. Quality Conformance Tests (4.4)

4.3 First Article Testing.

4.3.1 First Article Equipments. First Article Tests shall be accomplished on three Test Sets representative of the Production Test Sets. The Test Sets shall be identified with Nameplate and complete identification data in the same manner as production Test Sets, including serial number identification.

4.3.2 First Article Tests. The First Article Tests are intended to provide assurance that the design and operation of the Test Set will meet the

Source: https://assist.dla.mil -- Downloaded: 202610-23T09:54Z
Check the source to verify that this is the current version before use.

requirements. Successful completion of the test program does not relieve the contractor of the responsibility to furnish equipment that meets the performance requirements of this specification. An operational test shall be performed before and after each Environmental Test. First Article Tests shall consist of the Quality Conformance Tests of 4.4 and the following Environmental Tests of MIL-STD-810, Table I Column E.

4.3.2.1 Low Temperature. Method 502, Procedure I. The lower storage limit is -62 C for 72 hours and the lower operational limit is -40 C.

4.3.2.2 High Temperature. Method 501, Procedure 1. The higher storage limit and operational limit are both 71 C.

4.3.2.3 Altitude. Method 500, Procedure I.

4.3.2.4 Dust. Method 510, Procedure I. Test specimen will not be operated during test. Time interval between step 2 and step 3 will be 0 to 16 hours at the contractor's option.

4.3.2.5 Shock. Method 516, Procedure I. Apply shock per figure 516.1.1, peak value 20 g's, duration 11 milliseconds. Test item will not be operated during test.

4.3.2.6 Vibration. Method 514.1, Procedure XI.

4.3.2.7 Rain. Method 506, Procedure I. Equipment will not be operated during test.

4.3.2.8 Humidity. Method 507, Procedure I.

4.3.2.9 Fungus. Method 508, Procedure I. Test item will not be operated after test.

4.3.2.10 Salt Fog. Method 509, Procedure I.

4.4 Quality Conformance Tests. Quality Conformance Tests are those tests performed during production to verify the integrity of equipment, quality of workmanship and operational performance for compliance with the requirements of this specification. The contractor shall furnish all equipment except that which is authorized for bailment herein. All inspection and testing shall be under the supervision of the Government Representative. Quality Conformance Tests shall consist of the following:

a. Examination of Product

b. Continuity Test

c. Insulation Test

d. Environmental Sampling Test

Source: https://assist.dla.mil -- Downloaded: 202610-23T09:54Z
Check the source to verify that this is the current version before use.

4.4.1 Examination of Product. The Test Set shall be examined externally to determine conformance to this specification with respect to materials, workmanship and general requirements.

4.4.2 Continuity Test. A Continuity Test shall be conducted on each Test Set to demonstrate compliance with the continuity requirements of AF Drawing No. 69F32621.

4.4.3 Insulation Test. With the Test Set disconnected from the AN/PSM-6, a megger with high potential of 500 volts minimum shall be applied as follows:

a. Between each connector pin and the connector shall.

b. Between each connector pin and every other connector pin.

c* Between each connector pin or shell and the Test Set case.

d. The insulation resistance in each instance shall be 100 megohms minimum.

4.4.4 Environmental Sampling Test. During the course of production, Test Sets shall be subject to the Vibration Test, Method 514.1, Procedure XI of HIL-STD-810.

4.4.4.1 Sampling Procedure. Sampling Procedures provided by MIL-STD-105 for Special Inspection Level S-3, Single Sampling, Normal Inspection, Acceptable Quality Level (AQL) Value of 4.0 for Major Defects. An Insulation Test (4.4.3) shall be performed before the start of and after completion of each of the Environmental Sampling Tests (4.4.4).

4.4.4.2 Inspection Lot. An Inspection Lot shall consist of a maximum of one month’s production but not less that 25 Test Sets.

4.4.4.3 Unit of Product and Sample Selection. The unit of product for sampling purposes shall be one complete Test Set. Samples shall be selected in a random manner from the production lot. The lot identity shall be maintained during performance of this test, and no units from the lot shall be supplied prior to determination of acceptability of the sample.

4.4.4.4 Defect Classification. All defects resulting from the specified functional or mechanical requirements as a result of the vibration test shall be classified as major. Each unit which fails to meet one or more of the specified tests shall be deemed to be one major defect.

5. PREPARATION FOR DELIVERY

5.1 Packaging.

5.1.1 Level A. Each Test Set shall be packaged in accordance with Method IIb

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T09:54Z
Check the source to verify that this is the current version before use.

of MIL-P-116.

5.1.2 Level C. Test Sets shall be packaged in accordance with the manufacturer's commercial practice.

5.2 Packing.

5.2.1 Level A. Test Sets packaged in accordance with 5.1.1 shall be packed in containers conforming to PPP-B-591 Fiberboard, Wood-Cleated, over–seas type, PPP-B-601, Wood, Cleated-Plywood, overseas type, PPP-B-621 Wood Nailed and Lock-corner, Class 2, PPP-B-636 Fiberboard, Weather Resistant or PPP-B-40 Fiberboard, Corrugated Triple-wall Class 2. Boxes shall be sealed, closed and strapped for overseas shipment in accordance with the applicable box specification and appendix thereto. Wood or cleated boxes shall be lined with a sealed waterproof case liner conforming to MIL-L-10547 except that when the exterior container of Method IIb packages has strength and water resistance as specified in PPP-B-636, a case liner will not be required. The gross weight of wood, wood-cleated or triple-wall corrugated boxes shall not exceed 200 pounds; fiberboard boxes shall not exceed the weight limitation of the applicable box specification.

5.2.2 Level B. Test Sets packaged in accordance with 5.1.1 shall be packed in containers conforming to PPP-B-591 Fiberboard, Wood-Cleated, Domestic Type, PPP-B-601, Wood-Cleated-Plywood, Domestic Type, PPP-B-621, Wood, Nailed and Lock–corner, Class 1, PPP-B-636 Fiberboard Domestic or PPP-B-640 Fiberboard Corrugated triple-wall, Class 1. Boxes shall be sealed and closed in accordance with the requirements of the applicable box specification. The gross weight of wood, wood-cleated or triple-wall corrugated boxes shall not exceed 250 pounds; fiberboard boxes shall not exceed the weight limitations of the applicable specification.

5.2.3 Level C. Test Sets shall be packed in containers in a manner to insure acceptance and sale delivery at destination. Containers shall comply with the consolidated freight classification rules or other regulations as applicable to the mode of transportation.

5.3 Marking. In addition to any special marking required by the contract or order, marking for shipment shall be in accordance with MIL-STD-129.

5.4 Cure Dates. The contractor shall comply with the requirements of MIL-STD-480 as applicable.

6. NOTES

6.1 Intended Use. This Test Set is intended as a means of insuring that no voltage is present on any pin on Connector 1316, ATM-7D/E Guidance and Control Section prior to mating it with the warhead.

6.2 Ordering Data. Procurement documents should specify the following:

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T09:54Z
Check the source to verify that this is the current version before use.

6.2.1 Procurement Requirements.

a. Title, number, and date of this specification.

b. Levels of packaging and packing required. (See 5.1 and 5.2).

c. Serial numbers applicable to contract quantities of Test Sets.

d. Compliance with MIL-I-45208, Inspection System Requirements.

6.2.2 Contract Data Requirements. Data requirements shall be specified on a DD Form 1423 incorporated into the contract.

6.2.3 First Article. When first article is required, the contract or other procurement document should reflect the policy, instructions, and clauses set forth in the Armed Services Procurement Regulation, Section I, Part 19, pages 198.55 through 198.60, dated 1 January 1969.

6.2.4 Government Loaned Property. Procurement documents should specify that the Government shall loan the supplier an AN/PSM-6 Multimeter (FSN 6625-643-1686 or equal, MIL-M-4552) for the purpose of performing tests specified herein, upon written request by the contractor to the procuring activity.

CUSTODIAN:

Air Force - 84

PREPARING ACTIVITY

Air Force - 84

PROJECT NUMBER:

4935 - F005

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T09:54Z
Check the source to verify that this is the current version before use.