MILITARY SPECIFICATION

CONTROL, POWER SUPPLY: C-7674/VCC, AND CONTROL, TERMINAL SET: C-7827/VCC

1. SCOPE

1.1 This specification covers requirements for one type control, power supply and control, terminal set.

2. APPLICABLE DOCUMENTS

2.1 The following documents of the issue in effect on date of invitation for bids or request for proposal, form a part of the specification to the extent specified herein.

SPECIFICATIONS

MILITARY

MIL-T-152	-	Treatment, Moisture and Fungus-Resistant of Communications, Electronic and Associated Electrical Equipment.
MIL-T-704	-	Treatment and Painting of Materiel.
MIL-P-15024	-	Plates, Identification-Information and Marking for Identification of Electrical, Electronic and Mechanical Equipment.
MIL-P-16400	-	Electronic Equipment, Naval Ship and Shore, General Specification.
MIL-E-17555	-	Electronic and Electrical Equipment and Associated Repair Parts, Preparation for Delivery of.
MIL-E-21981	-	Electronics Type Designations, Identification Plates and Markings, Requirements for.
MIL-R-22732	-	Reliability Requirements for Shipboard and Ground Electronic Equipment.

Source: https://assist.dla.mil -- Downloaded: 202610-20T20:57Z
Check the source to verify that this is the currentversion before use.

STANDARDS

MILITARY

MIL-STD-129	-	Marking for Shipment and Storage.
MIL-STD-188	-	Military Communication System Technical Standards.
MIL-STD-810	-	Environmental Test Methods
MIL-STD-826	-	Electromagnetic Interference Test Requirements and Test Methods.

(Copies of specifications and standards required by suppliers in connection with specific procurement functions should be obtained from the procuring activity or as directed by the contracting officer.)

3. REQUIREMENTS

3.1 General. The Control, Power Supply, C-7674/VCC, and Control, Terminal Set, C-7827/VCC, to be furnished under contract or order shall conform to all requirements specified herein. Definitions for the abbreviations not defined may be obtained from MIL-STD-188.

3.1.1 Control, Power Supply C-7674/VCC. The control unit shall provide the various power supply options for vehicle mounted equipment. The unit shall receive power from alternating current (ac) main supply, from a vehicle battery or any other suitable 24-volt (V) battery. The unit shall provide unregulated 24-V power to two connectors on the front panel for ancillary equipment and regulated 24-V power for the radio equipment, carrier terminals and combiner.

3.1.2 Control, Terminal Set, C-7827/VCC. The control unit shall provide for connecting and switching of audio and high frequency (hf) carrier circuits between the carrier terminal, the radio set and the handset. The unit shall be used in conjunction with the Control, Power Supply, C-7674/VCC. A transistor shall be provided to control the receiver-transmitter (rt) relay in the Receiver Transmitter RT-524/VRC, so that a heavy current shall not be carried through the handset cable.

Source: https://assist.dla.mil -- Downloaded: 202610-20T20:57Z
Check the source to verify that this is the current version before use.

3.1.3 Type and function of equipment. The Control, Power Supply, C-7674/VCC and the Control, Terminal Set, C-7827/VCC together shall constitute a lightweight, high performance, tactical transistorized power supply and switching circuit. The unit shall also have the following characteristics:

(a) High reliability and ease of maintainability.
(b) Small physical size.

3.1.4 Mounts.

3.1.4.1 Mount, MT-4081/VCC. The Control, Power Supply, C-7674/VCC requires for operation one Mount, MT-4081/VCC. This mount is not part of the Control, Power Supply, C-7674/VCC.

3.1.4.2 Mount, MT-4080/VCC. The Control, Terminal Set, C-7827/VCC, requires for operation one Mount, MT-4080/VCC. This mount is not part of the Control, Terminal Set, C-7827/VCC.

3.2 First article. Prior to submission of any complete production units for acceptance, the contractor shall furnish first articles for testing under the direction and supervision of the cognizant Government inspector to determine conformance to this specification. First article is defined as a production sample which will be identical to the production items which the contractor will subsequently produce in fulfillment of the contract. Unless otherwise specified, a quantity of five first articles shall be furnished (see 6.2). Approval of the first articles by the activity concerned shall not relieve the contractor of the responsibility to supply equipment conforming to this specification. Examination and testing shall be as specified herein. Any changes or deviations of the production units from the first articles shall be subject to the approval of the contracting officer. The items subjected to first article tests may be included in the final shipment as part of the total quantity to be supplied under the contract, provided they have been completely refurbished.

3.3 Reliability assurance. Reliability shall receive major emphasis during the design, fabrication and construction of units. This emphasis shall be reflected in the assembly

Source: https://assist.dla.mil -- Downloaded: 2026-10-20T20:57Z
Check the source to verify that this is the current version before use.

processes and the determination of operational techniques. The first article, production and sample items shall be subjected to the mechanical and electrical tests specified in Section 4. Mechanical wear shall be such that mechanical or functional performance is not affected. Abrasion of painted surfaces is allowable. Electrical performance of the terminal shall not be degraded. The contractor is required to demonstrate that the unit is capable of calculated mean time between failure (MTBF) of not less than 15,000 hours. The contractor is required to demonstrate actual MTBF of not less than 500 hours under standard and service conditions. Test level No. 2 of MIL-R-22732 shall be utilized in establishing demonstrated test conditions.

3.4 Design and construction. Design and construction shall be as follows:

3.4.1 Mechanical parts. Where mechanical parts are employed, whose functions are to rotate, cam or oscillate against other mechanical parts and the best choice of materials includes other than those specified in MIL-E-16400, use of the other materials may take precedence.

3.4.2 Parts and materials. In the selection of parts and materials, the fulfillment of major objectives shall be the prime consideration. In all cases, general material requirements as to flammability, fungus-resistance and nontoxicity as specified in MIL-T-152 shall be met.

3.4.3 Nonstandard parts. When it has been determined that requirements cannot be met by use of parts and materials specified in MIL-E-16400, the contractor shall immediately inform the contracting officer by submission of detailed data, as required by MIL-E-16400, and shall request approval.

3.4.4 Components. Parts and materials approved by specifications listed in MIL-E-16400 shall be given first consideration.

3.4.5 Case material. Construction of the case, front panel for the units, and mounting base shall be made of cast aluminum alloy. Where panels are removable from the case and cables enter the front panel or case, such openings shall be

Source: https://assist.dla.mil -- Downloaded: 202640-20T20:57Z
Check the source to verify that this is the current version before use.

protected with gaskets and packing to assure watertight protection for the equipment when in transit, or in a nonoperating condition. The units shall be immersion-proof while operating, with external signal lines attached.

3.4.6 Treatment and painting. Treatment and painting shall conform to MIL-T-704. Color shall match Marine Corps green, No. 23 (see 6.3).

3.4.7 Standard conditions. The following conditions shall be used as the basis for establishing normal requirements for conducting laboratory and bench testing of the units.

(a) Room ambient temperature, +20° to +40° centigrade (C).

(b) Room ambient humidity, up to 95 percent relative.

3.4.8 Service conditions. The units shall operate satisfactorily under any of the following service conditions:

(a) Ambient temperature range, -40° C to +65° C.

(b) Altitude, sea level to 10,000 feet.

(c) Ambient humidity, range 0 to 95 percent relative.

(d) Vibration (see 4.3).

(e) Shock (see 4.4).

(f) Immersion (leakage)(see 4.5).

(g) Salt fog environment(see 4.11).

(h) Blowing sand and dust(see 4.12).

(i) Temperature shock (see 4.8).

(j) High temperature(see 4.6).

(k) Low temperature(see 4.7).

Source: https://assist.dla.mil -- Downloaded: 2026-10-20T20:57Z
Check the source to verify that this is the current version before use.

3.4.9 Storage conditions. The equipment shall be capable of being stored under the following conditions with a subsequent period of operation:

(a) Ambient temperature range - -62° C to +71° C
(b) Altitude - Sea level to 50,000 feet

3.4.10 Stability.

3.4.10.1 Electrical. The equipment shall operate as specified herein for at least 500 hours, either continuously or intermittently, independent of component failure without necessity for readjustment of any controls other than those located on the front panel.

3.4.10.2 Mechanical. All controls and adjustments shall be desgned so that their position of adjustment will not be altered when the equipment is subjected to the specified service conditions.

3.4.11 Interchangeability. All components and parts shall be physically, functionally, mechanically and electrically interchangeable with any other units produced under this specification.

3.4.12 Identification marking. Subassemblies shall be identified with the manufacturer's part number, steel stamped, rubber stamped or silk screened on a fixed surface if available, or on a permanent tag affixed in a manner which shall not impair operation of the assembly, and shall not be easily removable. This marking shall be visible when mounted in the assembly.

3.5 Fungus resistance. The units shall be rendered fungus proof by the selection of parts and materials which are nonnutrient for fungus.

3.6 Electrical characteristics. Unless otherwise specified herein, the electrical characteristics shall be as specified in the following paragraphs at nominal line voltage of the 115 alternating current volts (Vac).

3.6.1 Power supply. All 115-Vac circuits shall have an insulation resistance to ground of 50 megohms or greater at 500 direct current volts (Vdc).

Source: https://assist.dla.mil -- Downloaded: 2026-10-20T20:57Z
Check the source to verify that this is the current version before use.

3.6.1.1 Output and input voltage. The output voltage shall not exceed the maximum for the following ranges of input voltage:

(a) 100 to 120 Vac
(b) 24 to 32 Vdc

For direct current (dc) input voltages less than 24 V, the output voltage shall not exceed the input by more than 0.75 V for all working load conditions.

3.6.1.2 Load currents. The Control, Power Supply, C-7674/VCC, shall be capable of supplying the following continuous load currents to associated equipment over the input voltage ranges specified in 3.6.1.1.

(a) Regulated 13 amperes (A)

(b) Regulated 12 A and nonregulated 3 A.

3.6.1.3 Short circuit conditions. The Control, Power Supply, C-7674/VCC, shall be capable of withstanding a continuous or an intermittent short circuit condition at the 24-Vdc regulated output.

3.6.1.4 Ripple voltage. The root mean square (rms) ripple content of the 24-Vdc regulated output shall be 2 V maximum under maximum load or equivalent maximum load conditions.

3.6.2 Handset circuit. Provision shall be made for switching a H-138/U or H-189/R Handset connected to the Control, Terminal Set, C-7827/VCC, as follows:

(a) To Receiver-Transmitter, RT-524/VRC, providing simplex operation.

(b) Microphone to transmitter of RT-524/VRC, receiver to receiver R-442/VRC, providing duplex operation.

(c) To handset outlet of Terminal, Telegraph-Telephone, TH-81/GCC.

Source: https://assist.dla.mil -- Downloaded: 2026-10-20T20:57Z
Check the source to verify that this is the current version before use.

3.6.3 High frequency circuit. Provision shall be made for switching the hf input and output of a Terminal, Telegraph-Telephone, TH-81/GCC, connected to the Control, Terminal Set, C-7827/VCC, as follows:

(a) No connection.

(b) Output to Receiver Transmitter, RT-524/VRC, input to Receiver, R-442/VRC.

3.6.4 Terminal, Telegraph-Telephone TH-81, power circuit. Power shall be available at the Terminal, Telegraph-Telephone, TH-81/GCC, in all switch positions.

3.6.5 Receive/Transmit relay circuit. In order to reduce the handset cable current, the Control, Terminal Set, C-7827/VCC, shall provide a rt relay amplifier for Receiver-Transmitter, RT-524/VRC.

3.6.5.1 Energizing rt relay. Provision shall be made for energizing the rt relay when Terminal, Telegraph-Telephone, TH-81/GCC, is connected to Receiver-Transmitter, RT-524/VRC.

3.6.6 Circuit alarm. The Control, Terminal Set, C-7827/VCC, shall connect the Terminal, Telegraph-Telephone, TH-81/GCC alarm so as to be audible at the speaker of Receiver-Transmitter, RT-524/VRC.

3.7 Controls and connections. The control panels shall contain the following operator controls and shall be identified as follows:

(a) Front panel, Control, Power Supply, C-7674/VCC.

Control or Connector	Switch Position	Function
24 VDC NON REG connector J32		Provide 24 Vdc, nonregulated power for the operation of cipher equipment.
BAT connector J33		Connects power from the 24-V vehicle battery.

Source: https://assist.dla.mil -- Downloaded: 2026-10-20T20:57Z
Check the source to verify that this is the current version before use.

Control or Connector	Switch Position	Function
10A AC fuses F16 and F17		Protect the ac supply leads.
30A DC Fuse F18		Protects the leads from the vehicle battery.
POWER switch S21 (3-position)	115 VAC	Connects 115 Vac to the rectifier.
	OFF	Disconnects all power.
	24 VDC	Connects 24-Vdc power from the vehicle battery to the control unit.
115 VAC Captive cable		Connects to 115-Vac outlet.
C-7827/VCC Connector J35		Supplies 24 Vdc regulated to the Control, Terminal Set, C-7827/VCC.
R-442/VRC Connector J34		Provides connection to power connector J11 on rear of Mounts, MT-1898/VRC

(b) Front and side panels, Control, Terminal Set, C-7827/VCC.

Control or Connector	Switch Position	Function
Handset Connector J41		Provides connection for handset. It is connected to radio equipment for single-channel positions of the MODE switch. It is connected to the carrier terminal for the multi-channel position of the MODE switch.

Source: https://assist.dla.mil -- Downloaded: 202610-20T20:57Z
Check the source to verify that this is the current version before use.

Control or Connector	Switch Position	Function
24 VDC connector J42		Provides connection for power cable from Control, Power Supply, C-7674/VCC.
R-442/VRC Connector J43		Provides connection to output connector J12 on rear of Mount, MT-1898/VRC.
MODE switch S26 (3 position rotary)	SIMPLEX	Handset and transmitting antenna connected to the Receiver Transmitter, RT-524/VRC; the Receiver, R-442/VRC, is disconnected; provides single-channel simplex operation.
	SINGLE-CHANNEL DUPLEX	Handset and antennas connected to Receiver, R-442/VRC, and transmitter section of Receiver, Transmitter, RT-524/VRC; receiver section of Receiver Transmitter, RT-524/VRC, not connected; provides single-channel duplex operation.
	MULTI-CHANNEL DUPLEX	Transmitting side of carrier terminal connected to transmitter of Receiver Transmitter, RT-524/VRC; receiving side of carrier terminal connected to Receiver, R-442/VRC; receiver of the Receiver Transmitter, RT-524/VRC, not connected; handset connected to the HANDSET switch; provides multichannel duplex operation.

Source: https://assist.dla.mil -- Downloaded: 202610-20T20:57Z
Check the source to verify that this is the current version before use.

Control or Connector	Switch Position	Function
SPKR RT Captive Cable		Connects rt handset and rt relay amplifier to Terminal, Telegraph-Telephone, TH-81/GCC, alarm to rt No. 1 speaker.
X MODE RT Captive Cable		Connects Terminal, Telegraph-Telephone, TH-81/GCC hf input and output to rt.
R-442/VRC Connector J43		Connects audio output of Receiver, R442/VRC to hf input of Terminal, Telegraph-Telephone, TH-81/GCC.
HF Captive Cable		Connects to hf connector of Terminal, Telegraph-Telephone, TH-81/GCC.
HANDSET TERM. 1 Captive Cable		Connects to Handset Connector of Terminal, Telegraph-Telephone, TH-81/GCC.

3.8 Dimensions. The maximum external dimensions of the Control, Power Supply, C-7674/VCC, shall not exceed 8.875 inches wide by 11.250 inches deep by 5.0 inches high and the maximum dimensions of the Control, Terminal Set, C-7827/VCC, shall not exceed 4.593 inches wide by 9.312 inches deep by 2.500 inches high.

3.9 Weight. The weight of the Control, Power Supply, C-7674/VCC, shall not exceed 26 pounds and the weight of the Control, Terminal Set, C-7827/VCC, shall not exceed 7-1/2 pounds.

3.10 Identification plates. Identification plates shall be in accordance with MIL-P-15024 and shall be of aluminum

Source: https://assist.dla.mil -- Downloaded: 2026-10-20T20:57Z
Check the source to verify that this is the current version before use.

alloy where possible. Drawings for identification plates shall be submitted for approval 90 days prior to first article tests. Nomenclature shall be requested in accordance with MIL-E-21981 and shall be submitted 90 days prior to the first article testing.

3.11 Workmanship. Units covered by this specification shall be manufactured and finished in accordance with MIL-E-16400.

4. QUALITY ASSURANCE PROVISIONS

4.1 Responsibility for inspection. Unless otherwise specified in the contract or purchase order, the supplier is responsible for the performance of all inspection requirements as specified herein. Except as otherwise specified in the contract or order, the supplier may use his own or any other facilities suitable for the performance of the inspection requirements specified herein, unless disapproved by the Government. The Government reserves the right to perform any of the inspections set forth in the specification where such inspections are deemed necessary to assure supplies and services conform to prescribed requirements.

4.2 Inspection and tests. Inspection and tests shall consist of all tests specified herein to demonstrate that the units submitted for approval meet all requirements of this specification. First article testing shall be witnessed by a representative of the contracting officer.

4.2.1 Tests. Table I lists the tests required for first article, production and sample tests.

4.2.1.1 Inspection and test procedures. The detailed procedures for conducting tests shall be prepared by the contractor and submitted to the contracting officer for approval 30 days prior to the initiation of any official testing.

Source: https://assist.dla.mil -- Downloaded: 2026-10-20T20:57Z
Check the source to verify that this is the current version before use.

Table I - Tests

Electrical	Para.	Para. 3.4.7 Standard condition	4.3 Vibration	4.4 Shock	4.5 Immersion	4.6 High temp. +65° C	4.7 Low temp. -40° C	4.9 Humidity	4.10 Low pressure	4.11 Salt fog	4.12 Sand and dust	4.8 Temp. shock
		Environmental										
HF Circuit	3.6.3	FA P				FA S	FA S					
TH-81 Power	3.6.4	FA P	FA	FA	FA	FA S	FA S	FA	FA	FA	FA	FA
Receive-transmit relay circuit	3.6.5	FA P	FA	FA	FA	FA S	FA S	FA	FA	FA	FA	FA
Circuit alarm	3.6.6	FA				FA S	FA S					
Interference	4.13	FA										
Insulation resistance	3.6.1.1	FA P				FA S	FA S					
Output and input voltage	3.6.1.2	FA P	FA	FA	FA	FA S	FA S	FA	FA	FA	FA	FA
Load current	3.6.1.3	FA P	FA	FA	FA	FA S	FA S	FA	FA	FA	FA	FA
Surge current	3.6.1.4	FA				FA S	FA S					
Ripple voltage	3.6.1.5	FA P	FA	FA	FA	FA S	FA S	FA	FA	FA	FA	FA
Handset circuit	3.6.2	FA P				FA S	FA S					

Note: FA= First article test S= Sample test P= Production test

Source: https://assist.dla.mil -- Downloaded: 202640-20T20:57Z
Check the source to verify that this is the current version before use.

4.2.1.2 Tests to be performed. Units to be tested shall be the quantities indicated.

(a) First article. Unless otherwise specified, a quantity of five complete units shall be used to complete these tests (see 3.2). Tests performed on one unit need not be repeated on another. The Government representative will select which units shall be subjected to each test.

(b) Production. All units shall be subjected to the production tests.

(c) Samples. Sample units shall be randomly selected by the cognizant Government inspector.

Qty. produced	Qty. to be tested
1-49	1
50-99	2
100-149	3
150-199	4
200-300	5
	One additional equipment per 100 units.

4.3 Vibration test. One unit shall be subjected to the following vibration test with the unit operating. The unit shall be affixed to the vibration table and be subjected to the following conditions. Vibration in the frequency range of 10 to 55 hertz (Hz) at 5 gravity (g) or 0.060 inch total excursion, whichever is the limiting value. The frequency change shall be at a rate of less than 1 Hz. The duration of the test shall be 1/2 hour in each of three planes. There shall be no rigid body resonances and no signs of internal or external physical deterioration.

4.4 Shock test. One unit shall be subjected to the following shock test with the unit operating. The unit shall be mounted rigidly on the adapter plate of the LAB package testing machine. The machine shafts shall be operated in phase and adjusted in speed to produce average peak accelerations of 10 g's with occasional peaks of 20 g's as measured on the case of the equipment. Malfunction is permissible provided that normal operation can be restored by adjustment of front panel controls. There shall be no signs of internal or external physical deterioration.

Source: https://assist.dla.mil -- Downloaded: 202610-20T20:57Z
Check the source to verify that this is the current version before use.

4.5 Immersion (leakage) test. The unit shall be submerged in water to a depth of 3 feet, measured from its highest point. The unit shall be held in this position for 1 hour, and during the test all panel controls shall be operated three times through their full travel. There shall be no entry of water into the unit. There shall be no signs of internal or external physical deterioration.

4.6 High temperature test. The unit shall be tested in accordance with procedure I, method 501, of MIL-STD-810. The unit shall be operated at a temperature not less than 60° C nor greater than 65° C.

4.7 Low temperature test. The unit shall be tested in accordance with procedure I, method 502 of MIL-STD-810. The unit shall be operated at a temperature not greater than -40° C.

4.8 Temperature shock test. The unit shall be tested in accordance with procedure I, method 503, of MIL-STD-810 with exception that the maximum temperature shall be 71° C.

4.9 Humidity test. The unit shall be tested in accordance with procedure I, method 507, of MIL-STD-810.

4.10 Low pressure test. The unit shall be tested in accordance with procedure I, method 500, of MIL-STD-810.

4.11 Salt fog test. The unit shall be tested in accordance with procedure I, method 509, of MIL-STD-810. Salt deposits shall be removed by rinsing with tap water.

4.12 Sand and dust test. The unit shall be tested in accordance with procedure I, method 510, of MIL-STD-810.

4.13 Interference test. The units shall be tested for conducted interference and radiated interference in accordance with MIL-STD-826.

4.14 Test reports. The contractor shall prepare and submit to the procuring activity copies of all test reports not less than 10 days after completion of tests.

4.15 Approval. Approval of the first articles shall be by the contracting officer upon satisfactory completion of all tests.

Source: https://assist.dla.mil -- Downloaded: 2026-10-20T20:57Z
Check the source to verify that this is the current version before use.

4.16 Acceptance. With exception of the first articles, acceptance of all items shall be by the cognizant Government inspector.

5. PREPARATION FOR DELIVERY

5.1 Preservation, packaging and packing. Preservation, packaging and packing shall be level A or C in accordance with MIL-E-17555 as specified in the contract or order (see 6.2).

5.2 Marking. In addition to any special marking required by the contract or order, unit packages, intermediate packages, and shipping containers shall be marked in accordance with the requirements of MIL-STD-129.

6. NOTES

6.1 Intended use. This unit is employed with the Terminal, Telegraph-Telephone, TH-81/GCC to provide power and switching capabilities of this unit and the associated rt sets under tactical conditions.

6.2 Ordering data. Procurement documents should specify the following:

(a) Title, number, and date of this specification.
(b) Quantity of first articles required (see 3.2 and 4.2.1.2(a)).
(c) Level of preservation, packaging, and packing (see 5.1).

6.3 Color. Color chips for Marine Corps green, No. 23, may be obtained from the Commandant of the Marine Corps, (Code CSY-10), Headquarters, U.S. Marine Corps, Washington, D. C. 20380.

6.4 First article. The first articles shall be examined and tested for approval, at the contractor's plant or at an independent commercial testing laboratory acceptable to the procuring activity. First article tests shall be witnessed by a Government representative of the procuring activity. Approval of the first articles shall be by the contracting officer.

Preparing activity:
Navy - MC
Project No. 5805-N136

Source: https://assist.dla.mil -- Downloaded: 202610-20T20:57Z
Check the source to verify that this is the current version before use.

SPECIFICATION ANALYSIS SHEET

Form Approved
Budget Bureau No. 119-R004

INSTRUCTIONS

This sheet is to be filled out by personnel either Government or contractor, involved in the use of the specification in procurement of products for ultimate use by the Department of Defense. This sheet is provided for obtaining information on the use of this specification which will insure that suitable products can be procured with a minimum amount of delay and at the least cost. Comments and the return of this form will be appreciated. Fold on lines on reverse side, staple in corner, and send to preparing activity *(as indicated on reverse hereof)*.

PECIFICATION

RGANIZATION *(Of submitter)* | CITY AND STATE

ONTRACT NO. | QUANTITY OF ITEMS PROCURED | DOLLAR AMOUNT $

ATERIAL PROCURED UNDER A

☐ DIRECT GOVERNMENT CONTRACT ☐ SUBCONTRACT

. HAS ANY PART OF THE SPECIFICATION CREATED PROBLEMS OR REQUIRED INTERPRETATION IN PROCUREMENT USE?

A. GIVE PARAGRAPH NUMBER AND WORDING.

B. RECOMMENDATIONS FOR CORRECTING THE DEFICIENCIES.

. COMMENTS ON ANY SPECIFICATION REQUIREMENT CONSIDERED TOO RIGID

. IS THE SPECIFICATION RESTRICTIVE?

☐ YES ☐ NO IF "YES", IN WHAT WAY?

. REMARKS *(Attach any pertinent data which may be of use in improving this specification. If there are additional papers, attach to form and place both in an envelope addressed to preparing activity)*

MITTED BY *(Printed or typed name and activity)* | DATE

Source: https://assist.dla.mil -- Downloaded: 2026-10-20T20:57Z
Check the source to verify that this is the current version before use.

FOLD

DEPARTMENT OF THE NAVY

POSTAGE AND FEES PAID
NAVY DEPARTMENT

OFFICIAL BUSINESS

Commandant of the Marine Corps (CSY-10)
Headquarters, U. S. Marine Corps
Washington, D. C. 20380

FOLD

Source: https://assist.dla.mil -- Downloaded: 202610-20T20:57Z
Check the source to verify that this is the current version before use.