MILITARY SPECIFICATION
GENERATOR, SIGNAL SG-1171/U

This specification is approved for use by the Communications Research and Development Command, Department of the Army, and is available for use by all Departments and Agencies of the Department of Defense.

1 SCOPE

1.1 Scope. This specification defines a Generator, Signal, capable of producing various signal function wave-forms in the frequency range of 0 01 MHz to 10 MHz and is hereinafter called the equipment

1 2 Classification. The equipment defined by this specification shall be Type II, Class 5, Style E, Color R per MIL-T-28800 and as herein with the convertible/rack-mountable capability

2. APPLICABLE DOCUMENTS

2 1 Issues of documents. The following documents of the issue in effect on the date of invitation for bids, or the request for proposal, form a part of this specification to the extent specified herein

beneficial comments (recommendations, additions, deletions) and any pertinent data which may be used in improving this document should be addressed to. US Army Communications Research and Development Command, ATTN DRDCO-CM-DM, Fort Monmouth, New Jersey 07703 by using the self-addressed Standardization Document Improvement Proposal (DD Form 1426, appearing at the end of this document or by letter

FSC 6625

Source: https://assist.dla.mil -- Downloaded: 202610-22T19:55Z
Check the source to verify that this is the current version before use.

SPECIFICATIONS

MILITARY

MIL-T-28800	Test Equipment for Use with Electrical Electronic Equipment, General Specification for

STANDARDS

MILITARY

MIL-STD-461	Electromagnetic Interference Characteristics, Requirements for Equipments
MIL-STD-462	Electromagnetic Interference Characteristics, Measurement of
MIL-STD-781	Reliability Tests, Exponential Distribution

(Copies of specifications, standards, drawings and publications required by contractors in connection with specific procurement functions should be obtained from the procuring activity or as directed by the contracting officer.)

3. REQUIREMENTS

3.1 Classification of requirements. The requirements for the equipment are classified as follows:

REQUIREMENT	PARAGRAPH
Safety	3.2
Parts, materials and processes	3.3
Design and construction	3.4
Electrical power sources and connections	3.5
Dimensions and weight	3.6
Enclosure requirements	3.7
Marking and identification	3.8
Environmental requirements	3.9
Reliability requirements	3.10
Performance characteristics	3.11

Source: https://assist.dla.mil -- Downloaded: 202610-22T19:55Z
Check the source to verify that this is the current version before use.

3.2 Safety. Unless otherwise specified herein, the equipment shall comply with the Type II safety requirements specified in MIL-T-28800.

3.3 Parts, materials and processes. Unless otherwise specified herein, the equipment shall comply with the Type II parts, materials and processes requirements of MIL-T-28800.

3.3.1 Restricted materials. Equipment shall comply with the restricted material requirements of MIL-T-28800 including the requirement for mercury or radioactive materials and shall contain no combination of materials which cause deterioration of any material contained in the equipment due to effects of outgassing.

3.4 Design and construction. Unless otherwise specified herein, the equipment shall comply with the Type II, Class 5, Style E, Color R, design and construction requirements of MIL-T-28800 with the convertible/rack-mountable capability.

3.4.1 First article. When specified, the contractor shall furnish five sample equipments for first article inspection and approval. (See 4.3 and 6.2)

3.4.2 Mainframe plug-in concept. Equipment utilizing externally accessible, externally removable subassemblies (mainframe plug-in concept) do not meet the requirements of this specification and therefore are unacceptable. Items using this concept may be offered, provided the plug-in(s) shall not be removable by access through the front panel or rear panel with the unaided hand. A system part number shall be assigned to any such mainframe plug-in combination required to meet the requirements of this specification. The system part number shall be marked on the mainframe identification plate and any plug-in(s).

3.4.3 Controls. Unless otherwise specified herein, built-in adjustments and compensating devices shall not be externally accessible.

3.4.3.1 Front panel controls. All controls which are required to operate the equipment throughout its specified performance characteristics, shall be located on the front panel.

3.4.4 Accessibility. The equipment shall be constructed so that.

Source: https://assist.dla.mil -- Downloaded: 20261O-22T19:55Z
Check the source to verify that this is the current version before use.

3.4.4.1 Subassemblies. Subassemblies and chassis components can be removed without removing any other hard wired subassembly, printed circuit card or component.

3.4.4.2 Adjustments. Adjustments can be made without removing any component, printed circuit card or subassembly except the use of extender cards is permitted.

3.4.4.3 Printed circuits. Printed circuit cards can be removed without the need to unsolder cables and interconnecting wiring (connections to all printed circuit cards shall be through pin and socket connectors). Printed circuit cards (mother boards) designed primarily to distribute power and signals to other printed cards (daughter boards) are excluded from this requirement. When such mother boards are used, they shall be accessible from both sides to allow maintenance testing.

3.4.4.4 Indicator lights. Unless approved by the procuring activity upon presentation of acceptable reliability data, indicator lights other than light emitting diodes (LEDs) shall be accessible from the operator's side of the front panel.

3.4.4.5 Encapsulation and embedment. Encapsulation and embedment (potting) of subassemblies shall not be used.

3.4.5 Solid State construction. Unless otherwise specified herein, the equipment shall be of solid-state, modular, miniaturized construction.

3.5 Electrical power sources and connections. Unless otherwise specified herein, the equipment shall comply with the Type II electrical power sources and connections requirements of MIL-STD-2880. The equipment shall operate from a nominal 115/230 volts, single phase, 50, 60 and 400Hz source.

3.5.1 Maximum power. The maximum power consumption of the equipment shall be 50 watts.

3.5.2 Input power selection device. An input power selection device shall be provided for selection of input power voltages of 115 VAC or 230 VAC. Provision shall be incorporated to prevent accidental switching. When the equipment is delivered, the power selection device shall be in the 115 VAC position.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T19:55Z
Check the source to verify that this is the current version before use.

3.5.3 Fuses and circuit breakers. Fuses and circuit breakers shall be in accordance with MIL-T-28800. (115VAC/230VAC) Either common or separate fuseholders may be provided. If only one fuseholder is used (common), the equipment shall be provided with the 115VAC fuse installed and the 230VAC fuse shall be stowed with the accessories.

3.5.4 Input power switch. A front panel mounted power switch shall be provided. The ON position shall have panel identification lights for AC operation. The switch shall break both sides of the power source.

3.6 Dimensions and weight.

3.6.1 Dimensions. The overall dimensions shall be 152.4mm (6 in) maximum height, 381mm (15 in) maximum depth and the width as specified in MIL-T-28800 for rack-mounted equipment. A blank plate may be required to satisfy incremental height requirements.

3.6.2 weight. The maximum weight of the equipment shall be 8.89KG (20 lbs).

3.7 Enclosure requirements. Unless otherwise specified herein, the equipment shall comply with the Style E enclosure requirements of MIL-T-28800.

3.8 Marking and identification. Unless otherwise specified herein, the equipment shall comply with the Type II marking and identification requirements of MIL-T-28800.

3.8.1 Supplemental identification plate. The supplemental identification plate specified in MIL-T-28800 shall contain the following data only:

a. Nomenclature.
b. Procurement instrument identification number (PIIN).
c. Serial number
d. National stock number.
e. US

3.9 Environmental requirements. Unless otherwise specified herein, the equipment shall comply with the Class 5 environmental requirements of MIL-T-28800.

Source: https://assist.dla.mil -- Downloaded: 20261O-22T19:55Z
Check the source to verify that this is the current version before use.

3.9.1 Electromagnetic interference. The equipment shall comply with the following emission and susceptibility requirements of Notice 4, MIL-STD-461.

CE02	CS02	RE02.1	RS03
CE04	CS06	RE02	

RE02.1 and RS03 shall be performed from 14KHz to 1GHz with RS03 at a susceptibility level of one volt per meter (1V/m).

3.9.2 Humidity. The equipment shall meet the humidity requirements in accordance with the test specified in paragraph 4.5.5.1.1.3 of MIL-T-28800.

3.9.3 Vibration. The equipment shall comply with the Class 5 vibration requirements of MIL-T-28800, except that the equipment need not be operating during vibration.

3.10 Reliability requirements.

3.10.1 Reliability burn-in. Each equipment delivered against this specification shall be submitted to a minimum 96-hour on-time burn-in procedure as specified in 4.4 4. The last 24 nours of burn-in shall be failure free.

3.10.2 Reliability Reliability shall comply with requirements as specified herein. The specified MTBF snall be 2500 nours when tested as specified in 4.4.4. A failure shall be defined in MIL-STD-781, para 3.1, and as any departure from the required performance or operation of the required accuracies (not correctable by normal use of the operating controls) after the test is initiated. Test Level B, MIL-STD-781 snall be the required test level.

3.10.3 Maintainability requirements. The equipment shall comply with the Type II maintainability requirements of MIL-T-28800 (See 6 4)

3.11 Performance characteristics.

3 11.1 Output frequency. The output frequency range of the equipment shall extend from 0.01MHz to 10MHz. The accuracy of the output frequency shall be within ± 5 percent of the indicated frequency The minimum required output frequency of the equipment shall be divided into a maximum of 10 frequency bands.

3.11.1.1 Distortion The sine wave distortion snall not exceed 0.5 percent at 1KHz.

3.11.1.2 Frequency response. The output level shall not vary more than +/-1dB over any individual frequency band.

Source: https://assist.dla.mil -- Downloaded: 202610-22T19:55Z
Check the source to verify that this is the current version before use.

3.11.1.3 Harmonics. The sine wave harmonics shall be at least 30dB below the fundamental frequency.

3.11.2 Output signals. The output waveforms shall be selectable between sine, square, sawtooth, triangle and pulse waveforms.

3.11.2.1 DC offset. The DC offset shall be continuously adjustable from -10 volts DC to +10 volts DC.

3.11.2.2 Linearity The linearity error of the sawtooth and triangle waveforms shall be less than 1 percent at 100Hz.

3.11.2.3 Pulse width. The pulse width shall be continuously variable over a range of 0.1 microsecond to 5 seconds.

3 11.2.4 Pulse MOD transition time. The rise and fall time of the square and pulse waveforms shall be less than 21 nanoseconds each.

3 11.2.5 Synchronization output. The equipment shall provide a synchronization signal output of at least 1 volt peak-to-peak square wave. The source impedance shall be 50 ohms +/-10 percent.

3.11.3 Attenuation output. The output attenuation range shall be 50dB with 10dB vernier calibrated in 1dB steps

3 11.4 Output voltage. The output voltage shall be at least 10 volts peak-to-peak across a 50 ohm load The accuracy of the output voltage shall be within ±1dB of the indicated value.

3.11.5 Impedance output. The output impedance of the equipment shall be 50 ohms.

3 11.6 Primary connectors. The output signal connectors shall be series "BNC" female.

4. QUALITY ASSURANCE PROVISIONS

4.1 Responsibility for inspection. Unless otherwise specified in the contract, the contractor is responsible for the performance of all inspection requirements as specified herein. Except as otherwise specified in the contract, the contractor may use his own or any other facilities suitable for the performance of the inspection requirements specified herein, unless disapproved by the Government. The Government reserves the right to perform any of the inspections set forth in the specification where such inspections are deemed necessary to assure supplies and services conform to prescribed requirements.

Source: https://assist.dla.mil -- Downloaded: 202610-22T19:55Z
Check the source to verify that this is the current version before use.

4.2 Classification of inspections. The inspections required herein are classified as in a and b.

a. First article inspection (see 4.3).
b. Quality conformance inspection (see 4.3).

4.3 First article and quality conformance inspection. Unless otherwise specified herein, the first article and quality conformance inspections shall be in accordance with MIL-T-28800.

4.3.1 Test plan. Unless otherwise stated in the contract, the contractor shall prepare a test plan in accordance with paragraphs 4.3(a) and 4.4(a) of MIL-T-28800, for use with both classes of inspection. The test plan shall include as a minimum the tests listed in TABLES I, II, & III, the tests noted in section 4.4, and a description of the satisfactory operation check and satisfactory operation test, as defined in para 4.5 of MIL-T-28800. Unless otherwise required, the tests and inspections to be performed shall be identical for both classes of inspection.

4.3.2 Inspection sampling plan. The inspection sampling to be performed during both classes of inspection shall be as specified in MIL-T-28800, except as indicated below:

4.3.2.1 First production lot. Unless otherwise specified herein or in the contract, the Group C, D, E & F quality conformance inspections shall be performed on the first production lot only.

4.3.2.2 Group D and F tests. The Group D EMI tests and Group F Reliability test shall be performed during quality conformance inspection only if not performed during first article.

4.4 Quality assurance tests. Unless otherwise specified herein, the following tests shall be performed in accordance with MIL-T-28800.

4.4.1 Electromagnetic interference. One equipment shall be subjected to an EMI test for compliance with the requirements of 3.9.1. All test set-ups and procedures shall comply with the measurement techniques of Notice 3, MIL-STD-462. All emission and susceptability tests shall be performed with the supplied output cable connected to, and extended parallel with, the front of the equipment. The output cable shall be terminated to simulate a normal loading configuration.

4.4.2 Humidity. The equipment shall be subjected to the humidity test specified in para 4.5.5.1.1.3 of MIL-T-28800.

4.4.3 Vibration. The equipment shall be subjected to the vibration tests specified in MIL-T-28800, for Class 5 equipment, except that the equipment shall not be operated during the test. The satisfactory operation test shall be performed prior to and following vibration testing.

Source: https://assist.dla.mil -- Downloaded: 202640-22T19:55Z
Check the source to verify that this is the current version before use.

TABLE I

Examination and Test Groups

DESCRIPTION	RQMT.	TEST METHOD
Group A Preoperational Inspection Leakage Current Level A Performance	4.5.3.1* 3.2.1.3.1* TABLE II	4.3.1
Group B Level B Performance	TABLE III	4.3.1
Group C Electrical Power Environmental Requirements Humidity Vibration	3.5 3.9 3.9.2 3.9.3	4.3.1
Group D Electromagnetic Interference	3.9.1	4.4.1
Group E Dimensions Weight Front Panel Marking	3.6.1 3.6.2 3.8	4.3.1 4.3.1
Group F Reliability	3.10	4.3.1 4.4.4

*Paragraphs of MIL-T-28800

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T19:55Z
Check the source to verify that this is the current version before use.

TABLE II

Level A Performance Tests 1/

DESCRIPTION	REQUIREMENTS
Output Frequency	3 11.1
Output Signals	3.11.2
Output Attenuation	3.11.3
Output Voltage	3.11 4
Output Impedance	3.11.5

1/ Level A testing is abbreviated testing (see 6.4.1)

TABLE III

Level B Performance Tests

DESCRIPTION	REQUIREMENTS
Distortion	3.11.1.1
Frequency Response	3.11.1.2
Harmonics	3.11.1.3
DC Off Set	3.11.2.1
Linearity	3.11.2.2
Pulse Width	3 11.2.3
Pulse Modulation Transition Time	3.11.2.4
Synchronization Output	3.11.2.5

Source: https://assist.dla.mil -- Downloaded: 202640-22T19:55Z
Check the source to verify that this is the currentversion before use.

4.4.4 Reliability. The reliability tests shall be performed as follows:

4.4.4.1 Burn-in. Each deliverable equipment shall be subjected to a minimum 96 hours on-time burn-in period, prior to Group A testing. During the last 24 hours of burn-in, the equipment must operate failure free. Up until this time, equipment will be allowed to accumulate failures Each equipment which fails during the final 24 hour period shall be repaired and returned to test until it successfully survives a 24 hour period without failure. Failures which occur during the burn-in test shall be noted and reported, but shall not count toward the establishment of equipment MTBF. Prior to burn-in, the satisfactory operation test of 4.3.1 shall be conducted. Daily satisfactory operation checks (4.3.1) shall be conducted. For the last 24 hour failure free period, a complete satisfactory operation test shall be conducted prior to and after the period.

4.4.4.2 Reliability sampling plan.

4.4 4.2.1 First Article. The Group F reliability demonstration shall be conducted on at least five (5) samples. The use of ten (10) samples is encouraged, but not more than ten (10) samples shall be used.

4.4.4.2.2 Quality conformance inspection. The Group F reliability tests shall be performed on the first production lot, only if not performed during First Article testing. From those units of the first lot that have passed the required Group A and B tests, a random sample of ten (10) units shall be selected, for Group F testing.

4.4.4.2.3 Reliability test plan. The reliability tests shall be conducted in accordance with the following test plan:

θ_0 = 2,500 hrs

Number of Failures	Total Test Time* Accept** (Equal or More)	Reject*** (Equal or Less)
0	2000	N/A
1	3750	558
2	5325	2063
3	6875	3850
4	8375	5725
5	9875	7725
6	11,375	11,375 ****

* Total test time is total unit hours of "equipment ON" time (in hours).
** Accept if test time is greater than or equal to that listed.
*** Reject if test time is less than or equal to that listed.
**** Reject if test time is strictly less than 11,375 with 6 failures.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T19:55Z
Check the source to verify that this is the current version before use.

4.4.4.3 Test length. Testing shall continue until the total unit hours together with the total count of relevant equipment failures permit either an accept or reject decision in accordance with the specified test plan. Only equipment "ON" time may be used in MTBF or longevity determinations. Testing shall be monitored in such a manner that the times to failure may be estimated with reasonable accuracy. No single equipment "ON" time shall be less than one-half the average operating time of all equipments "ON" test.

4.4.4.4 Test conditions.

4.4.4.4.1 Operating mode (duty cycle). Prior to the burn-in, a satisfactory operation test shall be conducted. Daily satisfactory operation checks shall be conducted. For the last 24 hour failure free period, a complete satisfactory operation test shall be conducted prior to and after the period.

4.4.4.4.2 Test level. While under test, the equipment shall be subjected to the conditions specified by Test Level B, MIL-STD-781.

4.4.4.4.3 Input voltage cycling. When so directed by the procuring activity, voltage cycling shall be accomplished as follows: The input voltage shall be maintained at one hundred ten percent (110%) nominal voltage for one-third of the equipment "ON" cycle, at the nominal value for the second one-third of the equipment "ON" cycle, and at ninety percent (90%) for the final one-third of the equipment "ON" cycle. This cycling procedure is to be repeated continuously throughout the reliability test.

4.4.4.5 Reliability examination and test method. The following inspections shall be used to verify equipment operation during reliability testing. The satisfactory operation test of 4.3.1 shall be used to confirm proper equipment operation prior to and following reliability testing. The satisfactory operation test shall also be performed weekly to verify equipment operation. The satisfactory operation check of 4.3.1 shall be used to monitor proper operation of the equipment daily.

4.4.4.6 Reliability failure actions, Group F. In the event of failure(s) during reliability testing, failure action shall be taken as required in MIL-STD-781, para 5.5.

4.4.4.7 Corrective action, Group F. In the event the reliability test reaches a reject decision, corrective action shall be taken as required in MIL-STD-781, para 5.7.

4.4.5 Optional quality assurance system. The procuring activity may substitute tests from a Department of Defense (DoD) approved supplier's quality assurance system for any or all tests in TABLE I.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T19:55Z
Check the source to verify that this is the current version before use.

5. PACKAGING

5.1 Preservation, packaging. Packaging for delivery shall be in accordance with MIL-T-28800 and as specified by the procuring activity.

6. NOTES

6.1 Intended use. The equipment is intended for use in maintaining electronic communications equipment by equipment repair units in intermediate and depot maintenance.

6.1.1 Equipment replaced. Equipment procured according to this specification is intended to replace all versions of various older equipments now fielded. These equipments to be replaced are listed below:

AN/USM-256	SG-321/U
AN/USM-271	SG-722/U
SG-106/U	SG-747/U
SG-298/U	SG-796/U
SG-299/U	TS-583

6.2 Ordering data. Procurement documents should specify the following:

a. Title, number and date of this specification and any amendment thereto.
b. Packaging requirements (see Section 5).
c. When rough handling and functional tests are required.
d. Place of final inspection.
e. Technical literature required.
f. Quantity of tools and running spare parts required.
g. Marking for shipment and shipping containers.
h. Test plans and test reports.
i. Classification of inspection and number of samples required.
j. Rack mounting requirements.
k. Alternate power requirements.
l. Maintainability rationale.
m. Reliability rationale.

6.3 Contract data requirements.

a. Nomenclature assignment
b. National stock number.
c. Equipment sample test plans.
d. Pretest performance records.
e. First production test data.
f. Identification plate drawing.
g. Maintenance allocation chart.

Source: https://assist.dla.mil -- Downloaded: 202640-22T19:55Z
Check the source to verify that this is the currentversion before use.

6.4 Definitions.

6.4.1 Level A performance tests. Level A testing (TABLE II)is a reduced amount of testing which is performed on each equipment produced. Its purpose is to insure that all functions and modes of operation of the equipment are evaluated without extensively checking each parameter as required in the Level B test (TABLE III). The approved equipment test procedure shall specify the actual amount of testing to be performed.

6.4.2 Reliability rationale. Reliability rationale submitted with the bid should provide clear and concise rationale showing how the reliability of the equipment complies with minimum requirements of the solicitation. This may include data from previous reliability tests, reliability predictions and other data available to the offeror. In the absence of such data on the equipment being offered, such data on similar equipment of equal or greater complexity produced by the offeror may be submitted. However, such data must be clearly identified as comparative data, and accomplished with specifications and technical literature on the similar equipment. The acceptance of the submitted rationale does not relieve the successful bidder of performing and successfully completing the production reliability testing.

6.4.3 Maintainability rationale. Maintainability rationale submitted with the bid should provide clear and concise rationale showing how the maintainability of the equipment complies with requirements of the solicitation. This may include data from previous maintainability tests, records of repair and calibration data, and other data on the equipment available to the offeror. Data on selection of module size and other design features relevant to maintainability may also be submitted.

Custodian:

Army - CR

Review Activities:

Army - MD

User Activities:

Army - AL

Preparing Activity.

Army - CR

(Project 6625-A738)

Source: https://assist.dla.mil -- Downloaded: 202610-22T19:55Z
Check the source to verify that this is the current version before use.

STANDARDIZATION DOCUMENT IMPROVEMENT PROPOSAL

INSTRUCTIONS This form is provided to solicit beneficial comments which may improve this document and enhance its use DoD contractors, government activities, manufacturers, vendors, or other prospective users of the document are invited to submit comments to the government Fold on lines on reverse side, staple in corner, and send to preparing activity Attach any pertinent data which may be of use in improving this document If there are additional papers, attach to form and place both in an envelope addressed to preparing activity A response will be provided to the submitter, when name and address is provided within 30 days indicating that the 1426 was received and when any appropriate action on it will be completed

NOTE This form shall not be used to submit requests for waivers deviations or clarification of specification requirements on current contracts Comments submitted on this form do not constitute or imply authorization to waive any portion of the referenced document(s) or to amend contractual requirements

DOCUMENT IDENTIFIER *(Number)* AND TITLE

MIL-G-49193 (CR)

NAME OF ORGANIZATION AND ADDRESS OF SUBMITTER

HQ USA CORADCOM
ATTN DRDCO-CM-DM
Fort Monmouth, NJ 07703

☐ VENDOR ☐ USER ☐ MANUFACTURER

1 ☐ HAS ANY PART OF THE DOCUMENT CREATED PROBLEMS OR REQUIRED INTERPRETATION IN PROCUREMENT USE? ☐ IS ANY PART OF IT TOO RIGID RESTRICTIVE LOOSE OR AMBIGUOUS PLEASE EXPLAIN BELOW

A GIVE PARAGRAPH NUMBER AND WORDING

B RECOMMENDED WORDING CHANGE

C REASON FOR RECOMMENDED CHANGE(S)

2 REMARKS

SUBMITTED BY *(Printed or typed name and address — Optional)*	TELEPHONE NO
	DATE

DD FORM 1 OCT 76 1426 EDITION OF 1 JAN 72 WILL BE USED UNTIL EXHAUSTED

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T19:55Z
Check the source to verify that this is the current version before use.

FOLD

HQ. USA CORADCOM
ATTN DRDCO-CM-DM
Fort Monmouth NJ 07703

OFFICIAL BUSINESS
PENALTY FOR PRIVATE USE $300

POSTAGE AND FEES PAID



HQ. USA CORADCOM
ATTN DRDCO-CM-DM
Fort Monmouth NJ 07703

FOLD

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T19:55Z
Check the source to verify that this is the current version before use.