MILITARY SPECIFICATION

Test Set, Radio AN/PRM-30

This specification has been approved by the Bureau of Naval Weapons, Department of the Navy.

1. SCOPE

1.1 Scope - The test equipment covered by this equipment shall be for shop use and shall be suitable for troubleshooting and evaluation of the electrical capabilities of the Emergency Transmitter Beacon AN/PRT-5 and its associated power supply.

1.2 Classification - The TS-2136/PRT-5 shall be of one type and shall consist of the following items:

Items	Type Designation	Appl. Para.
Test Set, Radio	TS-2136/PRM-30	3.4.1
Adapter, Test	MX-7192/PRM-30	3.4.2
Cover, Test Set	CW-856/PRM-30	3.4.3
Cable, Test Set	W-1 of AN/PRM-30	3.4.4

2. APPLICABLE DOCUMENTS

2.1 General - The following documents of the issue in effect on the date of invitation for bids form a part of this specification to the extent specified herein:

SPECIFICATIONS

Military

MIL-E-4682 Electron Tubes and Transistors, Choice and Application of

MIL-T-5422 Testing, Environmental, Aircraft Electronic Equipment

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T05:09Z
Check the source to verify that this is the current version before use.

MIL-I-6181	Interference Control Requirements, Aircraft Equipment
MIL-M-7793	Meter, Time Totalizing
MIL-E-17555	Electronic and Electrical Equipment and Associated Repair Parts, Preparation for Delivery of
MIL-T-18303	Test Procedures; Preproduction and Inspection, for Aircraft Electronic and Associated Equipment
MIL-T-18307	Nomenclature and Nameplates for Aeronautical Electronic and Associated Equipment
MIL-T-21200	Test Equipment for Use with Electronic and Fire Control Systems, General Specification for
MIL-M-23904	Reliability Assurance for Production Acceptance of Avionic Equipment, General Specification for

STANDARDS

Military

MIL-STD-242	Electronic Equipment Parts
MS21993	Cable Assemblies, Power Electrical

2.2 Availability of Documents

(1) When requesting specifications, standards, drawings, and publications refer to both title and number. Copies of this specification and applicable specifications required by contractors in connection with specific procurement functions may be obtained upon application to the Commanding Officer, Naval Supply Depot, Code 105, 5801 Tabor Avenue, Philadelphia 20, Pennsylvania.

3. REQUIREMENTS

3.1 Parts and Materials - In the selection of parts and materials, fulfillment of major design objectives shall be the prime consideration. In so doing the following shall govern:

(1) Parts and materials requirements shall conform to Specification MIL-T-21200. Parts selected from specifications called out in Specification MIL-T-21200 shall be limited to those values, styles, tolerances, etc., set forth in MIL-STD-242.

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T05:09Z
Check the source to verify that this is the current version before use.

(2) Nonrepairable subassemblies, as outlined in Specification MIL-T-21200, shall be used when practicable. The general size of the subassembly, and the amount of circuitry to be included therein shall be approved by the procuring activity. Nonrepairable subassemblies must be reliable. A mean-time-to failure of more than 5000 hours should be the goal of each.

(3) When previously produced models of this equipment did not use nonrepairable subassemblies, the design shall not be changed to employ nonrepairable assemblies without the approval of the procuring activity.

3.1.1 Nonstandard Parts and Material Approval - Approval of the use of nonstandard parts and materials shall be obtained as outlined in Specification MIL-T-21200.

3.1.2 Electron Devices - Electron tubes, transistors and diodes shall be chosen and applied, and the complements reported as outlined in Specification MIL-E-4682.

3.2 Design and Construction - The equipment shall conform with all the applicable requirements of Specification MIL-T-21200 for design, construction and workmanship except as otherwise specified herein.

3.2.1 Total Weight - The total weight of the equipment, including cables, shall be a minimum consistent with good design and shall not exceed 15 pounds.

3.2.2 Reliability

3.2.2.1 Operational Stability - The equipment shall operate with satisfactory performance, continuously or intermittently for a period of at least 200 hours without the necessity for readjustment of any controls which are inaccessible to the operator during normal use.

3.2.2.2 Operating Life - The equipment shall have a minimum total operating life of 1000 hours with reasonable servicing and replacement of parts. Parts requiring scheduled replacement due to wear during the life of the equipment and, the wearout life of such parts, shall be determined by the contractor and submitted to the procuring agency.

3.2.2.3 Reliability in Mean Time Between Failures (MTBF) - The equipment shall have a minimum of 100 hours of mean (operating) time between failures when tested and accepted as outlined under the requirements of 4.4.3.

3.2.3 Cables and Connectors - The equipment shall provide for the use of cables and connectors in accordance with Specification MIL-T-21200. Insofar as is practicable, all connectors on the front panel shall be mounted along the lower edge of the panel and in no case shall their location be such that the connecting cables will interfere with the operating controls.

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T05:09Z
Check the source to verify that this is the current version before use.

3.2.4 Interchangeability - The equipment shall meet the interchangeability requirements as defined in Specification MIL-T-21200.

3.2.5 Interference Control - The generation of radio interference by the equipment and the vulnerability of the equipment to radio interference shall be controlled within the limits of Specification MIL-I-6181.

3.2.6 Maintenance Provisions and Field Testing - Provisions for maintenance shall be as specified in Specification MIL-T-21200. Specific test points and test facilities shall be provided to the greatest extent practicable for ease of field testing and maintenance.

3.2.7 Nomenclature and Nameplates - Nomenclature assignment and nameplate approval for equipment identification shall be in accordance with Specification MIL-N-18307.

3.2.8 Standard Conditions - The following conditions shall be used to establish normal performance characteristics under standard conditions and for making laboratory bench tests.

Temperature	Room ambient ($30^{o} \pm 10^{o}C$)
Altitude	Normal ground
Vibration	None
Humidity	Room Ambient
Input power voltage	Input power shall be received from transmitter beacon battery.

3.2.9 Service Conditions - The test equipment shall operate satisfactorily under any of the environmental service conditions or reasonable combination of these conditions as specified in Specification MIL-T-21200 for Class 3 equipment, except as modified herein.

3.2.10 Warm-Up Time - The time required for the equipment to warm-up prior to operations shall be kept to a minimum and shall not exceed one (1) minute under standard conditions and five (5) minutes at extreme service conditions.

3.2.11 Primary Input Power Requirements - The equipment shall operate from the self-contained battery of the Emergency Transmitter Beacon AN/PRT-5.

3.2.12 Standby Provisions - The equipment shall provide for a standby position whereby rated voltage shall be applied to all tube filaments. Except for the associated filament circuits, voltages shall not be applied to other parts of the equipment.

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T05:09Z
Check the source to verify that this is the current version before use.

3.2.13 Time Totalizing Meter - Unit TS-2136/PRM-30 shall contain a time totalizing meter in accordance with Military Specification MIL-I-81219(WP).

3.3 Performance - The performance of the equipment shall be as set forth below. Unless otherwise specified, these requirements shall apply under both standard and extreme service conditions. When reduced performance requirements for service conditions are acceptable, such variation will be specified.

3.4 Detailed Design Requirements -

3.4.1 Test Set TS-2136/PRM-30 - The test set shall meet the following requirements.

3.4.1.1 Function - The test set shall be portable, provide troubleshooting capabilities and shall be capable of providing GO-NO-GO indications of Emergency Transmitter Beacon, Model AN/PRT-5 functions as follows:

3.4.1.1.1 Battery Condition - The test set shall be capable of checking the battery condition under full load operation. A meter with a marker shall be provided for indicating minimum acceptable battery voltage.

3.4.1.1.2 Current Drain - The test set shall be capable of checking current drain of the emergency transmitter beacon under normal operating conditions. A meter shall be provided for indicating the maximum acceptable current drain.

3.4.1.1.3 Transmitter Checks - The test set shall be capable of indicating RF power output of each transmitter and audibly monitoring the sweep and keying performance of each transmitter.

3.4.1.2 Form Factor - The test set shall be enclosed in a carrying case not more than $13\frac{1}{2}$ inches by 10 inches by $8\frac{1}{4}$ inches.

3.4.1.3 Contents of Unit - The test set shall contain the following assemblies, subassemblies, circuits, etc.

3.4.1.3.1 Panel - The panel shall provide accessible mounting for all operating controls and audio and visual indicators.

3.4.1.3.2 Chassis - The chassis shall contain the necessary switching and amplifying circuits to provide indication of emergency transmitter beacon performance.

3.4.1.3.3 Case - A combination case in accordance with MIL-T-21200 shall provide suitable mounting for the front panel and chassis as well as storage space for an adapter and accessory cable.

3.4.1.4 Controls - The test set shall contain all necessary operating controls to switch-in and adjust the indicating devices.

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T05:09Z
Check the source to verify that this is the current version before use.

3.4.1.5 Indicating Devices - The test set shall be provided with indicating devices which will permit visual and audible monitoring of the functions of the test specimen.

3.4.2 Adapter, Test Set MX-7192/PRM-30 - The test set adapter shall meet the following requirements.

3.4.2.1 Function - The test set adapter shall provide the means of obtaining power for the test set, interconnections between the test set and battery and transmitter units. It shall also provide equivalent impedance loads to replace the emergency transmitter beacon antennas.

3.4.2.2 Form Factor - The test set adapter shall be self contained and shall not exceed 4-5/8 inches by 4 inches by 2 inches.

3.4.2.3 Contents of Adapter - The test set adapter shall contain the following assemblies, subassemblies, circuits, etc.

3.4.2.3.1 Interconnection Facilities - The adapter shall contain provisions for connection to the electronic portion of the emergency transmitter beacon and to the external power supply. It shall provide a means of connecting these items to the test set.

3.4.2.3.2 Simulated Transmitter Load - The adapter shall contain circuitry designed to replace the impedance of the transmitter antennas.

3.4.3 Cover CW-856/PRM-30 - Cover shall be in accordance with MIL-T-21200 and shall house cables and soft wear.

3.4.4 Cable, Interconnecting W-1 - A cable shall be provided for connecting the test set to the adapter. The cable shall be 6.5 feet long and shall have standard military connectors.

3.5 Design Data - No data is required by this specification (other than reports accompanying samples submitted for testing) or by applicable documents, unless specified in the contract or order. (See 6.7)

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T05:09Z
Check the source to verify that this is the current version before use.

4. QUALITY ASSURANCE PROVISIONS

4.1 Responsibility for Inspection - Unless otherwise specified in the contract or purchase order, the supplier is responsible for the performance of all inspection requirements as specified herein. Except as otherwise specified, the supplier may utilize his own facilities or any commercial laboratory acceptable to the Government. The Government reserves the right to perform any of the inspections set forth in the specification where such inspections are deemed necessary to assure supplies and services conform to prescribed requirements.

4.1.1 Classification of Tests - Items covered by this specification shall be subjected to the following tests to determine compliance with all applicable requirements:

(1) Preproduction Tests
(2) Initial Production Tests
(3) Acceptance Tests

4.2 Preproduction Tests - Preproduction tests shall be made on an equipment representative of the production equipments to be supplied under the contract. Preproduction tests shall be accomplished under the responsibility of the contractor and shall be conducted in accordance with the approved test procedure of 4.6. The government inspector and the procuring activity shall be advised when tests are to be conducted so that a representative may be designated to witness or supervise the tests when so desired. Contractors not having adequate facilities to conduct all required tests shall obtain the services of a commercial testing laboratory acceptable to the Government.

4.2.1 Preproduction Test Data - The contractor shall submit all data collected in conducting these tests to the procuring agency for review and approval. On first production contracts this data shall include a list of all electrical and electronic parts giving their specified voltage, current and temperature rating and the applied circuit voltage, current and ambient and surface temperatures. The ambient and surface temperature shall be obtained under the extreme high temperature operating condition.

4.2.2 Scope of Tests - Preproduction tests shall include all tests deemed necessary by the procuring activity to determine that the equipment meets all the requirements of this specification and the contract. Preproduction tests shall include environmental tests in accordance with the procedures of Specification MIL-T-5422 and interference tests in accordance with Specification MIL-I-6181.

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T05:09Z
Check the source to verify that this is the current version before use.

4.2.3 Preproduction Approval - Approval of the preproduction sample shall be by the procuring activity upon satisfactory completion of all tests. No production equipments shall be delivered prior to the approval of the preproduction sample. Prefabrication of production equipment prior to the approval of the preproduction sample is at the contractor's own risk. The approved preproduction sample shall be retained by the contractor for his use in the fabrication and testing of equipment to be submitted for acceptance. The preproduction sample shall not be considered as one of the equipments under the contract.

4.2.4 Production Equipments - Equipments supplied under the contract shall in all respects, including design, construction, workmanship, performance and quality, be equivalent to the approved preproduction sample. Each equipment shall be capable of successfully passing the same tests as imposed on the preproduction sample. Evidence of noncompliance with the above shall constitute cause for rejection and for equipment already accepted by the Government, it shall be the obligation of the contractor to make necessary corrections as approved by the procuring activity.

4.3 Initial Production Tests - One of the first 10 production equipments shall be selected and sent at the contractor's expense to a designated Government laboratory for tests. This equipment shall be selected by the procuring activity after the equipment has successfully passed all individual tests. The preproduction sample shall not be selected for this test.

4.3.1 Scope of Tests - This equipment may be subjected to any and all tests the procuring activity deems necessary to assure that the production equipment is equivalent to the previously approved preproduction sample in design, construction, workmanship, performance and quality and that it meets all applicable requirements.

4.3.2 Accessory Material - In addition to the complete equipment submitted for Initial Production Tests the contractor shall also submit such accessory material and data necessary to test the equipment.

4.3.3 Initial Production Sample Approval - Approval of the Initial Production sample shall be by the procuring activity upon satisfactory completion of all tests. Any design, material or performance defect made evident during this test shall be corrected by the contractor to the satisfaction of the procuring activity. Failure of the Initial Production sample to pass any of the tests shall be cause for deliveries of equipment under the contract to cease until proper corrective action is approved and accomplished. Corrective action shall also be accomplished on equipment previously accepted when requested by the procuring activity.

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T05:09Z
Check the source to verify that this is the current version before use.

4.3.4 Reconditioning of Initial Production Test Sample - On completion of the initial production test the equipment shall be reworked by the contractor by replacing all wear or damaged items. After reworking, the contractor shall resubmit the equipment for acceptance.

4.4 Acceptance Tests - The contractor shall furnish all samples and shall be responsible for accomplishing the acceptance tests. All inspection and testing shall be under the supervision of the government inspector. Contractors not having testing facilities satisfactory to the procuring activity shall engage the service of a commercial testing laboratory acceptable to the procuring activity. The contractor shall furnish test reports showing quantitative results for all acceptance tests. Such reports shall be signed by an authorized represenative of the contractor or laboratory, as applicable. Acceptance or approval of material during the course of manufacture shall not be construed as a guarantee of the acceptance of the finished product. Acceptance tests shall consist of the following:

(1) Individual Tests

(2) Sampling Tests

(3) Reliability Assurance Tests

4.4.1 Individual Tests - Each equipment submitted for acceptance shall be subjected to the individual tests. These tests shall be adequate to determine compliance with the requirements of material, workmanship, operational adequacy and reliability. As a minimum, each equipment accepted shall have passed the following tests:

(1) Examination of Product

(2) Operational Test

(3) Manufacturing Run In Test

4.4.1.1 Examination of Product - Each equipment shall be examined carefully to determine that the material and workmanship requirements have been met.

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T05:09Z
Check the source to verify that this is the current version before use.

4.4.1.2 Operational Test - Each equipment shall be operated long enough to permit the equipment temperature to stabilize and to check sufficient characteristics and record adequate data to assure satisfactory equipment operation.

4.4.1.3 Manufacturing Run In Test - Each equipment shall be operated under the conditions specified herein for a period of 6 hours without failure. A failure shall be defined as anything which causes malfunctioning of the equipment. Only those adjustments will be permitted which can be made by using such controls and adjustments that are accessible to the operator during the normal use of the equipment.

Temperature	Ambient room
Humidity	Ambient room
Vibration	Any selected frequency within the range of 20 to 30 cps (excluding resonant points) and a minimum amplitude of ± 3 g's

The equipment shall be vibrated (without vibration isolators) for a period of 10 minutes prior to the beginning of the 6-hour period of operation. Where feasible, the equipment shall be operated during this vibration period for the purpose of detecting flaws and imperfect workmanship. Operation within the specified limits of satisfactory performance is not necessarily required during the vibration period. The direction of vibration should be vertical to the normal mounting plane for 5 minutes and lateral to the plane for 5 minutes. Where it is not feasible to vibrate the equipment in 2 directions the vertical direction shall be used. During the 6-hour period of operation following the 10-minute vibration period, the equipment shall be mechanically cycled periodically through its various phases of operation. Should a failure occur, it should be repaired and the test started over, except that the 10-minute vibration period need not be repeated when it is certain the failure was not a result of the vibration. Should repetitive failures occur, corrective action shall be taken to eliminate this defect from future equipment. A record shall be kept of all failures. The 6-hour period specified above may be composed of two 3-hour periods to conform with standard working hours.

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T05:09Z
Check the source to verify that this is the current version before use.

4.4.2 Sampling Tests - Equipments selected for sampling tests shall first have passed the individual tests. Equipments shall be selected for sampling tests by the government inspector in accordance with the following: (Sampling tests shall not be conducted unless Reliability Assurance Tests of 4.4.3 are deleted by contractual action.)

Quantity of Equipments Offered for Acceptance	Quantity to be Selected For Sampling Test
First 10	0*
Next 50	1
Next 75	1
Next 100	1
	1 for each additional 200 or fraction thereof

*NOTE: If by contract action the Initial Production Test (4.3) is deleted, then a Sample Test shall be conducted on one equipment from the first 10 produced.

4.4.2.1 Scope of Tests - As a minimum, each equipment selected for sampling tests shall be subjected to the following tests:

(1) Complete operational test at ambient room conditions, making all necessary measurements to assure that all applicable specification requirements have been met.

(2) Operational test at certain environmental conditions. The conditions may vary for each equipment tested and should be based on results of the preproduction, initial production, individual and special tests.

(3) Manufacturing run in test specified in paragraph 4.4.1.3 except that the test duration shall be 120 hours with no restriction on the number of failures. However, each failure shall be analyzed as to cause and remedial action necessary to reduce the possibility of its recurrence in future equipment.

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T05:09Z
Check the source to verify that this is the current version before use.

4.4.3 Reliability Assurance Tests - Reliability assurance tests shall be conducted as required by Specification MIL-R-23094. Equipments selected for reliability assurance tests shall first have passed the individual tests.

4.4.3.1 Reliability Procedure - For the Reliability Qualification Plan, as outlined in Specification MIL-R-23094, Procedure I shall be used. For the Reliability Sampling Plan Procedure II shall be used.

4.4.3.2 Test Level - The Test Level shall be III; Table 1 of MIL-R-23094, except--54 shall be changed to 0°C. Equipment shall operate at all times except for cooling cycle.

4.4.3.3 Accept-Reject Criteria - Figure 14 of Specification MIL-R-23094 shall be used to determine the accept-reject criteria for the Reliability Qualification Test Plan. Figure 14 of Specification MIL-R-23094 shall be used to determine the accept-reject criteria for the Reliability Sampling Test Plan.

4.4.3.4 Length of Heat Portion of Cycle - After stabilization at the high temperature limit required by the test level, the equipment shall be operated three (3) to six (6) hours during each cycle.

4.4.3.5 Performance Characteristics to be Measured - The performance characteristics to be measured shall be as specified in contract.

4.4.3.6 Failure Criteria - In addition to the requirements of Specification MIL-R-23094, the following requirements shall be used to determine when a failure has occurred during the test:

(1) Whenever performance characteristics fall below the Acceptance requirement (paragraph 4.4.3.5) at least one failure has occurred. If subsequent analysis reveals that several parts have deteriorated, each shall be counted a failure, unless one caused the other parts to fail.

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T05:09Z
Check the source to verify that this is the current version before use.

4.4.4 Special Tests - Special tests shall be conducted on a quantity of equipments for the purpose of checking the effect of any design or material change on the performance of the equipment and to assure adequate quality control. The equipment selected for special tests may be selected from equipments previously subjected to the sampling or reliability assurance tests.

4.4.4.1 Special Test Schedule - Selection of equipments for special tests shall be made as follows:

(1) On an early equipment after an engineering or material change.

(2) Whenever failure reports or other information indicate additional tests are required. (This will be determined by the procuring activity.)

4.4.4.2 Scope of Tests - Special tests shall consist of such tests as approved by the procuring activity. Test procedures previously approved for the preproduction tests shall be used where applicable. When not applicable, the contractor shall prepare a test procedure and submit it to the procuring activity for approval prior to conducting the tests.

4.4.5 Equipment Failure - Should a failure occur during either the sampling, reliability assurance or special tests, the following action shall be taken:

(1) Determine the cause of failure.

(2) Determine if the failure is an isolated case or design defect.

(3) Submit to the procuring activity for approval, proposed corrective action intended to reduce the possibility of the same failure(s) occuring in future tests.

(4) Where practical, include a test in the individual test to check all equipment for this requirement until reasonable assurance is obtained that the defect has been satisfactorily corrected.

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T05:09Z
Check the source to verify that this is the current version before use.

4.5 Test Procedures - The procedures used for conducting preproduction tests and acceptance tests shall be prepared by the contractor and submitted to the procuring activity for review and approval. The right is reserved by the procuring activity or the government inspector to modify the tests or require any additional tests deemed necessary to determine compliance with the requirements of this specification or the contract. Specification MIL-T-18303 shall be used as a guide for preparation of test procedures. When approved test procedures are available from previous contracts such procedures will be provided and may be used when their use is approved by the procuring activity. However, the right is reserved by the procuring activity to require modification of such procedures, including additional tests, when deemed necessary.

4.6 Reconditioning of Tested Equipment - Equipment which has been subjected to acceptance tests shall be reconditioned by the contractor by replacing all wear or damaged items. After reworking the contractor shall resubmit the equipment for acceptance.

4.7 Presubmission Testing - No item, part or complete equipment shall be submitted by the contractor until it has been previously tested and inspected by the contractor and found to comply, to the best of his knowledge and belief, with all applicable requirements.

4.8 Rejection and Retest - Equipment which has been rejected may be reworked or have parts replaced to correct the defects and resubmitted for acceptance. Before resubmitting, full particulars concerning previous rejection and the action taken to correct the defects found in the original shall be furnished the government inspector.

5. PREPARATION FOR DELIVERY

5.1 General - All major units and parts of the equipment shall be preserved, packaged, packed and marked for the level of shipment specified in the contract or order in accordance with Specification MIL-E-17555.

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T05:09Z
Check the source to verify that this is the current version before use.

6. NOTES

6.1 Intended Use - The equipment covered by this specification shall be for shop use for troubleshooting and evaluation of the capabilities of the Emergency Transmitter Beacon AN/PRT-5 and Power Supply.

6.2 Test Values - Normal and limiting values of performance data shall be determined at normal battery input voltages. These data are to be used in testing the equipment at installation points for compliance with minimum acceptable standard of performance.

6.3 Performance Objectives - Minimum size and weight, simplicity of operation, ease of maintenance, and an improvement in the performance and reliability of the specific functions beyond the requirements of this specification are objectives which shall be considered in the production of this equipment. Where it appears a substantial reduction in size and weight or improvement in simplicity of design, performance, ease of maintenance or reliability will result from the use of materials, parts and processes other than those specified in Specification MIL-E-5400, it is desired their use be investigated. When investigation shows advantages can be realized, a request for approval shall be submitted to the procuring activity for consideration. Each request shall be accompanied by complete supporting information.

6.4 As a general rule non-repairable subassemblies should be encapsulated or hermetically-sealed. The number of connections internal to the subassembly should be held to a minimum. Detail parts tolerances and ratings should be so selected that the life of the subassembly is greater than that of a similar repairable one. With few exceptions (such as high voltage power supplies), the non-repairable subassembly should evidence a Mean-time-to-failure greater than 5000 hours, and for many applications this figure must be nearer 50,000 hours.

6.5 Precedence of Documents - When the requirements of the contract, this specification, or applicable subsidiary specifications are in conflict, the following precedence shall apply:

(1) Contract - The contract shall have precedence over any specification.

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T05:09Z
Check the source to verify that this is the current version before use.

(2) This Specification - This specification shall have precedence over all applicable subsidiary specifications. Any deviation from this specification, or from subsidiary specifications where applicable, shall be specifically approved in writing by the procuring activity.

(3) Referenced Specifications - Any referenced specification shall have precedence over all applicable subsidiary specifications referenced therein. All referenced specifications shall apply to the extent specified.

6.6 The parentheses (*), when used in the type designation, will be deleted or replaced by either a number or letter furnished by the procuring activity upon application by the contractor for assignment of nomenclature in accordance with 3.2.7. The complete type number shall be used on nameplates, shipping records and instruction books, as applicable.

6.7 Ordering Data - Purchasers should exercise any desired options offered herein, and procurement documents should specify the following:

(1) Title, number, and date of this specification.

(2) Selection of applicable levels of packaging and packing (see 5.1).

(3) Data requirements (see 3.5)

6.8. Asterisk - In specification revisions and superseding amendments an asterisk "*" preceding a paragraph number denotes paragraphs in which changes have been made from the previous issue. This has been done as a convenience only and the government assumes no liability whatsoever for any inaccuracies in these notations. Bidders and contractors are cautioned to evaluate the requirements of this document based on the entire content as written, irrespective of the asterisk notations and relationship to the last previous issue.

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T05:09Z
Check the source to verify that this is the current version before use.

SPECIFICATION ANALYSIS SHEET

Form Approved
Budget Bureau No. 119-R004

INSTRUCTIONS

This sheet is to be filled out by personnel either Government or contractor, involved in the use of the specification in procurement of products for ultimate use by the Department of Defense. This sheet is provided for obtaining information on the use of this specification which will insure that suitable products can be procured with a minimum amount of delay and at the least cost. Comments and the return of this form will be appreciated. Fold on lines on reverse side, staple in corner, and send to preparing activity *(as indicated on reverse hereof)*.

SPECIFICATION

MIL-T-81291(WP) TEST SET, RADIO AN/PRM-30

ORGANIZATION *(Of submitter)*	CITY AND STATE

CONTRACT NO.	QUANTITY OF ITEMS PROCURED	DOLLAR AMOUNT
		$

MATERIAL PROCURED UNDER A

☐ DIRECT GOVERNMENT CONTRACT ☐ SUBCONTRACT

1. HAS ANY PART OF THE SPECIFICATION CREATED PROBLEMS OR REQUIRED INTERPRETATION IN PROCUREMENT USE?

A. GIVE PARAGRAPH NUMBER AND WORDING.

B. RECOMMENDATIONS FOR CORRECTING THE DEFICIENCIES.

2. COMMENTS ON ANY SPECIFICATION REQUIREMENT CONSIDERED TOO RIGID

3. IS THE SPECIFICATION RESTRICTIVE?

☐ YES ☐ NO IF "YES", IN WHAT WAY?

4. REMARKS *(Attach any pertinent data which may be of use in improving this specification. If there are additional papers, attach to form and place both in an envelope addressed to preparing activity)*

SUBMITTED BY *(Printed or typed name and activity)*	DATE

DD FORM 1 APR 63 1426

C-8279

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T05:09Z
Check the source to verify that this is the current version before use.