MILITARY SPECIFICATION

MINE, AT, PRACTICE, XM69
LOADING, ASSEMBLING AND PACKING

1. SCOPE

1.1 This specification covers loading, assembling and packing for one type of practice anti-tank mine designated as Mine, AT, Practice, XM69.

2. APPLICABLE DOCUMENTS

2.1 The following documents of the issue in effect on date of invitation for bids or request for proposals, form a part of this specification to the extent specified herein.

SPECIFICATIONS

MILITARY

MIL-A-2550 - Ammunition and Special Weapons; General Specification For.

STANDARDS

MILITARY

MIL-STD-105 - Sampling Procedures and Tables for Inspection by Attributes (ABC-STD-105)
MIL-STD-109 - Quality Assurance Terms and Definitions
MIL-STD-1168 - Lot Numbering of Ammunition
MIL-STD-1235 - Single and Multilevel Continuous Sampling Procedures and Tables for Inspection by Attributes

DRAWINGS

U.S. ARMY MUNITIONS COMMAND

9256479 - Mine, Anti-Tank, Practice: XM69
9244175 - Carton, Packing, Ammunition for Mine, Anti-Tank XM66 or Practice XM69
9244176 - Box, Packing, Ammunition for Mine, Anti-Tank, XM66 or Practice XM69.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T20:39Z
Check the source to verify that this is the current version before use.

PUBLICATIONS

U.S. ARMY MUNITIONS COMMAND

ET - 9256479

(Copies of specifications, standards, drawings and publications required by suppliers in connection with specific procurement functions should be obtained from the procuring activity or as directed by the contracting officer).

3. REQUIREMENTS

3.1 Materials and parts.-Materials and parts shall be in accordance with applicable drawings and specifications.

3.2 Mine.-The mine shall comply with all requirements specified on Drawing (dwg.) 9256479 and will all requirements specified in applicable specifications.

3.3 Functioning.-The rocket shall fire when activated by the fuze and shall hit a target 8 feet long by 6 feet high located 90 to 100 feet from the launcher when tested as specified in 4.4.1.

3.4 Continuity and resistance of rocket, fins and cable assembly, training (see dwg. 9247231 covering a detail of dwg. 9256479).-The resistance of the spool and firing cable assembly shall be one ohm, minimum (min.) to two and a half ohms, (max.) when tested as specified in 4.4.2.

3.5 Workmanship.-All parts and assemblies shall be fabricated and assembled in a thorough, workmanlike manner. They shall be free of burrs, sharp edges, cracks, chips, dirt, corrosion products and other foreign material. The cleaning method used shall not be injurious to any of the parts nor shall the parts be contaminated by the cleaning agent. Surface coatings shall be continuous except for a few light scratches not exposing base material. All required markings shall be neat and sharply defined.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T20:39Z
Check the source to verify that this is the current version before use.

3.6 First article inspection.-This specification makes provisions for first article inspection. Requirements for the submission of first article samples by the contractor shall be as specified in the contract.

4. QUALITY ASSURANCE PROVISIONS

4.1 Responsibility for inspection.-Unless otherwise specified in the contract or purchase order, the supplier is responsible for the performance of all inspection requirements as specified herein. Except as otherwise specified in the contract/order, the supplier may use his own or any other facilities suitable for the performance of the inspection requirements specified herein, unless disapproved by the Government. The Government reserves the right to perform any of the inspections set forth in the specification where such inspections are deemed necessary to assure supplies and services conform to prescribed requirements. Reference shall be made to MIL-STD-109 to define terms used herein. The provisions of MIL-A-2550 shall apply.

4.1.1 Submission of product.-At the time each completed lot of items deliverable under the contract is submitted to the Government for acceptance, the contractor shall supply the following information accompanied by a certificate which attests that the information provided is correct and applicable to the product being submitted:

a. A statement that the lot complies with all of the quality assurance provisions specified in this specification.
b. Drawing and specification number and date, together with identification and date of changes thereto.
c. A statement that all material purchased by the contractor meets requirements when such material is controlled by Government or commercial specifications referenced in any of the contractual documents, and that certificates of conformance are on file and available for review.
d. Number of items in the lot.
e. Date submitted.

The certificate shall be signed by a responsible agent of the certifying organization. The initial certificate submitted shall be substantiated by evidence of the agent's authority to bind his principal. Substantiation of the agent's authority will not be required with subsequent certificates unless, during the course of the contract, this authority is vested in another agent of the certifying organization.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T20:39Z
Check the source to verify that this is the current version before use.

4.2 First article inspection

4.2.1 Submission.-The contractor shall submit a sample of eighteen assemblies to the Government for testing in accordance with the provisions of 4.2.2. All parts and materials shall be the same as will be used in production and shall be obtained from the same source of supply. Prior to submission, the sample shall be inspected by the contractor to the degree necessary to assure that it conforms to the requirements of the contract.

4.2.2 Inspection to be performed.-Assemblies, sub-assemblies and components will be subjected by the Government to any or all of the examinations specified in 4.3.2 of this specification and any or all requirements of the applicable drawings. Eighteen complete mines shall be tested in the following manner:

a. Continuity and resistance.-Eighteen rocket fins, and cable assemblies shall be tested as specified in 4.4.2.

b. Functioning.-Eighteen mines shall be tested as specified in 4.4.1.

4.2.3 Rejection.-If any assembly fails to comply with the applicable requirements, the first article sample shall be rejected. In the event of rejection, the Government reserves the right to require the contractor to take corrective action and submit a new first article sample or portion thereof. Until a first article sample is accepted, the contractor is, in no way, authorized by the Government to initiate regular production unless otherwise directed by the Contracting Officer.

4.3 Inspection provisions

4.3.1 Lot formation.-The term "inspection lot" as used in this specification is defined as an essentially homogeneous collection of units of product from which a representative sample is drawn and inspected to determine conformance with applicable requirements. The sample selected shall represent only that quantity of units from which the sample was drawn and shall not be construed to represent any prior or subsequent quantities presented for inspection. Homogeneity shall be considered to exist provided the inspection lot has been produced by one manufacturer, in one unchanged process, using the same materials and methods in accordance with the same drawings, same drawing revisions, same specifications and same specification revisions and complies with the provisions for submission of product as

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T20:39Z
Check the source to verify that this is the current version before use.

specified in MIL-STD-105. Changes to the process, specification, or drawing not affecting interchangeability, or storage, as determined by the Government, shall not be deemed to alter the homogeneity of an inspection lot. All material submitted for inspection in accordance with this specification shall comply with the homogeneity criteria specified herein regardless of the type of sampling procedure which is being applied to determine conformance with requirements. Lot numbering, as required, shall be in accordance with MIL-STD-1168. Each inspection lot of mines shall contain:

a. Fuzes from not more than one lot from one manufacturer.
b. Rocket, fins and cable assemblies from not more than one lot from one manufacturer.

4.3.2 Examination.-The examinations listed in the following subparagraphs shall be performed on inspection lots (see 4.3.1) of the components or assemblies designated in the applicable paragraph headings. Inspection for critical defects (and major defects, when so specified) shall be 100 percent. Sampling plans for major and minor defects shall be in accordance with MIL-STD-105 except that continuous sampling plans in accordance with MIL-STD-1235 may be used if approved by the Government. Instead of applying the AQL's designated herein to the groups of major and minor defects listed, the contractor may elect to apply AQL's to individual defects using an AQL of 0.40 percent for each major defect and an AQL of 0.65 percent for each minor defect. When this method is elected, it shall be applied to all of the major and minor defects listed in the applicable sub-paragraphs of this section, except where 100 percent inspection is specified, and be documented as part of the contractor's inspection system. Equipment necessary for the performance of the inspections listed shall be in accordance with 4.3.4.

4.3.2.1 Rocket, fins and cable assembly training (see dwg. 9247231 covering a detail of 9256479).

Categories	Defects	Method of Inspection	Code No.
Critical:			
1.	Safety pin cover missing	Visual	01001
2.	Shorting cap removed or not fully engaged with connector	Visual	01002
Major:	AQL 0.40 percent		
101.	Shorting clip not removed	Visual	01003
102.	Components missing, damaged or insecure	Visual	01004

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T20:39Z
Check the source to verify that this is the current version before use.

Minor:	AQL 0.65 percent		
201.	Evidence of poor workmanship (see 3.5).....	Visual	01005

4.3.2.2 Carton, packing, ammunition for mine, anti-tank XM66 or practice, XM69, prior to sealing (see dwg. 9244175).

Categories	Defects	Method of Inspection	Code No.
Critical:	None defined.		
Major:	AQL 0.40 percent		
101.	Components missing, damaged or insecure.....	Visual-Manual	02001
Minor:	AQL 1.0 percent		
201.	Marking misleading or unidentifiable.....	Visual	02002
202.	Evidence of poor workmanship (see 3.5).....	Visual	02003

4.3.2.3 Carton, packing, ammunition for mine, anti-tank XM66 or practice, XM69, after sealing (see dwg. 9244175).

Categories	Defects	Method of Inspection	Code No.
Critical:	None defined.		
Major:	AQL 0.40 percent		
101.	Tape broken, missing or loose.....	Visual-Manual	03001
Minor:	AQL 0.65 percent		
201.	Evidence of poor workmanship (see 3.5).....	Visual	03002

4.3.2.4 Box, packing, ammunition for mine, anti-tank, XM66 or practice XM69 (see dwg. 9244176).

Categories	Defects	Method of Inspection	Code No.
Critical:	None defined.		

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T20:39Z
Check the source to verify that this is the current version before use.

Major:	AQL 0.65 percent		
101.	Strapping missing, broken or loose	Visual-Manual	04001
102.	Box damaged so that contents are exposed or liable to become exposed	Visual	04002
103.	Contents loose	Manual	04003
Minor:	AQL 0.65 percent		
201.	Marking misleading or unidentifiable	Visual	04004

4.3.3 Testing

4.3.3.1 Functioning (see 3.3).-Thirty two (32) mine systems shall be selected at random from each production lot for this test. Test items shall be observed for failure to comply with the applicable requirements as classified in Table I, when tested as specified in 4.4.1.

TABLE I

Defect	Classification	Code No.
Rocket misfire (see 6.4)	Major	05001
Rocket misses target	Major	05002

The lot shall be rejected if any of the following individual test results occur:

a. Two or more rockets misfire, OR
b. Three or more rockets miss the target, OR
c. A combined total of three or more defects listed in "a" or "b" above occur.

4.3.3.2 Continuity and resistance of rocket, fins and cable assembly training (see 3.4) - Major defect - Code No. 06001.-This test shall be performed one hundred percent. Any cable which fails to comply with the applicable requirement shall be classed defective. The test shall be performed as specified in 4.4.2 using equipment in accordance with 4.3.4.

4.3.4 Inspection equipment - Equipment Tabulation Number ET-9256479 identifies the inspection equipment required to perform the examinations and tests prescribed in this section. The contractor shall design inspection equipment in accordance with the instructions in paragraph 6.3.

4.3.4.1 Government rights to documentation.-Inspection equipment drawings and lists provided and revised in accordance with the requirements of the ET may be used by DOD activities for design, procurement, manufacture, testing,

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T20:39Z
Check the source to verify that this is the current version before use.

evaluation, production and receiving inspection, overhaul, shipping, storage, identification of stock, ordering and storage of replacement parts, inspection of items at overhaul, general maintenance of equipment, construction survey and whenever inspection equipment drawings are needed.

4.4 Test methods and procedures

4.4.1 Functioning.-The rocket shall be emplaced using dirt or sand filled ballast assembly bags to hold the launcher tube firmly on the ground. Care should be taken to insure that both forward and aft ends of the launcher tube are clear, and that the forward end of the tube is approximately nine (9) inches above ground level. The rocket shall be aimed at a point on the vertical centerline of the target plate, 39 inches above ground level. The mine system shall be functioned by actuation of the fuze, and observation shall be made to determine compliance with the applicable requirement.

4.4.2 Continuity and resistance of rocket, fins and cable assembly training.-The reading shall be taken at the shorting plug and terminals of the cable with the shorting plug removed. Observation shall be made to determine compliance with the applicable requirement. Test equipment shall be in accordance with 4.3.4.

5. PREPARATION FOR DELIVERY

5.1 Preservation and packaging

5.1.1 Level A.-The mines shall be preserved, packaged and marked in accordance with drawing 9244175.

5.2 Packing

5.2.1 Level A.-The packaged mines shall be packed and marked in accordance with drawing 9244176.

6. NOTES

6.1 Ordering data.-Procurement documents shall specify the following:

a. Title, number and date of this specification.
b. Data cards.-Data cards shall be prepared for each lot in accordance with the information specified in MIL-STD-1167.
c. Provisions for submission of first article samples.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T20:39Z
Check the source to verify that this is the current version before use.

6.2 Inspection code numbers.-The five digit code numbers assigned to the inspections herein are to facilitate future data collection and analysis by the Government. These code numbers are also used to correlate the characteristics cited on Equipment Lists with the inspections listed in this specification. In addition, they should be cited as references on drawings of equipment designs submitted by the contractor to the Government for approval (see 6.3.5).

6.3 Inspection equipment.-The contractor shall design inspection equipment as required by the inspection Equipment Lists (EL) referenced on the applicable ET in accordance with the instructions of paragraphs 6.3.1 through 6.3.5.

6.3.1 Inspection equipment lists (EL).-Inspection equipment lists indicate the availability of inspection equipment designs by showing in the "number" column of the list of inspection equipment (Form SMUPA 1010) the numbers of drawings or Federal Stock numbers of existing equipment designs, or codes as indicated in paragraph 6.3.2. Design action required of the contractor is described in paragraphs 6.3.3 and 6.3.4. The contractor will be required to prepare detailed drawings in accordance with 6.3.4 for all the equipment coded as "Contractor Design" in the number column. These contractor designs must be approved by the Government prior to fabrication or procuring of the equipment. Designs shall be submitted for approval as specified in 6.3.5.

6.3.2 Inspection equipment list codes.-The inspection equipment as defined in 6.3.3 and 6.3.4 will be designated in the EL by the following codes:

CD - Contractor design on controlled contractor format and/or commercial equipment
MU - Army design, mandatory for use.

6.3.3 Army designs.-Army designs are reflected on detailed drawings which completely depict all the information necessary for the fabrication of the item of inspection equipment. The contractor need provide no design when an Army design is listed for an item of inspection equipment. Army designs fall into two basic classifications; mandatory (designated "MU") and non-mandatory (indicated by drawing or Federal Stock Number). When an inspection equipment list references mandatory Army designs, the contractor shall comply with, and use these designs accordingly. The contractor may, however, in connection with non-mandatory designs, design alternate inspection equipment or use comparable commercial equipment to facilitate his operations. Such contractor prepared designs or commercial equipment selections must be approved by the Government prior to fabrication or procuring of the equipment. Designs shall be submitted for approval as specified in 6.3.5.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T20:39Z
Check the source to verify that this is the current version before use.

6.3.4 Contractor designs.-Contractor designs are designs of inspection equipment for which the Government has assigned design responsibility to the contractor. Contractor designs shall be supported by detailed drawings which depict all the information necessary to completely fabricate, calibrate and operate an item of inspection equipment. This requires that the necessary views, dimensions, materials, finishes, notes, operating and calibration instructions be properly depicted in accordance with approved practices to the extent that further calculation or clarification will not be required. Unless otherwise specified, contractor designs may be developed on the format the contractor normally employs in his equipment design procedure provided such format reflects the detail and information specified above, subject to the following controls: All submitted contractor designs shall conform to MIL-D-1000, Category A, Form 2. Legibility and reproducibility shall permit conventional making or clearly understandable, high contrast reproductions. Contractors shall submit three copies of final designs as a flat set. Designs shall be submitted for approval as specified in 6.3.5.

6.3.5 Submission of contractor designs.-All submitted designs shall contain a reference to the applicable five digit code number contained in Section 4 of this specification and the appropriate component or assembly drawing number and revision letter to which the specific design applies. Unless otherwise specified on the EL, all designs of equipment for inspection of approval to the Commanding Officer, Picatinny Arsenal, ATTN: SMUPA-ND15. All other designs of inspection equipment shall be approved by the inspection element of the agency administering the contract; submission shall be as directed by the contracting officer. Partial submission of inspection equipment designs is permissible and encouraged. However, the Arsenal completion date for design review will be based on the date of the final submission of designs. Picatinny Arsenal design review will be accomplished normally within one month after receipt.

6.4 Misfire.-A misfire, as used herein, shall be any malfunction in which the rocket motor fails to ignite.

Custodian:
Army-MU

Preparing activity:
Army-MU

Project Number: 1345-A-309

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T20:39Z
Check the source to verify that this is the current version before use.