MIL-S-48891 (AR)
7 July 1977
SUPERSEDING
See Section 6

MILITARY SPECIFICATION

SHIPPING AND STORAGE CONTAINER: XM542

This specification is approved for use by all Departments and Agencies of the Department of Defense.

1. SCOPE

1.1 This specification covers requirements, quality assurance provisions, and the preparation for delivery criteria for one type of container entitled, Shipping and Storage Container: XM542 which is used to transport a Sprint or Spartan warhead.

2. APPLICABLE DOCUMENTS

2.1 The following documents, of the issue in effect on date of invitation for bids or request for proposals, form a part of this specification to the extent specified herein:

SPECIFICATIONS

MILITARY

MIL-T-5021	- Tests, Aircraft Welding Operator's Certification
MIL-H-6815	- Heat Treatment of Steels (Aircraft Pratice) Process for.
MIL-I-6866	- Inspection, Penetrant Method of.
MIL-M-50508	- Mounts, Resilient.
MIL-A-45898	- Adapter Assembly, Forward.
MIL-A-50233	- Adapter Assembly, Aft.

STANDARD

MILITARY

MIL-STD-105	- Sampling Procedures and Tables for Inspection by Attributes.
MIL-STD-1168	- Lot Numbering of Ammunition.
MIL-STD-1261	- Welding Procedures for Constructional Steels.

Beneficial comments (recommendations, additions, deletions), and any pertinent data which may be of use in improving this document, should be addressed to: Commander, US Army Armament Research and Development Command, ATTN: DRDAR-QAN-Q, Dover, New Jersey 07801, by using the self-addressed Standardization Document Improvement Proposal (DD Form 1426), appearing at the end of this document, or by letter.

FSC NUOR

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T19:43Z
Check the source to verify that this is the current version before use.

DRAWINGS

8859012	- Finishing Requirements for Ferrous Metal Containers.
8889030	- Adapter Assembly Warhead Section H4251 (Aft).
9223028	- Bottom Shell Assembly.
9223037	- Top Shell Assembly.
9223082	- Cradle Assembly.
9223093	- Shipping and Storage Container: XM542.
9248934	- Bracket Mounting for Adapter H4252A.
9248936	- Adapter Assembly Warhead Section H4252A (Forward).
9248941	- Bottom Assembly.
9248942	- Top Assembly.
9272840	- Elastomeric, Shear Mount.
9274151	- Shipping and Storage Container XM452 With Adapter WHS H4251 and Adapter WHS 4252A.
EL-9223028	- Equipment List.
EL-9223037	- Equipment List.
EL-9223082	- Equipment List.
EL-9223093	- Equipment List.
EL-9248934	- Equipment List.
EL-9248941	- Equipment List.
EL-9252148	- Equipment List.
EL-9274151	- Equipment List.

(Copies of specifications, standards, drawings, and publications required by suppliers in connection with specific procurement functions should be obtained from the procuring activity or as directed by the contracting officer.)

3. REQUIREMENTS

3.1 Materials. The contractor shall furnish objective evidence (see 6.2) that the material complies with the specifications listed on the applicable drawing.

3.2 Assembly. The container shall comply with all requirements specified on the drawing (dwg) 9223093, with all requirements specified herein, and with the requirements of all applicable specifications to the extent specified on the drawing and herein.

3.3 First article testing. Requirements for the submission of first article samples by the contractor shall be as specified in the contract (see 4.2).

3.4 Serialization. The contractor shall assign serial numbers as required by drawings. The contractor may select any number which complies with the drawing requirement. These numbers shall not be duplicated.

3.5 Performance. The container and its cradle assembly shall support, without damage, and permit the installation and removal of a warhead section or an approved test load. The

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T19:43Z
Check the source to verify that this is the current version before use.

test load shall be identical to the warhead section in configuration, center of gravity (cg), weight and possess all features needed for mounting to cradle assembly, and pillow block. The outer surface (skin) of a warhead section or the test load shall not touch any bare metal of the Cradle Assembly. The Container shall be loaded in the manner described in 4.4.1.

3.6 Physical characteristics. The container shall withstand, without damage, the handling operations described below. Handling shall be performed as described in 4.4.2.

3.6.1 Fork lifting. The container shall be lifted off the ground 4 times and transported a minimum of 50 feet after each lifting operation.

3.6.2 Stacking. The container shall support a load equivalent in weight to two loaded containers for a minium of 15 minutes.

3.6.3 Hoisting. The container shall be hoisted off the floor twice: Once suspended from its 4 lifepoints and once from any of its 4 liftpoints for a total of 2 hoisting operations. The container shall remain suspended for a minimum of 2 minutes for each operation.

3.6.4 Shock. The container shall be positioned and dropped flat; on its 4 skids; cornerwise on its 2 end skids; and rolled 1 complete rotation.

3.6.5 Towing. The container shall be towed a minimum distance of 50 feet at a speed of 3.0 ± 1/2 miles per hour over a concrete surface.

3.6.6 Transportation vibration. The container shall be subjected to the vibratory parameters specified in Table I along its vertical axes when tested as specified in 4.4.2.6.

Table I

Vibration Schedule

Three Axis Testing

Frequency Hertz (Hz)	Amplitude	Bi-Directional Time (minutes)	Number of Sweeps
5.5-13-5.5	0.30" double amplitude (da)	7.7	2
13-17-13	1.5g	2.0	2
17-25-17	0.1" da	3.1	2
25-37-25	2.5g	3.1	2
37-25-37	0.036" da	2.6	2

Sweep Rate 0.15 Oct/Min.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T19:43Z
Check the source to verify that this is the current version before use.

3.7 Seal integrity. The sealed container with or without the load shall withstand an iternal pressure of 10 ± 1 pound per square inch gauge (psig) maintained for 60 minutes minimum (min). The leakage rate cannot exceed 0.01 psig/hr. Testing shall be as described in 4.4.3.

3.8 Units of Product. Listed units, assembled into the container shall have conformed with designated specifications. Objective quality evidence, substantiating conformance, shall be made available to the Government Representative before units are assembled into container or used in connection with the container.

Unit of Product	Drawing	Specification
Elastomeric-Shear Mount	9272840	MIL-M-50508
Adapter Assembly (Forward)	9248936	MIL-A-45898
Adapter Assembly (AFT)	8889030	MIL-A-50233

3.9 First article lot. The provisions for a first article lot are set forth in the contract. Units of product in such a lot shall be subjected to the quality conformance inspections specified in 4.2.

3.10 Welder. Only welder(s) certified as prescribed in MIL-T-5021 is (are) authorized to make weldments.

3.11 Weldments. Welding shall be in accordance with MIL-STD-1261, Class 2, (see 4.4.4).

3.12 Penetrant (Before protective finish is applied). Penetrant inspection shall be in accordance with MIL-I-6866, Method II (see 4.4.4).

3.13 Workmanship.

3.13.1 Plastic and metal characteristics. All components shall be free from cracks, splits, cold flow, shrinkage, cold shuts, inclusions, porosity, or any similar characteristic.

3.13.2 Threads. Threads shall be full and undamaged for the entire minimum length or depth as required on the applicable drawing.

3.13.3 Burrs. Parts shall be free from burrs.

3.13.4 Foreign matter. Parts shall be free from chips, dirt, grease, rust, corrosion, or any embedded foreign material.

3.13.5 Cleaning. The cleaning method shall not be injurious to any of the parts, nor shall the parts be contaminated by the cleaning agent.

4. QUALITY ASSURANCE PROVISIONS

4.1 Responsibility for inspection. Unless otherwise specified in the contract or purchase order, the supplier is responsible for the performance of all inspection requirements as specified herein. Except as otherwise speci-

Source: https://assist.dla.mil - Downloaded: 2026-10-22T19:43Z
Check the source to verify that this is the current version before use.

fied in the contract or order, the supplier may use his own or any other facilities suitable for the performance of the inspection requirements specified herein, unless disapproved by the Government. The Government reserves the right to perform any of the inspections set forth in the specification where such inspections are deemed necessary to assure supplies and services conform to prescribed requirements.

4.2 First article inspection.

4.2.1 Quantity to be submitted. When the contract requires first article inspection, the contractor shall submit 1 complete assembly (see dwg 9223093) for first article testing to the testing facility designated in the invitation for bids or request for proposal.

4.2.2 Inspection and testing to be performed. The first article inspection sample shall be subjected to the inspections and tests specified in Table II. Tests shall be conducted in order specified in Table II.

Table II

First article inspection and tests

Inspection or Test	Dest	Non Dest
1. Classification of Characteristics/ Defects (see 4.3.2.1)		X
2. Performance (see 3.5)		X
3. Physical characteristics (see 3.6)		X
4. Weldments (see 3.11)		X
5. Penetrant (see 3.12)		X
6. Seal Integrity (see 3.7)		X

4.2.3 Inspection equipment. The inspection and testing specified in 4.2.2 shall be accomplished by using the gages and test equipment specified in 4.3.4.1.

4.2.4 Rejection. If any item fails to comply with any of the applicable requirements, the first article sample shall be rejected.

4.3 Quality conformance inspection.

4.3.1 Lot formation.

4.3.1.1 Production lot. A lot shall consist of parts and assemblies produced by one manufacturer in one unchanged process, in accordance with the same drawing, same drawing revision, same specification and same specification revision. Drawing, specification and process changes not affecting safety, performance, storage, or interchangeability, as determined by the Government, shall not necessitate changing the lot interfix number. The criteria and procedures for the assignment of lot numbers shall be in accordance with MIL-STD-1168.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T19:43Z
Check the source to verify that this is the current version before use.

4.3.1.2 Inspection lot. A lot or batch and its formation, size, and presentation is described in MIL-STD-105, Section 5. Accordingly, a lot shall mean an inspection lot and a batch shall mean an inspection batch for the purpose of this specification. The manner in which each inspection lot or batch is to be presented and identified by the contractor, shall be designated or approved by the Government representative.

4.3.2 Product inspection examination. A sample shall be selected at random from each inspection lot in accordance with the applicable major or minor defects/characteristics table (see Table III and Table IV), and inspected for all defects/characteristics in the applicable classification. Any defects/characteristics in the sample found to be defective shall reject the inspection lot. Sequence for the inspection of defects/characteristics in each classification need not be followed as long as all defects/characteristics inspections are performed.

Table III
Major Defects/Characteristics

Lot Size	Sample Size	Lot Size	Sample Size	Lot Size	Sample Size	Lot Size	Sample Size
1-16	all	28-29	23	52-56	31	132-156	39
17	16	30-31	24	57-62	32	157-191	40
18	17	32-34	25	63-69	33	192-244	41
19-20	18	35-36	26	70-76	34	245-334	42
21	19	37-40	27	77-86	35	335-519	43
22-23	20	41-43	28	87-97	36	520-1120	44
24-25	21	44-47	29	98-112	37	over 1120	45
26-27	22	48-51	30	113-131	38		

Table IV
Minor Defects/Characteristics

Lot Size	Sample Size	Lot Size	Sample Size	Lot Size	Sample Size	Lot Size	Sample Size
1-9	all	14-16	12	28-33	16	77-121	20
10	9	17-18	13	34-41	17	122-273	21
11	10	19-22	14	42-54	18	over 273	22
12-13	11	23-27	15	55-76	19		

Source: https://assist.dla.mil - Downloaded: 2026-10-22T19:43Z
Check the source to verify that this is the current version before use.

4.3.2.1 Classification of defects/characteristics (see 3.2). Critical, major and minor defects/characteristics are defined in MIL-STD-105. Inspection shall be conducted as follows:

4.3.2.1.1 Mount, elastomeric shear (see dwg 9272840).

Categories	Defects/Characteristics	Method of Inspection
Critical:	None defined.	
Major:		
	101. Objective quality evidence that mounts conform to specification missing, improper or incomplete (see note on dwg)	Visual
	102. Marking missing, improper, misplaced or illegible (see note on dwg)	Visual
	103. Mount damaged (VIZ: crack, split, gouge, rupture, etc)	Visual
	104. Mount older than 18 months (see note on dwg)	Visual
Minor:	None defined.	

4.3.2.1.2 Ground cable assembly (see dwg 9252148).

Categories	Defects/Characteristics	Method of Inspection
Critical:	None defined.	
Major:		
	101. Pin not peened over (see note on dwg) (2 places)	Visual
	102. Wire braid damaged	Visual
	103. Cable overall length less than 25 inches	Gage
	104. Failure of connector (2) to mate with corresponding member	Gage
	105. Objective evidence relative to material missing or improper (see 3.1)	Visual
Minor:		
	201. Marking missing, improper, misplaced or illegible	Visual
	202. Evidence of poor workmanship (see 3.13)	Visual

Source: https://assist.dla.mil - Downloaded: 2026-10-22T19:43Z
Check the source to verify that this is the current version before use.

4.3.2.1.3 Cradle assembly (see dwg 9223082).

Categories	Defects/Characteristics	Method of Inspection
Critical:	None defined.	
Major:		
101.	Components, missing, improper, loose, damaged or improperly assembled, installed	Manual/Visual
102.	Incorrect length between pillow blocks	Gage
103.	Incorrect dimensions of cradle assembly (length & width)	Gage
104.	Distance between locating pins	Gage
105.	Objective evidence relative to material missing or improper (see 3.1)	Visual
Minor:		
201.	Evidence of poor workmanship (see 3.13)	Visual

4.3.2.1.4 Top shell assembly (see dwg 9223037).

Categories	Defects/Characteristics	Method of Inspection
Critical:	None defined.	
Major:		
101.	Components improperly assembled, installed, or missing, damaged loose, improper, misplaced	Manual/Visual
102.	Improper cleaning and finishing (see note on dwg)	Visual
103.	Weld or weld spatter on surface described by note on dwg	Visual
104.	Incorrect distance between opposite holes (10 places) on flange, top, sides	Gage
105.	Incorrect distance between opposite holes (2 places) on flange, top, ends	Gage
106.	Incorrect distance between small hole on flange, top, end to hole flange, top, side	Gage
107.	Incorrect distance between small hole on flange top side to hole on flange, top, end (2 places)	Gage

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T19:43Z
Check the source to verify that this is the current version before use.

Major: (Cont)

108. Incorrect distance between tiering brackets (2 places).....Gage
109. Evidence of finish on surface described by note on dwg.....Visual
110. Incorrect placements of tiering bracket (4).....Gage
111. Certification of welder not in compliance with MIL-T-5021.....Visual

Minor:
201. Evidence of poor workmanship (see 3.13).....Visual

4.3.2.1.5 Bracket, mounting for adapter H4252A (see dwg 9248934).

Categories	Defects/Characteristics	Method of Inspection

Critical: None defined.

Major:
101. Location slots (2 slots) incorrect.....Gage
102. Width slots (2 slots) incorrect.....Gage
103. Location of thru holes (2 holes) incorrect.....Gage
104. Diameter hole (0.422) incorrect.....Gage
105. Diameter hole (0.563) incorrect.....Gage
106. Base perpendicular to Datum A within 0.005 (right bracket only dwg 9248934-1).....Gage
107. Base perpendicular to Datum B within 0.005 (left bracket only 9248934-2).....Gage
108. Thickness vertical section incorrect.....Gage
109. Thickness base (0.375) incorrect.....Gage
110. Protective finish incomplete.....Visual
111. Objective evidence relative to material missing or improper (see 3.1).....Visual

Minor:
201. Evidence of poor workmanship (see 3.13).....Visual

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T19:43Z
Check the source to verify that this is the current version before use.

4.3.2.1.6 Bottom shell assembly (see dwg 9223028).

Categories	Defects/Characteristics	Method of Inspection
Critical:	None defined.	
Major:		
101.	Components improperly assembled, installed, or missing, damaged, loose, improper, misplaced	Manual/Visual
102.	Improper finishing and cleaning (see note)	Visual
103.	Surface described on dwg not free from protective finish	Visual
104.	Weld or weld spatter on surface described by note	Visual
105.	Incorrect distance between holes at shear mount plates (2 places)	Gage
106.	Incorrect distance between hole in flange to hole in shear mount plate (2 places)	Gage
107.	Incorrect distance between opposite shear mount plate surfaces (2 places)	Gage
108.	Incorrect distance between opposite holes on bottom, side flanges (10 places)	Gage
109.	Incorrect distance between opposite holes on bottom end flanges (2 places)	Gage
110.	Incorrect distance (vertical) between pin on bottom end flange to hole on bottom side flange	Gage
111.	Incorrect distance (horizontal) between pin on bottom end flange to hole on bottom side flange	Gage
112.	Objective evidence relative to material missing or improper (see 3.1)	Visual
Minor:		
201.	Evidence of poor workmanship (see 3.13)	Visual

Source: https://assist.dla.mil Downloaded: 2026-10-22T19:43Z
Check the source to verify that this is the current version before use.

4.3.2.1.7 Top assembly (see 9248942).

Categories	Defects/Characteristics	Method of Inspection
Critical:	None defined.	
Major:		
101.	Components missing, loose, damaged, improper or misplaced	Manual/Visual
102.	Handlifts (4) improperly installed	Visual
103.	Humidity indicators improperly installed, assembled, or loose, damaged, improper, missing, misplaced	Manual/Visual
104.	Objective evidence relative to material missing or improper (see 3.1)	Visual
Minor:		
201.	Top assembly improperly painted (all over)	Visual
202.	Stenciling misplaced, misspelled or omitted	Visual
203.	Evidence of poor workmanship (see 3.13)	Visual

4.3.2.1.8 Bottom assembly (see dwg 9248941).

Categories	Defects/Characteristics	Method of Inspection
Critical:	None defined.	
Major:		
101.	Pressure relief valve (2) improperly installed, assembled, or loose, damaged, improper, missing, misplaced	Manual/Visual
102.	Record holder improperly installed, assembled, or loose, damaged, missing, misplaced	Manual/Visual
103.	Desiccant basket, improperly installed, assembled, or loose, damaged, improper, missing, misplaced	Manual/Visual
104.	Skid (4) loose, splintered, split or improperly installed, misplaced	Manual/Visual

Source: https://assist.dla.mil Downloaded: 2026-10-22T19:43Z
Check the source to verify that this is the current version before use.

Major: (Cont)

105. Towpoint (4) missing, or loose.....Manual/Visual
106. Shell damaged (VIZ: Dent, scratch, gouge, etc).....Visual
107. Components improperly installed, assembled or missing, damaged, improper, loose, misplaced.....Manual/Visual
108. Identification plate, missing, damaged, loose, improper or misplaced.....Manual/Visual
109. Shear mount (4) improperly installed, assembled, or loose, missing, damaged or improper.....Manual/Visual
110. Insufficient torque applied to screw (20) attaching shear mount to cradle assembly.....Gage
111. Objective evidence relative to material missing or improper (see 3.1).....Visual

Minor:

201. Protective finish damaged exposing base metal (all over).....Visual
202. Marking missing, improper, illegible, or misplaced.....Visual
203. Holes to accomodate seal misplaced.....Manual/Visual
204. Evidence of poor workmanship (see 3.13).....Visual

4.3.2.1.9 Shipping and Storage Container XM542 with Adapter Warhead Section H4251 and Adapter Warhead Section H4252A (see dwg 9274151) (Note this station is applicable only if dwg 9274151 is part of the pack).

Categories	Defects/Characteristics	Method of Inspection
Critical:	None defined.	
Major:		
	101. Objective evidence that H4251 and H4252A comply with their respective specifications	Visual
	102. H4251 and H4252A secured improperly (see Notes 1 and 2 on dwg)	Visual
	103. Cap screws securing adapter mounting brackets torqued improperly	Gage

Source: https://assist.dla.mil Downloaded: 2026-10-22T19:43Z
Check the source to verify that this is the current version before use.

Major: (Cont)

104. Cap screw securing pillow block clamp, torqued improperly.....Gage
105. Evidence of poor workmanship (see 3.13).....Visual

Minor: None Defined.

4.3.3 Testing. All tests shall be performed. Tests shall be performed in the order specified below:

Test	Test Classification
a. Performance	Major
b. Weldments	Major
c. Penetrant	Major
d. Seal integrity	Major

None of these tests are considered destructive and samples so tested may be returned to the lot.

4.3.3.1 Performance, weldments and seal integrity. All containers in the Inspection Lot shall be tested in accordance with 4.4.1 and 4.4.3. If any item fails to comply with 3.5, 3.11 and 3.7, the item shall be rejected and removed from the lot.

4.3.3.2 Penetrant. For this test a lot shall be divided into sub lots. A sub lot shall consist of 10 containers or less. One container shall be randomly selected from each sub lot and tested in accordance with 4.4.4. If any item fails to comply with 3.12, the lot from which the sample was selected shall be rejected.

4.3.4 Acceptance inspection equipment.

4.3.4.1 Major defects/characteristics and tests. Inspection and testing shall be performed with the acceptance inspection equipment, operating instructions, and calibration instructions specified on the Equipment Lists (EL) (see EL-listed in 2.1). When either of the conditions listed below exist, the contractor shall design require equipment or specify suitable commercial equipment and obtain approval prior to use on the contract.

a. Any deviation from equipment or procedures specified on the EL is desired (see 6.3).
b. The code "CD" is listed in the "Part or Identifying Number" column on the EL (see 6.1.2).

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T19:43Z
Check the source to verify that this is the current version before use.

4.3.4.2 Minor defects/characteristics and tests. Acceptance inspection equipment for minor defects/characteristics is not specified on ELs. The acceptance inspection equipment, operating instructions and calibration instructions used by the contractor for minor classification inspection shall be approved by the Government representative authorized by the procuring agency.

4.4 Test methods. The tolerances specified herein are absolute with no allowance for test equipment inaccuracy. The tolerances used by the manufacturer shall be equal to the absolute tolerances less the accuracy tolerances of the test equipment used.

4.4.1 Performance. The warhead section or approved test load with Aft Adapter Dwg 8889030 and Forward Adapter Dwg 9248936 attached by mounting screws sufficiently torqued, shall be lowered onto the cradle assembly of the container. The Aft ring shall be attached to the pillow blocks with 4 screws and two clamps, and the Forward Ring shall be attached to the cradle assembly with 4 screws. The mounting screws shall be torqued as specified in Dwg 9274151. The outer surface of the warhead section or test load shall not touch any bare metal of the cradle assembly. The top assembly of the container, properly oriented shall be lowered onto the bottom assembly of the container. After insuring that the top and bottom assembly and the gasket are interfacing properly, insert 32 screws, MS90726-60, into the holes provided. Turn screws by hand engaging only 2 or three threads. The Warhead section or approved load may be removed before screws are inserted and torqued as specified on dwg 9223093 before conducting the seal test, conforming to the requirements in 3.7.

4.4.2 Physical testing. The loading and sealed container shall be tested at ambient temperature as described below. Before and after testing, the container shall be tested and conform to the requirements in 3.7.

4.4.2.1 Fork lifting. The container shall be lifted off the floor from its 8 fork lift channels, 2 on one side; 2 on the other side; 2 on one end; and 2 on the other end. Each lift operation shall be repeated 1 time and transported 50 feet min each time.

4.4.2.2 Stacking. A load equal to two times the gross (loaded) weight of the container shall be applied to the top of the container in a manner simulating the effect of a similar container being stacked on the container supporting the load.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T19:43Z
Check the source to verify that this is the current version before use.

4.4.2.3 Hoisting. The container shall be hoisted off the ground by applying a steady and gradual lifting force without interruption. Hoisting operations shall be accomplished in the order listed.

a. Hoist container from designated lift point (4) and keep suspended off the ground for a minimum of 2 minutes.

b. Hoist container from one of its designated lift points. Keep suspended off the ground for a minimum of 2 minutes.

4.4.2.4 Dropping. The container shall be positioned and allowed to be dropped as described below:

a. Flat drop. The container, from its 4 designated lift points, shall be raised off the floor a height of 12 + 0.5 inches. Then release the container so that its 4 skids simultaneously land onto a concrete or equally hard flat surface.

b. Corner wise drop. The container shall be supported at one corner of its base on a block 5 + 0.5 inches high. A block 12 + 0.5 inches high shall be placed under the opposite corner of the same end. The opposite end of the container shall be raised a height of 24 + 0.5 inches. Release so that one skid is allowed to fall freely onto a concrete or equally hard-flat surface- then the other skid. Reverse the procedure so that the diagonally opposite end skid receives the 24 inches high drop.

c. Roll-over. The container, standing on its 4 skids on a concrete or equally hard-flat surface, shall be tipped slowly, sidewise up to a point when it will fall freely by its own weight. The container when tipped in the following sequence, shall constitute 1 complete revolution.

(1) From standing position to side.
(2) From side to top.
(3) From top to other side.
(4) From other side to standing on its skids.

4.4.2.5 Towing. The container, standing on its 4 skids, and with cables attached to the front 2 tow holes shall be towed for a minimum distance of 50 feet at approximately 3 miles per hour over a concrete or equally hard surface. Repeat by towing from the rear 2 tow holes. The tow cable shall be attached so that the container will not swerve from side to side while being towed.

4.4.2.6 Transportation vibration. The container, mounted onto a fixture capable of being orientated to vibrate the container on its vertical axis, shall be secured to an approved vibration device and tested to the requirements of 3.6.

Source: https://assist.dla.mil - Downloaded: 2026-10-22T19:43Z
Check the source to verify that this is the current version before use.

4.4.3 Seal integrity. The container shall be pressurized through the pressure relief port to a pressure of 10 ± 1.0 pounds per square inch gage (psig) with a gas that is non-corrosive to metallic, and non-metallic material. The specified pressure shall be maintained for 60 minutes minimum. After the 60 minutes have elapsed, the pressure drop in the manometer column shall not be greater than 0.01 psig. An approved "U" shaped tube manometer with increments graduated to allow visual detection in pressure drop, and filled with merian No. 3 oil shall be used for test. After testing, the pressure shall be released and the container shall be examined for damage (see 6.2). Release the pressure and reassemble and properly torque the pressure relief valve. Other test methods, or equal to or superior in sensitivity to the test described may be used, after approval is granted by the procuring activity (see 6.3) ATTN: DRDAR-QAN-I.

4.4.4 Weldments. Acceptability criteria for weldments are specified in MIL-W-8611, using the penetrant inspection method. Penetrant inspection shall be in accordance with Specification MIL-I-6866, Type II, Method. However, discontinuities if any, cannot be removed, unless removal method is approved by the procuring activity (see 6.3), ATTN: SARPA-QA-T.

5. PREPARATION FOR DELIVERY

5.1 Preservation and packaging. The container and its components shall be secured to prevent damage during its transportation.

5.2. Marking. Marking for delivery shall be on a label secured to the container. No shipping information is to be stenciled on exterior surface of the container.

6. NOTES

6.1 Ordering data. Procurement document shall specify:

(a) Title, number and date of this specification (see page 1).
(b) Test load or warhead section (see 3.5).
(c) First Article Lot (see 3.9).

6.2 Objective evidence. Records of contractor quality control and inspections which can be verified.

6.3 Acceptance inspection equipment (see 4.3.4.1). The contractor shall obtain approval from the Commander, US Army Armament Research and Development Command, ATTN: DRDAR-QAN-I, Dover, New Jersey 07801.

Source: https://assist.dla.mil Downloaded: 2026-10-22T19:43Z
Check the source to verify that this is the current version before use.

6.4 Damage. A defect that is detected by visual examination and listed under the following categories:

(1) Internal. VIZ: Illegible marking; damage in finish exposing base metal; loose component; broken or permanently set structural member; distorted, split, crack in shear mount; or separation of shear mount from mounting plate.

(2) External VIZ: Illegible marking, damage in finish, exposing base metal; loose component; broken or permanently set structural member; broken or crack in skin (4); puncture in shell or separation of weldment; crack; tear; damage in gasket. Damaged surface of warhead section or test load.

6.5 Supersession data. This specification supersedes the requirements of Purchase Description PA-PD-2236 dated 30 May 1972 and SCN 1, 2 and 3.

Custodian:
Army - (AR)

Preparing activity:
Army - (AR)

Project No. NUOR-A064

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T19:43Z
Check the source to verify that this is the current version before use.