MILITARY SPECIFICATION
TOWER AB-585( )/G

This amendment forms a part of MIL-T-55441(EL) 29 August 1967 and is approved for use by all Departments and Agencies of the Department of Defense.

Page 1

2.1 Add to Federal Specifications:

"NN-P-71	Pallet, Materials-handling, Wood (General Construction Requirements)
GGG-B-101	Bars: Chisel, Pinch, Pry, Wrecking, Digging, Tamping, Digging and Tamping; and Crowbars.
PPP-B-585	Box, Wood, Wirebound
PPP-B-591	Box, Fiberboard, Wood-cleated
PPP-B-601	Box, Wood, Cleated Plywood
PPP-B-621	Box, Wood, Nailed and Lock-Corner"
PPP-B-640	Boxes, Fiberboard, Corrugated, Triple-Wall

Delete"GGG-H-86 Hammer, Hand (Forged Steel Head)"

Replace "QQ-A-200/3" and "2024" with "QQ-A-200/2" and "2014", respectively.

Page 2

Change title of Military Specification MIL-E-17555 to:

"Electronic and Electrical Equipment, Accessories and Associated Repair Parts, Packaging and Packing of"

Add to Military Standards:

MIL-STD-147	Palletized and Containerized Unit Loads 40 inch X 48 inch Pallets, Skids, Runners, or Pallet Type Base

Page 3

Add drawing "SC-C-539505 Hammer" to drawing list.

Replace "SM-C-423628 Guy Bag" with "ES-D-212223 Accessories, Bag"

Page 4

Insert:

"3.3.3 Other Materials.- Only fungus inert and fungus resistant materials will be used. These materials shall be in accordance with requirement 4 of MIL-STD-454. When materials are treated for fungus resistance, treatment shall be in accordance with MIL-P-11268.

FSC 5445

Source: https://assist.dla.mil -- Downloaded: 202610-22T23:22Z
Check the source to verify that this is the currentversion before use.

3.3.3.1 Statement of treatment.- The statement of treatment shall indicate whether or not nutrient materials have been employed. If nutrient materials have been used, it shall also describe in detail the materials to be treated and the treating compounds and processes that the contractor proposed to use. (See 6.2)

3.4 Finish, protective: Insert the following between the second and third sentences: "The male connecting surfaces (studs) of the tower sections shall not be finished. These surfaces shall be masked to insure proper fit and unimpaired electrical contact."

3.6 Tower section (9 foot).- Add to the end of the paragraph:

"Constraints shall be provided to insure that the 3 panels fold and unfold in only one way so that the section can not be improperly assembled."

3.6.1 Three-panel assembly.- Add to end of first sentence:

"..with exception to obtain requirement cited in 3.6".

Page 5

3.6.2 Platform.- Change title to:

"3.6.2 Platform assembly.-"

3.6.3 Ladder.- Change title to:

"3.6.3 Ladder assembly.-"

3.6.5 Section pin clamp.- Change title to "3.6.5 Section interlocking clip." In first sentence replace "spring lock pins" with "interlocking clips." In second sentence replace "pin clamp" with "clips". In third sentence replace "pin clamps" with "clip pins".

Page 6

3.9 Base assembly.- Replace with:

"3.9 Base assembly.- The base assembly shall be composed of four adjustable base leg assemblies and a base frame".

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T23:22Z
Check the source to verify that this is the current version before use.

3.9.1 Replace with:

"3.9.1 Base leg assemblies shall conform to the model except that the bearings shall be corrosion resistant steel instead of carbon steel (see 3.3.2). The leg screws shall be aluminum alloy 2014-T6 conforming to QQ-A-200/2. The adjustable leg assembly shall function with an angularity of up to ± 5 degrees from level."

3.10.2 In last sentence delete "assembly".

3.10.3 Delete.

Page 7

3.12 Change "members" to "braces" in three places.

Page 8

3.13.1 Hauling rope.- Replace title with:

"3.13.1 Davit hauling line."

Change "250 feet" to "300 feet"

Add the following to the end of the paragraph:

"A Wilcox-Crittenden Figure 2311 No. 2, or equal safety snap hook and thimble shall be eye spliced to one end of the line. The other end of the line shall be fused to prevent raveling."

3.13.2 Davit guide clamp.- Replace lines 1, 2 and 3 with:

"3.13.2 Davit attachment assembly.- The davit attachment assembly shall include two davit retaining couplers for mounting and moving the davit along the vertical leg of the tower. The davit attachment assembly shall conform to the model except as follows:"

3.13.2(c) Change "davit hauling rope" to "davit hoisting line".

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T23:22Z
Check the source to verify that this is the current version before use.

Page 9

3.14.3 Guy tensioning device.- Add the following to the end of the first sentence: "except that all parts made of carbon steel shall be replaced with corrosion resistant steel parts (see 3.3.2). This includes but is not limited to the adjusting screw, jaws, and locking handle. In addition, the webbing strap and buckle used to secure the guy when not in use shall be replaced by a corrosion resistant steel chain and hook."

3.14.3.1 Change "tool" to "wrench" in three places.

Page 11

3.15.3 Digging bar.- Replace the first sentence with the following: "The digging bar shall be Type VII, Earth-Digging Bar, Size Number 3 in accordance with GGG-B-101."

3.16 Transit mounting.- Replace with:

"3.16 Transit mounting.- Twelve each two inch wide by six feet long webbing straps with approved military type buckles and tips shall be provided with each tower for mounting Tower AB-585( )/G in Truck, Cargo, 2 1/2 Ton, 6 x 6, M35. Eight each two inch wide by one foot long straps with buckles and tips shall be provided with each tower to bundle the anchors during transit. One bag per tower shall be provided to contain sixteen stakes GP-2. The bag shall be fabricated from cotton duck and include all necessary straps and buckles."

3.18 Tag line.- Replace with:

"3.18 Tag line.- The tag line shall be 175 feet long. Material shall be as specified for the davit hauling line, 3.13.1. Both ends shall be fused to prevent raveling."

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T23:22Z
Check the source to verify that this is the current version before use.

3.19 Anchor location rope.- Replace with:

"3.19 Anchor location rope.- The anchor location rope shall be 80 feet long overall after fabrication. Material shall be as specified for the sling, paragraph 3.13.3. A three inch diameter eye shall be formed in each end of the rope using a metal sleeve (Nicropress or equal). A metal sleeve shall be attached as a marker in the center of the rope."

3.20 Hammer: - Change "6 pound" to "8 pound" and replace "Federal Specification GGG-H-86" with "SC-C-539505".

3.21 Miscellaneous equipment carrier.- Change title to "Accessories bag" and change "SM-C-423628" to "ES-D-212223".

3.22 Tower grounding.- Replace with:

"3.22 Tower grounding.- Tower grounding connections as on the model shall be deleted except for the base section connection for the ground rod cable. One 5/8 inch diameter by 8-foot long ground rod with cable and hardware conforming to the model shall be furnished. The lug on the tower end of the ground cable and the fasteners and washers for attaching the ground cable to the tower shall be corrosion resistant steel. Wing nuts shall be made captive to prevent loss."

Page 12

3.25.1 Davit loading: Change "750 pounds" to "700 pounds".

3.28 Preproduction sample.- Replace with:

"3.28 First article.- When specified in the contract or purchase order, the contractor shall furnish first article units in accordance with 4.3."

Page 13

4.1 Responsibility for inspection.- Replace with:

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T23:22Z
Check the source to verify that this is the current version before use.

"4.1 Responsibility for inspection.- Unless otherwise specified in the contract or purchase order, the contractor is responsible for the performance of all inspection requirements as specified herein. Except as otherwise specified in the contract or purchase order, the contractor may use his own or any other facilities suitable for the performance of the inspection requirements specified herein, unless disapproved by the Government. The Government reserves the right to perform any of the inspections set forth in the specification where such inspections are deemed necessary to assure supplies and services conform to prescribed requirements."

4.2(a) Change "Preproduction" for "First article".

Page 14

4.3 Preproduction inspection.- Replace with:

"4.3 First article.- Unless otherwise specified in the contract or purchase order, the first article inspection shall be performed by the contractor.

4.3.1 First article units.- The contractor shall furnish one (1) first article unit of the complete AB-585( )/G.

4.3.2 First article inspection.- The first article inspection shall consist of the inspections specified in subsidiary documents covering the items listed in 4.4 and the inspections specified for Group A, Group B and Group C (see Table II, III, and IIIA respectively). The inspection shall be performed in the following order: 4.4, Group A and Group B for all units; and designated units for specific subgroup within Group C in accordance with 4.5.3.1.

4.3.3 First article data.- The first article test plan and test report(s) shall be as required in the purchase order or contract."

4.4 Inspection covered by subsidiary documents.- Replace with:

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T23:22Z
Check the source to verify that this is the current version before use.

"4.4 Inspections covered by subsidiary documents.- The following shall be inspected under the applicable subsidiary documents as part of the inspection required by this specification, and the inspection requirements specified in the contract or purchase order.

Finish	3.4
Marking	3.5"

Delete Table I in its entirety.

4.5 Quality conformance inspection of equipment before preparation for delivery.- In first sentence change "4.5.1 and 4.5.2" to "4.5.1 through 4.5.4". Delete last three sentences.

4.5.1 Group A inspection.- Replace with:

"4.5.1 Group A inspection.- Each unit on contract or purchase order shall be inspected for conformance to the inspections specified in Table II. Discrete lots shall be formed for units that pass this inspection. Factors of lot composition not defined herein, or in the contract or purchase order, shall be in accordance with MIL-STD-105. Each lot shall be subject to sampling inspection, utilizing the procedures of MIL-STD-105, using the general inspection levels, and AQL's indicated in Table II.

4.5.1.1 Order on inspection within Group A.- Group A inspection shall be performed in an order satisfactory to the Government."

4.5.2 Group B inspections.- Replace with:

"4.5.2 Group B inspection.- Group B inspection shall normally be performed in inspection lots that have passed Group A inspection and on samples selected from units that have been subjected to and met the Group A inspection. This inspection shall conform to Table III and to the special inspection levels of Table I of MIL-STD-105."

Source: https://assist.dla.mil -- Downloaded: 202610-22T23:22Z
Check the source to verify that this is the current version before use.

4.5.3 Reinspection of conforming Group B sample units.- Replace with:

"4.5.3 Group C inspection.- Group C inspection shall be performed on units that have passed Group A and Group B inspection. The inspection shall consist of the inspections specified in Table IIIA. Samples shall be selected in accordance with 4.5.3.1.

4.5.3.1 Sampling for Group C inspection.- One sample shall be selected at random for the inspection specified for Table IIIA from every 25 tower sections or fraction thereof produced. The first samples selected shall be at the start of the contract from the first quality conformance inspection production lot (see 4.5.3).

Table IIIA - Group C Inspection

Inspection	Req Para	Insp Para
Tower load	3.25	4.6

4.5.3.2 Group C failures.- Actions required relative to Group C failures shall be as specified in the contract or purchase order.

4.5.4 Reinspection of conforming Group B and Group C sample units.- Unless otherwise specified, sample units which have been subjected to and passed Group B and/or Group C inspection may be accepted on the contract provided all damage is repaired and the sample units are resubjected to and pass Group A inspection."

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T23:22Z
Check the source to verify that this is the current version before use.

4.6 Tower load test: Add after first sentence "with adjustable feet set in approximately their mid-range of adjustments".

Replace fifth and sixth sentences with the following: "Eight test guys, two at each tower corner, shall be attached to the lower guy location of the top 4.5 foot section of the tower. One test guy from each diagonally opposite corner of the tower shall be attached to each anchor located opposite the other two tower corners."

Replace the next to last sentence with the following: "The tower shall be oriented in this test such that the side of the section formed by snap-on members is parallel to the direction of the simulated wind load."

4.8 Guy test.- Replace with:

"4.8 Guy test.- The guys shall be tested to the rated loading of 3.14. No guy hardware shall fail or slip prior to the rated strength of the cable. The guy adjustment mechanism shall not damage the cable after 72 hours at the rated cable load. The tension shall be checked and adjusted at 24 hour intervals.

4.8.1 Cable jacket test.- The cable jackets shall be tested at 1/2 the rated loading of 3.14. The guy adjustment mechanism shall not damage the cable jacket other than surface abrasion after 72 hours at the applied load. The tension shall be checked and adjusted at 24 hour intervals."

Source: https://assist.dla.mil -- Downloaded: 202610-22T23:22Z
Check the source to verify that this is the current version before use.

4.9.2 Static - Change "six inches" to "three inches".

4.10 Platform test.- Replace with:

"4.10 Platform test.- The platform, when mounted on the section, shall be tested and proven capable of supporting a load of 800 pounds on 25 square inches of surface at any point. The permanent deformation, if any, shall be measured after each test, recorded and a test report furnished as required by the contract or purchase order."

4.11 Tension indicator - Replace with:

"4.11 Tension indicator.- The tension indicator shall be tested to determine loading required for the 300 pound, 400 pound and 500 pound settings. The load data obtained shall be recorded and a test report furnished as required by the contract or purchase order."

Pages 18 - 21

5. PREPARATION FOR DELIVERY.- Replace with:

"5. PREPARATION FOR DELIVERY.-

5.1 Preservation and packaging.- Preservation and packaging shall be level A or C, as specified (see 6.2).

5.1.1 Level A.-

5.1.1.1 Cleaning.- Tower AB-585( )/G shall be cleaned in accordance with process C-1 of MIL-P-116.

5.1.1.2 Drying.- Tower AB-585( )/G shall be dried in accordance with the applicable procedure of MIL-P-116.

5.1.1.3 Preservation application.- None required.

5.1.1.4 Unit packaging.- Unit packaging shall be in accordance with the methods prescribed in MIL-P-116 as specified herein.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T23:22Z
Check the source to verify that this is the current version before use.

5.1.1.4.1 Technical literature.- Each technical literature shall be packaged method 1C-1.

5.1.1.4.2 Running spares, accessories and ancillary items.- Running spares, accessories and ancillary items shall be packaged with MIL-E-17555. Unit containers shall be weather-resistant except when a waterproof or water-vaporproof barrier is required over the unit container by an established method of MIL-P-116. When stowage is provided in the equipment, the packaged items will be stowed within the compartments provided. Overflow packages will be consolidated within a close-fitting fiberboard box conforming to PPP-B-636, type CF, class weather-resistant. Fill all voids with paperboard conforming to PPP-P-291, type III, to prevent movement. Box closure shall be as specified in the appendix of the box specification.

5.1.1.4.3 Remaining items.- All remaining items of tower shall be packaged method III in accordance with MIL-P-116.

5.1.1.4.3.1 Cushioning.- All cushioning utilized in a method III package shall be fabricated of material equal to the weather-resistant requirements of the unit package container. The unit container shall conform to the requirements of PPP-B-636, type CF, class weather-resistant. Closure shall be in accordance with the appendix of the box specification.

5.1.1.4.3.2 Bundling and bonding.- Bundling or bonding shall be accomplished as required to group such items as rods, stakes, bars and sections to facilitate handling. Threaded ends and other vulnerable parts shall be protected by wraps to preclude damage such as abrasion or damage to threads.

5.1.2 Level C.- Tower AB-585( )/G shall be preserved and packaged in a manner that will afford adequate protection against physical and environmental damage during shipment, handling and limited intransit storage.

Source: https://assist.dla.mil -- Downloaded: 202610-22T23:22Z
Check the source to verify that this is the current version before use.

5.2 Packing.- Packing shall be level A, B or C, as specified. Shipping containers for all levels shall be capable of stacking and supporting superimposed loads during shipment and storage without damaging the container(s) or its contents. Selection of all shipping containers shall be based upon the mast economical container required to provide minimum, adequate protection for the applicable level specified (see 6.2).

5.2.1 Level A.- Each Tower, AB-585( )/G, packaged as specified in 5.1, shall be packed in containers selected from table V.

5.2.1.1 Container waterproofing.- Fiberboard boxes being placed directly in the shipping containers shall be waterproofed with tape conforming to PPP-T-76, in accordance with the taping requirements of the appendix of the box specification.

5.2.1.2 Dunnage.- Dunnage shall consist of materials treated to resist water.

5.2.1.3 Closure and strapping.- Closure and strapping shall be in accordance with the applicable container specification or appendix thereto except that metal strapping shall conform to QQ-S-781, type 1, class B.

5.2.2 Level B.- Each Tower AB-585( )/G, packaged as specified in 5.1, shall be packed in shipping containers selected from Table V.

5.2.2.1 Closure and strapping or reinforcing shall be in accordance with the applicable container specification or appendix thereto except that fiberboard shipping containers shall be reinforced by pressure-sensitive filament tape bonding or non-metallic strapping conforming to PPP-T-97, type IV and PPP-S-760, type II, respectively; selection of the material and application shall be in accordance with the appendix of the applicable box specification.

5.2.3 Level C.- Tower AB-585( )/G shall be packed in any shipping containers that comply with approved Federal or Military specifications in a manner that shall afford adequate protection to the package and its contents against physical and environmental deterioration and damage during limited shipment, handling and intransit storage.

Source: https://assist.dla.mil -- Downloaded: 202610-22T23:22Z
Check the source to verify that this is the current version before use.

5.3 Marking.- In addition to any special marking required by the contract or order, interior packages and exterior shipping containers shall be marked in accordance with MIL-STD-129.

TABLE V
CONTAINER REQUIREMENTS

Container	Specification	For Level A	For Level B	Wt. Limitation (Lbs)
Boxes, Wood Nailed and Lock-Corner Style 4	PPP-B-621	Class 2	Class 1	Specification Limitation (Note A)
Boxes, Wood, Nailed and Lock-Corner, Style 7	PPP-B-621	Class 2	Class 1	1000 (Note B)
Box, Wirebound Style 2 or 3	PPP-B-585	Class 3	Class 3	Specification Limitation (Note A)
Box, Wood Cleated Fiberboard	PPP-B-591	Not applicable	Class II (Note C)	Specification Limitation
Box, Cleated Plywood	PPP-B-601	Overseas Type	Domestic Type	Specification Limitation (Note A)
Boxes, Fiberboard, Corrugated, Triple-Wall, Style E, Grade A	PPP-B-640	Not applicable	Class 2 (Note C)	250
Box, Fiberboard, Type CF	PPP-B-636	Not applicable	Class Weather-resistant (Note C)	Specification Limitation

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T23:22Z
Check the source to verify that this is the current version before use.

Crates, Wood Open and Covered	PPP-C-650	Style B, Type V Covered	Style B, Type V Covered	Table 1 (Note B)
Crates, Wood	MIL-C-104	Type, Class, Style as applicable	Type, Class, Style as applicable	30,000 (Note B)

NOTE A. When the gross weight exceeds 200 pounds, or the container length and width is 48 x 24 inches or more and the weight exceeds 100 pounds, 3 x 4 inch skids, laid flat, shall be applied in accordance with the requirements of the container specification, or if not specified in the specification, in a manner which will adequately support the item and facilitate the use of material handling equipment.

NOTE B. Style 7 containers conforming to PPP-B-621 shall be considered for use only when the weight of a single item exceeds 400 pounds. Covered crates conforming to PPP-C-650 shall be used only when the weight of a single item exceeds 1000 pounds. Sheathed crates conforming to MIL-C-104 shall be used only when the weight of a single item exceeds 4000 pounds.

NOTE C. When the gross weight exceeds 200 pounds, or the container length and width is 48 x 24 inches or more and the weight exceeds 100 pounds, containers will be pallet-mounted on pallets, load type 1, conforming to MIL-STD-147, except that the pallet shall be softwood conforming to NN-P-71, type IV, size 2."

Page 21

6.2(c) Replace with:

"(c) Levels of preservation and packaging and packing (see section 5)."

6.2(d) Replace with:

"(d) When rough handling and functional tests are required."

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T23:22Z
Check the source to verify that this is the current version before use.

Add the following to 6.2 Ordering data.

"(k) Submission of the statement referenced in 3.3.3.1 as soon as possible after award of the contract. This statement should be submitted to the contracting officer."

Custodian:
Army- EL

Preparing Activity
Army-EL

Project No. 5445-A009

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T23:22Z
Check the source to verify that this is the current version before use.